

Addendum #1

Bid Opportunity: 7201-RW-22

Hespeler Public School Office Renovation

Closing Date: Wednesday, April 6, 2022 2:00 PM

The following issued by the Board shall form part of the Bid / Proposal Solicitation document. The revisions and additions noted herein along with any attachments shall be read in conjunction with all other related documents. This Addendum shall, take precedence over the previously issued documents where differences occur. Receipt of this addendum must be acknowledged in the Bidding System, bids&tenders.

If you have already submitted a Bid / Proposal, it will be automatically withdrawn as a result of this addendum. You must resubmit the Bid / Proposal acknowledging all addenda and revising your Bid / Proposal to comply with all addenda.

Section 1 – Vendor Questions

Question 1:

Architectural drawings don't show the door/screen schedule. Will you provide a door schedule?

Answer 1:

Refer to Specification section 08 11 15 Door Schedule and AD drawings 800 & 801.

Question 2:

Please refer to the Technical Data Sheet link (<u>https://www.gerflorusa.com/media/mipolam-affinity-tds-oct-2021.pdf</u>) for Gerflor Mipolam Affinity for consideration as an alternate for the Resilient Sheet

Flooring specified in Section 09 65 16 for the Hespeler PS Office Reno

project. This homogeneous sheet vinyl is to ASTM F1913 Type 2 standard, 2.0mm thick, 2m wide rolls with the Evercare surface treatment - no wax, no finish for the life of the product, and ISO 22196 anti-bacterial and ISO 21702 anti-viral activity, inhibits the spread of bacteria and viruses at 99%.

Answer 2:

Proposed alternate Gerflor Mipolam Affinity will be accepted.

Section 2 - Clarification / Initiated by the Board

The information below, attachments and drawings provide additional clarification and does not change the Scope or intent of the bid document.

ITEM 1 – Drawing A02 Demolition Floor Plan

.1 REVISE: Detail 1/A02 – Partial Ground Floor Plan – Demolition per attached SKA-1. Existing hollow metal doors to be removed in Foyer X102.

ITEM 2 – Drawing A03 Proposed Floor Plan

.1 REVISE: Detail 1/A03 – Partial Ground Floor Plan – Proposed per attached SKA-1. Existing hollow metal frame to be painted in Foyer X102.

ITEM 2 – Section 09 65 16 Resilient Sheet Flooring

.1 ADD: item 2.1.1.3 to read: "Acceptable Alternate Manufacturer: Mipolam Affinity by Gerflor.

ATTACHMENTS

Addendum No. 1 - in its entirety consists of the following:


- .1 Three (3) typed page of instructions.
- .2 One (1) 8.5" x 11" SKA drawings.
- .3 Electrical Addendum No. 1 one (1) typed page of instructions and one (1) 8.5"x11" SKE drawings, issued by DEI Consulting Engineers, dated March 29, 2022.

DRAWINGS

•

- SKA-1 Part Ground Floor Demolition & Proposed Plans
 SKE

- End of Addendum #1 -





March 29, 2022

Client:	Hossack & Associates Architect Inc.	RE:	Hespeler Public School – Office Renovation
	2150 Dunwin Drive, Unit #4		Cambridge, Ontario
	Mississauga, Ontario		
	L5L 5M8	Job #:	22029

Attn: Ms. Shauna Coates, B.Arch.Sc., LEED Green Assoc., OAAS/ Ms. Priscilla Ladouceur, B.E.S., B.Arch., OAA, MRAIC

ELECTRICAL ADDENDUM

ELECTRICAL

Item 1

- 1.0 Reference Drawing E1.2 and Attached Sketch SKE-1
 - .1 Lighting fixture equal for Type 'G1' added to 'LED Light Fixture Schedule', as shown on attached sketch.

Item 2

- 2.0 Reference Drawing E2.1 and Attached Sketch SKE-1
 - .1 Remove door holds and smoke detector relay bases (detector to remain) to suit removal of double doors within existing corridor by main entrance.

Chris Pathy, Electrical Engineering Technologist 22029 Addendum (E-LED Light Fixture Schedule)(SKE-1) Mar 29 22 cp/sad


> کا (۲ DEI Consulting Engineers | Project No: 22029

LED LIGHT FIXTURE SCHEDULE


	ltem	Manufacturer/Catalog Number	Voltage	Lamp	Mounting	Description	
	₽	G-LIGHTING CAT. GL-2800-C-1-A CANMAN LIGHTING CAT. #P7105-18-LH- 40K-CLV-WP-STBD-AC-OAH	120V	28W LED 2844lm 4000K	SUSPENDED	18" GLOBE SUSPENDED FIXTURE C/W SATIN WHITE ACRY DIMMING. MOUNTING HEIGHT AND FINISH TO BE CHOSEN	

E1.2-LED LIGHT FIXTURE SCHEDULE


SCALE: 1:100



E2.1-PARTIAL GROUND FLOOR PLAN - DEMOLITION SCALE: 1:100







HESPELER P.S. RENOVATIONS (REF. DWGS E1.2 & E2.1)

