



Halton District School Board

Addendum No. 2

RFT 22-155 Library Renovations – Aldershot High School

The following, issued by the Halton District School Board June 13, 2022, shall be incorporated in the specifications and shall form part of the proposal document for the above.

CLARIFICATION:

1. For clarification, all asbestos abatement work costs identified in the Asbestos scope of work shall be included in the base bid value.
2. Aldershot High school will be undergoing an electrical upgrade and the construction schedule is attached. (1 page)

REVISED:

The closing date and time of RFT 22-155 Library Renovations – Aldershot HS has been changed to Monday, June 20, 2022 on or before 2:00 pm Eastern Standard Time.

RECEIPT OF ADDENDA MUST BE ACKNOWLEDGED ON THE FORM OF TENDER.

PAGE 1 OF 2
END OF ADDENDUM 2

Project: ALDERSHOT HIGH SCHOOL

Prior to start day	Coordinate with Halton Hydro HV power shut down for the school on July 11/2022 Coordinate with Halton Hydro installation of Pad Mounted Transformer and Primary Feeders Coordinate Temporary Generator delivery on July 11/2022
July 4/2022	Mobilization
July 4 - 8/2022	Prepare and install footing for cable and conduit support. Install cable support system on the roof. Coordinate with Halton Hydro HV power shut down for the school on July 11/2022 Install secondary cables Coordinate Temporary Generator delivery
July 11-	Shut down and isolate HV power to school - By Halton Hydro Connect the Temporary Generator to feed: Panel "LPA" (Community Swimming Pole Bld.) Fire Alarm Panel Security Panel
July 11 - 15	Remove the Existing HV Switchgear, HV Transformer and Main Distribution Board Modify Housekeeping Pad Prepare opening in the roof for cable entry
July 18 - 22	Install New Main Distribution Board Install Main feeders from Pad Mounted Transformer to Main Distribution Board Install Communication Conduits Modification to Conduits for feeders in main electrical room
July 25 - 29	Reconnect all feeders to Main Distribution Board Disconnect Temporary Generator Turn ON Power to the School - Coordinate with Halton Hydro
July 29-	Demobilization