Waterloo Region District School Board

# REQUEST FOR TENDER

## GALT COLLEGIATE INSTITUTE

## EXTERIOR/ INTERIOR UPGRADES TO TASSIE HALL

## PROJECT NO. 26-7849-RFT

**ISSUE DATE: February 12, 2026**

The Bidding System will receive ELECTRONIC SUBMISSIONS, no later than **2:00:00 p.m. local time, on March 4, 2026 ("Closing Date and Time")**

DIVISION 00 – BIDDING AND CONTRACT DOCUMENTS


| | | |
|---|---|---|
| 00 00 01 | Table of Contents | 3 |
| 00 01 00 | Consultant/ Professional Seals | 1 |
| 00 21 13 | Instructions to Bidders | 12 |
| 00 21 14 | General Contractors, Subcontractors, Prequalified Rosters | 2 |
| 00 21 15 | Scope of Work | 1 |
| 00 31 34 | Subsurface Investigation Report | 1 |
| 00 31 34A | Soil Report | 1 |
| 00 41 13A | Asset and Warranty Card | 1 |
| 00 56 13 | Definitions Stipulated Price | 2 |
| 00 72 13 | Standard Terms and Conditions | 39 |
| 00 73 00 | The Supplementary Conditions | 59 |


DIVISION 01 – GENERAL CONDITIONS


| | | |
|---|---|---|
| 01 14 00 | Work Restrictions | 2 |
| 01 19 00 | Specifications and Documents | 2 |
| 01 21 00 | Allowances | 3 |
| 01 31 00 | Project Managing and Coordination | 6 |
| 01 32 00 | Construction Progress Documentation | 3 |
| 01 33 00 | Submittal Procedures | 5 |
| 01 35 17 | Fire Safety Procedures | 7 |
| 01 35 17A | Contractor Hot Work Permit | 1 |
| 01 35 23 | Health and Safety | 5 |
| 01 34 43 | Designated Substances | 5 |
| 01 34 43A | Asbestos Audit Report | 68 |
| 01 34 43B | Lead Report | 12 |
| 01 42 00 | References | 5 |
| 01 45 00 | Quality Control | 7 |
| 01 51 00 | Temporary Utilities | 5 |
| 01 53 00 | Temporary Construction Facilities | 6 |
| 01 54 00 | Materials and Equipment | 3 |
| 01 61 00 | Product Requirements | 5 |
| 01 70 00 | Examination and Preparation | 3 |
| 01 73 00 | Execution and Cutting and Patching | 4 |
| 01 74 00 | Cleaning and Waste Management | 4 |
| 01 78 10 | Closeout Submittals and Requirements | 6 |
| 01 78 40 | Maintenance Requirements | 3 |
| 01 79 00 | Demonstration and Training | 3 |


DIVISION 02 – EXISTING CONDITIONS


| | | |
|---|---|---|
| 02 41 19 | Selective Demolition | 3 |

DIVISION 03 – CONCRETE
REFER TO STRUCTURAL DRAWINGS

DIVISION 04 – MASONRY
REFER TO DRAWINGS

DIVISION 05 – METALS
REFER TO STRUCTURAL DRAWINGS

| | | |
|---|---|---|
| 05 50 00 | Metal Fabrications | 4 |

DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES

| | | |
|---|---|---|
| 06 10 00 | Rough Carpentry | 3 |
| 06 20 00 | Finish Carpentry | 3 |
| 06 40 00 | Architectural Woodwork | 9 |

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

| | | |
|---|---|---|
| 07 16 00 | Cementitious and Reactive Waterproofing | 3 |
| 07 21 13 | Board Insulation | 2 |
| 07 26 00 | Vapour Retarders | 2 |
| 07 27 10 | Air Barriers | 4 |
| 07 46 13 | Preformed Metal Siding | 5 |
| 07 51 13 | Built-Up Asphalt Roofing | 11 |
| 07 61 00 | Sheet Metal Flashing and Trim | 4 |
| 07 72 33 | Roof Hatches | 3 |
| 07 84 00 | Firestopping | 3 |
| 07 92 10 | Joint Sealing | 4 |

DIVISION 08 – DOORS AND OPENINGS

| | | |
|---|---|---|
| 08 71 10 | Finish Hardware | 2 |

DIVISION 09 – FINISHES

| | | |
|---|---|---|
| 09 21 16 | Gypsum Board Assemblies | 4 |
| 09 22 14 | Metal Furring and Lathing | 2 |
| 09 22 16 | Non-Structural Metal Framing | 2 |
| 09 22 27 | Acoustical Suspension | 2 |
| 09 65 16 | Resilient Flooring and Base | 4 |
| 09 68 00 | Carpeting | 3 |
| 09 91 10 | Painting | 8 |

DIVISION 10 – SPECIALTIES

| | | |
|---|---|---|
| 10 28 10 | Washroom Accessories | 3 |
| 10 62 00 | Auditorium Seating | 4 |

DIVISION 20 – MECHANICAL
20 05 00 Common Work Results for Mechanical 27

DIVISION 21
NOT APLICABLE

DIVISION 22 – PLUMBING
22 05 00 Common Work Results for Plumbing 11

DIVISION 23 – HEATING, VENTILATION, AND AIR CONDITIONING
23 05 00 Common Work Results for HVAC 43

DIVISION 24
NOT APPLICABLE

DIVISION 25 – INTEGRATED AUTOMATION
25 05 00 Integrated Automation 17

DIVISION 26 – ELECTRICAL 35

DIVISION 27 – COMMUNICATIONS 3

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY 11

DIVISION 31 – EARTHWORK
REFER TO STRUCTURAL DRAWINGS

DIVISION 32 – EXTERIOR IMPROVEMENTS
32 13 15 Concrete Walks, Curbs and Gutters 2

**END OF SECTION**

## 00 01 00 Consultant/ Professional Seals

1.1 The following professional seals and signatures are provided as required by Paragraph 1.21.1 (4) Division C of the Ontario Building Code and apply to the areas of expertise for which each consultant was commissioned.

1.1.1 Architect
**CORNERSTONE ARCHITECTURE INCORPORATED**
102-320 Thames Street
London Ontario N6A 0E1
Phone: 519 432 6644 Fax: 519 432 6737





1.1.2 Structural
**MTE CONSULTANTS INC.**
1061 Hargrieve Road
London Ontario N6E 1P6
Phone: 519 204 6510 Fax: 519 204 6511




1.1.3 Mechanical
**MNE ENGINEERING INC.**
22 Kevco Place
Kitchener Ontario N2C 2G5
Phone: 519 894 9408 Fax: 519 894 5682




1.1.4 Electrical
**MNE ENGINEERING INC.**
22 Kevco Place
Kitchener Ontario N2C 2G5
Phone: 519 894 9408 Fax: 519 894 5682




**END OF SECTION**

## DIVISION 00 – BIDDING AND CONTRACT DOCUMENTS

### 00 21 13 - Instructions to Bidders

#### 1.1 Designated Representative

To contact the Waterloo Region District School Board ("WRDSB" or the "Board") or ask questions in relation to this Procurement, bidders must initiate communication electronically through the Bidding System. The WRDSB will not accept any communications by any other means, except as specifically stated in the Procurement. Bidders must not communicate in any manner with anyone other than the Designated Representative.

The Designated Representative for this procurement process is:

Procurement Lead: Ardith Inapan
Title: Buyer
Waterloo Region District School Board
Email: ardith_inapan@wrdsb.ca

#### 1.2 Consultant

The WRDSB has hired the following consultant to assist in the preparation of this Procurement: Cornerstone Architecture

The Consultant and any subconsultants are not to respond to any questions or communicate with bidders and/or any interested parties from the bid issue date to the bid award notification. Reference: 1.5 Communication and Question Protocol.

The Consultant will be responsible for the contract administration of the project after the purchase order has been issued or the contract has been signed by the WRDSB.

#### 1.3 Blackout Period

A blackout period shall exist between the deadline for questions and the date of award. During this period, there shall be no communication between the Bidders, the WRDSB, or any WRDSB consultants or employees, unless initiated by the Board's Designated Representative, noted above.

#### 1.4 Doing Business with the Waterloo Region District School Board

Waterloo region District School Board (WRDSB) serves approximately 65,000 students in 123 schools, as well as alternative and continuing education sites. WRDSB is committed to creating learning environments that support the achievement and well-being of all students through partnering with staff, parents, families, caregivers, and communities to promote success in learning and life.

Bid opportunities above $10,001 CAD will be solicited through an electronic bidding system (bids&tenders) or the WRDSB may also utilize Supplier roster lists awarded through a competitive process, participate in cooperative procurements with various

public entities, or buying groups. These may include, but are not limited to, Ontario Education Collaborative Marketspace, Supply Ontario, and other Cooperative Group(s).

WRDSB competitive opportunities are posted on the Electronic Bidding System, bids&tenders/wrdsb.

The WRDSB only accept electronic Bid Submissions submitted through the Electronic Bidding System, bids&tenders/wrdsb

Bid opportunities may be posted as Public or by Invitation and are based on dollar thresholds outlined in Administration Procedure 4570 PROCUREMENT. Click here to access the WRDSB's Administrative Procedures, Section 4000 – Business Services.

**1.5 Certificate of Recognition (COR) Certification (General Contractors)**

i. All bidders must possess and maintain a valid Certificate of Recognition (COR) issued by a recognized certifying partner at the time of bid submission.
ii. Bidders shall provide proof of current COR Certification with their tender submission. Failure to provide acceptable documentation may render the bid non-compliant and subject to rejection.
iii. The WRDSB reserves the right to verify the validity and status of COR Certification at any time during the procurement process and throughout the term of the contract.
iv. If a bidder's COR Certification expires, is suspended, or is revoked during the contract period, the Board may, at its sole discretion, require immediate corrective action or terminate the contract without penalty

**1.6 Communication and Question Protocol**

Bidders and their representatives are NOT permitted to contact WRDSB Project Managers/Leads, agents of the WRDSB; any member of the WRDSB's governing body (such as Board of Trustees, or advisors); any employee, consultant, or agent of the WRDSB's Clients, other than the Designated Representative listed above. Any attempt by a Bidder to bypass or influence the procurement process may result in disqualification of the Bidder and the rejection of the Bidder's submission.

The WRDSB will not be responsible for any verbal statements, instructions, or representations. In case of difference between any verbal information and written document, the written document shall govern. Information obtained from any source, other than the Designated Representative, noted above in writing, shall not be relied upon.

The WRDSB shall not be bound by any verbal instruction or information provided by any WRDSB employee or consultant of the WRDSB. Only responses provided in an Addendum shall form part of this Procurement Document.

All requests for information, instructions, or clarifications shall be through the Bidding System by clicking on the "Submit a Question" button found within the bid detail of the specified Procurement. Addenda will be issued accordingly.

It is the responsibility of the Bidder to seek clarification of any matter that they consider unclear before submitting their application. The Board is not responsible for any misunderstanding of the Procurement documents on the part of the Bidder.

### 1.7 Anticipated Project Schedule

The following table represents the anticipated project timelines. This timeline is an estimate only and may be subject to change by the WRDSB at any time.

| DESCRIPTION | DATE |
|---|---|
| Issue Date of Tender | Thursday, February 12, 2026 |
| Non-Mandatory Pre-Bid Site Examination | Date: Thursday, February 19, 2026<br>Time: 2:30 pm local time<br>Galt Collegiate Institute<br>200 Water Street North<br>Cambridge Ontario N1R 6V2<br>Meeting Area: Main Office |
| Deadline for Questions | Friday, February 27, 2026 |
| Closing Date and Time | **Wednesday, March 4, 2026**<br>**2:00:00 pm local time** |
| Anticipated Contract Start / Work begins | Monday, March 9, 2026 |
| Roofing Work to be scheduled during summer months | Monday, July 6, 2026 – Friday, August 28, 2026. |
| Substantial Completion Date | Friday, December 18, 2026 |
| Ready for Takeover | Friday, January 29, 2027 |
| Deemed Complete Date | Friday, January 29, 2027 |

### 1.8 Site Pre-Bid Examination

Bidders are strongly encouraged to attend the non-mandatory pre-bid site meet and sign the attendance sheet. Date, time and location are provided above in the Anticipated Project Schedule. The WRDSB may not provide another opportunity to visit the site.

i. Bidders shall attend site meetings at their own risk and hold the WRDSB harmless for any issues or damage arising out of their attendance at the site meeting.
ii. The WRDSB will not consider any claims for additional payments during the execution of the Work for extra work or difficulties encountered resulting from conditions which were either visible or could be reasonably inferred from an examination of the Place of the Work and the available project information prior to the submission of Bids
iii. Absence from a non-mandatory site meeting will not disqualify any Bidder.
iv. Bidders are solely responsible for making their own assessment of the site.
v. Bidders are encouraged to bring their own measuring tape, camera, or other portable tools as required to the site meeting. Bidders are solely responsible for making their own assessment of the site.

**1.9 Secondary Site Examinations**

Bidders may request a secondary site examination visit through the Bidding System by clicking on the "Submit a Question" button found within the bid details page of that Procurement. Include the contact's name, phone number and email address of the person who will visit the site.

Bidders shall attend the secondary site examination visit at their own risk and hold the Board harmless for any issues or damage arising out of their attendance of the site meeting.

In the event the WRDSB holds a Mandatory Pre-Bid Site Examination meeting, Bidders not in attendance will not be provided an opportunity to a secondary stie examination visit.

Bidders must adhere to all communication protocols, as described above in 1.5. Communication Protocol.

The Owner will not consider any claims for additional payments during the execution of the Work for extra work or difficulties encountered resulting from conditions which were either visible or could be reasonably inferred from an examination of the Place of the Work and the available project information prior to the submission of Bids.

Bidders are encouraged to bring their own measuring tape, camera, or other portable tools as required to the site meeting. Bidders are solely responsible for making their own assessment of the site.

**1.10 Examination of Bid Documents and Work and Submitting Questions**

Bidders are required to fully acquaint themselves with the Procurement documents; fully inform themselves of all conditions, limitations and requirements involved in the Procurement; and obtain all information that may be necessary to complete those requirements before submitting a Bid.

Submission of a Bid shall be considered conclusive evidence that the Bidder has satisfied itself as to the requirements of this Procurement.

In the event a Bidder discovers any errors, discrepancies, inconsistencies, or omissions or requires clarification within this Procurement, they are to submit their observations and/or questions through bids&tenders by clicking on the "Submit a Question" button found within the bid detail of the specified Procurement by the Deadline for Questions specified in this paragraph.

Bidders are strongly encouraged to ask clear and concise questions(s) or statements citing the relevant section of the Procurement Document. The Board cannot guarantee a response to questions received by the Board after the Deadline for Questions.

The WRDSB has endeavored to provide complete, correct information and estimates to enable Bidders to accurately assess and determine the scope and complexity of the Work prior to submitting a Bid.

Bidders are solely responsible for determining if they require additional information or if anything appears incorrect or incomplete. The onus is on the Bidder to contact the Designated Representative prior to the Deadline for Responses indicated in this document, if they have any questions or queries whatsoever or find omissions from or discrepancies in this Procurement document, unnecessary restrictions in the terms of reference, or should they be in doubt as to the meaning of any part of this document.

Written responses or clarifications to issues of substance will be shared with all Bidders in the form of an Addendum.

**1.11 Electronic Bid Submission Only / Electronic Bidding System**

The Bidder must complete and submit their bid through the Bidding System only. All components of the submission and supporting documents must be in English only. Any other form of submittal will not be considered. It is the Bidder's responsibility to read the Procurement documents thoroughly including all attachments and addenda, if any, as these contain information that is highly pertinent to this Procurement and to clarify any details with the Designated Representative prior to their submission. To be considered, Bidders must respond to this Procurement.

To submit a bid, bidders must be registered with bids&tenders. The sole onus is on the bidder to have the most current correct information set-up in bids&tenders e.g. plan taker contact information, categories, and agency etc.

All Bids shall be submitted through bids&tenders only. The onus is on the Bidder to ensure all requirements of this Procurement are submitted.

If a bidder encounters technical issues, the onus is on the bidder to have this resolved prior to the closing date and time by contacting support@bidsandtenders.ca

Bidder shall have a "Vendor account" in the Bidding System and shall ensure the account is created with the Bidders full legal company name and be registered as a "plan taker" for this Procurement. Only the plan takers will have access to download bid documents, receive addenda email notifications, download addenda, and submit their bid electronically through the Bidding System.

The onus is on the Bidder to ensure that the Bid is received in the Bidding System on or before Closing Time. The Closing Time shall be determined by the Bidding System's web clock. The timing of the Bid submission shall be based on when the Bidding System receives the Bid, not when a Bidder submits a Bid.

Bidders shall allow sufficient time to upload their Bid submission including all requirements as stated in this Procurement and to resolve any issues that may arise as Bid transmission can be delayed in an "internet traffic jam" due to file transfer size, transmission speed, and other electronic considerations

All prices including provisional pricing, if requested, shall be submitted in the Schedule of Prices forms available through the Bidding System.

The Owner reserves the right to accept or reject any or all provisional bid prices submitted. Failure to submit provisional prices where required may result in the Bid being declared non-compliant.

Bids submitted by fax or paper copy, or any other format will not be accepted.

The Bidding System will not accept Bids after the Closing Time as determined by the Bidding System's web clock.

The WRDSB hereby consents to the use of an Electronic Signature for the signing of all documents requested hereunder. Acceptable forms of signatures include, but are not limited to, the typing of the Bidder's authorized signing officer's name or the inclusion of an image of the Bidder's authorized signing officer's signature, so long as the electronic signature is sufficient to identify the Bidder's authorized signing officer. The Bidder's authorized signing officer agrees that whatever form of electronic signature is provided constitutes a signature for the purpose of executing all documents requested hereunder.

Upon submitting a Bid, the Bidding System will send a confirmation email to the Bidder advising that the Bid was submitted successfully. If a Bidder does not receive a confirmation email despite submitting a Bid, the Bidder should contact technical support of the service provider hosting the Bidding System via email: support@bidsandtenders.ca

There will be no public opening for this Bid.

If a Bid is a joint submission of two (2) or more firms, a single Bid is to be coordinated and submitted by the lead Bidder with the required information. If two or more parties submitted a joint response to this Procurement, they shall decide between them who is to be the Bidder, without any involvement of the WRDSB.

Your online Bid submission shall be taken as your statement that you understand the requirements and agree to comply with the requirements as well as terms and conditions stated in this Procurement document, including WRDSB's Standard Terms and Conditions. Your Bid submission through the Bidding System confirms that you have checked and confirmed your pricing and by submitting the Bid online, you agree that you have not omitted any items from your Bid.

For construction projects with Bids above $200,000 the Successful Bidder will be required to execute a "Canadian Standard Form of Construction Contract to a Stipulated Sum" (CCDC 2 - 2020 including amendments thereto as set out in this Procurement.

**1.12 Bid Prices**

The amounts stipulated on the Schedule of Prices are intended to cover the cost of the complete Work as described in this Procurement Document.

All prices shall be in Canadian Funds, Free On Board (FOB) Destination, Freight Prepaid (WRDSB sites/locations).

Exclusive of the HST, or other similar taxes.

Unit pricing shall be exclusive of Harmonized Sales Tax (HST) but shall include all applicable costs including but not limited to overhead, material, labour, travel, fuel, fuel surcharge, equipment, disbursements, expenses, customs, charges, freight, shipping and handling costs, and all other charges of every kind attributable to the services, equipment or goods provided.

The person submitting the Bid on behalf of the Bidder must have authority to bind the Bidder.

Quantities may be estimated and subject to change, and therefore the WRDSB, at its discretion, may purchase more or less of the commodity based on the unit price bid.

All information required on the forms shall be completed in full including references and subcontractors that it proposes to use for Work described. Changes made to the list of subcontractors after the closing of the Bid must have prior written approval of the WRDSB's Project Representative.

All price(s) submitted shall be a reasonable price for each item as determined by the WRDSB and under no condition will an unbalanced Bid be considered. Submissions containing prices which appear to be so unbalanced as to likely affect the interests of the WRDSB adversely will be clarified and may be rejected.

Unit prices and/or optional pricing, if any will set the foundation for any approved increases or decreases in Work. The unit prices must remain fixed and firm for the term of the Contract, unless otherwise specified in this Procurement document.

Provisional or Optional Pricing may or may not be required for completion of the Work called for under the Contract. The WRDSB will decide necessity of these items and quantities thereon based on the unit prices(s) included in their Bid. If Provisional or Optional items are not purchased, or quantities are less than estimated, no adjustment or compensation will be awarded to the Bidder by the WRDSB. Optional pricing is not used for comparison of Bids for award purposes.

1.12.1 Bonding: for awards over $200,000.00 unless otherwise instructed is required – Refer to Standard Terms and Conditions, Clause #4 Bonding Requirements.

## 1.13 References

1.13.1 References are NOT required. This Section does not apply to this Project.

## 1.14 Addenda

All Addenda issued through the Bidding System shall form part of the Procurement Document.

The WRDSB shall not be bound by any verbal instruction or information provided by any WRDSB employee or consultant of the WRDSB. Only responses provided in an Addendum shall form part of this Procurement Document.

Prior to bid closing any discrepancies, omissions, questions, or clarifications regarding the procurement documents must be sent immediately through the Bidding System by clicking on the "Submit a Question" button found within the bid details page of that opportunity.no later than the deadline noted in the Anticipated Project Schedule. Those that are deemed pertinent to the Procurement Document will be addressed in the form of an Addendum.

It is understood and acknowledged that while the Procurement document includes specific requirements, a complete review and recommendation is required. Minor items or details not herein specified but obviously required for the Work shall be provided as if specified in conformance with modern practices. Any omissions or errors or misrepresentation of these requirements and specifications within the Procurement document shall not relieve the Bidder of the responsibility of providing the services or products as aforesaid.

Bidders shall acknowledge the receipt of all Addenda in the Bidding System prior to the submission of a Bid. Where Addenda has been issued, the system will not allow the Bidder to submit a Bid prior to acknowledging said Addenda.

Where an Addendum is issued after a Bid has been submitted, the Bidding System will automatically withdraw the submitted Bid. The Bid status will change to incomplete and will not be accepted by the WRDSB as a submitted Bid. It is the responsibility of the Bidder to make any required adjustments to their submission, acknowledge all Addenda and ensure the Bid has been received by the Bidding System. Bidders should check the Bidding System for Addenda up until the Bid Closing Date and Time.

Addenda cannot be acknowledged after the Closing Date and Time.

## 1.15 Edit and Withdrawal of Bid Submission

A Bidder who has submitted a bid may edit or withdraw its bid at any point up to the Closing Date and Time.

Any edits to a bid submission will cause the submission to automatically be withdrawn. The bid submission must be re-submitted to be accepted.

The Bidder is solely responsible for ensuring that its re-submission is received prior to Closing Date and Time. The closing time shall be determined by the web clock within the Bidding System. After such time, requests to withdraw Bid will not be considered.

**1.16 Irrevocable Period**

Bids will be irrevocable by the Bidder, and open for acceptance by the WRDSB, for **60 (sixty) days** following the Closing Date.

**1.17 Tie Bids**

Where two (2) or more Bids have been received reflecting the same, lowest Bid price, the time stamp for date and time submission in the Bidding System will dictate the award (earliest submission shall prevail).

**1.18 Bid Irregularities**

Bids with one or more of the following may be declared informal and/or disqualified and/or non-compliant:

i. Bids that do not comply strictly with all terms and conditions of the Procurement Document.

ii. Bids that are incomplete, conditional, qualified, or obscure.

iii. Bids that are based upon an unreasonable period for completion of the Work.

iv. Bids received from Bidders involved in Claims with either of the WRDSB or banned or on probation with the WRDSB.

v. Bids received from any Bidder deemed to be unskilled or inexperienced in the work contemplated, or those who have defaulted on, or failed to satisfactorily complete other similar work in the past.

vi. Bids submitted by Bidders that are not prequalified, where applicable.

**1.19 Bid Review**

i. All Bids received on or before the Closing Time will be reviewed for compliance based on this Procurement document. Non-compliant Bids will be rejected. Bids not meeting any of the mandatory requirements included in this Procurement document will be disqualified. Bidders may be contacted to clarify their submissions.

ii. Should there be any error in extensions, additions or computations, the WRDSB shall be entitled to correct such errors based upon the unit prices supplied, and the corrected total shall be considered as representing the intention of the Bidder and shall be used as the basis for comparison of Bids.

iii. It is the Bidder's responsibility to satisfy the WRDSB that they can comply with the requirements contained within this Procurement document and that they possess the necessary inventory, equipment, facilities, resources, and staff to perform the

work specified in this Procurement document. Bidders may be required to submit evidence of above in a form acceptable to the WRDSB. Substitution of materials, equipment, or methods different from those outlined in the terms of reference will not be accepted unless provided for within this Procurement document or with the written approval of the WRDSB.

iv. The WRDSB also reserves the right to examine Bidder's facilities, equipment and visit the subcontractors or subconsultants proposed and/or Bidder's existing and past clients. The award decision may be revised based on the above.

v. The WRDSB will not be responsible for travel costs if travel is required. No additional charges will be accepted by the WRDSB for any cost incurred by the Bidder or any other party in participating in the Bid evaluations.

vi. The WRDSB may, in its sole discretion, check references, conduct credit checks, review the litigation history and history of professional liability or other insurance claims, and obtain any other type of information that might aid the WRDSB in its selection. The WRDSB reserves the right to consider all, or any information received from all available sources, whether internally or externally obtained. The WRDSB may disqualify any Bid from further consideration based on results of reference or credit checks or review of litigation or claim history. The foregoing may include the WRDSB's own experiences with the respective Bidder(s) or any of the subcontractors and subconsultants proposed in their Bid.

## 1.20 Intent to Award

Bidders are advised not to make any business decisions, assignments, or any sub-contract for the execution of the Work, before receiving a Purchase Order from the WRDSB.

There shall be no obligation on the WRDSB because of seeking Bids or conducting the procurement process and the WRDSB reserves the right to pursue other Bidders, cancel the Procurement, issue a revised request, or to pursue any other course of action which would aid in meeting their needs.

If instructed, within **twenty-four (24) hours**, excluding hours occurring during a Saturday, Sunday, or a legal holiday, from the issuance date an intent to award from the WRDSB, the Bidder (the "Recommended Bidder") shall provide a list of all subcontractors/subconsultants that it proposes to use for all Work described in this Procurement including the Company Name, Subtrade Category and if applicable, related Divisions.

1.20.1 Within **seven (7) calendar days**, from the issuance date of an intent to award notice or requested by the WRDSB, the Bidder (the "Recommended Bidder") shall provide the following mandatory requirements:

i. Insurance certificate with coverage specified in the Procurement Document.
ii. WSIB clearance certificate valid on the date of award or an exemption letter (if applicable and requested).
iii. Non-Disclosure Agreement (NDA) duly signed by the authorized signatory (to be renewed annually). The WRDSB will provide this form.
iv. Bonding Requirements, if applicable, as specified in the Procurement Document.
v. An executed WRDSB issued Form of Agreement, if applicable, and duly signed by the authorized signatory.
vi. Any other submittal specified in the Procurement Document or in the intent to award, as a requirement of award.
vii. For construction projects above $200,000 the Successful Bidder will be required to execute a "Canadian Standard Form of Construction Contract to a Stipulated Sum" (CCDC 2 – 2020) including amendments thereto as set out in this Procurement.

1.20.2 The documents listed below will be incorporated as deemed necessary by the WRDSB, into the Contract with the Bidder. If there is a discrepancy between the wording of one document and the wording of any other document that appears on the list, the wording of the document that first appears on the list shall take precedence:

i. WRDSB approved change order(s) or Contract / Agreement / CCDC 2 - 2020 amendment(s)
ii. Purchase Order(s), Contract(s) Agreement(s) / CCDC 2 -2020 executed with the Bidder including exhibits
iii. Procurement document issued by the WRDSB, including addenda, if applicable
iv. Bid submitted by the Bidder

**1.21 Post- Closing/Pre-Award Meeting**

The WRDSB may request a meeting with Bidders after the bid closing dates.

**1.22 Award**

Unless otherwise stated, the contract will be awarded to the lowest compliant bidder on the base bid, who meets the requirements, the scope of work outlined in this Procurement, and satisfactory references and experience. The WRDSB reserves the right to decrease quantities and/or the Scope of Work or not award this Project, due to insufficient budget.

**1.23 Post-Award Meeting (Kick off Meeting)**

A post-award meeting may be held consisting of the successful Contractor, and their key personnel assigned to the contract, the WRDSB's Project Manager/Lead and if applicable

the Consultant, to discuss the program and exchange information before the contract commences. This meeting will be at the sole expense of the Bidder and shall be considered part of the contract. If applicable, the meeting date will be scheduled after the Award.

### 1.24 Post Award

In addition to all the WRDSB's other remedies, if a recommended Bidder fails to satisfy the requirements and/or execute the Form of Agreement or any other applicable conditions within seven (7) calendar days of notice of selection, the WRDSB may, in their sole and absolute discretion and without incurring any liability, rescind the selection of that Bidder.

The Bidder may protest within the five (5) day Notice of Intent to Award, after that, the protest will not be reviewed or accepted.

### 1.25 Award Posting Notification

For procurements valued at $121,200 or more, and in accordance with the Broader Public Sector Procurement Directive, once the WRDSB is satisfied that all requirements are met, the project award notification will be posted in the same manner as the procurement documents were posted. The notification will be posted after the purchase order and/or agreement between the successful bidder and the WRDSB has been issued/executed. The award notification will list the name of the successful bidder, agreement start and end dates, and any extension options.

**END OF SECTION**

## 00 21 14 – General Contractors, Subcontractors, Prequalified Rosters

### 1.1 General Contractors

1.1.1 Only invited prequalified General Contractors, by award through a competitive prequalification process, 7430-RFPQ, may submit a bid for this opportunity.

1.1.2 Invitations are based on awarded Project Size Categories. Only approved GCs (on the Roster) may bid on the project size categories based on their award.

1.1.3 A Site Supervisor and Project Manager, assigned to manage and supervise the Work, must be named in the Bidder's Contact Information Specification section through the electronic Bidding System only and include resumes. Personnel will be subject to approval by the WRDSB and cannot be changed without prior written approval from the WRDSB.

1.1.4 Refer to COR Certification Requirements, Clause 1.5.

### 1.2 Subcontractors/Subconsultants

1.2.1 Refer to specifications for products and suppliers that will be required.

1.2.2 The subcontractor/subconsultant list is not required at time of bid submission.

1.2.3 The subcontractor/subconsultant list is mandatory after the bid closing date from the Recommended Bidder within twenty-four (24) hours of receiving a request or intent to award from the WRDSB.

1.2.4 In the event the WRDSB has a Prequalified Roster List for a Trade Category required for this project, the General Contractors will select from the list below in *3.0 WRDSB Prequalified Roster Lists*. General Contractor's subcontracting other than the companies listed below or identified by Addendum will have their Bid ruled informal.

1.2.5 The Bidder (the "Recommended Bidder") shall provide a list of subcontractor/subconsultant that it proposes to use for all Work described in this Procurement including the specification sections, as per the following:

i. Bidders shall select experienced and qualified subcontractor/subconsultant or Suppliers in their field to perform or supply an item of Work indicated in this Procurement.

ii. The Bidder shall be fully aware of the capability of each subcontractor/subconsultant and/or Supplier included in its bid, including but not limited to technical ability, financial stability, and ability to maintain the proposed construction schedule.

iii. The WRDSB reserves the right to reject any proposed subcontractor/subconsultant or supplier, based on the following but not limited to unsatisfactory past performance, suspended/removed from doing business

with the WRDSB and/or outstanding/unresolved corrective action notice issued by the Owner to the subcontractor/subconsultant within the last three (3) years.

iv. The WRDSB reserves the right to obtain information from the Bidder and from third parties respecting the qualifications and experience of the Bidder's nominated list of subcontractor/subconsultant for such item of the Work.

v. The WRDSB reserves the right to examine Bidder's facilities, equipment and visit the subcontractor/subconsultant's proposed.

vi. The substitution of any subcontractor/subconsultant and/or suppliers after the list is submitted will not be accepted unless a valid reason is given in writing to and approved by the Owner, whose approval may be arbitrarily withheld.

vii. Where a bidder lists "own forces" in place of a subcontractor/subconsultant, the bidder shall conduct such item of the Work with its own forces.

viii. Where "own forces" have been listed by a bidder, the WRDSB reserves the right to obtain information from the bidder and from third parties respecting the qualifications and experience of the bidder's "own forces" for such item of the Work.

**1.3 WRDSB Prequalified Roster Lists**

The following subcontractors have been prequalified by the WRDSB through a competitive process. If the trade categories listed below are required for this Project, the General Contractor must select from the Prequalified Roster(s) below.

Prequalified Roofing Contractors:

| **Vendor Name** | **Email** | **Number** |
|---|---|---|
| Atlas Apex Roofing Inc. | jmcdowell@atlas-apex.com | (416) 421-6244 |
| Eileen Roofing Inc | dianne@eileenroofing.com | (416) 684-6153 |
| Flynn Canada Inc | sean.wormsbecker@flynncompanies.com | (416) 814-0440 |
| Lafleche Roofing (1992) Ltd. | chris@laflecheroofing.com | (519) 681-7610 |
| Nedlaw Roofing Ltd. | andrew@nedlawroofing.com | (519) 648-2218 |
| Nortex Roofing Ltd. | sandra@nortexroofing.com | (416) 236-6090 |
| Provincial Industrial Roofing & Sheet Metal Co. Ltd. | duglow@provincialroofing.com | (905) 669-2569 |
| Semple Gooder Roofing Corp | jouellette@semplegooder.com | (416) 743-5370 |
| Trio Roofing Systems Inc. | paulo@trioroofing.ca | (905) 456-1688 |

**END OF SECTION**

## 00 21 15 – Scope of Work

The scope of work for the Exterior/ Interior Upgrades to Tassie Hall project at Galt Collegiate Institute includes, but is not limited to the following:

1. Exterior work:
    - Reconstruction of roof on exit stair on West side of Tassie Hall for
    - Repointing of stone masonry (by Cash Allowance)
    - Replacement of exterior stairs on South side of Tassie Hall
    - Provision of new areaway on South side of Tassie Hall
    - Replacement of exterior doors and windows (by Cash Allowacne)
    - Sidewalk replacement on South and East sides of Tassie Hall
2. Interior Work:
    - Removal of existing seating on main level and mezzanine
    - Plaster repair (by Cash Allowance)
    - Refinishing of wood floors (by Cash Allowance)
    - Painting of all spaces
    - Provision of new seating on main level and mezzanine
    - Provision of new acoustic treatment (by Cash Allowance)
    - Removal of existing plumbing/ plumbing fixtures
    - Removal of existing HVAC equipment and services
    - Provision of new plumbing fixture and services
    - Provision of new HVAC Equipment for Tassie Hall and ancillary spaces, including the installation of new ductwork
    - Provision of new fire protection system (by Cash Allowance)
    - Provision of new controls systems
    - Removal of existing lighting, power and systems, including distribution
    - Provision of new lighting, power and systems, including all distribution.
3. Note: An Optional Price has been identified on the Electrical Drawing E2.1, as follows: Identify the price for all labour and materials associated with the deletion of the existing Teck feeders between ‘DP-BBB’ and ‘STL’; and the provision of 4-#3/0 T90 in 53mm EMT between ‘DP-BBB’ and ‘P32B’.

Refer to Drawings and Specifications for full Scope of Work.

**END OF SECTION**

## 00 31 34 – Subsurface Investigation Report – Not Applicable

### 1.0 General

### 1.1. Related Sections

.1 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. SUBSURFACE INVESTIGATION REPORT

.1 An investigation report with respect to the applicable building site and important immediate affected surroundings, is titled as follows:

.1 Title: Not Applicable

.2 Dated: Not Applicable

.3 Prepared By: Not Applicable

.2 A copy of this detailed investigation report is included as an appendix to this section.

.3 The subsurface investigation report records properties of the soils, subgrade conditions, and offers recommendations for the design of foundations.

.4 The report was prepared primarily for the use of the Consultants.

.5 The recommendations given shall not be construed as a requirement of this Contract unless also contained in the Contract Documents.

.6 The report, by its nature, cannot reveal all conditions that exist or can or might occur on the subject site. Should subsurface conditions be found or be a concern thereto, or to vary substantially from the investigation report, changes in the design and construction of foundations will be made, with resulting credits or expenditures to the Contract Price accruing to the Owner.

**END OF SECTION**

**Appendix 00 31 34A – Soil Report – NOT APPLICABLE.**

## Appendix 00 41 13A – Asset and Warranty Card

### WRDSB PROJECT ASSET & WARRANTY CARD

**Instructions:**

a. The WRDSB Project Asset & Warranty Card shall be filled out and completed for any project or work that calls for the replacement or new installation of any asset that has a warranty and requires ongoing preventative maintenance, as well any asset that is being removed.

b. The information for the WRDSB Project Asset & Warranty Card shall be collected and coordinated by the General Contractor responsible for the overall project. The WRDSB Project Asset & Warranty Card shall be filled out and submitted to the Board electronically to FAC_maintenance@wrdsb.ca and carbon copy the project coordinator at the point in time where the project is deemed "Substantially Complete" or at the start of the Warranty Period for said asset. For any project without a General Contractor, the Contractor or Trade responsible for the installation and/or removal of the asset shall complete the WRDSB Project Asset & Warranty Card and submit it to the Board in the same manner as mentioned above.

c. All items shall include the asset Identifier, asset description, location, manufacturer, model, serial number, and warranty end date (refer to example at bottom of page).

d. NO Warranty Period shall start without the written permission of the Board prior to the point of Substantial Completion of the project.

e. The Contractor that is responsible for the coordination and completion of the WRDSB Project Asset & Warranty Card shall ensure that the contractor or trade responsible for the installation of the item understands that the contractor or trade is responsible for the preventative and general maintenance of that item for the minimum 2 year warranty period as noted on the WRDSB Project Asset & Warranty Card.

f. **All** items installed under this contract that require ongoing preventative maintenance (PM) shall be included on the WRDSB Project Asset & Warranty Card. The following list contains examples to be included but not limited to;

| | | |
|---|---|---|
| Air Compressor | Chiller | Grease Trap |
| Air Handler- ERV, Heat Pump, RTU | Cooling Tower | Gym Equipment |
| AC Split -Indoor/Outdoor Unit | Elevator/Lift | Hoods- Kitchen/Fume |
| Automatic Doors | Eyewash Station-location only | Operable Partitions |
| Backflow Preventer | Fire Panel | Sprinkler System -area covered |
| Boiler | | Tech Equipment |

g. All maintenance during the warranty period shall be the responsibility of the contractor. This shall include, but not be limited to: air handling unit filter changes (3x min.per year), or as per manufacturers recommendations; servicing testable backflow preventors, including fees; and any and all required maintenance.

**Sample:**

| *To be filled out by Consultant* | | | | *To be filled out by Contractor* | | | | |
|---|---|---|---|---|---|---|---|---|
| IDENTIFIER | ASSET | LOCATION (incl. Rm. No.) | REMOVED (R), OR NEW (N) | CONTRACTOR | MANUFACTURER | MODEL | SERIAL NUMBER | WARRANTY END DATE |
| *Boiler 2* | *Condensing Boiler* | *Boiler Rm. B005* | *R* | *Bob's Mechanical* | *Viessman* | *Vitocrossal 300 CA3B* | *1234x5678y90* | *Jan. 1, 2025* |
| *HVAC 7* | *New RTU* | *Roof D* | *N* | *Bob's Mechanical* | *Daiken* | *DPS020A* | *ABCD1EFGH2IJ* | *Jan. 1, 2025* |
| *n/a* | *Gym Partition* | *Gyms 122/123* | *R* | *Extreme Partitions* | *Hufcor* | *933EC* | *n/a* | *Jun. 30, 2028* |
| | | | | | | | | |
| | | | | | | | | |

### WRDSB Project Asset & Warranty Card

Project Name: _____

**School / Location:** _____

Date: _____

| *To be filled out by Consultant* | | | | *To be filled out by Contractor* | | | | |
|---|---|---|---|---|---|---|---|---|
| IDENTIFIER | ASSET | LOCATION (include Room No.) | ASSET REMOVED (R) OR NEW (N) | CONTRACTOR | MANUFACTURER | MODEL | SERIAL NUMBER | WARRANTY END DATE |
| | | | | | | | | |

## 00 56 13 – Definitions Stipulated Price

### 1.1. Definitions Declaration

.1 CCDC 2-2020 Edition, Stipulated Price Contract as may be amended, forms the basis of Definitions between the Owner and Contractor.

.2 These Definitions are bound to the CCDC 2 Definitions and CCDC 2 General Conditions.

### 1.2. Supplementary Words and Terms to CCDC 2-2020

.1 The following words and terms are additional to the CCDC 2 Definitions.

.2 Addendum: A document that amends the Bid Documents during the Bidding Period and becomes part of the Contract Documents when a Contract is executed. (Plural: Addenda).

.3 Agreement: The signed and sealed legal instrument binding parties in a Contract, describing in strict terms their mutual arrangement, roles and responsibilities, commencement, and completion responsibilities.

.4 Alternative Price: The amount stipulated by a Bidder for an Alternative and stated as an addition, a deduction, or no change to the Bid Price.

.5 Authorities: Those having jurisdiction under law over Work or Parts thereof.

.6 Bid: To offer as a Bid stating for what price a Contractor will assume a Contract.

.7 Bid Documents: A set of documents consisting of the Instructions to Bidders, Bid Form, Contract Documents, and other information issued for the benefit of Bidders to prepare and submit a Bid.

.8 Bid Form: The specific and detailed form used to collect information about a Bid.

.9 Bidding: The process of preparing and submitting a Bid.

.10 Construction Documents: The Drawings and Project Manual. When combined with a Contract and Contract conditions, these documents form the Contract Documents.

.11 Contingency Allowance: An additional monetary amount added to a Project cost estimate and designated to cover unpredictable or unforeseen items of Work. The amount is usually based on some percentage of the estimated cost and expended and adjusted by Change Order. It is not intended to cover additions to the scope of Work.

.12 General Conditions: That part of the Contract Documents which sets forth many of the rights, responsibilities and relationships of the parties involved in a Contract.

.13 Exposed: Visible at completion of Work, in usable areas as well as interior of closets, cabinets, drawers, storage and service rooms, stairwells and exterior surfaces.

.14 Instructions To Bidders: Instructions contained in the Bid Documents to convey an Owner's expectations and criteria associated with submitting a Bid.

.15 Ready for Takeover: *Ready-for-Takeover* shall have been attained when the conditions set out in GC12.1, SC 55.1, 12.1.1

.16 Section: A portion of a Project Specification covering one or more segments of the total Work or requirements. Sections are included in a Project manual as required to meet Project requirements.

.17 Standard: A document describing a grade or a level of quality, which has been established by a recognized agency or organization, utilizing an internal voting process.

.18 Separate Price: A separate price for work to be added to the base price if selected by the Owner. This price type is not a part of the base bid price.

.19 Stipulated Price: An amount set forth in a Stipulated Price Contract as the total payment for the performance of the Work. Sometimes referred to as a stipulated sum or a lump sum stipulated price.

.20 Tender: Refer to definition of Bid.

.21 Unit Price: The amount payable for a single unit of Work as stated in a Schedule of Prices.

.22 Install: To remove from site storage, move or transport to intended location, install in position, connect to utilities, repair site caused damage, and make ready for use.

.23 Supply: To acquire or purchase, ship or transport to the site, unload, remove packaging to permit inspection for damage, re-package, replace damaged items, and safely store on-site.

.24 Provide: To Supply and Install

.25 Wherever words 'approved', 'selected', 'satisfactory', 'directed', 'permitted', 'inspected', 'instructed', 'required', 'submit', 'ordered', 'reviewed', 'reported to', or similar words or phrases are used in Contract Documents, it shall be understood, unless context provides otherwise, that words 'by Consultant' or 'to Consultants' follow.

.26 Words 'by others' when used in Specifications or on Drawings shall not mean by someone other than Contractor. Only means by which something shown or specified shall be indicated as not being in Contract is by initials 'NIC' or words 'not in Contract', 'by Owner', or 'by Other Contractor'.

**END OF SECTION**

## 00 72 13 – WRDSB Standard Terms and Condition

### 1. Applicable Terms and Conditions

None of the standard or other terms, conditions, or policies of the Bidder, whether published or otherwise shall be of any effect unless accepted by the WRDSB in writing. This includes, without limitations, terms in publications, website, sales invoice, delivery document as well as those commonly applied by the Bidder. WRDSB's acceptance of goods, equipment or service, acknowledgement thereon or paying invoices shall not imply acceptance of such terms, conditions, or provisions.

### 2. Bankruptcy

If, during the term of the Contract, the Supplier makes an assignment for the benefit of creditors, or becomes bankrupt or insolvent, or makes a proposal to its creditors, the Contract with the Supplier shall immediately be terminated, and the WRDSB shall be entitled to enter into an agreement with another party without the consent of the Supplier.

### 3. Basis of Award (Price factor)

Bidders shall be deemed to have included all costs related to the Work in the Total Price as provided in their Bid, except for items clearly identified as provisional in the Procurement document. In no case shall the invoicing for the entire Work performed exceed the Total Price unless additional Work is ordered by the WRDSB in writing. The unit prices as well as provisional pricing shall be used to invoice the additional or provisional work, as required by the WRDSB. For the purpose of award, the Total Price will be considered as representing the intention of the Bidders and will be used as the basis for comparison of Bids for the price factor.

### 4. Bonding Requirements

Bonding is only required if the project is equal to or greater than $200,000.00.

Note: The Bidding System has flagged these fields as mandatory. If your bid is less than $200,000.00, you may upload a pdf document stating: Not Applicable.

#### i. Bid Amount

Bonding requirements are based on the total base bid amount INCLUSIVE of ALL applicable taxes.

#### ii. Bid Deposit Bond & Agreement to Bond

Bid submissions must be accompanied by a bid deposit in the form of a digital Bid Bond in an electronically verifiable and enforceable (e-Bond) format in the amount of 10% of the total base bid (inclusive of HST) made payable to the Waterloo Region District School Board as surety that, if the Bid is accepted, a Contract will

be entered into for the proper performance of the work. For more information, contact your surety company or visit the Surety Association of Canada website.

Bid Submissions must be accompanied by an Agreement to Bond in the form of a digital Bond in an electronically verifiable and enforceable (e-Bond), completed and executed by the Bidder's Surety, assuring the successful Supplier shall provide for a Performance Bond for 50% of the total Contract Price, and a Labour and Material Payment Bond for 50% of the total Contract Price.

Bidders shall upload their digital Bid Deposit Bond and Agreement to Bond separately to the Bidding System, in the bid submission files labeled "Bid Deposit Bond" & "Agreement to Bond". If both Bonds are within one (1) document, upload it in both files. All instructions and details for accessing authentication shall be included with the digital Bonds uploaded in the Bidding System. Do not include and/or upload Performance Bond and Labour and Materials Bond in this section.

Bids that do not contain the bid deposit(s) in the required amount will be declared non-compliant and will be rejected. A scanned PDF copy of bonds or original certified cheque, bank draft, money order, etc. are not acceptable as Bid deposit and will result in your Bid being rejected.

The bid deposit of the Bidder whose submission is accepted shall be forfeited by the Bidder should the Bidder fail to execute a Contract or provide the necessary documents as required within this Procurement document (including but not necessarily limited to: signed agreement, satisfactory security, insurance certificate, appropriate Workplace Safety and Insurance Board letter of clearance certificate) within the time stipulated as a written notice from the WRDSB.

For bid amounts where Bonding is not requested, the Awarded Bidder agrees to pay to the WRDSB the difference in costs between the bid submitted and the final contract should the Awarded Bidder fail to either execute or deliver the contract documents in accordance with the Procurement within seven (7) calendar days of written notification of the award of the contract.

**iii. Performance and Labour & Materials Bonds**

For bid amounts where bonding is required, inclusive of all taxes, the Supplier shall provide a digital Bid Performance and Labour and Materials Bond in an electronically verifiable and enforceable (e-Bond) format in the amount(s) of not less than 50% Performance Bond and a 50% Labour and Materials Bond of the total Contract Price made payable to the Waterloo Region District School Board as surety that, if the Bid is accepted, a Contract will be entered into for the proper performance of the work and extends protection to Subcontractors, Suppliers,

and any other persons supplying labour or materials to the Project. For more information, contact your surety company or visit the Surety Association of Canada website.

If the Supplier fails to provide a performance bond and/or labour and materials bond when requested, the WRDSB may declare the bid deposit forfeited, and the Bidder will be held responsible for any increased costs or damages incurred by the WRDSB. Any Bidder who fails to provide all required documents within the timelines provided or otherwise fails to enter into an agreement with the WRDSB upon notice of being the Supplier may be subject to future bidding constraints by the WRDSB.

Performance bond shall guarantee all conditions as set out in the contract, including proper execution of the work and for all matters for which the Supplier is responsible for throughout the two (2) year period of maintenance and warranty.

Any costs associated with performance bond are the responsibility and cost of the Bidder.

Bonds must be submitted through the Bidding System within seven (7) calendar days of receiving the Intent to Award.

**5. Business Code of Conduct for Board Employees**

The WRDSB will not knowingly purchase goods and/or services from Suppliers who operate in contravention of local and international laws. If a product and/or service supplied to the WRDSB is discovered to be in contravention, the WRDSB reserves the right to rectify the issue with the Supplier, including the cancellation of the contract.

The WRDSB expects that all employees and Suppliers act within the parameters of the in Administration Procedure 4360 PRINCIPLES OF BUSINESS CONDUCT FOR BOARD EMPLOYEES. Click here to access the WRDSB's Administrative Procedures, Section 4000 – Business Services.

**6. Code of Conduct for Suppliers**

These Guidelines cover any contractor, supplier, consultant, business, firm, company or individual doing work, providing a service or delivering goods on any Waterloo Region District School Board property, as well as the Supplier's employees, subcontractors, agents, consultants, and others on site in connection with the Supplier's work or at the Supplier's express or implied invitation.

i. Courtesy and Respect: all Suppliers and their employees must conduct themselves in a manner that is lawful, courteous, respectful, businesslike, and free of bias to the WRDSB, its officer, employees, students, guests, or visitors.

ii. Language and Behavior: Suppliers and their employees cannot engage in behavior that is rude, threatening, or offensive. Use of profane or insulting language is prohibited. Harassment of any type, including sexual harassment is strictly prohibited. Abusive, derogatory, obscene or improper language, gestures, remarks, whistling, cat calls or other disrespectful behavior cannot be tolerated. Rough housing, fighting, fisticuffs, physical threats, destruction of property, vandalism, littering, or physical abuse of anyone on WRDSB property are not permitted under any circumstance.

iii. No Weapons, Alcohol, or Drugs: The use, possession, distribution, or sale of any weapon, alcohol, illegal drug, or controlled dangerous substance by any Supplier or Supplier's employee is prohibited. Offenders will be removed from WRDSB property and/or reported to the local Police Department.

iv. Smoking: Suppliers and their employees are not permitted to smoke on WRDSB property, in or near any buildings.

v. Fraternization: Suppliers and their employees may not fraternize or socialize with WRDSB students or employees.

vi. Appearance: Suppliers and their employees, where applicable, are required to wear appropriate Personal Protective Equipment (PPE), work wear, hard hats and safety footwear high-visibility clothing, while on WRDSB property. Articles of clothing must be neat and tidy in appearance, and cannot display offensive or inappropriate language, symbols, or graphics. WRDSB has the right to decide if such clothing is inappropriate.

vii. Identification: contracted suppliers and their employees are required to wear branded attire of the company they work for when on WRDSB property.

viii. Vehicles and Driving on WRDSB Property: Vehicles must clearly indicate the Supplier's company name, identifier number and telephone number. It must be readable from 8 meters (25 feet) away. Vehicles including movable Equipment/Machinery must not enter, leave or drive on WRDSB premises during nutritional breaks, before and after school hours, or anytime there are students or staff outside of the building.

ix. Reporting: The Supplier is required to report any matter involving a violation of these rules of conduct, any matter involving health or safety, including any altercations, to WRDSB Facilities staff.

The Supplier is responsible for its employees, agents, consultants and guests. If prohibited conduct does occur, the Supplier will take all necessary steps to stop and prevent any future occurrence. Any breach of these conditions will result in the removal of the person

responsible from the school premises and prohibited actions could result in the termination of any contract or agreement with WRDSB.

**7. Compliance with Laws, Acts and Regulations**

Suppliers shall abide by all applicable municipal, provincial and federal laws, as well as WRDSB Policies. Some of the applicable laws are highlighted below for information purposes only. In case of any discrepancy between this Procurement Document and the provision of applicable laws, the latter shall prevail. This list is not intended to be a comprehensive summary of relevant laws or be a complete list of applicable regulations or interpretation of the provisions of any laws

i. Accessibility for Ontarians with Disabilities Act (AODA)
ii. Architect Act
iii. Bill S-211 Fighting Against Forced Labour and Child Labour in Supply Chains Act
iv. Broader Public Sector Accountability Act, 2010
v. Building Ontario Businesses Initiative (BOBI) Act, 2022
vi. Canada Revenue Agency (CRA) regulations
vii. Confidentiality Acts (MFIPPA, PIPEDA etc.)
viii. Construction Act
ix. Education Act
x. Occupational Health and Safety Act
    a. Ontario Regulation 157/25, Section 27.1.
       This regulation requires Constructors to have a defibrillator (AED) on construction projects with 20 or more regularly employed workers (effective January 1, 2026), and ensure a worker trained in CPR/AED operation is present at all times.
xi. Supply Ontario: Supply Chain Management Act (Government, Broader Public Sector and Health Sector Entities), 2019, S.O. 2019, c. 15, Sched. 37
xii. Trade Agreements (CETA/CFTA etc.)
xiii. Workplace Safety and Insurance Act (WSIB)
xiv. WRDBS Procurement Services Policies website
xv. WRDSB Policies and Procedures

Non-compliance with provincial and/or federal laws, or WRDSB Policies may result in rejection of the Bidder's Bid submission and/or termination of Contract.

Bidders should make themselves aware of provisions in all applicable provincial and federal laws as well as WRDSB policies and ensure full compliance. Non-compliance may result in rejection of Bid and/or termination of Contract.

The Supplier(s) will be required to comply with all applicable federal, provincial laws as well as WRDSB policies in performing its obligations under the Contract including, without limitation, the Occupational Health and Safety Act, as amended, and the Workplace Safety and Insurance Act, 1997, as amended, and Accessibility for Ontarians With

Disabilities Act, 2005, S.O. 2005, c.11, Accessibility Standards for Customer Services O. Reg. 429/07 requirements, under the Accessibility for Ontarians With Disabilities Act, 2005, as amended, or any successor legislation applicable, and to provide to the WRDSB, upon request, periodic reports and evidences confirming such compliance.
By supplying the goods or equipment and/or providing services, the Supplier warrants that the goods or equipment supplied, and services provided to the WRDSB conforms in all respects to the standards and codes set forth by federal and provincial agencies. Failure to comply with this condition will be considered a breach of this Contract.

The obligations of the parties and resolutions of any disputes shall be governed by and construed in accordance with the laws of the Province of Ontario and the federal laws of Canada, including the Construction Act, as to interpretation and performance, and shall be treated, in all respects, as an Ontario contract. The parties shall attorn to the exclusive jurisdiction of the courts of the Province of Ontario.

**8. Confidential Information, MFIPPA, and PIPEDA**

All information and documentation provided by the WRDSB or to the WRDSB in connection with this Procurement, before or after the issuance of this Procurement is the sole property of the WRDSB and shall be treated as confidential, subject to the provisions of the Municipal Freedom of Information and Protection of Privacy Act (MFIPPA).

Bidders shall identify any confidential information in their Bid Submission. The WRDSB will make reasonable efforts to safeguard confidential information, subject to its disclosure requirements under MFIPPA or any other disclosure requirements imposed by law or by order of a court or competent tribunal. Bidders are advised that their Bid submissions may be disclosed, on a confidential basis, to advisers retained by the WRDSB to advise or assist with the Bid process, including the evaluation of Bid submissions.

Bidders should be aware that when submitting a Bid, the name, title, and contact information will be made public upon request. Under MFIPPA, and as a record of the WRDSB, the Bid prices submitted and agreed to under contract with the WRDSB can also be made available through a Freedom of Information request. Bidders will be notified regarding requests for any other information submitted in a Bid; information may be disclosed to a requester in whole or part unless otherwise considered exempt from disclosure under MFIPPA.

The Supplier represents and warrants that if it is or becomes subject to any private sector privacy legislation during the Term it will be solely responsible for compliance with such legislation. Without limitation, the Supplier represents and warrants that if it is subject to the *Personal Information Protection and Electronic Documents Act*, S.C. 2000, c.5, including any further amendments thereto (PIPEDA):

i. it and all the Supplier's Subcontractors shall ensure the PIPEDA compliance of all PIPEDA Protected Information it collects directly from individuals or indirectly from the WRDSB, uses or discloses while performing their obligations under this Agreement; and,

ii. without limitation, it shall ensure the PIPEDA compliance of all PIPEDA Protected Information it transfers or discloses to the WRDSB.

**9. Confirmation to Proceed**

No work shall commence until the WRDSB has issued a purchase order and/or contract, if applicable to the Supplier. Goods/Service or Work as described shall not commence until all the required documents have been submitted to Procurement Services and the Form of Agreement and/or the CCDC 2 - 2020, if applicable, are executed by the Supplier and the WRDSB. For payment purposes, a Purchase Order shall be generated and issued to the Supplier. The Purchase Order number must appear on all invoices to ensure prompt payment.

**10. Conflict of Interest**

By submitting a Bid, the Bidder confirms that they have no conflict of interest with respect to other work and/or other clients. The Bidder shall ensure that all subcontractors, subconsultants and suppliers also have no conflict with respect to other work and/or other clients.

The Supplier, subcontractors and sub-suppliers and any of their respective advisors, partners, directors, officers, employees, agents, and volunteers shall not engage in any activity or provide any services where such activity or the provision of such services creates a conflict of interest (actually or potentially, in the sole opinion of the Owner) with the provision of the Work pursuant to the Contract. The Supplier acknowledges and agrees that a conflict of interest, as described in this section includes, but is not limited to, the use of Confidential Information where the Owner has not specifically authorized such use.

The Supplier shall disclose to the Owner, in writing, without delay, any actual or potential situation that may be reasonably interpreted as either a conflict of interest or a potential conflict of interest, including the retention of any Subcontractor or Supplier that is directly or indirectly affiliated with or related to the Supplier.

The Supplier covenants and agrees that it will not hire or retain the services of any employee or previous employee of the Owner where to do so constitutes a breach by such employee or previous employee of the Owner's conflict of interest policy, as it may be amended from time to time, until after completion of the Work/Services under the Contract.

It is of the essence of the Contract that the Owner shall not have direct or indirect liability to any Subcontractor or Supplier, and that the Owner relies on the maintenance of an arm's-length relationship between the Supplier and its Subcontractors and Sub-suppliers. Consistent with this fundamental term of the Contract, the Supplier will not enter into any agreement or understanding with any Subcontractor or Supplier, whether as part of any contract or any written or oral collateral agreement, pursuant to which the parties thereto agree to cooperate in the presentation of a claim for payment against the Owner, directly or through the Supplier, where such claim is, in whole or in part, in respect of a disputed claim by the Subcontractor or Supplier against the Supplier, where the payment to the Subcontractor or Supplier by the Supplier is agreed to be conditional or contingent on the ability to recover those amounts or a portion thereof from the Owner, failing which the Supplier shall be saved harmless from all or a portion of those claims. The Supplier acknowledges that any such agreement would undermine the required arm's-length relationship and constitute a conflict of interest. For greater certainty, the Supplier shall only be entitled to advance claims against the Owner for amounts pertaining to Subcontractor or Supplier claims where the Supplier has actually paid or unconditionally acknowledged liability for those claims or where those claims are the subject of litigation or binding arbitration between the Subcontractor or Supplier and the Supplier has been found liable for those claims.

A breach by the Supplier, any of the Subcontractors, Sub-suppliers or any of their respective advisors, partners, directors, officers, employees, agents, and volunteers shall entitle the Owner to terminate the Contract, in addition to any other rights and remedies that the Owner has in the Contract, in law, or in equity."

**11. Construction Act Guidelines**

For Work that is governed by the provisions of the Construction Act, the Construction Act shall apply where applicable including in respect to release of 10% holdback, 2% deficiency holdback, adjudication, and the provision of security.

**12. Criminal Background Checks and Collection of Personal Information**

The WRDSB must comply with Ontario Regulation 521/01 (Collection of Personal Information) of the Education Act with respect to criminal background checks and offence declarations.

If required by the WRDSB, the Supplier will provide to the WRDSB, or designate, a Criminal Background check for pertinent individuals covering offences under the Criminal Code, the Controlled Drugs and Substances Act, and any other offences which would be revealed by a search of the automated Criminal Records Retrieval System.

An Offence Declaration on a WRDSB-approved form for every employee of the Supplier who may come in direct contact with WRDSB staff and/or students on a regular basis at any WRDSB site prior to the occurrence and on or before September 1 each year

thereafter may be required. Updated Offence Declarations may be required annually. The WRDSB will determine in its sole discretion whether this is a requirement.

Termination of contracts may be the result of non-compliance to this requirement.

**13. Damage Responsibility of Supplier**

The Supplier, their agents and all workers and persons employed by them or under their control, shall use due care that no person or property is injured and that no rights are infringed in the prosecution of the work, and the Supplier shall be solely responsible for all damages by whomsoever claimable in respect of any injury to persons or to lands, buildings, structures, utilities, survey markers, fences, livestock, trees, crops, roads, ways, ditches, drains and in watercourses, whether natural or artificial, or property or whatever description and in respect of any infringement of any right, privilege or easement whatever occasioned in the carrying on of the work or any part thereof, or by any neglect, misfeasance or nonfeasance on the Supplier's part or on the part of any of his agents, workers and persons employed by them or under their control shall bear the full cost thereof and shall at his own expense make such temporary provisions as may be necessary to ensure the avoidance of any such damage, injury or infringement.

The Supplier shall indemnify and save harmless the WRDSB from and against all claims, demands, loss, costs, damages, actions suits or other proceedings by whomsoever made, brought, or prosecuted in any manner based upon, occasioned by, or attributed to any such damage, injury, or infringement.

Notwithstanding the indemnity provisions contained in this section, where in the opinion of the WRDSB Representative the Supplier has failed to rectify any damage, injury or infringement or has failed to adequately compensate any person for any damage, injury or infringement for which the Supplier is responsible under the Contract, the WRDSB, following notice in writing to the Supplier of his intention so to do, may withhold payment of any monies due to the Supplier under this or any other Contract until the Supplier has rectified such damage, injury or infringement or has paid adequate compensation for such damage, injury or infringement.

**14. Damage Reporting**

If a utility structure or device, utility cable/conduit, or utility related infrastructure is damaged, the Supplier shall notify the WRDSB representative the same working day of any service disruption or damage and the Supplier will immediately notify the utility company to initiate repair. The Supplier will additionally make every reasonable effort to advise impacted resident(s) of a service disruption.

It is understood that all damage caused by workers engaged in the work under these specifications will be repaired by the Supplier and at the Supplier's sole expense. Damaged turf areas will be levelled and seeded, all horticultural planting damaged beyond repair will be replaced and any damage to structures, utilities, signs, light fixtures, landscape furniture, irrigation systems etc. will be repaired or replaced. Repair work will

be carried out by skilled workers acceptable to the WRDSB representative. All repairs and replacements will be approved by a WRDSB representative prior to final payment.

**15. Debriefing Requests**

For procurements valued at $121,200 or more, and in accordance with the Broader Public Sector Procurement Directive, unsuccessful Bidders are entitled to a debriefing to receive feedback with respect to their Bid submission. To obtain a debriefing, Bidders shall contact the Single Point of Contact listed in this Procurement Document in writing with their request within sixty (60) calendar days of the award notification.

**16. Default**

If the Supplier fails to properly, promptly, and fully carry out the Work required by these documents, the WRDSB reserves the right to notify the Supplier to discontinue all Work under this Contract, to advertise for new Bids or carry out the Work in any way as the WRDSB may, in their sole discretion, deem best.

The Supplier further agrees to indemnify and save harmless the Indemnified Parties from all loss, damage, liability, cost, charge, or expense whatsoever which it, they or any of them may suffer, incur or be put to by reason of such default or failure.

**17. Delay Claims**

The Supplier shall be responsible for all deliverables including lead times. The bidder shall include in their bid price any costs associated with an extended schedule beyond the stated substantial completion date due to delayed deliveries of items. Cost is to be inclusive of any afterhours work required due to the school being occupied by staff and students during the school year until completion.

The WRDSB will not accept or consider any "delay claim" requests for delayed deliverables outlined in the tender documents.

**18. Delivery and Transportation Charges**

Unless otherwise specified under the Special Provisions and/or Scope of Work and Deliverables sections of this document, prices documented shall be net prices including transportation and delivery charges fully paid by the Supplier and Free On Board (FOB) Destination, Freight Prepaid (any/all WRDSB locations).

**19. Designated Substances**

The Occupational Health and Safety Act of Ontario (OHSA) allow for certain toxic substances to be especially designated. The OHSA defines a designated substance as “a biological, chemical, or physical agent or combination thereof prescribed as a designated substance to which the exposure of a worker is prohibited, regulated, restricted, limited, or controlled”. Ontario Regulation 490/09 - Designated Substances (O.Reg. 490/09), made under the Occupational Health and Safety Act outlines required steps to control exposure of workers to designated substances. Under O. Reg. 490/09 there are eleven (11)

designated substances: acrylonitrile, arsenic, asbestos, benzene, coke oven emissions, ethylene oxide, isocyanates, lead, mercury, silica and vinyl chloride. This regulation applies to every employer and worker at a workplace where the designated substances are present, produced, processed, used, handled or stored and at which a worker is likely to be exposed to the designated substance.

**i. Asbestos**

Asbestos-containing material (ACMs) were identified during the completion of the Asbestos Audit Update Report (AAU), prepared by WRDSB retained consultants. Each facility was surveyed, and if applicable, an AAU Report is available, refer to attached**,** Appendix 01 35 34A. If these materials, including those deemed or suspected, will be disturbed, or will likely be disturbed, during building maintenance, renovations, construction, or demolition activities, they must be handled and disposed of in accordance with the procedures prescribed by O. Reg. 278/05.

Should the Supplier encounter asbestos, not noted in the above AAU Report, which would be disturbed during the course of the Work they should stop the work in that immediate area and report the same to the WRDSB Contact.

All asbestos work must be conducted by Suppliers approved by the WRDSB, who are trained in the type of asbestos operations required and should be overseen by a qualified third-party Health, Safety and Environmental professional. To conduct Type 3 asbestos operations, Suppliers must be certified as Asbestos Abatement Workers AAW (Trade code 253W) and Asbestos Abatement Supervisors AAS (Trade code 253S) by The Ministry of Training, Colleges and Universities as prescribed by Section 20 of O. Reg. 278/05.

Unless otherwise specifically covered by Cash Allowance or Contingency Allowance for known asbestos materials, include in this contract for the removal under abatement, in compliance with O. Reg. 278/05, of all known asbestos containing materials, as identified in the audit, within 0.6 meter (2’-0”) of all new services, materials, and equipment, and/or as required to complete the work. No claims for extra cost will be accepted for areas known to contain asbestos containing materials.

**ii. Lead**

Lead was historically used in mortar pigments, ceramic glazing; plumbing solder, electrical equipment and electronics solder, in pipe gaskets as packing in cast iron bell and spigot joints of sanitary drains, flexible plumbing connections, flashing panels, acoustical dampeners, phone cable casing and some architectural applications. The assessment of lead for this assignment was limited to paint on interior and exterior surfaces which may be disturbed during the Work.

Preliminary paint, coatings or materials were collected within the work area to determine if lead-containing paints, including lead-based paints, are present. The analytical results, if applicable, including the location marked on the floor plans are available, refer to attached, Appendix 01 35 34B.

Should the Supplier encounter paint and coatings, not sampled, that would be disturbed during the course of the Work, they should stop the work in that immediate area and report the same to the WRDSB Contact.

Unless otherwise specifically covered by Cash Allowance or Contingency Allowance for known lead-containing paint and coatings, include in this contract for the removal or disturbance of lead-containing materials, must be completed in compliance with "Lead on Construction Projects" guideline (April 2011). No claims for extra cost will be accepted for lead-containing paint or coatings in identified areas.

The classification of typical lead-containing construction tasks is based on presumed airborne concentrations obtained from the U.S. Occupational Safety and Health Administration (OSHA), the Ontario Ministry of Labour, and published research studies. The classification of Type 1, Type 2, or Type 3 operations are grouped based on the following concentrations of airborne lead

Supplier shall inform all workers of the presence of paint finishes that are lead containing. Disturbance of lead-containing materials, paints or surface coatings shall be conducted in accordance with the procedures outlined in the Environmental Abatement Council of Canada (EACC) "Lead Guideline" (October 2014) and/or the Ministry of Labour (MOL) "Lead on Construction Projects" guideline (April 2011). The extent of procedures required depends on the type of work to be conducted. Waste to be handled and disposed of in accordance with O.Reg. 347.

**iii. Mercury**

Mercury is typically used in building service applications such as thermometers, barometers, thermostats, gauges, electrical switches, and lighting products including fluorescent light bulbs and a variety of High Intensity Discharge (HID) lamps as mercury vapour, metal halide and high pressure sodium lamps. Lamps and other devices that require demolition are to be handled with care and kept intact to avoid potential exposure. Any mercury-containing lamps or other equipment that are demolished are to be recycled. Waste to be handled and disposed of in accordance with O.Reg. 347.

**iv. Silica**

Silica is present in rock, stone, soil, and sand. Masonry products such as concrete block, brick, and mortar, as well as concrete and associated products contain silica.

Due to its ubiquitous nature, silica was historically used in a wide variety of building materials and is still used today in new construction.

All work involving the demolition silica-containing materials shall follow the procedures outlined in the MOL "Silica on Construction Projects" guideline. Type 1 operations may be necessary based on the type of work conducted and the Supplier shall implement dust suppression methods and protect workers.

**v. Other Designated Substance**

In addition to asbestos and/or lead, silica, and mercury are present in all WRDSB facilities. New construction, renovation, or alterations require compliance by the Supplier with the applicable legislation. Other designated substances (i.e., acrylonitrile, arsenic, benzene, coke oven emissions, isocyanates, ethyl oxide, and vinyl chloride) are not encountered in WRDSB facilities as significant constituents or in a form that would represent an exposure concern.

**20. Dispute Resolution**

All disputes arising out of or in connection with this Contract, or in respect of any legal relationship associated with or derived from this Contract, other than with respect to the WRDSB's right to terminate this Contract, shall first be mediated pursuant to the National Mediation Rules of the ADR Institute of Canada, Inc. Despite this agreement to mediate, the Supplier or the WRDSB may apply to a court of competent jurisdiction or other competent authority for interim measures of protection at any time. All disputes remaining unsettled after mediation shall be arbitrated and finally resolved before a single arbitrator pursuant to the National Arbitration Rules of the ADR Institute of Canada, Inc. The place of mediation and arbitration shall be Toronto, Ontario, Canada. The language of the mediation shall be English.

**21. Duty to Disclose Change of Control**

If the Supplier undergoes a change in control, the Supplier shall immediately disclose such change in control to the Designated Representative and shall comply with any terms and conditions subsequently prescribed by the WRDSB resulting from the disclosure.

**22. Electrical Safety Requirements**

All electrical equipment and components must be C.S.A., or Electrical Safety Association (E.S.A.) certified. A certification sticker must be affixed to the equipment in a visible location.

**23. Emergency and Maintenance**

The care of the Works until completed, delivered to and accepted by the WRDSB, rests solely with the Supplier who shall assume all risk of damage to the work.

For emergency and maintenance measures, the name, address, and telephone number of a responsible official of the contracting firm shall be given to the WRDSB's contact person in charge of the project, if requested. This official shall always be available and

have the necessary authority to mobilize workers and machinery and to take any action as directed by the WRDSB in the event emergency or maintenance measures are required, although the emergency or requirement of maintenance may have been caused by the Supplier's negligence, Act of God, or any cause whatsoever.

Should the Supplier be unable to carry out the required immediate remedial measures, the WRDSB may carry out the necessary repairs and the costs for this work shall be deducted from payments due to the Supplier.

## 24. Equivalents and Alternatives

### 24.1 Equivalents or Brands Names

24.1.1 Any reference to a brand name or a particular manufacturer shall be understood to have been made solely for the purpose of establishing and describing required performance and quality levels of the product to be supplied, unless specified otherwise.

24.1.2 No reference to the brand name of a particular manufacturer shall be construed to restrict Bidders to that manufacturer. Bidders are invited to Bid equivalent and comparable equipment or items of any manufacturer, pending approval from the WRDSB in the form of an Addendum. It is the Bidder's responsibility to demonstrate that the item meets the specifications.

24.1.3 Bidders shall request through the Bidding System by clicking on the "Submit a Question" button found within the bid details page of that Procurement that a proposed product be considered an approved equivalent prior to the Deadline for Questions in the Anticipated Project Schedule. Upon receipt of a request, the WRDSB will respond by providing further instructions where you may submit documentation.

24.1.4 The response must include enough detail to determine equivalency by comparing the WRDSB's specifications to the equivalent product. It will not be the WRDSB's responsibility to make this comparison.

24.1.5 The WRDSB/ Consultant may, depending on the nature of the product request site visits within a reasonable distance (preferable within 100 km of the WRDSB) showing product and installation based on a certain age, minimum 18 months in use, room use, room size, etc. based on same or similar purpose as described in this Procurement.

24.1.6 The WRDSB/Consultant will endeavor to complete a review and decide prior to the Closing Date, and, if required, the WRDSB reserves the right to extend the Closing Date to complete its review. However, in the event additional time is required beyond a suitable extension to the Closing Date, the request will be pending until the product is thoroughly vetted, therefore, it may not be approved for this Procurement.

24.1.7 If the WRDSB is willing to consider the product with its differences, it will be communicated in the form of an Addendum prior to the Closing Date.

24.1.8 The cost of any testing requirements to establish acceptable equivalent or comparable products will be borne by the Bidder, unless otherwise stated by the WRDSB.

**24.2 Alternatives and Substitutions**

24.2.1 After Contract Award, the Contractor may submit an alternate material or piece of equipment to the Consultant and Owner for review. An Alternate will only be evaluated and considered acceptable if it meets the intent of the original design and specifications, and where there is a credit or no additional cost to the Owner. The Specification Sections contain pertinent performance criteria, quality, function and requirements for materials and methods to achieve work described.

24.2.2 Material or equipment of equal or better performance and quality may be offered in substitution for those specified. Requests for review of substitute items of material and equipment will not be accepted by the Consultant from anyone other than the Contractor. All requests for substitution must be accompanied by a detailed listing of the expected cost savings to the Owner.

24.2.3 Substitutions will not be considered when they are indicated or implied on Shop Drawings or product data submittals without a separate written request.

24.2.4 Requests for substitution shall include any request for changes from the Contractor that require significant design changes, redesign, or significant design reviews.

A request for substitution constitutes a representation that the Contractor:

i. Has investigated the proposed product and determined that it meets or exceeds the quality level of the specified product.
ii. Will provide the same warranty for the substitution as for the specified product.
iii. Will coordinate the installation and amend other Work which may be required for the Work to be complete at the Contractor's expense and at no additional cost to the Owner.
iv. Waives claims for additional costs or time extension which may subsequently become apparent.
v. Will reimburse the Owner for review or redesign services.

24.2.5 Request for substitution to be made by written application to the Consultant and is to include sufficient data to enable the Consultant to assess the acceptability of requirements, including the following:

i. All submittal information required for the specified equipment, including all deviations from the specified requirements and/or necessitated by the requested substitution.
ii. Materials of construction, including material specifications and references.

iii. Dimensional drawings, showing required access and clearances, including any changes to the work required to accommodate the proposed substitution.

iv. Drawings and details showing changes if the offered substitution necessitates changes to or coordination with other portions of the Work. Perform these changes as part of the substitution of material or equipment at no additional cost.

v. Certification that the proposed substitute will adequately perform the functions and achieve the results called for by the general design, be similar and of equal substance to that specified and be suited to the same use as that specified with the same or better warranty.

vi. Information and performance characteristics for all system components and ancillary devices to be furnished as part of the proposed substitution.

vii. Certification that acceptance of the proposed substitute will not prejudice achievement of Substantial Performance.

viii. Itemization of all costs including any licenses fee or royalty that will result directly or indirectly from the acceptance of the proposed substitution. Include redesign and cost of claims of any other contract affected by the resulting change.

ix. Guaranteed credit or cost reduction offered if the proposed substitution is accepted and a waiver of claims for additional expenses which may subsequently become apparent.

x. Recommended maintenance requirements and availability of spare parts and service.

xi. Written confirmation from subcontractors and suppliers on cost, schedule, and technical requirements if requested by the Consultant.

24.2.6 Consultant will evaluate each proposed substitution. Consultant will be the sole judge of acceptability, and no substitute will be ordered, installed, or utilized without the Consultant's prior written acceptance by either a Change Order or a reviewed shop drawing. The burden of proof is on the Contractor.

24.2.7 Pay the Consultant's cost for evaluating the requested substitution even though the request may be denied, or for additional redesign work required because of any substitution. Costs will be charged on a time and expense basis and will be deducted from progress payments due to the Contractor.

**25. Evidence of Quality**

It is the Bidder’s responsibility to prove their product/service quality meets the WRDSB’s requirements and Bidders may be required to submit evidence in a form acceptable to the WRDSB. Substitution of materials, equipment or methods different from those outlined in the specifications / terms of reference will not be accepted unless provided for within the Procurement document or without the written approval of the WRDSB.

**26. Force Majeure**

If either party is delayed in the performance of their obligations under this Contract by Force Majeure, then the Contract Time shall be extended for such reasonable time as the Owner, and the Supplier shall agree. The extension of time shall not be less than the time lost because of the event causing the delay, unless the parties agree to a shorter extension. Neither party shall be entitled to payment for costs incurred by such delays. Upon reaching agreement on the extension of the Contract Time attributable to the Force Majeure event, the Owner and the Supplier shall execute a Change Order indicating the length of the extension to the Contract Time and confirming that there are no costs payable by the either party for the extension of Contract Time. However, if at the time an event of Force Majeure arises a party is in default of its obligations under the Contract and has received a notice of default shall not excuse a party from its obligation to cure the default(s). For greater certainty, the defaulting party, to the extent possible, must continue to address and cure the default notwithstanding an event of Force Majeure."

Any cause, unknown at the effective date of the Contract and beyond either party's control, other than financial difficulties, bankruptcy or insolvency, which prevents the performance by a party, or both, of any of their respective obligations under the Contract and the event of Force Majeure did not arise from a party's default and could not be avoided or mitigated by the exercise of reasonable effort or foresight. Force Majeure includes Labour Disputes; fire; unusual delay by common carriers or unavoidable casualties; delays in obtaining third-party licenses, permits, agreements, or approvals (excluding approvals of any Subcontractors or Suppliers of any tier); civil disturbance; emergency acts, orders, legislation, regulations or directives or revoking of funding from any government or other public authority; acts of a public enemy; war; riot; sabotage; blockage; embargo; lightning; earthquake; adverse weather conditions but only if substantially beyond the weather norms of the Place of the Work; acts of God; or declared epidemic or pandemic outbreak or other public health emergency (e.g. SARS, COVID-19)

If in the reasonable opinion of either party to this Contract that performance of the Contract is made impossible by force majeure, then either party shall notify the other in writing and the WRDSB shall either terminate the Contract forthwith without any future payments being made or authorize the Bidder to continue performance of the Contract with such adjustments as may be required by the existence of the force majeure and agreed upon by both parties.

**27. Hold Back or Set Off**

The WRDSB may hold back payment or set off against payment if, in the opinion of the WRDSB, the Supplier has failed to comply with any requirements of the Contract.

**28. Hot Work Procedure**

Take all precautions to Work safely and to provide the necessary protection to persons and property from Hot Work. This includes, but is not limited to Brazing, Cutting,

Grinding, Soldering, Thawing Pipe, Torch Applied Roofing and Welding. With all such activity these steps are to be followed:

i. Whenever possible, complete Hot Work in a welding shop or out of doors at the school.
ii. Flammable liquids, dust lint and oily deposits to be removed from within 50-ft (15m) of Work. Remove other combustibles where possible. Otherwise protect with fire-resistive tarpaulins or metal shields.
iii. Explosive atmosphere in area eliminated. Floors swept clean. Combustible floors wet down, covered with damp sand or fire-resistive tarpaulins.
iv. All wall and floor openings covered. Fire-resistive tarpaulins suspended beneath Work.
v. For on-site Work (indoor and out of doors), advise the Head Custodian, Principal, Consultant (if assigned) and Project Coordinator/Lead prior to Work being performed, and of related dangers.
vi. Where the Fire Alarm system is required to be set to stand-by to discourage false alarms from smoke detectors provide a firewatch throughout the building or structure being worked on. NEVER put the fire alarm system in stand-by mode when the building is occupied by staff or students.
vii. In the event of a fire because of the Hot Work, notify the fire department immediately. Report incident to the head custodian, the Consultant, if assigned, and Project Coordinator immediately, whether extinguished or not. Provide a fire incident report to the WRDSB.
viii. Barriers must be set up to protect staff and students (i.e. pylons, shields, and caution tape) from exposure to arc flash and smoke migration.
ix. Have all necessary doors, windows and/or drapes closed. Confer with the Head Custodian to shut down all fan systems in the area to reduce or eliminate smoke distribution.
x. Provide and keep fire extinguishers handy and in good Working condition. Temporarily cover all smoke detectors in the area during time of Work.
xi. Provide a fire watch/spot check for several hours after Work is completed. Uncover smoke detectors.
xii. On new construction, the requirements of the Hot Wok permit may be waived, until such time as either Substantial Completion or Occupancy is granted, whichever comes first.
xiii. On additions to existing buildings, the requirements for Hot Work permits shall remain in place.

### 28.2 Hot Work Permit

i. Each permit is valid for seven (7) days only and must be renewed prior to its expiration date
ii. The contractor must obtain Hot Work Permits from the WRDSB's representative prior to the start of work.
iii. The contractor must complete the form as required and must keep the form on site.
iv. Return each completed form to the WRDSB's representative on the date of expiration.
v. The most current version of the Permit and its requirements shall be used for the purposes of the Work.

## 29. Incurred Costs

The WRDSB will not be liable, nor reimburse any Bidder for costs incurred in the preparation of the Bid, or any other services that may be requested as part of the procurement process.

## 30. Indemnification

The Bidder will indemnify and save harmless and defend the WRDSB, and their respective elected officials, officers, employees, agents and their respective successors and assigns, from and against all actions claims and demands whatsoever which may be brought against or made upon any of the Indemnified Parties and against all losses, liability, judgments, claims, costs, demands or expenses which the Indemnified Parties may sustain, suffer, or be put to resulting from or arising out of the Bidder's failure to exercise reasonable care, skill or diligence in the performance or rendering of any Work or service required hereunder to be performed or rendered by the Bidder, its agents, servants, employees or Subcontractors, or any of them as well as for the infringement of or use of any intellectual property rights including any copyright or patent arising out of the reproduction or use in any manner of any plans, designs, drawings, specifications, information, negatives, data, material, sketches, notes, documents, memoranda, or computer software furnished by the Bidder in the performance of this Contract.

## 31. Inspection of Supplier's Work and Equipment.

i. The WRDSB reserves the right to inspect and/or have demonstration of the products/equipment/services offered prior to award of this Procurement.

ii. The WRDSB reserves the right to have all work, including maintenance and repair work reviewed by a third-party Contractor, Agency, or Consultant to confirm that work within this Contract is being completed satisfactorily.

## 32. Insurance Requirements

If selected, it is the responsibility of the Supplier and its Insurance Broker to review all potential operations and exposures to determine if the coverage and limits noted below

are sufficient to address all insurance related exposures presented by the specification of the Project, Work, or Supply. The Supplier shall ensure its undertaking, business, and equipment under the following coverage to protect and indemnify and save harmless the WRDSB.

Throughout the term of this Contract (including any renewal thereof), the Supplier shall obtain, upload through bids&tenders and maintain at its own expense, including the cost of any applicable deductible or self-insured retention, the following policies of insurance:

i. **Commercial General Liability Insurance** shall be in the name of the Supplier, and shall name the **Waterloo Region District School Board** and any other person or party identified in the contract documents, as an **additional insured**, with limits of not less than $5 Million inclusive per occurrence for bodily injury, death, and damage to property, including loss of use thereof, for itself and each of its employees, *Subcontractors* and/or agents. To achieve the desired limit, umbrella, or excess liability insurance may be used. The policy shall be endorsed to provide the *Owner* with not less than 30 days' notice, in writing, in advance of any cancellation and of change or amendment restricting coverage.

ii. **Automobile Liability Insurance** in respect of licensed vehicles with limits of not less than $2 Million inclusive per occurrence for bodily injury, death and damage to property, covering all licensed vehicles owned or leased by the Supplier, and endorsed to provide the Owner with not less than 30 days' notice, in writing, in advance of any cancellation, change or amendment restricting coverage. Where the policy has been issued pursuant to a government-operated automobile insurance system, the Supplier shall provide the Owner with confirmation of automobile insurance coverage for all automobiles registered in the name of the Contractor.

iii. **Contractor's Equipment Insurance:** If applicable/requested, Broad Form Contractor's Equipment Insurance: The General Contractor shall provide and maintain during the term of the Agreement coverage for construction machinery and equipment used by the Contractor for the performance of the work. Such insurance shall be in a form acceptable to the WRDSB and shall not allow subrogation claims by the Insurer against the WRDSB.

iv. **All Risk Installation Floater:** If applicable/requested, the General Contractor shall provide and maintain during the term of the Agreement an All Risk Installation Floater Insurance policy covering the installation of any machinery and equipment associated with the construction project. Coverage shall be in an amount equal to the value of the machinery and/or equipment and shall include coverage while it is in transit too, while stored at a temporary location, and awaiting installation at the work site.

v. **Professional Liability Insurance (Errors and Omissions):** If applicable/requested, Contractors and/or Consultants shall ensure its professional consultants, architects, landscape architects, planners, engineers, including IT providing a professional service in connection with the contract, maintain until three (3) years after the Agreement, Professional Liability Insurance to a limit not less than $1 Million per claim providing coverage for acts, errors and omissions arising from their professional services performed under this Agreement including but not limited to . design errors, project management mistakes, failure to perform etc. The policy SIR/deductible shall not exceed $100,000 per claim and if the policy has an aggregate limit, the amount of the aggregate shall be double the required per claim limit. Certificates evidencing such coverage shall be supplied to the WRDSB prior to the completion of the project and in accordance with the provisions stated above.

vi. **Pollution Liability:** If applicable, (i.e., for projects with environmental liability concerns) the General Contractor shall take out and keep in force Contractor's Pollution Liability (CPL) coverage to ensure that its work does not exacerbate any pre-existing environmental conditions during construction. Coverage shall be in an amount of not less than $5 Million per claim or per occurrence, or such greater amount as the WRDSB may from time to time require, naming the WRDSB as an additional insured, whose coverage shall be maintained in force for 1 year following the termination of the Contract. The policy SIR/deductible shall not exceed $100,000 per claim and if the policy has an aggregate limit, the amount of the aggregate shall be double the required per occurrence limit.

vii. **Cyber Insurance**: If applicable/requested: In addition to the insurance required under the Agreement, the Contractor shall procure and maintain cyber and network privacy insurance at its sole cost and expense with an aggregate limit of not less than $1 million per occurrence.

The insurance policy shall include coverage for any and all liabilities, damages, claims, losses, costs, and expenses of any kind that may be incurred by or asserted resulting from or related to: (1) any act, error, omission, or negligence related to the Proponent's technology and/or professional services; (2) intellectual property infringement arising out of software and/or content; (3) breaches of security and/or data; (4) violation or infringement of any right to privacy, or any breach of federal, provincial or local security and/or privacy laws or regulations; and (5) theft, damage, destruction, or corruption of any WRDSB data or any employee, or student of WRDSB, including without limitation, unauthorized access, unauthorized use, identity theft, theft of personally identifiable information or confidential corporate information, the transmission of a computer virus or other type of malicious code.

Evidence of coverage must be provided to the WRDSB within 7 days of the Intent to Award. The policy must be kept in force by the Proponent during the term of this

Agreement and for three (3) years (either as a policy in force or Extended Reporting Endorsement) after this Agreement is terminated or after completion of the Project provided for herein, whichever is later. Proof of insurance may be requested during the agreement term and for three (3) years after. If the policy is to be cancelled or non-renewed for any reason, a 90-day notice of said cancellation or non-renewal must be provided to the WRDSB. The WRDSB has the right to request that the Proponent purchase an Extended Reporting Endorsement at the Proponent's sole expense.

viii. **Provisions**: Prior to the commencement of work, the Supplier shall forward a Certificate of Insurance evidencing this insurance with the executed Agreement. The Certificate shall state that coverage will not be suspended, voided, canceled, reduced in coverage or in limits except after thirty (30) days (ten (10) days if cancellation is due to non-payment of premium) prior written notice by certified mail to the WRDSB.

It is also understood and agreed that in the event of a claim any deductible or self-insured retention under these policies of insurance shall be the sole responsibility of the General Contractor and that this coverage shall preclude subrogation claims against the WRDSB and any other person insured under the policy and be primary insurance in response to claims. Any insurance or self-insurance maintained by the WRDSB and any other person insured under the policy shall be considered excess of the Contractor's insurance and shall not contribute with it. The minimum amount of insurance required herein shall not modify, waive, or otherwise alter the Contractor's obligation to fully indemnify the WRDSB under this Agreement.

The WRDSB reserves the right to modify the insurance requirements as deemed suitable.

**ix. Third Party Claims Process:**

a. The WRDSB's claims process for Third Party claims is to refer the claimant directly to the Supplier and to leave the resolution of the claim with the Supplier. This applies regardless of whether it is an insured loss.

b. As WRDSB has a responsibility to the taxpayers, we must ensure that claimants are dealt with in a fair and efficient manner. Claims reported to the Supplier, either directly by a third party or through the WRDSB shall be promptly investigated by the Supplier. The Supplier shall contact the third party claimant within 48 hours of receipt of notice of a claim. The Supplier shall initiate an investigation of the claim immediately upon notice, and advise the third party claimant in writing, with a copy to the WRDSB, of its position regarding the claim within 21 calendar days of the notice. The Supplier shall include in its response the reasons for its position.

c. Should this position not resolve the claim and be accepted by the third party claimant, the Supplier shall immediately report the claim to its Insurer for further review. (Insurer for this purpose is defined as either the Claims Department of the Supplier's Insurance Company or the Claims Administrator at the Supplier's Insurance Broker.) The Supplier's Insurer upon receipt of this claim shall advise the third party claimant by letter, with a copy to the WRDSB, that it is now investigating the claim. When a final position on the claim has been determined, the Supplier's Insurer shall advise the third party claimant by letter, with a copy to the WRDSB. Failure to follow this procedure shall permit the WRDSB to investigate and resolve any such claims.

d. Nothing herein shall limit the right of the WRDSB to investigate and resolve any such claims notwithstanding the response of the Supplier and/or its Insurer and to seek indemnification from the Supplier or to exercise any other rights under the Contract.

e. The WRDSB may, without breaching this contract, retain from the funds owing to the Supplier an amount that, as between the WRDSB and the Supplier, is equal to the balance in the WRDSB's favour of all outstanding debts, claims or damages, whether related to this contract.

**33. Invoicing and Payment Terms**

33.1 Submit all invoices to finance-ap@wrdsb.ca for payment at the completion of the Work or after receipt of goods, unless otherwise stated. Not Applicable for Credit Card orders.

33.2 Fiscal Year End: All work scheduled within a single school year (Sept 1-Aug 31) must be completed and invoiced received by the WRDSB no later than August 31 of that same school year, unless budgets dictate that work must extend into the following school year and/or mutually agreed upon both parties.

33.3 New Account, in advance of invoicing, upon request, Suppliers will provide:

i. necessary company information to set up a WRDSB account and
ii. banking information to receive payment by Electronic Funds Transfer (EFT).

33.4 Requests to change company information must be submitted in writing accompanied by a legal document/letter signed by a lawyer on the law firm's letterhead.

33.5 Invoices must contain the following information, where applicable, to be deemed complete:

i. Purchase Order Number
ii. Invoice Date
iii. Unique Invoice Number

iv. Supplier name and address
v. Quantity, Unit Price, Unit of Measure and Extended Price
vi. Description for each line item
vii. Date of Service Call, if applicable
viii. HST
ix. Payment Terms
x. Work Order Number, if applicable
xi. Name of WRDSB Project Lead, if known, and

33.6 Payment terms shall be net thirty days (30) days after receipt of invoice, unless otherwise agreed by the WRDSB in writing. An early payment discount, if offered, may be considered on a mutual agreement basis. Payment may be delayed if the invoice is incorrect or the goods, equipment and/or services are not acceptable to the WRDSB. The WRDSB will not pay any interest, penalty, or late fee for delayed payments. The WRDSB preferred payment method is Credit Card or EFT, however alternate payment methods may be approved. Suppliers are required to invoice promptly, without delay. For Work that falls under the Construction Act, refer to 34 Construction Act – Proper Invoice.

**34. Construction Act – Proper Invoice**

The WRDSB will pay such invoice within twenty-eight (28) calendar days of the WRDSB's receipt of such proper invoice if the work has been performed to the satisfaction of the WRDSB For Work that is governed by the provisions of the Construction Act and the Regulations thereto, the Supplier shall submit its invoices in the form of a Proper Invoice. For the purposes of this section, a "Proper Invoice" shall include the following:

i. the Supplier's name, address, telephone number, and mailing address.
ii. the date of the Proper Invoice and the period during which the services or materials for which payment is being made were supplied.
iii. information identifying the authority, whether in the contract or otherwise, under which the services or materials were supplied.
iv. a description, including quantity where appropriate, of the services or materials that were supplied during the payment period.
v. the amount payable for the services or materials that were supplied during the payment period, with a clear identification of the portions of the amount that are holdbacks, and HST.
vi. the name, title, telephone number, and mailing address of the person to whom payment is to be sent.
vii. the payment terms as specified by the WRDSB in the Contract.
viii. the invoice number and if applicable, the revision number.
ix. the Supplier's HST number.
x. invoices and time sheets from all subtrades whose work is included in the Proper Invoice, if required in the Contract.

xi. backup documentation to support any cash allowances and extra work claimed in the Proper Invoice.

xii. a schedule of values indicating:

a. for lump sum contracts, the percentage of work completed per division with each division further subdivided to show the percentage of work completed for each subtrade,

b. for unit price contracts, the tender quantity, unit of measure, previous quantity, current quantity, to-date quantity,

c. an updated list of change orders, showing the percentage of work completed under each change order, and

d. an updated cash allowance list, showing the percentage of work completed in respect of each cash allowance, if required by the Contract.

xiii. a Statutory Declaration where required by the Contract attesting to the truth of the statements made therein.

**35. Interpretive Value of Headings**

The headings in this Procurement document or subsequent Agreements are for convenience of reference only and in no manner modify, interpret, or construe the Procurement document or subsequent Agreements.

**36. Licenses and Permits**

The Supplier will be responsible for applications and fees associated with all licenses and permits required by all governing bodies. The Supplier will attach a copy of all permits, and any other required documentation to the applicable assigned work order for WRDSB records.

**37. Locates**

All required utility locates must be obtained before any on-site work commences, be available for Supplier operator/employee review, and are the sole responsibility of the Supplier. Any damage to any utility installation arising from work performed by the Supplier or their employees shall be the Supplier's responsibility.

The Supplier will obtain all utility locates in advance of work and all cost(s) associated with obtaining the utility locates will be the Supplier's responsibility.

The Supplier shall possess the ability to supply and or share with the WRDSB Representative utility locates for the sole purpose of Quality Control inspections. This is to be done at no additional cost to the WRDSB.

**38. Log Reports**

If requested, the Supplier must submit a completed Log Report with invoices. The WRDSB may request more frequent log submissions if it is necessary.

**39. Materials - Specifications**

Only new materials in perfect condition will be accepted. Demonstrators, seconds, or defective materials are unacceptable. Any materials found not to be in a new condition or as specified will be returned to the Supplier at the Supplier's expense.

**40. Material Safety Data Sheets (M.S.D.S.)**

Where applicable, a materials safety data sheet (M.S.D.S.), must accompany all purchased goods, that fall under the requirements of the Occupational Health and Safety Act. The WRDSB will not accept any additional charges or surcharges related to the supply of M.S.D.S.

**41. Mathematical Errors (Unit Prices Prevail)**

Should there be any error in extensions, additions or computations, the WRDSB shall be entitled to correct such errors based upon the unit prices supplied, and the corrected total shall be considered as representing the intention of the Bidder and shall be used as the basis for comparison of bid submissions.

**42. No Branding**

The Supplier shall not place any sign at the site, public meetings, any public or private property or along curbside prior, during or after the Work without prior written permission of the WRDSB.

**43. No Collusion**

Bidders/Proponents including any of their agents are prohibited from engaging in any comparison of figures or arrangement with any other individual, corporation or person submitting a Bid/Proposal for the same Work and shall be fair in all respects and shall be without collusion or fraud.

**44. No Lobbying**

Any attempt by the Bidder or its agents to contact any of the following people, directly or indirectly, with respect to this procurement may lead to disqualification:

i. any elected or appointed officer.
ii. any staff of the WRDSB except the Designated Representative as identified in the Procurement Document; or
iii. any other person connected in any way with the procurement.

**45. No Smoking and Scent-Free Environment**

The Province of Ontario has legislated under the Smoke Free Ontario Act that smoking is not permitted on any WRDSB owned properties. Furthermore, most WRDSB properties are “scent free”. Smoking will not be permitted on-site. Offenders will be asked to leave the site, and infractions could result in corrective action and or fine.

**46. Non-Assignment**

No assignment by the Supplier shall relieve the Supplier of any responsibility for the full performance of all its' obligations under this contract.

The Supplier shall not change its corporate name without the prior written approval of the WRDSB.

**47. Non-Disclosure Agreement (NDA)**

The WRDSB requires all service providers to sign off on a non-disclosure agreement and for the service provider to complete the Software Privacy and Security Standards Document (if necessary) in accordance with WRDSB procedure AP4790. Prior to any sharing of WRDSB personal, sensitive, or confidential information, the Supplier will be subject to further privacy and security reviews as required. This agreement will be renewed on an annual basis.

**48. Ownership of Work**

For the purposes of this paragraph:

**"Deliverables"** means all material prepared by the Bidder forming the Work under this Contract including, without limitation, all electronic media, reports, documents, and instruments of service.

**"Intellectual Property Rights**" means any and all rights provided under: (a) patent law; (b) copyright law; (c) trade-mark law; (d) industrial design law; (e) any other statutory provision or common law principle applicable to this Contract, including trade secret law; and (f) any and all registrations and licenses in relation to the foregoing; and

**"Personnel"** means employees, representatives, agents, and Subcontractors.

The Bidder and the WRDSB acknowledge and agree that the development of the Deliverables and the provision of the Work may result in the creation or development of new intellectual property and may contain or utilize the existing intellectual property of the Bidder or of third parties. Accordingly, the Bidder and the WRDSB agree as follows.

i. Except as set out in paragraph (b) below, the Bidder hereby assigns and agrees to assign to the WRDSB all right, title and interest, including all Intellectual Property Rights, in and to each Deliverable from the moment of creation, and will cause its Personnel to assign the same. The Bidder will cause its Personnel to waive all moral rights they may have in each Deliverable.
ii. To the extent that a Deliverable contains or utilizes the intellectual property of the Bidder or a third party ("Retained Materials"), and the Bidder expressly identifies such Retained Materials, the Bidder and the applicable third party will, subject to the following sentence, retain all their respective right, title and interest, including all Intellectual Property Rights, which each may have in such Retained Materials. To the extent that a Deliverable contains or utilizes Retained Materials, the Bidder hereby grants to each of the WRDSB a royalty-free, irrevocable, perpetual, world-

wide, non-exclusive license to make, use, sell, modify, prepare derivative works, disclose, publish, sublicense, copy and communicate by electronic means such Retained Materials.

iii. The Supplier agrees to always cooperate fully and will cause its Personnel to always cooperate fully, with respect to signing such documents and doing such acts and other things reasonably requested by the WRDSB to confirm the transfer of ownership rights in the Deliverables.

**49. Patent, Copyright and Other Proprietary Rights**

The Bidder (by responding) agrees that the Bid on acceptance by the Designated Representative, becomes the property of the WRDSB. The copyright for respective purchased concepts and/or materials will become the property of the WRDSB unless otherwise mutually agreed upon by the Bidder and the WRDSB.

All reports submitted by the successful bidder, including the "Asbestos Audit Update Report" dated [Month/Day/Year], and any related documentation, shall become the exclusive property of the Board upon submission, including all associated intellectual property rights, except for any pre-existing intellectual property of the contractor unless otherwise agreed in writing.

The consultant shall ensure the accuracy and legal compliance of all submitted materials, which may be verified or audited by the Board.

The Board and its authorized agents may use, reproduce, and disclose the report as necessary to fulfill obligations under applicable legislation, including the Occupational Health and Safety Act, Ontario Regulation 278/05, and relevant privacy laws such as but not limited to Freedom of Information and Protection of Privacy Act (FIPPA), the Municipal Freedom of Information and Protection of Privacy Act (MFIPPA).

All information shall be treated as confidential and shall not be disclosed by the consultant to third parties without prior written consent from the Board representative, unless required by law.

All Bids, other documents as well as correspondence are subject to the provisions of the Municipal Freedom of Information and Protection of Privacy Act (MFIPPA).

**50. Performance**

i. Where the Supplier is in default in conducting any of its obligations under the contract, the WRDSB may issue a verbal warning outlining the deficiency in supply or other aspects of performance and requiring the Supplier to correct those deficiencies within such period as stated.

ii. If the deficiency is not corrected within the time specified, or there is a further instance of deficient performance, the WRDSB may issue a written notice to the Supplier, identifying the deficiency in performance and setting a final date or period for its correction.

iii. If corrective steps are not taken by the final date or within that time, the WRDSB may terminate the Contract and take corrective action.

iv. Termination of any Contract can be immediate depending on the severity of the default.

v. The Supplier shall have no right to perform the services contemplated under this agreement beyond the time when such services become unsatisfactory to the WRDSB; and in the event that Supplier shall be discharged before all the services contemplated hereunder have been completed, or the services are for any reason terminated, stopped or discontinued because of the inability of the Supplier to serve under this agreement they shall be paid only for that portion of the Work which shall have been satisfactorily completed at the time of termination.

vi. Where deemed appropriate, a performance evaluation shall be completed by the WRDSB. The evaluation report shall be reviewed with Procurement Services, and a copy of the completed evaluation forwarded to the Supplier for their records. Dependent on the evaluation scoring, the WRDSB may request a corrective action plan and/or project size/value may be affected on future bid opportunities for your company.

**51. Permits and Licenses**

Unless stated otherwise, the Supplier shall apply for all required permits and licenses, supply all necessary notices required for the Work and pay all required fees. These costs shall be included in the Total Price. A copy of all permits, and any other required documentation shall be provided to the WRDSB upon request.

**52. Proceedings Against the WRDSB**

The Bidder represents and warrants that the Bidder is not a party to any legal suits, actions, litigation proceedings, arbitrations, alternative dispute resolutions, investigations, or claims (Hereinafter collectively referred to as “Claims”) by or against or otherwise involving the WRDSB and the Bidder. The WRDSB may reject any Bid in the event of potential, current, pending, or threatened litigation, arbitration, alternative dispute resolution, or disputes involving the WRDSB and the Bidder.

**53. Protection of WRDSB Assets**

The Supplier (the Supplier / Subcontractor) shall be informed of and protect all WRDSB assets including existing structures and vehicles, to the satisfaction of the WRDSB. Any damage shall be reported to the WRDSB and subsequently repaired and/or replaced by the Supplier, at their expense, to the satisfaction of the WRDSB. The Supplier shall not cause any inconvenience to WRDSB operations, staff, public or users of the WRDSB facilities, within reason. Communication between the successful Supplier and the school

(or WRDSB representative if school contact is not available) must be timely and effective to ensure all stakeholders are considered / aware of work to be completed.

**54. Records, Inspection, Audits**

The WRDSB will have the right, upon reasonable notice, to full access to the accounts and records of the Supplier in respect of the goods, services and equipment provided by it under the Contract, for the purposes of inspection and/or audit. The Supplier shall make and retain such records during the term of the Contract and for a minimum of seven (7) years following its termination, cancellation, or expiry.

**55. Reserved Rights of the WRDSB**

The WRDSB reserve the right, in their respective sole and unfettered discretion, to:

i. Reject any Bid received from a Bidder which is party to any potential, current, past or existing suits, actions, and litigation proceedings, arbitrations, alternative dispute resolutions, investigations, Bidder performance evaluations that are below expectations, significant or persistent deficiencies in performance of any substantive requirement or obligation under a prior agreement or agreements or claims by or against or otherwise involving either of the WRDSB and the Bidder.
ii. waive formalities and accept Bids which substantially comply with the requirements of this tender.
iii. accept any Bid in whole or in part.
iv. accept, reject, or cancel any or all Optional or Provisional pricing.
v. discuss with any Bidders different or additional terms to those contemplated in this Procurement Document or in any Bid submission.
vi. make public the names of any or all Bidders.
vii. accept or reject equivalent or alternative brand names.
viii. check references other than those provided by any Bidder.
ix. Verify with any Bidder or with a third party any information set out in a Bid.
x. reject any, or any part of, any or all Bids, or cancel the bidding process at any stage and/or issue a new Bid call for the same or similar deliverables.
xi. disqualify any Bidder:
    a. whose Bid contains misrepresentations or any other, inaccurate, or misleading information, or any qualifications within its Bid,
    b. who has engaged in conduct prohibited by the Procurement Document,
    c. with inadequate credentials or due to unsatisfactory past performance,
xii. reject Bid(s) from Bidder who has engaged in lobbying or has contravened any of the terms of the Procurement Document.
xiii. reject a Bid based on:
    a. information provided by references or credit check or other due diligence efforts,
    b. the information provided by a Bidder pursuant to the WRDSB exercising its clarification rights under the procurement process, or
    c. other relevant information that arises during the procurement process.

xiv. choose to reject a Bid if only a single Bid is received and cancel the bidding process or enter direct negotiations with the sole Bidder.

xv. accept a Bid other than the lowest or highest scoring and/or to not accept any Bid for any reason whatsoever.

xvi. award the contract as split-order, lump sum or individual-item basis, or such combination as shall best serve the interests of the WRDSB.

xvii. negotiate in circumstances permitted for in the Bid document or by relevant policies, or directives, and include additional terms and conditions during the process of negotiations.

xviii. no longer consider a Bidder if a satisfactory outcome is not reached as part of negotiation, as determined by the WRDSB in their sole discretion and move to the next highest ranked Bid in such event.

xix. select a Bidder other than the Bidder whose Bid reflects the lowest cost to the WRDSB and/or award the Contract to any Bidder.

xx. award any business/Work described in this Procurement to more than one (1) Bidder.

xxi. not award the Contract if the costs of completing the Work exceed budget funding; or do not respond to all requirements or do not represent fair market value or where necessary internal approvals are not obtained, and

xxii. if the WRDSB receives a bid from a Supplier with Rates that are abnormally lower than the Rates in other Bids, the WRDSB may verify with the Bidder that the Bidder satisfies the conditions for participation and can fulfill the Agreement.

These reserved rights are in addition to any other expressed rights or any other rights which may be implied in the circumstances. The WRDSB shall not be liable for any expenses, costs or losses suffered by any Bidder or any third party resulting from the WRDSB exercising any of its express or implied rights under this bidding process.

**56. Responsibilities of the Supplier**

Acceptance of a purchase order issued by the WRDSB and/or a signed agreement shall constitute a contract (the "Contract") between the WRDSB and the Supplier, which shall bind the Supplier on their part to furnish and deliver the goods, equipment and services at the prices given and in accordance with the conditions of the Procurement document.

The Supplier shall:

i. perform the Contract in accordance with the specifications, terms and conditions under which it is awarded.

ii. act in a professional manner always when dealing with WRDSB staff, with the public, and while working on site.

iii. not, except with the consent of the WRDSB in writing, release information relating to any subsequent order for advertising, promotional or technical purposes or otherwise give it publicly in any fashion, nor shall the name of either of the WRDSB

be used for, or in connection with, any advertising or promotional purpose of the Supplier.

iv. treat information gained while working with the WRDSB confidentially and not use it for any other project and return it to the WRDSB if requested.

v. submit to Finance – Accounts Payable, an invoice for payment at the completion of the Work, unless otherwise stated. All applicable taxes, including HST, are to be itemized separately on invoices. Include the purchase order number on each invoice; and

vi. provide necessary information if they wish to receive payment by Electronic Funds Transfer (EFT).

**57. Site and Work Examination**

i. Bidders will accept the site conditions, and the requirements of the Work, as is. No modifications to the Bid will be accepted after the Closing Time.

ii. No claim for extras will be allowed for Work or difficulties encountered due to conditions of the site which were visible, knowable, or reasonably inferable, prior to the time of submission of Bid. Bidders shall accept sole responsibility for any error or neglect on their part in this regard.

iii. Before submitting a Bid, each Bidder shall:
   a. carefully examine this entire Procurement Document to determine the extent of the Work, and various provisions including the maps, drawings, reports and specifications.
   b. immediately report all discrepancies between the various documents and site conditions.
   c. provide the names of Subcontractors, subconsultants, and suppliers to whom the Bidder intends to sublet a portion or portions of the Work with complete information as to the requirements of the Work. This is to include maps, drawings, reports, specifications, and all requirements of the Procurement Document including any addenda.

iv. In the event of discrepancies between the maps, drawings, reports, and the specifications regarding quantity or quantities of materials or items, and in the absence of Addenda in clarification of said discrepancies, the Bidder is to include for the larger quantity or quantities.

v. No additional payments will be made for any costs incurred through failure of the Bidder to abide by provisions stipulated in all the articles and sub-articles of this item.

vi. Any soils investigation, environmental, geotechnical, or other reports prepared or obtained with respect to the Place of the Work (collectively the “Reports”) are available from the Consultant. Where the Work involves existing buildings,

structures, facilities, plant or equipment, any reports, data, or as-built drawings concerning such buildings, structures, facilities, plant or equipment (collectively the "Data") are available from the Consultant. The Reports should not be considered a representation of the site conditions of the entire Place of the Work, and the Reports and Data are provided for general information and guidance purposes only. Neither the Owner nor the Consultant guarantees the accuracy or completeness of the Reports or the Data, nor does either assume any responsibility for any interpretations or conclusions that bidders may make or draw from the Reports or the Data.

vii. Each Bidder is solely responsible, at its own cost and expense, to conduct its own independent research and due diligence, or to perform any other investigations considered necessary by the Bidder to satisfy itself as to all existing conditions. The Bidders' obligations set out in this paragraph apply irrespective of any Reports, Data or any information contained in the Bid Documents.

viii. No allowances will be made for additional costs, and no claims will be entertained in connection with conditions which could reasonably have been ascertained by investigation or other due diligence undertaken prior to the Submission Deadline, and/or in connection with Work which is required and which is reasonably inferable from the Bid Documents, the Reports and/or Data as being necessary.

**58. Site Existing Services, if applicable**

The position of utility pole lines, underground conduits, and services, watermains, sewers and other underground and over ground utilities and structures are not necessarily known, and the accuracy of the position of such utilities and structures on any reference documents is not guaranteed. The WRDSB will not be responsible for damages or extra work caused or occasioned by the Supplier relying on this or any other information or records.

Before starting work, the Supplier shall familiarize themselves of the exact location of all such utilities and structures and shall assume all liability for damage to them. Where extra measures are required to support utility poles during construction either by the utility involved or the Supplier themself, the costs involved shall be borne by the Supplier. The Supplier will be responsible for any fees that may be associated with these services.

**59. Site Inspection and Control**

A representative of the WRDSB (appointed by the WRDSB) reserves the right to enter the site at any time for the review & inspection. The presence of a said representative does not indicate satisfaction or compliance unless these comments are made by the representative and submitted to the Supplier in written form.

**60. Site Investigation**

Bidders shall not rely solely upon information furnished by the WRDSB but shall do their own investigation of the locations and quantity of the work to be completed under this

contract.

The Bidder assumes all risk of conditions, existing or arising, in the course of the work, which might or could make the work or any items therefore more expensive in character, or more onerous to fulfill, than was contemplated or known when the Bid was made, or the Contract signed.

**61. Site Safety and Clean Up**

For safety of students, staff, and community members alike, it is expected that cleanup operations will progress with the job.

Repair work will be conducted by skilled workers acceptable to the WRDSB Representative, under the liability of the Supplier.

The WRDSB Authorized Representative must approve all repairs and replacements prior to final payment.

**62. Suspension of Bidders**

At the sole discretion of the Manager of Procurement Services, any Bidder may be suspended from consideration for default of delivery, unsatisfactory performance, safety concerns, lobbying or contravention of the Procurement Document.

**63. Sustainable Purchasing**

The procurement needs of the WRDSB represent a significant level of responsibility to demonstrate leadership and support for greener business practices. Integrating environmental performance and impact into supply chain decisions is a commitment to improvement of the environment and the quality of life.

Green procurement shall be viewed in the context of achieving value for money for the total life-cycle costs. It requires the inclusion of environmental impact considerations into the procurement process, including planning, acquisition, use and disposal. Value for money should include the consideration of environmentally tangible and intangible factors when determining the total life-cycle costs and environmental impact.

**64. Termination**

If the Supplier fails to comply with any provision of this agreement or otherwise fails to fulfil its obligations hereunder in a competent manner satisfactory to the WRDSB, the WRDSB may give the Supplier notice in writing of such failure. If the Supplier has not remedied its failure within ten (10) working days of the said notice, the WRDSB shall be entitled to exercise any one or more of the following remedies:

i. The WRDSB may terminate the contract without further notice and exercise its rights to the Contract security provided by the Supplier.
ii. The WRDSB may withhold any payment due to the Supplier hereunder until the Supplier has remedied its failure.

iii. The WRDSB may engage the services of another Bidder to remedy the Supplier's failure and obtain reimbursement therefore from the Supplier. The said reimbursement may be obtained either through deduction from any amounts owing to the Supplier hereunder, or through any other legal means available to the WRDSB; or

iv. The WRDSB may assert any other remedy available to it in law or equity.

Unless the WRDSB expressly agrees to the contrary, any failure of the WRDSB to exercise any of the foregoing remedies, or the granting of any extension or indulgences, shall not be prejudicial to any right of the WRDSB to subsequently obtain such remedies.

**65. Termination for Convenience**

The WRDSB may terminate the Contract, in whole or in part, whenever the WRDSB determine that such termination is in the best interests of the WRDSB without showing cause, upon providing written notice to the Supplier. The WRDSB shall pay all reasonable costs incurred by the Supplier/Contract up to the date of termination considering the Work performed and/or services were provided in accordance with the Contract and to the complete satisfaction of the WRDSB. Payment shall be in accordance with prices as per Contract. However, in no event shall the Supplier be paid an amount, which exceeds the Total Bid Price. The Supplier will not be reimbursed for any profits which may have been anticipated but which have not been earned up to the date of termination.

**66. Termination for Lack of Funding**

Should the WRDSB fail to appropriate funds to enable payments including multi-year agreements, the WRDSB may cancel the contract without termination charges, provided the Supplier receives thirty (30) days written notice of such termination from the WRDSB.

**67. Tools and Equipment**

All equipment and methods used to fulfill this contract shall be in accordance with best practices, guidelines, regulations, and standards with respect to safety and quality.

No equipment, tools or materials are to be stored or left overnight within WRDSB property.

At the time of bid, if requested, the bidders will indicate the type of equipment that will be used to fulfill the terms and conditions of this contract. Prior to the WRDSB entering into an agreement with the Supplier, or at any time during the contract, the WRDSB may, at its discretion, request an inspection of the equipment proposed for use.

It is the responsibility of the Supplier, in the event of a major mechanical equipment breakdown, to have available substitute equipment of similar capability. It shall be supplied and put into service to fulfill the requirements of this procurement. Failure to provide alternative equipment within expectations specified within this procurement may result in termination of the contract. It is the responsibility of the Supplier to ensure

work continues and deadlines are met, despite any unforeseen interruption because of equipment failure.

It is the Supplier's responsibility to ensure that the equipment and the operator, are licensed in accordance with the Ministry of Transportation. The WRDSB may, at their discretion, require the Supplier to provide proof that the equipment has passed a recent (within the last 12 months) government safety inspection and that the operators are suitably licensed prior to commencement of the contract. All vehicles, tools, equipment, and voltage rated gloves requiring dielectric testing shall have current certification and all applicable documentation.

The equipment must be in good working order, and the Supplier is responsible for all general and preventative maintenance, fuel, and repair and those costs shall be included in the bid. All preventative maintenance and repairs are to be conducted off peak hours. No other charges to the WRDSB shall apply.

**68. Traffic/Pedestrian Safety**

Vehicles, including Couriers and movable Equipment/Machinery must take all precautions to avoid entering or driving on WRDSB premises during nutritional breaks, before and after school hours, or anytime there are students or staff outside of the building.

**69. Traffic Control and Site use**

Supplier's activities shall be limited to areas for work and storage as directed by the WRDSB. Except where expressly permitted by the WRDSB, materials and/or equipment must not be stored within four metres of the travelled portion of any roadway. Notwithstanding the foregoing, the Supplier shall, at their own expense, remove any equipment or material, which, in the WRDSB's opinion, constitutes a traffic hazard.

The Supplier shall plan and schedule the routes of vehicles transporting all materials to, from or within the job, so that vehicular movements are accomplished with minimum interference and interruption to traffic. This will necessitate vehicles to "slip off" or "slip on" in the direction of traffic lanes.

The Supplier shall maintain the adjacent side streets in a condition free from debris resulting from their operations, such as materials spilling from trucks. It is expected that the Supplier shall regularly inspect the surface condition of these streets and promptly dispose of all the debris.

Should the Supplier be unable to conduct the required remedial measures, the WRDSB may conduct the necessary maintenance and the costs for the work shall be deducted from payments due to the Supplier.

The Supplier shall, at his own expense and to the satisfaction of the WRDSB, provide all vehicular traffic control equipment, signs, material, and labor required to perform the work in a safe manner in accordance with the "Occupational Health and Safety Act" and the "Ontario Traffic Manual" (Book 7). The Supplier shall assure that all required

forms are completed and on-site for inspection. In the event a traffic control company is contracted for the purpose of signage, information regarding the Supplier must be included in the quotation and included with the bid price.

The Supplier shall be responsible for the supply of traffic flag person(s) where required under the "Ontario Traffic Manual" (Book 7), with all costs included in the base unit price.

**70. Usage Reports**

The WRDSB, at no additional cost, may request detailed usage reports or activity log reports in Excel (unprotected) to be provided annually or upon request. Reports may include but are not limited to descriptions, codes, quantities, extended quantity, price.

**71. Variation of Bid Prices**

No variation in the Total Price, unit prices and/or optional pricing will be permitted after Closing Time, except in the instance of variation solely due to an increase or decrease in the rate of eligible taxes, beyond the control of the Bidder, occurring after the time of submission of their Bid. An increase or a decrease in the rate of eligible taxes, under these circumstances, shall alter the price of the Bid, but only to the extent of the tax increase or decrease.

**72. Volume and Exclusivity**

Quantities and/or WRDSB sites may be added, deleted, or adjusted at the discretion of the WRDSB due to but not limited to unintentional omissions, inventory adjustments, new schools/school closures, and/or budget restraints.

The WRDSB makes no guarantee of value or volume of work to be assigned to the Supplier. Any agreement executed with the Supplier may not be an exclusive contract for the provision of the described goods/services. The WRDSB reserves the right to contract with other Supplier for good(s) and/or service(s) of the same as or like the deliverables or may obtain such good(s) and service(s) internally.

**73. Waiver**

No term or provision of the Procurement Document shall be deemed waived, and no breach consented to, unless such waiver or consent is in writing and signed by an authorized representative of the party claimed to have waived or consented to the breach. No consent by a party to, or waiver of, a breach under the procurement process shall constitute consent to, waiver of, or excuse for any other, different, or subsequent breach.

The WRDSB does not accept responsibility for any information or any errors or omissions which may be contained in the Procurement Document, or the data, materials or documents disclosed or as provided to the Bidders pursuant to the procurement. The WRDSB make no representation or warranty, either expressed or implied, in fact or in law with respect to the accuracy or completeness of the Procurement Document or such data, materials or documents and the WRDSB shall not be responsible for any actions, costs, losses or liability whatsoever arising from any Bidder's reliance or use of the Procurement

Document or any other technical or historical data, materials or documents provided by the WRDSB. The Bidder is responsible for obtaining its own independent financial, legal, accounting, and technical advice with respect to any information included in the Procurement Document or in any data, materials, or documents provided or required by the WRDSB.

**74. Warranty and Maintenance**

The Supplier, at the time of substantial completion, shall furnish a written warranty covering material, maintenance, and work performed under the contract for a minimum period of two (2) years from the date of completion, unless otherwise stated. Individual sections may extend warranties beyond the two (2) year time frame. The Supplier is responsible for all required maintenance complete with materials and labour during the warranty period.

**75. Work Continuity**

The Supplier shall take adequate care to protect the Work, the WRDSB's property, adjacent properties and shall be fully responsible for any damage or injury due to their act or neglect or is attributable to the acts or omissions of the Supplier, its Subcontractors, sub-suppliers, agents, employees, officers, directors, and all other persons and other entities for whose acts the Supplier may be liable or for whom it is responsible in law and their respective officers, directors, agents and employees.

The Supplier shall ensure minimal to no disturbance to the user(s) of the surrounding facilities. Replacement and repairs due to any damage caused to any existing structure, WRDSB equipment, public assets or private property during the Work shall be the responsibility of the Supplier.

**76. Work Requirements**

The Supplier shall perform entire work with minimal to no disturbance to the routine operations of the respective facility. Further, the Supplier shall ensure safety of WRDSB assets, students, staff as well as public always.

**77. Workplace Safety Insurance Board (WSIB) Certificate**

The WRDSB requires all Suppliers and service providers be in full compliance with all requirements imposed upon them by the Workplace Safety Insurance Board. All certificates of training and Safety Policies and Manuals must be available for presentation upon request.

Prior to a formal award and commencing the services covered by this Procurement, the recommended Bidder(s) make available to the WRDSB a copy of certificates of good standing with the Workplace Safety and Insurance Board (“WSIB Certificates”) listing appropriate NAICS Code and Code Description stating that the Supplier/consultant and all of its subcontractors/consultants have complied with the requirements of the Workplace Safety and Insurance Act and in particular, that all requisite premiums under such Act

have been paid. Where the Bidder is exempt from registration with the WSIB, the Bidder must provide evidence of such by way of written confirmation from WSIB.

WSIB Certificate evidencing renewal or replacement of Certificates listing appropriate NAICS Code and Code Description shall be uploaded through the Bidding System within 72 hours of the expiration or replacement of the current certificate, without demand by the WRDSB.

**END OF SECTION**

**00 73 00 "The Supplementary Conditions"**

**SUPPLEMENTARY CONDITIONS & AMENDMENTS TO STANDARD CONSTRUCTION DOCUMENT CCDC2 -2020 STIPULATED PRICE SUBCONTRACT**

**(the "Supplementary Conditions")**

**AGREEMENT, DEFINITIONS, AND**

**GENERAL CONDITIONS**

The Standard Construction Document CCDC 2 2020 for a Stipulated Price Contract, English version, consisting of the Agreement Between *Owner* and Contractor, Definitions and General Conditions of the Stipulated Price Contract, Parts 1 to 13 inclusive, governing same, together with the changes with the new *Construction Act* is hereby made part of these *Contract Documents*, with the following amendments, additions and modifications:

**AGREEMENT BETWEEN OWNER AND CONTRACTOR**

**ARTICLE A-1 – THE WORK**

| | | |
|---|---|---|
| SC17.1 | A-1.3 | Amend Article A-1.3 by deleting all of the words after *"Contract Documents"* and replace them with the following"<br><br>"attain<br><br>.1 *Substantial Performance of the Work* by the 18th day of December in the year 2026.<br>.2 (if applicable) *Occupancy* by the 18th day of December in the year 2026, and<br>.3 *Ready-for-Takeover* by the 29th day of January in the year 2027." |
| SC1.1 | | |

**ARTICLE A-3 – CONTRACT DOCUMENTS**

| | | |
|---|---|---|
| SC2.1 | A-3.1 | Add the following documents to the list of *Contract Documents* in Article A-3.1:<br><br>• Waterloo Region District School Board's Supplementary Conditions & Amendments to Standard Construction Document CCDC 2-2020 Stipulated Price Subcontract, May 2022 Version, including any Special Supplementary Conditions listed in Appendix 2 thereto<br><br>• *Drawings*<br><br>• *Specifications*<br><br>• Performance Bond (Form 32 -Performance Bond under Section 85.1 of the *Act*) if applicable<br><br>• Labour and Material Payment Bond (Form 31 – Labour and Material Payment Bond under Section 85.1 of the *Act*), if applicable |

**ARTICLE A-4 – CONTRACT PRICE**

| | | |
|---|---|---|
| SC3.1 | A-4.4 | Delete Article A-4.4 and replace it with the following:<br><br>"4.4 The *Contract Price* shall remain fixed for the duration of the *Contract Time*, subject only to adjustments as provided for in the *Contract Documents*. For certainty, and without limiting the general application of the preceding sentence, the *Contractor* assumes all risks in connection with cost increases for overhead, *Products, Labour*, and *Construction Equipment* prescribed by the *Contract Documents* for the performance of the *Work*, and the *Contractor* assumes all responsibility for liabilities and additional costs that may arise as a result of the *Contractor's* inclusion of any *Product, Construction Equipment, Supplier*, or *Subcontractor* in its calculation of the *Contract Price*." |

**ARTICLE A-5 – PAYMENT**

| | | |
|---|---|---|
| SC4.1 | A-5.1 | Delete Article A- 5.1 in its entirety including all subparagraphs and replace it with the following: |

| | | |
|---|---|---|
| | | "5.1 Subject to the provisions of the *Contract Documents* and the *Construction Act*, the *Owner* shall:<br><br>.1 make progress payments to the *Contractor* on account of the *Contract Price* when due together with such *Value Added Taxes* as may be applicable to such payments,<br><br>.2 upon *Substantial Performance of the Work* as certified by the *Consultant*, and on the 61st day after the publication of the certificate of *Substantial Performance of the Work*, in accordance with the *Construction Act*, there being no claims for lien registered against the title to the *Place of the Work* and no written notices of lien delivered to the *Owner*, pay the *Contractor* the unpaid balance of the 10% holdback, together with such *Value Added Taxes* as may be applicable to such payment, less any amount stated in the *Owner's Notice of Non-Payment*.<br><br>.3 after *Ready-for-Takeover* has been achieved in accordance with the *Contract Documents* and the *Work* is complete, there being no claims for lien registered against the title to the *Place of the Work* and no written notices of lien delivered to the *Owner*, pay the *Contractor* any unpaid balance of the *Contract Price* in accordance with GC 5.5 – FINAL PAYMENT, excluding *Deficiency Holdback*, together with such *Value Added Taxes* as may be applicable to such payment." |
| SC 4.2 | A-5.2.1 | Delete subparagraph 5.2.1 in its entirety and replace it with the following:<br><br>".1 Should either party fail to make payments as they become due under the terms of the *Contract* or in an award by arbitration or court, interest shall also become due and payable on such unpaid amounts at the prejudgment interest rate prescribed by the *Courts of Justice Act* (Ontario), as it may change from time to time." |

***NEW* ARTICLE A-9 – CONFLICT OF INTEREST**

| | | |
|---|---|---|
| SC3.1 | A-9 | Add new ARTICLE A-9 CONFLICT OF INTEREST as follows:<br><br>"**ARTICLE A-9 CONFLICT OF INTEREST**<br><br>9.1 The *Contractor*, *Subcontractors* and *Suppliers* and any of their respective advisors, partners, directors, officers, employees, agents, and volunteers shall not engage in any activity or provide any services where such activity or the provision of such services creates a conflict of interest (actually or potentially, in the sole opinion of the *Owner*) with the provision of the *Work* pursuant to the *Contract*. The *Contractor* acknowledges and agrees that a conflict of interest, as described in this Article A-9, includes, but is not limited to, the use of *Confidential Information* where the *Owner* has not specifically authorized such use.<br><br>9.2 The *Contractor* shall disclose to the *Owner*, in writing, without delay, any actual or potential situation that may be reasonably interpreted as either a conflict of interest or a potential conflict of interest, including the retention of any *Subcontractor* or *Supplier* that is directly or indirectly affiliated with or related to the *Contractor*.<br><br>9.3 The *Contractor* covenants and agrees that it will not hire or retain the services of any employee or previous employee of the *Owner* where to do so constitutes a breach by such employee or previous employee of the *Owner's* conflict of interest policy, as it may be amended from time to time, until after completion of the *Work* under the *Contract*.<br><br>9.4 It is of the essence of the *Contract* that the *Owner* shall not have direct or indirect liability to any *Subcontractor or Supplier*, and that the *Owner* relies on the maintenance of an arm's-length relationship between the *Contractor* and its *Subcontractors and Suppliers*. Consistent with this fundamental term of the *Contract*, the *Contractor* will not enter into any agreement |

| | | |
|---|---|---|
| | | or understanding with any *Subcontractor or Supplier*, whether as part of any contract or any written or oral collateral agreement, pursuant to which the parties thereto agree to cooperate in the presentation of a claim for payment against the *Owner*, directly or through the *Contractor*, where such claim is, in whole or in part, in respect of a disputed claim by the *Subcontractor or Supplier* against the *Contractor*, where the payment to the *Subcontractor or Supplier* by the *Contractor* is agreed to be conditional or contingent on the ability to recover those amounts or a portion thereof from the *Owner*, failing which the *Contractor* shall be saved harmless from all or a portion of those claims. The *Contractor* acknowledges that any such agreement would undermine the required arm's-length relationship and constitute a conflict of interest. For greater certainty, the *Contractor* shall only be entitled to advance claims against the *Owner* for amounts pertaining to *Subcontractor or Supplier* claims where the *Contractor* has actually paid or unconditionally acknowledged liability for those claims or where those claims are the subject of litigation or binding arbitration between the *Subcontractor or Supplier* and the *Contractor* has been found liable for those claims.<br><br>9.5 Notwithstanding paragraph 7.1.2 of GC 7.1 - OWNER'S RIGHT TO PERFORM THE WORK, TERMINATE THE CONTRACTOR'S RIGHT TO CONTINUE WITH THE WORK, OR TERMINATE THE CONTRACT, a breach of this Article A-9 by the *Contractor*, any of the *Subcontractors*, or any of their respective advisors, partners, directors, officers, employees, agents, and volunteers shall entitle the *Owner* to terminate the *Contract*, in addition to any other rights and remedies that the *Owner* has in the *Contract*, in law, or in equity." |

***NEW* ARTICLE A-10 TIME OF THE ESSENCE**

| | | |
|---|---|---|
| SC6.1 | Article A-10 | Add the following new Article A-10 as follows:<br><br>**"ARTICLE A-10 TIME OF THE ESSENCE**<br><br>10.1 It is agreed that one of the reasons the *Contractor* was selected by the *Owner* for this *Contract* is the *Contractor's* representation and covenant that it will attain *Substantial Performance, Occupancy (*if applicable), and *Ready-for-Takeover* within the *Contract Time* stated in Article A-1 of this *Contract*.<br><br>10.2 The *Contractor* acknowledges and agrees that it is responsible to marshal its resources and those of its *Subcontractors and Suppliers* in a manner which will permit timely attainment of *Substantial Performance, Occupancy (*if applicable), and *Ready-for-Takeover*. The *Contractor* agrees that time is of the essence of this *Contract*." |
| SC6.2 | | |

**DEFINITIONS**

| | | |
|---|---|---|
| ***Revisions to Existing Definitions*** | | |
| SC5.1 | Consultant | Amend the definition of "Consultant" by adding the following to the end of the definition:<br><br>"For the purposes of the *Contract*, the terms "*Consultant"*, "*Architect*" and "*Engineer*" shall be considered synonymous." |
| SC5.2 | Payment Legislation/Construction Act | Delete the Definition of *Payment Legislation* and replace it with "Construction Act" as follows:<br><br>"**Construction Act**<br><br>*Construction Act* means the *Construction Act*, R.S.O. 1990, c. C.30, as amended, including all regulations passed under it that are enforceable as of the date of execution of this *Contract*. For certainty, the first procurement process for the *Project* (*i.e.*, the "improvement" as that term is defined in the *Construction Act*) commenced on or after October 1, 2019." |
| SC5.3 | Ready-for-Takeover | Amend the Definition of *Ready-for-Takeover* by deleting all the words after "as verified" and replacing them with "and approved by the *Owner*." |
| ***New Definitions*** | | |
| | Adjudication | Add the following definition:<br><br>"**Adjudication**<br><br>*Adjudication* means construction dispute interim adjudication as defined under the *Construction Act*." |
| | Close-Out Documentation | Add the following new definition:<br><br>"**Close-Out Documentation**<br>*Close-Out Documentation* has the meaning given to it under GC 5.4.2." |
| | Confidential Information | Add the following definition:<br><br>"**Confidential Information**<br><br>*Confidential Information* means all the information or material of the *Owner* that is of a proprietary or confidential nature, whether it is identified as proprietary or confidential or not, including but not limited to information and material of every kind and description (such as drawings and move-lists) which is communicated to or comes into the possession or control of the *Contractor* at any time, but *Confidential Information* shall not include information that:<br><br>.1 is or becomes generally available to the public without fault or breach on the part of the *Contractor*, including without limitation breach of any duty of confidentiality owed by the *Contractor* to the *Owner* or to any third party, but only after that information becomes generally available to the public;<br><br>.2 the *Contractor* can demonstrate to have been rightfully obtained by the *Contractor* from a third party who had the right to transfer or disclose it to the *Contractor* free of any obligation of confidence; |

| | | |
|---|---|---|
| | | .3 the *Contractor* can demonstrate to have been rightfully known to or in the possession of the *Contractor* at the time of disclosure, free of any obligation of confidence; or<br><br>.4 is independently developed by the *Contractor* without use of any *Confidential Information*." |
| | Construction Schedule | Add the following definition:<br><br>"**Construction Schedule**<br>*Construction Schedule* means the schedule for the performance of the *Work* provided by the *Contractor*, and approved by the *Owner*, pursuant to GC 3.4.1, including any amendments to the *Construction Schedule* made pursuant to the *Contract Documents*." |
| | Construction Schedule Update | Add the following definition:<br><br>"**Construction Schedule Update**<br><br>*Construction Schedule Update* means an update to the *Construction Schedule* by the *Contractor* using Microsoft Project (or other approved scheduling software) that accurately depicts the progress of the *Work* relative to the critical path established in the *Construction Schedule* approved in GC 3.5.1 (or any approved successor *Construction Schedule*), aligns with the currently approved date for *Substantial Performance of the Work*, shows up-to-date projected major activity sequences and durations, and shows any changes or delays in anticipated completion dates of major activities in the *Work* relative to the last *Construction Schedule Update,* and includes the following minimum deliverables:<br><br>(a) a record version of the updated *Construction Schedule* in .pdf format;<br><br>(b) an editable copy of the updated original digital file of the *Construction Schedule* (*e.g.*, .mpp format files for Microsoft Project)." |
| | Deficiency Holdback | Add the following definition:<br><br>**Deficiency Holdback** - a value applied to the total contract value to cover the cost of completing deficiencies in, or correcting defects in The Work. |
| | Direct Costs | Add the following definition:<br><br>"**Direct Costs**<br><br>*Direct Costs* are the reasonable costs of performing the contract or subcontract including costs related to the additional supply of services or materials (including equipment rentals), insurance and surety bond premiums, and costs resulting from seasonal conditions, that would not have been incurred, but do not include indirect damages suffered, such as loss of profit, productivity or opportunity, or any head office overhead costs." |
| | EFT | Add the following definition:<br><br>"**EFT** |

| | | |
|---|---|---|
| | | *EFT* has the definition given to it under GC 5.3.2." |
| | Excess Soil | Add the following definition:<br><br>"**Excess Soil**<br>*Excess Soil* means "excess soil" as that term is defined under section 3 of the *Excess Soil Regulation*." |
| | Excess Soil Regulation | Add the following Definition:<br><br>"**Excess Soil Regulation**<br>*Excess Soil Regulation* means O. Reg. 406/19: On-Site and Excess Soil Management to the *Environmental Protection Act,* R.S.O. 1990, c. E.19." |
| | Final Pre-Invoice Submission Meeting | Add the following ne definition:<br><br>"**Final Pre-Invoice Submission Meeting**<br>*Final Pre-Invoice Submission Meeting* has the meaning given to it in GC 5.5.1." |
| | Force Majeure | Add the following definition:<br><br>"**Force Majeure**<br><br>*Force Majeure* means any cause, unknown at the effective date of the *Contract* and beyond either party's control, other than financial difficulties, bankruptcy or insolvency, which prevents the performance by a party, or both, of any of their respective obligations under the *Contract* and the event of *Force Majeure* did not arise from a party's default and could not be avoided or mitigated by the exercise of reasonable effort or foresight. *Force Majeure* includes *Labour Disputes*; fire; unusual delay by common carriers or unavoidable casualties; delays in obtaining third-party licences, permits, agreements, or approvals (excluding approvals of any *Subcontractors* or *Suppliers* of any tier); civil disturbance; emergency acts, orders, legislation, regulations or directives or revoking of funding from any government or other public authority; acts of a public enemy; war; riot; sabotage; blockage; embargo; lightning; earthquake; adverse weather conditions but only if substantially beyond the weather norms of the *Place of the* Work; acts of God; or declared epidemic or pandemic outbreak or other public health emergency (*e.g*. SARS, COVID-19)." |
| | Install | Add the following definition:<br><br>"**Install**<br><br>*Install* means install and connect. *Install* has this meaning whether or not the first letter is capitalized." |
| | Labour Dispute | Add the following definition:<br><br>"**Labour Dispute**<br><br>*Labour Dispute* means any lawful or unlawful labour problems, work stoppage, labour disruption, strike, job action, slow down, lock-outs, picketing, refusal to work or continue to work, refusal to supply materials, cessation or work or other labour controversy which does, or might, affect the *Work*." |

| | | |
|---|---|---|
| | Notice of Non-Payment | Add the following definition:<br><br>"**Notice of Non-Payment**<br><br>*Notice of Non-Payment* means a notice of non-payment of holdback (Form 6) or a notice of non-payment (Form 1.1) under the *Act*, as applicable to the circumstances." |
| | OHSA | Add the following definition:<br><br>"**OHSA**<br><br>*OHSA* means the *Occupational Health and Safety Act*, R.S.O. 1990, c. O.1, as amended, including all regulations thereto." |
| | Overhead | Add the following definition:<br><br>"**Overhead**<br><br>*Overhead* means all site and head office operations and facilities, all site and head office administration and supervision; all duties and taxes for permits and licenses required by the authorities having jurisdiction at the *Place of the Work*; all requirements of Division 1, including but not limited to submittals, warranty, quality control, calculations, testing and inspections; meals and accommodations; and, tools, expendables and clean-up costs." |
| | Payment Period | Add the following definition:<br><br>"**Payment Period**<br><br>*Payment Period* has the definition given to it under GC 5.2.1." |
| | Pre-Invoice Submission Meeting | Add the following definition:<br><br>"**Pre-Invoice Submission Meeting**<br><br>*Pre-Invoice Submission Meeting* has the definition given to it under GC 5.2.1." |
| | Proper Invoice | Add the following definition:<br><br>"**Proper Invoice**<br><br>*Proper Invoice* means a "proper invoice" as that term is defined in Section 6.1 of the *Act*, including the minimum requirements set out in Appendix "1" of the Supplementary Conditions." |
| | Proper Invoice Submission Date | Add the following definition:<br><br>"**Proper Invoice Submission Date**<br><br>*Proper Invoice Submission Date* has the definition given to it under GC 5.2.2.1." |
| | Request for Information (RFI) | Add the following definition:<br><br>"**Request for Information (RFI)**<br><br>*Request for Information* or *RFI* means written documentation sent by the *Contractor* to the *Owner* or to the *Owner's* representative or the *Consultant* requesting written clarification(s) and/or interpretation(s) of the *Drawings* and/or *Specifications*, |

| | | |
|---|---|---|
| | | *Contract* requirements and/or other pertinent information required to complete the *Work* of the *Contract* without applying for a change or changes to the *Work*." |
| | Restricted Period | Add the following definition:<br><br>"**Restricted Period**<br><br>*Restricted Period* means the (inclusive) period of time between December 1 to January 8 and August 15 to September 15 of any given year throughout the duration of the *Contract*." |

**GENERAL CONDITIONS OF THE STIPULATED PRICE CONTRACT**

Where a General Condition or paragraph of the General Conditions of the *Contract* is deleted by these amendments, the numbering of the remaining General Conditions or paragraphs shall remain unchanged, unless stated otherwise herein, and the numbering of the deleted item will be retained, unused.

**PART 1 GENERAL PROVISIONS**

**GC 1.1 CONTRACT DOCUMENTS**

| | | |
|---|---|---|
| SC5.1 | 1.1.3 | Delete GC 1.1.3 in its entirety and replace it with the following:<br><br>"1.1.3 The *Contractor* shall review the *Contract Documents* and shall report promptly to the *Consultant* any error, inconsistency, or omission the *Contractor* may discover. Such review by the *Contractor* shall be undertaken with the standard of care described in GC 3.13.1. Except for its obligation to make such a review and report the result, the *Contractor* does not assume any responsibility to the *Owner* or to the *Consultant* for the accuracy of the *Contract Documents*. Provided it has exercised the degree of care and skill described in this GC 1.1.3, the *Contractor* shall not be liable for damage or costs resulting from such errors, inconsistencies, or omissions in the *Contract Documents*, which the *Contractor* could not reasonably have discovered through the exercise of the required standard of care." |
| SC5.2 | 1.1.4 | Delete GC 1.1.4 in its entirety and replace it with the following:<br><br>"1.1.4 Except for the obligation to complete the review prescribed in GC 1.1.3, and report the results as set out in this GC 1.1.4, the *Contractor* is not responsible for errors, omissions or inconsistencies in the *Contract Documents*. If there are errors, omissions or inconsistencies discovered by or made known to the *Contractor* as part of its review under GC 1.1.3 or at any time during the performance of the *Work*, the *Contractor* shall immediately notify the *Consultant*, and request instructions, a *Supplemental Instruction*, *Change Order*, or *Change Directive*, as the case may require, and shall not proceed with the *Work* affected until the *Contractor* has received corrected or additional information from the *Consultant*. The *Contractor* shall not be liable for damage or costs resulting from such errors, inconsistencies, or omissions in the *Contract Documents*, which the *Contractor* could not reasonably have discovered through the exercise of care and skill described in GC 3.13." |
| | 1.1.5.1 | Delete GC 1.1.5.1 and replace with the following:<br><br>".1 the order of priority of documents, from highest to lowest, shall be:<br><br>.1 Supplementary Conditions;<br><br>.2 the Agreement between the Owner and the Contractor;<br><br>.3 the Definitions; |

| | | |
|---|---|---|
| | | .4 the General Conditions;<br>.5 Division 01 of the *Specifications*<br>.*6* technical *Specifications;*<br>.7 material and finishing schedules; and<br>.8 the *Drawings*. |
| | 1.1.5.5 | Delete GC 1.1.5.5 and replace with the following:<br>".5 Noted materials and annotations on the *Drawings* shall govern over the graphic representation of the *Drawings.*" |
| | 1.1.5.6 to 1.1.5.8 | Add the following new GC 1.1.5.6 to 1.1.5.8 as follows:<br>".6 Finishes in the room finish schedules shall govern over those shown on the *Drawings.*<br>.7 Architectural drawings shall have precedence over structural, plumbing, mechanical, electrical and landscape drawings insofar as outlining, determining and interpreting conflicts over the required design intent of all architectural layouts and architectural elements of construction, it being understood that the integrity and installation of the systems designed by the *Consultant* or its sub-*Consultants* are to remain with each of the applicable drawing disciplines.<br>.8 Should reference standards contained in the *Specifications* conflict with the *Specifications*, the *Specifications* shall govern. Should reference standards and *Specifications* conflict with each other or if certain requirements of the *Specifications* conflict with other requirements of the *Specifications*, the more stringent requirements shall govern." |
| | 1.1.9 | Add the following to the end of GC 1.1.9:<br>"The *Specifications* are divided into divisions and sections for convenience but shall be read as a whole and neither such division nor anything else contained in the *Contract Documents* will be construed to place responsibility on the *Owner* or the *Consultant* to settle disputes among the *Subcontractors* and *Suppliers* with respect to such divisions. The *Drawings* are, in part, diagrammatic and are intended to convey the scope of the *Work* and indicate general and appropriate locations, arrangements and sizes of fixtures, equipment, outlets and other elements. The *Contractor* shall obtain more accurate information about the locations, arrangements and sizes from study and coordination of the *Drawings,* including *Shop Drawings* and shall become familiar with conditions and spaces affecting those matters before proceeding with the *Work.* Where site conditions require reasonable minor changes where the change requires only the additional labour two hours or less, the *Contractor* shall make such changes at no additional cost to the *Owner.* Similarly, where known conditions or existing conditions interfere with new installation and require relocation, the *Contractor* shall include such relocation in the *Work.* The *Contractor* shall arrange and install fixtures and equipment in such a way as to conserve as much headroom and space as possible. The schedules are those portions of the *Contract Documents*, wherever located and whenever issued, which compile information of similar content and may consist of drawings, tables and/or lists.*"* |
| | 1.1.13 | Add new paragraphs 1.1.13 as follows:<br>1.1.13 The *Contractor* shall keep one copy of the current *Contract Documents*, *Supplemental Instructions*, contemplated *Change Orders*, *Change Orders*, *Change Directives*, cash allowance disbursement authorizations, reviewed *Shop Drawings*, submittals, reports and records of meeting at the *Place of the Work*, in good order and available to the *Owner* and *Consultant*." |

**GC 1.3 RIGHTS AND REMEDIES**

| | | |
|---|---|---|
| SC6.1 | 1.3.2 | In paragraph 1.3.2 delete the word "No" from the beginning of the paragraph and replace it with the words:<br><br>"Except with respect to the requirements set out in paragraphs 6.4.1, 6.5.4, 6.6.1 and 8.3.2, no…" |

***NEW* GC 1.5 EXAMINATION OF DOCUMENTS AND SITE**

| | | |
|---|---|---|
| SC8.1 | 1.5 | Add new GC 1.5 – EXAMINATION OF DOCUMENTS AND SITE as follows:<br><br>"**GC 1.5 EXAMINATION OF DOCUMENTS AND SITE**<br><br>1.5.1 The *Contractor* declares and represents that in tendering for the *Work*, and in entering into a Contract with the *Owner* for the performance of the *Work*, it has investigated for itself the character of the *Work t*o be done, based on information generally available from a visit to the *Place of the Work* and to the standard set out under GC 3.14.1 and further represents and warrants and acknowledges that it considered and took into account in the *Contract Price* all reasonably known impacts and restrictions arising from the COVID-19 pandemic, including without limitation corresponding legislative changes that may impact performance of the *Project*, various weather conditions that may affect the *Work*, the availability of supplies and labour or other conditions or risks that the *Contractor* knew about or reasonably ought to have known about prior to the date of the *Contract.* The *Contractor* has assumed and does hereby assume all risk of known conditions now existing or arising in the course of the *Work* which might or could make the Work, or any items thereof more expensive in character, more onerous to fulfill than was contemplated or known when the tender was made or the *Contract* signed.<br><br>1.5.2 The *Contractor* also declares that prior to commencement of the *Work*, where in tendering for the *Work* and in entering into this *Contract*, the *Contractor* relied upon information furnished by the *Owner* or any of its agents or servants respecting the nature or confirmation of the ground at the site of the Work, the Contractor shall review to the standard specified in GC 3.14.1, the accuracy of the information furnished by the *Owner*. If a condition is materially different than what is stated in the information furnished by the *Owner*, the *Contractor* shall, no later than five (5) *Working Days* after the first observation of such condition(s), deliver to the *Owner* and to the *Consultant* a *Notice in Writing* specifying the materially different condition and the *Contractor* shall not proceed with the affected part of the Work until receiving written direction from the *Owner* or the *Consultant*. Where the *Contractor* fails to provide prompt *Notice in Writing* in accordance with this GC 1.5.2, the *Contractor* expressly waives and releases the *Owner* from all claims with respect to the said information with respect to the *Work*. |

**PART 2 ADMINISTRATION OF THE CONTRACT**

**GC 2.2 ROLE OF THE CONSULTANT**

| | | |
|---|---|---|
| SC11.1 | 2.2.5 | Delete paragraph 2.2.4 and replace it with the following:<br><br>"2.2.4 Upon receipt of an application for payment that satisfies the requirement of a *Proper Invoice*, based on the *Consultant's* observations and evaluation of the *Contractor's* application for payment, the *Consultant* will determine the amounts owing to the *Contractor* under the *Contract* and will issue certificates for payment as provided in Article A-5 - PAYMENT, GC 5.3 - PAYMENT, GC 5.4 SUBSTANTIAL PERFORMANCE OF THE WORK |

| | | |
|---|---|---|
| | | AND PAYMENT OF HOLDBACK, and GC 5.5 - FINAL PAYMENT. If the *Consultant* determines that the amount payable to the *Contractor* differs from the amount stated in a *Proper Invoice*, the *Consultant* shall notify the *Owner* as provided in GC 5.3.1.2 and prepare a draft of the applicable *Notice of Non-Payment* for the amount in dispute." |
| | 2.2.6 | In the first sentence of paragraph 2.2.6, delete the words "Except with respect to GC 5.1 – FINANCING INFORMATION REQUIRED OF THE OWNER". |
| | 2.2.12 | At paragraph 2.2.12, insert the following at end of that paragraph:<br><br>"If, in the opinion of the *Contractor*, the *Supplemental Instruction* involves an adjustment in the *Contract Price* or in the *Contract Time*, it shall, within ten (10) *Working Days* of receipt of a *Supplemental Instruction*, provide the *Consultant* with a notice in writing to that effect. Failure to provide written notification within the time stipulated in this paragraph 2.2.12 shall be deemed an acceptance of the *Supplemental Instruction* by the *Contractor*, without any adjustment in the *Contract Price* or *Contract Time*." |

**GC 2.3 REVIEW AND INSPECTION OF THE WORK**

| | | |
|---|---|---|
| SC10.1 | 2.3.2 | Amend paragraph 2.3.2 by adding the words "and *Owner*" after the words "*Consultant*" in the second and third lines. |
| | 2.3.3 | Delete paragraph 2.3.3 in its entirety and replace it with the following:<br><br>"2.3.3 The *Contractor* shall furnish promptly two copies to the *Consultant* and one copy to the *Owner* of all certificates and inspection reports relating to the *Work*." |
| | 2.3.4 | In paragraph 2.3.4 add the word "review" after the word "inspections" in the first and second lines of paragraph 2.3.4. |
| | 2.3.5 | In paragraph 2.3.5 in the first line after the word "*Consultant*", add "or the *Owner*". |
| | 2.3.8 | Add a new paragraph 2.3.8 as follows:<br><br>"2.3.8 The *Consultant* will conduct periodic reviews of the *Work* in progress, to determine general conformance with the requirements of the *Contract Documents*. Such reviews, or lack thereof, shall not give rise to any claims by the *Contractor* in connection with construction means, methods, techniques, sequences and procedures, nor in connection with construction safety at the *Place of Work*, responsibility for which belongs exclusively to the *Contractor*." |

**GC 2.4 DEFECTIVE WORK**

| | | |
|---|---|---|
| SC11.1 | 2.4.1 | Amend GC 2.4.1 by inserting ", the *Owner* and/or its agent" in the first sentence following "rejected by the *Consultant*". |
| | 2.4.1.1 to 2.4.1.2 | Add new paragraphs 2.4.1.1 and 2.4.1.2 as follows:<br><br>"2.4.1.1 The *Contractor* shall rectify, in a manner acceptable to the *Consultant* and to the *Owner through the Consultant* all defective work and deficiencies throughout the *Work*, whether or not they are specifically identified by the *Consultant*.<br><br>2.4.1.2 The *Contractor* shall prioritize the correction of any defective work, which, in the sole discretion of the *Owner through the Consultant*, adversely affects the day to day operations |

| | | |
|---|---|---|
| | | of the *Owner* or which, in the sole discretion of the *Consultant*, adversely affects the progress of the *Work*." |
| | 2.4.2 | Delete paragraph 2.4.2 in its entirety and replace it with the following:<br><br>"2.4.2 The *Contractor* shall promptly pay the *Owner* for costs incurred by the *Owner*, the *Owner's* own forces or the *Owner's* other contractors, for work destroyed or damaged or any alterations necessitated by the *Contractor's* removal, replacement or re-execution of defective work." |
| | 2.4.4 | Add new paragraph 2.4.4 as follows:<br><br>"2.4.4 Neither acceptance of the *Work* by the *Consultant* or the *Owner*, nor any failure by the *Consultant* or the *Owner* to identify, observe or warn of defective *Work* or any deficiency in the *Work* shall relieve the *Contractor* from the sole responsibility for rectifying such defect or deficiency at the *Contractor's* sole cost, even where such failure to identify, observe or warn is negligent." |

**PART 3 EXECUTION OF THE WORK**

**GC 3.1 CONTROL OF THE WORK**

| | | |
|---|---|---|
| SC12.1 | 3.1.2 | Amend paragraph 3.1.2 by inserting the words "Construction Schedule" after the word "sequences". |
| SC12.2 | 3.1.3 & 3.1.4 | Add new paragraphs 3.1.3 and 3.1.4 as follows:<br><br>"3.1.3 Prior to commencing individual procurement, fabrication and construction activities, the *Contractor* shall verify at the *Place of the Work*, all relevant measurements and levels necessary for proper and complete fabrication, assembly and installation of the *Work* and shall further carefully compare such field measurements and conditions with the requirements of the *Contract Documents*. Where dimensions are not included or exact locations are not apparent, the *Contractor* shall immediately notify the *Consultant* in writing and obtain written instructions from the *Consultant* before proceedings with any part of the affected *Work*.<br><br>3.1.4 Notwithstanding the provisions of paragraphs 3.1.1 and 3.1.2, the *Owner* shall have access to the site at all times to monitor all aspects of construction. Such access shall in no circumstances affect the obligations of the *Contractor* to fulfill its contractual obligations." |

**GC 3.2 CONSTRUCTION BY OWNER OR OTHER CONTRACTORS**

| | | |
|---|---|---|
| SC13.1 | 3.2.2.1 | Delete subparagraph 3.2.2.1 and replace it with "[Intentionally left blank]". |
| | 3.2.3.2 | Delete subparagraph 3.2.3.2 and replace it with the following:<br><br>".2 co-ordinate and schedule the activities and work of other contractors and the *Owner's* own forces, including where other contractors or the Owner's own forces are used after the *Owner* and the *Contractor* cannot reach agreement on the value of a change, with the *Work* of the *Contractor* and connect as specified or shown in the *Contract Documents*." |
| | 3.2.3.4 | Delete the period at the end of subparagraph 3.2.3.4 and replace it with a semicolon. |
| | 3.2.3.5 | Add new subparagraph 3.2.3.5 as follows: |

| | | |
|---|---|---|
| | | ".5 Subject to GC 9.4 CONSTRUCTION SAFETY, for the *Owner's* own forces and for other contractors, assume overall responsibility for compliance with all aspects of the applicable health and safety legislation in force at the *Place of the Work*, including all of the responsibilities of the "constructor", pursuant to the *OHSA*." |

**GC 3.3 TEMPORARY WORK**

| | | |
|---|---|---|
| SC14.1 | 3.3.2 | In paragraph 3.3.2, in the second line after the words "where required by law", insert "or by the *Consultant*". |

**GC 3.4 CONSTRUCTION SCHEDULE**

| | | |
|---|---|---|
| SC17.1 | 3.4.1 | Delete GC 3.4.1 in its entirety and replace it with the following:<br><br>"3.4.1 The *Contractor* shall:<br><br>1 within five (5) calendar days of receiving written confirmation of the award of the *Contract*, prepare and submit to the *Owner* and the *Consultant* for their review and approval, a construction schedule in the format indicated below that indicates the timing of the activities of the *Work* and provides sufficient detail of the critical events and their inter-relationship to demonstrate the *Work* will be performed in conformity with the *Contract Time* and in accordance with the *Contract Documents.* Such schedule is to include a delivery schedule for *Products* whose delivery is critical to the schedule for the *Work* or are required by the *Contract* to be included in a *Products* delivery schedule. The *Contractor* shall employ construction scheduling software, being the latest version of "Microsoft Project", that permits the progress of the *Work* to be monitored in relation to the critical path established in the schedule. The *Contractor* shall provide such schedule and any successor or revised schedules in both original digital file format (*e.g.,* .mpp format for Microsoft Project), portable data file (PDF) format, and hard copy. Once accepted by the *Owner* and the *Consultant*, the construction schedule submitted by the *Contractor* shall become the baseline "**Construction Schedule**";<br><br>.2 provide the expertise and resources, such resources including manpower equipment and tools, as are necessary on a best efforts basis to maintain progress under the accepted baseline *Construction Schedule* or revised construction schedule accepted by the *Owner* pursuant to GC 3.4 CONSTRUCTION SCHEDULE, which includes without limitation, the *Contractor*'s use of all possible and, if necessary, extraordinary measures, to bring the progress of the *Work* into compliance with the *Construction Schedule*, such as (i) increasing the presence of its own forces at the *Place of the Work*; (ii) directing any *Subcontractors* or *Suppliers* to increase their labour forces and equipment; (iii) working overtime and extra shifts; and (iv) providing any additional supervision and coordination of the *Project*, all at the *Contractor's* own cost and expense save and except where GC 6.5.1, 6.5.2, or 6.5.3 apply; and,<br><br>.3 monitor the progress of the *Work* on a weekly basis relative to the baseline *Construction Schedule*, or any revised *Construction Schedule* accepted by the *Owner* pursuant to GC 3.4 CONSTRUCTION SCHEDULE, deliver a *Construction Schedule Update* to the *Consultant* and *Owner* with each application for payment, at a minimum, or as may be reasonably required |

| | | |
|---|---|---|
| | | by the *Consultant* and advise the *Consultant* and the *Owner* weekly in writing of any variation from the baseline or slippage in the schedule; and,<br><br>.4 if after applying the expertise and resources required under paragraph 3.4.1.2, the *Contractor* forms the opinion that the slippage in schedule reported in paragraph 3.4.1.3 cannot be recovered by the *Contractor*, it shall, in the same notice provided under paragraph 3.4.1.3, indicate to the *Consultant* if the *Contractor* intends to apply for an extension of *Contract Time* as provided in PART 6 —CHANGES IN THE WORK; and,<br><br>.5 ensure that the *Contract Price* shall include all costs required to phase or stage the *Work*." |
| | 3.4.2 | Add new GC 3.4.2 and GC 3.4.3 as follows:<br><br>"3.4.2 If, at any time, it should appear to the *Owner* or the *Consultant* that the actual progress of the *Work* is behind schedule or is likely to become behind schedule, or if the *Contractor* has given notice of such to the *Owner* or the *Consultant* pursuant to GC 3.4.1.3, the *Contractor* shall, either at the request of the *Owner* or the *Consultant*, or following giving notice pursuant to GC 3.4.1.3, take appropriate steps to cause the actual progress of the *Work* to conform to the schedule or minimize the resulting delay. Within 5 calendar days of the request by the *Owner* or the *Consultant* or the notice being given pursuant to GC 3.4.1.3, the *Contractor* shall produce and present to the *Owner* and the *Consultant* a plan demonstrating how the *Contractor* will recover the performance of the *Work* to align with the currently approved *Construction Schedule*.<br><br>3.4.3 The *Contractor* shall not amend the *Construction Schedule* without the prior written consent of the *Owner*.. Any revisions to the *Construction Schedule* approved by the *Owner* shall not be deemed to be an extension of the *Contract Time*. All requests by the Contractor for a revision to the Construction Schedule that include an extension to the *Contract Time* must be approved by the *Owner* through an executed *Change Order*." |

**GC 3.5 SUPERVISION**

| | | |
|---|---|---|
| SC17.1 | 3.5.1 | Delete GC 3.5.1 and replace it with the following:<br><br>"3.5.1 The *Contractor* shall employ a competent full-time superintendent, acceptable to the *Owner* and *Consultant*, who shall be in full time attendance at the *Place of the Work* while the *Work* is being performed. The superintendent shall not be changed by the *Contractor* without valid reason which shall be provided in writing and shall not be changed without prior consultation with and agreement by the Owner and the *Consultant*. The *Contractor* shall replace the superintendent within 7 *Working Days* of the *Owner's* written notification, if the superintendent's performance is not acceptable to the *Owner*. The *Contractor* shall provide the *Owner* and the *Consultant* with the names, addresses and telephone numbers of the superintendent referred to in this GC 3.5.1 and other responsible persons who may be contacted for emergency and other reasons during non-working hours. ." |

| | | |
|---|---|---|
| | 3.5.2 | Delete GC 3.5.2 and replace it with the following:<br><br>"3.5.2 The superintendent, and any project manager appointed by the *Contractor*, shall represent the *Contractor* at the *Place of the Work* and shall have full authority to act on written instructions given by the *Consultant* and/or the *Owner*. Instructions given to the superintendent or the project manager shall be deemed to have been given to the *Contractor* and both the superintendent and any project manager shall have full authority to act on behalf of the *Contractor* and bind the *Contractor* in matters related to the *Contract*." |
| | 3.5.3 to 3.5.6 | Add new GC 3.5.3, 3.5.4, 3.5.5 and 3.5.6 as follows:<br><br>"3.5.3 The *Owner* may, at any time during the course of the *Work*, request the replacement of the appointed representative(s). Immediately upon receipt of the request, the *Contractor* shall make arrangements to appoint an acceptable replacement, which is approved by the *Owner*.<br><br>3.5.4 The supervisory staff assigned to the *Project* shall also be fully competent to implement efficiently all requirements for scheduling, coordination, field engineering, reviews, inspections and submittals defined in the *Specifications,* and have a minimum 5 years documented "Superintendent/Project Management" experience.<br><br>3.5.5 The *Consultant and Owner* shall reserve the right to review the record of experience and credentials of supervisory staff assigned to the *Project* prior to commencement of the *Work*.<br><br>3.5.6 A superintendent assigned to the *Work* shall be "Gold Seal Certified" as per the Canadian Construction Association; or a superintendent that can demonstrate the requisite experience and success related to the *Project* to the sole satisfaction of the *Owner*." |

**GC 3.6 SUBCONTRACTORS AND SUPPLIERS**

| | | |
|---|---|---|
| SC18.1 | 3.6.1.1 | In paragraph 3.6.1.1 add to the end of the second line the words "including any warranties and service agreements which extend beyond the term of the *Contract*." |
| | 3.6.1.2 | In subparagraph 3.6.1.2 after the words "the *Contract Documents*" add the words "including any required surety bonding". |
| | 3.6.2 | Delete paragraph 3.6.2. in its entirety and replace it with the following:<br><br>"3.6.2 The substitution of any *Subcontractor* and/or *Suppliers* after submission of the *Contractor's* bid will not be accepted unless a valid reason is given in writing to and approved by the *Owner*, whose approval may be arbitrarily withheld. The reason for substitution must be provided to the *Owner* and to the original *Subcontractor* and/or *Supplier* and the *Subcontractor* and/or *Supplier* shall be given the opportunity to reply to the *Contractor* and *Owner.* The *Contractor* shall be fully aware of the capability of each *Subcontractor* and/or *Supplier* included in its bid, including but not limited to technical ability, financial stability and ability to maintain the proposed construction schedule." |
| | 3.6.7, 3.6.8, | Add new paragraphs 3.6.7, 3.6.8, 3.6.9, and 3.6.10 as follows: |

| | | |
|---|---|---|
| | 3.6.9 & 3.6.10 | "3.6.7 The *Contractor* represents and warrants that it has confirmed the availability of its *Subcontractors* for the *Project* and, in particular, for the performance of their respective portions of the *Work* to ensure completion of the *Project* within the *Contract Price* and the *Contract Time*.<br><br>3.6.8 The *Consultant* or the *Owner*, acting reasonably, may from time to time require the *Contractor* to remove from the *Project* any personnel of the *Contractor*, including project managers, superintendents or *Subcontractors*. Such persons shall be replaced by the *Contractor* in a timely fashion to the satisfaction of the *Consultant* or the *Owner*, as the case may be, at no cost to the *Owner*.<br><br>3.6.9 Where provided in the *Contract*, the *Owner* may assign to the *Contractor*, and the *Contractor* agrees to accept, any contract procured by the *Owner* for *Work* or services required on the *Project* that has been pre-tendered or pre-negotiated by the *Owner*, and upon such assignment, the *Owner* shall have no further liability to any party for such contract.<br><br>3.6.10 The *Contractor* covenants that each subcontract or supply contract which the *Contractor* enters into for the purpose of performing the *Work* shall expressly provide for the assignment thereof to the *Owner* (at the option of the *Owner*) and the assumption by the *Owner* of the obligations of the *Contractor* thereunder, upon the termination of the *Contract* and upon written notice by the *Owner* to the other parties to such subcontracts or supply contracts, without the imposition of further terms or conditions; provided, however, that until the *Owner* has given such notice, nothing herein contained shall be deemed to create any contractual or other liability upon the *Owner* for the performance of obligations under such subcontracts or supply contracts and the *Contractor* shall be fully responsible for all of its obligations and liabilities (if any) under such subcontracts and supply contracts." |

**GC 3.7 LABOUR AND PRODUCTS**

| | | |
|---|---|---|
| SC19.1 | 3.7.1 | Amend paragraph 3.7.1 by adding the words, "…, agents, *Subcontractors* and *Suppliers*…" after the word "employees" in the first line. |
| SC19.2 | 3.7.2 | Delete paragraph 3.7.2 and substitute with the following:<br><br>"3.7.2 *Products* provided shall be new and shall conform to all current applicable specifications of the Canadian Standards Association, Canadian Standards Board or General Standards Board, ASTM, National Building Code, provincial and municipal building codes, fire safety standards, and all governmental authorities and regulatory agencies having jurisdiction at the *Place of the Work*, unless otherwise specified. *Products* which are not specified shall be of a quality consistent with those specified and their use acceptable to the *Consultant*. *Products* brought on to the *Place of the Work* by the *Contractor* shall be deemed to be the property of the *Owner*, but the *Owner* shall be under no liability for loss thereof or damage thereto arising from any cause whatsoever. The said *Products* shall be at the sole risk of the *Contractor*. Workmanship shall be, in every respect, first class and the *Work* shall be performed in accordance with the best modern industry practice." |
| | 3.7.4 to 3.7.8 | Add new paragraphs 3.7.4, 3.7.5, 3.7.6, 3.7.7, and 3.7.8 as follows:<br><br>"3.7.4 Upon receipt of a *Notice in Writing* from the *Owner,* the *Contractor* shall immediately remove from the *Place of the Work*, tradesmen and labourers or anyone whose conduct |

| | | |
|---|---|---|
| | | jeopardizes the safety of the *Owner's* operations or who are considered by the *Owner* or the *Consultant* to be unskilled or otherwise objectionable. Immediately upon receipt of the request, the *Contractor* shall make arrangements to appoint an acceptable replacement.<br><br>3.7.5 The *Contractor* shall cooperate with the *Owner* and its representatives and shall take all reasonable and necessary actions to maintain stable and harmonious labour relations with respect to the *Work* at the *Place of the Work*, including cooperation to attempt to avoid *Work* stoppages, trade union jurisdictional disputes and other *Labour Disputes*. Any costs arising from labour disputes shall be at the sole expense of the *Contractor.*<br><br>3.7.6 The cost for overtime required beyond the normal *Working Day* to complete individual construction operations of a continuous nature, such as pouring or finishing of concrete or similar work, or *Work* that the *Contractor* elects to perform at overtime rates without the *Owner* requesting it, shall not be chargeable to the *Owner*.<br><br>3.7.7 All manufactured *Products* which are identified by their proprietary names or by part or catalogue number in the *Specifications* shall be used by the *Contractor.* No substitutes for such specified *Products* shall be used without the written approval of the *Owner* and the *Consultant*. Substitutes will only be considered by the *Consultant* when submitted in sufficient time to permit proper review and investigation. When requesting approval for the use of substitutes, the *Contractor* shall include in its submission any proposed change in the *Contract Price*. The *Contractor* shall use all proprietary *Products* in strict accordance with the manufacturer's directions. Where there is a choice of proprietary *Products* specified for one use, the *Contractor* may select any one of the *Products* so specified for this use.<br><br>3.7.8 Materials, appliances, equipment and other *Products* are sometimes specified by reference to brand names, proprietary names, trademarks or symbols. In such cases, the name of a manufacturer, distributor, *Supplier* or dealer is sometimes given to assist the *Contractor* to find a source *Supplier*. This shall not relieve the *Contractor* from its responsibility from finding its own source of supply even if the source names no longer supplies the *Product* specified. If the *Contractor* is unable to obtain the specified *Product*, the *Contractor* shall supply a substitute product equal to or better than the specified *Product,* as approved by the *Consultant* with no extra compensation. Should the *Contractor* be unable to obtain a substitute *Product* equal to or superior to the specified *Product* and the *Owner* accepts a different Product, the *Contract Price* shall be adjusted accordingly, as approved by the *Consultant*." |

**GC 3.8 SHOP DRAWINGS**

| | | |
|---|---|---|
| SC21.1 | 3.8.1 | Delete paragraph 3.8.1 in its entirety and replace with the following:<br><br>"3.8.1 The *Contractor* shall provide shop drawings as described in the *Contract Documents* and as the *Consultant* may reasonably request." |
| | 3.8.3 | Delete paragraph 3.8.3 and replace it with the following:<br><br>"3.8.3 The *Contractor* shall prepare a *Shop Drawings* schedule acceptable to the *Owner* and the *Consultant* prior to the first application for payment. A draft of the proposed *Shop* |

| | | |
|---|---|---|
| | | *Drawings* schedule shall be submitted by the *Contractor* to the *Consultant* and the *Owner* for approval. The draft *Shop Drawings* schedule shall clearly indicate the phasing of *Shop Drawings* submissions. The *Contractor* shall periodically re-submit the *Shop Drawings* schedule to correspond to changes in the *Construction Schedule*." |
| | 3.8.5 | Delete paragraph 3.8.5 in its entirety and substitute the following:<br><br>"3.8.5 At the time of providing *Shop Drawings*, the *Contractor* shall advise the *Consultant* in writing of any deviations in *Shop Drawings* from the requirements of the *Contract Documents*. The *Consultant* shall indicate the acceptance of such deviation expressly in writing. Where manufacturers' literature is submitted in lieu of scaled drawings, it shall be clearly marked in ink, to indicate the specific items for which review is requested." |
| | 3.8.8 to 3.8.12 | Add new paragraphs 3.8.8, 3.8.9, 3.8.10, 3.8.11, and 3.8.12 as follows:<br><br>"3.8.8 Reviewed *Shop Drawings* shall not authorize a change in the *Contract Price* and/or the *Contract Time*.<br><br>3.8.9 Except where the parties have agreed to a different *Shop Drawings* schedule pursuant to paragraph 3.10.3, the *Contractor* shall comply with the requirements for *Shop Drawings* submissions stated in the *Specifications*.<br><br>3.8.10 The *Contractor* shall not use the term "by others" on *Shop Drawings* or other submittals. The related trade, *Subcontractor* or *Supplier* shall be stated.<br><br>3.8.11 Certain *Specifications* sections require the *Shop Drawings* to bear the seal and signature of a professional engineer. Such professional engineer must be registered in the jurisdiction of the *Place of the Work* and shall have expertise in the area of practice reflected in the *Shop Drawings*.<br><br>3.8.12 The *Consultant* will review and return *Shop Drawings* and submittals in accordance with the schedule agreed upon in paragraph 3.10.3, The *Contractor* shall allow the *Consultant* a minimum of 10 *Working Days* to review *Shop Drawings* from the date of receipt. If resubmission of *Shop Drawings* is required, a further 10 *Working Day* period is required for the *Consultant's* review." |

***NEW* GC 3.9 USE OF THE WORK**

| | | |
|---|---|---|
| SC22.1 | GC 3.9 | Add new GC 3.9 – USE OF THE WORK as follows:<br><br>"**GC 3.9 USE OF THE WORK**<br><br>3.9.1 The *Contractor* shall confine *Construction Equipment*, *Temporary Work*, storage of *Products*, waste products and debris, and operations of employees and *Subcontractors* to limits indicated by laws, ordinances, permits, by the direction of the *Owner* or the *Consultant*, or the *Contract Documents* and shall not unreasonably encumber the *Place of the Work*. |

| | | |
|---|---|---|
| | | 3.9.2 The *Contractor* shall not load or permit to be loaded any part of the *Work* with a weight or force that will endanger the safety of the *Work*.<br><br>3.9.3 The *Owner* shall have the right to enter or occupy the *Place of the Work* in whole or in part for the purpose of placing fittings and equipment, or for other use before *Substantial Performance of the Work*, if, in the opinion of the *Consultant*, such entry and occupation does not prevent or substantially interfere with the *Contractor* in the performance of the *Contract* within the *Contract Time.* Such entry or occupation shall neither be considered as acceptance of the *Work* or in any way relieves the *Contractor* from its responsibility to complete the *Contract*." |

"

***NEW* GC 3.10 CUTTING AND REMEDIAL WORK**

| | | |
|---|---|---|
| SC23.1 | GC 3.10 | Add new GC 3.10 – CUTTING AND REMEDIAL WORK as follows:<br><br>"**GC 3.10 CUTTING AND REMEDIAL WORK**<br><br>3.10.1 The *Contractor* shall perform the cutting and remedial work required to make the affected parts of the *Work* come together properly. Such cutting and remedial work shall be performed by specialists familiar with the *Products* affected and shall be performed in a manner to neither damage nor endanger the *Work*.<br><br>3.10.2 The *Contractor* shall coordinate the *Work* to ensure all cutting and remedial work required is kept to a minimum.<br><br>3.10.3 Unless specifically stated otherwise in the *Specifications*, the *Contractor* shall do all cutting and making good necessary for the proper installation and performance of the *Work.*<br><br>3.10.4 To avoid unnecessary cutting, the *Contractor* shall lay out its work and advise the *Subcontractors,* when necessary, where to leave holes for installation of pipes and other work." |

***NEW* GC 3.11 CLEAN UP**

| | | |
|---|---|---|
| SC24.1 | 3.11.1, 3.11.2, 3.11.3, 3.11.4, 3.11.5 & 3.11.6 | Add new paragraphs 3.11.1, 3.11.2, 3.11.3, 3.11.4, 3.11.5, and 3.11.6 as follows:<br><br>"3.11.1 The *Contractor* shall maintain the *Work* in a safe and tidy condition and free from the accumulation of waste products and debris, other than that caused by the *Owner*, other contractors or their employees. The *Contractor* shall remove accumulated waste and debris at least once a week as a minimum or as required by the nature of the *Work*.<br><br>3.11.2 Before applying for *Substantial Performance of the Work*, the *Contractor* shall remove waste products and debris, other than that resulting from the work of the *Owner*, other contractors or their employees, and shall leave the *Place of the Work* clean and suitable for use or occupancy by the *Owner*. The *Contractor* shall remove products, tools, materials, |

| | | |
|---|---|---|
| | | *Construction Equipment,* and *Temporary Work* not required for the performance of the remaining work.<br><br>3.11.3 As a condition precedent to submitting its application for final payment, the *Contractor* shall remove any remaining products, tools, materials, *Construction Equipment*, *Temporary Work*, and waste products and debris, other than those resulting from the work of the *Owner*, other contractors or their employees.<br><br>3.11.4 The *Contractor* shall clean up garbage during and after construction and maintain the *Place of the Work* in a neat and orderly condition on a daily basis. Prior to leaving the *Place of the Work* and following completion of the *Work*, the *Contractor* shall make good all damage to the building and its components caused by the performance of the *Work* or by any *Subcontractor* or *Supplier*. The *Contractor* shall leave the *Place of the Work* in a clean and finished state; remove all *Construction Equipment* and materials; remove all paint, stains, labels, dirt, etc. from the *Place of the Work*; and touch up all damaged painted areas (if applicable). The *Contractor* shall be responsible for restoring those areas of the *Place of the Work*, impacted by the *Work*, to their original condition."<br><br>3.11.5 Without limitation to or waiver of the *Owner's* other rights and remedies, the *Owner* shall have the right to back charge to the *Contractor* the cost of damage to the site caused by transportation in and out of the *Place of the Work* by the *Contractor*, *Subcontractors* or *Suppliers,* if not repaired before final payment.<br><br>3.11.6 The *Contractor* shall dispose of debris at a location and in a manner acceptable to the *Owner* (and to the authorities having jurisdiction at the *Place of the Work* and at the disposal area) and the *Contractor* shall cover containers with tarpaulins." |

***NEW* GC 3.12 EXCESS SOIL MANAGEMENT**

| | | |
|---|---|---|
| SC25.1 | GC 3.12 | Add new GC 3.12 – EXCESS SOIL MANAGEMENT as follows:<br><br>"**GC 3.12 EXCESS SOIL MANAGEMENT**<br><br>3.12.1 The *Contractor* shall be solely responsible for the proper management of all *Excess Soil* at the *Place of the Work* and for performance of the *Work* in compliance with the rules, regulations and practices required by the *Excess Soil Regulation* until such time as *Ready-for-Takeover* is achieved. Without restricting the generality of the previous sentence, the *Contractor*'s responsibility under this GC 3.12 includes the designation, transportation, tracking, temporary and/or final placement, record keeping, and reporting of all *Excess Soil* in connection with the Work all in compliance with the *Excess Soil Regulation*.<br><br>3.12.3 The *Contractor* shall indemnify and save harmless the *Owner*, their agents, officers, directors, administrators, employees, consultants, successors and assigns from and against the consequences of any and all health and safety infractions committed directly by the *Contractor*, or those for whom it is responsible at law, under the *Excess Soil Regulation*, or any environmental protection legislation, including the payment of legal fees and disbursements on a substantial indemnity basis. Such indemnity shall apply to the extent |

| | | |
|---|---|---|
| | | to which the *Owner* is not covered by insurance." |

***NEW* GC 3.13 CONTRACTOR STANDARD OF CARE**

| | | |
|---|---|---|
| SC25.1 | 3.13 | Add a new GC 3.13 – CONTRACTOR STANDARD OF CARE as follows:<br><br>"**GC 3.13 CONTRACTOR STANDARD OF CARE**<br><br>"3.13.1 In performing its services and obligations under the *Contract*, the *Contractor* shall exercise the standard of care, skill and diligence that would normally be provided by an experienced and prudent contractor supplying similar services for similar projects. The *Contractor* acknowledges and agrees that throughout the *Contract,* the performance of the *Contractor's* obligations, duties and responsibilities shall be interpreted in accordance with this standard. The *Contractor* shall exercise the same standard of care, skill and diligence in respect of any *Products*, personnel or procedures which it may recommend to the *Owner* or employ on the *Project*.<br><br>3.13.2 The *Contractor* further represents, covenants and warrants to the *Owner* that:<br><br>.1 the personnel it assigns to the *Project* are appropriately experienced;<br><br>.2 it has a sufficient staff of qualified and competent personnel to replace any of its appointed representatives, subject to the *Owner's* approval, in the event of death, incapacity, removal or resignation; and<br><br>.3 there are no pending, threatened or anticipated claims, liabilities or contingent liabilities that would have a material effect on the financial ability of the *Contractor* to perform its work under the *Contract*." |

**PART 4 ALLOWANCES**

**GC 4.1 CASH ALLOWANCES**

| | | |
|---|---|---|
| SC27.1 | 4.1.3 | In GC 4.1.3 delete the words "through the *Consultant*" and replace them with "in writing." |
| | 4.1.4 | Delete GC 4.1.4 in its entirety and replace it with the following:<br><br>"4.1.4 Where the actual cost of the *Work* under any cash allowance exceeds the amount of the allowance, any unexpended amounts from other cash allowances shall be reallocated, by the *Consultant* at the *Owner*'s direction, to cover the shortfall, and, in that case, there shall be no additional amount added to the *Contract Price* for overhead and profit. Only where the actual cost of the *Work* under all cash allowances exceeds the total amount of all cash allowances shall the *Contractor* be compensated for the excess incurred and substantiated, plus an amount for overhead and profit on the excess only, as set out in the *Contract Documents.*" |

| | | |
|---|---|---|
| | 4.1.7 | Delete GC 4.1.7 in its entirety and replace it with the following:<br><br>"4.1.7 The net amount of any unexpended cash allowances, after providing for any reallocations as contemplated in paragraph 4.1.4, shall be deducted from the *Contract Price* by *Change Order* without any adjustment for the *Contractor's* overhead and profit on such amount." |
| | 4.1.8 and 4.1.9 | Add new GC 4.1.8 and 4.1.9 as follows:<br><br>"4.1.8 The *Owner* reserves the right to call, or to have the *Contractor* call, for competitive bids for portions of the *Work* to be paid for from cash allowances.<br><br>4.1.9 Cash allowances cover the net cost to the *Contractor* of services, *Products*, *Construction Equipment*, freight, unloading, handling, storage, installation, provincial sales tax, and other authorized expenses incurred in performing any *Work* stipulated under the cash allowances but does not include any *Value Added Taxes* payable by the *Owner* and the *Contractor."* |

**PART 5 PAYMENT**

**GC 5.1 FINANCING INFORMATION REQUIRED OF THE OWNER**

| | | |
|---|---|---|
| SC28.1 | 5.1 | Delete GC 5.1 – FINANCING INFORMATION REQUIRED OF THE OWNER and all paragraphs thereunder, including any reference to GC 5.1 throughout the *Contract*. |

**GC 5.2 APPLICATIONS FOR PAYMENT**

| | | |
|---|---|---|
| SC29.1 | 5.2.1 | Delete GC 5.2.1 and replace it with the following:<br><br>"5.2.1 Upon execution of the *Contract*, and in any event prior to the *Contractor* submitting its first application for payment, the *Owner* shall issue a purchase order to the *Contractor* for the performance of the *Contract*. The number indicated on such purchase order must be clearly identifiable on all applications for payment. Applications for payment shall be dated the last day of each month or an alternative day of each month agreed to in writing by the parties, with each month representing one payment period under the *Contract* (each a "**Payment Period**"). Within 3 calendar days of the end of each *Payment Period*, the *Contractor* will submit a draft application for payment to the *Owner* and the *Consultant*. Upon receipt of the draft application for payment, and within 7 calendar days, a representative of each of the *Contractor*, *Owner*, and the *Consultant* shall attend a meeting to discuss and review the work completed during the *Payment Period*, including quantities, if applicable (the "**Pre-Invoice Submission Meeting**"). In the event that the scheduled date for the *Pre-Invoice Submission Meeting* is not a *Working Day*, the *Pre-Invoice Submission Meeting* shall occur on the next *Working Day*. The *Contractor* shall bring with it to the *Pre-Invoice Submission Meeting* the following:<br><br>.1 a copy of the draft application for payment; |

| | | |
|---|---|---|
| | | .2 any documents the *Contractor* is required to bring to the *Pre-Invoice Submission Meeting* as stipulated in the *Contract Documents* or as reasonably requested by the *Owner*; and<br><br>.3 any other documents reasonably requested, in advance, by the *Owner* or the *Consultant*." |
| SC29.2 | 5.2.2 | Delete GC 5.2.2 in its entirety and replace it with the following:<br><br>"5.2.2 Applications for payment shall be given in accordance with the following requirements:<br><br>.1 Within 5 calendar days following the *Pre-Invoice Submission Meeting*, the *Contractor* shall deliver its application for payment to the *Owner* and to the *Consultant* for *Work* performed during the *Payment Period* ("**Proper Invoice Submission Date**") subject to the following:<br><br>.1 If the fifth calendar day following the *Pre-Invoice Submission Meeting*, to which an invoice relates falls on a day that is not a *Working Day*, the *Proper Invoice Submission Date* shall be deemed to fall on the next *Working Day*.<br><br>.2 The application for payment must be delivered to the *Owner* and to the *Consultant* in the same manner as a *Notice in Writing* during the hours of 9:00 am to 4:00pm (EST) on the *Proper Invoice Submission Date*. Delivery to the *Owner* shall be to the following email address:<br><br>**facilities_cap@wrdsb.ca**<br><br>.3 If an application for payment is received after 4:00 p.m. (EST) on the applicable *Proper Invoice Submission Date*, the application for payment will not be considered or reviewed by the *Owner* and *Consultant* until the next *Proper Invoice Submission Date.* Notwithstanding the foregoing, the *Owner* in its sole and absolute discretion may elect to accept an application for payment submitted after 4:00 p.m. on the applicable *Proper Invoice Submission Date*; however, such acceptance shall not be construed as a waiver of any of its rights or waive or release the *Contractor*'s obligations to strictly comply with the requirements prescribed in this subparagraph 5.2.2.3.<br><br>.4 No applications for payment shall be accepted by the *Owner* prior to the *Proper Invoice Submission Date*.<br><br>.5 All applications for payment shall include all of the requirements for a *Proper Invoice* prescribed by the *Construction Act* and this *Contract* and be dated the last day of the applicable *Payment Period*;" |
| SC29.3 | 5.2.3 | Delete GC 5.2.3 and replace it with the following:<br><br>"5.2.3 The amount claimed shall be for the value, proportionate to the amount of the *Contract*, of *Work* performed and *Products* delivered and incorporated into the *Work* as of the last date of the applicable *Payment Period*. Materials may also be deemed to be supplied to an improvement, for payment purposes, when, in the *Owner's* opinion, they are placed |

| | | |
|---|---|---|
| | | and properly secured on the land on which the improvement is made, or placed upon land designated by the *Owner* or agent of the *Owner*, but placing the materials on the land so designated does not, of itself, make that land subject to a lien. No amount claimed shall include products delivered and incorporated into the work, unless the products are free and clear of all security interests, liens and other claims of third parties. No amount claimed shall include *Products* delivered to the *Place of the Work* unless the *Products* are free and clear of all security interests, liens, and other claims of third parties." |
| SC29.4 | 5.2.4 | After the word "*Consultant*" in GC 5.2.4 add the words "and the *Owner*" |
| SC29.5 | 5.2.5 | After the word "*Consultant*" in GC 5.2.5 add the words "or the *Owner*". |
| | | |
| SC29.6 | 5.2.9 | Add new 5.2.9 as follows:<br><br>"5.2.9 The *Contractor* shall prepare and maintain current as-built drawings which shall consist of the *Drawings* and *Specifications* revised by the *Contractor* during the *Work*, showing changes to the *Drawings* and *Specifications*, which current as-built drawings shall be maintained by the *Contractor* and made available to the *Consultant* for review with each application for progress payment. The *Consultant* shall recommend to the *Owner* that the *Owner* retain a reasonable amount for the value of the as-built drawings not presented for review." |

**GC 5.3 PAYMENT**

| | | |
|---|---|---|
| SC30.1 | 5.3.1 | Delete GC 5.3.1 in its entirety, including all subparagraphs thereunder, and replace it with the following:<br><br>"5.3.1 After receipt by the *Owner* and the *Consultant* of an application for payment submitted by the *Contractor* in accordance with GC 5.2 - APPLICATIONS FOR PAYMENT:<br><br>.1 the *Consultant* will either:<br><br>(a) issue to the *Owner* with a copy to the *Contractor*, a progress payment certificate in the amount applied for by the *Contractor* in the *Proper Invoice*, or<br><br>(b) issue to the *Owner*, with a copy to the *Contractor*, a certificate for payment for an amount determined by the *Consultant* to be properly due to the *Contractor* after applying any credits, withheld amounts, or other set-offs which the *Consultant* has determined that the *Owner* is entitled to notwithstanding any notice of dispute or disagreement that the *Contractor* may have served, along with the *Consultant's* reasons why an amount other than what is claimed in the *Proper Invoice* is properly due to the *Contractor*, which finding the *Owner* may accept or amend prior to the *Owner* issuing a *Notice of Non-Payment*, if any, in accordance with GC 5.3.2;<br><br>.2 the *Owner* shall make payment to the *Contractor* on account as provided in Article A-5 PAYMENT, |

| | | |
|---|---|---|
| | | (a) in the amount stated in the certificate for payment, or<br><br>(b) in the amount stated in the certificate for payment less such amount stated in the *Owner's Notice of Non-Payment* issued pursuant to GC 5.3.3,<br><br>on the 28th calendar day after receipt of a *Proper Invoice*, unless such 28th calendar day lands on a day that is other than a *Working Day*, in which case payment shall be made on the next *Working Day* after such 28th day." |
| | 5.3.2 to 5.3.7 | Add new paragraphs 5.3.2, 5.3.3, 5.3.4, 5.3.4, 5.3.5, 5.3.6, and 5.3.7 as follows:<br><br>5.3.2 All payments to the *Contractor* shall be processed using electronic funds transfer ("**EFT**") and deposited directly to the *Contractor's* bank account unless agreed to otherwise by the *Contractor* and the *Owner* in writing. Prior to the *Contractor* submitting its first application for payment, the *Owner* and the *Contractor* shall exchange such information as is necessary to facilitate *EFT* payments.<br><br>5.3.3 In the event that the application for payment delivered by the *Contractor* pursuant to GC 5.2 - APPLICATIONS FOR PAYMENT does not include the requirements for a *Proper Invoice* or where the *Owner* disputes the amount claimed as payable in the *Proper Invoice*, then the *Owner* shall within 14 calendar days of receipt of the application for payment, issue a *Notice of Non-Payment* (Form 1.1).<br><br>5.3.4 Where the *Owner* has delivered a *Notice of Non-Payment*, the *Owner* and the *Contractor* shall first engage in good faith negotiations to resolve the dispute. If within 5 calendar days following the issuance of a *Notice of Non-Payment*, despite good faith efforts by both parties and the assistance of the *Consultant*, the *Owner* and the *Contractor* cannot resolve the dispute, either party may commence an *Adjudication* in accordance with the procedures set out in the *Construction Act.* Any portion of the *Proper Invoice* which is not the subject of the *Notice of Non-Payment* shall be payable within the time period set out in GC 5.3.1.2.<br><br>5.3.5 Provided that the *Owner* complies with its obligations under the *Construction Act*, and subject to any interim determination of an adjudicator in accordance with any *Adjudication*, and where applicable, a final determination made in accordance with the dispute resolution |

| | | |
|---|---|---|
| | | processes prescribed by this *Contract*, the *Owner* shall be entitled to claim in a *Notice of Non-Payment* a right to deduct from or, set off against, any payment of the *Contract Price*:<br><br>.1 any amount expended by the *Owner* in exercising the *Owner's* rights under this *Contract* to perform any of the *Contractor's* obligations that the *Contractor* has failed to perform;<br><br>.2 any damages, costs or expenses (including, without limitation, reasonable legal fees and expenses) incurred by the *Owner* as a result of the failure of the *Contractor* to perform any of its obligations under the *Contract*;<br><br>.3 any other amount owing from the *Contractor* to the *Owner* under this *Contract*.<br><br>5.3.6 The amounts disputed and described under the *Notice of Non-Payment* shall be held by the *Owner* until all disputed amounts of the *Proper Invoice* have been resolved pursuant to PART 8 – DISPUTE RESOLUTION.<br><br>5.3.7 The *Contractor* represents, warrants, and covenants to the *Owner* that it is familiar with its prompt payment and trust obligations under the *Construction Act* and will take all required steps and measures to ensure that it complies with the applicable prompt payment and trust provisions under the *Construction Act* including, without limitation, section 8.1 of the *Construction Act*. Evidence of the *Contractor's* compliance under this GC 5.3.7, including evidence demonstrating that all *EFTs* by the *Owner* to the *Contractor* are kept in a bank account in the *Contractor's* name will be made available to the *Owner* within 5 *Working Days* following receipt by the *Contractor* of a *Notice in Writing* making such request." |

**GC 5.4 SUBSTANTIAL PERFORMANCE OF THE WORK- AND PAYMENT OF HOLDBACK**

| | | |
|---|---|---|
| SC32.1 | GC 5.4 | Delete GC 5.4 – SUBSTANTIAL PERFORMANCE OF THE WORK AND PAYMENT OF HOLDBACK in its entirety and replace it with the following:<br><br>"**GC 5.4 SUBSTANTIAL PERFORMANCE OF THE WORK AND PAYMENT OF HOLDBACK**<br><br>5.4.1 When the *Contractor* considers that *Substantial Performance of the Work* has been achieved, the *Contractor* shall prepare and submit to the *Consultant* and the *Owner* a comprehensive deficiency list of items to be completed or corrected, including any incomplete *Close-Out Documentation*, and apply for a review by the *Consultant* and the *Owner* to establish *Substantial Performance of the Work*. Failure to include an item on the list does not alter the responsibility of the *Contractor* to complete the *Contract*.<br><br>5.4.2 Prior to, or as part of its written application for *Substantial Performance of the Work* the *Contractor* shall submit to the *Consultant* submit to the *Consultant* all closeout documentation required by the *Contract Documents*, including but not limited to, warranties, manuals, guarantees, as-built drawings, warranty cards and all other relevant literature from suppliers and manufacturers including, but not limited to, where applicable |

(the "**Close-Out Documentation**"):

.1 equipment, maintenance, and operations manuals;
.2 equipment specifications, data sheets and brochures, parts lists and assembly drawings, performance curves and other related data;
.3 line drawings, value charts and control sheets sequences with description of the sequence of operations;
.4 warranty documents;
.5 guarantees;
.6 certificates;
.7 service and maintenance reports;
.8 *Specifications*;
.9 *Shop Drawings*;
.10 coordination drawings;
.11 testing and balancing results and reports;
.12 *Commissioning* and quality assurance documentation;
.13 distribution system diagrams;
.14 spare parts;
.15 samples;
.16 existing reports and correspondence from authorities having jurisdiction in the *Place of the Work*;
.17 inspection certificates;
.18 red-lined record drawings from the construction trailer in two copies and
.19 other materials or documentation required to be submitted under the *Contract.*

5.4.3 The *Consultant* will review the *Work* to verify the validity of the application and shall promptly, and in any event, no later than 30 calendar days after receipt of the *Contractor's* complete deficiency list and application:

.1 prepare a final deficiency list incorporating all items to be completed or corrected, including any incomplete or unsubmitted *Close-Out Documentation*. Each item shall have an indicated value for correction or completion and the determination of the total value of such items shall be determined pursuant to GC 5.8 – DEFICIENCY HOLDBACK. The final deficiency list complete with values is to be included with the *Consultant's* draft verification and shall be reviewed with the *Owner* prior to the *Consultant* rendering a determination in accordance with GC 5.4.3.2

.2 having completed the requirements set out in GC 5.4.3.1,

(a) the *Consultant* shall advise the *Contractor* in writing that the *Work* or the designated portion of the *Work* is not substantially performed and give reasons why, or

(b) the *Consultant* shall state the date of *Substantial Performance of the Work* in a certificate and issue a copy of that certificate to each the *Owner* and the *Contractor.*

5.4.4 Following the issuance of the certificate of *Substantial Performance of the Work* referenced in subparagraph 5.4.3.2(b):

| | | |
|---|---|---|
| | | .1 The Contractor shall publish, in a construction trade newspaper in the area of the location of the Work, a copy of the certificate of S*ubstantial Performance of the Work* referred to in GC 5.4.2.2(b) within seven (7) calendar days of receiving a copy of the certificate signed by the *Consultant*, and the *Contractor* shall provide suitable evidence of the publication to the *Consultant* and the *Owner*. If the Contractor fails to publish such notice, the Owner shall be at liberty to publish said certificate and back-charge the Contractor its reasonable costs for doing so;<br><br>.2 The *Contractor* shall complete the *Work* within forty (40) calendar days of the date certified as the date of *Substantial Performance of the Work*;<br><br>.3 Notwithstanding any other provisions of the *Contract,* no payments will be processed between *Substantial Performance of the Work* and *Ready-for-Takeover*;<br><br>.4 The *Owner* reserves the right to contract out any or all unfinished *Work* if it has not been completed within forty (40) days of *Substantial Performance of the Work* using, without limitation, the funds retained in accordance with GC 5.8 - DEFICIENCY HOLDBACK, without prejudice to any other right or remedy and without affecting the warranty period. The cost to the *Owner* of completing the *Work* including *Owner* and *Consultant* wages and materials shall be deducted from the *Contract Price.*<br><br>5.4.5 After publication of the certificate of the *Substantial Performance of the Work*, and provided that the *Contractor* has completed performance of the *Work* within the 40 calendar days following certification of *Substantial Performance of the Work*, the *Contractor* may submit an application for payment of the outstanding *Construction Act* holdback amount, which application for payment shall:<br><br>.1 include all of the requirements listed in EXHIBIT "1" - PROJECT SPECIFIC REQUIREMENTS FOR A PROPER INVOICE, as applicable to the application for payment of the holdback amount; and<br><br>.2 include a statement that the *Contractor* has not received any written notices of lien or any claims for liens from any *Subcontractor* or *Supplier.*<br><br>5.4.6 The *Construction Act* holdback amount shall become due and payable the day immediately following the expiration of the holdback period prescribed by the *Construction Act* (in most cases being the 61st calendar day following the publication of the certificate of *Substantial Performance of the Work* referred to in GC 5.4.4.1), subject to the occurrence of any of the following:<br><br>.1 the preservation of a lien in respect of the *Project* that has not been satisfied, discharged or otherwise provided for in accordance with the *Construction Act*;<br><br>.2 receipt by the *Owner* of a written notice of lien that has not been satisfied, discharged or otherwise provided for in accordance with the *Construction Act*; or<br><br>.3 prior to the expiry of 40 calendar days following the publication of the certificate of *Substantial Performance of the Work,* the *Owner* publishes a *Notice of Non-Payment* of holdback in accordance with the *Construction Act* (Form 6)*,* setting out the amount of holdback that will not be paid, which may include non-payment to secure the correction of deficiencies and/or the completion of the *Work*. |

| | | |
|---|---|---|
| | | 5.4.7 Notwithstanding the *Owner's* obligation to make payment of the holdback amount in accordance with GC 5.4.6, the processing of such payment remains subject to the *Owner's* internal *EFT* timing limitations. The *Owner* covenants, and the *Contractor* agrees, that payment of the holdback shall be made by *EFT* at the first opportunity during the *Owner's* normal processing of *EFTs* upon the holdback becoming due in accordance with GC 5.4.6.. |

**GC 5.5 FINAL PAYMENT**

| | | |
|---|---|---|
| SC35.1 | GC 5.5 | Delete GC 5.5 in its entirety, including all subparagraphs thereunder and replace it with the following:<br><br>"5.5.1 When *Ready-for-Takeover* has been achieved in accordance with GC 12.1 – READY-FOR-TAKEOVER and the *Contractor* considers the *Work* is complete, and after the *Contractor*, the *Owner*, and the *Consultant* have attended a *Pre-Invoice Submission Meeting* analogous to the requirement in GC 5.2.1 (the "***Final Pre-Invoice Submission Meeting***"), the *Contractor* may submit an application for final payment to the *Owner* and to the *Consultant*, which application for payment shall:<br><br>.1 include all of the requirements set out in GC 5.2.2, including without limitation those requirements listed in APPENDIX "1" - PROJECT SPECIFIC REQUIREMENTS FOR A PROPER INVOICE that are specific to an application for final payment; and<br><br>.2 if applicable, (a) a certificate from the *Consultant* or written confirmation from the *Owner* that the deficiencies or incomplete *Work* waived by the *Owner* pursuant to GC 12.1.2 have been fully rectified as of the date of the *Contractor's* application for final payment, and/or (b) written confirmation, signed by the *Owner* and the *Contractor,* that the *Contract Price* has been reduced by a specified amount in exchange for the *Owner* releasing the *Contractor* of its obligation to rectify the certain outstanding deficiencies and/or incomplete *Work* waived by the *Owner* pursuant to GC 12.1.2, as detailed in such written confirmation.<br><br>5.5.2 No later than 5 calendar days prior to the *Final Pre-Invoice Submission Meeting*, the *Contractor* will, if not already provided, submit to the *Consultant* all *Close-Out Documentation*.<br><br>5.5.3 Delivery of all *Close-Out Documentation* is a requirement for the *Proper Invoice* for final payment.<br><br>5.5.4 After receipt by the *Owner* and the *Consultant* of an application for payment submitted by the *Contractor* that is a *Proper Invoice* and by no later than 10 calendar days after the receipt of the *Proper Invoice*:<br><br>.1 the *Consultant* will either:<br><br>(a) issue to the *Owner* with a copy to the *Contractor*, a progress payment certificate in the amount applied for by the *Contractor* in the *Proper Invoice*, or |

(b) deliver a finding to the *Owner* with reasons why an amount other than what is claimed in the *Proper Invoice* is properly due to the *Contractor*, which finding the *Owner* may accept or amend prior to issuing a *Notice of Non-Payment* (Form 1.1), if any, in accordance with GC 5.5.2;

.2 the *Owner* shall make payment to the *Contractor* on account as provided in Article A-5 PAYMENT,

(a) in the amount stated in the certificate for payment, or

(b) in the amount stated in the certificate for payment less such amount stated in the *Owner's Notice of Non-Payment* issued pursuant to GC 5.5.5,

on the 28th calendar day after receipt of a *Proper Invoice*, unless such 28th calendar day lands on a day that is other than a *Working Day*, in which case payment shall be made on the next *Working Day* after such 28th day.

5.5.5 In the event that the application for final payment delivered by the *Contractor* does not include the requirements of GC 5.5.1 (including the requirements for a *Proper Invoice*) and GC 5.5.2 or where the *Owner* disputes the amount claimed as payable in the *Proper Invoice*, then the *Owner* shall within 14 calendar days of receipt of the application for payment, issue a *Notice of Non-Payment*. Where the *Owner* has delivered a *Notice of Non-Payment*, as specified under this GC 5.5.5, the *Owner* and the *Contractor* shall first engage in good faith negotiations to resolve the dispute. If within 5 calendar days following the issuance of a *Notice of Non-Payment*, despite good faith efforts by both parties with the assistance of the *Consultant*, the *Owner* and the *Contractor* cannot resolve the dispute, either party may commence an *Adjudication* in accordance with the procedures set out in the *Construction Act*. Any portion of the *Proper Invoice* which is not the subject of the *Notice of Non-Payment* shall be payable within the time period set out in GC 5.5.4.2.

5.5.6 Subject to the provisions of the *Construction Act* and any other rights conferred on the *Owner* at law or under this *Contrac*t to withhold payment or back charge or set-off against payment, the *Owner* shall pay the amount payable under a *Proper Invoice* for final payment in accordance with the *Construction Act*.

5.5.7 When the *Consultant* issues a certificate of completion in accordance with GC 5.5.4.1, the *Consultant* shall also issue a certificate for release of any holdback for finishing work amount. In accordance with the *Construction Act,* the *Owner* may retain any amounts which are required by law to satisfy any liens against the *Work*, in respect of any third party claims made to the *Owner* in respect of the *Contract* or the *Work*, and in respect of any claims the *Owner* may have against the *Contractor*. Subject to the foregoing, the *Owner* shall release the holdback in accordance with the *Construction Act.*"

**GC 5.6 DEFERRED WORK**

| | | |
|---|---|---|
| SC33.1 | 5.6.1 | Delete paragraph 5.6.1 and replace with the following:<br><br>"5.6.1 If because of conditions reasonably beyond the control of the *Contractor*, there are items of work that cannot be performed, payment in full for that portion of the *Work* which has been performed as certified by the *Consultant* shall not be withheld or delayed by the *Owner* on account thereof, but the *Owner* may withhold, subject to its requirement to issue a *Notice of Non-Payment* under the *Construction Act*, until the remaining portion of the *Work* is finished, only such an amount that the *Consultant* determines is sufficient and reasonable to cover the cost of performing such remaining work. The remaining work shall be valued as deficient work as defined in GC 5.8.1." |

***NEW* GC 5.8 DEFICIENCY HOLDBACK**

| | | |
|---|---|---|
| SC34.1 | 5.8.1 | Add new GC 5.8 – DEFICIENCY HOLDBACK as follows:<br><br>"**GC 5.8 DEFICIENCY HOLDBACK**<br><br>5.8.1 Notwithstanding any provisions contained in the *Contract Documents* concerning certification and release of monies to the *Contractor*, the *Owner* reserves the right to retain a *Deficiency Holdback*, In addition to the Construction Act holdback. The *Deficiency Holdback* in the value of 2% shall be applied against the total Contract value and shall be applied to each progress payment. The *Deficiency Holdback* shall be payable to the Contractor upon the confirmation of completion of all deficiencies and defects in work by the Consultant and the Owner.<br><br>5.8.2 In performing the calculation under GC 5.8.1,<br><br>.1 no individual deficiency will be valued at less than five hundred dollars ($500.00); and<br><br>.2 for any *Close-Out Documentation* not submitted in advance of or as part of the *Contractor's* application for *Substantial Performance of the Work*, an amount shall be retained by the *Owner* as part of the deficiency holdback that is equal to the estimated time and material costs to retain a third-party to re-create the applicable *Close-Out Documentation*, as determined by the *Consultant*, until such time as the applicable *Close-Out Documentation* is submitted and approved.<br><br>5.8.3 The deficiency holdback shall be due and payable to the *Contractor* on the 61st day following completion of all of the deficiencies listed by the *Consultant* and confirmed to be corrected, there being no claims for lien registered against the title to the *Place of the Work* issued in accordance with the *Construction Act*, and less any amounts disputed under an *Owner*'s *Notice of Non-Payment* (Form 1.1)." |

**PART 6 CHANGES IN THE WORK**

**GC 6.1 OWNER'S RIGHT TO MAKE CHANGES**

| | | |
|---|---|---|
| SC37.1 | 6.1.2 | Add the following to the end of GC 6.1.2: |

| | | |
|---|---|---|
| | | "This requirement is of the essence and it is the express intention of the parties that any claims by the *Contractor* for a change in the *Contract Price* and/or *Contract Time* shall be barred unless there has been strict compliance with PART 6 - CHANGES IN THE WORK. No verbal dealings between the parties and no implied acceptance of alterations or additions to the *Work* and no claims that the *Owner* has been unjustly enriched by any alteration or addition to the *Work*, whether in fact there is any such unjust enrichment or not, shall be the basis of a claim for additional payment under this *Contract,* an increase to the *Contract Price*, or a claim for any extension of the *Contract Time*." |
| | 6.1.3 to 6.1.8 | Add new paragraphs 6.1.3, 6.1.4, 6.1.5, 6.1.6, 6.1.7 and 6.1.8 as follows:<br><br>"6.1.3 The *Contractor* agrees that changes resulting from construction coordination, including but not limited to, scheduling, site surface conditions, site coordination, and *Subcontractor and Supplier* coordination are included in the *Contract Price* and the *Contractor* shall be precluded from making any claim for a change in the *Contract Price* as a result of such changes.<br><br>6.1.4 Labour costs shall be actual, prevailing rates at the *Place of the Work* paid to workers, plus statutory charges on labour including WSIB, unemployment insurance, Canada pension, vacation pay, hospitalization and medical insurance. The *Contractor* shall provide these rates, when requested by the *Consultant*, for review and/or agreement.<br><br>6.1.5 Quotations for changes to the *Work* shall only include *Direct Costs* and be accompanied by itemized breakdowns together with detailed, substantiating quotations or cost vouchers from *Subcontractors* and *Suppliers,* submitted in a format acceptable to the *Consultant* and shall include any *Direct Costs* associated with extensions in *Contract Time.*<br><br>6.1.6 When both additions and deletions covering related *Work* or substitutions are involved in a change to the *Work*, payment, including *Overhead* and profit, shall be calculated on the basis of the net difference, if any, with respect to that change in the *Work*.<br><br>6.1.7 Changes to the contract shall be quoted to permit the work to be executed within the *Contract Time* unless approved by the *Consultant* and the *Owner.*<br><br>6.1.8 No extension to the *Contract Time* shall be granted for changes in the *Work* unless the *Contractor* can clearly demonstrate that such changes significantly alter the overall construction schedule submitted at the commencement of the *Work.* Extensions of *Contract Time* and all associated costs, if approved, shall be included in the relevant *Change Order*.<br><br>6.1.9 When a change in the *Work* is proposed or required, the *Contractor* shall within 10 calendar days submit to the *Consultant* for review a claim for a change in *Contract Price* and/or *Contract Time.* Should 10 calendar days be insufficient to prepare the submission, the *Contractor* shall within 5 calendar days, advise the *Consultant* in writing of the proposed date of submission of the claim. Claims submitted after the dates prescribed herein will not be considered." |

| | | |
|---|---|---|
| | | |

**GC 6.2 CHANGE ORDER**

| | | |
|---|---|---|
| SC38.1 | 6.2.1 | In paragraph 6.2.1 after the last sentence in the paragraph add the following:<br><br>"The adjustment in the *Contract Time* and the *Contract Price* shall include an adjustment, if any, for delay or for the impact that the change in the *Work* has on the *Work* of the *Contractor*, and once such adjustment is made, the *Contractor* shall be precluded from making any further claims for delay or impact with respect to the change in the *Work.*" |
| | 6.2.3 to 6.2.5 | Add new paragraphs 6.2.3, 6.2.4, and 6.2.5 as follows:<br><br>"6.2.3 The value of a change shall be determined in one or more of the following methods as directed by the *Consultant*:<br><br>.1 by estimate and acceptance of a lump sum;<br><br>.2 by negotiated unit prices which include the *Contractor's* overhead and profit, or;<br><br>.3 by the actual *Direct Cost* to the *Owner,* such costs to be the actual cost after all credits included in the change have been deducted, plus the following ranges of mark-up on such costs:<br><br>.1 Contractor on work of their own forces, 5% overhead, 5% profit.<br><br>.2 Subcontractor on work of their own forces, 5% overhead, 5 % profit<br><br>.3 Contractor on work of Subcontractor, 5% overhead only.<br><br>6.2.4 All quotations shall include *Direct Costs* and be submitted in a complete manner listing:<br><br>.1 quantity of each material,<br>.2 unit cost of each material,<br>.3 man hours involved,<br>.4 cost per hour,<br>.5 *Subcontractor* quotations submitted listing items 1 to 4 above and item 6 below.<br>.6 mark-up.<br><br>6.2.5 The *Owner* and the *Consultant* will not be responsible for delays to the *Work* resulting from late, incomplete or inadequately broken-down valuations submitted by the *Contractor.*" |
| | | |

**GC 6.3 CHANGE DIRECTIVE**

| | | |
|---|---|---|
| SC39.1 | 6.3.6.1 | Amend paragraph 6.3.6.1 by deleting the final period and adding the following:<br><br>".1 Contractors work by their own forces - 5% overhead and 5% profit, Subcontractor work by their own forces – 5% overhead and 5% profit, Contractors on Subcontractors work – 5% overhead only. |
| | 6.3.6.2 | Delete paragraph 6.3.6.2 and replace it with the following:<br><br>".2 If a change in the *Work* results in a net decrease in the *Contract Price*, the amount of the credit shall be the net cost, without deduction for *Overhead* or profit." |
| | 6.3.7.1(4) | Delete GC 6.3.7.1(4). |
| | 6.3.7.7 | Amend GC 6.3.7.7 by deleting the words "described in paragraph 6.3.7.1" and replacing them with "approved by the *Owner* in writing and in advance of any such expenses being incurred;" |
| | 6.3.7.9 | Amend GC 6.3.7.9 by adding the following to the end of the paragraph:<br><br>"…when specifically requested by the *Owner* or as directed by the *Consultant*;". |
| | 6.3.7.10 | Amend GC 6.3.7.10 by adding the following to the end of the paragraph:<br><br>", provided that such amounts are not caused by negligent acts, omissions, or default of the *Contractor* or *Subcontractor*;". |
| | 6.3.7.13 | Delete GC 6.3.7.13. |
| | 6.3.7.15 | Delete GC 6.3.7.15. |
| | 6.3.7.17 | Delete GC 6.3.7.17 in its entirety including all subparagraphs. |
| | 6.3.11 | Delete GC 6.3.11 and replace it with the following:<br><br>"6.3.11 The value of the *Work* performed as a result of a *Change Directive* shall not be eligible to be included in progress payments until the amount, including the method for determining the amount, of such *Change Directive* has been determined." |

**GC 6.4 CONCEALED OR UNKNOWN CONDITIONS**

| | | |
|---|---|---|
| SC40.1 | 6.4.1 | Delete paragraph 6.4.1 in its entirety and replace with the following:<br><br>"6.4.1.1 Prior to the submission of the bid on which the Contract was awarded, the Contractor confirms that it carefully investigated the Place of the Work insofar as the Place of Work |

| | | |
|---|---|---|
| | | was available for investigation and, in doing so, applied to that investigation the degree of care and skill required by paragraph 3.14.1<br><br>6.4.1.2 No claim by the *Contractor* will be considered by the *Owner* or the *Consultant* in connection with conditions which could reasonably have been ascertained by such investigation or other due diligence undertaken prior to the execution of the *Contract*. |
| | 6.4.2 | Amend paragraph 6.4.2 by adding a new first sentence as follows:<br><br>"Having regard to paragraph 6.4.1, if the *Contractor* believes that the conditions of the *Place of the Work* differ materially from those reasonably anticipated, differ materially from those indicated in the *Contract Documents* and were concealed from discovery notwithstanding the conduct of the investigation described in paragraph 6.4.1, it shall provide the *Owner* and the *Consultant* with *Notice in Writing* no later than five (5) *Working Days* after the first observation of such conditions."<br><br>-and-<br><br>amend the existing second sentence of paragraph 6.4.2 in the second line, following the word "materially" by adding the words "or were concealed from discovery notwithstanding the conduct of the investigation described in paragraph 6.4.1,". |
| | 6.4.3 | Delete paragraph 6.4.3 in its entirety and substitute the following:<br><br>"6.4.3 If the *Consultant* makes a finding pursuant to paragraph 6.4.2 that no change in the *Contract Price* or the *Contract Time* is justified, the *Consultant* shall report in writing the reasons for this finding to the *Owner* and the *Contractor*." |
| | 6.4.5 | Add new paragraph 6.4.5 as follows:<br><br>"6.4.5 No claims for additional compensation or for an extension of *Contract Time* shall be allowed if the *Contractor* fails to give *Notice in Writing* to the *Owner* or *Consultant,* as required by paragraph 6.4.2." |

**GC 6.5 DELAYS**

| | | |
|---|---|---|
| SC41.1 | 6.5.1 | In paragraph 6.5.1 delete the words after the word "for" in the fourth line and replace them with the words "…reasonable *Direct Costs* directly flowing from the delay, but excluding any consequential, indirect or special damages (including, without limitation, loss of profits, loss of opportunity or loss of productivity)." |
| | 6.5.2 | Delete GC 6.5.2 in its entirety and replace it with the following:<br><br>"6.5.2 If the *Contractor* is delayed in the performance of the *Work* by a stop work order issued by a court or other public authority and providing that such order was issued on account of a direct breach, violation, contravention, or a failure to abide by any laws, ordinances, rules, regulations, or codes by the *Owner*, *Other Contractor(s)*, or the *Consultant*, and relating to the *Work* or the *Place of the Work*, then the *Contract Time* shall be extended for such reasonable time as the *Consultant* may determine. The *Contractor* shall be reimbursed by |

| | | |
|---|---|---|
| | | the *Owner* for reasonable *Direct Costs* directly flowing from the delay, but excluding any consequential, indirect or special damages (including, without limitation, loss of profits, loss of opportunity or loss of productivity)." |
| | 6.5.3 | Delete paragraph 6.5.3 in its entirety and replace with the following:<br><br>"6.5.3 If either party is delayed in the performance of their obligations under this *Contract* by *Force Majeure*, then the *Contract Time* shall be extended for such reasonable time as the *Owner* and the *Contractor* shall agree. The extension of time shall not be less than the time lost as a result of the event causing the delay, unless the parties agree to a shorter extension. Neither party shall be entitled to payment for costs incurred by such delays. Upon reaching agreement on the extension of the *Contract Time* attributable to the *Force Majeure* event, the *Owner* and the *Contractor* shall execute a *Change Order* indicating the length of the extension to the *Contract Time* and confirming that there are no costs payable by the either party for the extension of *Contract Time*. However, if at the time an event of *Force Majeure* arises a party is in default of its obligations under the *Contract* and has received a notice of default pursuant to PART 7 – DEFAULT NOTICE, this paragraph 6.5.3 shall not excuse a party from its obligation to cure the default(s). For greater certainty, the defaulting party, to the extent possible, must continue to address and cure the default notwithstanding an event of *Force Majeure*." |
| | 6.5.4 | Delete paragraph 6.5.4 in its entirety and replace it with the following:<br><br>"6.5.4 No extension or compensation shall be made for delay or impact on the *Work* unless notice in writing of a claim is given to the *Consultant* not later than ten (10) *Working Days* after the commencement of the delays or impact on the *Work*, provided however, that, in the case of a continuing cause of delay or impact on the *Work*, only one notice of claim shall be necessary." |
| | 6.5.6 to 6.5.8 | Add new paragraphs 6.5.6, 6.5.7 and 6.5.8 as follows:<br><br>"6.5.6 If the *Contractor* is delayed in the performance of the *Work* by an act or omission of the *Contractor* or anyone directly or indirectly employed or engaged by the *Contractor,* or by any cause within the *Contractor's* control, then (i) firstly, at its expense, and to the extent possible, the *Contractor* shall accelerate the work and/or provide overtime work to recover time lost by a delay arising under this paragraph 6.5.6, and (ii) secondly, where it is not possible for the *Contractor* to recover the time lost by implementing acceleration measures and/or overtime work, the *Contract Time* may be extended for such reasonable time as the *Owner* may decide in consultation with the *Consultant* and the *Contractor*. The *Owner* shall be reimbursed by the *Contractor* for all reasonable costs incurred by the *Owner* as the result of such delay, including, but not limited to, Owner's staff costs, the cost of all additional services required by the *Owner* from the *Consultant* or any sub-consultants, project managers, or others employed or engaged by the *Owner*, and in particular, the costs of the *Consultant's* services during the period between the date of *Substantial Performance of the Work* stated in Article A-1 herein, as the same may be extended through the provision of |

| | | |
|---|---|---|
| | | these General Conditions, and any later or actual date of *Substantial Performance of the Work* achieved by the *Contractor*.<br><br>6.5.7 Without limiting the obligations of the *Contractor* described in GC 3.2 – CONSTRUCTION BY OWNER OR OTHER CONTRACTORS or GC 9.4 – CONSTRUCTION SAFETY, the *Owner* or *Consultant* may, by *Notice in Writing*, direct the *Contractor* to stop the *Work* where the *Owner* or *Consultant* determines that there is an imminent risk to the safety of persons or property at the *Place of the Work*. In the event that the *Contractor* receives such notice, it shall immediately stop the *Work* and secure the site. The *Contractor* shall not be entitled to an extension of the *Contract Time* or to an increase in the *Contract Price* unless the resulting delay, if any, would entitle the *Contractor* to an extension of the *Contact Time* or the reimbursement of the *Contractor's* costs as provided in paragraphs 6.5.1, 6.5.2 or 6.5.3.<br><br>6.5.8 No claim for delay shall be made by the *Contractor* and the *Contract Time* shall not be extended due to climatic conditions or arising from the *Contractor's* efforts to maintain the *Construction Schedule*." |

**PART 7 DEFAULT NOTICE**

**GC 7.1 OWNER'S RIGHT TO PERFORM THE WORK, TERMINATE THE CONTRACTOR'S RIGHT TO CONTINUE WITH THE WORK OR TERMINATE THE CONTRACT**

| | | |
|---|---|---|
| SC43.1 | 7.1.2 | In GC 7.1.2, delete the words "and if the *Consultant* has given a written statement to the *Owner* and *Contractor* which provides the detail of such neglect to perform the *Work* properly or such failure to comply with the requirements of the *Contract* to a substantial degree". |
| SC43.2 | 7.1.3.4 | Add a new subparagraph 7.1.3.4 as follows:<br><br>".4 an "acceptable schedule" as referred to in subparagraph 7.1.3.2. means a schedule approved by the *Consultant* and the *Owner* wherein the default can be corrected within the balance of the *Contract Time* and shall not cause delay to any other aspect of the *Work* or the work of other contractors, and in no event shall it be deemed to give a right to extend the *Contract Time*." |
| | 7.1.4.1 | Delete subparagraph 7.1.4.1 and replace it with the following:<br><br>".1 correct such default and deduct the cost, including *Owner's* expenses, thereof from any payment then or thereafter due the *Contractor*." |
| | 7.1.4.2 | Delete subparagraph 7.1.4.2 and replace it with the following:<br><br>".2 by providing *Notice in Writing* to the *Contractor*, terminate the *Contractor's* right to continue with the *Work* in whole or in part or terminate the *Contract*, and publish a notice of termination (Form 8) in accordance with the *Act*." |
| | 7.1.5.3 | In subparagraph 7.1.5.3 delete the words: "however, if such cost of finishing the *Work* is less than the unpaid balance of the *Contract Price*, the *Owner* shall pay the *Contractor* the difference" |
| | 7.1.6 to 7.1.10 | Delete GC 7.1.6 and replace it with new paragraphs 7.1.6, 7.1.7, 7.1.8, 7.1.9 and 7.1.10 as follows: |

| | | |
|---|---|---|
| | | "7.1.6 In addition to its right to terminate the *Contract* set out herein, the *Owner* may terminate this *Contract* at any time for any other reason and without cause upon giving the *Contractor* fifteen (15) *Working Days Notice in Writing* to that effect. In such event, the *Contractor* shall be entitled to be paid for all *Work* performed including reasonable profit, for loss sustained upon *Products* and *Construction Equipment*, and such other damages as the *Contractor* may have sustained as a result of the termination of the *Contract*, but in no event shall the *Contractor* be entitled to be compensated for any loss of profit on unperformed portions of the *Work*, or indirect, special, or consequential damages incurred.<br><br>7.1.7 The *Owner* may suspend *Work* under this *Contract* at any time for any reason and without cause upon giving the *Contractor Notice in Writing* to that effect. In such event, the *Contractor* shall be entitled to be paid for all *Work* performed to the date of suspension and be compensated for all actual costs incurred arising from the suspension, including reasonable profit, for loss sustained upon *Products* and *Construction Equipment*, and such other damages as the *Contractor* may have sustained as a result of the suspension of the *Work*, but in no event shall the *Contractor* be entitled to be compensated for any indirect, special, or consequential damages incurred. In the event that the suspension continues for more than thirty (30) calendar days, the *Contract* shall be deemed to be terminated and the provisions of paragraph 7.1.6 shall apply.<br><br>7.1.8 In the case of either a termination of the *Contract* or a suspension of the *Work* under GC 7.1 - OWNER'S RIGHT TO PERFORM THE WORK, TERMINATE THE CONTRACTOR'S RIGHT TO CONTINUE WITH THE WORK, OR TERMINATE THE CONTRACT or GC 7.2 - CONTRACTOR'S RIGHT TO SUSPEND THE WORK OR TERMINATE THE CONTRACT, the *Contractor* shall use its best commercial efforts to mitigate the financial consequences to the *Owner* arising out of the termination or suspension, as the case may be.<br><br>7.1.9 Upon the resumption of the *Work* following a suspension under GC 7.1 - OWNER'S RIGHT TO PERFORM THE WORK, TERMINATE THE CONTRACTOR'S RIGHT TO CONTINUE WITH THE WORK, OR TERMINATE THE CONTRACT or GC 7.2 - CONTRACTOR'S RIGHT TO SUSPEND THE WORK OR TERMINATE THE CONTRACT, the *Contractor* will endeavour to minimize the delay and financial consequences arising out of the suspension.<br><br>7.1.10 The *Contractor's* obligations under the *Contract* as to quality, correction, and warranty of the *Work* performed by the *Contractor* up to the time of termination or suspension shall continue after such termination of the *Contract* or suspension of the *Work*." |

**GC 7.2 CONTRACTOR'S RIGHT TO SUSPEND THE WORK OR TERMINATE THE CONTRACT**

| | | |
|---|---|---|
| SC44.1 | 7.2.2 | Delete paragraph 7.2.2 and replace it with the following:<br><br>"7.2.2 If the *Work* is suspended or otherwise delayed for a period of 40 consecutive *Working Days* or more under a stop work order issued by a court or other public authority on account of a breach, violation, contravention, or a failure to abide by any laws, ordinances, rules, regulations, or codes directly by the *Owner*, the *Owner's* other contractor(s), or the *Consultant*, and relating to the *Work* or the *Place of the Work*, the *Contractor* may, without |

| | | |
|---|---|---|
| | | prejudice to any other right or remedy the *Contractor* may have, terminate the *Contract* by giving the *Owner* Notice in *Writing* to that effect." |
| SC44.2 | 7.2.3.1 | Delete subparagraph 7.2.3.1 in its entirety. |
| | 7.2.3.2 | Delete subparagraph 7.2.3.2 in its entirety. |
| | 7.2.3.4 | In subparagraph 7.2.3.4, delete the words "except for GC 5.1 - FINANCING INFORMATION REQUIRED OF THE OWNER". |
| | 7.2.5 | Delete paragraph 7.2.5 and replace it with the following:<br>"7.2.5 If the default cannot be corrected within the 5 *Working Days* specified in paragraph 7.2.4, the *Owner* shall be deemed to have cured the default if it:<br>.1 commences correction of the default within the specified time;<br>.2 provides the *Contractor* with an acceptable schedule for such correction; and,<br>.3 completes the correction in accordance with such schedule." |
| | 7.2.6 to 7.2.9 | Add new paragraphs 7.2.6, 7.2.7, 7.2.8 and 7.2.9 as follows:<br>"7.2.6 If the *Contractor* terminates the *Contract* under the conditions described in GC 7.2 – CONTRACTOR'S RIGHT TO SUSPEND THE WORK OR TERMINATE THE CONTRACT, the *Contractor* shall be entitled to be paid for all *Work* performed to the date of termination, as determined by the *Consultant*. The *Contractor* shall also be entitled to recover the direct costs associated with termination, including the costs of demobilization and losses sustained on *Products* and *Construction Equipment*. The *Contractor* shall not be entitled to any recovery for any special, indirect or consequential losses, including loss of profit.<br>7.2.7 The *Contractor* shall not be entitled to give notice of the *Owner's* default or terminate the *Contract* in the event the *Owner* withholds certificates or payment or both in accordance with the *Contract* because of:<br>.1 the *Contractor's* failure to pay all legitimate claims promptly, or<br>.2 the failure of the *Contractor* to discharge construction liens which are registered against the title to the *Place of the Work.*<br>7.2.8 The *Contractor's* obligations under the *Contract* as to quality, correction and warranty of the *Work* performed by the *Contractor* up to the effective date of termination shall continue in force and shall survive termination of this *Contract* by the *Contractor*.<br>7.2.9 If the *Contractor* suspends the *Work* or terminates the *Contract* as provided for in GC 7.2 – CONTRACTOR'S RIGHT TO SUSPEND THE WORK OR TERMINATE THE CONTRACT, the *Contractor* shall ensure the site and the *Work* are left in a safe, secure condition as required by authorities having jurisdiction at the *Place of the Work* and the *Contract Documents*." |

**PART 8 DISPUTE RESOLUTION**

**GC 8.1 AUTHORITY OF THE CONSULTANT**

| | | |
|---|---|---|
| SC45.1 | 8.1.3 | Delete paragraph 8.1.3 in its entirety and substitute as follows:<br><br>"8.1.3 If a dispute is not resolved promptly, the *Consultant* will give such instruction as in the *Consultant's* opinion are necessary for the proper performance of the *Work* and to prevent delays pending settlement of the dispute. The parties shall act immediately according to such instructions, it being understood that by doing so neither party will jeopardize any claim the party may have." |

**GC 8.2 ADJUDICATION**

| | | |
|---|---|---|
| SC45.2 | 8.2.2 to 8.2.7 | Add new GC 8.2.2, 8.2.3, 8.2.4, 8.2.5, 8.2.6, and 8.2.7 as follows:<br>"8.2.2 Save and except where the *Contractor* has given an undertaking, in accordance with the *Act*, to refer a dispute to *Adjudication*, prior to delivering a notice of *Adjudication* in a form prescribed by the *Act*, the parties agree to first address all disputes with at least one in-person meeting with the *Owner's* representative, the *Consultant's* representative, and the *Contractor's* representative. The parties agree that such steps will be taken to resolve any disputes in a timely and cost-effective manner.<br>8.2.3 Notwithstanding any other provisions in PART 8 DISPUTE RESOLUTION, the parties shall engage in *Adjudication* proceedings as required by, and in accordance with, the *Construction Act*.<br>8.2.4 The following procedures shall apply to any *Adjudication* the parties engage in under the *Construction Act*:<br><br>.1 any hearings shall be held at a venue within the jurisdiction of the *Place of the Work* or such other venue as the parties may agree and which is acceptable to the adjudicator;<br><br>.2 the *Adjudication* shall be conducted in English;<br>.3 each party may be represented by counsel throughout an *Adjudication*;<br>.4 there shall not be any oral communications with respect to issues in dispute that are the subject of an *Adjudication* between a party and the adjudicator unless it is made in the presence of both parties or their legal representatives; and<br>.5 a copy of all written communications between the adjudicator and a party shall be given to the other party at the same time.<br>8.2.5 Any documents or information disclosed by the parties during an *Adjudication* are confidential and the parties shall not use such documents or information for any purpose other than the *Adjudication* in which they are disclosed and shall not disclose such documents and information to any third party, unless otherwise required by law, save and except the for the adjudicator.<br>8.2.6 If the *Contractor* fails to comply with any of the notice requirements set out in the *Contract*, including the time limits set out in any of the following:<br><br>.1 GC 6.4 – CONCEALED OR UNKNOWN CONDITIONS;<br>.2 GC 6.5 – DELAYS;<br>.3 GC 6.6 – CLAIMS FOR A CHANGE IN CONTRACT PRICE;<br>.4 PART 8 DISPUTE RESOLUTION |

| | | |
|---|---|---|
| | | .5 GC 9.2 – TOXIC AND HAZARDOUS SUBSTANCES<br>.6 GC 9.3 – ARTIFACTS AND FOSSILS; or<br>.7 GC 9.5 - MOULD<br><br>in respect of any claim or dispute, the *Contractor* shall have no entitlement whatsoever (including to an increase in the *Contract Price*, or an extension of *Contract Time*) in the context of an *Adjudication* under the *Construction Act* and waives the right to make any such claims or disputes in an *Adjudication*. This GC 8.2.6 shall operate conclusively as an estoppel and bar in the event such claims or disputes are brought in an *Adjudication* and the *Owner* may rely on this GC 8.2.6 as a complete defence to any such claims or disputes.<br><br>8.2.7 The parties hereby acknowledge and agree,<br><br>.1 that counterclaims, claims of set-off or the exercise or use of other contractual rights that permit the *Owner* to withhold, deduct or retain from monies otherwise owed to the *Contractor* under the *Contract* may be referred to, and included as part of, *Adjudications* under the *Construction Act*;<br>.2 that disputes related to the termination or abandonment of the *Contract*, as well as any disputes that arise or are advanced following the termination or abandonment of the *Contract*, shall not be referred to *Adjudication* under the *Construction Act*;<br>.3 that notice(s) of *Adjudication,* with respect to any dispute or claim relating to the *Project,* shall not be given, and no *Adjudication* shall be commenced following *Contract* completion, *Contract* abandonment, or termination of the *Contract*;<br>.4 that any *Adjudication* between the *Contractor* and a *Subcontractor* or a supplier that relates to an *Adjudication* between the *Owner* and the *Contractor* shall be joined together to be adjudicated by a single adjudicator, provided that the adjudicator agrees to do so, and the *Contractor* shall include a provision in each of its contracts that contain an equivalent obligation to this GC 8.2.7.4; and<br>.5 that, other than where the *Contractor* is obliged to commence an *Adjudication* pursuant to an undertaking under the *Construction Act,* neither the *Owner* nor the *Contractor* shall commence an *Adjudication* during the *Restricted Period*.<br><br>8.2.8 The parties acknowledge and agree that no *Adjudication*, arbitration, action, suit or other proceeding may be brought by the *Contractor* against the *Owner* in respect of a claim for an increase to the *Contract Price* as set out in GC 6.6, before the *Consultant* has issued its findings in respect of same, pursuant to GC 6.6.5. For greater clarity and without limiting the foregoing, the amount applied for in each *Proper Invoice* shall not include any amounts pertaining to the *Contractor's* claim for an increase in *Contract Price* unless and until the *Consultant* has issued a written notice to the *Contractor* regarding the validity of such claim, as provided for in GC 6.6.5. However, nothing in this GC 8.2.8 shall prevent a *Contractor* from commencing an *Adjudicatio*n where, pursuant to the *Construction Act*, the *Contractor* is required to give an undertaking to a *Subcontractor* to commence an *Adjudication* following delivery of a *Notice of Non-Payment*." |

**GC 8.3 NEGOTIATION, MEDIATION AND ARBITRATION**

| | | |
|---|---|---|
| SC46.1 | 8.3.1 | Amend paragraph 8.3.1 by changing part of the second line from "shall appoint a *Project Mediator*" to "may appoint a *Project Mediator,* except that such an appointment shall only be made if both the *Owner* and the *Contractor* agree." |
| | 8.3.4 | Amend paragraph 8.3.4 by changing part of the second line from "the parties shall request the *Project Mediator"* to "and subject to paragraph 8.3.1 the parties may request the *Project Mediator".* |
| | 8.3.6 to 8.3.9 | Delete paragraphs 8.3.6, 8.3.7 and 8.3.8 in their entirety and replace them with the following new GCs 8.3.6, 8.3.7, 8.3.8, and 8.3.9:<br>"8.3.6 The dispute may be finally resolved by arbitration under the Rules for Arbitration of Construction Disputes as provided in CCDC 40 in effect at the time of bid closing, provided that both the *Contractor* and the *Owner* agree. If the *Contractor* and the *Owner* agree to resolve the dispute by arbitration, the arbitration shall be conducted in the jurisdiction of the *Place of the Work*.<br>8.3.7 Prior to delivering a notice of *Adjudication* in a form prescribed by the *Act*, the parties agree to first address all disputes by attending at least one meeting with the *Owner*'s representative, the *Consultant*'s representative, and the *Contractor*'s representative, prior to commencing an *Adjudication*. The parties agree that such steps will be taken to resolve any disputes in a timely and cost effective manner. If a resolution to the dispute(s) is not made at such a meeting, any party who plans to commence an *Adjudication* shall provide the other party with 5 *Working Days' Notice in Writing* of its intention to issue a notice of *Adjudication*.<br>8.3.8 Other than where the *Contractor* is obliged to commence an *Adjudication* pursuant to an undertaking under the *Construction Act*, neither the *Owner* nor the *Contractor* shall commence an *Adjudication* during the *Restricted Period*.<br>8.3.9 Where either party has delivered a notice of *Adjudication* in a form prescribed by the *Act*, the procedures and rules set out under the *Construction Act* and the regulations thereto shall govern the *Adjudication*." |

**PART 9 PROTECTION OF PERSONS AND PROPERTY**

**GC 9.1 PROTECTION OF WORK AND PROPERTY**

| | | |
|---|---|---|
| SC47.1 | 9.1.1.1 | Delete subparagraph 9.1.1.1 in its entirety and substitute the following:<br>".1 errors in the *Contract Documents* which the *Contractor* could not have discovered applying the standard of care described in paragraph 3.14.1;" |
| | 9.1.2 | Delete paragraph 9.1.2 in its entirety and substitute as follows:<br>"9.1.2 Before commencing any *Work*, the *Contractor* shall determine the locations of all underground or hidden utilities and structures indicated in or inferable from the *Contract Documents*, or that are inferable from an inspection of the *Place of the Work* exercising the degree of care and skill described in paragraph 3.14.1." |
| | 9.1.5 | Add new paragraph 9.1.5 as follows:<br>"9.1.5 With respect to any damage to which paragraphs 9.1.3 or 9.1.4 apply, the *Contractor* shall neither undertake to repair or replace any damage whatsoever to the work of other |

| | | |
|---|---|---|
| | | contractors, or to adjoining property, nor acknowledge that the same was caused or occasioned by the *Contractor*, without first consulting the *Owner* and receiving written instructions as to the course of action to be followed from either the *Owner* or the *Consultant*. Where, however, there is danger to life, the environment, or public safety, the *Contractor* shall take such emergency action as it deems necessary to remove the danger." |

**GC 9.2 TOXIC AND HAZARDOUS SUBSTANCES**

| | | |
|---|---|---|
| SC48.1 | 9.2.1 | Amend GC 9.2.1 by inserting the following to the end of the paragraph:<br><br>"For the purposes of GC 9.2 – TOXIC AND HAZARDOUS SUBSTANCES, *Excess Soil* shall not be considered a 'toxic and hazardous substance'." |
| SC48.2 | 9.2.5.5 | Add a new subparagraph 9.2.5.5 as follows:<br><br>".5 in addition to the steps described in subparagraph 9.2.5.3, take any further steps it deems necessary to mitigate or stabilize any conditions resulting from encountering toxic or hazardous substances or materials." |
| | 9.2.6 | Amend GC 9.2.6 by adding the following words after the word "responsible" in the second line:<br><br>"or whether any toxic or hazardous substances or materials already at the *Place of the Work* (and which were then harmless or stored, contained or otherwise dealt with in accordance with legal and regulatory requirements) were dealt with by the *Contractor* or anyone for whom the *Contractor* is responsible in a manner which does not comply with legal and regulatory requirements, or which threatens human health and safety or the environment, or material damages to the property of the *Owner* or others,". |
| | 9.2.8 | Amend GC 9.2.8 by adding the following words after the word "responsible" in the second line:<br><br>"or whether any toxic or hazardous substances or materials already at the *Place of the Work* (and which were then harmless or stored, contained or otherwise dealt with in accordance with legal and regulatory requirements) were dealt with by the *Contractor* or anyone for whom the *Contractor* is responsible in a manner which does not comply with legal and regulatory requirements, or which threatens human health and safety or the environment, or material damages to the property of the *Owner* or others,". |
| | 9.2.10 | Add new paragraph 9.2.10 as follows:<br><br>"9.2.10 The *Contractor*, *Subcontractors* and *Suppliers* shall not bring on to the *Place of the Work* any toxic or hazardous substances and materials except as required in order to perform the *Work*. If such toxic or hazardous substances or materials are required, storage in quantities sufficient to allow work to proceed to the end of any current work week only shall be permitted. All such toxic and hazardous materials and substances shall be |

| | | |
|---|---|---|
| | | handled and disposed of only in accordance with all laws and regulations that are applicable at the *Place of the Work*." |

**GC 9.4 CONSTRUCTION SAFETY**

| | | |
|---|---|---|
| SC49.1 | 9.4.1 | Delete GC 9.4.1 in its entirety and replace it with the following:<br><br>"9.4.1 The *Contractor* shall be solely responsible for construction safety at the *Place of the Work* and for compliance with the rules, regulations, and practices required by the *OHSA*, including, but not limited to those of the "constructor", and shall be responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the performance of the *Work*. The *Contractor*'s health and safety program documentation shall be made available for review by the *Owner* or *Consultant* immediately upon request. Without limiting the foregoing, the *Contractor* shall be solely responsible for construction safety in respect of the *Consultant*, *Subcontractors* and *Suppliers*, the *Owner's* own forces, *Other Contractors*, and all persons attending the *Place of the Work* during the course of the *Project*." |
| | 9.4.2 | Amend GC 9.4.2 by adding the following words after "and the *Contractor*":<br><br>", *Subcontractors* and *Suppliers*". |
| | 9.4.3 | Amend GC 9.4.3 by adding the following words after "and the *Contractor*":<br><br>", *Subcontractors* and *Suppliers*". |
| | 9.4.4 | Delete GC 9.4.4 and replace it with the following:<br><br>"9.4.4 The *Owner* undertakes to include in its contracts with other contractors and in its instructions to its own forces the requirement that the other contractor or its own forces, as the case may be, comply with the policies and procedures of and the directions and instructions from the *Contractor* with respect to occupational health and safety and related matters." |
| | 9.4.5 | Delete GC 9.4.5 in its entirety and replace it with the following:<br><br>"9.4.5 Prior to the commencement of the *Work*, the *Contractor* shall submit to the *Owner*:<br><br>.1 a current WSIB clearance certificate;<br>.2 copies of the *Contractor*'s insurance policies having application to the *Project* or certificates of insurance, at the option of the *Owner*;<br>.3 documentation setting out the *Contractor*'s in-house safety programs;<br>.4 a copy of the Notice of Project filed with the Ministry of Labour naming itself as "constructor" under the *OHSA*; and |

| | | |
|---|---|---|
| | | . 5 copies of any documentation or notices to be filed or delivered to the authorities having jurisdiction for the regulation of occupational health and safety at the *Place of the Work*;" |
| | 9.4.6 to 9.4.12 | Add new GC 9.4.6, 9.4.7, 9.4.8, 9.4.9, 9.4.10, 9.4.11, and 9.4.12 as follows:<br><br>"9.4.6 The *Contractor* shall indemnify and save harmless the *Owner*, its agents, trustees, officers, directors, employees, consultants, successors, appointees, and assigns from and against the consequences of any and all safety infractions committed by the *Contractor* under *OHSA* and any other occupational health and safety legislation in force at the *Place of the Work* including the payment of legal fees and disbursements on a solicitor and client basis. Such indemnity shall apply to the extent to which the *Owner* is not covered by insurance.<br><br>9.4.7 If the *Owner* is of the reasonable opinion that the *Contractor* has not taken such precautions as are necessary to ensure compliance with the requirements of paragraph 9.4.1, the *Owner* may take any remedial measures which it deems necessary, including stopping the performance of all or any portion of the *Work,* and the *Owner* may use its employees, the *Contractor*, any *Subcontractor* or any other contractors to perform such remedial measures.<br><br>9.4.8 The *Contractor* shall file any notices or any similar document required pursuant to the *Contract* or the safety regulations in force at the *Place of the Work*. This duty of the *Contractor* will be considered to be included in the *Work* and no separate payment therefore will be made to the *Contractor*.<br><br>9.4.9 Unless otherwise provided in the *Contract Documents*, the *Contractor* shall develop, maintain and supervise for the duration of the *Work* a comprehensive safety program that will effectively incorporate and implement all required safety precautions. The program shall, at a minimum, respond fully to the applicable safety regulations and general construction practices for the safety of persons or property, including, without limitation, any general safety rules and regulations of the *Owner* and any workers' compensation or occupational health and safety statutes or regulations in force at the *Place of the Work*.<br><br>9.4.10 The *Contractor* shall provide a copy of the safety program described in GC 9.4.9 hereof to the *Consultant* for delivery to the *Owner* prior to the commencement of the *Work*, and shall, ensure, as far as it is reasonably practical to do so, that every employer and worker performing work in respect of the *Project* complies with such program.<br><br>9.4.11 The *Contractor* shall arrange regular safety meetings, and shall supply and maintain, at its own expense, at its office or other well-known place at the job site, safety equipment necessary to protect the workers and general public against accident or injury as prescribed by the authorities having jurisdiction at the *Place of the Work*, including, without limitation, articles necessary for administering first-aid to any person and an emergency procedure for the immediate removal of any injured person to a hospital or a doctor's care.<br><br>9.4.12 The *Contractor* shall promptly report in writing to the *Owner* and the *Consultant* all accidents of any sort arising out of or in connection with the performance of the *Work*, whether on or adjacent to the job site, giving full details and statement of witnesses. If death or serious injuries or damages are caused, the accident shall be promptly reported |

| | | |
|---|---|---|
| | | by the *Contractor* to the *Owner* and the *Consultant* by telephone or messenger in addition to any reporting required under the applicable safety regulations.”.” |

**PART 10 GOVERNING REGULATIONS**

**GC 10.1 TAXES AND DUTIES**

| | | |
|---|---|---|
| SC50.1 | 10.1.2 | Amend paragraph 10.1.2 by adding the following sentence to the end of the paragraph:<br><br>“For greater certainty, the *Contractor* shall not be entitled to any mark-up for overhead or profit on any increase in such taxes and duties and the *Owner* shall not be entitled to any credit relating to mark-up for overhead or profit on any decrease in such taxes. The *Contractor* shall provide a detailed breakdown of Additional taxes if requested by the *Owner* in a form satisfactory to the *Owner*.” |
| | 10.1.3 | Add new paragraph 10.1.3 as follows:<br>“10.1.3 Where the *Owner* is entitled to an exemption or a recovery of sales taxes, customs duties, excise taxes or *Value Added Taxes* applicable to the *Contract*, the *Contractor* shall, at the request of the *Owner*, assist with the application for any exemption, recovery or refund of all such taxes and duties and all amounts recovered or exemptions obtained shall be for the sole benefit of the *Owner*. The *Contractor* agrees to endorse over to the *Owner* any cheques received from the federal or provincial governments, or any other taxing authority, as may be required to give effect to this paragraph.” |

**GC 10.2 LAWS, NOTICES, PERMITS, AND FEES**

| | | |
|---|---|---|
| SC51.1 | 10.2.5 | Amend paragraph 10.2.5 by adding the words “Subject to paragraph 3.4” at the beginning of the paragraph.<br><br>-and-<br><br>Add the following to the end of the second sentence:<br><br>“…and no further *Work* on the affected components of the *Contract* shall proceed until these directives have been obtained by the *Contractor* from the *Consultant*.” |
| | 10.2.6 | Amend paragraph 10.2.6 by adding the following sentence to the end of the paragraph:<br><br>“In the event the *Owner* suffers loss or damage as a result of the *Contractor’s* failure to comply with paragraph 10.2.5 and notwithstanding any limitations described in paragraph 12.1.1, the *Contractor* agrees to indemnify and to hold harmless the *Owner* and the *Consultant* from and against any claims, demands, losses, costs, damages, actions suits or proceedings resulting from such failure by the *Contractor*.” |
| | 10.2.7 | Amend paragraph 10.2.7 by inserting the words “which changes were not, or could not have reasonably been known to the *Owner* or to the *Contractor*, as applicable, at the time of bid closing and which changes did not arise as a result of a public emergency or other *Force Majeure* event” to the second line, after the words “authorities having jurisdiction”. |
| | 10.2.8 | Add new paragraph 10.2.8 as follows:<br>“10.2.8 The *Contractor* shall furnish all certificates that are required or given by the appropriate governmental authorities as evidence that the *Work* as installed conforms with the laws |

| | | |
|---|---|---|
| | | and regulations of authorities having jurisdiction, including certificates of compliance for the *Owner's* occupancy or partial occupancy. The certificates are to be final certificates giving complete clearance of the *Work*, in the event that such governmental authorities furnish such certificates." |

**GC 10.4 WORKERS' COMPENSATION**

| | | |
|---|---|---|
| SC52.1 | 10.4.1 | Delete paragraph 10.4.1 and replace with the following:<br><br>"10.4.1 Prior to commencing the *Work*, and with each and every application for payment thereafter, including the *Contractor's* application for payment of the holdback amount following *Substantial Performance of the Work* and again with the *Contractor's* application for final payment, the *Contractor* shall provide evidence of compliance with workers' compensation legislation in force at the *Place of the Work*, including payments due thereunder." |

**GC 11.1 INSURANCE**

| | | |
|---|---|---|
| SC53.1 | 11.1 | Delete entirety of GC 11.1 and replace with the following:<br>"**GC 11.1 INSURANCE**<br>11.1.1 Without restricting the generality of GC 12 – INDEMNIFICATION, the *Contractor* shall provide, maintain, and pay for the insurance coverages specified in GC 11.1 – INSURANCE. Unless otherwise stipulated, the duration of each insurance policy shall be from the date of commencement of the *Work* until the expiration of the warranty periods set out in the *Contract Documents*. Prior to commencement of the *Work* and upon the placement, renewal, amendment, or extension of all or any part of the insurance, the *Contractor* shall promptly provide the *Owner* with confirmation of coverage and, if required, a certified true copy of the policies certified by an authorized representative of the insurer together with copies of any amending endorsements.<br>.1 **General Liability Insurance**<br>General liability insurance shall be in the name of the *Contractor,* with the *Owner* and the *Consultant* named as Additional insureds, with limits of not less than $5,000,000.00 inclusive per occurrence for bodily injury, death, and damage to property, including loss of use thereof, for itself and each of its employees, *Subcontractors* and/or agents. The insurance coverage shall not be less than the insurance required by IBC Form 2100, or its equivalent replacement, provided that IBC Form 2100 shall contain the latest edition of the relevant CCDC endorsement form. To achieve the desired limit, umbrella, or excess liability insurance may be used. All liability coverage shall be maintained for completed operations hazards from the date of *Ready-for-Takeover*, as set out in the certificate of *Ready-for-Takeover,* on an ongoing basis for a period of 6 years following *Ready-for-Takeover*. Where the *Contractor* maintains a single, blanket policy, the Addition of the *Owner* and the *Consultant* is limited to liability arising out of the *Project* and all operations necessary or incidental thereto. The policy shall be endorsed to provide the *Owner* with not less than 30 days' notice, in writing, in advance of any cancellation and of change or amendment restricting coverage.<br>.2 **Automobile Liability Insurance**<br>Automobile liability insurance in respect of licensed vehicles shall limits of not less than $2,000,000.00 inclusive per occurrence for bodily injury, death and damage to property, |

covering all licensed vehicles *owned* or leased by the *Contractor*, and endorsed to provide the *Owner* with not less than 30 days' notice, in writing, in advance of any cancellation, change or amendment restricting coverage. Where the policy has been issued pursuant to a government-operated automobile insurance system, the *Contractor* shall provide the *Owner* with confirmation of automobile insurance coverage for all automobiles registered in the name of the *Contractor.*

.3 **Aircraft and Watercraft Liability Insurance**

Intentional Deleted. Not Applicable

**.4 Property and Boiler and Machinery Insurance**

(1) Builder's Risk property insurance shall be in the name of the *Contractor* with the *Owner* and the *Consultant* named as Additional insureds. The policy shall insure against all risks of direct physical loss or damage to the property insured which shall include all property included in the *Work*, whether owned by the *Contractor* or the owner or owned by others, so long as the property forms part of the *Work*. The property insured also includes all materials and supplies necessary to complete the work, whether installed in the work temporarily or permanently, in storage on the project site, or in transit to the project site, as well as temporary buildings, scaffolding, falsework forms, hoardings, excavation, site preparation and similar work. The insurance shall be for not less than the sum of the amount of the contract price and the full value of products that are specified to be provided by the owner for incorporation into the work, if applicable, with the deductible of $10,000.00 payable by the contractor. The insurance shall include the foregoing and, otherwise, shall not be less than the insurance required by IBC Form 4042 or its equivalent replacement provided that the IBC Form 4042 shall include the latest Addition of the relevant CCDC endorsement form. The coverage shall be based on a completed value form and shall be maintained continuously until ten (10) days after the date of the final certificate of payment.

(2) Boiler and machinery insurance shall be in the name of the *Contractor*, with the *Owner* and the *Consultant* named as Additional insureds, for not less than the replacement value of the boilers, pressure vessels and other insurable objects forming part of the *Work*. The insurance provided shall not be less than the insurance provided by the "Comprehensive Boiler and Machinery Form" and shall be maintained continuously from commencement of use or operation of the property insured and until 10 days after the date of the final certificate for payment.

(3) The policies shall allow for partial or total use or occupancy of the *Work.*

(4) The policies shall provide that, in the case of a loss or damage, payment shall be made to the *Owner* and the *Contractor* as their respective interests may appear. The *Contractor* shall act on behalf of the *Owner* for the purpose of adjusting the amount of such loss or damage payment with the insurers. When the extent of the loss or damage is determined, the *Contractor* shall proceed to restore the *Work*. Loss or damage shall not affect the rights and obligations of either party under the *Contract* except that the *Contractor* shall be entitled to such reasonable extension of the *Contract Time,* relative to the extent of the loss or damage, as determined by the *Owner*, in its sole discretion.

| | | |
|---|---|---|
| | | (5) The *Contractor* shall be entitled to receive from the *Owner*, in Addition to the amount due under the *Contract*, the amount at which the *Owner's* interest in restoration of the *Work* has been appraised, such amount to be paid as the restoration of the *Work* proceeds and as provided in GC 5.2 – APPLICATIONS FOR PROGRESS PAYMENT and GC 5.3 – PROGRESS PAYMENT. In Addition, the *Contractor* shall be entitled to receive from the payments made by the insurer the amount of the *Contractor's* interest in the restoration of the *Work*.<br><br>(6) In the case of loss or damage to the *Work* arising from the work of other contractors, or the *Owner's* own forces, the *Owner*, in accordance with the *Owner's* obligations under paragraph 3.2.2.4 of GC 3.2 – CONSTRUCTION BY OWNER OR OTHER CONTRACTORS, shall pay the *Contractor* the cost of restoring the *Work* as the restoration of the *Work* proceeds and as provided in GC 5.2 – APPLICATIONS FOR PROGRESS PAYMENT and GC 5.3 – PROGRESS PAYMENT.<br><br>**.5 Contractors' Equipment Insurance**<br><br>"All risks" contractors' equipment insurance covering construction machinery and equipment used by the *Contractor* for the performance of the *Work*, excluding boiler insurance, shall be in a form acceptable to the *Owner* and shall not allow subrogation claims by the insurer against the *Owner*. The policies shall be endorsed to provide the *Owner* with not less than 30 days' notice, in writing, in advance of cancellation, change or amendment restricting coverage. Subject to satisfactory proof of financial capability by the *Contractor* for self-insurance of his equipment, the *Owner* agrees to waive the equipment insurance requirement.<br><br>11.1.2 The *Contractor* shall be responsible for deductible amounts under the policies except where such amounts may be excluded from the *Contractor's* responsibility by the terms of GC 9.1 - PROTECTION OF WORK AND PROPERTY and GC 9.2 - DAMAGES AND MUTUAL RESPONSIBILITY.<br><br>11.1.3 Where the full insurable value of the *Work* is substantially less than the *Contract Price*, the *Owner* may reduce the amount of insurance required to waive the course of construction insurance requirement.<br><br>11.1.4 If the *Contractor* fails to provide or maintain insurance as required by the *Contract Documents*, then the *Owner* shall have the right to provide and maintain such insurance and provide evidence of same to the *Contractor*. The *Contractor* shall pay the costs thereof to the *Owner* on demand, or the *Owner* may deduct the amount that is due or may become due to the *Contractor*.<br><br>11.1.5 All required insurance policies shall be with insurers licensed to underwrite insurance in the jurisdiction of the *Place of the Work*." |

***NEW* GC 11.2 CONTRACT SECURITY**

| | | |
|---|---|---|
| SC52.1 | GC 11.2 | Add new GC 11.2 – CONTRACT SECURITY as follows: |

| | | |
|---|---|---|
| | | "**GC 11.2 CONTRACT SECURITY**<br><br>11.2.1 The *Contractor* shall, prior to the execution of the *Contract*, furnish a performance bond and labour and material payment bond which meets the requirements under paragraph 11.2.2.<br>11.2.2 The performance bond and labour and material payment bond shall:<br>.1 be issued by a duly licensed surety company, which has been approved by the *Owner* and is permitted under the *Construction Act*,<br>.2 be issued by an insurer licensed under the *Insurance Act* (Ontario) and authorized to transact a business of suretyship in the Province of Ontario;<br>.3 shall be in the form prescribed by the *Construction Act*;<br>.4 have a coverage limit of at least 50 per cent of the *Contract Price*, or such other percentage of the *Contract Price* as stated in the *Contract Documents*;<br>.5 extends protection to *Subcontractors*, *Suppliers,* and any other persons supplying labour or materials to the *Project*; and<br>.6 shall be maintained in good standing until the fulfillment of the *Contract*, including all warranty and maintenance periods set out in the *Contract Documents*..<br>11.2.3 It is the intention of the parties that the performance bond shall be applicable to all of the *Contractor's* obligations in the *Contract Document* and, wherever a performance bond is provided with language which conflicts with this intention, it shall be deemed to be amended to comply. The *Contractor* represents and warrants to the *Owner* that it has provided its surety with a copy of the *Contract Documents* prior to the issuance of such bonds.<br>11.2.4 Without limiting the foregoing in any way, the bonds shall indemnify and hold harmless the *Owner* for and against costs and expenses (including legal and *Consultant* services and court costs) arising out of or as a consequence of any default of the *Contractor* under this *Contract*.<br>11.2.4 The *Contractor* shall be responsible for notifying the surety company of any changes made to the *Contract* during the course of construction.<br>11.2.5 The premiums for bonds required by the *Contract Documents* shall be included in the *Contract Price*.<br>11.2.6 Should the *Owner* require additional bonds by the *Contractor* or any of his *Subcontractors*, after the receipt of bids for the *Work*, the *Contract Price* shall be increased by all direct costs attributable to providing such bonds. The *Contractor* shall promptly provide the *Owner*, through the *Consultant*, with any such bonds that may be required." |

**PART 12 OWNER TAKEOVER**

**GC 12.1 READY-FOR-TAKEOVER**

| | | |
|---|---|---|
| SC55.1 | 12.1.1 | Delete GC 12.1.1 in its entirety and replace it with the following:<br>"12.1.1 *Ready-for-Takeover* shall be achieved when all of the following has occurred, as verified and approved by the *Owner*:<br>.1 *Substantial Performance of the Work* has been achieved, as certified by the *Consultant*; |

| | | |
|---|---|---|
| | | .2 a permit for occupancy of the *Place of the Work* has been obtained from the authorities having jurisdiction;<br><br>.3 the *Work* to be performed under the *Contract* has satisfied the requirements for deemed completion in accordance with Section 2(3) of the *Construction Act*,<br><br>.4 final cleaning and waste removal, as required by the *Contract Documents*;<br><br>.5 the *Contractor* has delivered to the *Consultant* and the *Owner* all inspection certificates from authorities having jurisdiction with respect to any component of the *Work* which has been completed;<br><br>.6 subject only to GC 12.1.2, the entire *Work* has been completed to the requirements of the *Contract Documents*, including completion of all items on the punch list prepared at the time of *Substantial Performance of the Work* and the *Work* is being used for its intended purpose, and is so certified by the *Consultant*;<br><br>.7 subject only to GC 12.1.2, the *Contractor* has submitted to the *Owner* and the *Consultant* in a collated and organized matter, all *Close-Out Documentation* and any other materials or documentation required by the *Contract Documents*;<br><br>.8 subject only to GC 12.1.2, all *Products*, systems and components of the *Project* have been commissioned and certified for operation and accepted by the *Owner* and *Consultant*, and<br>9 subject only to GC 12.1.2, the *Contractor* has submitted to the *Owner* and the *Consultant* full and complete as-built drawings and *Specifications* revised by the *Contractor* to reflect the as-built state of the *Work*, clearly showing changes to the *Drawings* and *Specifications* from the original *Contract Documents*, all of which have been approved by the *Owner* acting reasonably." |
| SC55.2 | 12.1.2 | Delete GC 12.1.2 in its entirety and replace it with the following:<br><br>"12.1.2 The *Owner* may, in its sole, absolute, and unfettered discretion, waive compliance with a requirement, or a part thereof, for achieving *Ready-for-Takeover* set out in GC 12.1.1.6 to 12.1.1.9 (inclusive). Where the *Owner* exercises the discretion afforded under this GC 12.1.2, the *Contractor* shall be required to comply with GC 5.5.1.2 as part of its application for final payment and the *Owner* and the *Contractor*, in consultation with the *Consultant*, shall establish a reasonable date for completing the *Work*." |
| SC55.3 | 12.1.3 | Delete GC 12.1.3 in its entirety and replace it with the following:<br><br>"12.1.3 When the *Contractor* considers the *Work Ready-for-Takeover*, it shall submit a written application to the *Owner* and the *Consultant* for review." |
| SC55.4 | 12.1.4 | In GC 12.1.4, delete the words "list and" from the second line. |
| SC55.5 | 12.1.5 | Delete GC 12.1.5 in its entirety and replace it with the following: |

| | | |
|---|---|---|
| | | "12.1.5 Following the confirmation of the date of *Ready-for-Takeover* by the *Consultant* and as confirmed by the *Owner*, the *Contractor* may submit a final application for payment in accordance with GC 5.5 – FINAL PAYMENT." |
| SC55.6 | 12.1.6 | Delete GC 12.1.6 in its entirety. |

**GC 12.2 EARLY OCCUPANCY**

| | | |
|---|---|---|
| SC56.1 | GC 12.2 | Delete GC 12.2 – EARLY OCCUPANCY BY THE OWNER in its entirety, including all subparagraphs thereunder and replace it with the following:<br><br>"12.2.1 The Owner reserves the right to take possession of and use for any intended purpose any portion or all of the undelivered portion of the Project even though the Work may not have reached Substantial Performance of the Work. Where the Work extends beyond the Contract Time, progress and completion of the Work shall not unduly interfere with the delivery of scheduled school programs. The taking of possession or use of any such portion of the Project shall not be deemed to be the Owner's acknowledgement or acceptance of the Work or Project nor shall it relieve the Contractor of any of its obligations under the Contract.<br><br>12.2.2 Whether the Project contemplates Work by way of renovations in buildings which will be in use or be occupied during the course of the Work or where the Project involves Work that is adjacent to a structure which is in use or is occupied, the Contractor, without in any way limiting its responsibilities under this Contract, shall take all reasonable steps to avoid interference with fire exits, building access and egress, continuity of electric power and all other utilities, to suppress dust and noise and to avoid conditions likely to propagate mould or fungus of any kind and all other steps reasonably necessary to promote and maintain the safety and comfort of the users and occupants of such structures or adjacent structures." |

**GC 12.3 WARRANTY**

| | | |
|---|---|---|
| SC57.1 | 12.3.1<br><br>12.3.2 | Delete from the first line of paragraph 12.3.1 the words "one year" and replace it with the words "two years"<br>Delete from the first line of paragraph 12.3.2 the word "The" and replace it with the words "Subject to GC 1.1.3, the…" |
| | 12.3.7 to 12.3.12 | Add new paragraphs 12.3.7 to 12.3.12 as follows:<br>"12.3.7 Where required by the *Contract Documents*, the *Contractor* shall provide a maintenance bond as security for the performance of the *Contractor's* obligations as set out in GC 12.3 WARRANTY.<br><br>12.3.8 The *Contractor* shall provide fully and properly completed and signed copies of all warranties and guarantees required by the *Contract Documents*, containing:<br><br>.1 the proper name of the *Owner*;<br>.2 the proper name and address of the *Project*; |

| | | |
|---|---|---|
| | | .3 the date the warranty commences, which shall be at the "*Ready-for-Takeover*" unless otherwise agreed upon by the *Consultant* in writing.<br>.4 a clear definition of what is being warranted and/or guaranteed as required by the *Contract Documents*; and<br>.5 the signature and seal (if required by the governing law of the *Contract*) of the company issuing the warranty, countersigned by the *Contractor*.<br><br>12.3.9 Should any *Work* need to be repaired or replaced during the time period for which it is covered by the specified warranty, a new warranty shall be provided under the same conditions and for the same period as specified herein before. The new warranty shall commence at the completion of the repair or replacement.<br><br>12.3.10 The *Contractor* shall ensure that its *Subcontractors* are bound to the requirements of GC 12.3 – WARRANTY for the *Subcontractor's* portion of the *Work.*<br><br>12.3.11 The *Contractor* shall ensure that all warranties, guarantees or other obligations for *Work*, services or *Products* performed or supplied by any *Subcontractor, Supplier* or other person in connection with the *Work* are obtained and available for the direct benefit of the *Owner.* In the alternative, the *Contractor* shall assign to the *Owner* all warranties, guarantees or other obligations for *Work*, services or *Products* performed or supplied by any *Subcontractor, Supplier* or other person in connection with the *Work* and such assignment shall be with the consent of the assigning party, where required by law, or by the terms of that party's contract. Such assignment shall be in addition to, and shall in no way limit, the warranty rights of the *Owner* under the *Contract Documents*.<br><br>12.3.12 The *Contractor* shall commence or correct any deficiency within 2 *Working Days* after receiving a *Notice in Writing* from the *Owner* or the *Consultant*, and shall complete the *Work* as expeditiously as possible, except in the case where the deficiency prevents maintaining security or where basic systems essential to the ongoing business of the *Owner* and/or its tenants cannot be maintained operational as designed. In those circumstances all necessary corrections and/or installations of temporary replacements shall be carried out immediately as an emergency service. Should the *Contractor* fail to provide this emergency service within 8 hours of a request being made during the normal business hours of the *Contractor*, the *Owner* is authorized, notwithstanding GC 3.1, to carry out all necessary repairs or replacements at the *Contractor's* expense." |

**PART 13 INDEMNIFICATION AND WAIVER**

**GC 13.1 INDEMNIFICATION**

| | | |
|---|---|---|
| SC58.1 | GC 13.1 | Delete GC 13.1 – INDEMNIFICATION in its entirety and replace it with the following:<br><br>*"*13.1.1 The *Contractor* shall indemnify and hold harmless the *Owner*, its parent, subsidiaries and affiliates, their respective partners, trustees, officers, directors, agents and employees and the *Consultant* from and against any and all claims, liabilities, expenses, demands, losses, damages, actions, costs, suits, or proceedings (hereinafter called "claims"), whether in respect of claims suffered by the *Owner* or in respect of claims by third parties, that directly or indirectly arise out of, or are attributable to, the acts or |

| | | |
|---|---|---|
| | | omissions of the *Contractor*, its employees, agents, *Subcontractors*, *Suppliers* or any other persons for whom it is in law responsible (including, without limitation, claims that directly or indirectly arise out of, or are attributable to, loss of use or damage to the *Work*, the *Owner's* property or equipment, the *Contractor's* property or equipment or equipment or property adjacent to the *Place of the Work* or death or injury to the *Contractor's* personnel).<br><br>13.1.2 The *Owner* shall indemnify and hold the *Contractor*, its agents and employees harmless from and against claims, demands, losses, costs, damages, actions, suits or proceedings arising out of the *Contractor*'s performance of the *Contract* which are attributable to a lack of or defect in title or an alleged lack of or defect in title to the *Place of the Work*.<br><br>13.1.3 The provisions of GC 13.1 - INDEMNIFICATION shall survive the termination of the *Contract,* howsoever caused and no payment or partial payment, no issuance of a final certificate of payment and no occupancy in whole or in part of the *Work* shall constitute a waiver or release of any of the provisions of GC 13.1<br><br>13.1.4 Notwithstanding the provisions of GC1.1 - CONTRACT DOCUMENTS, GC 1.1.6, GC13.1 - INDEMNIFICATION shall govern over the provisions of GC 1.3.1 of GC1.3 – RIGHTS AND REMEDIES." |

**GC 13.2 WAIVER OF CLAIMS**

| | | |
|---|---|---|
| | 13.2.1 | In paragraph 13.2.1 in the third line after the word "limitation" add the words "claims for delay pursuant to GC 6.5 DELAYS"<br><br>-and-<br><br>add the words "(collectively "**Claims**")" after "*Ready-for-Takeover*" in the fourth line. |
| | 13.2.1.1 | In subparagraph 13.2.1.1, in each instance change the word "claims" to "Claims" and change the word "claim" to "Claim". |
| | 13.2.1.2 | In subparagraph 13.2.1.2 change the word "claims" to "Claims". |
| | 13.2.1.3 | Delete subparagraph 13.2.1.3 in its entirety. |
| | 13.2.1.4 | In paragraph 13.2.1.4 change the word "claims" to "Claims". |
| | 13.2.2.1 | In paragraph 13.2.2.1 delete the words "in paragraphs 13.2.1.2 and 13.2.1.3" and replace them with "in paragraph 13.2.1.2"<br><br>-and-<br><br>change the word "claims" to "Claims" in both instances and change the word "claim" to "Claim". |

| | | |
|---|---|---|
| | 13.2.3 | Delete paragraph 13.2.3 in its entirety. |
| | 13.2.4 | Delete paragraph 13.2.4 in its entirety. |
| | 13.2.5 | Delete paragraph 13.2.5 in its entirety. |
| | 13.2.6 | In paragraph 13.2.6 change the word "claim" to "Claim" in all instances in the paragraph. |
| | 13.2.8 | In paragraph 13.2.8 change "The party" to "The *Contractor*<br><br>-and-<br><br>change the word "claim" to "Claim" in all instances in the paragraph. |
| | 13.2.9 | In paragraph 13.2.9 delete the words "under paragraphs 13.2.1 or 13.2.3" and replace them with "under paragraph 13.2.1"<br><br>-and-<br><br>change both instances of the words "the party" to "the *Contractor*". Change the word "claim" to "Claim" in all instances in the paragraph. |

***NEW* PART 14 OTHER PROVISIONS**

| | | |
|---|---|---|
| SC58.1 | 14.1 | Add new PART 14 – OTHER PROVISIONS as follows:<br><br>"**PART 14 OTHER PROVISIONS**<br><br>**GC 14.1 OWNERSHIP OF MATERIALS**<br><br>14.1.1 Unless otherwise specified, all materials existing at the *Place of the Work* at the time of execution of the *Contract* shall remain the property of the *Owner*. All *Work* and *Products* delivered to the *Place of the Work* by the *Contractor* shall be the property of the *Owner.* The *Contractor* shall remove all surplus or rejected materials as its property when notified in writing to do so by the *Consultant*." |
| | 14.2 | Add new GC 14.2 – CONSTRUCTION LIENS as follows:<br><br>**"GC 14.2 LIENS**<br><br>14.2.1 Notwithstanding any other provision in the *Contract*, the *Consultant* shall not be obligated to issue a certificate, and the *Owner* shall not be obligated to make payment, |

subject to the *Owner*'s requirement to issue a *Notice of Non-Payment* (Form 1.1) to the *Contractor*, if at the time such certificate or payment was otherwise due:

.1 a claim for lien has been registered against the *Project* lands by a *Subcontractor* or a *Supplier* that has not been vacated or discharged by the *Contractor* in accordance with the requirements of this *Contract*, or

.2 if the *Owner* or a mortgagee of the *Project* lands has received a written notice of a lien that has not been resolved by the *Contractor* through the posting of security or otherwise.

14.2.2 In the event a construction lien arising from the performance of the *Work* is registered or preserved against the *Project* lands by a *Subcontractor* or a *Supplier*, or a written notice of a lien is given or a construction lien action is commenced against the *Owner* by a *Subcontractor* or a *Supplier*, then the *Contractor* shall, at its own expense:

.1 within 10 calendar days of registration of the construction lien, vacate or discharge the lien from title to the premises (i.e. the *Place of the Work*). If the lien is merely vacated, the *Contractor* shall, if requested, undertake the *Owner*'s defence of any subsequent action commenced in respect of the lien, at the *Contractor*'s sole expense;

.2 within 10 calendar days of receiving notice of a written notice of a lien, post security with the Ontario Superior Court of Justice so that the written notice of a lien no longer binds the parties upon whom it was served; and

.3 satisfy all judgments and pay all costs arising from such construction liens and actions and fully indemnify the *Owner* against all costs and expenses arising from same, including legal costs on a full indemnity basis.

14.2.3 In the event that the *Contractor* fails or refuses to comply with its obligations pursuant to paragraph 14.2.2, the *Owner* shall, at its option, be entitled to take all steps necessary to address any such construction liens including, without limitation and in addition to the *Owner's* rights under paragraph 13.2.4, the posting of security with the Ontario Superior Court of Justice to vacate the claim for lien from title to the *Project* lands, and in so doing will be entitled to a full indemnity from the *Contractor* for all legal fees, security, disbursements and other costs incurred and will be entitled to deduct same from amounts otherwise owing to the *Contractor*.

14.2.4 In the event that any *Subcontractor* or *Supplier* registers any claim for lien with respect to all or part of the *Place of Work*, the *Owner* shall have the right to withhold, in addition to the statutory holdback, the full amount of said claim for lien plus either: (a) $250,000 if the claim for lien is in excess of $1,000,000 or (b) 25% of the value of the claim for lien and to bring a motion to vacate the registration of said claim for lien and any associated certificate of action in respect of that lien, in accordance with Section 44 of the *Act*, by paying into court as security the amount withheld.

14.2.5 Nothing in this GC 14.2 serves to preclude the *Contractor* from preserving and perfecting its lien in the event of non-payment by the *Owner*."

**APPENDIX 1**
**to the Supplementary Conditions**

**Project-specific requirements for a "*Proper Invoice*"**

To satisfy the requirements for a *Proper Invoice*, the following criteria, as may be applicable in each case, must be included with the *Contractor's* application for payment:

.1 the written bill or request for payment must be in writing;

.2 the *Contractor*'s name and current address;

.3 the *Contractor*'s HST registration number;

.4 the date the application for payment was prepared by the *Contractor*;

.5 the period of time in which the services or materials were supplied to the *Owner*;

.6 the purchase order number provided by the *Owner*;

.7 reference to the provisions of the *Contract* under which payment is being sought (e.g. GC 5.3 –PAYMENTS for progress payments, GC 5.4 – SUBSTANTIAL PERFORMANCE OF THE WORK AND PAYMENT OF HOLDBACK GC 5.5 – FINAL PAYMENT for final payment, etc.);

.8 a description, including quantities where appropriate, of the services or materials, or a portion thereof, that were supplied and form the basis of the *Contractor's* request for payment;

.9 the amount the *Contractor* is requesting to be paid by the *Owner*, set out in a statement based on the schedule of values approved under GC 5.2.4, separating out any statutory or other holdbacks, set-offs and HST;

.10 a sworn Statutory Declaration in the form CCDC 9A-2018, only for second and subsequent progress payments;

.11 a current Workplace Safety Insurance Board clearance certificate;

.12 a pre-approved schedule of values, supplied by the *Contractor*, for Divisions 1 through 14 of the *Specifications* (or equivalent Construction Specifications Institute Masterformat) of the *Work*, aggregating the total amount of the *Contract Price*, including all supporting invoicing;

.13 a separate pre-approved schedule of values, supplied by each *Subcontractor*, for each of Division 15, 16, and 17 of the *Specifications* (or equivalent Construction Specifications Institute Masterformat) of the *Work*, aggregating the total amount of the *Contract Price*, including all supporting invoicing;

.14 invoices and other supporting documentation for all claims against the cash allowance;

.15 a current, acceptable, and up to date *Construction Schedule Update*;

.16 if requested by the *Owner*, a current and valid certificate(s) of insurance as required under GC 11.1 – INSURANCE;

.17 the name, title, telephone number and mailing address of the person at the place of business of the *Contractor* to whom payment is to be directed;

.18 a current, up to date, and approved *Shop Drawing* log;

.19 in the case of the *Contractor's* application for final payment, in addition to the foregoing requirements (as applicable):

(a) any *Close-Out Documentation*, together with complete and final as-built drawings;

(b) the *Contractor's* written request for release of the deficiency holdback, including a statement that no written notices of lien have been received by it;

(c) the *Contractor's* written certification that there are no outstanding claims, pending claims or future claims from the *Contractor* or their *Subcontractors* or *Suppliers*; and

(d) sufficient evidence of the *Contractor's* compliance with GC 3.11.

**END OF AMENDMENTS TO CCDC 2 - 2020**

**DIVISION 01 - GENERAL REQUIREMENTS**

**01 14 00 – Work Restrictions**

## 1.0 GENERAL

### 1.1. SECTION INCLUDES

.1 Connecting to existing services

.2 Special scheduling requirements

### 1.2. RELATED SECTIONS

.1 Section 01 53 00 - Temporary Construction.

.2 Section 01 33 00 - Submittal Procedures.

.3 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.3. EXISTING SERVICES

.1 Notify Owner and Consultant and utility companies of intended interruption of services and obtain required permission.

.2 Where Work involves breaking into or connecting to existing services, give Consultant and Owner forty-eight (48) hours of notice for necessary interruption of mechanical or electrical service throughout the course of work.

.1 Keep duration of interruptions minimum.

.2 Perform interruptions after normal working hours of occupants, preferably on weekends.

.2 Provide for vehicular, pedestrian and personnel traffic.

.3 Construct barriers in accordance with Section 01 53 00.

### 1.2. AFTER HOURS WORK

.1 Schedule Work with school staff through the Board's contact so as to limit disruption to school operations. Include for any overtime, to ensure orderly and continuous progression of Work and operation of school.

.2 Direct calls from Contractors to Board staff to adjust alarms and to arrange for access will not be accepted. All correspondence must be through the Project Manager.

.3 Arrange 48 hours in advance with the Board to obtain an access card and adjust security alarms for after hours Work.

.4 Bidders are cautioned that the Board will be compensated by the Contractor for false alarms. Any costs associated with each false alarm will be levied against the

Contractor for false fire alarm activation or security alarm activation. These costs may include, but are not limited to:

.1 Fines or penalties imposed by the local Fire Services,

.2 Fines or penalties imposed by the local Police Services,

.3 Overtime costs borne by the Board.

.5 Contractors are responsible for ensuring doors and windows are secured prior to leaving school.

.6 Unless specifically stated otherwise school activities take precedence over Contractor's activities.

## 1.3. SPECIAL REQUIREMENTS

.1 Schedule and perform work in occupied areas to the Board Representative's approval.

.2 Schedule and perform noise generating work to the Board Representative's approval.

.3 Submit schedule of special requirements or disruptions in accordance with Section 01 33 00.

.4 All Contractor personnel are restricted to the job site and necessary access routes. No personnel shall visit other areas or buildings without specific authorization.

**END OF SECTION**

**01 19 00 – Specifications and Documents**

## 1.0 GENERAL

### 1.1. RELATED DOCUMENTS

.1 This Section describes requirements applicable to all sections within Divisions 02 to 49.

### 1.2. WORDS AND TERMS

.1 Conform to definitions and their defined meanings in the Agreement and Definitions portion of CCDC 2 for Supplementary Words and Terms listed in Section 00 56 13.

### 1.3. COMPLEMENTARY DOCUMENTS

.1 Generally, drawings indicate graphically, the dimensions and location of components and equipment. Specifications indicate specific components, assemblies, and identify quality.

.2 Drawings, specifications, diagrams and schedules are complementary, each to the other, and what is required by one, to be binding as if required by all.

.3 Should any conflict or discrepancy appear between documents, which leaves doubt as to the intent or meaning, apply the Precedence of Documents article below or obtain guidance or direction from Consultant.

.4 Examine all discipline drawings, specifications, schedules, diagrams and related Work to ensure that Work can be satisfactorily executed.

.5 All specification sections of the Project Manual and Drawings are affected by requirements of Division 01 sections.

### 1.4. PRECEDENCE OF DOCUMENTS

.1 In the event of conflict within and between the Contract Documents, the order of priority within specifications and drawings for this project are - from highest to lowest:

.1 the Agreement and Definitions between the Owner and the Construction

.2 the Defined Terms, Definitions;

.3 Supplementary Conditions;

.4 the General Conditions;

.5 Sections of Division 01 of the specifications;

.6 Technical specifications Sections of Divisions 02 through 49 of the specifications.

.7 Schedules and Keynotes:
  .1 Material and finishing schedules within the specifications, then;
  .2 Material and finishing schedules on drawings, then;
  .3 Keynotes and definitions thereto, then;

.8 Drawings:
  .1 Drawings of larger scale shall govern over those of smaller scale of the same date, then;
  .2 Dimensions shown on drawings shall govern over dimensions scaled from drawings, then;
  .3 Location of utility outlets indicated on architectural detail drawings takes precedence over positions or mounting heights located on mechanical or electrical Drawings.

.9 Later dated documents shall govern over earlier documents of the same type.

## 1.5. SPECIFICATION GRAMMAR

.1 Specifications are written in the imperative command mode, in an abbreviated form.

.2 Imperative language of the technical sections is always directed to the Contractor identified as a primary constructor, as sole executor of the Contract, unless specifically noted otherwise.
  .1 This form of imperative command mode statement requires the primary constructor to perform such action or Work.
  .2 Perform all requirements of the Contract Documents whether stated imperatively or otherwise.

.3 Division of the Work among subcontractors, suppliers, or others is solely the prime contractor's responsibility. The Consultant(s) and specification authors assume no responsibility to function or act as an arbiter to establish subcontract scope or limits between sections or divisions of Work.

**END OF SECTION**

**01 21 00 – Allowances**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 45 00 – Quality Control.

.2 This section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. GENERAL

.1 Allowances included herein are for items of Work which could not be fully quantified prior to Bidding.

.2 Expend each allowance as directed by the Consultant. Work covered by allowances shall be performed for such amounts and by such persons as directed by Consultant.

.3 Funds will be expended by means of Cash Allowance allocations and contingency allowance allocations.

.4 Progress payments for Work and Products authorized under allowances will be made in accordance with the payment terms set out in the Conditions of the Contract.

.5 The Contractor shall bid the work involved and submit the Bids received to the Consultant and the Board, for approval

.6 The Contractor shall submit 3 bids unless directed by the Board.

### 1.3. CASH ALLOWANCES

.1 Cash allowances, cover the net cost to the Contractor of services, products, construction machinery and equipment, freight, handling, unloading, storage, installation where indicated, and other authorized expenses incurred in performing the Work. Cash allowances shall not be included by a subcontractor in the amount for their subcontract work.

.2 Supply only allowances shall include:

- .1 Net cost of Products.
- .2 Delivery to Site.
- .3 Applicable taxes and duties, excluding HST.

.3 Supply and install allowances shall include:

- .1 Net cost of Products.
- .2 Delivery to Site.
- .3 Unloading, storing, handling or products on site.

.4 Installation, finishing and commissioning of products.

.5 Applicable taxes and duties, excluding HST.

.4 Inspection and testing allowances shall include:

.1 Net cost of inspection and testing services.

.2 Applicable taxes and duties, excluding HST.

.5 Other costs related to work covered by cash allowances are not covered by the allowance, but shall be included in the Contract Price.

.6 Where costs under a cash allowance exceed the amount of the allowance, the Contractor will be compensated for any excess incurred and substantiated plus an allowance for overhead and profit as set out in the Contract Documents.

.7 Progress payments on accounts of work authorized under cash allowances shall be included in the monthly certificate for payment.

.8 Submit, before application for final payment, copies of all invoices and statements from suppliers and subcontractors for work which has been paid from cash allowances.

## 1.4. ALLOWANCES SCHEDULE

Include in the Bid Price a cash allowance of to address the cost of the following items:

| | | |
|---|---|---|
| 1 | Designated Substance Removal (Additional removal not already identified in the ACM Summary report) | $10,000.00 |
| 2 | Removal of Waste Materials – Bat Excrement (As directed by Consultant) | $10,000.00 |
| 3 | Independent Testing & Inspection (soil, concrete, mortar, structural steel, air barrier, paving, painting) (As directed by the Consultant) | $10,000.00 |
| 4 | Exterior Masonry Repointing (Including installation of new stone at new openings indicated on Drawings) | $525,000.00 |
| 5 | Roof Tie-ins for new HVAC Units on existing flat roof and sloped roof: | $10,000.00 |
| 6 | Supply and Installation of New Doors/ Frames | $25,000.00 |
| 7 | Supply and Installation of New Exterior Windows | $12,500.00 |

| | | |
|---|---|---|
| 8 | Supply and Installation of Finishing Hardware (including door operators) | $22,500.00 |
| 9 | Repair of Interior Plaster (Including walls, ceilings and repairs to column capital) | $125,000.00 |
| 10 | Wood Floor Refinishing | $55,000.00 |
| 11 | Supply and Installation of New Acoustic Treatment | $7,500.00 |
| 12 | New Fire Protection System - Sprinklers (Work of Division 21) | $550,000.00 |
| 13 | Fire Alarm Interlocks and Integration (Work of Divisions 26 & 28 work associated with Work of Division 21) | $10,000.00 |
| 14 | Data cabling installation and network equipment (Including terminations) | $7,500.00 |
| 15 | Supply of Type S Luminaires (installation to be included in Base Bid) | $14,000.00 |
| 16 | Refurbishment of Heritage Exit Signs (removal and reinstallation to be included in base Bid) | $6,000.00 |
| | **Total of All Allowances:** | **$1,400,000.00** |

**END OF SECTION**

**01 31 00 – Project Managing and Coordination**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 32 00 - Construction Progress Documentation.

.2 Section 01 33 00 - Submittal Procedures.

.3 Section 01 53 00 – Temporary Construction Facilities

.4 Section 01 61 00 – Product Requirements

.5 Section 01 78 10 – Closeout Submittals and Requirements

.6 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. PROJECT COORDINATION

.1 Perform coordination of progress schedules, submittals, use of site, temporary utilities, construction facilities and construction Work, with progress of Work of other contractors, under instructions of the Consultant.

.2 The Contractor shall have total control of the Work and shall effectively direct and supervise the Work so as to ensure conformity with the Contract Documents and within the Contract Time.

.3 The Contractor shall be solely responsible for the construction means, methods, sequences, and procedures and for coordinating parts of the Work under the contract.

.4 Coordinate progress of the Work, progress schedules, submittals, use of site, temporary utilities, construction facilities, safety regulations and fire protection, as per authorities having jurisdiction codes.

.5 The Consultant has the authority to stop the Work:

.1 whenever they observe or are made aware of unsafe conditions.

.2 whenever it is deemed necessary to protect the interests of the Board,

.3 whenever materials or workmanship are in contravention to the Contract Documents.

### 1.3. SITE SUPERVISOR AND PROJECT MANAGER

.1 If requested, the Contractor shall provide the Consultant, in writing, the name of the Project Manager and Site Supervisor, and proof of competent experience in similar projects.

.2 Performance of the Contractors Project Manager and Site Supervisor

.1 If the Board and or the Consultant become concerned with any of: Site Safety, Project Schedule, or general compliance with the tender documents due to the performance of the Site Supervisor or Project Manager, the Consultant and or the Board will identify the concerns in writing to the Contractor.

.2 The Contractor shall respond in writing to the Board and Consultant with a corrective action for each item within 24 hours.

.3 If it is found that any of the corrections are not immediately implemented, the Consultant and the Board shall meet with the General Contractor to review the credentials including curriculum vitae and comparable experience of a replacement Site Supervisor and or Project Manager proposed by that Contractor.

.4 All outstanding concerns initiating the replacement of the personnel will be immediately addressed to the satisfaction of the Consultant and the Board.

.3 If the Board and or the Consultant become concerned with site safety, project schedule or general compliance with the tender documents due to the performance of the Site Supervisor or the Project Manager, the Consultant or the Board will issue the concerns in writing to the Contractor. The Contractor shall respond in writing within 24 hours to the Consultant and the Board. If any of the corrections are not immediately implemented, the Consultant or the Board will schedule a meeting with the Consultant, General Contractor and the Board. At this meeting the Contractor will introduce the new Project Manager, and or Site Supervisor and present the Curriculum Vitae for each showing proof of comparable experience in similar projects. The Contractor will then address the outstanding concerns to the satisfaction of the Consultant and the Board.

.4 The Project Manager, and/or Site Supervisor shall not be replaced by the Contractor without prior written approval from the Board and the Consultant.

## 1.4. PERMITS

.1 **The Board will obtain & pay for all building permits, but the Contractor is responsible for all other permits, including electrical inspection and fire alarm verification.**

## 1.5. CONSTRUCTION DOCUMENTS

.1 The Consultant will provide the Contractor with PDF copies of both the drawings and the specification and CAD format files of the drawings at no charge to the Contractor. All printing will be at the cost of the Contractor including the AS-BUILT documents.

## 1.6. PRE-CONSTRUCTION MEETING

.1 Immediately prior to construction and upon notification by the Consultant of a time and date, the Contractor shall attend the preconstruction meeting at a location as determined by the Consultant, along with authoritative representatives of certain key subcontractors as specifically indicated in the conference notice. Agenda to include following:

- .1 Appointment of official representative of participants in Work.
- .2 Project communications procedures
- .3 Schedule of Work, progress scheduling (including long lead items, cash allowance items) as specified in Section 01 32 00.
- .4 Schedule of submission of shop drawings, samples, colour chips as specified in Section 01 33 00.
- .5 Requirements for temporary facilities, washrooms, refuse bin, site sign, offices, storage sheds, utilities, fences as specified in Section 01 53 00.
- .6 Delivery schedule of specified equipment as specified in Section 01 61 00.
- .7 Proposed changes, change orders, procedures, approvals required, mark-up percentages permitted, time extensions, overtime, and administrative requirements.
- .8 Owner furnished products.
- .9 Record drawings as specified in Section 01 78 10.
- .10 Maintenance material and data as specified in Section 01 78 10.
- .11 Take-over procedures, acceptance, and warranties as specified in Section 01 78 10.
- .12 Monthly progress claims, administrative procedures, photographs, and holdbacks.
- .13 Appointment of inspection and testing agencies
- .14 Insurances and transcript of policies.
- .15 Review Vendor Performance Evaluation for the Contractor and Subcontractors
- .16 Hot Work Permit Process
- .17 Security Access, Fire Alarm shutdown procedures
- .18 Any other items as required by the owner, contractor, or Consultant.

## 1.7. ON-SITE DOCUMENTS

.1 Maintain at job site at all times, one copy (written or digital) each of the following:

- .1 Complete set of Contract drawings.
- .2 Specifications.
- .3 All Addenda.

.4 Site Instructions and Sketches
.5 Reviewed shop drawings and samples.
.6 Change Orders and Contemplated Change Orders.
.7 Other modifications to Contract.
.8 Site Instructions
.9 Colour schedule
.10 Hardware List
.11 Field test reports.
.12 Copy of approved Work schedule.
.13 Manufacturers' installation and application instructions.
.14 Progress reports and meeting minutes.
.15 Approved building permit documents.
.16 Copy of current Ontario Building Code and National Building Code.
.17 CSA Standard, CGSB Specifications. ASTM Documents and other standards referenced to in the specifications.
.18 Labour conditions and wage schedules.
.19 Applicable current editions of municipal regulations and by-laws. Current building codes, complete with addenda bulletins applicable to the Place of the Work.

## 1.8. SCHEDULES

.1 Within three weeks following the award of the Contract, submit a detailed, trade by trade progress schedule for the work in a bar chart form acceptable to the Consultant.
.2 Submit preliminary construction progress schedule as specified in Section 01 32 00 to Consultant coordinated with Consultant's project schedule.
.3 After review, revise and resubmit schedule to comply with revised project schedule.
.4 During progress of Work revise and resubmit as directed by the Consultant.
.5 Provide schedule updates every month with request for Payment, for duration of Contract.

## 1.9. CONSTRUCTION PROGRESS MEETINGS

.1 Prior to the commencement of the Work, the Contractor together with the Consultant shall mutually agree to a sequence for holding regular "on site meetings".
.2 The Contractor will organize site meetings. Ensure persons, whose presence is required, are present and relative information is available to allow meetings to be conducted efficiently.

.3 Contractor, major subcontractors and consultants involved in Work are to be in attendance.

.4 Post and forward copies of progress schedules for advice of Subcontractors, Owner and Consultant.

.5 Notify parties minimum five (5) days prior to meetings.

.6 Record minutes of meetings and circulate to attending parties and affected parties not in attendance within two (2) days after meeting.

.7 Agenda to include following:

- .1 Review, approval of minutes of previous meeting.
- .2 Review of Work progress since previous meeting.
- .3 Field observations, problems, conflicts.
- .4 Problems which impede construction schedule.
- .5 Review of off-site fabrication delivery schedules.
- .6 Corrective measures and procedures to regain projected schedule.
- .7 Revision to construction schedule.
- .8 Progress schedule, during succeeding work period.
- .9 Review submittal schedules: expedite as required.
- .10 Maintenance of quality standards.
- .11 Review proposed changes for effect on construction schedule and on completion date.
- .12 Review site security issues.
- .13 Other business.

.8 Schedule additional meetings, to expedite progress, should work require it.

.9 Keep Owner and Consultant informed of progress, of delays and potential delays during all stages of Work. Do everything possible to meet progress schedule

.10 Schedule and administer pre-installation meetings when specified in sections and when required to coordinate related or affected Work.

## 1.10. SUBMITTALS

.1 Prepare and issue submittals to Consultant for review.

.2 Submit preliminary Shop Drawings, product data and samples for review for compliance with Contract Documents; for field dimensions and clearances, for relation to available space, and for relation to Work of other contracts. After review, revise and resubmit for transmittal to Consultant.

.3 Submit requests for payment for review, and for transmittal to Consultant.

.4 Submit requests for interpretation of Contract Documents, and obtain instructions through Consultant.

.5 Process substitutions through Consultant.

.6 Process change orders through Consultant.

.7 Deliver closeout submittals for review and preliminary inspections, for transmittal to Consultant.

## 1.11. RECORD (AS-BUILT) DOCUMENTS AND SAMPLES

.1 Procedures for record as-built documents and samples as specified in Section 01 78 10.

.2 Keep as-built documents and samples available for inspection by the Consultant.

## 1.12. CLOSEOUT PROCEDURES

.1 Take-over procedures, acceptance, and warranties as specified Section 01 78 10

.2 Notify Consultant and Board when Work is considered ready for Substantial Performance.

.3 Accompany Consultant and Board on preliminary inspection to determine items listed for completion or correction.

.4 Comply with Consultant's instructions for correction of items of Work listed in executed certificate of Substantial Performance.

.5 Notify Consultant of instructions for completion of items of Work determined in Consultant's final inspection.

**END OF SECTION**

**01 32 00 – Construction Progress Documentation**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 33 00 - Submittal Procedures.

.2 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. SCHEDULES

.1 Within seven 7 days following the award of the Contract, submit a detailed cash flow chart broken down on a monthly basis, in a manner acceptable to the Consultant. Cash flow chart shall indicate anticipated Contractor's monthly progress billings from commencement of work until completion.

.2 Update cash flow chart whenever changes occur to scheduling and in manner and at times satisfactory to Consultant.

.3 Submit schedule of values at least fourteen (14) days before the first application

.4 Submit schedules as follows:

.1 Submittal Schedule for Shop Drawings and Product Data.

.2 Submittal Schedule for Samples.

.3 Submittal Schedule for timeliness of Owner-furnished Products.

.4 Product Delivery Schedule.

.5 Cash Allowance Schedule for acquiring Products and Installation.

.6 Shutdown or closure activity.

### 1.3. CONSTRUCTION PROGRESS SCHEDULING

.1 Submit initial schedule to the Consultant and the Board in duplicate within seven (7) days after following the award.

.2 Schedule Format.

.1 Prepare schedule in form of a horizontal bar chart.

.2 Split horizontally for projected and actual performance.

.3 Provide horizontal time scale identifying each Working Day of each week.

.3 Schedule Submission.

.1 Consultant will review schedule and return reviewed copies within five (5) days after receipt.

.2 Submit schedules in electronic format, forward to the Consultant and Owner as a pdf. file.

.3 Resubmit finalized schedule within five (5) days after return of review copy.

.4 Submit revised progress schedule with each application for payment.

.5 Distribute copies of revised schedule to:

.1 Job site office.

.2 Subcontractors.

.3 Other concerned parties.

.6 Instruct Consultant to report to Contractor within ten (10) days, any problems anticipated by timetable shown in schedule.

.4 Submit revised schedules with Application for Payment, identifying changes since previous version.

.5 Select either of the following paragraphs to identify the type and format of schedule required.

.6 Show complete sequence of construction by activity, identifying Work of separate stages and other logically grouped activities. Indicate the early and late start, early and late finish, float dates, and duration.

.7 Indicate estimated percentage of completion for each item of Work at each submission.

.8 Indicate submittal dates required for shop drawings, product data, samples, and product delivery dates, including those furnished by Owner and required by Allowances.

.9 Include dates for commencement and completion of each major element of construction:

.1 Site clearing.

.2 Site utilities.

.3 Foundation Work.

.4 Structural framing.

.5 Subcontractor Work.

.6 Equipment Installations.

.7 Finishes.

.10 Indicate projected percentage of completion of each item as of first day of month.

.11 Indicate progress of each activity to date of submission schedule.

.12 Indicate changes occurring since previous submission of schedule:

.1 Major changes in scope.

.2 Activities modified since previous submission.

.3 Revised projections of progress and completion.

.4 Other identifiable changes.

.13 Provide a written report to define:
- .1 Problem areas, anticipated delays, and impact on schedule.
- .2 Corrective action recommended and its effect.
- .3 Effect of changes on schedules of other subcontractors.

## 1.4. PROGRESS PHOTOGRAPHS

.1 Digital Photography:
- .1 Submit electronic copy of progress photographs of project, Digital format, minimum 300 in megapixel resolution.
- .2 Identification: Name and number of project and date of exposure indicated.
- .3 Provide both interior and exterior photographs.
- .4 Number of Viewpoints: Locations of viewpoints determined by Consultant.
- .5 Frequency: Monthly with progress statement. Provide the required number of pictures to accurately reflect the submitted progress percentage.

## 1.5. SHOP DRAWING SUBMITTAL SCHEDULE

.1 Include schedule for submitting shop drawings, product data, samples

.2 Indicate dates for submitting, review time, resubmission time, and last date for meeting fabrication schedule.

.3 Include dates when shop drawings and samples will be required for Owner-furnished products.

.4 Include dates when reviewed submittals will be required from Consultant.

.5 Provide final signed off copies of the shop drawings in digital format to the Board.

**END OF SECTION**

## 01 33 00 – Submittal Procedures

### 1.0 GENERAL

### 1.1 RELATED SECTIONS

1. Section 01 32 00 - Construction Progress Documentation.
2. Section 01 78 10 - Closeout Submittals.
3. This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.1 ADMINISTRATIVE

1. Submit to Consultant submittals listed for review. Submit with reasonable promptness and in orderly sequence so as to not cause delay in Work. Failure to submit in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
2. Work affected by submittal shall not proceed until review is complete.
3. Present Shop Drawings, product data, samples and mock-ups in Metric (SI) units. Shop drawings containing imperial measurements will be rejected.
4. Where items or information is not manufactured or produced in SI Metric units, converted values within the metric measurement to the next largest imperial size available. Tolerances of .0625 acceptable.
5. Review submittals prior to submission to Consultant. This review represents that necessary requirements have been determined and verified, or will be, and that each submittal has been checked and coordinated with requirements of Work and Contract Documents.
6. Submittals not stamped, signed, dated, identified as to specific project, and attesting to their being reviewed will be returned without being examined and shall be considered rejected.
7. Shop drawings which require the approval of a legally constituted authority having jurisdiction shall be submitted by Contractor to such authority for approval. Such shop drawings shall receive final approval of authority having jurisdiction before Consultant's final review.
8. No work, requiring a shop drawing submission, shall be commenced until the submission has received Consultant's final review. Only shop drawings bearing Consultant's review stamp are to be sent and used on the job site.
9. Notify Consultant, in writing at time of submission, identifying deviations from requirements of Contract Documents stating reasons for deviations.

10. Shop drawings shall not contain substituted materials unless such substitutions have been requested in advance and approved by Consultant.
11. Verify field measurements and affected adjacent Work are coordinated.
12. Contractor's responsibility for errors and omissions in submission is not relieved by Consultant's review of submittals.
13. Contractor's responsibility for deviations in submission from requirements of Contract Documents is not relieved by Consultant review.
14. Keep one (1) reviewed copy of each submission on site.

## 1.2 SHOP DRAWINGS AND PRODUCT DATA

.1 The term "Shop Drawings" means drawings, diagrams, illustrations, schedules, performance charts, brochures and other data which are to be provided by Contractor to illustrate details of a portion of Work.

.2 The term "design team" means Consultant and Sub-consultants whether Sub-consultants are employees of Consultant or not, and includes structural, mechanical, electrical, etc.

.3 Indicate materials, methods of construction and attachment or anchorage, erection diagrams, connections, explanatory notes and other information necessary for completion of Work. Where articles or equipment attach or connect to other articles or equipment, indicate that such items have been coordinated, regardless of Section under which adjacent items will be supplied and installed. Indicate cross references to design drawings and specifications.

.4 Allow fourteen (14) days for Consultant's review of each submission.

.5 Adjustments made on Shop Drawings by Consultant are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Consultant prior to proceeding with Work.

.6 Make changes in Shop Drawings as Consultant may require, consistent with Contract Documents. When resubmitting, notify Consultant in writing of any revisions other than those requested.

.7 Accompany submissions with transmittal letter, containing:

.1 Date.

.2 Project title and number.

.3 Contractor's name and address.

.4 Identification and quantity of each shop drawing, product data and sample.

.5 Other pertinent data.

.8 Submissions shall include:
  .1 Date and revision dates.
  .2 Project title and number.
  .3 Name and address of:
    .1 Subcontractor.
    .2 Supplier.
    .3 Manufacturer.
  .4 Contractor's stamp, signed by Contractor's authorized representative certifying approval of submissions, verification of field measurements and compliance with Contract Documents.
  .5 Details of appropriate portions of Work as applicable:
    .1 Fabrication.
    .2 Layout, showing dimensions, including identified field dimensions, and clearances.
    .3 Setting or erection details.
    .4 Capacities.
    .5 Performance characteristics.
    .6 Standards.
    .7 Operating weight.
    .8 Wiring diagrams.
    .9 Single line and schematic diagrams.
    .10 Relationship to other parts of the Work.

.9 After Consultant's review, distribute copies.

.10 Submit Shop Drawings in Pdf. format for each requirement requested in specification Sections and as consultant may reasonably request.

.11 Submit product data sheets or brochures in Pdf. format for requirements requested in specification sections and as requested by Consultant where Shop Drawings will not be prepared due to standardized manufacture of product.

.12 Delete information not applicable to project.

.13 Supplement standard information to provide details applicable to project.

.14 If upon review by Consultant, no errors or omissions are discovered or if only minor corrections are made, the drawings will be stamped as reviewed or reviewed as modified and will be returned. At this point fabrication and installation of Work may proceed. If Shop Drawings are rejected, noted copy will be returned and re-submission of corrected Shop Drawings, through same procedure indicated above, must be performed before fabrication and installation of Work may proceed.

.15 Signed drawings shall be returned to and retained by Contractor who is then responsible for distribution of copies of corrected shop drawing to appropriate Subcontractors for appropriate action and to municipal building department for their records of those subjects required by authorities.

.16 The Consultant's review is for the sole purpose of ascertaining conformance with the general design concept. This review shall not mean the Consultant approves the detail design inherent in the shop drawings, responsibility for which shall remain with the Contractor submitting same, and this review shall not relieve the Contractor of his responsibility for meeting the requirements of the Contract Documents. The Contractor is responsible for dimensions to be confirmed and correlated at the job site for information that pertains solely to fabrication processes or to techniques of construction and installation and for coordination of the work of all subtrades.

## 1.3 SAMPLES

.1 Submit for review to the Consultant three (3) samples as requested in respective specification Sections.

.2 Submit samples with identifying labels bearing material or component description, manufacturer's name and brand name, Contractor's name, project name, location in which material or component is to be used, and date.

.3 Deliver samples prepay any shipping charges involved for delivering samples to destination point and returning to point of origin if required.

.4 Provide samples of special products, assemblies, or components when so specified.

.5 No work requiring a sample submission shall commence until submission has received Consultant's final review.

.6 Notify Consultant in writing, at time of submission of deviations in samples from requirements of Contract Documents.

.7 Where colour, pattern or texture is criterion, submit full range of samples.

.8 Adjustments made on samples by Consultant are not intended to change Contract Price. If adjustments affect value of Work, state such in writing to Consultant prior to proceeding with Work.

.9 Make changes in samples which Consultant may require, consistent with Contract Documents.

.10 Reviewed and accepted samples will become standard of workmanship and material against which installed Work will be verified.

## 1.4 MOCK-UP

.1 Erect mock-ups to Section 01 45 00.

## 1.5 CERTIFICATES AND TRANSCRIPTS

.1 Immediately after award of Contract, and prior to commencing the work submit the performance bond and the labour and materials payment bond as described in the bid documents.

.2 Submit transcription of certified true copies of insurance immediately after award of Contract.

.3 A current WSIB clearance certificate

.4 The bidder's health and safety policy for the project.

.5 A copy of the notice of project issued by the ministry of labour for the project

.6 Building materials, components and elements specified without the use of trade or proprietary names shall meet requirements specified. If requested by Consultant, submit evidence of meeting requirements specified. Evidence shall consist of certification based on tests carried out by an independent testing agency. Certification based on previous tests for same materials, components or elements is acceptable. Certification shall be in form of written test reports prepared by testing agency.

**END OF SECTION**

**01 35 17 – Fire Safety Procedures**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 14 00 – Work Restrictions.

.2 Section 01 31 00 - Project Managing and Coordination.

.3 Section 01 33 00 - Submittal Procedures.

.4 Section 01 35 23 – Health and Safety

.5 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

.6 Appendix 01 35 17A Contractor Hot Work Permit

### 1.2. FIRE SAFETY PLAN

.1 Contractors and their personnel will be familiar with this section and its requirements.

.2 The contractor must take all necessary precautions during the carrying out of the work to prevent the possibility of fire occurring.

### 1.3. FIRE PROTECTION

.1 Provide and maintain temporary fire protection equipment during performance of Work required by the governing codes, regulations and bylaws.

.2 The contractor will, at all times, when welding, brazing and performing any operation with an open flame, combustible adhesives or flammable solvents keep a portable, operable fire extinguisher within 3 meters of the operation.

### 1.4. HOT WORK

.1 Take all precautions to Work safely and to provide the necessary protection to persons and property from Hot Work. This includes, but is not limited to Brazing, Cutting, Grinding, Soldering, Thawing Pipe, Torch Applied Roofing and Welding. With all such activity these steps are to be followed:

.1 Whenever possible, complete Hot Work in a welding shop or out of doors at the school.

.2 Flammable liquids, dust lint and oily deposits to be removed from within 50-ft (15m) of Work. Remove other combustibles where possible. Otherwise protect with fire-resistive tarpaulins or metal shields.

.3 Explosive atmosphere in area eliminated. Floors swept clean. Combustible floors wet down, covered with damp sand or fire-resistive tarpaulins.

.4 All wall and floor openings covered. Fire-resistive tarpaulins suspended beneath Work.

.5 For on-site Work (indoor and out of doors), advise the Head Custodian, Principal, Consultant (if assigned) and Project Coordinator prior to Work being performed, and of related dangers.

.6 Where the Fire Alarm system is required to be set to stand-by to discourage false alarms from smoke detectors provide a firewatch throughout the building or structure being worked on. NEVER put the fire alarm system in stand-by mode when the building is occupied by staff or students.

.7 In the event of a fire as a result of the Hot Work, notify the fire department immediately. Report incident to the head custodian, the Consultant, if assigned, and Project Coordinator immediately, whether extinguished or not. Provide a fire incident report to the Board.

.8 Barriers must be set up to protect staff and students (i.e. pylons, shields, and caution tape) from exposure to arc flash and smoke migration.

.9 Have all necessary doors, windows and/or drapes closed. Confer with the Head Custodian to shut down all fan systems in the area to reduce or eliminate smoke distribution.

.10 Provide and keep fire extinguishers handy and in good Working condition. Temporarily cover all smoke detectors in the area during time of Work.

.11 Provide a fire watch/spot check for several hours after Work is completed. Uncover smoke detectors.

.12 On new construction, the requirements of the Hot Wok permit may be waived, until such time as either Substantial Completion or Occupancy is granted, whichever comes first.

.13 On additions to existing buildings, the requirements for Hot Work permits shall remain in place.

## 1.5. HOT WORK PERMIT

.1 **A sample Hot Work Permit is attached to the specifications – refer to attached Appendix 01 35 17-A**

.2 Each permit is valid for seven (7) days only and must be renewed prior to its expiration date

.3 The Contractor must obtain Hot Work Permits from the School Board's representative prior to the start of work.

.4 The contractor must complete the form as required and must keep the form on site.

.5 Return each completed form to the School Board's representative on the date of expiration.

.6 The most current version of the Permit and its requirements shall be used for the purposes of the Work.

## 1.6. FIRE PROTECTION SYSTEMS

.1 Any Modifications to Fire Alarm system and its devices including service, additions and changes in device location must be performed only by a Certified Fire Alarm Technician as per the Ontario Fire Code section 1.1, subsection 1.1.5.

.2 The Contractor will receive from the Board's contact a contact number for the monitoring service and a school system number.

.3 Bidders are cautioned that the Board will be reimbursed for the cost of false alarms. Refer to Section 01 14 00 Work Restrictions, Para. 1.4.4.

.4 An approved inspection firm shall verify all new fire alarm devices, in accordance with CSA regulations. Certificate of Verification is required before occupancy.

## 1.7. FIRE ALARM SHUT-DOWN PROCEDURE

.1 Plan the operation such that the required work minimizes system down time to the least amount possible. Do not shut the system down or engage silence mode when the building is occupied by students. Only shut the system down when necessary.

.2 For the purposes of this section, unoccupied shall mean when the school is not occupied by students.

.3 Wherever possible, shut down only the zone needing work,

.4 and schedule down time in unoccupied school hours.

.5 Contractor(s) shall ensure all costs are included in their bid price for work related to the fire alarm system outside of regular hours and/or during unoccupied school hours. This shall include evening and weekend work.

.6 A fire alarm system must remain active when the building is not occupied by school or contractor's forces and should never be offline overnight.

.7 Procedure

The following procedure shall be followed when a fire alarm system is completely or partially affected by maintenance, shutdown, bypass, silence, loss of power, or any other nomenclature that affects the proper operation of the complete system.

.1 Inform both the principal and head custodian whenever the fire alarm system is to be disabled prior to any partial or whole system shut down. Where school staff are not available, ensure that the Project Coordinator and/or area supervisor are informed.

.2 Ensure that the school or building administration has advised all staff when the fire alarm system is disabled and/or when it is back online. This will include instructions to call 911 if they detect smoke or a fire.

.3 Immediately prior to alarm system shutdown and upon restoring the fire alarm system, the person supervising the shutdown must:

.1 obtain the school account number, located on a red decal attached to the fire alarm panel. This number will be formatted as 20-9xxx, with the xxx being the school location code,

.2 contact Direct Detect at 519-741-2494 (the fire alarm monitoring company), to inform them of the state of the fire alarm and the approximate amount of time the fire alarm will be offline. They will require the building name and account number, the contact name, the contractor name as well as any other information they request, and

.3 contact Bestell at 519-741-2494 (the current security monitoring company), to inform them of the state of the fire alarm and the approximate amount of time the fire alarm will be offline. They may require the building name and account number as well as any other information they request.

.4 A fire watch, at the Contractor's expense, shall be undertaken by a person with the sole and express purpose of completing the following tasks and in the event of the detection of smoke, fire, or any other emergency, notifying the fire department, and the building occupants. The fire watch patrol shall:

.1 patrol all halls and high-risk areas affected,

.2 have access to a phone and call 911 if they see or detect smoke or fire,

.3 report any other problems they encounter,

.4 notifying the building occupants in the event of an emergency and

.5 remain on patrol until the fire alarm system is reactivated and fully operational.

.5 Contact Direct Detect, Bestell, and school administration to inform them that the fire alarm is back online.

.6 In the event that a fire alarm system is activated, whether by smoke, fire or accidentally, the system must not be reset until authorized by the Fire Department (verbally or in person) and the cause of the alarm has been investigated.

## 1.8. FIRE PROTECTION EQUIPMENT IMPAIRMENT

.1 Fire Protection Equipment referred to in this section includes sprinkler systems, special fire suppression systems, and kitchen hood suppression systems.

.2 The Contractor will take all precautions including restrict all Hot Work operations and shut down hazardous processes during all Fire protection equipment impairment.

.3 Do not shut the Fire protection equipment down unless necessary. Plan the operation required to reduce system impairment time to the least amount possible.

.4 Wherever possible, shut down only the Fire protection equipment needing Work and schedule this impairment time for unoccupied school hours. Allow for this in your bid pricing.

.5 Discuss the possible down time with the head custodian and principal prior to any partial or whole system impairment.

.6 The school administration shall advise all staff of Fire protection equipment shut down. This will include instructions to call 911 if they see a fire and when system is back online

.7 The Contractor will plan to use temporary protection such as extra extinguishers, charged hose lines and temporary sprinkler protection during all Fire protection equipment impairment.

.8 If the sprinkler system is restorable, either in whole or in part, the Contractor or subcontractor shall assign someone to restore the system promptly in the event of a fire.

.9 A fire patrol may need to be established and will include the following at the Contractor's expense:

- .1 Patrol all halls and high-risk areas affected.
- .2 Fire patrol shall have access to a phone and call 911 if they see a fire.
- .3 Report all other problems they encounter.
- .4 Remain on patrol until the system is back on.

.10 The Contractor shall inform all sub trades that the Board has a Red Tag Permit System and it shall be used for all Fire protection equipment impairment.

.11 For ease of use, a Factory Mutual hanging wall kit has been put in place at all Board Fire protection equipment locations. Supplies of Red Tag Permits are provided there.

## 1.9. FIRE ALARM MODIFICATIONS AND MAINTENANCE

.1 Very important changes to Ontario Building Code as they relate to the Standard for the Verification of Fire Alarm Systems CAN/ULC-S537-M have taken effect December 24, 1999. (Minister's Ruling 99-BC-01)

.1 Clause 5.1: "Addition of conventional field device(s), or modification(s), to existing input circuit(s) or output circuit(s) shall require re-verification of all devices served by those input circuit(s) or output circuit(s)." If one device is added to a zone, the entire zone or in the case of a single zone panel the entire system is to be verified.

.2 Clause 5.2: "Addition of input circuit(s) or output circuit(s) to an existing fire alarm system shall require verification of the new circuit(s) in accordance with this standard, and shall also require all previously existing circuit(s) to be tested as follows:

.3 TEST: One conventional field device on each circuit shall be operated to confirm activation of all output circuits in accordance with the systems design." Even though no other zones have been touched, one device per input zone is to be tested when the Fire Alarm system is modified.

.4 Clause 5.5: "Where a transponder is added to an existing system, the transponder shall be verified in accordance with subsections 3.2, Wiring; and subsection 3.3 Control Units; and with CAN/ULC-S536, Standard for the Inspection and Testing of Fire Alarm Systems as well as re-verification of existing field devices and verification of new conventional field devices." If a new addressable device is added to a system, the new device is to be tested; as well a test must be conducted on all addressable devices on the loop.

.5 Clause 5.6: "Where an existing fire alarm system control unit is replaced with a new control unit, it shall be verified in accordance with CAN/ULC-S536, Standard for the Inspection and Testing of Fire Alarm Systems. Replacement of any control panel will require the testing of all existing fire alarm devices.

.2 The Contractor and subcontractors shall include in the bid price for the above ULC Standards requirements referenced in the Ontario Building Code.

## 1.10. INSTALLATION AND/OR REPAIR OF ROOFING

.1 The Contractor will review with the Consultant and the Board's representative of the location of any asphalt kettles and the dates the kettles will be in use. The Contractor, in the course of performing roofing work, will ensure all personnel utilize the following precautions:

.1 Use only kettles equipped with thermometers or gauges in good working order.

.2 Locate kettles in a safe place outside of the building.

.3 Maintain continuous supervision while kettles are in operation and provide metal covers for the kettles to smother any flames in case of fire.

.4 All roofing materials stored in locations no closer than 15 meters to any structures.

## 1.11. FIRE DEPARTMENT ACCESS

.1 Designated fire routes must be maintained. The Fire Department must be advised of any work that would impede fire apparatus response.

## 1.12. SMOKING PRECAUTIONS

.1 Smoking is not permitted anywhere on Board properties. Workers who wish to smoke must leave the property, and not within sight of students. Any worker found to be in contravention of the Ontario Smoke Free Act will be subject to legislated fines.

## 1.13. FLAMMABLE LIQUIDS

.1 The handling and storage on site of flammable liquids are to be governed by the current National Fire Code of Canada.

.2 Flammable liquids such as gasoline, kerosene and naphtha may be kept for ready use in quantities not exceeding 10 imperial gallons provided they are stored in approved safety cans bearing the Underwriter's Laboratory of Canada or Factory Mutual seal of approval.

.3 Transfer of flammable liquids is prohibited within buildings.

.4 Transfer of flammable liquids must not be carried out in the vicinity of open flame or any type of heat producing devices.

.5 Flammable liquids having a flashpoint below 100° F (37.7°C) such as naphtha or gasoline must not be used as solvents or cleaning agents.

.6 Flammable waste liquids, for disposal, must be stored in approved containers located in a safe ventilated area. Quantities are to be kept to a minimum.

**END OF SECTION**

## Appendix 013517-A Contractor Hot Work Permit

Waterloo Region District School Board

# Appendix - 013517-A

Facility Services

## CONTRACTOR HOT WORK PERMIT

**STOP!**
**Avoid hot work or seek an alternative method if possible.**

This hot work permit is required for any temporary operation involving open flames or producing heat and/or sparks.
This includes but is not limited to: brazing, cutting, grinding, soldering, torch-applied roofing and welding.
**A SEPARATE PERMIT IS REQUIRED FOR EACH AREA**

Board Supervisor/ Manager/Proj. Coordinator Responsibilities:
i. Verify precautions taken in Section A
ii. Complete and retain Part 1
iii. Complete Section B prior to commencement of Hot Works
iv. Issue Part 2 to Contractor completing Hot Work & Post
v. Obtain Part 2 when Fire Monitoring complete
vi. Return Part 1 and Part 2 to Controller, Facility Services

Contractor Responsibilities:
i. Verify precautions taken in Section A
ii. Complete Section C during each day that Hot Works takes place
iii. Return Part 2 to Board Supervisor/ Manager/Proj. Coordinator

PART 1

**Section A Indicate Precautions Taken**

- ☐ Available sprinklers, hose streams, and extinguishers available and in service

**Within 35' or 11m of hot work**

- ☐ Flammable liquid, dust, lint and oily deposits removed
- ☐ Explosive atmosphere in area eliminated
- ☐ Floors swept clean
- ☐ All wall and floor openings covered
- ☐ Combustible floors covered with fire resistant sheets
- ☐ Protect or shut down ducts that might carry sparks/smoke

**Hot work on walls, ceiling or roofs**

- ☐ Construction is noncombustible and without combustible covering or insulation
- ☐ Combustible materials on other side of walls, ceilings or roofs moved away
- ☐ Combustible structure wetted down

**Hot work on enclosed equipment**

- ☐ Enclosed equipment cleaned of all combustible material
- ☐ Containers purged of flammable liquid/vapour
- ☐ Pressurized vessels, piping & equipment removed from service, isolated & vented

**Fire watch/hot work and monitoring**

- ☐ Fire watch will be provided during and for 1 hour after work including break
- ☐ Fire watch is trained and supplied with suitable extinguishers
- ☐ Fire watch is trained in the use of sounding fire alarm
- ☐ Fire watch conductec in adjoining areas, above and below the space where appropriate
- ☐ Monitor hot work area for an additional 2 hours after fire watch
- ☐ Other precautions taken (please detail):

_____
_____
_____
_____

**Section B Authorization Granted**

Board Supervisor/Manager/Proj. Coordinator: _____
Print Name _____ Signature

Permit Valid from / to: (max. 7 days) _____ From This Date _____ To This Date

**(Maximum 7 days or until end of hot work whichever is sooner)**

**Section C Contractor and Location Affected**

| Dates: (max 7 days) | Name of Contractor conducting hot work | Name & signature of individual assigned to fire watch | Name & signature of individual assigned to fire monitoring |
|---|---|---|---|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

School:

Room/Area: _____

Nature of Job: _____

I verify the above location has been examined each day, the precautions listed in Section A have been taken each day, and permission is authorized for this work.
I further acknowledge that if activity is during school operational hours, that appropriate notification has been given to school administration.

Hot Works Contractor: _____
Signature

School Administrator notified: _____
Print Name

**In Case of Emergency call: 911 - Then call: 519-570-0003 Ext. 4123**

Refer to WRDSB Administration Procedure 1200 Hot Works/Fire Watch (Copies Available on Request)

I:\Facility Srv\Controller\Board Procedures\2014-15\Hot Work Permit - Contractors - Final.xls

**01 35 23 – Health and Safety**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 31 00 - Project Managing and Coordination.

.2 Section 01 33 00 - Submittal Procedures.

.3 Section 01 35 17 – Fire Safety Requirements

.4 Section 01 35 43 –**Designated Substances**

.5 Section 01 41 00 – Regulatory Requirements

.6 Section 01 53 00 – Temporary Construction Facilities

.7 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. REFERENCES

.1 Province of Ontario, including requirements for a "Prime Contractor" as defined by the Act.

### 1.3. SAFETY PLAN

.1 Develop written site-specific Health and Safety Plan based on hazard assessment prior to commencing any site Work and continue to implement, maintain, and enforce plan until final demobilization from site. The Health and Safety Plan must address project specifications.

.2 Consultant may respond in writing, where deficiencies or concerns are noted and may request resubmission with correction of deficiencies or concerns.

.3 Be governed by pertinent safety requirements of Federal or Provincial Governments and of municipal bodies having authority, particularly the Ontario Construction Safety Act, The Occupational Health and Safety Act for Ontario, and regulations of Ontario Ministry of Labour, and work in conjunction with proper safety associations operating under the authority of Ontario Workers' Compensation Act. Protect Owner, Owner's employees, the public and those employed on the Work from bodily injury and to protect adjacent public and private property and Owner's property from damage. Furnish and maintain protection, such as warning signs, tarpaulins, guard rails, barriers, guard lights, night lights, railings around shafts, pits and stairwells, etc. as required. Remove temporary protective measures when no longer required.

## 1.4. TEMPORARY WORK

.1 Temporary work requiring engineering proficiency for the design, erection, operation maintenance and removal shall be designed and bear the stamp of the registered professional Engineer or Architect. Detail drawings will be submitted to the Consultant for review prior to commencing any work.

.2 Before a temporary structure is used, the person responsible for design, or their representative, shall inspect the structure and certify it has been constructed according to their design.

## 1.5. RESPONSIBILITY

.1 The "Prime Contractor" according to applicable local jurisdiction, is responsible for health and safety of persons on site, safety of property on site and for protection of persons adjacent to site and environment to the extent that they may be affected by conduct of Work.

.2 Comply with and enforce compliance by employees with safety requirements of Contract Documents, applicable federal, provincial, territorial, and local statutes, regulations, and ordinances, and with site-specific Health and Safety Plan.

.3 Should any unforeseen or peculiar safety-related factor, hazard, or condition become evident during performance of Work, and follow procedures in place for Employee's Right to Refuse Work in accordance with Acts and Regulations of Health and Safety Act having jurisdiction. Advise the Board and the Consultant verbally and in writing.

.4 The Contractor shall make their own arrangements for emergency treatment of accidents. Any accidents shall be reported immediately to the Board contact.

.5 The Contractor agrees to hold the Board harmless of any and all liability of every nature and description, which may be suffered through bodily injuries, involving deaths of any persons, by reasons of negligence of the Contractor, his agents, employees, or his subcontractors.

## 1.6. SUBMITTALS

.1 Make submittals in accordance with Section 01 33 00.

.2 Submit site-specific Health and Safety Plan: Within ten (10) days after the date of Notice to Proceed and prior to commencement of Work. Health and Safety Plan must include:

.1 Results of site specific safety hazard assessment.

.2 Results of safety and health risk or hazard analysis for site tasks and operation

.3 Submit one (1) copy of Contractor's authorized representative's work site health and safety inspection reports to Consultant and Owner.

.4 Submit copies of reports or directions issued by Federal, Provincial and Territorial health and safety inspectors.

.5 Submit copies of incident and accident reports.

.6 Submit Material Safety Data Sheets (MSDS) to Consultant.

.7 Consultant's review of Contractor's final Health and Safety plan should not be construed as approval and does not reduce the Contractor's overall responsibility for construction Health and Safety.

.8 Medical Surveillance: Where prescribed by legislation, regulation or safety program, submit certification of medical surveillance for site personnel prior to commencement of Work, and submit additional certifications for any new site personnel to Consultant.

.9 On-site Contingency and Emergency Response Plan: Address standard operating procedures to be implemented during emergency situations.

.10 File Notice of Project with the Ministry of Labour prior to commencement of Work.

## 1.7. SAFETY ACTIVITIES

.1 Perform site specific safety hazard assessment related to the project.

.2 Schedule and administer Health and Safety meeting with Consultant prior to commencement of Work.

.3 Perform Work in accordance with Section 01 41 00 - Regulatory Requirements and this section.

## 1.8. HEALTH AND SAFETY COORDINATOR

.1 Employ and assign to Work, competent and authorized representative as Health and Safety Coordinator. Health and Safety Coordinator must:

.1 have previous experience as a Health & Safety coordinator,

.2 have working knowledge of occupational safety and health regulations,

.3 be responsible for completing Contractor's Health and Safety Training Sessions and ensuring that personnel not successfully completing required training are not permitted to enter site to perform Work,

.4 be responsible for implementing, enforcing daily and monitoring site-specific Contractor's Health and Safety Plan, and

.5 be on site during execution of Work.

## 1.9. POSTING OF DOCUMENTS

.1 Ensure applicable items, articles, notices and orders are posted in conspicuous location on site in accordance with Acts and Regulations of Health and Safety Act having jurisdiction, and in consultation with Consultant.

## 1.10. CORRECTION OF NON-COMPLIANCE

.1 Immediately address health and safety non-compliance issues identified by authority having jurisdiction or by Consultant or by the Board.

.2 Provide Consultant and/or Board with written report of action taken to correct non-compliance of health and safety issues identified.

.3 Consultant and or the Board may stop Work if non-compliance of health and safety regulations is not corrected.

## 1.11. PROJECT/SITE CONDITIONS

.1 Work at site will involve contact with:

.1 Refer to Section 01 35 43 **Designated Substances**

## 1.12. HAZARDOUS WORK

.1 Blasting or other use of explosives is not permitted at the place of work.

## 1.13. WORK STOPPAGE

.1 Give precedence to safety and health of public and site personnel and protection of environment over cost and schedule considerations for Work.

## 1.14. LOCKOUT PROCEDURES

.1 All Work to be done on electrical systems or machinery, where the unexpected switching on of the system or machinery could result in personal injury to a student, staff, employee, or the Contractor's employee, must be done in accordance with the Contractor's standard lockout procedure.

.2 The Contractor shall provide his/her own locks for the above procedure.

.3 The lock shall include contact information for the person(s) locking out such devices.

## 1.15. OVERHEAD LIFTING

.1 Under no circumstances will a crane or lifting device be used over an occupied space.

.2 When working adjacent to occupied spaces, ensure a clearance of one (empty) classroom, or a minimum of 10m between any occupied space and the furthest possible reach of the crane.

## 1.16. WARNING SIGNS AND NOTICES

.1 Notices shall be posted advising of the hazard but will not be considered a substitute for providing approved protection, separation, and space from the hazard.

## 1.17. FIRE PROTECTION

.1 Provide and maintain temporary fire protection equipment during performance of Work required by the governing codes, regulations and bylaws.

.2 Burning rubbish and construction waste materials is not permitted on site.

.3 Maintain placed or installed Fire Protection to protect the portions of the Work during construction.

## 1.18. SCENT-FREE ENVIRONMENT

.1 The Board requires that, where advised, a building may be deemed scent-free and as such, the wearing of scented products is prohibited.

.2 Any methods or materials that are found to create negative responses in staff or students shall cease and be removed under advisement of the Consultant and or the Board, until alternate methods can be determined.

**END OF SECTION**

**01 35 43 –Designated Substances**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 35 23 – Health and Safety Requirements.

.2 Section 01 41 00 – Regulatory Requirements.

.3 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. REFERENCES

.1 Province of Ontario, including requirements for a "Prime Contractor" as defined by the Act.

### 1.3. ASBESTOS and OTHER REGULATED SUBSTANCES

.1 An Asbestos Audit, as prepared by WRDSB retained consultants, for this facility, is attached under Appendix 01 35 43A. A duplicate set is also available in the Facilities Services Departments located in the Education Centre. Unless specifically covered by a Cash Allowance or Contingency Allowance that states otherwise, include in this Contract the required removal of all asbestos containing materials (ACM) to complete the work. No claims for extra costs will be accepted for areas known to contain ACM that are within the scope of this Work.

.2 A Project Specific Designated Substance/ Lead Report, as prepared by WRDSB retained consultants or Environmental Officer for this facility, is attached under Appendix 01 35 43B.

.3 Comply with applicable legislation regarding asbestos. Should the Contractor encounter asbestos not noted in the referenced Asbestos Audit that would be disturbed during the course of the Work, they should stop the work in that immediate area and report the same to the Consultant and Board contact.

.4 In addition, Lead, Mercury, Silica, and Isocyanates are anticipated to be present in existing facilities. New construction, renovations, or alterations require compliance by the Contractor with the applicable legislation.

### 1.4. PROTOCOL FOR ABATEMENT WORK

.1 This Protocol establishes the requirements to be followed by all Asbestos Abatement Contractors working in buildings owned or operated by the Waterloo Region District School Board (hereinafter referred to as the Board). This protocol applies to Type 1,

Type 2 and Type 3 Operations as identified in the most current form of Ontario Regulation 278 as amended, and applies to both emergency and non-emergency work, whether directly retained by the Board or working as a subcontractor to a General Contractor retained by the Board.

.2 Asbestos Abatement Contractors must maintain appropriate insurance coverage and WSIB certification and provide proof upon request.

.3 Asbestos Abatement Contractors shall only use personnel certified by the Ontario College of Trades and must provide the Board with proof of asbestos certification (AAS and AAW) for all supervisors and all staff involved.

.4 School Access: During regular school hours, all abatement contractors are to report to the school office upon arrival. They must sign in all personnel and identify to a person of authority, preferably the Principal, their purpose for being there as well as the area of work. After school hours, ensure card-in/card-out procedures are followed and building security is maintained. Contractor staff shall NOT prop doors open, and ensure that doors are locked.

.5 Communication:

.1 Asbestos Abatement Contractor will contact the school's Principal and/or Vice Principal (phone numbers are available on the WRDSB website) to set up a firm date and time for the abatement (removal/repair). This communication shall allow at least 72 hours notice ahead of the proposed work unless it is emergency work.

.2 Confirmation of the date shall be via email to the following:

.1 Principal / Vice-principal

.2 Facility Manager

.3 Environmental Officers (environmental@wrdsb.ca)

.3 When working under a general contractor, also notify:

.1 Project manager for the General Contractor

.2 Architect/Consultant for the project

.3 The Board's Project Coordinator

.4 This communication shall indicate the date, the start time, the anticipated completion time (including any required air clearances and teardowns), the asbestos abatement type, and the areas of work within the school or building. It should also identify any mechanical equipment that is required to be disabled for the duration of the operations.

.5 For emergency work where requested by Area Supervisors, Facility Managers, On-Call Manager/Supervisor, or Environmental Officers, no notification to the school is required by the abatement contractor. Notification to the Principal or

Vice-Principal will be managed by the Area Supervisor, Facility Manager, On-Call Manager/Supervisor, or Environmental Officers.

.6 For **Type 2 Removals**, also notify: the Ministry of Labour, Immigration, Training and Skills Development (MLITSD) where required by Regulation.

.7 For Type 3 Removals, also notify: Manager of Health, Safety & Security, (healthandsafety@wrdsb.ca); and, the MLITSD where required by Regulation.

.8 Discussions related to the work, whether with media, school staff, or any others, is NOT permitted. Questions or enquiries shall be directed to the Board's Communication Officer (comms-team@wrdsb.ca) by the person(s) seeking information, where warranted.

.6 Asbestos Removal Assessment

.1 When working directly with the Board to undertake non-emergency abatement, the contractor is to assess the work on site and provide a cost estimate to the Environmental Officer. Some work will require discussion with the Facility Manager or Environmental Officer to determine if additional work should be done to completely remove all additional ACM material from the area or similar.

.2 When abatement is to be done under a General Contractor, the proposed work is to be quoted directly to the General Contractor. Additional abatement not already within the original scope of work or tender is to be quoted to the General Contractor for approval by the Project Coordinator or Architect.

.7 Asbestos Operations

.1 Asbestos operations shall be conducted according to Type, where each Type will require special timing and considerations as follows:

.2 **Type 1:** Any time behind a secured door or enclosure.

.3 **Type 2:** Any time when students and teaching staff are NOT present in the building, and behind a secured door or enclosure. During the school year, the work shall be performed outside of the regular program hours, Monday to Friday, anytime on weekends, when no regular programs are scheduled.

.4 The work shall be performed anytime during March Break, Winter Break, and Summer Break, when teaching staff are NOT present in the building.

.5 **Type 3:** Outside of school regular program hours, during unoccupied times, and behind a secured door or enclosure. During the school year, the work shall be performed outside of the regular program hours, Monday or Friday, anytime on weekends, provided all rentals are cancelled and card access is restricted for teaching staff entering the facility.

.6 The work shall be performed anytime during March Break, Winter Break, and Summer Break, provided all rentals are cancelled and card access is restricted for teaching staff entering the facility

.7 Facility Services personnel and Office staff may be present in the building due to training in Asbestos Awareness.

.8 All Type 3 work must consider one (1) additional day in case the clearance sampling fail.

.9 Emergency work shall be carried out the same day (evening/night) or under exceptional conditions the following day/evening/night. Contractors shall exercise discretion when working in the school to minimize the potential for health and safety concerns by the staff, students, and school community. Where warranted, contact Area Supervisor, Facility Manager, On-Call Manager/Supervisor, or Environmental Officer to obtain further direction.

.10 Before beginning any Type 1, Type 2, or Type 3 Operations, the work area must be secured, all doors locked, WHITE poly and caution tape used in open areas/corridors and “construction” warning signs added to all access points to keep school staff and students clear of all work areas.

.11 If the work area is in use by Board staff, contact the Area Supervisor to assist in vacating the area. If unable, contact the Area Supervisor, Facility Manager, On-Call Manager/Supervisor, Environmental Officer, or Project Coordinator to reschedule the work.

.12 Board preference is to use “construction” warning signs at all areas accessible to school staff and students. Behind those secured areas, a sufficient number of “asbestos” signs, posted in compliance with O. Reg. 278/05.

.13 The Asbestos Abatement Contractor is responsible to disable the air handling unit/fan serving the work area (school wing, floor, or multiple floors if air handling unit/fan serve more than one floor) and prevent operation using Lock-out/Tag-out devices for each air handling unit/fan. Exercise caution during the heating season to ensure areas of the building are maintained above freezing and ensure equipment is turned back on after abatement/air clearance completed.

.14 Asbestos Abatement Contractor’s employees shall put on/take off PPE within the work area marked by construction signs. No employee shall leave the work area wearing PPE.

.15 All dust and waste is to be cleaned up and removed at frequent/regular intervals as the work proceeds and immediately upon completion, but no later than the end of the work day. No waste bags or similar are to be left behind.

No additional construction work shall be performed by an Asbestos Abatement Contractor.

## 1.5. SUBMITTALS

.1 Once the abatement is completed, forward a Letter of Completion to the Environmental Officers (environmental@wrdsb.ca). This letter shall be received no later than 72 hours after completion of each abatement area/phase and shall include any sample results. The letter must also clearly identify what specifically has been abated and where (Fixed Reference Numbers), so that this information can be attached to the current AAU Asbestos Audits for future updates.

.2 For those projects requiring air clearance, ensure this info is sent without delay but in all cases no later than 24 hours after sampling. All Type 3 work must take into account that the initial samples may not pass and the contractor must allow one (1) additional day to re-clean and re-sample before school is to resume operations. For those projects not under the direct supervision of an Environmental Consultant, the contractor is to expedite the air clearance sampling with the lab of their choice and carry these costs.

.3 Forward Air Clearance results to:

- .1 Principal/Vice-principal (contact info sent with Work Request)
- .2 Facility Manager (contact info sent with Work Request)
- .3 Environmental Officers (environmental@wrdsb.ca)
- .4 Manager of Mechanical, Electrical and Environmental Services (lou_lima@wrdsb.ca)
- .5 Manager of Health, Safety & Security (healthandsafety@wrdsb.ca)
- .6 Project team when working under a General Contractor

## 1.6. ACKNOWLEDGEMENT

.1 The protocols for asbestos work must be read and understood by Asbestos Contractor.

.2 Submit a signed copy of the most current copy of *PROTOCOL FOR ABATEMENT WORK (ASBESTOS ABATEMENT CONTRACTORS)* to the General Contractor, the Consultant, and the Board's Environmental Officer.

**END OF SECTION**

## Appendix 01 35 43A Asbestos Audit Report

# Galt Collegiate Institute

## 2024 Asbestos Audit Update Report

**Project Location:**
200 Water Street North, Cambridge, ON

**Prepared for:**
Waterloo Region District School Board
51 Ardelt Avenue
Kitchener, ON  N2C 2R5

**Prepared by:**
MTE Consultants
520 Bingemans Centre Drive
Kitchener, ON  N2B 3X9

January 17, 2024
**Revision:** June 24, 2024

**MTE File No.:** C34532-944

*Engineers, Scientists, Surveyors.*

MTE Consultants
520 Bingemans Centre Drive, Kitchener, Ontario N2B 3X9

January 17, 2024
**Revision:** June 24, 2024

MTE File No.: C34532-944

Waterloo Region District School Board
51 Ardelt Avenue
Kitchener, ON N2C 2R5

**RE: 2024 Asbestos Audit Update – Galt Collegiate Institute**
**200 Water Street North, Cambridge, Ontario**

## 1.0 INTRODUCTION

MTE Consultants Inc. (MTE) was authorized by the Waterloo Region District School Board (WRDSB) to conduct the 2024 Asbestos Audit Update for the subject building.

The purpose of the assignment was to re-assess and document the location, type, and condition of identified asbestos-containing materials (ACM) present within the building and make appropriate recommendations for management, abatement or remedial activities, as required.

The audit was conducted in accordance with the Ontario Ministry of Labour, *Regulation 278/05-Designated Substance-Asbestos on Construction Projects and in Buildings and Repair Operations* (O. Reg. 278/05). This report shall replace previous audit reports.

## 2.0 SCOPE OF WORK

The Scope of Work for this assessment was completed by MTE and included the following activities:

- Review of existing and historical reports and documentation pertaining to ACM within the building;
- Visual inspection to assess the condition of previously identified ACM, excluding portable structures;
- Collection of building material samples that are suspect ACM, as applicable;
- Submission of samples to an accredited laboratory, as applicable;
- Photographic log of damaged materials; and
- Preparation of this report with findings and recommendations.

## 3.0 METHODOLOGY AND ASSESSMENT CRITERIA

This inspection was conducted by visual and laboratory identification methods for the assessment of ACM and their corresponding location, use, condition, and friability. The areas outlined in Section 2.0 were inspected limited to building components, materials and service connections. Notwithstanding that reasonable attempts were made to identify all ACMs, the possibility of concealed material exists and may not become visible until substantial demolition has occurred and therefore are currently undocumented and did not include the following.

- The following rooms:
  - WRDSB Room 168 – Hydro One electrical room and school staff do not have access keys.
  - WRDSB Room 179 – Not accessible with on keys on site and school staff did not have access keys.
  - WRDSB Room 915 – Not accessible due to warning that alarm will be activated. Emergency stairwell only.
  - WRDSB Room 204E – Not accessible with on keys on site and school staff did not have access keys.
- Locations that may be hazardous to the surveyor, such as electrical equipment.
- Where invasive inspection could cause consequential damage to the property or impair the integrity of the equipment, such as roof systems, underground services or components of mechanical equipment.
- Locations concealed by building finishes that require substantial demolition or removal for access or determination of quantities.
- Materials that is present in such an inconsistent fashion that without complete removal of finishes, the extent cannot be determined.
- Non-permanent items or personal contents, furnishings.
- Settled dust or airborne agents unless otherwise stated.

## 3.1 Condition of ACM

During the audit process the general condition of ACMs were observed and noted. Materials which are damaged can pose an increased exposure risk to workers, building occupants and the public. While assessing damage can be subjective, abatement items were grouped into two categories to aid in remedial prioritization.

*Monitor Annually*

These are items which display minor isolated damage; however, do not pose an immediate risk to workers from exposure to asbestos fibres due to the current condition of the material and/or location. No remediation is required at this time; however, these items should be monitored on a yearly basis for evidence of continued degradation. Should the condition of the material change, an evaluation should be completed by a competent person to determine remedial action.

*Abatement Action Required*

These are items which display damage and may pose potential risk to workers from exposure to asbestos fibres due to the physical condition and/or location of the material. Clean-up, repair or removal of these materials is required as soon as reasonably possible.

# 4.0 FINDINGS

An inspection of the building was conducted by MTE on January 3, 2024. The 4-storey school was constructed in 1853 with additions in 1876, 1906, 1923, 1954, 1956, 1962, and 1986. The inspection did not include areas of post 1990 construction or renovation (where all building finishes have been removed and replaced), as applicable.

The Asbestos Management Database is provided in **Appendix A** and associated Figures are provided in **Appendix B**. These together provide a current summary of the ACM identified throughout the building.

A summary of the damaged ACM identified at the time of the inspection is provided in **Appendix C**.

## 4.1 Analytical Results

During this inspection, no samples were collected.

Refer to Appendix C, Table 3 for a detailed summary of the analytical results for each sampled material.

## 4.2 Removed ACM

A summary of ACM that has been removed since the previous audit/inspection is provided below:

WRDSB Room 101

- 3 parged pipe fittings.

WRDSB Room 103

- 4 parged pipe fittings.

WRDSB Room 103A

- 2 parged pipe fittings.

WRDSB Room 105A

- 12”x12” beige with brown vinyl floor tile.

WRDSB Room 111

- 1 parged pipe fitting.
- Window caulking.

WRDSB Room 175

- 200 ft² of Transite ceiling.

WRDSB Room 177

- 2 parged pipe fittings.

WRDSB Room 266A-E, 265A-C, & 267

- 2’x2’ long thin fissure ceiling tile.

## 4.3 Discovery of Additional ACM

ACM or suspect ACM that was not previously identified includes the following:

Non-Friable Material:

- WRDSB Room 213A – 4 duct expansion joints.

### 4.4 Damaged ACM

Damaged ACM was identified. Refer to **Appendix C, Tables 1** and **2** for a detailed summary of required actions, specific to each material. At the time of the audit, all other ACM at the building was noted to be in good condition.

## 5.0 RECOMMENDATIONS

### 5.1 Remedial

Damaged ACM was identified. Refer to Appendix C, Tables 1 and 2 for a detailed summary of required actions, specific to each material. At the time of the audit, all other ACM at the building was noted to be in good condition.

Type 1 abatement Operations may be conducted internally by trained and qualified WRDSB staff. All other abatement work must be conducted by certified asbestos contractors trained and qualified to conduct the type of work required.

All asbestos work must be conducted by staff and/or contractors who are trained and experienced in the type of asbestos operations required, and should be overseen by a qualified third party Health, Safety and Environmental professional. In order to conduct Type 3 asbestos operations, contractors must be certified as Asbestos Abatement Workers AAW (Trade code 253W) and Asbestos Abatement Supervisors AAS (Trade code 253S) by The Ministry of Training, Colleges and Universities (Ministry of Advanced Education and Skills Development) as prescribed by Section 20 of O. Reg. 278/05.

### 5.2 Long Term Management

This audit was conducted for the long term management of ACM within the building. Prior to future construction or renovation projects, additional assessments and/or sampling may be required.

There are no requirements under current legislation to remove ACM from a building simply because it is present. However, O. Reg. 278/05 requires that an Asbestos Management Plan be implemented and maintained. Asbestos awareness training should be provided for staff that may come in contact with ACM during routine duties or in emergency situations.

ACM that will be disturbed, or will likely be disturbed, during building maintenance, renovations, construction, or demolition activities must be handled and disposed of in accordance with the procedures prescribed by O. Reg. 278/05.

ACM may also be present in concealed locations. If any construction, renovation, alteration, or maintenance activities are required or planned, invasive inspections of concealed locations for potential ACM must be performed prior to such activities. Should any suspect ACM be discovered, work should cease and the materials should not be disturbed. Suspect ACM must be treated as asbestos-containing or sampled and proven to not contain asbestos. Any activities that require disturbance of ACM must be performed in accordance with O. Reg. 278/05.

## 6.0 LIMITATIONS

Services performed by **MTE Consultants Inc.** (MTE) were conducted in a manner consistent with the level of care and skill ordinarily exercised by members of the Environmental Engineering & Consulting profession. No other representation expressed or implied as to the accuracy of the information, conclusions or recommendations is included or intended in this report.

This report was completed for the sole use of MTE and the Client. It was completed in accordance with the approved Scope of Work referred to in Section 2.0. As such, this report may not deal with all issues potentially applicable to the site and may omit issues that are or may be of interest to the reader. MTE makes no representation that the present report has dealt with all-important environmental features, except as provided in the Scope of Work. All findings and conclusions presented in this report are based on site conditions, as they existed during the time period of the investigation. This report is not intended to be exhaustive in scope or to imply a risk-free facility.

Any use which a third party makes of this report, or any reliance on, or decisions to be made based upon it, are the responsibility of such third parties. MTE accepts no responsibility for liabilities incurred by or damages, if any, suffered by any third party as a result of decisions made or actions taken, based upon this report. Others with interest in the site should undertake their own investigations and studies to determine how or if the condition affects them or their plans.

It should be recognized that the passage of time might affect the views, conclusions and recommendations (if any) provided in this report because environmental conditions of a property can change. Should additional or new information become available, MTE recommends that it be brought to our attention in order that we may re-assess the contents of this report.

All of which is respectfully submitted,

**MTE Consultants Inc.**

**Zack Hopkins, B.E.S.**
Technologist, Indoor Environments
519-743-6500 ext. 1300
zhopkins@mte85.com

**Paul Semeniuk, B.E.S., C.E.T.**
Manager, Indoor Environments
519-743-6500 ext. 1324
psemeniuk@mte85.com

ZJH: jmm
Attach.
M:\34532\944\1 - Reports\4 - Formatted\Galt CI\1-June 2024 Revision\34532-944_2024-06-24_Rpt_AAU_Galt CI - Revision.docx

# Appendix A

# Asbestos Management Database

| | School Name | Legend: | Notes: |
|---|---|---|---|
| | **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| | **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| | Original: 1853 | | |
| | Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | | | | | |
| **Structure/Additions** | | | | | | | | | | |
| | | | | | | | | | | |
| | Throughout | Structure | Concrete | Concrete | - | Non ACM | - | - | - | - |
| | Throughout | Façade | Brick Veneer | Brick and Mortar | - | Non ACM | - | - | - | - |
| | Throughout | Not Inspected | Not Inspected | Roofing Materials | NF | Suspect ACM | VC | - | - | - |
| | Throughout | Ceiling | 1'x1' Ceiling Tile Mastic | Mastic on Medium and Small Pinhole (Cellulose) | - | Non ACM | SL | S02ABC | 11/14/2018 | ND |
| | Throughout | Ceiling | 1'x1' Ceiling Tile Mastic | Mastic on Random Pinhole | - | Non ACM | SL | S01ABC | 11/14/2018 | ND |
| | Throughout | Ceiling | 1'x1' Ceiling Tile Mastic | Patterned Pinhole | NF | ACM | HM | GCI-207-1x1ACT | 20-Mar-07 | 1% Amosite |
| | Original Building | Structure | Deck | Wood | - | Non ACM | - | - | - | - |
| | Original Building | Windows | Interior Panes | Black Sealant | NF | ACM | SL | S23 | 28-Jun-18 | 5% Chrysotile |
| | Original Building | Windows | Exterior Frames | Not Inspected | | | | | | |
| | Original Building | Windows | Exterior Panes | Not Inspected | | | | | | |
| | Original Building | Floor | Mastic | Black Mastic | - | Non ACM | SL | 32523-800-Galt-S08 | 16-Mar-09 | ND |
| | 1876 Addition | Structure | Deck | Wood | - | Non ACM | - | - | - | - |
| | 1876 Addition | Windows | Exterior Frames | Not Inspected | | | | | | |
| | 1876 Addition | Windows | Exterior Panes | Not Inspected | | | | | | |
| | 1876 Addition | Floor | Mastic | Black Mastic | - | Non ACM | SL | S24 | 28-Jun-18 | ND |
| | 1906 Addition | Structure | Deck | Wood | - | Non ACM | - | - | - | - |
| | 1906 Addition | Windows | Interior Frames | Beige Sealant | - | Non ACM | SL | S16 | 28-Jun-18 | ND |
| | 1906 Addition | Windows | Interior Panes | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1906 Addition | Windows | Exterior Frames | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1906 Addition | Windows | Exterior Panes | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1906 Addition | Doors | Interior Frames | White Sealant | - | Non ACM | SL | S15 | 28-Jun-18 | ND |
| | 1906 Addition | Doors | Exterior Frames | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1906 Addition | Doors | Exterior Panes | White Sealant | - | Non ACM | SL | S14 | 28-Jun-18 | ND |
| | 1906 Addition | Floor | Mastic | Black Mastic | | Non ACM | SL | 32523-800-Galt-S03a | 16-Mar-09 | ND |
| | 1923 Addition | Structure | Deck | Wood | - | Non ACM | - | - | - | - |
| | 1923 Addition | Windows | Interior Frames | Grey Sealant | - | Non ACM | SL | S11 | 28-Jun-18 | ND |
| | 1923 Addition | Windows | Interior Panes | Grey Sealant | - | Non ACM | SL | S11 | 28-Jun-18 | ND |
| | 1923 Addition | Windows | Exterior Frames | Grey Sealant | - | Non ACM | SL | S11 | 28-Jun-18 | ND |
| | 1923 Addition | Windows | Exterior Panes | Grey Sealant | - | Non ACM | SL | S11 | 28-Jun-18 | ND |
| | 1923 Addition | Doors | Interior Frames | White Sealant | - | Non ACM | SL | S10 | 28-Jun-18 | ND |
| | 1923 Addition | Doors | Interior Panes | Grey Sealant | - | Non ACM | SL | S09 | 28-Jun-18 | ND |
| | 1923 Addition | Doors | Exterior Frames | Beige Sealant | - | Non ACM | SL | S12 | 28-Jun-18 | ND |
| | 1923 Addition | Doors | Exterior Panes | Black Sealant | NF | ACM | SL | S13 | 28-Jun-18 | 0.5% Chrysotile |
| | 1923 Addition | Floor | Mastic | Black Mastic | NF | ACM | SL | 32523-800-Galt-S07a | 16-Mar-09 | 0.5% Chrysotile |
| | 1929 Addition | Structure | Deck | Wood | - | Non ACM | - | - | - | - |
| | 1929 Addition | Windows | Interior Frames | Beige Sealant | - | Non ACM | SL | S27 | 28-Jun-18 | ND |
| | 1929 Addition | Windows | Interior Panes | Black Sealant | NF | ACM | SL | S26 | 28-Jun-18 | 8% Chrysotile |
| | 1929 Addition | Windows | Exterior Frames | Not Inspected | | | | | | |
| | 1929 Addition | Windows | Exterior Panes | Not Inspected | | | | | | |
| | 1929 Addition | Floor | Mastic | Black Mastic | - | Non ACM | SL | S28 | 28-Jun-18 | ND |

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | **School Name** | | **Legend:** | | | | | **Notes:** | | | |
| | **Galt Collegiate Institute** | | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | | | | | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** | | | |
| | **Date Built:** | | | | | | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** | | | |
| | Original: 1853 | | | | | | | | | | |
| | Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | | | | | | | | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| | 1954 Addition | Structure | Deck | Steel | - | Non ACM | - | - | - | - |
| | 1954 Addition | Windows | Interior Frames | Grey Sealant | NF | ACM | SL | S19 | 28-Jun-18 | 1% Chrysotile |
| | 1954 Addition | Windows | Interior Panes | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1954 Addition | Windows | Exterior Frames | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1954 Addition | Windows | Exterior Panes | Black Sealant | - | Non ACM | SL | S20 | 28-Jun-18 | ND |
| | 1954 Addition | Doors | Interior Frames | Grey Sealant | NF | ACM | HM | S19 | 28-Jun-18 | 1% Chrysotile |
| | 1954 Addition | Doors | Interior Panes | Black Sealant | - | Non ACM | HM | S20 | 28-Jun-18 | ND |
| | 1954 Addition | Doors | Exterior Frames | Grey Sealant | NF | ACM | SL | S21 | 28-Jun-18 | 1% Chrysotile |
| | 1954 Addition | Doors | Exterior Panes | Black Sealant | - | Non ACM | HM | S20 | 28-Jun-18 | ND |
| | 1956 Addition | Structure | Deck | Steel | - | Non ACM | - | - | - | - |
| | 1962 Addition | Structure | Deck | Steel | - | Non ACM | - | - | - | - |
| | 1962 Addition | Windows | Interior Frames | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1962 Addition | Windows | Interior Panes | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1962 Addition | Windows | Exterior Frames | Grey Sealant | NF | ACM | SL | S07 | 28-Jun-18 | 1% Chrysotile |
| | 1962 Addition | Windows | Exterior Panes | Black/Grey Sealant | NF | ACM | SL | S08 | 28-Jun-18 | 10% Chrysotile |
| | 1962 Addition | Doors | Interior Frames | Beige Sealant | - | Non ACM | SL | S06 | 28-Jun-18 | ND |
| | 1962 Addition | Doors | Interior Panes | Brown Sealant | NF | ACM | SL | S04 | 28-Jun-18 | 10% Chrysotile |
| | 1962 Addition | Doors | Exterior Frames | Silicon Sealant | - | - | - | - | - | - |
| | 1962 Addition | Doors | Exterior Panes | Silicon Sealant | - | - | - | - | - | - |
| | 1962 Addition | Floor | Mastic | Black Mastic | NF | ACM | SL | 32523-800-Galt-S15a | 16-Mar-09 | 1.2% Chrysotile |
| | 1986 Addition | Structure | Deck | Steel | - | Non ACM | - | - | - | - |
| | 1986 Addition | Windows | Interior Frames | Grey Sealant | NF | ACM | SL | S01 | 28-Jun-18 | 0.5% Chrysotile |
| | 1986 Addition | Windows | Interior Panes | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1986 Addition | Windows | Exterior Frames | Grey Sealant | NF | ACM | HM | S01 | 28-Jun-18 | 0.5% Chrysotile |
| | 1986 Addition | Windows | Exterior Panes | Black Sealant | NF | ACM | HM | S02 | 28-Jun-18 | 8% Chrysotile |
| | 1986 Addition | Doors | Interior Frames | Silicon Sealant | - | Non ACM | - | - | - | - |
| | 1986 Addition | Doors | Interior Panes | Black Sealant | NF | ACM | SL | S02 | 28-Jun-18 | 8% Chrysotile |
| | 1986 Addition | Doors | Exterior Frames | Grey Sealant | NF | ACM | SL | S03 | 28-Jun-18 | 1% Chrysotile |
| | 1986 Addition | Doors | Exterior Panes | Black Sealant | NF | ACM | HM | S02 | 28-Jun-18 | 8% Chrysotile |
| | 1986 Addition | Floor | Mastic | Black Mastic | - | Non ACM | SL | S08 | 20-Mar-15 | ND |
| | | | | | | | | | | |
| **Level 1** | | | | | | | | | | |
| | | | | | | | | | | |
| 100 | Custodial | Floor | 12"x12" Vinyl Floor Tile | White with Grey Fleck and Blue Fleck | - | Non-ACM | SL | 32523-800-Galt-S21 | 16-Mar-09 | ND |
| 100 | Custodial | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 100 | Custodial | Wall | Drywall | - | - | Non ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |
| 100 | Custodial | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 100 | Custodial | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | SL | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 100 | Custodial | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 100 | Custodial | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | SL | GCI-152-PI | 20-Mar-07 | ND |
| 101 | Classroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 101 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-103A-CP-01,02,03 | 20-Mar-07 | ND |
| 101 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 101 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 101 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 101 | Classroom | Piping | Expansion Joint | - | F | ACM | VC | - | - | - |
| 101A | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 101A | Classroom | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 101A | Classroom | Wall | Wood Paneling | - | - | Non-ACM | - | - | - | - |
| 101A | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 101B | Office | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 101B | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-103A-CP-01,02,03 | 20-Mar-07 | ND |
| 101B | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 101B | Office | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 102 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 102 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | SO02ABC | 20-Mar-07 | ND |
| 102 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 102 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 102A | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 102A | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 102A | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 102A | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 103 | Classroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 103 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 103 | Classroom | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 103 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 103 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 103 | Classroom | Ducting | Expansion Joint | - | NF | ACM | VC | - | - | - |
| 103A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 103A | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-103A-CP-01,02,03 | 20-Mar-07 | ND |
| 103A | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | SL | GCI-103A-1x1ACT | 20-Mar-07 | ND |
| 103A | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-103A-CP-01,02,03 | 20-Mar-07 | ND |
| 103A | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 103A | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 103B | Classroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 103B | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 103B | Classroom | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 103B | Classroom | Ducting | Expansion Joint | - | NF | ACM | VC | - | - | - |
| 104 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 104 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 104 | Classroom | Wall | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 104 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 104A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 104A | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 104A | Classroom | Wall | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 104A | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |

| | School Name | Legend: | Notes: |
|---|---|---|---|
| | **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| | **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| | Original: 1853 | | |
| | Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 105 | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige with Brown and White Fleck | NF | ACM | HM | 32523-800-Galt-S03 | 16-Mar-09 | 2.3% Chrysotile |
| 105 | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 105 | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 105 | Storage | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 105 | Storage | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 105A | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige with Brown and White Fleck | NF | ACM | HM | 32523-800-Galt-S03 | 16-Mar-09 | 2.3% Chrysotile |
| 105A | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 105A | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 106 | Computer Room | Floor | 12"x12" Vinyl Floor Tile | Cream and Burgundy | - | Non-ACM | SL | GCI-108-12x12FT | 20-Mar-07 | ND |
| 106 | Computer Room | Wall | Plaster | - | - | Non-ACM | SL | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 106 | Computer Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 106 | Computer Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 107 | Classroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 107 | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-19A-DWC-01,02,03 | 20-Mar-07 | ND |
| 107 | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 107 | Classroom | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 107 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 107 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 107 | Classroom | Ducting | Expansion Joint | - | F | ACM | VC | - | - | - |
| 107A | Classroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 107A | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 107A | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-19A-DWC-01,02,03 | 20-Mar-07 | ND |
| 107A | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 107A | Classroom | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 107A | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 107A | Classroom | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 107B | Classroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 107B | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-19A-DWC-01,02,03 | 20-Mar-07 | ND |
| 107B | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 107B | Classroom | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 107B | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 107B | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 107B | Classroom | Ducting | Expansion Joint | - | F | ACM | VC | - | - | - |
| 107C | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 107C | Storage | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 107C | Storage | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 107C | Storage | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 107C | Storage | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 107D | Corridor | Floor | Vinyl Sheet Flooring | Smokey Cloud | - | Non-ACM | HM | 32523-800-Galt-S16 | 16-Mar-09 | ND |
| 107D | Corridor | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 107D | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 107D | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 108 | Computer Room | Floor | 12"x12" Vinyl Floor Tile | Cream and Burgundy | - | Non-ACM | SL | GCI-108-12x12FT | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 108 | Computer Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 108 | Computer Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 108 | Computer Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 108 | Computer Room | Piping | Pipe Fitting | Parged Cement | - | Non-ACM | SL | GCI-108-PARGE-01,02,03 | 20-Mar-07 | ND |
| 109A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 109A | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-19A-DWC-01,02,03 | 20-Mar-07 | ND |
| 109A | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 109A | Classroom | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 109B | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 109B | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 109B | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 109B | Classroom | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 109B | Classroom | Pipe Fitting | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 109B | Classroom | Pipe Fitting | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 109C | TV Studio | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 109C | TV Studio | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 109C | TV Studio | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 109C | TV Studio | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 109D | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 109D | Storage | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 109D | Storage | Ceiling | 1'x1' Ceiling Tile | Large Random Pinhole (Cellulose/Stapled) | - | Non-ACM | - | - | - | - |
| 109E | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 109E | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 109E | Classroom | Ceiling | 1'x1' Ceiling Tile | Large Random Pinhole (Cellulose/Stapled) | - | Non-ACM | - | - | - | - |
| 109F | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 109F | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 109F | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 109F | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 109F | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 109G | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 109G | Office | Wall | Drywall | - | - | Non-ACM | SL | GCI-19A-DWC-01,02,03 | 20-Mar-07 | ND |
| 109G | Office | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 109G | Office | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 111 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 111 | Classroom | Floor | Rubber | - | - | Non-ACM | - | - | - | - |
| 111 | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 111 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 111 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 111 | Classroom | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 111A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 111A | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 111A | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 111B | Cyclone Room | Not Inspected | | | | | | | | |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 111C | Office | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 111C | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 111C | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 111C | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 112 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 112 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 112 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 112 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 114 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 114 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 114 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 114 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 114 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 115 | Classroom | Floor | 9"x9" Vinyl Floor Tile | Green with White Streak | NF | ACM | HM | 32523-800-Galt-S18 | 16-Mar-09 | 1.3% Chrysotile |
| 115 | Classroom | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S18 | 16-Mar-09 | ND |
| 115 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 115 | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 115 | Classroom | Ceiling | Drywall | - | - | Non ACM | HM | GCI-8206-DWC-02 | 20-Mar-07 | ND |
| 115 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 115 | Classroom | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 116 | Office | Floor | 12"x12" Vinyl Floor Tile | White with Brown Fleck | - | Non-ACM | HM | 32523-800-Galt-S19 | 16-Mar-09 | ND |
| 116 | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 116 | Office | Ceiling | 2'x4' Short Fissure | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 116A | Office | Floor | 12"x12" Vinyl Floor Tile | White with Brown Fleck | - | Non-ACM | HM | 32523-800-Galt-S19 | 16-Mar-09 | ND |
| 116A | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 116A | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 116A | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 117 | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 117 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 117 | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 117 | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 117A | Mechanical Room | Floor | 9"x9" Vinyl Floor Tile | Green with White Streak | NF | ACM | HM | 32523-800-Galt-S18 | 16-Mar-09 | 1.3% Chrysotile |
| 117A | Mechanical Room | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S18 | 16-Mar-09 | ND |
| 117A | Mechanical Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 117A | Mechanical Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 117A | Mechanical Room | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 117A | Mechanical Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 117A | Mechanical Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 118 | Classroom | Floor | 12"x12" Vinyl Floor Tile | White with Brown Fleck | - | Non-ACM | SL | 32523-800-Galt-S19 | 16-Mar-09 | ND |
| 118 | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 118 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 118 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 119 | Classroom | Floor | 9"x9" Vinyl Floor Tile | Green with White Streak | NF | ACM | HM | 32523-800-Galt-S18 | 16-Mar-09 | 1.3% Chrysotile |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 119 | Classroom | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S18 | 16-Mar-09 | ND |
| 119 | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 119 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 119 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 150 | Exterior Storage | Not Inspected | | | | | | | | |
| 151 | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 151 | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 151 | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 151 | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 151A | Mechanical Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 151A | Mechanical Room | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 151A | Mechanical Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 151A | Mechanical Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 151A | Mechanical Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 151A | Mechanical Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 151B | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 151B | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 151B | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 151B | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 153 | Transformer Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 153 | Transformer Room | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 153 | Transformer Room | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 153 | Transformer Room | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 153 | Transformer Room | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-DWC-01 to 07 | 20-Mar-07 | ND |
| 153 | Transformer Room | Ceiling | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 153 | Transformer Room | Upper Ceiling | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 153 | Transformer Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 153 | Transformer Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 154 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 154 | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-DWC-01 to 07 | 20-Mar-07 | ND |
| 154 | Office | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-DWC-01 to 07 | 20-Mar-07 | ND |
| 154A | Water Service | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 154A | Water Service | Wall | Drywall | - | - | Non-ACM | HM | GCI-DWC-01 to 07 | 20-Mar-07 | ND |
| 154A | Water Service | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-DWC-01 to 07 | 20-Mar-07 | ND |
| 155 | Landing | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 155 | Landing | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 155 | Landing | Wall | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 156 | Changeroom | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 156 | Changeroom | Wall | Drywall | - | - | Non-ACM | HM | S05 | 5-Aug-15 | ND |
| 156 | Changeroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 156 | Changeroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 156A | Changeroom | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 156A | Changeroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 156A | Changeroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 156A | Changeroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 156B | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 156B | Washroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |
| 156B | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 156B | Washroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 157 | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 157 | Storage | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 157 | Storage | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 157 | Storage | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 158 | Changeroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 158 | Changeroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-202-DWC-04 | 20-Mar-07 | ND |
| 158 | Changeroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 158 | Changeroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 158A | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 158A | Washroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-202-DWC-04 | 20-Mar-07 | ND |
| 158A | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 158A | Washroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 160 | Office | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 160 | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-202-DWC-04 | 20-Mar-07 | ND |
| 160 | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 160A | Corridor | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 160A | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-202-DWC-04 | 20-Mar-07 | ND |
| 160A | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 160A | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 161 | Mechanical Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 161 | Mechanical Room | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 161 | Mechanical Room | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 161 | Mechanical Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 162 | Lobby | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 162 | Lobby | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 162 | Lobby | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 162 | Lobby | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 162 | Lobby | Ceiling | 2'x'4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 162 | Lobby | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 162 | Lobby | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 162A | Lobby | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 162A | Lobby | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 162A | Lobby | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 162A | Lobby | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 162A | Lobby | Ceiling | 2'x'4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 162A | Lobby | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 162A | Lobby | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 162B | Storage | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 162B | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 162B | Storage | Wall | Field Stone | - | - | Non-ACM | - | - | - | - |
| 162B | Storage | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 162B | Storage | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 162B | Storage | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 163 | Electrical Room | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 163 | Electrical Room | Wall | Metal | - | - | Non-ACM | - | - | - | - |
| 163 | Electrical Room | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 163 | Electrical Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |
| 163 | Electrical Room | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-153-CP-01,02,03 | 20-Mar-07 | ND |
| 163 | Electrical Room | Ceiling | Plaster | Upper Ceiling | - | Non-ACM | SL | GCI-153-UCP-01, 02, 03 | 20-Mar-07 | ND |
| 164 | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 164 | Storage | Wall | Field Stone | - | - | Non-ACM | - | - | - | - |
| 164 | Storage | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 164 | Storage | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 164 | Storage | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 164A | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 164A | Storage | Wall | Field Stone | - | - | Non-ACM | - | - | - | - |
| 164A | Storage | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 164A | Storage | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 164A | Storage | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 165A | Electrical Room | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 165A | Electrical Room | Wall | Metal | - | - | Non-ACM | - | - | - | - |
| 165A | Electrical Room | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 165A | Electrical Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |
| 165A | Electrical Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-CP-01,02,03 | 20-Mar-07 | ND |
| 165B | Corridor | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 165B | Corridor | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 165B | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |
| 165B | Corridor | Wall | Steel | - | - | Non-ACM | - | - | - | - |
| 165B | Corridor | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 165B | Corridor | Ceiling | 2'x4' Ceiling Tile | - | - | Non-ACM | SL | GCI-165A-CT | 20-Mar-07 | ND |
| 165C | Fan Room | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 165C | Fan Room | Wall | Metal | - | - | Non-ACM | - | - | - | - |
| 165C | Fan Room | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 165C | Fan Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |
| 165C | Fan Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-CP-01,02,03 | 20-Mar-07 | ND |
| 165D | Fan Room | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 165D | Fan Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-301-DWC-04 | 20-Mar-07 | ND |
| 165D | Fan Room | Ceiling | Plaster | Presumed Based on Wall Sample | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 165D | Fan Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 167 | Mechanical Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |

| | School Name | Legend: | Notes: |
|---|---|---|---|
| | **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| | **Date Built:**<br>Original: 1853<br>Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 167 | Mechanical Room | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 167 | Mechanical Room | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 167 | Mechanical Room | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-167-CP-01,02,03 | 20-Mar-07 | ND |
| 167 | Mechanical Room | Piping | Pipe Fitting | Parged Cement | F | ACM | SL | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 167 | Mechanical Room | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 167 | Mechanical Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 167 | Mechanical Room | Piping | Vermiculite | Ceiling Patch | F | ACM | SL | GCI-BR-VERM | 20-Mar-07 | 5% Chrysotile |
| 167A | Corridor | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 167A | Corridor | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 167A | Corridor | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 167B | Office | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 167B | Office | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 167B | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 167B | Office | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 168 | Transformer Room | Not Inspected | | | | | | | | |
| 169 | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 169 | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 169 | Storage | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 170 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 170 | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 170 | Washroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 171 | Change Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 171 | Change Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 171 | Change Room | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 171 | Change Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 171A | Shower | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 171A | Shower | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 171A | Shower | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 171A | Shower | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 171A | Shower | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 171B | Change Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 171B | Change Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 171B | Change Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 171C | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 171C | Washroom | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 171C | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 172 | Change Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 172 | Change Room | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 172 | Change Room | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 172 | Change Room | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-172-HardStucco-01,02,03 | 20-Mar-07 | ND |
| 172 | Change Room | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 172A | Shower | Floor | Ceramic | - | - | Non-ACM | - | - | - | - |
| 172A | Shower | Wall | Ceramic | - | - | Non-ACM | - | - | - | - |

## School Name

**Galt Collegiate Institute**

**Date Built:**

Original: 1853

Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986

## Legend:

**HM -** Homogenous Material - homogeneous with previously sampled material
**SL** - Sample Location - Material Sampled
**VC** - Visually Confirmed - Material not sampled, deemed ACM
**NF** - Non-Friable
**F**- Friable

## Notes:

**All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.**

**Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.**

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 172A | Shower | Ceiling | Transite Paneling | Asbestos Cement | NF | ACM | VC | - | - | - |
| 172A | Shower | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 172B | Washroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 172B | Washroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 172B | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-174-CP-01,02,03 | 20-Mar-07 | ND |
| 173 | Storage | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 173 | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 173 | Storage | Ceiling | Steel | - | - | Non-ACM | - | - | - | - |
| 174 | Mechanical Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 174 | Mechanical Room | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 174 | Mechanical Room | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-174-CP-01,02,03 | 20-Mar-07 | ND |
| 174 | Mechanical Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 175 | Quiet Area | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 175 | Quiet Area | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 175 | Quiet Area | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 175 | Quiet Area | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 175 | Quiet Area | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 175 | Quiet Area | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 175 | Quiet Area | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 175 | Quiet Area | Ceiling | Transite | Pegboard | NF | ACM | VC | - | - | - |
| 175A | Work Room | Floor | 12"x12" Vinyl Floor Tile | Black and White (Post 2007) | - | Non-ACM | - | - | - | - |
| 175A | Work Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 175A | Work Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 175A | Work Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 175A | Work Room | Ceiling | Transite | Pegboard | NF | ACM | VC | - | - | - |
| 175B | Quiet Area | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 175B | Quiet Area | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 175B | Quiet Area | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 175B | Quiet Area | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 175B | Quiet Area | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 175B | Quiet Area | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 175B | Quiet Area | Ceiling | Transite | Pegboard | NF | ACM | VC | - | - | - |
| 175C | Seminar Room | Floor | 12"x12" Vinyl Floor Tile | Black and White (Post 2007) | - | Non-ACM | - | - | - | - |
| 175C | Seminar Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 175C | Seminar Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 175C | Seminar Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 175C | Seminar Room | Ceiling | Transite | Pegboard | NF | ACM | VC | - | - | - |
| 176 | Workroom | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 176 | Workroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 176 | Workroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 176 | Workroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 176 | Workroom | Ceiling | 2'x2' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 176 | Workroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 176 | Workroom | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:**<br>Original: 1853<br>Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 177 | Media Room | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 177 | Media Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 177 | Media Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 177 | Media Room | Wall | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 177 | Media Room | Ceiling | 2'x2' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 177 | Media Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 177 | Media Room | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 178 | Seminar Room | Floor | 12"x12" Vinyl Floor Tile | Black (Post 2007) | - | Non-ACM | - | - | - | - |
| 178 | Seminar Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 178 | Seminar Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 178 | Seminar Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 178 | Seminar Room | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 179 | Network Room | Not Inspected | | | | | | | | |
| 180 | Washroom | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 180 | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 180 | Washroom | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 180A | Washroom | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 180A | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 180A | Washroom | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 181 | Washroom | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 181 | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 181 | Washroom | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 182 | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 182 | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 182 | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 182A | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 182A | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 182A | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 183 | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 183 | Office | Floor | Vinyl Sheet Flooring | Beige | - | Non-ACM | HM | S03 | 20-Mar-15 | ND |
| 183 | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 183 | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 183A | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 183A | Storage | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 183A | Storage | Ceiling | Drywall | - | - | Non-ACM | HM | S05 | 5-Aug-15 | ND |
| 184 | Mechanical Room | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 184 | Mechanical Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 184 | Mechanical Room | Ceiling | Drywall | - | - | Non-ACM | HM | S05 | 5-Aug-15 | ND |
| 184 | Mechanical Room | Piping | Fibreglass | - | - | Non-ACM | - | - | - | - |
| 185 | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 185 | Storage | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 185 | Storage | Ceiling | Steel | - | - | Non-ACM | - | - | - | - |
| 185 | Storage | Ducting | Duct Expansion Joint | - | NF | ACM | VC | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 186 | Servery | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 186 | Servery | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 186 | Servery | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 186 | Servery | Ceiling | Drywall | - | - | Non-ACM | HM | S05 | 5-Aug-15 | ND |
| 187 | Servery | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 187 | Servery | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 187 | Servery | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 187 | Servery | Ceiling | Drywall | - | - | Non-ACM | HM | S05 | 5-Aug-15 | ND |
| 188 | Kitchen | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 188 | Kitchen | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 188 | Kitchen | Ceiling | Drywall | - | - | Non-ACM | HM | S05 | 5-Aug-15 | ND |
| 189 | Cafeteria | Floor | Vinyl Sheet Flooring | Beige | - | Non-ACM | HM | GCI-170/8404/8101A/189 | 20-Mar-15 | ND |
| 189 | Cafeteria | Floor | Vinyl Sheet Flooring | Red | - | Non-ACM | SL | S04 | 20-Mar-15 | ND |
| 189 | Cafeteria | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 189 | Cafeteria | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | S06DE, GCI-189-CS-01,02,03,04,05 | 20-Mar-15 | ND |
| 189 | Cafeteria | Ceiling | 2'x2' Ceiling Tile | Dense Pinhole | - | Non-ACM | SL | S07 | 20-Mar-15 | ND |
| 189 | Cafeteria | Ceiling | 2'x2' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 189 | Cafeteria | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 189A | Student Activities | Floor | 12"x12" Vinyl Floor Tile | Beige with Grey and Peach | - | Non-ACM | SL | S08 | 20-Mar-15 | ND |
| 189A | Student Activities | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 189A | Student Activities | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 189B | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige with Grey and Peach | - | Non-ACM | HM | S08 | 20-Mar-15 | ND |
| 189B | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 189B | Washroom | Ceiling | Drywall | - | - | Non-ACM | HM | S05 | 5-Aug-15 | ND |
| 190 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 190 | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 190 | Washroom | Ceiling | 2'x4' Ceiling Tile | Flat (Post 2007) | - | Non-ACM | - | - | - | - |
| 191 | Storage | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 191 | Storage | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 191 | Storage | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 903 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 903 | Stairwell | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 903 | Stairwell | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 904 | Stairwell | Floor | 12"x12" Vinyl Floor Tile | Brown Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 904 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 904 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 905 | Stairwell | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 905 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 905 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 906 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 906 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 906 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 909 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 909 | Stairwell | Wall | Concrete Block | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 909 | Stairwell | Ceiling | Concrete | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 909 | Stairwell | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 909 | Stairwell | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 910 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 910 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 910 | Stairwell | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-910-CS-01,02,03 | 20-Mar-07 | ND |
| 911 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 911 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 911 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-106-WP-01,02,03 | 20-Mar-07 | ND |
| 911 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 912 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 912 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 912 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 912 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 912 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 912 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 913 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 913 | Stairwell | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 913 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 915 | Stairwell | Not Inspected | | | | | | | | |
| 916 | Stairwell | Not Inspected | | | | | | | | |
| 8101A | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8101A | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8101A | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8101A | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8101A | Corridor | Piping | Pipe Fittings | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8101A | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8101B | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8101B | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8101B | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8101B | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8101B | Corridor | Piping | Pipe Fittings | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8101B | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8101C | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8101C | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8101C | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8101C | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8101C | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8101C | Corridor | Piping | Pipe Fittings | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8101C | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8101D | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 8101D | Corridor | Wall | Plaster | - | - | Non-ACM | SL | GCI-8108B-WP-01,02,03,04 | 20-Mar-07 | ND |
| 8101D | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8101D | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8101D | Corridor | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-8101B-CP-01,02,03,04 | 20-Mar-07 | ND |
| 8101D | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8101D | Corridor | Piping | Pipe Fittings | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8101D | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8101F | Corridor | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 8101F | Corridor | Wall | Drywall | - | - | Non-ACM | SL | GCI-19A-DWC-01,02,03 | 20-Mar-07 | ND |
| 8101F | Corridor | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 8101F | Corridor | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 8102 | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8102 | Corridor | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8102 | Corridor | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 8102 | Corridor | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-8101B-CP-01,02,03,04 | 20-Mar-07 | ND |
| 8102 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8102 | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8103 | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8103 | Corridor | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8103 | Corridor | Wall | Plaster | - | - | Non-ACM | SL | GCI-8103-WP01,02,03 | 20-Mar-07 | ND |
| 8103 | Corridor | Wall | Drywall | - | - | Non-ACM | SL | GCI-8103-DWC-01,02,03 | 20-Mar-07 | ND |
| 8103 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8103 | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8103 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8103A | Corridor | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 8103A | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8103A | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8103A | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8103A | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8104 | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8104 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8104 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8104 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8104 | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8105 | Corridor | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 8105 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8105 | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-8206A-DWC-02 | 20-Mar-07 | ND |
| 8105 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8105 | Corridor | Ceiling | 2'x2' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8106 | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8106 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8106 | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8106 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 8106 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8106 | Corridor | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 8106A | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8106A | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 8106A | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8106A | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8108A | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8108A | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8108A | Corridor | Ceiling | Hard Texture Coat | - | - | Non-ACM | HM | S06ABC | 20-Mar-15 | ND |
| 8108B | Corridor | Floor | 12"x12" Vinyl Floor Tile | Brown with Dense Fleck | - | Non-ACM | HM | 32523-800-Galt-S06 | 16-Mar-09 | ND |
| 8108B | Corridor | Floor | Vinyl Sheet Flooring | Beige | - | Non-ACM | SL | S03 | 20-Mar-15 | ND |
| 8108B | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8108B | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8108B | Corridor | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | S06ABC | 20-Mar-15 | ND |
| 8108B | Corridor | Piping | Pipe Insulation | - | - | Non-ACM | SL | GCI-8101B-PI | 20-Mar-15 | ND |
| 8108C | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8108C | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8108C | Corridor | Wall | Stone | - | - | Non-ACM | - | - | - | - |
| 8108C | Corridor | Ceiling | Hard Texture Coat | - | - | Non-ACM | HM | S06ABC | 20-Mar-15 | ND |
| | | | | | | | | | | |
| **Level 2** | | | | | | | | | | |
| | | | | | | | | | | |
| 201 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 201 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Brown with Dark Brown Fleck | - | Non-ACM | SL | GCI-305-12x12FT | 20-Mar-07 | ND |
| 201 | Classroom | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 201 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 201 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 201 | Classroom | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 202 | Office | Floor | Vinyl Sheet Flooring | Smokey Cloud | - | Non-ACM | HM | 32523-800-Galt-S16 | 16-Mar-09 | ND |
| 202 | Office | Wall | Plaster | - | - | Non-ACM | SL | GCI-202-WP-03 | 20-Mar-07 | ND |
| 202 | Office | Wall | Drywall | - | - | Non-ACM | SL | GCI-202-DWC-04 | 20-Mar-07 | ND |
| 202 | Office | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 202 | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 202 | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 202 | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 202A | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 202A | Office | Wall | Wood | - | - | Non-ACM | - | - | - | - |
| 202A | Office | Wall | Plaster | - | - | Non-ACM | SL | GCI-8206A-WP-01 | 20-Mar-07 | ND |
| 202A | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 202A | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 202B | Classroom | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 202B | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 202B | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 202C | Storage | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 202C | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 202C | Storage | Wall | Wood | - | - | Non-ACM | - | - | - | - |
| 202C | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 202C | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 202D | Washroom | Floor | Vinyl Sheet Flooring | Wood (Post 2009) | - | Non-ACM | - | - | - | - |
| 202D | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 202D | Washroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 203 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Brown with Dark Brown Fleck | NF | Non-ACM | HM | S08 | 16-Mar-09 | 5% Chrysotile |
| 203 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 203 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-203-DWC-05 | 20-Mar-07 | ND |
| 203 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 203 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 203A | Storage | Wood | - | - | - | Non-ACM | - | - | - | - |
| 203A | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 203A | Storage | Wall | Drywall | - | - | Non-ACM | SL | GCI-203-DWC-05 | 20-Mar-07 | ND |
| 203A | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 203A | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 204 | Office | Floor | Vinyl Sheet Flooring | Wood (Post 2009) | - | Non-ACM | - | - | - | - |
| 204 | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 204 | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 204 | Office | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 204A | Office | Floor | Vinyl Sheet Flooring | Wood (Post 2009) | - | Non-ACM | - | - | - | - |
| 204A | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 204A | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 204C | Office | Floor | Vinyl Sheet Flooring | Wood (Post 2009) | - | Non-ACM | - | - | - | - |
| 204C | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 204C | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 204C | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 204C | Office | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 204D | Office | Floor | Vinyl Sheet Flooring | Wood (Post 2009) | - | Non-ACM | - | - | - | - |
| 204D | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 204D | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 204D | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 204D | Office | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 204E | Vault | Not Inspected | | | | | | | | |
| 204F | Office | Floor | Vinyl Sheet Flooring | Wood (Post 2009) | - | Non-ACM | - | - | - | - |
| 204F | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 204F | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 204F | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 204F | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 205 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 205 | Classroom | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 205 | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-203-DWC-05 | 20-Mar-07 | ND |
| 205 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 205 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-201-CP-02 | 20-Mar-07 | ND |
| 206 | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 206 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 206 | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 206 | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 206A | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 206A | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 206A | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 206B | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 206B | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 206B | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 206C | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 206C | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 206C | Washroom | Ceiling | 2'x4' Ceiling Tile | Medium Fissure Random Pinhole (Post 2009) | - | Non-ACM | - | - | - | - |
| 206C | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 207 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 207 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-207-WP-07 | 20-Mar-07 | ND |
| 207 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 207 | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-207-CP-03 | 20-Mar-07 | ND |
| 207 | Classroom | Ceiling | 1'x1' Ceiling Tile | Pattern Pinhole | NF | ACM | SL | GCI-207-1x1ACT | 20-Mar-07 | 1% Amosite |
| 207 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 207 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 208 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 208 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-208-WP-02 | 20-Mar-07 | ND |
| 208 | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-208-CP-01 | 20-Mar-07 | ND |
| 208 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 209 | Career Center | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 209 | Career Center | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 209 | Career Center | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 209 | Career Center | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 209 | Career Center | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 210 | Classroom | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 210 | Classroom | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 210 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 210 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 210A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 210A | Classroom | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 210A | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 210A | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 210B | Storage | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 210B | Storage | Wall | Brick | - | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 210B | Storage | Wall | Drywall | - | - | Non-ACM | HM | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 210B | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 211 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 211 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 211 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 211 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 211 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 211 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 211A | Storage | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 211A | Storage | Wall | Drywall | Post 2007 | - | Non-ACM | - | - | - | - |
| 211A | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole (Post 2007) | - | Non-ACM | - | - | - | - |
| 212 | Classroom | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 212 | Classroom | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 212 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 212 | Classroom | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 212A | Instructor | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 212A | Instructor | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 212A | Instructor | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 212A | Instructor | Ceiling | 1'x1' Ceiling Tile | Random Pinhole | - | Non-ACM | HM | S01ABC | 14-Nov-18 | ND |
| 212B | Storage | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 212B | Storage | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 212B | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 212B | Storage | Ceiling | 1'x1' Ceiling Tile | Random Pinhole | - | Non-ACM | HM | S01ABC | 14-Nov-18 | ND |
| 212C | Storage | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 212C | Storage | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 212C | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 212C | Storage | Ceiling | 1'x1' Ceiling Tile | Random Pinhole | - | Non-ACM | SL | S01ABC | 14-Nov-18 | ND |
| 212D | Storage | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 212D | Storage | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 212D | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 212D | Storage | Ceiling | 1'x1' Ceiling Tile | Random Pinhole | - | Non-ACM | HM | S01ABC | 14-Nov-18 | ND |
| 212E | Storage | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 212E | Storage | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 212E | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 212E | Storage | Ceiling | 1'x1' Ceiling Tile | Random Pinhole | - | Non-ACM | HM | S01ABC | 14-Nov-18 | ND |
| 212F | Storage | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 212F | Storage | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 212F | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 212F | Storage | Ceiling | 1'x1' Ceiling Tile | Random Pinhole | - | Non-ACM | HM | S01ABC | 14-Nov-18 | ND |
| 213 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige with Tan and Grey | - | Non-ACM | HM | 32523-800-Galt-S02 | 16-Mar-09 | ND |
| 213 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 213 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 213 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:**<br>Original: 1853<br>Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 213 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 213A | Classroom | Floor | 9"x9" Vinyl Floor Tile | Grey with White Streak | NF | ACM | SL | 32523-800-Galt-S12 | 16-Mar-09 | 0.5% Chrysotile |
| 213A | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 213A | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 213A | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 213A | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 214 | Gymnasium | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 214 | Gymnasium | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 214 | Gymnasium | Ceiling | Wood Baton | - | - | Non-ACM | - | - | - | - |
| 214 | Gymnasium | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 214A | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 214A | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 214A | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 214A | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 214A | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 214B | Gymnasium | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 214B | Gymnasium | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 214B | Gymnasium | Ceiling | Wood Baton | - | - | Non-ACM | - | - | - | - |
| 214B | Gymnasium | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 215 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 215 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 215 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 215 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 215 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 215 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 215A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 215A | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 215A | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 217 | Changeroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 217 | Changeroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 217 | Changeroom | Ceiling | 2"x4" Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 217 | Changeroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 217 | Changeroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 217 | Changeroom | Ducting | Expansion Joints | - | NF | ACM | VC | - | - | - |
| 218 | Classroom | Floor | 9"x9" Vinyl Floor Tile | Pink with White Fleck | NF | ACM | SL | 32523-800-Galt-S10 | 16-Mar-09 | 1.3% Chrysotile |
| 218 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 218 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 218 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 218 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 218 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 219 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 219 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 219 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 219 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 219 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 219 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 219A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 219A | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 219A | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 219A | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 219A | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 219A | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 220 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 220 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 220 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 220 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 220 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 220 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 221 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 221 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 221 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 221 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 221 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 221 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 222 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 222 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 222 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 222 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 222 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 223 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 223 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 223 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 223 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 223 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 223 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 224 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 224 | Classroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 224 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 224 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 224 | Classroom | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 224 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 225 | Weight Room | Floor | 12"x12" Vinyl Floor Tile | Beige/Grey Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 225 | Weight Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 225 | Weight Room | Wall | Stone | - | - | Non-ACM | - | - | - | - |
| 225 | Weight Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 225 | Weight Room | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 226 | Office | Floor | 12"x12" Vinyl Floor Tile | Beige/Grey Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 226 | Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 226 | Office | Wall | Stone | - | - | Non-ACM | - | - | - | - |
| 226 | Office | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 227 | Weight Room | Floor | 12"x12" Vinyl Floor Tile | Beige/Grey Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 227 | Weight Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 227 | Weight Room | Wall | Stone | - | - | Non-ACM | - | - | - | - |
| 227 | Weight Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 227 | Weight Room | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 228 | Fitness Room | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 228 | Fitness Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 228 | Fitness Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 228 | Fitness Room | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 230 | Gymnasium | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 230 | Gymnasium | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 230 | Gymnasium | Ceiling | Steel Deck | - | - | Non-ACM | - | - | - | - |
| 230 | Gymnasium | Piping | Pipe Fitting | Fibreglass | - | Non-ACM | - | - | - | - |
| 230A | Storage | Floor | 12"x12" Vinyl Floor Tile | Brown with Dense Fleck | - | Non-ACM | HM | 32523-800-Galt-S06 | 16-Mar-09 | ND |
| 230A | Storage | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 230A | Storage | Ceiling | Streel Deck | - | - | Non-ACM | - | - | - | - |
| 230B | Storage | Floor | 12"x12" Vinyl Floor Tile | Brown (Post 2008) | - | Non-ACM | - | - | - | - |
| 230B | Storage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 230B | Storage | Ceiling | Steel Deck | - | - | Non-ACM | - | - | - | - |
| 250 | Tassie Hall | Wall | Carpet | - | - | Non-ACM | - | - | - | - |
| 250 | Tassie Hall | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 250 | Tassie Hall | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 250 | Tassie Hall | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | SL | GCI-250-1x1ACT | 20-Mar-07 | ND |
| 251 | Tassie Hall Stage | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 251 | Tassie Hall Stage | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 251 | Tassie Hall Stage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 251 | Tassie Hall Stage | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | SL | GCI-250-1x1ACT | 20-Mar-07 | ND |
| 251 | Tassie Hall Stage | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 251 | Tassie Hall Stage | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 251A | Dressing Room | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 251A | Dressing Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 251A | Dressing Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 251A | Dressing Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 251A | Dressing Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 251B | Dressing Room | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 251B | Dressing Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 251B | Dressing Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 251B | Dressing Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 251B | Dressing Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 252 | Storage | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 252 | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 252 | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 252A | Lobby | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 252A | Lobby | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 252A | Lobby | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 253 | Staff Lounge | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 253 | Staff Lounge | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 253 | Staff Lounge | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 253 | Staff Lounge | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 253 | Staff Lounge | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 253A | Lobby | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 253A | Lobby | Wall | Drywall | - | - | Non-ACM | HM | GCI-203-DWC-05 | 20-Mar-07 | ND |
| 253A | Lobby | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 253B | Washroom | Floor | Vinyl Sheet Flooring | Smokey Cloud | - | Non-ACM | HM | 32523-800-Galt-S16 | 16-Mar-09 | ND |
| 253B | Washroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 253B | Washroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-258-WP-04 | 20-Mar-07 | ND |
| 253B | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 254 | Staff Room | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 254 | Staff Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 254 | Staff Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 254 | Staff Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 254 | Staff Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 254 | Staff Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 256 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 256 | Washroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-203-DWC-05 | 20-Mar-07 | ND |
| 256 | Washroom | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-203-DWC-05 | 20-Mar-07 | ND |
| 257 | Washroom | Floor | Vinyl Sheet Flooring | Smokey Cloud | - | Non-ACM | HM | 32523-800-Galt-S16 | 16-Mar-09 | ND |
| 257 | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 257 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 258 | Washroom | Floor | Vinyl Sheet Flooring | Smokey Cloud | - | Non-ACM | HM | 32523-800-Galt-S16 | 16-Mar-09 | ND |
| 258 | Washroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-205-DWC-06 | 20-Mar-07 | ND |
| 258 | Washroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-258-WP-04 | 20-Mar-07 | ND |
| 258 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 259 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 259 | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 259 | Washroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-259-DWC-07 | 20-Mar-07 | ND |
| 259 | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 259 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 260 | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 260 | Office | Floor | 12"x12" Vinyl Floor Tile | Brown with Dense Fleck | - | Non-ACM | HM | 32523-800-Galt-S06 | 16-Mar-09 | ND |
| 260 | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 260 | Office | Ceiling | 2'x2' Ceiling Tile | Textured | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 260 | Office | Ceiling | 2'x2' Ceiling Tile | Thin Long Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 260 | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 260 | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 260A | Exam Room | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 260A | Exam Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 260A | Exam Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 260A | Exam Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 260B | Exam Room | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 260B | Exam Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 260B | Exam Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 260B | Exam Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 261 | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 261 | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 261 | Storage | Ceiling | 2'x2' Ceiling Tile | Short Fissure Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 262 | First Aid | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 262 | Nurse | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 262 | First Aid | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 262 | First Aid | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 262 | First Aid | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 263 | Exam Room | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 263 | Exam Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 263 | Exam Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 263 | Exam Room | Ceiling | 2'x2' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 264 | Coffee | Floor | Vinyl Sheet Flooring | Light Yellow Cobblestone | - | Non-ACM | SL | 32523-800-Galt-S13 | 16-Mar-09 | ND |
| 264 | Coffee | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 264 | Coffee | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 264 | Coffee | Ceiling | 2'x2' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 265 | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 265 | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 265 | Washroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 265 | Washroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 265 | Washroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 266A | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 266A | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 266A | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 266A | Office | Ceiling | 2'x2' Ceiling Tile | Long Thin Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 266B | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 266B | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 266B | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 266B | Office | Ceiling | 2'x2' Ceiling Tile | Long Thin Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 266C | Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 266C | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 266C | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 266C | Office | Ceiling | 2'x2' Ceiling Tile | Long Thin Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 266C | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |

# School Name

**Galt Collegiate Institute**

**Date Built:**

Original: 1853

Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986

**Legend:**

**HM -** Homogenous Material - homogeneous with previously sampled material
**SL** - Sample Location - Material Sampled
**VC** - Visually Confirmed - Material not sampled, deemed ACM
**NF** - Non-Friable
**F**- Friable

**Notes:**

**All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.**

**Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.**

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 266C | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 266D | Classroom | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 266D | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 266D | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 266D | Classroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 266D | Classroom | Ceiling | 2'x2' Ceiling Tile | Long Thin Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 266E | Classroom | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 266E | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 266E | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 266E | Classroom | Ceiling | 2'x2' Ceiling Tile | Long Thin Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 267 | Classroom | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 267 | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 267 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 267 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 267 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 267 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 268A | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 268A | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 268A | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 268A | Office | Ceiling | 2'x2' Ceiling Tile | Long Thin Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 268B | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 268B | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 268B | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 268B | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 268B | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 268B | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 268C | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 268C | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 268C | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 268C | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 268C | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 268C | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 269 | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 269 | Office | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 269 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 269 | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 269 | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 269 | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 269A | Meeting Room | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 269A | Meeting Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 269A | Meeting Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 270 | Changeroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 270 | Changeroom | Wall | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 270 | Changeroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 270 | Changeroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 270A | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 270A | Washroom | Wall | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 270A | Washroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 270A | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 270B | Instructors | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 270B | Instructors | Wall | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 270B | Instructors | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 270B | Instructors | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 270C | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 270C | Washroom | Wall | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 270C | Washroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 270C | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 270D | Stairwell | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 270D | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 270D | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 270D | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 271 | Changeroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 271 | Changeroom | Wall | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 271 | Changeroom | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 271 | Changeroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 271 | Changeroom | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 271A | Instructors | Floor | 9"x9" Vinyl Floor Tile | Beige with Thick Brown Streaks | NF | ACM | SL | 32523-800-Galt-S15 | 16-Mar-09 | 1.1% Chrysotile |
| 271A | Instructors | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 271A | Instructors | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 271A | Instructors | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 271B | Shower | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 271B | Shower | Wall | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 271B | Shower | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 271C | Washroom | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 271C | Washroom | Wall | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 271C | Washroom | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 271D | Access | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 271D | Access | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 271D | Access | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 272 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 272 | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 272 | Washroom | Ceiling | 2'x4' Ceiling Tile | Plain (Post 2007) | - | Non-ACM | - | - | - | - |
| 273 | Washroom | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 273 | Washroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 273 | Washroom | Wall | Ceramic | - | - | Non-ACM | - | - | - | - |
| 273 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 273 | Washroom | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 274 | Washroom | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 274 | Washroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 274 | Washroom | Wall | Ceramic | - | - | Non-ACM | - | - | - | - |
| 274 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-275-CP-05 | 20-Mar-07 | ND |
| 274 | Washroom | Ceiling | Hard Texture Coat | - | NF | ACM | SL | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 275 | Washroom | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 275 | Washroom | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 275 | Washroom | Wall | Ceramic | - | - | Non-ACM | - | - | - | - |
| 275 | Washroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-275-CP-05 | 20-Mar-07 | ND |
| 275 | Washroom | Ceiling | Hard Texture Coat | - | NF | ACM | HM | S03 | 5-Aug-15 | 1.3% Chrysotile |
| 276 | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 276 | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 276 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 276A | Shower | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 276A | Shower | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 276A | Shower | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 276B | Shower | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 276B | Shower | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 276B | Shower | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 276C | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 276C | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 276C | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 277 | Instructors Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 277 | Instructors Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 277 | Instructors Office | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 277A | Instructors Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 277A | Instructors Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 277A | Instructors Office | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 277B | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 277B | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 277B | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 277C | Mechanical Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 277C | Mechanical Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 277C | Mechanical Room | Ceiling | Steel Deck | - | - | Non-ACM | - | - | - | - |
| 277C | Mechanical Room | Piping | Pipe Fittings | Fibreglass | - | Non-ACM | - | - | - | - |
| 278 | Changeroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 278 | Changeroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 278 | Changeroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 278A | Shower | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 278A | Shower | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 278A | Shower | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 278B | Changeroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 278B | Changeroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 278B | Changeroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 278C | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 278C | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 278C | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 279 | Instructors Office | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 279 | Instructors Office | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 279 | Instructors Office | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 279A | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 279A | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 279A | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 279B | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 279B | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 279B | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 279B | Washroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 279B | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 279B | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 901 | Stairwell | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 901 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 901 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 903 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 903 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 903 | Stairwell | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 903 | Stairwell | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 904 | Stairwell | Not Inspected | | | | | | | | |
| 905 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 905 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 905 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-207-CP-03 | 20-Mar-07 | ND |
| 909 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 909 | Stairwell | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 909 | Stairwell | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | S01ABC | 6-May-15 | ND |
| 909 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 910 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 910 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 910 | Stairwell | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-910-CS-01,02,03 | 20-Mar-07 | ND |
| 911 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 911 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 911 | Stairwell | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 912 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 912 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 912 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-214B-CP-06 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 912 | Stairwell | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 913 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 913 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 913 | Stairwell | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 914 | Stairwell | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 914 | Stairwell | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 914 | Stairwell | Ceiling | Steel Deck | - | - | Non-ACM | - | - | - | - |
| 915 | Stairwell | Not Inspected | | | | | | | | |
| 916 | Stairwell | Not Inspected | | | | | | | | |
| 952 | Lobby | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 952 | Lobby | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 952 | Lobby | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 2085 | Stairwell | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 2085 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 2085 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8201 | Corridor | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 8201 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8201 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8201 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8201 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8202 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8202 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8202 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8203 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8203 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8203 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8204 | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8204 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 8204 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8205 | Corridor | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 8205 | Corridor | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 8205 | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-203-DWC-05 | 20-Mar-07 | ND |
| 8205 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8205 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-201-CP-02 | 20-Mar-07 | ND |
| 8205 | Corridor | Pipe | Piping | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8205 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8206 | Stairwell | Not Inspected | | | | | | | | |
| 8206A | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8206A | Corridor | Floor | Drywall | - | - | Non-ACM | SL | GCI-8206A-DWC-01,02,03 | 20-Mar-07 | ND |
| 8206A | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 8206A | Corridor | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8206B | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8206B | Corridor | Wall | Concrete | - | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 8206B | Corridor | Wall | Plaster | - | - | Non-ACM | SL | GCI-214B-CP-06 | 20-Mar-07 | ND |
| 8206B | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | SL | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8206B | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8206B | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8207 | Corridor | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 8207 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 8207 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8208 | Corridor | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 8208 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 8208 | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 8208 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8208 | Corridor | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 8209 | Corridor | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 8209 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-314-CP-01 | 20-Mar-07 | ND |
| 8209 | Corridor | Ceiling | 2'x2' Ceiling Tile | Long Thin Fissure | NF | ACM | HM | 32523-800-Galt-S14 | 16-Mar-09 | 0.5% Amosite, 1.2% Chrysotile |
| 8209 | Corridor | Ceiling | 2'x2' Ceiling Tile | Short Fissure Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8210 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8210 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 8210 | Corridor | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-8211-CS-01,02,03 | 20-Mar-07 | ND |
| 8211 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8211 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 8211 | Corridor | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-8211-CS-01,02,03 | 20-Mar-07 | ND |
| 8212 | Corridor | Floor | Vinyl Sheet Flooring | Beige Cobblestone | NF | ACM | HM | 32523-800-Galt-S01ab | 20-Mar-07 | 3.1 Chrysotile |
| 8212 | Corridor | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 8212 | Corridor | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 8212 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 8213 | Corridor | Floor | Vinyl Sheet Flooring | Beige Cobblestone | NF | ACM | HM | 32523-800-Galt-S01ab | 20-Mar-07 | 3.1 Chrysotile |
| 8213 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-208-WP-02 | 20-Mar-07 | ND |
| 8213 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-208-CP-01 | 20-Mar-07 | ND |
| 8214 | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8214 | Corridor | Floor | Drywall | - | - | Non-ACM | SL | GCI-8206A-DWC-01,02,03 | 20-Mar-07 | ND |
| 8214 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 8214 | Corridor | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8214 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8214 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8215 | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8215 | Corridor | Wall | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8215 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8216 | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8216 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8216 | Corridor | Ceiling | 2'x4' Ceiling Tile | Texture Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8216 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8216 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 8216 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8217 | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8217 | Corridor | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8217 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8217 | Corridor | Ceiling | 2'x2' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | SL | GCI-8217,8218-2x2CT | 20-Mar-07 | ND |
| 8218 | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8218 | Corridor | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8218 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8218 | Corridor | Ceiling | 2'x2' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | SL | GCI-8217,8218-2x2CT | 20-Mar-07 | ND |
| 8219 | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8219 | Corridor | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8219 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8219 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 8220 | Corridor | Floor | Vinyl Sheet Flooring | Gold | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8220 | Corridor | Floor | Leveling Compound | - | - | Non-ACM | HM | 32523-800-Galt-S20 | 16-Mar-09 | ND |
| 8220 | Corridor | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 8220 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | S04 | 5-Aug-15 | ND |
| 8221 | Corridor | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 8221 | Corridor | Floor | Drywall | - | - | Non-ACM | SL | GCI-8206A-DWC-01,02,03 | 20-Mar-07 | ND |
| 8221 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-258-WP-04 | 20-Mar-07 | ND |
| 8221 | Corridor | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8222 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8222 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8222 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8223 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8223 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 8223 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| | | | | | | | | | | |
| **Level 3** | | | | | | | | | | |
| | | | | | | | | | | |
| 301 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Brown with Dark Brown Fleck | NF | ACM | SL | 32523-800-Galt-S08 | 16-Mar-09 | 5.0% Chrysotile |
| 301 | Classroom | Floor | Leveling Compound | - | - | Non-ACM | SL | 32523-800-Galt-S08 | 16-Mar-09 | ND |
| 301 | Classroom | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 301 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-302-DWC-04,05,06 | 20-Mar-07 | ND |
| 301 | Classroom | Ceiling | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 301 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 301A | Classroom | Floor | 12"x12" Vinyl Floor Tile | Grey (Post 2007) | - | Non-ACM | - | - | - | - |
| 301A | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 301A | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 301A | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 301A | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 301A | Classroom | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 302 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | S02 | 16-Mar-09 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 302 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 302 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-302-DWC-07,08,09 | 20-Mar-07 | ND |
| 302 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 302 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 302 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 302 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 302A | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | S02 | 16-Mar-09 | ND |
| 302A | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 302A | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 303 | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 303 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 303 | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 303 | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 303 | Office | Above Ceiling | Firespray | - | - | Non-ACM | SL | GCI-305-FS-01,02,03 | 20-Mar-07 | ND |
| 303A | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 303A | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 303A | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 303A | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 303A | Office | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 303A | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 304 | Prep Area | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 304 | Prep Area | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 304 | Prep Area | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 304 | Prep Area | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 304 | Prep Area | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 304A | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | S02 | 16-Mar-09 | ND |
| 304A | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 304A | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 305 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 305 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 305 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 305 | Classroom | Ceiling | 2'x4' Ceiling Tile | Long Fissure Random Pinhole | - | Non-ACM | SL | GCI-350-4x2CT | 20-Mar-07 | ND |
| 306 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 306 | Office | Wall | Hard Texture Coat | - | - | Non-ACM | HM | S03ABC | 14-Nov-18 | ND |
| 306 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 306 | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 306 | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 306 | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 306A | Corridor | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 306A | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 306A | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 306B | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 306B | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 306B | Washroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-302-DWC-07,08,09 | 20-Mar-07 | ND |
| 306B | Washroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 306C | Storage | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 306C | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 306C | Storage | Wall | Hard Texture Coat | - | - | Non-ACM | SL | S03ABC | 14-Nov-18 | ND |
| 306C | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 307 | Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 307 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 307 | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 307 | Office | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 308 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 308 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 308 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 308 | Classroom | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 308 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 308 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 309 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 309 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-311-CP-06 | 20-Mar-07 | ND |
| 309 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 309 | Classroom | Ceiling | Plaster | - | - |  | SL | GCI-309-CP07 | 20-Mar-07 | ND |
| 309 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 309 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 310 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 310 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-310-WP-01 | 20-Mar-07 | ND |
| 310 | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-317-CP-03 | 20-Mar-07 | ND |
| 310 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 310 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 310 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 311 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 311 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-311-WP-06 | 20-Mar-07 | ND |
| 311 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 311 | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-311-CP-06 | 20-Mar-07 | ND |
| 311 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 311 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 312 | Office | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 312 | Office | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 312 | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 312 | Office | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 312 | Office | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 313 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 313 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-313-WP-03 | 20-Mar-07 | ND |
| 313 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 313 | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-313-CP-05 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 313 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 313 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 314 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 314 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-314-WP-05, 07 | 20-Mar-07 | ND |
| 314 | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-314-CP-01,02 | 20-Mar-07 | ND |
| 314 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 315 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 315 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 315 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 315 | Classroom | Ceiling | Plaster | | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 316 | Custodial Office | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 316 | Custodial Office | Wall | Plaster | - | - | Non-ACM | SL | GCI-356-WP-04 | 20-Mar-07 | ND |
| 316 | Custodial Office | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-356-CP-01 | 20-Mar-07 | ND |
| 316A | Custodial Office | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 316A | Custodial Office | Wall | Plaster | - | - | Non-ACM | SL | GCI-356-WP-04 | 20-Mar-07 | ND |
| 316A | Custodial Office | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-356-CP-01 | 20-Mar-07 | ND |
| 317 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 317 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-317-WP-02 | 20-Mar-07 | ND |
| 317 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 317 | Classroom | Ceiling | Plaster | - | - | Non-ACM | SL | GCI-317-CP-04 | 20-Mar-07 | ND |
| 317 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 317 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 317A | Corridor | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 317A | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 317A | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 317A | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 318 | Classroom | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 318 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-316-DWC-01,02,03 | 20-Mar-07 | ND |
| 318 | Classroom | Wall | Brick | - | - | Non-ACM | - | - | - | - |
| 318 | Classroom | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 318 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 318 | Classroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 318 | Classroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 318A | Storage | Floor | 12"x12" Vinyl Floor Tile | Grey Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 318A | Storage | Wall | Drywall | - | - | Non-ACM | HM | GCI-316-DWC-01,02,03 | 20-Mar-07 | ND |
| 318A | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 318A | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 350 | Dressing Room | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 350 | Dressing Room | Wall | Plaster | - | - | Non-ACM | SL | S01 | 20-Mar-15 | ND |
| 350 | Dressing Room | Ceiling | Plaster | - | - | Non-ACM | HM | S01 | 20-Mar-15 | ND |
| 350 | Dressing Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 350 | Dressing Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 350A | Washroom | Floor | 12"x12" Vinyl Floor Tile | Blue Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:**<br>Original: 1853<br>Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 350A | Washroom | Wall | Plaster | - | - | Non-ACM | SL | S01 | 20-Mar-15 | ND |
| 350A | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | S01 | 20-Mar-15 | ND |
| 350A | Washroom | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 350A | Washroom | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 351 | Roof Space Access | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 351 | Roof Space Access | Wall | Plaster | - | - | Non-ACM | SL | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 351 | Roof Space Access | Wall | Fireproofing | - | - | Non-ACM | SL | S02 | 20-Mar-15 | ND |
| 351 | Roof Space Access | Ceiling | Wood | - | - | Non-ACM | - | - | - | - |
| 351 | Roof Space Access | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-351-CS-01,02,03 | 20-Mar-07 | ND |
| 351 | Roof Space Access | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 351 | Roof Space Access | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 351A | Projector Room | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 351A | Projector Room | Wall | Plaster | - | - | Non-ACM | HM | S01 | 20-Mar-15 | ND |
| 351A | Projector Room | Ceiling | Plaster | - | - | Non-ACM | HM | S01 | 20-Mar-15 | ND |
| 351B | Roof Space Access | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 351B | Roof Space Access | Wall | Plaster | - | - | Non-ACM | SL | GCI-351-WP-01,02 | 20-Mar-07 | ND |
| 351B | Roof Space Access | Wall | Fireproofing | - | - | Non-ACM | SL | S02 | 20-Mar-15 | ND |
| 351B | Roof Space Access | Ceiling | Wood | - | - | Non-ACM | - | - | - | - |
| 351B | Roof Space Access | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-351-CS-01,02,03 | 20-Mar-07 | ND |
| 352 | Custodial | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 352 | Custodial | Wall | Plaster | - | | | | | | |
| 352 | Custodial | Wall | Drywall | - | - | Non-ACM | HM | GCI-302-DWC-04,05,06 | 20-Mar-07 | ND |
| 352 | Custodial | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 355 | Storage | Floor | 12"x12" Vinyl Floor Tile | Crème with Long Brown Streaks | - | Non-ACM | HM | 32523-800-Galt-S09 | 16-Mar-09 | ND |
| 355 | Storage | Wall | Hard Texture Coat | - | - | Non-ACM | HM | GCI-3rdFL-Stair-903-CS-01,02,03 | 20-Mar-07 | ND |
| 355 | Storage | Ceiling | Wood | - | - | Non-ACM | - | - | - | - |
| 355 | Storage | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 357 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 357 | Washroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 357 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 358 | Mechanical Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 358 | Mechanical Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 358 | Mechanical Room | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 358 | Mechanical Room | Piping | Pipe Fittings | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 358 | Mechanical Room | Piping | Pipe Insulation | - | F | ACM | HM | 005 Straight Pipe Insulation, Boy's Washroom 505 | 26-Oct-90 | 25-50% Chrysotile |
| 358 | Mechanical Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 358 | Mechanical Room | Ducting | Duct Expansion Joint | - | NF | ACM | VC | - | - | - |
| 359 | Mechanical Room | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 359 | Mechanical Room | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 359 | Mechanical Room | Ceiling | Concrete | - | - | Non-ACM | - | - | - | - |
| 359 | Mechanical Room | Piping | Pipe Fittings | Fibreglass | - | Non-ACM | - | - | - | - |
| 901 | Stairwell | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 901 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 901 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 901 | Stairwell | Piping | Pipe Fittings | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 901 | Stairwell | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 902 | Emergency Exit Stairwell | Not Inspected | | | | | | | | |
| 903 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 903 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-153-WP-01,02,03 | 20-Mar-07 | ND |
| 905 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 905 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 905 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 907 | Stairwell | Floor | Vinyl Sheet Flooring | Beige Cobblestone | NF | ACM | HM | 32523-800-Galt-S01a | 16-Mar-09 | 3.1% Chrysotile |
| 907 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 907 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 907 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 907 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 908 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 908 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 908 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 909 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 909 | Stairwell | Wall | Hard Texture Coat | - | - | Non-ACM | SL | GCI-313-CP-05 | 20-Mar-07 | ND |
| 909 | Stairwell | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 909 | Stairwell | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-313-CP-05 | 20-Mar-07 | ND |
| 909 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 909 | Stairwell | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 909 | Stairwell | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 910 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 910 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 910 | Stairwell | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-910-CS-01,02,03 | 20-Mar-07 | ND |
| 911 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 911 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 911 | Stairwell | Ceiling | Steel Deck | - | - | Non-ACM | - | - | - | - |
| 914 | Stairwell | Floor | Concrete | - | - | Non-ACM | - | - | - | - |
| 914 | Stairwell | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 914 | Stairwell | Ceiling | Steel Deck | - | - | Non-ACM | - | - | - | - |
| 8301 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8301 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8301 | Corridor | Ceiling | Hard Texture Coat | - | - | Non-ACM | HM | GCI-351-CS-01,02,03 | 20-Mar-07 | ND |
| 8301 | Corridor | Ceiling | 1'x1' Ceiling Tile | Medium and Small Pinhole (Cellulose) | - | Non-ACM | - | - | - | - |
| 8302 | Corridor | Floor | Vinyl Sheet Flooring | Beige Cobblestone | NF | ACM | HM | 32523-800-Galt-S01a | 16-Mar-09 | 3.1% Chrysotile |
| 8302 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 8302 | Corridor | Wall | Hard Texture Coat | - | - | Non-ACM | HM | GCI-351-CS-01,02,03 | 20-Mar-07 | ND |
| 8302 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8302 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8302 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |

| | | | | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|
| | **School Name** | | **Legend:** | | | | | **Notes:** | | | |
| | **Galt Collegiate Institute** | | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | | | | | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** | | | |
| | **Date Built:** | | | | | | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** | | | |
| | Original: 1853 | | | | | | | | | | |
| | Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | | | | | | | | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 8304 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8304 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8304 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8304 | Corridor | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-3rdFL-Stair-903-CS-01,02,03 | 20-Mar-07 | ND |
| 8304 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8304A | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 8304A | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8304A | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8207-CP-04 | 20-Mar-07 | ND |
| 8304A | Corridor | Ceiling | Hard Texture Coat | - | - | Non-ACM | SL | GCI-3rdFL-Stair-903-CS-01,02,03 | 20-Mar-07 | ND |
| 8304A | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8305 | Corridor | Floor | 12"x12" Vinyl Floor Tile | Crème with Long Brown Streaks | - | Non-ACM | SL | 32523-800-Galt-S09 | 16-Mar-09 | ND |
| 8305 | Corridor | Wall | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 8305 | Corridor | Wall | Hard Texture Coat | - | - | Non-ACM | HM | GCI-3rdFL-Stair-903-CS-01,02,03 | 20-Mar-07 | ND |
| 8305 | Corridor | Ceiling | Plaster | - | NF | ACM | HM | S02 | 14-Sep-17 | 1% Chrysotile |
| 8305 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8306 | Corridor | Floor | 12"x12" Vinyl Floor Tile | Light Beige Dense Fleck (Post 2007) | - | Non-ACM | - | - | - | - |
| 8306 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-311-CP-06 | 20-Mar-07 | ND |
| 8306 | Corridor | Wall | Concrete | - | - | Non-ACM | - | - | - | - |
| 8306 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-311-CP-06 | 20-Mar-07 | ND |
| 8306 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8306 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8307 | Corridor | Floor | Vinyl Sheet Flooring | Beige Cobblestone | NF | ACM | HM | 32523-800-Galt-S01a | 16-Mar-09 | 3.1% Chrysotile |
| 8307 | Corridor | Floor | Mastic | - | - | Non-ACM | SL | 32523-800-Galt-S01a | 16-Mar-09 | ND |
| 8307 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 8307 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8307 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 8307 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8307 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8308 | Corridor | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 8308 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 8308 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-313-WP-03 | 20-Mar-07 | ND |
| 8308 | Corridor | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8308 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 8309 | Corridor | Floor | Vinyl Sheet Flooring | Beige Cobblestone | NF | ACM | HM | 32523-800-Galt-S01a | 16-Mar-09 | 3.1% Chrysotile |
| 8309 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-356-WP-04 | 20-Mar-07 | ND |
| 8309 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8309 | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8309 | Corridor | Piping | Pipe Fittings | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 8309 | Corridor | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| | | | | | | | | | | |
| **Level 4** | | | | | | | | | | |
| | | | | | | | | | | |
| 401 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 401 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-401-WP-06 | 20-Mar-07 | ND |
| 401 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 401 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 401 | Classroom | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 401A | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 401A | Storage | Wall | Plaster | - | - | Non-ACM | SL | GCI-401A-WP-07 | 20-Mar-07 | ND |
| 401A | Storage | Wall | Texture Coat | - | - | Non-ACM | HM | S03ABC | 14-Nov-18 | ND |
| 401A | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 401B | Storage | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 401B | Storage | Wall | Plaster | - | - | Non-ACM | SL | GCI-401-WP-06 | 20-Mar-07 | ND |
| 401B | Storage | Wall | Drywall | - | - | Non-ACM | SL | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 401B | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 401C | Storage | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 401C | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 401C | Storage | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 401C | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 402 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Dense Fleck (Post 2009) | - | Non-ACM | - | - | - | - |
| 402 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 402 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 402A | Dark Room | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 402A | Dark Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 402A | Dark Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 402A | Dark Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 402A | Dark Room | Piping | Pipe Fitting | Parged Cement | F | ACM | HM | 003 Typical Elbow, Boiler Room | 26-Oct-90 | 50-75% Chrysotile |
| 402A | Dark Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 402AB | Dark Room | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | S02ABC | 16-Mar-09 | ND |
| 402AB | Dark Room | Wall | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 402AB | Dark Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 402AB | Dark Room | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 402AC | Classroom | Floor | 12"x12" Vinyl Floor Tile | Dense Fleck (Post 2009) | - | Non-ACM | - | - | - | - |
| 402AC | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 402AC | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 403 | Art Prep Room | Floor | 12"x12" Vinyl Floor Tile | Beige with Brown and White Fleck | NF | ACM | HM | 32523-800-Galt-S03 | 16-Mar-09 | 2.3% Chrysotile |
| 403 | Art Prep Room | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 403 | Art Prep Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 403 | Art Prep Room | Piping | Transite Pipe | - | NF | ACM | VC | - | - | - |
| 403 | Art Prep Room | Piping | Pipe Insulation | Fibreglass | - | Non-ACM | - | - | - | - |
| 403A | Kiln Room | Floor | 12"x12" Vinyl Floor Tile | Beige with Brown and White Fleck | NF | ACM | HM | 32523-800-Galt-S03 | 16-Mar-09 | 2.3% Chrysotile |
| 403A | Kiln Room | Mastic | Mastic | - | - | Non-ACM | HM | 32523-800-Galt-S03 | 16-Mar-09 | ND |
| 403A | Kiln Room | Floor | Brick | Refractory Brick | - | Non-ACM | - | - | - | - |
| 403A | Kiln Room | Wall | Plaster | - | - | Non-ACM | SL | GCI-405-WP-04 | 20-Mar-07 | ND |
| 403A | Kiln Room | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 403A | Kiln Room | Ceiling | Transite Paneling | - | NF | ACM | VC | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 404 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 404 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-404-WP-01,02,03 | 20-Mar-07 | ND |
| 404 | Classroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 404 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 404 | Classroom | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 405 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 405 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 405 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-405-DWC-03 | 20-Mar-07 | ND |
| 405 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 405 | Classroom | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-405-DWC-03 | 20-Mar-07 | ND |
| 406 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 406 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 406 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 406A | Office | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 406A | Office | Wall | Plaster | - | - | Non-ACM | SL | GCI-406A-WP-01 | 20-Mar-07 | ND |
| 406A | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 407 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Brown with Dense Fleck | - | Non-ACM | SL | 32523-800-Galt-S06 | 16-Mar-09 | ND |
| 407 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-407-WP-03 | 20-Mar-07 | ND |
| 407 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-407-DWC-03 | 20-Mar-07 | ND |
| 407 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 407A | Storage | Floor | 12"x12" Vinyl Floor Tile | Brown with Dense Fleck | - | Non-ACM | HM | 32523-800-Galt-S06 | 16-Mar-09 | ND |
| 407A | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-409-WP-04 | 20-Mar-07 | ND |
| 407A | Storage | Wall | Drywall | - | - | Non-ACM | HM | GCI-409-DWC-04 | 20-Mar-07 | ND |
| 407A | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 407B | Laundry | Floor | 12"x12" Vinyl Floor Tile | Brown with Dense Fleck | - | Non-ACM | HM | 32523-800-Galt-S06 | 16-Mar-09 | ND |
| 407B | Laundry | Wall | Plaster | - | - | Non-ACM | HM | GCI-409-WP-04 | 20-Mar-07 | ND |
| 407B | Laundry | Wall | Drywall | - | - | Non-ACM | HM | GCI-409-DWC-04 | 20-Mar-07 | ND |
| 407B | Laundry | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 407C | Kitchen | Floor | 12"x12" Vinyl Floor Tile | Brown with Dense Fleck | - | Non-ACM | HM | 32523-800-Galt-S06 | 16-Mar-09 | ND |
| 407C | Kitchen | Wall | Plaster | - | - | Non-ACM | HM | GCI-409-WP-04 | 20-Mar-07 | ND |
| 407C | Kitchen | Wall | Drywall | - | - | Non-ACM | HM | GCI-409-DWC-04 | 20-Mar-07 | ND |
| 407C | Kitchen | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 408 | Classroom | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 408 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 408 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 408A | Storage | Floor | 12"x12" Vinyl Floor Tile | Beige Dense Fleck | - | Non-ACM | HM | GCI-102-12x12FT | 16-Mar-09 | ND |
| 408A | Storage | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 408A | Storage | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 409 | Classroom | Floor | 9"x9" Vinyl Floor Tile | Beige with Brown and White Fleck | NF | ACM | SL | 32523-800-Galt-S07 | 16-Mar-09 | 2.8% Chrysotile |
| 409 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-409-WP-04 | 20-Mar-07 | ND |
| 409 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-409-DWC-04 | 20-Mar-07 | ND |
| 409 | Classroom | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 409 | Classroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-409-WP-04 | 20-Mar-07 | ND |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:**<br>Original: 1853<br>Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |


| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 409 | Classroom | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-409-DWC-04 | 20-Mar-07 | ND |
| 410 | Language | Floor | Carpet | - | - | Non-ACM | - | - | - | - |
| 410 | Language | Wall | Plaster | - | - | Non-ACM | SL | GCI-410-WP-02 | 20-Mar-07 | ND |
| 410 | Language | Wall | Drywall | - | - | Non-ACM | SL | GCI-453-DWC-01,02,03 | 20-Mar-07 | ND |
| 410 | Language | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 412 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 412 | Classroom | Wall | Plaster | - | - | Non-ACM | HM | GCI-414-WP-07 | 20-Mar-07 | ND |
| 412 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 412 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 412 | Classroom | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 414 | Classroom | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 414 | Classroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-414-WP-07 | 20-Mar-07 | ND |
| 414 | Classroom | Wall | Drywall | - | - | Non-ACM | SL | GCI-414-DWC-06 | 20-Mar-07 | ND |
| 414 | Classroom | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 414 | Classroom | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 416 | Office | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 416 | Office | Wall | Plaster | - | - | Non-ACM | SL | GCI-416-WP-06 | 20-Mar-07 | ND |
| 416 | Office | Wall | Drywall | - | - | Non-ACM | SL | GCI-416-DWC-05 | 20-Mar-07 | ND |
| 416 | Office | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 452 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 452 | Washroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-452-WP-03 | 20-Mar-07 | ND |
| 452 | Washroom | Wall | Drywall | - | - | Non-ACM | HM | GCI-405-DWC-03 | 20-Mar-07 | ND |
| 452 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 453 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 453 | Washroom | Wall | Drywall | - | - | Non-ACM | - | - | - | - |
| 453 | Washroom | Wall | Plaster | - | - | Non-ACM | - | - | - | - |
| 453 | Washroom | Ceiling | 2'x4' Ceiling Tile | Flat (Post 2007) | - | Non-ACM | - | - | - | - |
| 454 | Washroom | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 454 | Washroom | Wall | Concrete Block | - | - | Non-ACM | - | - | - | - |
| 454 | Washroom | Wall | Plaster | - | - | Non-ACM | SL | GCI-454-WP-05 | 20-Mar-07 | ND |
| 454 | Washroom | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-414-WP-07 | 20-Mar-07 | ND |
| 454 | Washroom | Pyroblock | Pyroblock | - | - | Non-ACM | SL | GCI-454-PB | 20-Mar-07 | ND |
| 455 | Custodial | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 455 | Custodial | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 455 | Custodial | Wall | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 455 | Custodial | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 903 | Stairwell | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |
| 903 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 903 | Stairwell | Ceiling | Hard Texture Coat | - | - | Non-ACM | HM | GCI-172-HardStucco | 20-Mar-07 | ND |
| 905 | Stairwell | Floor | Terrazzo | - | - | Non-ACM | - | - | - | - |
| 905 | Stairwell | Wall | Plaster | - | - | Non-ACM | HM | GCI-409-WP-04 | 20-Mar-07 | ND |
| 905 | Stairwell | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-409-WP-04 | 20-Mar-07 | ND |
| 8401 | Corridor | Floor | Ceramic Tile | - | - | Non-ACM | - | - | - | - |

| School Name | Legend: | Notes: |
|---|---|---|
| **Galt Collegiate Institute** | **HM -** Homogenous Material - homogeneous with previously sampled material<br>**SL** - Sample Location - Material Sampled<br>**VC** - Visually Confirmed - Material not sampled, deemed ACM<br>**NF** - Non-Friable<br>**F**- Friable | **All quantities provided on Figures, if known. Refer to the Asbestos Audit Update Report for condition of ACM and recommended actions.** |
| **Date Built:** | | **Dates provided in Material Description/Room Description columns indicates date of installation/renovation and confirms the finishes as non-ACM.** |
| Original: 1853 | | |
| Addition(s): 1876, 1906, 1923, 1929, 1954, 1956, 1962, 1986 | | |

| WRDSB Fixed Reference Number | Room Description | Inspected Item | Inspected Material | Material Description | Friability | Asbestos Classification | Sample / Identification Summary | Sample ID | Sample Date | % Asbestos & Fibre Type |
|---|---|---|---|---|---|---|---|---|---|---|
| 8401 | Corridor | Wall | Plaster | - | - | Non-ACM | SL | GCI-455-WP-07 | 20-Mar-07 | ND |
| 8401 | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 8401 | Corridor | Ceiling | Plaster | - | - | Non-ACM | HM | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 8401 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8404 | Corridor | Floor | Vinyl Sheet Flooring | Beige Cobblestone | NF | ACM | SL | 32523-800-Galt-S01a | 16-Mar-09 | 3.1% Chrysotile |
| 8404 | Corridor | Wall | Plaster | - | - | Non-ACM | SL | GCI-8404N-WP-01, 02 | 20-Mar-07 | ND |
| 8404 | Corridor | Wall | Drywall | - | - | Non-ACM | SL | GCI-8404N-DWC-01, 02 | 20-Mar-07 | ND |
| 8404 | Corridor | Ceiling | 2'x4' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8404 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8405 | Corridor | Floor | 12"x12" Vinyl Floor Tile | Beige with Brown and White Fleck | NF | ACM | SL | 32523-800-Galt-S03 | 16-Mar-09 | 2.3% Chrysotile |
| 8405 | Corridor | Wall | Plaster | - | - | Non-ACM | SL | GCI-8405-WP-05 | 20-Mar-07 | ND |
| 8405 | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-401-DWC-04 | 20-Mar-07 | ND |
| 8405 | Corridor | Wall | Hard Texture Coat | - | - | Non-ACM | HM | S03ABC | 14-Nov-18 | ND |
| 8405 | Corridor | Ceiling | 2'x2' Ceiling Tile | Textured Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S23 | 16-Mar-09 | ND |
| 8406 | Corridor | Floor | Wood | - | - | Non-ACM | - | - | - | - |
| 8406 | Corridor | Wall | Plaster | - | - | Non-ACM | HM | GCI-414-WP-07 | 20-Mar-07 | ND |
| 8406 | Corridor | Wall | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| 8406 | Corridor | Ceiling | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | - | Non-ACM | HM | 32523-800-Galt-S17 | 16-Mar-09 | ND |
| 8406 | Corridor | Ceiling | Drywall | - | - | Non-ACM | HM | GCI-412-DWC-07 | 20-Mar-07 | ND |
| | | | | | | | | | | |
| **Summary of Potential ACM Hidden or Not Assessed** | | | | | | | | | | |
| | | | | | | | | | | |
| | Throughout Building | Not Inspected | Not Inspected | Wall Cavity Insulation | | | | | | |
| | Throughout Building | Not Inspected | Not Inspected | Door Core Insulation | | | | | | |

# Appendix B

## Figures




| |
|---|
| Original Building - Interior Window Pane, Black Sealant is ACM |
| Original Building - Exterior Window Frame Sealant is Suspected to Contain Asbestos |
| Original Building - Exterior Window Pane Sealant is Suspected to Contain Asbestos |
| 1876 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos |
| 1876 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos |
| 1923 Addition - Exterior Door Pane, Black Sealant is ACM |
| 1923 Addition - Vinyl Floor Tile Mastic is ACM |
| 1929 Addition - Interior Window Pane, Black Sealant is ACM |
| 1929 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos |
| 1929 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos |
| 1954 Addition - Interior Window Frame, Grey Sealant is ACM |
| 1954 Addition - Interior Door Frame, Grey Sealant is ACM |
| 1954 Addition - Exterior Door Frame, Grey Sealant is ACM |
| 1962 Addition - Exterior Window Frame, Grey Sealant is ACM |
| 1962 Addition - Exterior Window Pane, Black/Grey Sealant is ACM |
| 1962 Addition - Interior Door Pane, Brown Sealant is ACM |
| 1962 Addition - Vinyl Floor Tile Mastic is ACM |
| 1986 Addition - Interior Window Frame, Grey Sealant is ACM |
| 1986 Addition - Exterior Window Frame, Grey Sealant is ACM |
| 1986 Addition - Exterior Window Pane, Black Sealant is ACM |
| 1986 Addition - Interior Door Pane, Black Sealant is ACM |
| 1986 Addition - Exterior Door Frame, Grey Sealant is ACM |
| 1986 Addition - Exterior Door Pane, Black Sealant is ACM |

**NOTES:**

ALL DRAWINGS TO BE REFERENCED WITH THE ASSOCIATED REPORT, LOCATIONS AND QUANTITIES ARE APPROXIMATE.

ALL KNOWN OR SUSPECT ASBESTOS-CONTAINING MATERIALS AND/OR DESIGNATED MATERIALS ARE NOT DEPICTED ON THIS DRAWING. REFER TO THE REPORT FOR A COMPLETE LIST OF IDENTIFIED MATERIALS.

THIS FIGURE IS COLOUR DEPENDENT, PHOTOCOPIES MAY ALTER INTERPRETATION OF THE FIGURE. ALWAYS REFER TO ORIGINAL DRAWINGS AND REPORT.

Legend

- 13 — Fixed Reference Number
- No Access
- Post 1986 Construction

Asbestos-Containing Materials (ACM):

- Floor Tile
- Rolled Flooring
- Ceiling Tile at Ceiling Level
- 1'x1' Ceiling Tiles Located within False Ceiling above non-ACM 2'x4' Ceiling Tiles
- Friable Soft Textured Ceiling
- Non-Friable Hard Textured Ceiling
- Spray-On Fire Proofing
- Transite (Asbestos Cement) Paneling
- Duct Insulation
- x2(1) — Pipe Fitting Insulation w Quantity (Brackets Indicate # of Damaged Fittings)
- Pipe Insulation (Vertical and Horizontal)
- Transite (Asbestos Cement) Pipe (Vertical and Horizontal)
- x2(1) — Duct Expansion Joints w Quantity (Brackets Indicate # of Damaged Joints)
- Friable Debris


MTE
Ph. (519) 743-6500 www.mte85.com



CLIENT
WATERLOO REGION DISTRICT SCHOOL BOARD

PROJECT
2024 ASBESTOS AUDIT UPDATE

DRAWING
GALT COLLEGIATE INSTITUTE

FIRST FLOOR

| | |
|---|---|
| Project Manager: P. Semeniuk | Date: JANUARY 2024 |
| Design By: WRDSB | Project No.: 34532-944 |
| Drawn By: S-P. Lemieux | Drawing No.: 1.0 |
| Scale: N.T.S. | |




Original Building - Interior Window Pane, Black Sealant is ACM
Original Building - Exterior Window Frame Sealant is Suspected to Contain Asbestos
Original Building - Exterior Window Pane Sealant is Suspected to Contain Asbestos
1876 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos
1876 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos
1923 Addition - Exterior Door Pane, Black Sealant is ACM
1923 Addition - Vinyl Floor Tile Mastic is ACM
1929 Addition - Interior Window Pane, Black Sealant is ACM
1929 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos
1929 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos
1954 Addition - Interior Window Frame, Grey Sealant is ACM
1954 Addition - Interior Door Frame, Grey Sealant is ACM
1954 Addition - Exterior Door Frame, Grey Sealant is ACM
1962 Addition - Exterior Window Frame, Grey Sealant is ACM
1962 Addition - Exterior Window Pane, Black/Grey Sealant is ACM
1962 Addition - Interior Door Pane, Brown Sealant is ACM
1962 Addition - Vinyl Floor Tile Mastic is ACM
1986 Addition - Interior Window Frame, Grey Sealant is ACM
1986 Addition - Exterior Window Frame, Grey Sealant is ACM
1986 Addition - Exterior Window Pane, Black Sealant is ACM
1986 Addition - Interior Door Pane, Black Sealant is ACM
1986 Addition - Exterior Door Frame, Grey Sealant is ACM
1986 Addition - Exterior Door Pane, Black Sealant is ACM

**NOTES:**

ALL DRAWINGS TO BE REFERENCED WITH THE ASSOCIATED REPORT, LOCATIONS AND QUANTITIES ARE APPROXIMATE.

ALL KNOWN OR SUSPECT ASBESTOS-CONTAINING MATERIALS AND/OR DESIGNATED MATERIALS ARE NOT DEPICTED ON THIS DRAWING. REFER TO THE REPORT FOR A COMPLETE LIST OF IDENTIFIED MATERIALS.

THIS FIGURE IS COLOUR DEPENDENT, PHOTOCOPIES MAY ALTER INTERPRETATION OF THE FIGURE. ALWAYS REFER TO ORIGINAL DRAWINGS AND REPORT.

Legend

- 13 — Fixed Reference Number
- No Access
- Post 1986 Construction

Asbestos-Containing Materials (ACM):

- Floor Tile
- Rolled Flooring
- Ceiling Tile at Ceiling Level
- 1'x1' Ceiling Tiles Located within False Ceiling above non-ACM 2'x4' Ceiling Tiles
- Friable Soft Textured Ceiling
- Non-Friable Hard Textured Ceiling
- Spray-On Fire Proofing
- Transite (Asbestos Cement) Paneling
- Duct Insulation
- x2(1) — Pipe Fitting Insulation w Quantity (Brackets Indicate # of Damaged Fittings)
- Pipe Insulation (Vertical and Horizontal)
- Transite (Asbestos Cement) Pipe (Vertical and Horizontal)
- x2(1) — Duct Expansion Joints w Quantity (Brackets Indicate # of Damaged Joints)
- Friable Debris

MTE
Ph. (519) 743-6500 www.mte85.com


CLIENT
WATERLOO REGION DISTRICT SCHOOL BOARD


PROJECT
2024 ASBESTOS AUDIT UPDATE


DRAWING
GALT COLLEGIATE INSTITUTE

SECOND FLOOR

| | |
|---|---|
| Project Manager: P. Semeniuk | Date: JANUARY 2024 |
| Design By: WRDSB | Project No.: 34532-944 |
| Drawn By: S-P. Lemieux | Drawing No.: 2.0 |
| Scale: N.T.S. | |




Original Building - Interior Window Pane, Black Sealant is ACM
Original Building - Exterior Window Frame Sealant is Suspected to Contain Asbestos
Original Building - Exterior Window Pane Sealant is Suspected to Contain Asbestos
1876 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos
1876 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos
1923 Addition - Exterior Door Pane, Black Sealant is ACM
1923 Addition - Vinyl Floor Tile Mastic is ACM
1929 Addition - Interior Window Pane, Black Sealant is ACM
1929 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos
1929 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos
1954 Addition - Interior Window Frame, Grey Sealant is ACM
1954 Addition - Interior Door Frame, Grey Sealant is ACM
1954 Addition - Exterior Door Frame, Grey Sealant is ACM
1962 Addition - Exterior Window Frame, Grey Sealant is ACM
1962 Addition - Exterior Window Pane, Black/Grey Sealant is ACM
1962 Addition - Interior Door Pane, Brown Sealant is ACM
1962 Addition - Vinyl Floor Tile Mastic is ACM
1986 Addition - Interior Window Frame, Grey Sealant is ACM
1986 Addition - Exterior Window Frame, Grey Sealant is ACM
1986 Addition - Exterior Window Pane, Black Sealant is ACM
1986 Addition - Interior Door Pane, Black Sealant is ACM
1986 Addition - Exterior Door Frame, Grey Sealant is ACM
1986 Addition - Exterior Door Pane, Black Sealant is ACM

**NOTES:**

ALL DRAWINGS TO BE REFERENCED WITH THE ASSOCIATED REPORT, LOCATIONS AND QUANTITIES ARE APPROXIMATE.

ALL KNOWN OR SUSPECT ASBESTOS-CONTAINING MATERIALS AND/OR DESIGNATED MATERIALS ARE NOT DEPICTED ON THIS DRAWING. REFER TO THE REPORT FOR A COMPLETE LIST OF IDENTIFIED MATERIALS.

THIS FIGURE IS COLOUR DEPENDENT, PHOTOCOPIES MAY ALTER INTERPRETATION OF THE FIGURE. ALWAYS REFER TO ORIGINAL DRAWINGS AND REPORT.

Legend

- 13 — Fixed Reference Number
- No Access
- Post 1986 Construction

Asbestos-Containing Materials (ACM):

- Floor Tile
- Rolled Flooring
- Ceiling Tile at Ceiling Level
- 1'x1' Ceiling Tiles Located within False Ceiling above non-ACM 2'x4' Ceiling Tiles
- Friable Soft Textured Ceiling
- Non-Friable Hard Textured Ceiling
- Spray-On Fire Proofing
- Transite (Asbestos Cement) Paneling
- Duct Insulation
- x2(1) — Pipe Fitting Insulation w Quantity (Brackets Indicate # of Damaged Fittings)
- Pipe Insulation (Vertical and Horizontal)
- Transite (Asbestos Cement) Pipe (Vertical and Horizontal)
- x2(1) — Duct Expansion Joints w Quantity (Brackets Indicate # of Damaged Joints)
- Friable Debris

MTE
Ph. (519) 743-6500 www.mte85.com


CLIENT
WATERLOO REGION DISTRICT SCHOOL BOARD


PROJECT
2024 ASBESTOS AUDIT UPDATE


DRAWING
GALT COLLEGIATE INSTITUTE

THIRD FLOOR

| | |
|---|---|
| Project Manager: P. Semeniuk | Date: JANUARY 2024 |
| Design By: WRDSB | Project No.: 34532-944 |
| Drawn By: S-P. Lemieux | Drawing No.: 3.0 |
| Scale: N.T.S. | |




| |
|---|
| Original Building - Interior Window Pane, Black Sealant is ACM |
| Original Building - Exterior Window Frame Sealant is Suspected to Contain Asbestos |
| Original Building - Exterior Window Pane Sealant is Suspected to Contain Asbestos |
| 1876 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos |
| 1876 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos |
| 1923 Addition - Exterior Door Pane, Black Sealant is ACM |
| 1923 Addition - Vinyl Floor Tile Mastic is ACM |
| 1929 Addition - Interior Window Pane, Black Sealant is ACM |
| 1929 Addition - Exterior Window Frame Sealant is Suspected to Contain Asbestos |
| 1929 Addition - Exterior Window Pane Sealant is Suspected to Contain Asbestos |
| 1954 Addition - Interior Window Frame, Grey Sealant is ACM |
| 1954 Addition - Interior Door Frame, Grey Sealant is ACM |
| 1954 Addition - Exterior Door Frame, Grey Sealant is ACM |
| 1962 Addition - Exterior Window Frame, Grey Sealant is ACM |
| 1962 Addition - Exterior Window Pane, Black/Grey Sealant is ACM |
| 1962 Addition - Interior Door Pane, Brown Sealant is ACM |
| 1962 Addition - Vinyl Floor Tile Mastic is ACM |
| 1986 Addition - Interior Window Frame, Grey Sealant is ACM |
| 1986 Addition - Exterior Window Frame, Grey Sealant is ACM |
| 1986 Addition - Exterior Window Pane, Black Sealant is ACM |
| 1986 Addition - Interior Door Pane, Black Sealant is ACM |
| 1986 Addition - Exterior Door Frame, Grey Sealant is ACM |
| 1986 Addition - Exterior Door Pane, Black Sealant is ACM |

**NOTES:**

ALL DRAWINGS TO BE REFERENCED WITH THE ASSOCIATED REPORT, LOCATIONS AND QUANTITIES ARE APPROXIMATE.

ALL KNOWN OR SUSPECT ASBESTOS-CONTAINING MATERIALS AND/OR DESIGNATED MATERIALS ARE NOT DEPICTED ON THIS DRAWING. REFER TO THE REPORT FOR A COMPLETE LIST OF IDENTIFIED MATERIALS.

THIS FIGURE IS COLOUR DEPENDENT, PHOTOCOPIES MAY ALTER INTERPRETATION OF THE FIGURE. ALWAYS REFER TO ORIGINAL DRAWINGS AND REPORT.

Legend

- 13 — Fixed Reference Number
- No Access
- Post 1986 Construction

Asbestos-Containing Materials (ACM):

- Floor Tile
- Rolled Flooring
- Ceiling Tile at Ceiling Level
- 1'x1' Ceiling Tiles Located within False Ceiling above non-ACM 2'x4' Ceiling Tiles
- Friable Soft Textured Ceiling
- Non-Friable Hard Textured Ceiling
- Spray-On Fire Proofing
- Transite (Asbestos Cement) Paneling
- Duct Insulation
- x2(1) — Pipe Fitting Insulation w Quantity (Brackets Indicate # of Damaged Fittings)
- Pipe Insulation (Vertical and Horizontal)
- Transite (Asbestos Cement) Pipe (Vertical and Horizontal)
- x2(1) — Duct Expansion Joints w Quantity (Brackets Indicate # of Damaged Joints)
- Friable Debris

MTE
Ph. (519) 743-6500 www.mte85.com

CLIENT
WATERLOO REGION DISTRICT SCHOOL BOARD

PROJECT
2024 ASBESTOS AUDIT UPDATE

DRAWING
GALT COLLEGIATE INSTITUTE


FOURTH FLOOR

| | |
|---|---|
| Project Manager: P. Semeniuk | Date: JANUARY 2024 |
| Design By: WRDSB | Project No.: 34532-944 |
| Drawn By: S-P. Lemieux | Drawing No.: 4.0 |
| Scale: N.T.S. | |

# Appendix C

# Tables


| TABLE 1 - INTERNAL ABATEMENT MANAGEMENT | | | | | | |
|---|---|---|---|---|---|---|
| **Galt Collegiate Institute** | | | | | | |
| **Material** | **WRDSB Fixed Reference Number** | **Material Description** | **Approximate Quantity** | **Photograph - Context** | **Photograph - Detail** | **Required Action** |
| **Asbestos Non-Friable** | 117A | 9" x 9" Green Floor Tile and exposed mastic | Throughout |  |  | Repair/Removal in accordance with O. Reg. 278/05 as a Type 1 Operation |
| **Asbestos Non-Friable** | 119 | 9" x 9" Green Floor Tile | 2 Tiles |  |  | Monitor Annually |
| **Abestos Friable** | Throughout above ceiling | Pipe Fittings - Fittings Throughout Building are unjacketed and are or have the potential to Fail/Fall | Throughout ceiling space |  |  | It is recommended that unjacketed fittings be removed throughout the building, as they are failing and have a high potential to create a hazardous condition when this occurs. See Table 2 - Location 8101C for an example of a failed fitting with debris. |
| **Asbestos Non-Friable** | 203 | 12"x12" Tan with Brown Floor Tile | <1m$^2$ |  |  | Monitor Annually |
| **Asbestos Non-Friable** | 8205 | 12"x12" Tan with Brown Floor Tile | <1m$^2$ |  |  | Monitor Annually |

| TABLE 1 - INTERNAL ABATEMENT MANAGEMENT | | | | | | |
|---|---|---|---|---|---|---|
| **Galt Collegiate Institute** | | | | | | |
| **Material** | **WRDSB Fixed Reference Number** | **Material Description** | **Approximate Quantity** | **Photograph - Context** | **Photograph - Detail** | **Required Action** |
| **Asbestos Non-Friable** | 213A | Floor Tile Mastic | <1m$^2$ |  |  | Repair/Removal in accordance with O. Reg. 278/05 as a Type 1 Operation |
| **Asbestos Non-Friable** | 301 | 12"x12" Tan with Brown Floor Tile<br>Tile is lifting cracking and failing throughout the room | Throughout |  |  | Removal in accordance with O. Reg. 278/05 as a Type 1 Operation |
| **Asbestos Non-Friable** | 403A - kiln | Transite Panel | <0.5 m$^2$ |  |  | Monitor Annually |
| **Asbestos Non-Friable** | 403 | 12"x12" Beige with Brown Floor Tile | 3 Tiles |  |  | Monitor Annually |
| **Asbestos Non-Friable** | 409 | 9"x9" Beige with Brown Floor Tile | 3 Tiles |  |  | Monitor Annually |

| TABLE 1 - INTERNAL ABATEMENT MANAGEMENT | | | | | | |
|---|---|---|---|---|---|---|
| **Galt Collegiate Institute** | | | | | | |
| **Material** | **WRDSB Fixed Reference Number** | **Material Description** | **Approximate Quantity** | **Photograph - Context** | **Photograph - Detail** | **Required Action** |
| **Asbestos Non-Friable** | 8302 | Vinyl Sheet Flooring - Beige Pebble Pattern | <1m$^2$ |  |  | Monitor Annually |
| **Asbestos Non-Friable** | 8307 | Vinyl Sheet Flooring - Beige Pebble Pattern | <1m$^2$ |  |  | Monitor Annually |
| **Asbestos Non-Friable** | 8404 | Vinyl Sheet Flooring - Beige Pebble Pattern | Throughout |  |  | Seal Seam in accordance with O. Reg. 278/05 as a Type 1 Operation |
| **Asbestos Non-Friable** | 8404 | Vinyl Sheet Flooring - Beige Pebble Pattern | Throughout |  |  | Monitor Annually |
| **Asbestos Non-Friable** | 207 | 1' x 1' Ceiling Tiles | 1 Loose Tile, Damaged Tiles (Above Drop Ceiling and at Window Sill) |  |  | Secure/Remove Loose Tile in accordance with O. Reg. 278/05 as a Type 1 Operation<br>Monitor Remaining Tiles Annually |



| TABLE 1 - INTERNAL ABATEMENT MANAGEMENT | | | | | | |
|---|---|---|---|---|---|---|
| **Galt Collegiate Institute** | | | | | | |
| **Material** | **WRDSB Fixed Reference Number** | **Material Description** | **Approximate Quantity** | **Photograph - Context** | **Photograph - Detail** | **Required Action** |
| **Asbestos Non-Friable** | 8213 | Vinyl Sheet Flooring - Beige Pebble Pattern | <1m$^2$ |  |  | Monitor Annually |

Notes:
1) A copy of this report should be provided to all prospective contractors prior to tender or quotation, in accordance with Section 30 of the Occupational Health and Safety Act.
2) Recommended actions are the minimum required actions, as prescribed by the appropriate Acts, regulations, guidelines, standards, codes and general best practice measures. The Contractor may choose to alter the approach and combine or break out sections of work. This is acceptable provided that the appropriate Acts, regulations, guidelines, standards and codes are followed and afford protection for the health and safety of workers, occupants and the public that is at least equal to the protection that would be provided by complying with the minimum requirements.
3) All waste generated is subject to characterization and disposal in accordance with Ontario Regulation 347.

| TABLE 2 - EXTERNAL ABATEMENT MANAGEMENT | | | | | | |
|---|---|---|---|---|---|---|
| **Galt Collegiate Institute** | | | | | | |
| **Material** | **WRDSB Fixed Reference Number** | **Material Description** | **Approximate Quantity** | **Photograph - Context** | **Photograph - Detail** | **Required Action** |
| **Asbestos Friable** | 8101C | Fitting Debris on Ceiling Tiles | <1m$^2$ |  |  | **Restrict all access above ceiling in Corridor 8101C and any adjacent corridors that connect to 8101C (8101D, 8106) above ceiling. Access shall only occur in accordance with O. Reg. 278/05 as a Type 2 Operation** Cleaning and Removal in accordance with O. Reg. 278/05 as a Type 2 Operation |
| **Asbestos Friable** | 103 | Insulation on Pipe Fitting | 1 |  |  | Removal in accordance with O. Reg. 278/05 as a Type 2 Operation **NOTE: Ensure an adequate approval inspection occurs following all asbestos abatement work** |
| **Asbestos Friable** | 167 | Insulation on Pipe Fitting | 1 |  |  | Removal in accordance with O. Reg. 278/05 as a Type 2 Operation |
| **Asbestos Friable** | 177 | Insulation Debris at Removed Pipe Fittings,<br><br>NOTE: Concrete and Plaster Debris on Ceiling Tiles | <1m$^2$ |  |  | Cleaning/Removal in accordance with O. Reg. 278/05 as a Type 2 Operation |

## TABLE 2 - EXTERNAL ABATEMENT MANAGEMENT

### Galt Collegiate Institute

| Material | WRDSB Fixed Reference Number | Material Description | Approximate Quantity | Photograph - Context | Photograph - Detail | Required Action |
|---|---|---|---|---|---|---|
| **Asbestos Friable** | 358 | Insulation Debris Below Removed Pipe Fittings at Site of Water Loss and Repairs. Assume debris may contaion asbestos due to location and fittings removed as part of work at locaiton | <1m$^2$ |  |  | Cleaning/Removal in accordance with O. Reg. 278/05 as a Type 2 Operation<br>**NOTE: Ensure an adequate approval inspection occurs following all asbestos abatement work** |
| **Asbestos Friable** | 358 | Incomplete or Unsecured Removal of Pipe Fittings | <1m$^2$ |  |  | Cleaning/Removal in accordance with O. Reg. 278/05 as a Type 2 Operation<br>**NOTE: Ensure an adequate approval inspection occurs following all asbestos abatement work** |
| **Asbestos Friable** | 8214 | Damaged Insulation on Pipe Fittings at ceiling opening | 1 |  |  | Replace Ceiling Tile,<br>Cleaning/Removal in accordance with O. Reg. 278/05 as a Type 2 Operation |
| **Asbestos Friable** | 8106 | Insulation on Pipe Straights at fitting exposed and debris on celiing tiles | <1m |  |  | Cleaning/Removal in accordance with O. Reg. 278/05 as a Type 2 Operation |

Notes:
1) A copy of this report should be provided to all prospective contractors prior to tender or quotation, in accordance with Section 30 of the Occupational Health and Safety Act.
2) Recommended actions are the minimum required actions, as prescribed by the appropriate Acts, regulations, guidelines, standards, codes and general best practice measures. The Contractor may choose to alter the approach and combine or break out sections of work. This is acceptable provided that the appropriate Acts, regulations, guidelines, standards and codes are followed and afford protection for the health and safety of workers, occupants and the public that is at least equal to the protection that would be provided by complying with the minimum requirements.
3) All waste generated is subject to characterization and disposal in accordance with Ontario Regulation 347.

| TABLE 3: BULK ASBESTOS SAMPLING SUMMARY | | | | | | |
|---|---|---|---|---|---|---|
| **Sample #** | **Location** | **Material Description** | **Material Description** | **Asbestos Content (%)** | **Fibre Type** | **Is Material ACM** |
| **March 20, 2007 Asbestos Audit Update** | | | | | | |
| GCI-402-12x12FT | 4021 | 12x12 Floor Tile | Beige with Tan and Grey | ND | - | No |
| GCI-108-12x12FT | 1093 | 12x12 Floor Tile | Crème and Burgundy Fleck | ND | - | No |
| **GCI-105A-9x9FT** | **1041** | **9x9 Floor Tile** | **-** | **1** | **Chrysotile** | **Yes** |
| **GCI-105A-12x12FT** | **1041** | **12x12 Floor Tile** | **Beige with Brown and White Fleck** | **0.5** | **Chrysotile** | **Yes** |
| GCI-102-12x12FT | 1080 | 12x12 Floor Tile | Beige Dense Fleck | ND | - | No |
| GCI-408-9x9FT | 4029 | 9x9 Floor Tile | Brown with Dark Brown | ND | - | No |
| GCI-408-9x9FT-GRN | 4029 | 9x9 Floor Tile | Green with White Streak | ND | - | No |
| GCI-356-12x12FT | 3008 | 12x12 Floor Tile | - | ND | - | No |
| GCI-206A-12x12FT | 2108 | 12x12 Floor Tile | Beige Dense Fleck | ND | - | No |
| GCI-305-12x12FT | 3044 | 12x12 Floor Tile | Brown with Dark Brown Fleck | ND | - | No |
| GCI-301-12x12FT | 3040 | | | ND | - | No |
| GCI-301A-12x12FT | 3036 | | | ND | - | No |
| **GCI-8205-12x12FT** | **2072** | **12x12 Floor Tile** | **Brown with Dark Brown Fleck** | **1** | **Chrysotile** | **Yes** |
| GCI-115-9x9FT | 1020 | 9x9 Floor Tile | Green with White Streak | 0.3 | Chrysotile | Yes |
| GCI-215-9x9FT | 2040 | 9x9 Floor Tile | Light Yellow | 0.2 | Chrysotile | Yes |
| GCI-217-9x9FT | 2038 | 9x9 Floor Tile | White with Green and Grey | 0.1 | Chrysotile | Yes |
| GCI-8108B,RAMP-12x12FT | 1011 | 12x12 Floor Tile | Brown Dense Fleck | ND | - | No |
| GCI-305-FS-01 | 3041 | Firespray | Firespray | ND | - | No |
| GCI-305-FS-02 | 3041 | | | ND | - | No |
| GCI-305-FS-03 | 3041 | | | ND | - | No |
| GCI-170-LF | 1048 | Linoleum Flooring | Beige Cobblestone (Gold) | ND | - | No |
| GCI-8404-LF | 4006 | | | ND | - | No |
| GCI-8101A-LF | 1011 | | | ND | - | No |
| GCI-189-LIN | 1000 | | | ND | - | No |
| GCI-906-LF | 1086 | Linoleum Flooring | Gold | ND | - | No |
| GCI-8217,8218-RLF | 2009 | Rolled Linoleum Flooring | Gold | ND | - | No |
| GCI-101-1x1ACT-RH | 1050 | 1x1 Ceiling Tile | Random Hole | ND | - | No |
| GCI-101-1x1ACT-RPH | 1050 | 1x1 Ceiling Tile | Random Pinhole | ND | - | No |
| GCI-906-1x1ACT | 1087 | 1x1 Ceiling Tile | Random Pinhole | ND | - | No |
| GCI-212(PR1)-1x1ACT | 2125 | 1x1 Ceiling Tile | Random Pinhole | ND | - | No |
| GCI-107D-1x1ACT-WHT | 1042 | 1x1 Ceiling Tile | - | ND | - | No |
| GCI-107D-1x1ACT-TAN | 1042 | 1x1 Ceiling Tile | - | ND | - | No |
| GCI-103A-1x1ACT | 1046 | 1x1 Ceiling Tile | Medium and Small Pinhole | ND | - | No |
| GCI-165A-CT | 1062 | 2x4 Ceiling Tile | Textured Pinhole | ND | - | No |
| GCI-8101A-4x2CT-SFPH | 1011 | 2x4 Ceiling Tile | Short Fissure Random Pinhole | ND | - | No |
| GCI-304B-4x2CT | 3020 | 2x4 Ceiling Tile | Long Fissure Random Pinhole | ND | - | No |
| GCI-305-4x2CT | 3018 | 2x4 Ceiling Tile | Long Fissure Random Pinhole | ND | - | No |
| GCI-250-1x1ACT | 2082 | 1x1 Ceiling Tile | Cellulose | ND | - | No |
| **GCI-207-1x1ACT** | **2068** | **1x1 Ceiling Tile** | **Patterned Pinhole** | **1** | **Amosite** | **Yes** |
| GCI-8217,8218-2x2CT | 2009 | 2x2 Ceiling Tile | Textured Pinhole | ND | - | No |
| GCI-172-HardStucco-01 | 1089 | Hard Stucco | Ceiling | ND | - | No |
| GCI-172-HardStucco-02 | | | | ND | - | No |
| GCI-172-HardStucco-03 | | | | ND | - | No |
| GCI-8206B-PARGE | 2099 | Parging | On Mechanical | ND | - | No |
| GCI-108-PARGE-01 | 1093 | Parging | On Beam | ND | - | No |
| GCI-108-PARGE-02 | | | | ND | - | No |
| GCI-108-PARGE-03 | | | | ND | - | No |
| GCI-8211-CS-01 | 2113 | Stucco | Ceiling | ND | - | No |
| GCI-8211-CS-02 | | | | ND | - | No |
| GCI-8211-CS-03 | | | | ND | - | No |
| GCI-910-CS-01 | 2130 | Ceiling Stucco | Ceiling | ND | - | No |
| GCI-910-CS-02 | 2130 | | | ND | - | No |
| GCI-910-CS-03 | 2130 | | | ND | - | No |
| GCI-351-CS-01 | 3028 | Ceiling Stucco | Ceiling | ND | - | No |
| GCI-351-CS-02 | 3028 | | | ND | - | No |
| GCI-351-CS-03 | 3028 | | | ND | - | No |
| GCI-3rdFL-Stair-903-CS-01 | 3031 | Ceiling Stucco | Ceiling | ND | - | No |
| GCI-3rdFL-Stair-903-CS-02 | 3031 | | | ND | - | No |
| GCI-3rdFL-Stair-903-CS-03 | 3031 | | | ND | - | No |
| GCI-902-CS-01 | 3030 | Ceiling Stucco | Ceiling | ND | - | No |
| GCI-902-CS-02 | 3030 | | | ND | - | No |
| GCI-902-CS-03 | 3030 | | | ND | - | No |
| GCI-189-CS-01 | 1000 | | | ND | - | No |
| GCI-189-CS-02 | 1000 | | | ND | - | No |
| GCI-189-CS-03 | 1000 | | | ND | - | No |
| GCI-189-CS-04 | 1000 | | | ND | - | No |
| GCI-189-CS-05 | 1000 | | | ND | - | No |

| TABLE 3: BULK ASBESTOS SAMPLING SUMMARY | | | | | | |
|---|---|---|---|---|---|---|
| **Sample #** | **Location** | **Material Description** | **Material Description** | **Asbestos Content (%)** | **Fibre Type** | **Is Material ACM** |
| GCI-153-UCP-01 | 1060 | Plaster | Upper Ceiling | ND | - | No |
| GCI-153-UCP-02 | | | | ND | - | No |
| GCI-153-UCP-03 | | | | ND | - | No |
| GCI-153-CP-01 | 1060 | Plaster | Ceiling | ND | - | No |
| GCI-153-CP-02 | | | | ND | - | No |
| GCI-153-CP-03 | | | | ND | - | No |
| GCI-167-CP-01 | 1054 | Plaster | Ceiling | ND | - | No |
| GCI-167-CP-02 | | | | ND | - | No |
| GCI-167-CP-03 | | | | ND | - | No |
| GCI-103A-CP-01 | 1046 | Plaster | Ceiling | ND | - | No |
| GCI-103A-CP-02 | | | | ND | - | No |
| GCI-103A-CP-03 | | | | ND | - | No |
| GCI-174-CP-01 | 1095 | Plaster | Ceiling | ND | - | No |
| GCI-174-CP-02 | | | | ND | - | No |
| GCI-174-CP-03 | | | | ND | - | No |
| GCI-208-CP-01 | 2110 | Plaster | Ceiling | ND | - | No |
| GCI-201-CP-02 | 2076 | | | ND | - | No |
| GCI-207-CP-03 | 2069 | | | ND | - | No |
| GCI-8207-CP-04 | 2087 | | | ND | - | No |
| GCI-275-CP-05 | 2031 | | | ND | - | No |
| GCI-214B-CP-06 | 2036 | | | ND | - | No |
| GCI-8101B-CP-01 | 1108 | Plaster | Ceiling | ND | - | No |
| GCI-8101B-CP-02 | 1108 | | | ND | - | No |
| GCI-8101B-CP-03 | 1108 | | | ND | - | No |
| GCI-8101B-CP-04 | 1108 | | | ND | - | No |
| GCI-314-CP-01 | 3012 | Plaster | Ceiling | ND | - | No |
| GCI-314-CP-02 | 3012 | | | ND | - | No |
| GCI-310-CP-03 | 3014 | | | ND | - | No |
| GCI-317-CP-04 | 3052 | | | ND | - | No |
| GCI-313-CP-05 | 3049 | | | ND | - | No |
| GCI-311-CP-06 | 3047 | | | ND | - | No |
| GCI-309-CP-07 | 3046 | | | ND | - | No |
| GCI-356-CP-01 | 3008 | Plaster | Ceiling | ND | - | No |
| GCI-106-WP-01 | 1092 | Plaster | Wall | ND | - | No |
| GCI-106-WP-02 | 1092 | | | ND | - | No |
| GCI-106-WP-03 | 1092 | | | ND | - | No |
| GCI-153-WP-01 | 1060 | Plaster | Wall | ND | - | No |
| GCI-153-WP-02 | 1060 | | | ND | - | No |
| GCI-153-WP-03 | 1060 | | | ND | - | No |
| GCI-8103-WP-01 | 1094 | Plaster | Wall | ND | - | No |
| GCI-8103-WP-02 | 1094 | | | ND | - | No |
| GCI-8103-WP-03 | 1094 | | | ND | - | No |
| GCI-404-WP-01 | 4024 | Plaster | Wall | ND | - | No |
| GCI-404-WP-02 | 4024 | | | ND | - | No |
| GCI-404-WP-03 | 4024 | | | ND | - | No |
| GCI-8404N-WP-01 | 4006 | Plaster | Wall | ND | - | No |
| GCI-8404N-WP-02 | 4006 | | | ND | - | No |
| GCI-407-WP-03 | 4001 | | | ND | - | No |
| GCI-409-WP-04 | 4000 | | | ND | - | No |
| GCI-454-WP-05 | 4033 | | | ND | - | No |
| GCI-416-WP-06 | 4034 | | | ND | - | No |
| GCI-414-WP-07 | 4032 | | | ND | - | No |
| GCI-406A-WP-01 | 4025 | Plaster | Wall | ND | - | No |
| GCI-410-WP-02 | 4030 | | | ND | - | No |
| GCI-452-WP-03 | 4007 | | | ND | - | No |
| GCI-405-WP-04 | 4008 | | | ND | - | No |
| GCI-8405-WP-05 | 4015 | | | ND | - | No |
| GCI-401-WP-06 | 4016 | | | ND | - | No |
| GCI-455-WP-07 | 4019 | | | ND | - | No |
| GCI-310-WP-01 | 3014 | Plaster | Wall | ND | - | No |
| GCI-317-WP-02 | 3052 | | | ND | - | No |
| GCI-313-WP-03 | 3049 | | | ND | - | No |
| GCI-356-WP-04 | 3008 | | | ND | - | No |
| GCI-314-WP-05 | 3012 | | | ND | - | No |
| GCI-311-WP-06 | 3047 | | | ND | - | No |
| GCI-314-WP-07 | 3012 | | | ND | - | No |

| TABLE 3: BULK ASBESTOS SAMPLING SUMMARY | | | | | | |
|---|---|---|---|---|---|---|
| **Sample #** | **Location** | **Material Description** | **Material Description** | **Asbestos Content (%)** | **Fibre Type** | **Is Material ACM** |
| GCI-8206A-WP-01 | 2036 | Plaster | Wall | ND | - | No |
| GCI-208-WP-02 | 2110 | | | ND | - | No |
| GCI-202-WP-03 | 2099 | | | ND | - | No |
| GCI-258-WP-04 | 2092 | | | ND | - | No |
| GCI-201-WP-05 | 2076 | | | ND | - | No |
| GCI-205-WP-06 | 2071 | | | ND | - | No |
| GCI-207-WP-07 | 2069 | | | ND | - | No |
| GCI-8101B-WP-01 | 1108 | Plaster | Wall | ND | - | No |
| GCI-8101B-WP-02 | 1108 | | | ND | - | No |
| GCI-8101B-WP-03 | 1108 | | | ND | - | No |
| GCI-8101B-WP-04 | 1108 | | | ND | - | No |
| GCI-351-WP-01 | 3028 | Plaster | Wall | ND | - | No |
| GCI-351-WP-02 | 3028 | Plaster | Wall | ND | - | No |
| GCI-401A-WP-07 | 4014 | Plaster | Wall | ND | - | No |
| GCI-8101B-PI | 1108 | Pipe Insulation | On Straight | ND | - | No |
| GCI-152-PI | 1067 | Pipe Insulation | On Straight | ND | - | No |
| GCI-454-PB | 4033 | Pyro Block | - | ND | - | No |
| **GCI-BR-VERM** | **Boiler Room Assume Throughout** | **Vermiculite** | **Ceiling Patch** | **5** | **Chrysotile** | **Yes** |
| GCI-109A-DWC-01 | 1037 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-109A-DWC-02 | | | Wall | ND | - | No |
| GCI-109A-DWC-03 | | | Wall | ND | - | No |
| GCI-8103-DWC-01 | 1094 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-8103-DWC-02 | 1094 | | Wall | ND | - | No |
| GCI-8103-DWC-03 | 1094 | | Wall | ND | - | No |
| GCI-453-DWC-01 | 4037 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-453-DWC-02 | 4037 | | Wall | ND | - | No |
| GCI-453-DWC-03 | 4037 | | Wall | ND | - | No |
| GCI-316-DWC-01 | 3006 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-316-DWC-02 | 3006 | | Wall | ND | - | No |
| GCI-316-DWC-03 | 3006 | | Wall | ND | - | No |
| GCI-8206A-DWC-01 | 2036 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-8206A-DWC-02 | 2036 | | | ND | - | No |
| GCI-8206A-DWC-03 | 2036 | | | ND | - | No |
| GCI-202-DWC-04 | 2099 | | | ND | - | No |
| GCI-203-DWC-05 | 2072 | | | ND | - | No |
| GCI-205-DWC-06 | 2071 | | | ND | - | No |
| GCI-259-DWC-07 | 2070 | | | ND | - | No |
| GCI-8404N-DWC-01 | 4006 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-8404N-DWC-02 | 4006 | | | ND | - | No |
| GCI-407-DWC-03 | 4001 | | | ND | - | No |
| GCI-409-DWC-04 | 4000 | | | ND | - | No |
| GCI-416-DWC-05 | 4034 | | | ND | - | No |
| GCI-414-DWC-06 | 4032 | | | ND | - | No |
| GCI-412-DWC-07 | 4031 | | | ND | - | No |
| GCI-405-DWC-03 | 4008 | Drywall Joint Compound | | ND | - | No |
| GCI-401-DWC-04 | 4016 | Drywall Joint Compound | | ND | - | No |
| GCI-301-DWC-04 | 3036 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-301-DWC-05 | 3036 | | Wall | ND | - | No |
| GCI-301-DWC-06 | 3036 | | Wall | ND | - | No |
| GCI-302-DWC-07 | 3020 | Drywall Joint Compound | Wall | ND | - | No |
| GCI-302-DWC-08 | 3020 | | Wall | ND | - | No |
| GCI-302-DWC-09 | 3020 | | Wall | ND | - | No |
| **March 16, 2009 Asbestos Audit Update** | | | | | | |
| **32523-800-Galt-S01a** | **4006** | **Vinyl sheet flooring** | **Beige Cobblestone (Gold)** | **ND** | **-** | **No** |
| **32523-800-Galt-S01b** | | | | **3.1 (flooring)<br>ND (mastic)** | **Chrysotile<br>-** | **Yes** |
| 32523-800-Galt-S02a | 4021 | 12"x12" Floor Tile | Beige Dense Fleck | ND | - | No |
| 32523-800-Galt-S02b | | | | ND | - | No |
| 32523-800-Galt-S02c | | | | ND | - | No |
| **32523-800-Galt-S03a** | **4015** | **12"x12" Floor Tile** | **Beige with Brown and White Fleck** | **2.3 (tile)<br>ND (mastic)** | **Chrysotile<br>-** | **Yes** |
| **32523-800-Galt-S03b** | | | | **ND (tile)<br>ND (mastic)** | **-<br>-** | **No** |
| **32523-800-Galt-S03c** | | | | **ND (tile)<br>ND (mastic)** | **-<br>-** | **No** |
| 32523-800-Galt-S04a | 4029 | 9"x9" Floor Tile | Brown with Dark Brown | ND | - | No |
| 32523-800-Galt-S04b | | | | ND | - | No |
| 32523-800-Galt-S05a | 4029 | 9"x9" Floor Tile | Green with White Streak | ND | - | No |
| 32523-800-Galt-S05b | | | | ND | - | No |
| 32523-800-Galt-S06a | 4001 | 12"x12" Floor Tile | Brown Dense Fleck | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S06b | | | | ND (tile)<br>ND (mastic) | -<br>- | No |

| TABLE 3: BULK ASBESTOS SAMPLING SUMMARY | | | | | | |
|---|---|---|---|---|---|---|
| **Sample #** | **Location** | **Material Description** | **Material Description** | **Asbestos Content (%)** | **Fibre Type** | **Is Material ACM** |
| 32523-800-Galt-S06c | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| **32523-800-Galt-S07a** | **4000** | **9"x9" Floor Tile** | **Beige with Brown and White Fleck** | **2.8 (tile)<br>0.5 (mastic)** | **Chrysotile<br>Chrysotile** | **Yes** |
| **32523-800-Galt-S07b** | | | | **NA (tile)<br>Trace (mastic)** | **-<br>Chrysotile** | **Yes** |
| **32523-800-Galt-S07c** | | | | **NA (tile)<br>Trace (mastic)** | **-<br>Chrysotile** | **Yes** |
| **32523-800-Galt-S08a** | **3036** | **12"x12" Floor Tile** | **Brown with Dark Brown Fleck** | **5.0 (tile)<br>ND (mastic)<br>ND (leveling compound)** | **Chrysotile<br>-<br>-** | **Yes** |
| **32523-800-Galt-S08b** | | | | **ND (mastic)<br>ND (leveling compound)** | **-<br>-** | **No** |
| **32523-800-Galt-S08c** | | | | **ND (mastic)** | **-** | **No** |
| 32523-800-Galt-S09a | 3043 | 12"x12" Floor Tile | Crème with Long Brown Streaks | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S09b | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S09c | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| **32523-800-Galt-S10a** | **2029** | **9"x9" Floor Tile** | **Pink with White Fleck** | **1.3** | **Chrysotile** | **Yes** |
| **32523-800-Galt-S10b** | | | | **NA** | **-** | **No** |
| **32523-800-Galt-S10c** | | | | **NA** | **-** | **No** |
| **32523-800-Galt-S11a** | **2038** | **9"x9" Floor Tile** | **White with Green and Grey** | **1.3** | **Chrysotile** | **Yes** |
| **32523-800-Galt-S11b** | | | | **NA** | **-** | **No** |
| **32523-800-Galt-S11c** | | | | **ND (mastic)** | **-** | **No** |
| **32523-800-Galt-S12a** | **2042** | **9"x9" Floor Tile** | **Grey with White Streak** | **0.5 (tile)<br>ND (mastic)** | **Chrysotile<br>-** | **Yes** |
| **32523-800-Galt-S12b** | | | | **Trace** | **Chrysotile** | **Yes** |
| **32523-800-Galt-S12c** | | | | **Trace** | **Chrysotile** | **Yes** |
| 32523-800-Galt-S13a | 2051 | Vinyl Sheet Flooring | Light Yellow Cobblestone | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S13b | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S13c | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| **32523-800-Galt-S14a** | **2053** | **2'x2' Ceiling Tile** | **Long Thin Fissure** | **0.5 (tile)<br>1.2 (mastic)** | **Amosite<br>Chrysotile** | **Yes** |
| **32523-800-Galt-S14b** | | | | **NA** | **-** | **No** |
| **32523-800-Galt-S14c** | | | | **NA** | **-** | **No** |
| **32523-800-Galt-S15a** | **2138** | **9"x9" Floor Tile** | **Beige with Thick Brown Streaks** | **1.1 (tile)<br>ND (mastic)** | **Chrysotile<br>-** | **Yes** |
| **32523-800-Galt-S15b** | | | | **NA** | **-** | **No** |
| **32523-800-Galt-S15c** | | | | **ND (mastic)** | **-** | **No** |
| 32523-800-Galt-S16a | 1038 | Vinyl sheet flooring | Smokey Cloud | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S16b | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S16c | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S17a | 1067 | 2'x4' Ceiling Tile | Short Fissure Random Pinhole | ND | - | No |
| 32523-800-Galt-S17b | | | | ND | - | No |
| 32523-800-Galt-S17c | | | | ND | - | No |
| **32523-800-Galt-S18a** | **1015** | **9"x9" Floor Tile** | **Green with White Streak** | **1.3 (tile)<br>ND (mastic)<br>ND (leveling compound)** | **Chrysotile<br>-<br>-** | **Yes** |
| **32523-800-Galt-S18b** | | | | **NA** | **-** | **No** |
| **32523-800-Galt-S18c** | | | | **NA** | **-** | **No** |
| 32523-800-Galt-S19a | 1016 | 12"x12" Floor Tile | White with Brown Fleck | ND (tile)<br>ND (caulk) | -<br>- | No |
| 32523-800-Galt-S19b | | | | ND (tile)<br>ND (caulk)<br>ND (caulk) | -<br>-<br>- | No |
| 32523-800-Galt-S19c | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S20a | 1048 | Vinyl sheet flooring | Gold | ND (tile)<br>ND (mastic)<br>ND (leveling compound) | -<br>-<br>- | No |
| 32523-800-Galt-S20b | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S20c | | | | ND (tile) | - | No |
| 32523-800-Galt-S21a | 1067 | 12"x12" Floor Tile | White with Grey and Blue Fleck | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S21b | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| 32523-800-Galt-S21c | | | | ND (tile)<br>ND (mastic) | -<br>- | No |
| **32523-800-Galt-S22a** | **2037** | **9"x9" Floor Tile** | **Light Yellow** | **1.2 (tile)<br>ND (mastic)** | **Chrysotile<br>-** | **Yes** |
| **32523-800-Galt-S22b** | | | | **NA (tile)<br>ND (mastic)** | **-<br>-** | **No** |
| **32523-800-Galt-S22c** | | | | **NA (tile)<br>ND (mastic)** | **-<br>-** | **No** |
| 32523-800-Galt-S23a | 2036 | 2'x4' Ceiling Tile | Textured Pinhole | ND | - | No |
| 32523-800-Galt-S23b | | | | ND | - | No |
| 32523-800-Galt-S23c | | | | ND | - | No |
| **November 16, 2012 Additional Sampling** | | | | | | |

| TABLE 3: BULK ASBESTOS SAMPLING SUMMARY | | | | | | |
|---|---|---|---|---|---|---|
| **Sample #** | **Location** | **Material Description** | **Material Description** | **Asbestos Content (%)** | **Fibre Type** | **Is Material ACM** |
| S01A | 2082 | Plaster | Plaster | Layer 1: ND | - | No |
| | | | | Layer 2: ND | - | No |
| S01B | | | | Layer 1: ND | - | No |
| | | | | Layer 2: ND | - | No |
| S01C | | | | Layer 1: ND | - | No |
| | | | | Layer 2: ND | - | No |
| S02A | 2083 | Plaster | Plaster | ND | - | No |
| S02B | | | | ND | - | No |
| S02C | | | | ND | - | No |
| **June 14, 2013 Library Sampling** | | | | | | |
| S01A | 1104 | Flooring Mastic | Brown | ND | - | No |
| S01B | | | | ND | - | No |
| S01C | | | | ND | - | No |
| S02A | 1104 | Flooring Mastic | Black | ND | - | No |
| S02B | | | | ND | - | No |
| S02C | | | | ND | - | No |
| S02A | 2083 | Ramp Floor Tile | - | ND (Tile)<br>ND (Mastic) | - | No |
| S02B | | | | ND (Tile)<br>ND (Mastic) | - | No |
| S02C | | | | ND (Tile)<br>ND (Mastic) | - | No |
| **March 20, 2015 Asbestos Audit Update** | | | | | | |
| S01A | 3024 | Plaster | Plaster | ND (Skim Coat)<br>ND (plaster) | -<br>- | No |
| S01B | | | | ND (Skim Coat)<br>ND (plaster) | -<br>- | No |
| S01C | | | | ND (Skim Coat)<br>ND (plaster) | -<br>- | No |
| S02A | 3028 | Firespray | Firespray | ND | - | No |
| S02B | | | | ND | - | No |
| S02C | | | | ND | - | No |
| S03A | 1011 | Vinyl Sheet Flooring | Beige Pebble | ND | - | No |
| S03B | | | Beige Pebble | ND | - | No |
| S03C | | | Beige Pebble | ND | - | No |
| S04A | 1000 | Vinyl Sheet Flooring | Red | ND | - | No |
| S04B | | | Red | ND | - | No |
| S04C | | | Red | ND | - | No |
| S05A | 1011 | Vinyl Sheet Flooring | Salmon/Pink | ND | - | No |
| S05B | | | | ND | - | No |
| S05C | | | | ND | - | No |
| S06A | 1011 | Texture Coat | Texture Coat | ND | - | No |
| S06B | | | | ND | - | No |
| S06C | | | | ND | - | No |
| S06D | | | | ND | - | No |
| S06E | | | | ND | - | No |
| S07A | 1000 | Ceiling Tile | Dense Pinhole | ND | - | No |
| S07B | | | | ND | - | No |
| S07C | | | | ND | - | No |
| S08A | 1001 | 12"x12" Vinyl Floor Tile | Beige with Grey and Peach | ND (Floor Tile)<br>ND (mastic) | -<br>- | No |
| S08B | | | | ND (Floor Tile)<br>ND (mastic) | -<br>- | No |
| S08C | | | | ND (Floor Tile)<br>ND (mastic) | -<br>- | No |
| **May 6, 2015 Asbestos Audit Update** | | | | | | |
| S01A | 2067 | Hard Texture Coat | Hard Texture Coat | ND | - | No |
| S01B | 2067 | Hard Texture Coat | Hard Texture Coat | ND | - | No |
| S01C | 2067 | Hard Texture Coat | Hard Texture Coat | ND | - | No |
| **August 5, 2015 Sampling** | | | | | | |
| S01A | 2051 | Drywall Joint Compound | Drywall Joint Compound | ND | - | No |
| S01B | 2053 | | | ND | - | No |
| S01C | 2064 | | | ND | - | No |

| TABLE 3: BULK ASBESTOS SAMPLING SUMMARY | | | | | | |
|---|---|---|---|---|---|---|
| **Sample #** | **Location** | **Material Description** | **Material Description** | **Asbestos Content (%)** | **Fibre Type** | **Is Material ACM** |
| S02A | 2052 | Plaster | Plaster | ND | - | No |
| S02B | | | | ND | - | No |
| S02C | | | | ND | - | No |
| **S03A** | **2031** | **Hard Texture Coat** | **Hard Texture Coat** | **1.3** | **Chrysotile** | **Yes** |
| **S03B** | | | | **NA** | **-** | **Yes** |
| **S03C** | | | | **NA** | **-** | **Yes** |
| S04A | 2010 | Plaster | Plaster | ND | - | No |
| S04B | 2011 | | | ND | - | No |
| S04C | 2011 | | | ND | - | No |
| S05A | 1011 | Drywall Joint Compound | Drywall Joint Compound | ND | - | No |
| S05B | 1003 | | | ND | - | No |
| S05C | 1003 | | | ND | - | No |
| S06A | 1020 | Drywall Joint Compound | Drywall Joint Compound | ND | - | No |
| S06B | 1020 | | | ND | - | No |
| S06C | 1104 | | | ND | - | No |
| **September 14, 2017 Additional Sampling** | | | | | | |
| S01A | 1064 | Plaster | Skim Coat | Layer 1: ND | - | No |
| S01B | | | | Later 1: ND | - | No |
| | | | | Layer 2: ND | - | No |
| S01C | | | | Layer 1: ND | - | No |
| **S02A** | **1064** | **Plaster** | **Grey Layer on Lattice** | Layer 1: ND | - | No |
| | | | | Layer 2: ND | - | No |
| **S02B** | | | | Layer 1: ND | - | No |
| | | | | Layer 2: ND | - | No |
| **S02C** | | | | Layer 1: ND | - | No |
| | | | | **Layer 2: 1** | **Chrysotile** | **Yes** |
| **June 28, 2018 Asbestos Audit Update** | | | | | | |
| **S01A** | **-** | **Interior Window Frame - Grey Sealant (1986 Addition)** | **Interior Window Frame - Grey Sealant (1986 Addition)** | **0.5** | **Chrysotile** | **Yes** |
| **S01B** | **-** | | | **NA** | **-** | **Yes** |
| **S01C** | **-** | | | **NA** | **-** | **Yes** |
| **S02A** | **-** | **Interior Door Pane - Black Sealant (1986 Addition)** | **Interior Door Pane - Black Sealant (1986 Addition)** | **8** | **Chrysotile** | **Yes** |
| **S02B** | **-** | | | **NA** | **-** | **Yes** |
| **S02C** | **-** | | | **NA** | **-** | **Yes** |
| **S03A** | **-** | **Exterior Door Frame - Grey Sealant (1986 Addition)** | **Exterior Door Frame - Grey Sealant (1986 Addition)** | **1** | **Chrysotile** | **Yes** |
| **S03B** | **-** | | | **NA** | **-** | **Yes** |
| **S03C** | **-** | | | **NA** | **-** | **Yes** |
| **S04A** | **-** | **Interior Door Pane - Brown Sealant (1962 Addition)** | **Interior Door Pane - Brown Sealant (1962 Addition)** | **10** | **Chrysotile** | **Yes** |
| **S04B** | **-** | | | **NA** | **-** | **Yes** |
| **S04C** | **-** | | | **NA** | **-** | **Yes** |
| S05A | 1027 | Plaster (1962 Addition) | Plaster (1962 Addition) | ND | - | No |
| S05B | | | | ND | - | No |
| S05C | 1023 | | | ND | - | No |
| S05D | | | | ND | - | No |
| S06A | - | Interior Door Frame - Beige Sealant (1962 Addition) | Interior Door Frame - Beige Sealant (1962 Addition) | ND | - | No |
| S06B | - | | | ND | - | No |
| S06C | - | | | ND | - | No |
| **S07A** | **-** | **Exterior Window Frame - Grey Sealant (1962 Addition)** | **Exterior Window Frame - Grey Sealant (1962 Addition)** | **1** | **Chrysotile** | **Yes** |
| **S07B** | **-** | | | **NA** | **-** | **Yes** |
| **S07C** | **-** | | | **NA** | **-** | **Yes** |
| **S08A** | **-** | **Exterior Window Pane - Black/Grey Sealant (1962 Addition)** | **Exterior Window Pane - Black/Grey Sealant (1962 Addition)** | **10** | **Chrysotile** | **Yes** |
| **S08B** | **-** | | | **NA** | **-** | **Yes** |
| **S08C** | **-** | | | **NA** | **-** | **Yes** |
| S09A | - | Interior Door Pane - Grey Sealant (1923 Addition) | Interior Door Pane - Grey Sealant (1923 Addition) | ND | - | No |
| S09B | - | | | ND | - | No |
| S09C | - | | | ND | - | No |
| S10A | - | Interior Door Pane - Grey Sealant (1923 Addition) | Interior Door Pane - Grey Sealant (1923 Addition) | ND | - | No |
| S10B | - | | | ND | - | No |
| S10C | - | | | ND | - | No |
| S11A | - | Interior Window Frame - Grey Sealant (1923 Addition) | Interior Window Frame - Grey Sealant (1923 Addition) | ND | - | No |
| S11B | - | | | ND | - | No |
| S11C | - | | | ND | - | No |
| S12A | - | Exterior Door Frame - Beige Sealant (1923 Addition) | Exterior Door Frame - Beige Sealant (1923 Addition) | ND | - | No |
| S12B | - | | | ND | - | No |
| S12C | - | | | ND | - | No |
| **S13A** | **-** | **Exterior Door Pane - Black Sealant (1923 Addition)** | **Exterior Door Pane - Black Sealant (1923 Addition)** | **0.5** | **Chrysotile** | **Yes** |
| **S13B** | **-** | | | **NA** | **-** | **Yes** |
| **S13C** | **-** | | | **NA** | **-** | **Yes** |

**TABLE 3: BULK ASBESTOS SAMPLING SUMMARY**

| Sample # | Location | Material Description | Material Description | Asbestos Content (%) | Fibre Type | Is Material ACM |
|---|---|---|---|---|---|---|
| S14A | - | Exterior Door Pane - Black Sealant (1906 Addition) | Exterior Door Pane - Black Sealant (1906 Addition) | ND | - | No |
| S14B | - | | | ND | - | No |
| S14C | - | | | ND | - | No |
| S15A | - | Interior Door Frame - White Sealant (1906 Addition) | Interior Door Frame - White Sealant (1906 Addition) | ND | - | No |
| S15B | - | | | ND | - | No |
| S15C | - | | | ND | - | No |
| S16A | - | Interior Window Frame - Beige Sealant (1906 Addition) | Interior Window Frame - Beige Sealant (1906 Addition) | ND | - | No |
| S16B | - | | | ND | - | No |
| S16C | - | | | ND | - | No |
| S17A | 1045 | Drywall Joint Compound (1954 Addition) | Drywall Joint Compound (1954 Addition) | ND | - | No |
| S17B | | | | ND | - | No |
| S17C | | | | ND | - | No |
| S18A | 1045 | Plaster (1954 Addition) | Plaster (1954 Addition) | ND | - | No |
| S18B | | | | ND | - | No |
| S18C | | | | ND | - | No |
| **S19A** | **-** | **Interior Window Frame - Grey Sealant (1954 Addition)** | **Interior Window Frame - Grey Sealant (1954 Addition)** | **1** | **Chrysotile** | **Yes** |
| **S19B** | **-** | | | **NA** | **-** | **Yes** |
| **S19C** | **-** | | | **NA** | **-** | **Yes** |
| S20A | - | Exterior Window Pane - Black Sealant (1954 Addition) | Exterior Window Pane - Black Sealant (1954 Addition) | ND | - | No |
| S20B | - | | | ND | - | No |
| S20C | - | | | ND | - | No |
| **S21A** | **-** | **Exterior Door Frame - Grey Sealant (1954 Addition)** | **Exterior Door Frame - Grey Sealant (1954 Addition)** | **1** | **Chrysotile** | **Yes** |
| **S21B** | **-** | | | **NA** | **-** | **Yes** |
| **S21C** | **-** | | | **NA** | **-** | **Yes** |
| S22A | 1050 | Drywall Joint Compound (1956 Addition) | Drywall Joint Compound (1956 Addition) | ND | - | No |
| S22B | | | | ND | - | No |
| S22C | | | | ND | - | No |
| **S23A** | **-** | **Interior Window Pane - Black Sealant (1853 Original Building)** | **Interior Window Pane - Black Sealant (1853 Original Building)** | **5** | **Chrysotile** | **Yes** |
| **S23B** | **-** | | | **NA** | **-** | **Yes** |
| **S23C** | **-** | | | **NA** | **-** | **Yes** |
| S24A | 2072 | Vinyl Floor Tile Mastic (1876 Addition) | Vinyl Floor Tile Mastic (1876 Addition) | ND | - | No |
| S24B | | | | ND | - | No |
| S24C | | | | ND | - | No |
| S25A | 1054 | Drywall Joint Compound (1976 Addition) | Drywall Joint Compound (1976 Addition) | ND | - | No |
| S25B | | | | ND | - | No |
| S25C | | | | ND | - | No |
| **S26A** | **-** | **Interior Window Pane - Black Sealant (1929 Addition)** | **Interior Window Pane - Black Sealant (1929 Addition)** | **8** | **Chrysotile** | **Yes** |
| **S26B** | **-** | | | **NA** | **-** | **Yes** |
| **S26C** | **-** | | | **NA** | **-** | **Yes** |
| S27A | - | Interior Window Pane - Black Sealant (1929 Addition) | Interior Window Pane - Black Sealant (1929 Addition) | ND | - | No |
| S27B | - | | | ND | - | No |
| S27C | - | | | ND | - | No |
| S28A | 3051 | Vinyl Floor Tile Mastic (1929 Addition) | Vinyl Floor Tile Mastic (1929 Addition) | ND | - | No |
| S28B | | | | ND | - | No |
| S28C | | | | ND | - | No |
| S29A | 3054 | Drywall Joint Compound (1929 Addition) | Drywall Joint Compound (1929 Addition) | ND | - | No |
| S29B | | | | ND | - | No |
| S29C | | | | ND | - | No |
| **November 14, 2018 Additional Sampling** | | | | | | |
| S01A | 212C | 1x1 Ceiling Tile | Random Pinhole | ND | - | No |
| | | Mastic on 1x1 Ceiling Tile | Mastic | ND | - | No |
| S01B | | 1x1 Ceiling Tile | Random Pinhole | ND | - | No |
| | | Mastic on 1x1 Ceiling Tile | Mastic | ND | - | No |
| S01C | | 1x1 Ceiling Tile | Random Pinhole | ND | - | No |
| | | Mastic on 1x1 Ceiling Tile | Mastic | ND | - | No |
| S02A | 101 | Mastic on 1x1 Ceiling Tile Medium Fissure and Small Pinhole | Mastic | ND | - | No |
| S02B | | | | ND | - | No |
| S02C | | | | ND | - | No |
| S03A | 306C | Hard Texture Coat | Walls | ND | - | No |
| S03B | | | | ND | - | No |
| S03C | | | | ND | - | No |

**NA**: Not Analyzed due to stop positive method **ND**: No asbestos fibres detected above the laboratory minimum detection limit

A bulk material sample containing 0.5% or more asbestos therefore establishes that material as asbestos-containing. In accordance with Table 1 of O. Reg. 278/05, a minimum number of samples for the material to be classified as non asbestos. A homogeneous material is defined by O. Reg. 278/05 “as material that is uniform in colour and texture”. Homogeneous samples are identified by an alphabetical suffix to sample names to represent multiple samples of a homogeneous material. When a homogeneous material is analysed it is determined to be asbestos-containing upon the first positive detection of asbestos equal to or greater than 0.5%. Subsequent samples of the same material are therefore not analysed. Some bulk samples are comprised of multiple layers and as such will require multiple analysis. In such cases each layer is isolated at the laboratory and analysed individually to determine asbestos content. As a result the laboratory may report additional samples beyond the submitted number of samples or include multiple analyses as subsets within a sample.

## Appendix 01 35 43B– Lead Report

Waterloo Region
District School Board

51 Ardelt Avenue, Kitchener, ON N2C 2R5
Tel: 519-570-0003, Fax: 519 576-0478
**FACILITY SERVICES**

**November 25, 2024**

**RE: Paint and Coatings bulk Sampling – Letter of Findings**
**Galt Collegiate Institute, 200 Water Street North, Cambridge, Ontario**
**Project-Specific Work Areas – Corridor/Fixed Reference No. 8214**

## 1. INTRODUCTION

Paint and coatings samples were collected for lead content analysis within Galt Collegiate Institute, specifically, Corridor/Fixed Reference No. 8214. The samples were collected from surfaces within the project-specific location and submitted to ALS Environmental for the determination of lead content.

The extent of our paint sample collection and assessment area is outlined on the floor plan attached in Appendix A.

## 2. METHODOLOGY

An assessment for lead in paint was conducted by retrieving paint chip samples from representative surfaces within the area assessed that were deemed to have a potential to be disturbed as part of the planned renovation activities. The condition of painted surfaces from which samples were taken were also visually assessed for signs of deterioration such as cracking, chipping, flaking, bubbling and deterioration due to friction. Based on the degree and extent of deterioration, the conditions of these surfaces were assessed as good, fair, or poor.

The number of paint chip samples retrieved for analysis was based on surface colours observed. Samples were not retrieved from paint finishes with limited application. All paint chip samples were retrieved by scraping the paint down to the base material substrate to ensure collection of all layers of paint. Additional care was taken to avoid collection of the underlying substrate to reduce analytical substrate matrix interference.

Upon completion of our assessment, a paint chip sample was submitted to ALS Environmental for the determination of lead content. Analysis was conducted by the laboratory following the EPA Method 6010. Result of analysis was reported by the laboratory in micrograms per gram (µg/g).

## 3. RESULTS

Results of analysis for the determination of lead content are summarized in Table 1, below. The Laboratory Certificate of Analysis is included as Appendix B.

**TABLE 1: Summary of Lead-in-Paint Analytical Results**

| Sample No. | Location | Surface | Paint Colour | Condition | Lead Conc. (µg/g) | EACC Classification |
|---|---|---|---|---|---|---|
| Sa1 | Corridor/FR#8214 | Throughout | White | Good | 13.6 | '*De Minimis*' Level of Lead |

Note: 1 mg/kg = 1 µg/g

## 4. CONCLUSIONS


'*De* Minimis' Level of Lead in Paint

The paint sample, Sa1, collected from the painted white surfaces observed throughout Corridor/Fixed Reference No. 8214, which was representative of the work area, in entirety, was determined to have a lead content below 1,000 µg/g Lead by Weight, which is considered a "*de minimis*" level of lead in paint as per the October 2014 Environmental Abatement Council of Canada (EACC) publication, "Lead Guideline for Construction, Renovation, Maintenance or Repair" (herein after referred to as the "EACC Lead Guideline").

Prepared by:

Jeff Cull
Environmental Officer
jeff_cull@wrdsb.ca


**Appendix A**
**Extent of Assessment Area & Paint Sample Locations**




FIXED REFERENCE ROOM NUMBERS

0 5 10 20 30 50 70 FT

| | | | |
|---|---|---|---|
| WATERLOO REGION DISTRICT SCHOOL BOARD | | | |
| PROJECT: | GALT COLLEGIATE INSTITUTE - CAMBRIDGE | | |
| TITLE: | SECOND LEVEL FLOOR PLAN - FIXED REFERENCE ROOM NUMBERS | | |
| Date: FEB 2024 | Drawn by: ADO | Appr.: | |
| Prev. Rev: APR 2023 ADO | Scale: 1" = 60'-0" | Dwg.No: 4 OF 6 | |




FIXED REFERENCE ROOM NUMBERS

| | | | |
|---|---|---|---|
| WATERLOO REGION DISTRICT SCHOOL BOARD | | | |
| PROJECT: GALT COLLEGIATE INSTITUTE - CAMBRIDGE | | | |
| TITLE: THIRD LEVEL FLOOR PLAN - FIXED REFERENCE ROOM NUMBERS | | | |
| Date: APR 2023 | Drawn by: ADO | Appr.: | |
| Prev. Rev: OCT 2022 ADO | Scale: 1" = 60'-0" | Dwg.No: 5 OF 6 | |

**Appendix B**
**Laboratory Certificate of Analysis**

# ALS Canada Ltd.

right solutions.
right partner.

## CERTIFICATE OF ANALYSIS

| | | | |
|---|---|---|---|
| **Work Order** | : **WT2434586** | Page | : 1 of 2 |
| Client | : **Waterloo Region District School Board** | Laboratory | : ALS Environmental - Waterloo |
| Contact | : Jeff Cull | Account Manager | : Candice Hunter |
| Address | : 51 Ardelt Avenue<br>Kitchener ON Canada N2C 2E1 | Address | : 60 Northland Road, Unit 1<br>Waterloo ON Canada N2V 2B8 |
| Telephone | : 519 502 8343 | Telephone | : +1 519 886 6910 |
| Project | : GCI SUMMER RENO 2025 | Date Samples Received | : 20-Nov-2024 14:50 |
| PO | : ---- | Date Analysis Commenced | : 21-Nov-2024 |
| C-O-C number | : ---- | Issue Date | : 21-Nov-2024 13:45 |
| Sampler | : JC | | |
| Site | : ---- | | |
| Quote number | : Non - Regulated Standing SOA | | |
| No. of samples received | : 1 | | |
| No. of samples analysed | : 1 | | |

This report supersedes any previous report(s) with this reference. Results apply to the sample(s) as submitted. This document shall not be reproduced, except in full.

This Certificate of Analysis contains the following information:

- General Comments
- Analytical Results

Additional information pertinent to this report will be found in the following separate attachments: Quality Control Report, QC Interpretive report to assist with Quality Review and Sample Receipt Notification (SRN).

### *Signatories*

This document has been electronically signed by the authorized signatories below. Electronic signing is conducted in accordance with US FDA 21 CFR Part 11.

| *Signatories* | *Position* | *Laboratory Department* |
|---|---|---|
| Greg Pokocky | Manager - Inorganics | Metals, Waterloo, Ontario |

## General Comments

The analytical methods used by ALS are developed using internationally recognized reference methods (where available), such as those published by US EPA, APHA Standard Methods, ASTM, ISO, Environment Canada, BC MOE, and Ontario MOE. Refer to the ALS Quality Control Interpretive report (QCI) for applicable references and methodology summaries. Reference methods may incorporate modifications to improve performance.
Where a reported less than (<) result is higher than the LOR, this may be due to primary sample extract/digestate dilution and/or insufficient sample for analysis.

Where the LOR of a reported result differs from standard LOR, this may be due to high moisture content, insufficient sample (reduced weight employed) or matrix interference.

Please refer to Quality Control Interpretive report (QCI) for information regarding Holding Time compliance.

Key : CAS Number: Chemical Abstracts Services number is a unique identifier assigned to discrete substances
LOR: Limit of Reporting (detection limit).
Measurement Uncertainty: The reported uncertainties in this report are expanded uncertainties calculated using a coverage factor of 2, which gives a level of confidence of approximately 95%.
Surrogate: An analyte that is similar in behavior to target analyte(s), but that does not occur naturally in environmental samples. For applicable tests, surrogates are added to samples prior to analysis as a check on recovery.

| *Unit* | *Description* |
|---|---|
| mg/kg | milligrams per kilogram |

>: greater than.
<: less than.

Test results reported relate only to the samples as received by the laboratory.

UNLESS OTHERWISE STATED on SRN or QCI Report, ALL SAMPLES WERE RECEIVED IN ACCEPTABLE CONDITION.

## Workorder Comments

<1 or Not Detected with LOR of 1 equals Zero (0).

## Analytical Results

WT2434586-001

Sub-Matrix:**Paint Chips**
(Matrix: **Soil/Solid**)

*Client sample ID:* Sa1
*Client sampling date / time:* 18-Nov-2024

| *Analyte* | *CAS Number* | *Result* | *LOR* | *Unit* | *Method/Lab* | *Prep Date* | *Analysis Date* | *QCLot* |
|---|---|---|---|---|---|---|---|---|
| Metals | | | | | | | | |
| **Lead** | 7439-92-1 | 13.6 | 5.0 | mg/kg | E494.Pb/WT | 21-Nov-2024 | 21-Nov-2024 | 1776687 |

Please refer to the General Comments section for an explanation of any result qualifiers detected.

SOL-321

# Chain of Custody (COC) / Analytical Request Form

www.alsglobal.com

Canada Toll Free: 1 800 668 9878

Affix ALS barcode label here (lab use only)

COC Number: 14 - VM

Page 1 of 1

| Report To | | Report Format / Distribution | Select Service Level Below (Rush Turnaround Time (TAT) is not available for all tests) |
|---|---|---|---|
| Company: | Waterloo Region District School Board | Select Report Format: ☑ PDF ☐ EXCEL ☐ EDD (DIGITAL) | R ☐ Regular (Standard TAT if re |
| Contact: | Jeff Cull | Quality Control (QC) Report with Report ☑ Yes ☐ No | P ☐ Priority (2-4 bus. days if re |
| Address: | 51 Ardelt Ave, Kitchener ON, N2C 3R5 | ☐ Criteria on Report - provide details below if box checked | E ☑ Emergency (1-2 bus. days |
| | | Select Distribution: ☑ EMAIL ☐ MAIL ☐ FAX | E2 ☐ Same day or weekend eme |
| Phone: | 519-502-8343 | Email 1 or Fax JEFF_CULL@WRDSB.CA | Specify Date Required for E2,E |
| | | Email 2 | |
| **Invoice To** | Same as Report To ☑ Yes ☐ No | **Invoice Distribution** | Indicate Filtered (F), Preser |
| | Copy of Invoice with Report ☐ Yes ☑ No | Select Invoice Distribution: ☑ EMAIL ☐ MAIL ☐ FAX | |
| Company: | | Email 1 or Fax FINANCE-AP@WRDSB.CA | |
| Contact: | | Email 2 | |

Environmental Division
Waterloo
Work Order Reference
WT2434586

Telephone : +1 519 886 6910

| Project Information | | Oil and Gas Required Fields (client use) | |
|---|---|---|---|
| ALS Quote #: | | Approver ID: | Cost Center: |
| Job #: | GCI Summer Reno 2025 | GL Account: | Routing Code: |
| PO / AFE: | | Activity Code: | |
| LSD: | | Location: | |

**ALS Lab Work Order # (lab use only)** WT2434586 | **ALS Contact:** CH | **Sampler:** JC

| ALS Sample # (lab use only) | Sample Identification and/or Coordinates (This description will appear on the report) | Date (dd-mmm-yy) | Time (hh:mm) | Sample Type | Lead Content (Lab) | Paint Sample | Number of Containers |
|---|---|---|---|---|---|---|---|
| | Sa1 | 18-Nov-24 | PM | Solid | X | | 1 |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

**Drinking Water (DW) Samples[1] (client use)**

Are samples taken from a Regulated DW System? ☐ Yes ☐ No

Are samples for human drinking water use? ☐ Yes ☐ No

**Special Instructions / Specify Criteria to add on report (client Use)**

**SAMPLE CONDITION AS RECEIVED (lab use only)**

Frozen ☐ | SIF Observations Yes ☐ No ☐

Ice packs Yes ☐ No ☐ | Custody seal intact Yes ☐ No ☐

Cooling Initiated ☐

| INITIAL COOLER TEMPERATURES °C | | | FINAL COOLER TEMPERATURES °C | | |
|---|---|---|---|---|---|
| | | | | 20.1 | |

| SHIPMENT RELEASE (client use) | | | INITIAL SHIPMENT RECEPTION (lab use only) | | | FINAL SHIPMENT RECEPTION (lab use only) | | |
|---|---|---|---|---|---|---|---|---|
| Released by: | Date: | Time: | Received by: | Date: | Time: | Received by: | Date: | Time: |
| JEFF CULL | NOV 20 2024 | 1:06 PM | | | | | NOV 20 2024 | 1450 |

REFER TO BACK PAGE FOR ALS LOCATIONS AND SAMPLING INFORMATION

WHITE - LABORATORY COPY YELLOW - CLIENT COPY

NA-FM-0326e v09 Front/04 January 2014

Failure to complete all portions of this form may delay analysis. Please fill in this form LEGIBLY. By the use of this form the user acknowledges and agrees with the Terms and Conditions as specified on the back page of the white - report copy.

1. If any water samples are taken from a **Regulated Drinking Water (DW) System**, please submit using an **Authorized DW COC form**.

**Appendix C**
**Site Photographs**





Photo 1: Corridor/Fixed Reference No. 8214

**01 42 00 – References**

## 1.0 GENERAL

### 1.1. SECTION INCLUDES

.1 References and standards.

.2 Standards producing industry organizations and their addresses.

### 1.2. RELATED SECTIONS

.1 Section 01 61 00 – Product Requirements.

.2 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.3. REFERENCES

.1 For Products or quality specified by association, trade, or other references or consensus standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.

.2 Conform to reference standard by Ontario Building Code except where a specific date is established or required by code.

.3 Obtain copies of standards where required by product specification sections.

.4 Neither the contractual relationships, duties, or responsibilities of the parties in Contract nor those of the Consultant shall be altered from the Contract Documents by mention or inference otherwise, in any reference document.

### 1.4. STANDARDS

.1 The following associations and organizations are cited in Specification Sections. Acronym, name, address, and Internet URL addresses are as follows:

.2 Canadian Organizations:

.1 **ACEC** – Association of Consulting Engineering Companies – Canada, 130 Albert Street, Suite 420, Ottawa, ON K1P 5G4; URL: http://www.acec.ca.

.2 **AWMAC** - Architectural Woodwork Manufacturers Association of Canada, 516-4 Street West, High River, AB T1V 1B6; URL: http://www.awmac.com.

.3 **Canada Green Building Council**, 330 - 55 rue Murray Street, Ottawa, ON. K1N5M3; Tel: 613-241-1184, Fax: 613-241-5750; URL: http://www.cagbc.org.

.4 **CCA** - Canadian Construction Association, 75 Albert St., Suite 400, Ottawa, ON K1P 5E7; URL: http://www.cca-acc.com.

.5 **CCDC** – Canadian Construction Documents Committee, Refer to ACEC, CCA, CSC or RAIC; URL: http://www.CCDC.org.

.6 **CGA** - Canadian Gas Association, 20 Eglinton Avenue West, Suite 1305, Toronto, ON M4R 1K8; URL: http://www.cga.ca.

.7 **CGSB** - Canadian General Standards Board, Place du Portage, Phase III, 6B1, 11 Laurier Street, Hull, QC K1A 0S5; URL: http://w3.pwgsc.gc.ca/cgsb.

.8 **CISC** - Canadian Institute of Steel Construction, 201 Consumers Road, Suite 300, Willowdale, ON M2J 4G8; URL: http://www.cisc-icca.ca.

.9 **CLA** - Canadian Lumbermen's Association, 27 Goulburn Avenue, Ottawa, ON K1N 8C7; URL: http://www.cla-ca.ca.

.10 **CNLA** - Canadian Nursery Landscape Association, RR #4, Stn. Main,7856 Fifth Street, Milton, ON L9T 2X8; URL: http://www.canadanursery.com.

.11 **CRCA** - Canadian Roofing Contractors Association, 155 Queen Street,Suite 1300, Ottawa, ON K1P 6L1; URL: http://www.roofingcanada.com.

.12 **CSA** - Canadian Standards Association International, 178 Rexdale Blvd., Toronto, ON M9W 1R3; URL: http://www.csa-international.org.

.13 **CSC** - Construction Specifications Canada, 120 Carlton Street, Suite 312, Toronto, ON M5A 4K2; URL: http://www.csc-dcc.ca.

.14 **CSDMA** - Canadian Steel Door Manufacturers Association, One Yonge Street, Suite 1801, Toronto, ON M5E 1W7; URL: http://www.csdma.org.

.15 **CSPI** - Corrugated Steel Pipe Institute, 652 Bishop Street N, Unit 2A, Cambridge, ON N3H 4V6; URL: http://www.cspi.ca.

.16 **CSSBI** - Canadian Sheet Steel Building Institute, 652 Bishop St. N., Unit 2A, Cambridge, ON N3H 4V6; URL: http://www.cssbi.ca.

.17 **CUFCA** - Canadian Urethane Foam Contractor's Association, Box 3214, Winnipeg, MB R3C 4E7; URL: http://www.cufca.ca.

.18 **CWC** - Canadian Wood Council, 1400 Blair Place, Suite 210, Ottawa, ON. K1J 9B8; URL: http://www.cwc.ca.

.19 **EC** - Environment Canada, Conservation and Protection, Inquiry Centre, 351 St. Joseph Blvd, Hull, QC KIA 0H3; URL: http://www.ec.gc.ca.

.20 **EFC** - Electro Federation of Canada, 5800 Explorer Drive, Suite 200, Mississauga, ON L4W 5K9; URL: http://www.electrofed.com.

.21 **MPI** - The Master Painters Institute, 4090 Graveley Street, Burnaby, BC V5C 3T6; URL: http://www.paintinfo.com.

.22 **NABA** - National Air Barrier Association, PO Box 2747, Winnipeg, MB R3C 4E7; URL: http://www.naba.ca.

.23 **NLGA** - National Lumber Grades Authority, 406-First Capital Place, 960 Quayside Drive, New Westminster, BC V3M 6G2; URL: http://www.nlga.org.

.24 **NRC** - National Research Council, Building M-58, 1200 Montreal Road, Ottawa, ON K1A 0R6; URL: http://www.nrc.gc.ca.

.25 **QPL** - Qualification Program List, c/o Canadian General Standards Board, Place du Portage, Phase III, 6B1, 11 Laurier Street, Hull, QC K1A 1G6; URL: http://www.pwgsc.gc.ca/cgsb.

.26 **RAIC** - Royal Architectural Institute of Canada, 55 Murray Street, Suite 330, Ottawa, ON K1N 5M3; URL: http://www.raic.org.

.27 **SCC** - Standards Council of Canada, 270 Albert Street, Suite 2000, Ottawa, ON K1P 6N7; URL: http://www.scc.ca.

.28 **TTMAC** - Terrazzo, Tile and Marble Association of Canada, 30 Capston Gate, Unit 5 Concord, ON L4K 3E8; URL: http://www.ttmac.com.

.29 **ULC** - Underwriters' Laboratories of Canada, 7 Crouse Road, Toronto, ON M1R 3A9; URL: http://www.ulc.ca.

.3 USA Organizations:

.1 **AA** - Aluminum Association, 900 19th Street N.W., Washington, DC 20006; URL: http://www.aluminum.org.

.2 **AASHTO** - American Association of State Highway and Transportation Officials, 444 N Capitol Street N.W., Suite 249, Washington, DC 20001; URL: http://www.aashto.org.

.3 **AHA** - American Hardboard Association, 1210W Northwest Hwy, Palatine, IL 60067; URL: http://www.hardboard.org.

.4 **AITC** - American Institute of Timber Construction, 7012 S. Revere Parkway, Suite 140, Englewood, CO 80112; URL: http://www.aitc-glulam.org.

.5 **AMCA** - Air Movement and Control Association Inc., 30 West University Drive, Arlington Heights, IL 60004-1893; URL: http://www.amca.org.

.6 **ANSI** - American National Standards Institute, 25 West 43rd Street, 4th Floor, New York, NY 10036; URL: http://www.ansi.org.

.7 **APA** - The Engineered Wood Association, P.O. Box 11700, Tacoma, WA 98411-0700; URL: http://www.apawood.org.

.8 **API** - American Petroleum Institute, 1220 L St. Northwest, Washington, DC 20005-4070; URL: http://www.api.org.

.9 **ARI** - Air Conditioning and Refrigeration Institute, 4100 N Fairfax Drive, Suite 200, Arlington, VA 22203; URL: http://www.ari.org.

.10 **ASHRAE** - American Society of Heating, Refrigeration and Air-Conditioning Engineers, 1791 Tullie Circle NE, Atlanta, GA 30329; URL: http://www.ashrae.org.

.11 **ASME** - American Society of Mechanical Engineers, ASME Headquarters, 3 Park Avenue, New York, NY 10016-5990; URL: http://www.asme.org.

.12 **ASTM International**, 100 Barr Harbor Drive West, Conshohocken, PA 19428-2959; URL: http://www.astm.org.

.13 **AWCI** - Association of the Wall and Ceiling Industries International, 803 West Broad Street, Suite 600 , Falls Church, UA 22046; URL: http://www.awci.org.

.14 **AWPA** - American Wire Producer's Association, 801 N Fairfax Street, Suite 211, Alexandria, VA 22314-1757; URL: http://www.awpa.org.

.15 **AWPA** - American Wood Preservers' Association, P.O. Box 5690, Granbury TX 76049-0690; URL: http://www.awpa.com

.16 **AWS** - American Welding Society, 550 N.W. LeJeune Road, Miami, FL 33126; URL: http://www.amweld.org.

.17 **AWWA** - American Water Works Association, 6666 W. Quincy Avenue, Denver, CO 80235; URL: http://www.awwa.org.

.18 **EIMA** - EIFS Industry Manufacturer's Association, 3000 Corporate Center Drive, Suite 270, Morrow, GA 30260; URL: http://www.eima.com.

.19 **ISAP** - International Society for Asphalt Paving, 400 Selby Avenuse, Suite 1, St. Paul, MN 55102; URL: http://www.asphalt.org.

.20 **IEEE** - Institute of Electrical and Electronics Engineers, IEE Corporate Office, 3 Park Avenue, 17th Floor, New York, NY 10016-5997;URL: http://www.ieee.org

.21 **MSS** - Manufacturers Standardization Society of the Valve and Fittings Industry, 127 Park Street, N.E., Vienna, VA 22180-4602; URL: http://www.mss-hq.com.

.22 **NAAMM** - National Association of Architectural Metal Manufacturers, 8 South Michigan Avenue, Suite 1000, Chicago, IL 60603;URL: http://www.naamm.org.

.23 **NEMA** - National Electrical Manufacturers Association, 1300 N 17th Street, Suite 1847, Rosslyn, VA 22209; URL: http://www.nema.org.

.24 **NFPA** - National Fire Protection Association, 1 Batterymarch Park, P.O. Box 9101Quincy, MA 02269-9101; URL: http://www.nfpa.org.

.25 **NFSA** - National Fire Sprinkler Association, P.O. Box 1000, Patterson, NY 12563; URL: http://www.nfsa.org.

.26 **NHLA** - National Hardwood Lumber Association, 6830 Raleigh-La Grange Road, Memphis, TN 38184-0518; URL: http://www.natlhardwood.org.

.27 **NSPE** - National Society of Professional Engineers, 1420 King Street, Alexandria, VA 22314-2794; URL: http://www.nspe.org.

.28 **PCI** - Prestressed Concrete Institute, 209 W. Jackson Blvd., Suite 500, Chicago, IL 60606-6938; URL: http://www.pci.org.

.29 **PEI** - Porcelain Enamel Institute, PO Box 920220, Norcross, GA 30010; URL: http://www.porecelainenamel.com.

.30 **SSPC** - The Society for Protective Coatings, 40 24th Street, 6th Floor, Pittsburgh, PA 15222-4656;URL: http://www.sspc.org.

.31 **TPI** - Truss Plate Institute, 583 D'Onofrio Drive, Suite 200, Madison, WI 53719; URL: http://www.tpinst.org.

.32 **UL** - Underwriters' Laboratories, 333 Pfingsten Road, Northbrook, IL60062-2096; URL: http://www.ul.com.

**END OF SECTION**

**01 45 00 – Quality Control**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 21 00 - Allowances.

.2 Section 01 78 10 – Closeout Submittals and Requirements

.3 Section 01 79 00 – Demonstration and Training

.4 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. REFERENCES

.1 **ISO/IEC** 17025-2005 - General Requirements for the Competence of Testing and Calibration Laboratories.

.2 **SCC** (Standards Council of Canada).

### 1.3. INSPECTION BY AUTHORITY

.1 Allow Authorities Having Jurisdiction access to Work. If part of Work is in preparation at locations other than Place of Work, allow access to such Work whenever it is in progress.

.2 Give timely notice requesting inspection whenever portions of the Work are designated for special tests, inspections or approvals, either when described in the Contract Documents or when required by law in the Place of the Work.

.3 If Contractor covers or permits to be covered Work that has been designated for special tests, inspections or approvals before such is made, uncover such Work, have inspections or tests satisfactorily completed and make good such Work.

### 1.4. REVIEW BY CONSULTANT

.1 Consultant may order any part of the Work to be reviewed or inspected if Work is suspected to be not in accordance with Contract Documents.

.2 If, upon review such work is found not in accordance with Contract Documents, correct such Work and pay the cost of additional review and correction.

.3 If such Work is found in accordance with Contract Documents, The owner will pay the cost of review and replacement.

## 1.5. INDEPENDENT INSPECTION AGENCIES

.1 Independent Inspection and Testing Agencies will be engaged by Contractor for the purpose of inspecting and testing portions of Work.

.2 The Board may, at their discretion, request that the Consultant direct the Contractor to engage independent inspecting and or testing agencies to review or test the Work.

.3 Allocate Costs for inspections and testing to Section 01 21 00.

.4 Provide equipment required for executing inspection and testing by appointed agencies.

.5 Employment of inspection and testing agencies does not relax responsibility to perform Work in accordance with Contract Documents.

.6 If defects are revealed during inspection and/or testing, the appointed agency will request additional inspection and testing to ascertain the full degree of defect. Correct defects and irregularities as advised by the Consultant at no cost to the Owner. Contractor shall pay costs directly to the inspection agency for retesting and re-inspection.

## 1.6. ACCESS TO WORK

.1 Allow inspection and testing agencies access to Work, off site manufacturing and fabrication plants.

.2 Cooperate to provide reasonable access and facilities for such access.

## 1.7. CONTRACTOR RESPONSIBILITIES

.1 Notify appropriate agency minimum 48 hours in advance of requirement for tests, in order that attendance arrangements can be made.

.2 Submit samples and materials required for testing, as specifically requested in specifications. Submit with reasonable promptness and in an orderly sequence so as not to cause delay in Work.

.3 Provide labour and facilities to obtain and handle samples and materials on site. Provide sufficient space to store and cure test samples.

## 1.8. DUTIES & AUTHORITY OF TESTING AGENCY

.1 Testing agency is expected to do the following:

.1 Act in a professional and unprejudiced basis and carry out inspection and testing functions to establish compliance with requirements of Contract Documents.

.2 Check work as it progresses and prepare reports stating results of tests and conditions of work and state in each report whether specimens tested conform to requirements of Contract Documents, specifically noting deviations.

.3 Distribute reports as follows

.1 Consultant

.2 Owner

.3 Contractor

.2 Testing agency is not authorized to amend or release any requirements of Contract Documents, nor to approve or accept any portion of work.

## 1.9. REJECTED WORK

.1 The Contractor shall remove defective Work, whether result of poor workmanship, use of defective products or damage and whether incorporated in Work or not, which has been rejected by the Consultant as failing to conform to Contract Documents. Replace or re-execute in accordance with Contract Documents.

.2 Make good other Contractor's work damaged by such removals or replacements promptly.

.3 If, it is not expedient to correct defective Work or Work not performed in accordance with Contract Documents, the Owner may choose to accept the condition. The difference in value between Work performed and that called for by Contract Documents shall be deducted from the Contract value via Change Order. The amount of this change shall be determined by the Consultant. The Contractor shall warrant the work performed for the time period specified as if it were performed in accordance with the Contract Documents.

## 1.10. TESTING OF EXCAVATION & BACKFILL

.1 The Consultant must approve all Sample and fill tests prior to purchase.

.2 In coordination with the Consultant and Contractor, inspect and test backfill and fill to ensure the degree of compaction specified has been obtained.

.3 Inspect excavation at required levels in regard to bearing values for footings, foundations and floor slabs.

.4 Authorization and calculation of extra excavation work, if required, due to unsatisfactory bearing shall be adjusted by Unit Price.

## 1.11. CONCRETE STRENGTH TESTS

.1 Review the proposed concrete mix design and check test if considered necessary.

.2 Obtain representative samples of fresh concrete for each mix design of concrete placed in any one day as directed by the Consultant.

.3 Make standard slump tests.

.4 Mould three (3) standard 150mm diameter cylindrical test specimens from each sampling of fresh concrete. Store specimens as per best practice while they are on the site. Cure all cylinders in the laboratory under standard moisture and temperature conditions. Compression test one of the cylinders at 7 days and the remaining two at 28 days after sampling. Each concrete cylinder test report shall contain the specific location of concrete represented by sample, design strength, aggregate size, admixtures used, date, hour and temperature at time of sampling, percentage air content, unit weight and test strength of cylinder.

.5 When concrete is placed under the conditions of "Cold Weather Requirements" make one additional cylinder; store it in a heated enclosure for 24 hours and then store it on the job site in a place protected from disturbance and off the ground. Compressive test this cylinder 7 days after sampling.

.6 Determine the air content of air entrained standard weight concrete.

.7 Determine the air content and unit weight of light weight concrete by the volumetric method.

.8 Additional testing required because of changes in materials or proportions of the mix requested by the Contractor as well as any extra testing of concrete or materials occasioned by their failure to meet specification requirements or testing of the structure or performance of the structure, including load testing, shall be carried out at the Contractor's expense.

## 1.12. INSPECTION OF STRUCTURAL STEEL

.1 Ensure all steel has mill test reports that comply with the Specification prior to purchase.

.2 Inspect fabrication of steel in the plant.

.3 Inspect erection work at site including fit-up, placing, plumbing, levelling, temporary bracing, field cutting and alterations.

.4 Shop and field inspect welded and bolted connections and painting.

.5 High strength bolts - the installation and testing of bolts shall conform to the requirements of CSA S16-1969. Check one representative connection in ten by torque testing every bolt, and check each bolt in every connection with a tap of hammer for soundness. Enforce requirements of connection type.

.6 Examine visually all welded joints for inclusions, porosity, lack of fusion penetration or even contour, undercuts and cracks. Root passes shall be checked for penetration and cracks from the back of the joint. Any suspect welds shall be checked ultrasonically.

## 1.13. INSPECTION OF METAL DECK

.1 Check deck for gauge, type and protective coating thickness to ensure compliance with Specification.

.2 Inspect erection work at the site including anchorage.

## 1.14. INSPECTION AND TESTING OF PAVING

.1 Testing shall be carried out in three stages as described below by means of sufficient site visits to ensure satisfactory results but in no case less than three site visits.

.2 Test within 16 hours from time called to do so by the Contractor, since paving is a critical item at the end of the project.

.3 Stage One:

.1 Visual inspection and compaction tests of subsoil.

.4 Stage Two:

.1 Inspection of granular sub-base (after each layer is placed or after the last layer is placed and compacted).

.2 On site density tests.

.3 Verify thickness of various levels. (Minimum of 4 checks shall be done on thickness in a paved area of 250$m^2$ or less, and 1 additional check for each additional 250$m^2$ or part thereof).

.4 Laboratory tests: moisture content and grading of materials.

.5 Stage Three:

.1 Inspection of asphalt installation.

.2 Checking of thickness and density of material and checking suitability of equipment used.

.6 Standard Proctor Test shall be carried out for all projects.

.7 Further, grain size analysis and Marshall test shall be carried out if visual inspection is not satisfactory or, if there is reason to suspect materials supplied are not acceptable.

.8 All laboratory tests shall be performed according to A.S.T.M. methods, latest revisions

.9 Paving Contractor shall obtain from their supplier grading tables of materials used and submit them to the testing laboratory for approval. The paving contractor shall ensure material delivered complies with grading tables.

.10 Be responsible for all approvals given to the Paving Contractor. At completion of the paving project, inform the Consultant all tests were performed according to the Specifications and the Contractor's performance has been approved.

.11 The Consultant will not entertain any credits for work either not performed or incorrectly performed by the contractor. If thicknesses or consistencies of sub-base are not as specified, or if asphaltic material is not as specified, then the Contractor shall remove the same at their expense and provide proper specified materials.

## 1.15. BUILDING THERMOGRAPHIC SCAN

.1 Upon completion of the Work, the Consultant and/or Owner may arrange for an independent agency to carry out a thermographic scan of the building to determine acceptability of thermal performance of the building envelope.

.2 Consultant, prior to start of construction work, will designate a sample area of the building to include a portion of exterior wall and roof.

.3 Consultant will implement a special inspection program for this sample area to be carried out as construction progresses. Contractor shall not cover any completed work until notifying the Consultant and receiving acceptance of completed work. Contractor shall remove and replace any work which is installed in contravention of this requirement.

.4 Results of a thermographic scan of the entire building will be evaluated and compared to those of the sample area to determine acceptance or rejection of any part of the building envelope.

.5 Contractor shall carry out remedial work as required to bring the quality of any rejected portion of the building envelope to that of the sample area. Contractor shall pay for costs of any follow-up thermographic scans required to determine acceptability of remedial work. This procedure shall be repeated until all parts of the building envelope have been accepted.

## 1.16. TESTS AND MIX DESIGNS

.1 Furnish test results and mix designs as may be requested.

.2 The cost of tests and mix designs beyond those called for in Contract Documents or beyond those required by law of Place of Work shall be appraised by Consultant and may be authorized as recoverable.

## 1.17. MOCK-UP

.1 Prepare mock-up for Work specifically requested in specifications. Include for Work of all Sections required to provide mock-ups.

.2 Prepare mock-ups for Consultants review with reasonable promptness and in an orderly sequence, so as not to cause any delay in Work.

.3 Failure to prepare mock-ups in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.

.4 If requested, Consultant will assist in preparing a schedule fixing dates for preparation.

.5 Remove mock-up at conclusion of Work or when acceptable to the Consultant. Repair any damage and clean-up at place of mock-up.

.6 Approved mock-up may remain as part of Work.

## 1.18. EQUIPMENT AND SYSTEMS

.1 Submit adjustment and balancing reports for mechanical and electrical systems to the consultant.

.2 Refer to Sections 01 78 10 and 01 79 00 for definitive requirements.

**END OF SECTION**

**01 51 00 – Temporary Utilities**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 52 00 - Construction Facilities.

.2 Section 01 53 00 - Temporary Construction.

.3 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. INSTALLATION AND REMOVAL

.1 Provide temporary utilities controls in order to execute work expeditiously.

.2 Location of temporary facilities shall be subject to the Consultant's approval.

.3 Salvage and assist in recycling products for potential reuse wherever possible.

.4 Remove temporary facilities from the site when directed by the Consultant.

### 1.3. DEWATERING

.1 Provide temporary drainage and pumping facilities to keep excavations and the site free from standing water. Provide necessary pumps (including spare pumps) and temporary drainage for keeping the Work free of water throughout the construction period. Locate sumps away from foundation elements. Control grading around excavation to prevent surface water from draining into excavation and from damaging adjoining property.

### 1.4. WATER SUPPLY

.1 Provide continuous supply of potable water for construction use until such time as permanent municipal water supply is available.

.2 Hose extensions to be provided by subcontractors requiring them.

.3 For New Builds, arrange for connection with the appropriate utility company and pay all costs for installation, maintenance, removal, and usage costs until occupancy has been achieved.

.4 For additions and renovations the contractor can use existing Board service unless noted otherwise.

### 1.5. TEMPORARY HEATING AND VENTILATION

.1 Provide temporary heating required during construction period, including unit rental costs, maintenance.

.2 Provide temporary heating fuel, if not already available on site, until such time as a permanent natural gas line is installed, and thereafter fuel costs shall be borne by the Board. The Contractor shall provide all connections and piping between the permanent fuel source and the heating appliance(s).

.3 Provide temporary heat and ventilation in enclosed areas as required to:

.1 Facilitate progress of Work.

.2 Protect Work and products against dampness and cold.

.3 Prevent moisture condensation on surfaces.

.4 Provide ambient temperatures and humidity levels for storage, installation and curing of materials.

.5 Provide adequate ventilation to meet health regulations for a safe working environment.

.4 Maintain temperatures of minimum:

.1 10 degrees C in areas where construction is in progress, until takeover by the Board. Contractor to ensure temporary enclosures remain sealed and penetrations are repaired or closed in a timely fashion.

.2 16 degrees C in areas where finishes are in progress.

.3 16 degrees C in building once it is enclosed.

.4 Refer to other Sections for intermittent heating requirements up to 21 degrees C. Provide insulated tarp enclosures for openings as required to enclose the building after completion of main building shell components and roof.

.5 If the Contractor fails to ensure the temporary enclosures remained sealed (including temp doors when not in use) the Consultant and or the Board shall require the contractor to pay 40% of that months usage charge

.5 Use forced hot air heaters. Open-flame type heaters or salamanders are not permitted. Ventilate direct fired heating units to the outside.

.6 Uniformly distribute heat to avoid hot and cold areas and to prevent excessive drying.

.7 Early heating of the building shell will be required to expedite interior finishing to meet the project schedule.

.8 Ventilating:

.1 Prevent accumulations of dust, fumes, mists, vapours or gases in areas occupied during construction.

.2 Provide local exhaust ventilation to prevent harmful accumulation of hazardous substances into the atmosphere of occupied areas.

.3 Dispose of exhaust materials in a manner that will not result in harmful exposure to persons.

.4 Ventilate storage spaces containing hazardous or volatile materials.

.5 Ventilate temporary sanitary facilities.

.6 Continue operation of ventilation and exhaust system for time after cessation of work process to assure removal of harmful contaminants.

.7 Provide minimum 1 air change per hour for enclosed areas receiving architectural finishes.

.8 Do not allow excessive build-up of moisture inside the building.

.9 The permanent mechanical systems for the new building, when installed in safe operating conditions, may be used for temporary heating or cooling if approved in writing by the Consultant, without penalty to the warranty.

.10 Follow the requirements of "Temporary Use of New Permanent Services and Equipment" if the permanent heating system installed under the contract is intended to be used for temporary heating during the construction.

.11 Provide competent persons to operate and maintain permanent systems for the duration of temporary use period.

.12 Perform required repairs and maintenance immediately after each inspection. Pay for operating costs. Upon termination of temporary use period, services and equipment shall be inspected, tested, adjusted, fitters replaced, balanced, cleaned and lubricated.

.13 Permanent services and equipment shall be turned over to the Owner in new and perfect operating condition.

.14 Use of permanent systems and equipment as temporary facilities shall not affect the guarantee conditions and guarantee period for such systems and equipment. Make due allowance to ensure Owner will receive full benefits of the equipment manufacturer's warranty from the date of Substantial Performance.

.15 Ensure date of Substantial Performance of the Work and Warranties for heating system do not commence until entire system is in as near original condition as possible and is certified by Consultant.

.16 Maintain strict supervision of operation of temporary heating and ventilating equipment to:

.1 Conform with applicable codes and standards.

.2 Enforce safe practices.

.3 Prevent abuse of services.

.4 Prevent damage to finishes.

.5 Vent direct-fired combustion units to outside.

.17 Be responsible for damage to Work due to failure in providing adequate heat and protection during construction.

## 1.6. TEMPORARY POWER AND LIGHT

.1 Provide temporary electrical service and system including lighting and power system for use by all Sections.

.2 Contractor will provide a source for, and pay the costs of temporary power during construction for temporary lighting and operating of power tools until such time as a permanent source is available.

.3 Contractor to ensure that the use of power from a source provided by the Board shall not exceed the capacity of the current use required for the operation of any existing facility.

.4 Install and maintain temporary electrical service and systems in accordance with Construction Safety Association's "Temporary Wiring Standards on Construction Sites", the Ontario Electrical Code and other authorities having jurisdiction.

.5 Provide at least one temporary panel on each floor with service capacity suitable for construction requirements and to authorities and utilities approval.

.6 Provide temporary wiring with lighting to all areas of each floor to provide adequate lighting.

- .1 Lighting levels must be maintained at a minimum of 10 foot candles, or to suit the particular location or operation, whichever is greater.
- .2 Do not use materials of the temporary service in permanent installation.
- .3 Increase lighting levels equivalent to the final requirements when finishing operations are underway.

.7 Extension cords, lights, etc., required by various subcontractors and run from above outlet positions will be supplied and maintained by the party or parties requiring the same.

.8 Follow requirements of "Temporary Use of New Permanent Services and Equipment" if electrical power and lighting systems installed under the contract are intended to be used for temporary electricity and lighting during the construction.

.9 Electrical power and lighting systems installed under this contract can be used for construction provided damages are made good and all lamps that have been used for more than two months are replaced with new lamps.

.10 For New Builds, arrange for connection with the appropriate utility company and pay all costs for installation, maintenance, removal and usage costs until occupancy has been achieved.

.11 For Additions and renovations the contractor can use existing Board service unless noted otherwise.

.12 Provide and pay for temporary power for electric cranes and other equipment requiring temporary power in excess of above noted requirements.

## 1.7. TEMPORARY COMMUNICATION FACILITIES

.1 Contractor to provide and pay for temporary Phone, e-mail and printer hook up, for the duration of contract until completion for use by the contractor.

.2 The site superintendent is to have email access and a printer on site.

**END OF SECTION**

**01 53 00 – Temporary Construction Facilities**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 51 00 - Temporary Utilities.

.2 Section 01 35 23 – Health and Safety

.3 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. INSTALLATION AND REMOVAL

.1 Provide temporary construction facilities in order to execute work expeditiously.

.2 Remove temporary facilities from the site when directed by the Consultant.

### 1.3. PROTECTION FOR OFF-SITE AND PUBLIC PROPERTY

.1 Protect surrounding private and public property from damage during performance of Work.

.2 Be responsible for damage incurred.

### 1.4. PROTECTION OF SURROUNDING WORK

.1 Provide protection for finished and partially finished Work from damage.

.2 Provide necessary cover and protection.

.3 Be responsible for damage incurred due to lack of or improper or inappropriate protection.

### 1.5. ROOF AND STRUCTURE PROTECTION

.1 Ensure no part of Work or existing structures are subjected to a load, which will endanger its safety or will cause permanent deformation.

.2 The Contractor when indicated by the Board Contact or Consultant shall provide roof protection. Ensure all precautions are taken to avoid liability for roof damage.

.3 Typical roof protection shall consist of a layer of 1 inch rigid foam insulation set directly on the roof surface and a layer of 19 mm (3/4 inch) plywood in all places under scaffold legs, ladder legs and in areas of foot traffic or falling debris.

### 1.6. WORK SITE ENCLOSURE & SAFETY BARRIERS

.1 Erect and maintain for the duration of the work:

.1 a minimum 1800mm high chain link fence or self-supporting, heavy duty, interconnected fence panels (commonly referred to as Insta-fence) for a temporary site enclosure (hoarding) completely around perimeter of work site,
.2 any temporary posts shall be completely removed by the contractor prior to occupancy,
.3 under no circumstance shall t-bar posts be used on Board property,
.4 any additional safety devices including full hoarding as required and noted on the drawings, to protect the students, staff, public and private property from injury and damage,
.5 any additional requirements as regulated by authorities having jurisdiction, local by-laws and zoning.

.2 The Contractor is to assume full responsibility for any injury or damage caused due to failure to comply with Paragraph 1 above.
.3 Any hazardous conditions identified outside of the main fenced area will be barricaded with a fence complying to the above.
.4 Provide lockable truck entrance gate/gates and at least one (1) pedestrian door as directed and conforming to applicable traffic restrictions on adjacent streets. Equip gates with locks and keys with restricted availability, in the project office.
.5 Erect and maintain pedestrian walkways including roof and side covers, complete with signs and electrical lighting as required by law.
.6 Provide barriers around trees and plants designated to remain.
.7 Protect from damage by equipment and construction procedures.

## 1.7. TREE PROTECTION

.1 Protect all existing trees to remain from damage during construction period. Make good, at Contractor's expense, trees damaged during construction.
.2 Confine movement of heavy equipment, storage of same, and storage of materials to a predetermined area. Do not store materials or place equipment over root systems of any existing trees to remain.
.3 Install fencing or approved equal at limits of drip line of existing trees to remain unless directed otherwise. Where this case is not practical, and only if approved by the Consultant, the trunks shall be protected with an approved tree guard.
.4 No rigging cables shall be wrapped around or installed in trees. Do not flush concrete trucks or cement mixing machines over root systems or near trees. Flush concrete trucks or cement mixing machines in areas approved by the Consultant.
.5 Areas where root systems of trees are exposed directly adjacent to a structure will be backfilled with good loam only.

.6 Whenever excavating is required within branch spread of trees that are to remain, the contractor shall contact the consultant for direction prior to the start of work.

.7 If any existing tree to remain is injured and does not survive the following year, it will, as determined by the Board, be removed in its entirety and be replaced with a tree of similar size and value, as directed by the Consultant.

.8 Should the destroyed tree be of such a size or shape that it cannot be feasibly replaced, the Contractor shall compensate the Owner for the minimum sum of five thousand dollars ($5,000.00) per destroyed tree.

## 1.8. GUARD RAILS AND BARRIERS

.1 Provide secure, rigid guard rails and barricades around deep excavations, open shafts, open stairwells, open edges of floors and roofs.

.2 Erect and maintain for the duration of the Work, safety devices and barricades including hoarding, as required, to protect the staff, students, public and private property, from injury and damage.

.3 The Contractor is to ensure that all requirements from authorities having jurisdiction and all requirements from the Owner are met.

.4 The Contractor is to assume full responsibility for any damage caused due to his failure to comply with paragraph 2 above.

.5 Hazardous conditions on the exterior shall be fenced.

## 1.9. WEATHER ENCLOSURES

.1 Provide weather-tight closures to unfinished door and window openings, tops of shafts and other openings in floors and roofs.

.2 Close off floor areas where walls are not finished; seal off other openings; enclose building interior work for temporary heat.

.3 Design enclosures to withstand wind pressure.

## 1.10. DUST TIGHT BARRIERS

.1 Provide dust tight barriers and screens or partitions to localize dust generating activities, and for protection of workers, finished areas of Work and public.

.2 Maintain and relocate protection until such work is complete.

.3 Where required, adjust air handling units to eliminate migration of dust.

## 1.11. SCAFFOLDING

.1 Erect scaffolding independent of walls and use in such a manner limiting interference with other work. When not in use, move scaffolding as necessary to permit installation of other work. Construct and maintain scaffolding in a rigid, secure and safe manner. Remove it promptly when no longer required. Protect the surface on which scaffolding is bearing.

## 1.12. SHORING, BRACING, PILING

.1 Provide shoring, bracing, piling, sheeting and sheet piling and underpinning required to support soil banks, existing work and property in accordance with Construction Safety Act and other applicable regulations. Maintain shoring until the building is strong enough and sufficiently braced to withstand pressure of backfilling. Make construction aids free of permanent work so they may be removed entirely when no longer required, without damaging the Work. Locate construction aids so adequate room is left for damp-proofing foundation walls, laying substructure drainage and other work.

.2 Shoring and false work over one tier in height shall be designed and shall bear the stamp of a registered professional engineer, having experience in this field.

## 1.13. HOISTING

.1 Provide, operate and maintain services required for moving of workers, materials and equipment. Make financial arrangements with Subcontractors for use thereof.

.2 Machinery shall be operated by qualified operator.

## 1.14. OVERHEAD LIFTING

.1 Any condition requiring the use of a crane or lifting device over a Board structure must follow the requirements of Health and Safety Section 01 35 23, Paragraph 1.15 Overhead Lifting.

## 1.15. ELEVATORS/LIFTS

.1 When elevators/lifts are to be used by construction personnel, provide protective coverings for finish surfaces of elevator cabs and entrances.

.2 Coordinate use of elevator cabs with Consultant and the Board.

## 1.16. USE OF THE WORK

.1 Confine work and operations of employees by Contract Documents. Do not unreasonably encumber premises with Products.

.2 Do not load or permit to load any part of Work with a weight or force that will endanger the Work.

## 1.17. CONSTRUCTION PARKING

.1 Construction personnel vehicle parking, to be confined to the work site enclosure, or.

.2 Parking will be permitted on site only where and if it does not disrupt the employees of the place of work as directed by the Board

.3 Permission to park vehicles on site does not imply any liability or responsibility for safe keeping of vehicles and contents thereof by the School Board.

## 1.18. ACCESS TO SITE

.1 Provide and maintain adequate access to the project site.

.2 Build and maintain temporary roads where necessary and provide snow removal within the area of work, and access to the work, during the period of Work. The area shall be restored to the satisfaction of the Board at the completion of the project.

.3 If authorized to use existing roads for access to project site, maintain such roads for duration of Contract and make good damage resulting from Contractors' use of roads.

.4 Clean roadways and taxi areas where used by Contractor's equipment.

## 1.19. SECURITY

.1 The Contractor shall ensure the security of the work site, contents, and built structures for the duration of the project.

.2 The Contractor shall be responsible to provide and pay for security personnel to guard the site and contents of the site after working hours and during holidays as required.

.3 Notify the Board of the use of security guards or systems.

.4 The Board shall not be responsible for the loss, theft, or vandalism.

## 1.20. OFFICES

.1 Provide and maintain, until completion of Contract, for Contractor's use, a temporary office, large enough to accommodate site administrative activities and site meetings, complete with light, heat, air conditioning, ventilation, table and chairs. Do not store materials in the office area; keep clean and tidy.

.2 Provide a clearly marked and fully stocked first-aid case in a readily available location.

.3 Subcontractors may provide their own offices as necessary. Direct location of these offices.

## 1.21. EQUIPMENT, TOOL AND MATERIALS STORAGE

.1 Provide and maintain, in a clean and orderly condition, lockable weatherproof sheds and platforms for storage of tools, equipment and materials.

.2 Review storage areas on site with the Consultant. Store materials and equipment to ensure preservation of quality of product and fitness for the Work. Store materials and equipment on wooden platforms or other hard, clean surfaces, raised above the ground or in water tight storage sheds of sufficient size for storage of materials and equipment which might be damaged by storage in the open. Locate stored materials and equipment to facilitate prompt inspection.

.3 Store packaged materials and equipment undamaged, in their original wrappings or containers, with manufacturer's labels and seals intact.

.4 Locate materials not required to be stored in weatherproof sheds on site in a manner to cause least interference with work activities.

.5 Storage sheds required by subcontractors shall be provided by them.

## 1.22. SANITARY FACILITIES

.1 Provide weatherproof temporary toilet/sanitary facilities for the work force in accordance with governing regulations and ordinances.

.2 Service temporary toilet/sanitary facilities as required by authorities but not less than weekly.

.3 Post notices and take such precautions as required by local health authorities.

.4 The use of existing washroom facilities is not allowed unless specifically approved by the Board. The Contractor will be required to clean and maintain the existing washrooms to Board standards.

.5 Except where connected to the municipal sewer system, periodically remove wastes from Site.

.6 Keep toilet/sanitary facilities clean and sanitary and protect from freezing.

.7 Keep sanitary facilities clean and fully stocked with the necessary supplies at all times.

**END OF SECTION**

## 01 54 00 – Materials and Equipment

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 This Section describes requirements applicable to all Sections within Divisions 02 to 49

### 1.2. PRODUCT AND MATERIAL QUALITY

.1 Products, materials, equipment and articles referred to as “Products”; throughout the specifications incorporated in the Work, shall be new, not damaged or defective, and of the best quality, compatible with specifications for the purpose intended. If requested, furnish evidence as to type, source and quality of products provided.

.2 Defective products will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is a precaution against oversight or error. Remove and replace defective products at own expense, and be responsible for delays and expenses caused by rejections.

.3 Should any dispute arise as to the quality or fitness of products, the decision rests strictly with the Board contact, based upon requirements of the Contract Documents.

.4 Current Material Safety Data Sheets shall be on file with the successful Contractor and shall be provided to the Board contact upon request, within twenty-four (24) hours.

.5 Material safety data sheets are not required for products currently WHMIS exempt.

### 1.3. EQUIPMENT/TOOL MATERIALS STORAGE, HANDLING, AND PROTECTION

.1 Handle and store products in a manner to prevent damage, adulterations, deterioration, and soiling, and in accordance with manufacturer’s instructions.

.2 Store packaged or bundled products in original and undamaged condition, with manufacturer’s seals and labels intact.

.3 Store products subject to damage from weather in weatherproof enclosures.

.4 Provide and maintain tools, equipment and materials in a clean and orderly condition. Board tools, ladders, lifts, power cords, flashlights etc. are not to be used.

.5 Materials are to be stored in a manner to cause the least interference with WorK activities.

.6 The Contractor shall determine with the Board contact, prior to ordering materials, those locations that are suitable for receiving and storage of materials and equipment.

.7 All materials and equipment shall be kept in a secure area, at Contractor's expense, or removed from the job site when Work is not actually in progress.

.8 Vehicles, trailers or other similar apparatus may not be stored or parked overnight at site without written authorization from Board contact. Written requests are to be forwarded directly to the Board contact.

.9 Approval for parking does not imply any liability or responsibility for safe keeping by the Board.

.10 The Contractor may use the existing electrical and water services, as required, for the Work, and the costs of these services shall be borne by the Board.

## 1.4. WORKMANSHIP

.1 Workmanship shall be the best quality, executed by Workers experienced and skilled in the respective duties for which they are employed. Immediately notify the Consultant if required Work is such as to make it impractical to produce required results.

.2 Do not employ any unfit persons or anyone unskilled in their required duties.

.3 Decisions as to the quality or fitness of Workmanship in cases of dispute rest solely with the Board contact, whose decision is final.

.4 All Contractor personnel are restricted to the job site and necessary access routes. No personnel shall visit other areas or buildings without specific authorization.

.5 The Contractor shall make their own arrangements for emergency treatment of accidents.

.6 Any accidents shall be reported immediately to the Board contact.

.7 The Contractor agrees to hold the Board harmless of any and all liability of every nature and description, which may be suffered through bodily injuries, involving deaths of any persons, by reasons of negligence of the Contractor, his agents, employees, or his Subcontractors.

.8 The Contractor shall supply constant on-site supervision in the form of a Project Superintendent. The Project Superintendent shall have within their authority to negotiate minor changes regarding scheduling, manpower and equipment.

## 1.5. MANUFACTURER'S INSTRUCTIONS

.1 Unless otherwise indicated in the specifications, install, apply or erect products in accordance with manufacturer's instructions. Do not rely on labels or enclosures provided with products. Obtain written instructions directly from manufacturers.

## 1.6. TOOLS OF THE TRADE

.1 The Board will not pay the Awarded Bidder a fee for tools and equipment that are considered "tools of the trade" that are required to perform the work in this Tender or any change orders.

## 1.7. EXISTING EQUIPMENT

.1 Contractor shall demolish and dispose of all existing equipment specified to be removed and or replaced including obsolete services not being reused. The Board shall have first rights of refusal on all demolished equipment and or parts and the Contractor shall provide a minimum of (5) working days notice prior to disposal of the equipment, parts, or equipment and set aside same in a suitable location to be recovered by Board technicians.

**END OF SECTION**

**01 61 00 – Product Requirements**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

.2 Section 01 31 00 – Project Managing and Coordination

### 1.2. TERMINOLOGY

.1 New: Produced from new materials.

.2 Renewed: Produced or rejuvenated from an existing material to like-new condition to serve a new or existing service.

.3 Defective: A condition determined exclusively by the Consultant.

### 1.3. PRODUCT QUALITY

.1 The term 'new' in the following paragraph does not exclude re-manufactured products that have some or all of the materials recycled from other sources. Preference in recycling is for post-consumer recycled materials.

.2 Products, materials, equipment, parts or assemblies (referred to as Products) incorporated in Work:

.3 New Product, not damaged or defective, of best quality (compatible with specification requirements) for purpose intended. If requested, provide evidence as to type, source and quality of Products provided.

.4 Defective Products, whenever identified prior to completion of Work, will be rejected, regardless of previous inspections. Inspection does not relieve responsibility, but is precaution against oversight or error. Remove and replace defective Products at own expense and be responsible for delays and expenses caused by rejection.

.5 Should any dispute arise as to the quality or fitness of Products, decision rests strictly with Consultant.

.6 Unless otherwise indicated in specifications, maintain uniformity of manufacture for any particular or like item throughout the building.

### 1.4. AVAILABILITY

.1 Immediately upon receipt of the Board's Purchase Order, review Product delivery requirements and anticipate foreseeable supply delays for any items.

.2 Immediately upon receipt of the Board's Purchase Order the Contractor shall issue Purchase Orders and or Contracts to all Sub-trades. Provide proof to the Consultant and the Board within 3 days. The Subcontractors shall identify in writing any delivery issues within 14 days of receiving the Contractor's purchase order or contract. The Schedule noted in 01-31 00 1.7.1 shall incorporate all deliveries and installation.

.3 If delays in supply of Products are foreseeable, notify Consultant of such, in order that substitutions or other remedial action may be authorized in ample time to prevent delay in performance of Work.

.4 In the event of failure to notify Consultant at commencement of Work and should it subsequently appear that Work may be delayed for such reason, Consultant reserves the right to substitute more readily available Products of similar character, at no increase in Contract Price or Contract Time.

## 1.5. STORAGE AND PROTECTION

.1 Store and protect Products in accordance with manufacturers' written instructions.

.2 Store with seals and labels intact and legible.

.3 Store sensitive Products in weather tight, climate controlled, enclosures in an environment favourable to Product.

.4 For exterior storage of fabricated Products, place on sloped supports above ground.

.5 Cover Products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of Products.

.6 Store loose granular materials on solid flat surfaces in a well-drained area. Prevent mixing with foreign matter.

.7 Provide equipment and personnel to store Products by methods to prevent soiling, disfigurement, or damage.

.8 Arrange storage of Products to permit access for inspection. Periodically inspect to verify Products are undamaged and are maintained in acceptable condition.

## 1.6. TRANSPORTATION AND HANDLING

.1 Transport and handle Products in accordance with manufacturer's written instructions.

.2 Promptly inspect shipments to ensure that Products comply with requirements, quantities are correct, and Products are undamaged.

.3 Provide equipment and personnel to handle Products by methods to prevent soiling, disfigurement, or damage.

.4 Suitably pack, crate and protect products during transportation to site to preserve their quality and fitness for the purpose intended.

.5 Store products in original, undamaged condition with manufacturer's labels and seals intact until they are being incorporated into completed work.

.6 Protect materials from damage by extreme temperatures or exposure to the weather.

## 1.7. EXISTING UTILITIES

.1 When breaking into or connecting to existing services or utilities, execute Work at times directed by local governing authorities, with minimum disturbance to the owner.

.2 Protect, relocate or maintain existing active services. When services are encountered, cap off in a manner approved by authority having jurisdiction. Stake and record location of capped service.

## 1.8. MANUFACTURER'S WRITTEN INSTRUCTIONS

.1 Unless otherwise indicated in specifications, install or erect Products to manufacturer's written instructions. Do not rely on labels or enclosures provided with Products. Obtain written instructions directly from manufacturers.

.2 Notify Consultant in writing, of conflicts between specifications and manufacturer's instructions, so that Consultant may establish course of action.

.3 Improper installation or erection of Products, due to failure in complying with these requirements, authorizes Consultant to require removal and reinstallation at no increase in Contract Price or Contract Time.

## 1.9. QUALITY OF WORK

.1 Ensure Quality of Work is of highest standard, executed by workers experienced and skilled in respective duties for which they are employed. Immediately notify Consultant if required Work is such as to make it impractical to produce required results.

.2 Do not employ anyone unskilled in their required duties. Consultant and or Board reserves right to require dismissal from site any workers deemed incompetent or careless.

.3 Decisions as to standard or fitness of Quality of Work in cases of dispute rest solely with Consultant, whose decision is final.

.4 Products, materials, systems and equipment shall be applied, installed, connected, erected, used, cleaned and conditioned in accordance with the applicable manufacturer's printed directions.

.5 Where specified requirements are in conflict with manufacturer's written directions, follow manufacturer's directions. Where specified requirements are more stringent than manufacturer's directions, comply with specified requirements.

## 1.10. COORDINATION

.1 Ensure cooperation of workers in laying out Work. Maintain efficient and continuous supervision.

.2 Be responsible for coordination and placement of openings, sleeves and accessories.

.3 Contractor is responsible to ensure suppliers or distributors of materials specified or alternatives accepted, which he intends to use, have materials with original schedule, and similarly it shall be the responsibility of all subcontractors and suppliers to so inform the Contractor.

.4 Contractor shall contact Consultant immediately upon receipt of information indicating materials or items, will not be available on time, in accordance with the latest approved schedule, and similarly it shall be the responsibility of all subcontractors and suppliers to so inform the Contractor.

.5 The above, in no way releases the Contractor, or their subcontractors and suppliers of their responsibility for ensuring timely ordering of materials and items required, including the necessary expediting, to complete the Work as scheduled in accordance with the Contract Documents including temp accommodations and or materials to ensure occupancy date is achieved.

## 1.11. CONCEALMENT

.1 In finished areas, conceal pipes, ducts and wiring in floors, walls and ceilings, except where indicated otherwise.

.2 Before installation, inform the Consultant if there is interference. Install as directed by the Consultant at no additional cost to the Board.

## 1.12. REMEDIAL WORK

.1 Perform remedial work required to repair or replace parts or portions of Work identified as defective or unacceptable. Coordinate adjacent affected Work as required.

.2 Perform remedial work by specialists familiar with materials affected. Perform in a manner to neither damage nor put at risk any portion of Work.

## 1.13. LOCATION OF FIXTURES

.1 Inform Consultant of conflicting installation. Install as directed.

## 1.14. FASTENINGS - EQUIPMENT

.1 Use fastenings of standard commercial sizes and patterns with material and finish suitable for service.

.2 Use heavy hexagon heads, semi-finished unless otherwise specified. Use Type 304 or 316 stainless steel for exterior areas.

.3 Bolts may not project more than one diameter beyond nuts.

.4 Use plain type washers on equipment, sheet metal and soft gasket lock type washers where vibrations occur. Use resilient washers with stainless steel.

## 1.15. PROTECTION OF WORK IN PROGRESS

.1 Prevent overloading of any part of the Project.

.2 Do not cut, drill or sleeve any load bearing structural member, unless specifically indicated, without written approval of the Consultant.

**END OF SECTION**

**01 70 00 – Examination and Preparation**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. REFERENCES

.1 Owner's identification of existing survey control points and property limits.

### 1.3. SUBMITTALS

.1 NOT APPLICABLE.

### 1.4. QUALIFICATIONS OF SURVEYOR

.1 NOT APPLICABLE.

### 1.5. SURVEY REFERENCE POINTS

.1 NOT APPLICABLE.

### 1.6. SURVEY REQUIREMENTS

.1 NOT APPLICABLE.

### 1.7. SUBSURFACE CONDITIONS

.1 Promptly notify Consultant in writing if discovered surface or subsurface conditions at Place of Work differ materially from those indicated in Contract Documents.

.2 Advise the Consultant of a reasonable assumption of probable conditions when determined.

.3 After prompt investigation, should Consultant determine that conditions do differ materially, instructions will be issued for changes in Work.

### 1.8. EXAMINATION

.1 The Contractor is expected to be totally familiar with site conditions and shall assume full responsibility for the cost involved in repairing any damage to the building, site and services, city property, adjacent buildings, etc., during general construction, regardless of the extent of the damage.

.2 Inspect existing conditions, including elements or adjacent Work subject to irregularities, damage, movement, including Work during cutting and patching.

.3 The Contractor shall provide all equipment necessary to make a full and detailed site evaluation. This shall include but not be limited to ladders, flashlights and hand tools.

.4 The Contractor expressly agrees that conditions above existing suspended acoustic ceilings, but below fixed structure, unless obscured by an additional ceiling above, shall be considered exposed conditions for the purposes of making findings under the provisions of the Contract. There shall be no claims for extra costs for extra Work in these areas.

.5 After uncovering, inspect conditions affecting performance of the Work.

.6 Beginning of cutting or patching means acceptance of existing conditions.

## 1.9. PREPARATION

.1 Provide supports to assure structural integrity of surroundings; provide devices and methods to protect other portions of the project from damage.

.2 Provide protection from elements for areas which may be exposed by uncovering work; maintain excavations free of water.

## 1.10. EXISTING SERVICES

.1 Before commencing work, establish location and extent of service lines in the area of Work and notify the Consultant of findings.

.2 Remove abandoned service lines running through existing and new structures. Cap or seal lines at cut-off points as directed by the Consultant.

## 1.11. LOCATION OF EQUIPMENT AND FIXTURES

.1 Inform Consultant of conflicting installations, install as directed.

.2 Locate equipment, fixtures and distribution systems to provide minimum interference and maximum usable space and in accordance with manufacturer's recommendations for safety, access and maintenance.

.3 Inform Consultant of impending installation and obtain approval for actual location.

.4 Submit field drawings to indicate relative position of various services and equipment when required by Consultant.

## 1.12. SURVEY RECORD

.1 Maintain a complete, accurate log of control and survey work as it progresses.

.2 On completion of foundations and major site improvements, prepare a certified survey showing dimensions, locations, angles and elevations of Work.

.3 Record locations of maintained, re-routed and abandoned service lines.

**END OF SECTION**

**01 73 30 – Execution and Cutting and Patching**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 32 00 - Construction Progress Documentation: Submittals and scheduling.

.2 Section 01 61 00 - Product Requirements.

.3 Section 01 70 00 – Examination and Preparation

.4 Individual Product Specification Sections:

.1 Cutting and patching incidental to work of the Section.

.2 Advance notification to other sections of openings required in Work of those Sections.

### 1.2. SUBMITTALS

.1 Submit written request in advance of cutting or alteration which affects:

.1 Structural integrity of any element of Project.

.2 Integrity of weather exposed or moisture resistant element.

.3 Efficiency, maintenance, or safety of any operational element.

.4 Visual qualities of sight exposed elements.

.5 Work of Owner or separate contractor.

.2 Include in request:

.1 Identification of Project.

.2 Location and description of affected Work.

.3 Necessity for cutting or alteration.

.4 Description of proposed Work and Products to be used.

.5 Alternatives to cutting and patching.

.6 Effect on work of Owner or separate contractor.

.7 Written permission of affected separate contractor.

.8 Date and time work will be executed.

### 1.3. TOLERANCES

.1 Monitor fabrication and installation tolerance control of Products to produce acceptable Work.

.2 Do not permit tolerances to accumulate beyond effective or practical limits.

.3 Comply with manufacturers' tolerances. In case of conflict between manufacturers' tolerances and Contract Documents, request clarification from the Consultant before proceeding.

.4 Adjust Products to appropriate dimensions; position and confirm tolerance acceptability, before permanently securing Products in place.

## 2.0 PRODUCTS

### 2.1. MATERIALS

.1 Primary Products: Those required for original installation.

.2 Product Substitution: For any proposed change in materials, submit a request for substitution described in Section 01 33 00.

## 3.0 EXECUTION

### 3.1. EXAMINATION

.1 Examine existing conditions prior to commencing Work, including elements subject to damage or movement during cutting and patching.

.2 After uncovering existing Work, assess conditions affecting performance of work.

.3 Beginning of cutting or patching means acceptance of existing conditions.

### 3.2. PREPARATION

.1 Provide temporary supports to ensure structural integrity of the Work. Provide devices and methods to protect other portions of the Project from damage.

.2 Provide protection from elements for areas which may be exposed by uncovering work.

.3 Maintain excavations free of water.

### 3.3. CUTTING

.1 Execute cutting and fitting as needed to complete the Work. Prior to any cutting and or coring of concrete floors the contractor shall confirm the area is free of services or rebar. Notify the Consultant of any interferences.

.2 Uncover work to install improperly sequenced work.

.3 Remove and replace defective or non-conforming work.

.4 Remove samples of installed work for testing for Hazardous materials.

.5 Provide openings in the Work for penetration of mechanical and electrical work.

.6 Employ experienced installer to perform cutting for weather exposed and moisture resistant elements, and sight exposed surfaces.

.7 Cut rigid materials using a masonry saw or core drill. Pneumatic tools are not allowed without prior approval.

.8 Do all cutting, patching, and making good, to leave a finished condition and to make the several parts of the work come together properly. Coordinate work to keep cutting and patching to a minimum.

.9 Make cuts with clean, true, smooth edges. Fit unit to tolerance established by test standard practice for applicable work. Make patches invisible in the final assembly.

.10 Cutting shall be done in a manner to keep patching to minimum. Obtain Consultant's approval of method to be used to conceal new mechanical and electrical services before beginning cutting. Chasing of concrete surfaces is not permitted.

.11 Cutting or coring of any structural concrete is to be reviewed and approved by the Consultant.

.12 Do not endanger any work by cutting, digging or otherwise altering, and do not cut nor alter any load bearing element without written authorization by Consultant. Provide bracing, shoring and temporary supports as required to keep construction safely supported at all times

.13 Any cost caused by omission or ill-timed work shall be borne by the party responsible thereof.

.14 Regardless of which Section of work is responsible for any portion of cutting and patching, in each case tradesmen qualified in work being cut and patched shall be employed to ensure it is correctly done.

## 3.4. PATCHING

.1 Execute patching to complement adjacent Work.

.2 Fit Products together to integrate with other Work.

.3 Execute work by methods to avoid damage to other Work, and which will provide appropriate surfaces to receive patching and finishing.

.4 Employ original installer to perform patching for weather exposed and moisture resistant elements, and sight-exposed surfaces.

.5 Restore work with new Products in accordance with requirements of Contract Documents.

.6 Fit work with adequate support to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.

.7 At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with firestop material.

.8 Refinish surfaces to match adjacent finish. For continuous surfaces, refinish to the nearest intersection or natural break. For an assembly, refinish the entire unit.

.9 Complete and tightly fit all construction to pipes, ducts and conduits which pass through construction to completely prevent the passage of air.

.10 Patching and making good shall be done by trade specialists in material to be treated, and shall be made undetectable in finished work when viewed from a distance of 1.5m under normal lighting.

**END OF SECTION**

**01 74 00 – Cleaning and Waste Management**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Common Work by All Trades

.2 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

.3 Conduct cleaning and disposal operations to comply with local ordinances and environmental protection legislation.

.4 Store volatile wastes in covered metal containers, and remove them from premises at the end of each working day.

.5 Provide adequate ventilation during use of volatile or noxious substances. Use of building ventilation systems is not permitted for this purpose.

## 2.0 PRODUCTS

### 2.1. CLEANING PRODUCTS

.1 Cleaning Agents and Materials: Low VOC content wherever possible. The Consultant and the Board shall be notified prior to use of any exception.

## 3.0 EXECUTION

### 3.1. CLEANING DURING CONSTRUCTION

.1 Maintain the Work in tidy condition, free from accumulation of waste products and debris, other than that caused by the Owner or other Contractors.

.2 Remove waste material and debris from the work areas and deposit in a waste container at the end of each working day.

.3 Vacuum clean interior areas prior to the start of finishing work. Maintain areas free of dust and other contaminants during finishing operations.

.4 Individual Subcontractors are responsible for the daily clean-up and removal of debris related to, or generated by, their own work. The overall responsibility for project cleanliness rests with the Contractor.

.5 The Contractor shall be responsible for snow removal within the construction area.

.6 Make arrangements with and obtain permits from authorities having jurisdiction for disposal of waste and debris.

.7 Wherever possible recycle materials

.8 Containers:
  .1 Provide adequate number and sizes of on-site garbage and recycling containers within designated work site as required for collection of waste materials and debris on a daily basis.
  .2 Provide additional waste containers when the extent of work warrants.
  .3 Provide and use clearly marked, separate bins for recycling.

.9 Dispose of waste materials and debris at registered waste disposal and recycling facility.

.10 Remove oily rags, waste and other hazardous substances from premises at close of each day, or more often when required.

.11 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly painted surfaces nor contaminate building systems.

## 3.2. WASTE MANAGEMENT

.1 Audit, separate and dispose of construction waste generated by new construction or by demolition of existing structures in whole or in part, in accordance with Ontario Regulations 102/94 and 103/94 made under the Environmental Protection Act.

.2 Containers:
  .1 Provide adequate number and sizes of on-site garbage and recycling containers within designated work site as required for collection of waste materials and debris on a daily basis.
  .2 Provide additional waste containers when the extent of work warrants.
  .3 Provide and use clearly marked, separate bins for recycling.

.3 Fires, and burning of rubbish or waste on site is strictly prohibited.

.4 Burying of rubbish or waste materials on site is strictly prohibited.

.5 Disposal of waste or volatile materials such as mineral spirits, oil, gasoline or paint thinner into ground, waterways, or sewer systems is prohibited.

.6 Empty waste containers on a regular basis to prevent contamination of site and adjacent properties by wind-blown dust or debris

## 3.3. PREPARATION FOR FINAL CLEANING

.1 Prior to final cleaning the General Contractor shall:
  .1 remove all surplus products, tools, construction machinery and equipment not required for the performance of remaining work, and thereafter remove any remaining materials, equipment, waste and debris,
  .2 replace all filters installed on any equipment in operation in the area of work,

.3 remove all paint spots or overspray from all affected surfaces, and

## 3.4. FINAL CLEANING PRIOR TO ACCEPTANCE: INTERIOR

.1 Prior to applying for Substantial Performance of the Work, or, prior to Owner occupancy of the building or portion of the building affected by the Work, whichever comes first, conduct full and complete final cleaning operations for the areas to be occupied.

.2 Final cleaning operations shall be performed by an experienced professional cleaning company, possessing equipment and personnel sufficient to perform full building cleaning operations. Contractors “broom cleaning” is not acceptable as a “Final Clean”. The cleaning contractor shall:

.1 clean interiors of all millwork and surfaces of any furniture and equipment present,

.2 use only cleaning materials recommended by the manufacturer of the surface to be cleaned,

.3 remove all stains, spots, scuff marks, dirt, dust, remaining labels, adhesives or other surface imperfections,

.4 clean and polish all glass and mirrors and remove remaining manufacturer's and safety "X" labels,

.5 clean and polish all finished metal surfaces such as enamelled or stainless steel, chrome, aluminum, brass, and bronze,

.6 clean and polish all vitreous surfaces such as plumbing fixtures, ceramic tile, porcelain enamel, or other such materials,

.7 clean all ceramic tile surfaces in accordance with the manufacturer's instructions,

.8 vacuum, clean and dust behind grilles, louvres and screens,

.9 steam clean all unprotected carpets immediately prior occupancy by Owner, and

.10 clean all equipment and fixtures to a sanitary condition.

.3 For any areas to be occupied after the owner’s initial occupancy, provide full cleaning operations as outlined above prior to turning over to Owner,

.4 The Board’s supplies and equipment must not be used for any cleaning operations including, but not limited to: garbage cans, mops, brooms, rags, ladders, chemicals etc.

## 3.5. FINAL CLEANING PRIOR TO ACCEPTANCE: EXTERIOR

.1 For areas affected by construction final exterior cleaning operations shall be performed by the General Contractor or competent Subcontractor. Contractor's "broom cleaning" only is not acceptable.

.2 Final exterior cleaning shall include:

.1 broom clean and wash exterior walkways, steps, and surfaces; rake clean other surfaces of grounds,

.2 remove dirt and other disfiguration from exterior surfaces,

.3 sweep and wash clean paved areas,

.4 replace filters of mechanical equipment for all equipment that was in use during construction,

.5 clean all roofs, gutters, downspouts, areaways, drywells, and drainage systems,

.6 remove debris and surplus materials from crawl areas and other accessible concealed spaces.

.7 remove overspray

**END OF SECTION**

**01 78 10 – Closeout Submittals and Requirements**

## 1.0 GENERAL

### 1.1. RELATED SECTIONS

.1 Section 01 78 10 – WRDSB Warranty Card, Appendix 00 41 13A

### 1.2. TAKE-OVER PROCEDURES

.1 Take over procedures will be in strict accordance with the requirements as set out in this Section.

### 1.3. SUBSTANTIAL PERFORMANCE

.1 Prior to requesting a Substantial Performance deficiency inspection submit 2 hard copies, 1 digital copy of the Operating and Maintenance Manuals for Consultants approval.

.2 Application for Substantial Performance must include:

.1 One (1) electronic copy of inspection and acceptance certificates required from regulatory agencies, including but not limited to.

.1 Certificates of Approval of the Work by the local Building Department.

.2 Electrical Inspection Certificate of Inspection.

.3 Fire Alarm Verification Certificate.

.3 Advise Consultant in writing, when the project has been substantially completed. If Consultant agrees this stage has been reached, the Consultant shall prepare a complete list of deficiencies and submit copies of this list to Contractor and the Board.

### 1.4. COMMENCEMENT OF LIEN PERIODS

.1 The date of publication of the Certificate of Substantial Performance of the Work, provided to the contractor by the Consultant, shall be the date for commencement of the lien period.

### 1.5. TOTAL PERFORMANCE

.1 Prior to requesting a final inspection submit written certificate that the following have been performed:

.1 Work has been completed and inspected for compliance with Contract Documents and is ready for final inspection

.2 Defects have been corrected and deficiencies have been completed.

.3 Equipment and systems have been tested and are fully operational. Submit two copies of the balancing reports
.4 Certificates required by the contractor have been submitted.
.5 Operation of systems have been demonstrated to Owner's personnel.
.6 Submit Record drawings.
.7 Submit maintenance materials.
.8 Provide certified site survey

.2 When items noted above are completed, request final inspection of Work by consultant, and building inspector. If Work is deemed incomplete by Consultant, complete outstanding items and request re-inspection.

## 1.6. PAYMENT OF SUBSTANTIAL PERFORMANCE HOLDBACK

.1 Prior to the release of lien holdback provide one copy of the following by the Contractor and each subcontractor:
.1 Statutory Declaration or Declaration of Last supply
.2 Workplace Safety and Insurance Board “Certificate of Clearance”.
.2 The Contractor shall submit an application for payment of the holdback amount.
.3 After the receipt of an application for payment which will include a Statutory Declaration and WSIB Clearance from the, the Consultant will issue a certificate for payment of the holdback amount.

## 1.7. FINAL PAYMENT

.1 When the Contractor considers final deficiencies and defects have been corrected and it appears requirements of Contract have been completed, make application for final payment.
.2 When the Consultant finds the Contractor's application for final payment valid, the Consultant will issue a final certificate of payment
.3 The Board reserves the right to charge the Contractor for school access card(s) that have not been returned.
.4 The cost to reprogram or replace the card(s) access system is estimated at $50.00 (fifty dollars) for each card issued, $30.00 (thirty dollars) for each keybox key, plus $35.00 (thirty five dollars) administration fee.

## 1.8. CLOSEOUT SUBMITTALS

.1 Prepare instructions and data using personnel experienced in maintenance and operation of described products and submit them to the Consultant for review.
.2 Copy will be returned to the contractor with the Consultant's comments.

.3 Revise content of documents as required prior to final submission.

.4 Two (2) weeks prior to Substantial Performance of the Work, submit to the Consultant, the final copies of operating and maintenance manuals.

.5 Ensure spare parts, maintenance materials and special tools provided are new, undamaged or defective, and of same quality and manufacture as products provided in Work.

.6 If requested, furnish evidence as to type, source and quality of products provided.

.7 Defective products will be rejected, regardless of previous inspections. Replace products at own expense.

.8 Pay costs of transportation.

## 1.9. OPERATION AND MAINTENANCE MANUAL FORMAT

.1 Provide two copies of operating and maintenance data, prepared on 215 X 280mm sheets in printed or typewritten form, contained in 3-ring binders with soft vinyl covers for materials and equipment which require special maintenance or operating procedures.

.2 When multiple binders are used, correlate data into related consistent groupings. Identify contents of each binder at the front of each volume.

.3 Cover: Identify each binder with type or printed title 'Project Record Documents'; list title of project and identify subject matter of contents.

.4 Arrange content by the divisions of the specifications under Section numbers and sequence of Table of Contents.

.5 Provide tabbed fly leaf for each separate product and system, with typed description of product and major component parts of equipment.

.6 Include the following in each manual:

.1 Complete list of subcontractors and suppliers, their addresses and telephone numbers. Provide 24 hour emergency telephone numbers for such subcontractors as Plumbing, Electrical, Sprinklers, Fire System, Heating, etc.

.2 Specified warranties for contractor, each subcontractor and supplier.

.3 WRDSB Project Asset and Warranty Card, Appendix 00 41 13A

.4 Copy of finish hardware list, complete with all amendments and revisions and lock manufacturer's descriptive and service literature.

.5 Schedule of paints and coatings. Include sufficient explanation to fully identify each surface with the applicable paint or coating used. Enclose a copy of the colour schedule.

.6 Maintenance instructions for finished surfaces.

.7 Brochures, cuts of equipment and fixtures.

.8 Operating and maintenance instructions for equipment.

.9 Submit copies of letters from manufacturers of equipment and systems indicating their technical representatives have inspected and tested systems and are satisfied with methods of installation, connection and operations. These letters shall state names of persons present at testing, methods used and list of functions performed.

.10 Submit one complete set of reviewed shop drawings of architectural, structural, mechanical and electrical items, folded to 215 x 280mm size, contained in heavy duty manila envelopes, numbered and labelled. Follow specification format with no more than one Section per envelope, hard copy and PDF.

.11 Relevant certificates issued by authorities having jurisdiction

.12 Computer disc or flash drive with all the above documentation in PDF format

## 1.10. RECORDING ACTUAL SITE CONDITIONS

.1 Record information on a set of black line opaque drawings, and within the Project Manual.

.2 Annotate with coloured felt tip marking pens, maintaining separate colours for each major system, for recording changed information.

.3 Record information concurrently with construction progress. Do not conceal Work of the Project until required information is accurately recorded.

.4 Contract drawings and shop drawings: legibly mark each item to record actual construction, including:

.1 Measured depths of elements of foundation in relation to finish first floor datum.

.2 Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.

.3 Measured locations of internal utilities and appurtenances, referenced to visible and accessible features of construction.

.4 Field changes of dimension and detail.

.5 Changes made by change orders.

.6 Details not on original Contract Drawings.

.7 References to related shop drawings and modifications.

.5 Specifications: legibly mark each item to record actual construction, including:

.1 Manufacturer, trade name, and catalogue number of each product actually installed, particularly optional items and substitute items.

.2 Changes made by Addenda and change orders.

.6 Other Documents: Maintain warranties, test reports and samples required by individual specifications sections.

## 1.11. RECORD (AS-BUILT) DOCUMENTS AND SAMPLES

.1 Store AS-BUILT documents and samples in the field office apart from documents used for construction. Provide files, racks, and secure storage.

.2 Label AS-BUILT documents and file in accordance with section number listings in List of Contents of the Project Manual. Label each document AS-BUILT DOCUMENTS in neat, large, printed letters.

.3 Maintain AS-BUILT documents in clean, dry and legible condition. Do not use as-built documents for construction purposes.

.4 Keep as-built documents and samples available for inspection by the Consultant.

## 1.12. RECORD DRAWINGS

.1 Prior to Substantial Performance of the Work, update the marked up information from the AS-BUILT documents to a master set of drawing.

.2 Submit one set of completed AS-BUILT documents to the Consultant for review.

.3 Documents will be returned to the contractor with the Consultant's comments.

.4 Revise content of documents as required prior to final submission.

.5 After the review is completed resubmit to the Consultant for Consultant to produce electronic record drawings for the owner to use.

## 1.13. SPARE PARTS

.1 Provide spare parts, in quantities specified in individual specification sections.

.2 Provide items of same manufacture and quality as items in Work.

.3 Receive and catalogue all items. Submit inventory listing to Consultant. Include approved listings in the Maintenance Manual.

.4 Obtain receipt for delivered products and submit prior to final payment.

## 1.14. REPLACEMENT (MAINTENANCE) MATERIALS

.1 Deliver to site, unload and store where directed, replacement (maintenance) materials as required elsewhere in these Specifications. Obtain a signed receipt from the Owner's Representative for delivered materials and include a copy of receipt in Operation and Maintenance manuals.

.2 Package materials so they are protected from damage and loss of essential properties.

.3 Label packaged materials for proper identification of contents.

## 1.15. SPECIAL TOOLS

.1 Provide special tools, in quantities specified in the individual specification section.

.2 Provide items with tags identifying their associated function and equipment.

.3 Receive and catalogue all items. Submit inventory listing to Consultant. Include approved listings in Maintenance Manual

## 1.16. FINAL SITE SURVEY

.1 NOT APPLICABLE.

## 1.17. WARRANTIES AND BONDS

.1 Separate each warranty or bond with index tab sheets keyed to Table of Contents listing.

.2 List subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.

.3 Except for items put into use with Owner's permission, leave the date of beginning of time of warranty until the Date of Substantial Performance is determined. The date of Substantial Performance of the Work shall be the date for commencement of the warranty period.

.4 Verify that documents are in proper form, contain full information, and are notarized.

.5 Co-execute submittals when required.

.6 Retain warranties and bonds until time specified for submittals.

**END OF SECTION**

**01 78 40 – Maintenance Requirements**

## 1.0 GENERAL

### 1.1. SECTION INCLUDES

.1 Equipment and systems.
.2 Materials and finishes.
.3 Spare parts
.4 Maintenance manuals.
.5 Special tools.
.6 Storage, handling and protection.
.7 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.2. RELATED SECTIONS

.1 Section 01 45 00 - Quality Control.
.2 Section 01 78 40 – Maintenance Requirements.
.3 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.3. EQUIPMENT AND SYSTEMS

.1 Each Item of Equipment and Each System: include description of unit or system, and component parts. Give function, normal operation characteristics, and limiting conditions. Include performance curves, with engineering data and tests, and complete
.2 Panel board circuit directories: provide electrical service characteristics, controls, and communications.
.3 Include installed colour coded wiring diagrams.
.4 Operating Procedures: include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
.5 Maintenance Requirements: include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
.6 Provide servicing and lubrication schedule, and list of lubricants required.
.7 Include manufacturer's printed operation and maintenance instructions.

.8 Include sequence of operation by controls manufacturer.

.9 Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.

.10 Provide installed control diagrams by controls manufacturer.

.11 Provide coordination Drawings, with installed colour coded piping diagrams.

.12 Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.

.13 Provide a list of original manufacturer's spare parts, current prices, and recommended quantities to be maintained in storage.

.14 Include test and balancing reports as specified in Section 01 45 00.

.15 Additional requirements: As specified in individual specification sections.

## 2.0 PRODUCTS

### 2.1. MATERIALS AND FINISH

.1 Building Products, Applied Materials, and Finishes: include product data, with catalogue number, size, composition, and colour and texture designations.

.2 Instructions for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.

.3 Moisture-protection and Weather-exposed Products: include manufacturer's recommendations for cleaning agents and methods, precautions against detrimental agents and methods, and recommended schedule for cleaning and maintenance.

.4 Building Envelope: include copies of drawings of building envelope components, illustrating the interface with similar or dissimilar items to provide an effective air, vapour and thermal barrier between indoor and outdoor environments. Include an outline of requirements for regular inspections and for regular maintenance to ensure that on-going performance of the building envelope will meet the initial building envelope criteria.

.5 Additional Requirements: as specified in individual specifications sections.

### 2.2. SPARE PARTS

.1 Provide spare parts, in quantities specified in individual specification sections.

.2 Provide items of same manufacture and quality as items in Work.

.3 Receive and catalogue all items. Submit inventory listing to Consultant. Include approved listings in the Maintenance Manual.

.4 Obtain receipt for delivered products and submit prior to final payment.

## 2.3. MAINTENANCE MATERIALS

.1 Provide maintenance and extra materials, in quantities specified in individual specification sections.

.2 Provide items of same manufacture and quality as items in Work.

.3 Receive and catalogue all items. Submit inventory listing to Consultant. Include approved listings in the Maintenance Manual.

.4 Obtain receipt for delivered products and submit prior to final payment.

## 2.4. SPECIAL TOOLS

.1 Provide special tools, in quantities specified in the individual specification section.

.2 Provide items with tags identifying their associated function and equipment.

.3 Receive and catalogue all items. Submit inventory listing to Consultant. Include approved listings in the Maintenance Manual.

# 3.0 EXECUTION

## 3.1. DELIVERY TO SITE

.1 Deliver to place of work and store.

.2 General Contractor to receive and acknowledge delivery from contractors and subcontractors of all parts and materials assembled for maintenance requirements. Provide a summary inventory list to the Consultant and/or the Board after all materials are gathered and verification of location. Signatures of receipt will not be accepted from anyone except the General Contractor’s representative.

## 3.2. STORAGE, HANDLING AND PROTECTION

.1 Consult with the Board to determine location for storage.

.2 Store spare parts, maintenance materials, and special tools in manner to prevent damage or deterioration.

.3 Store in original and undamaged condition with manufacturer's seal and labels intact.

.4 Store components subject to damage from weather in weatherproof enclosures.

.5 Store paints and freezable materials in a heated and ventilated room.

.6 Remove and replace damaged products at own expense and to the satisfaction of the Consultant.

**END OF SECTION**

**01 79 00 – Demonstration and Training**

## 1.0 GENERAL

### 1.1. SECTION INCLUDES

.1 Procedures for demonstration and instruction of Products, equipment and systems to Owner's personnel.

.2 Seminars and demonstrations.

### 1.2. RELATED SECTIONS

.1 This Section describes requirements applicable to all Sections within Divisions 02 to 49.

### 1.3. DESCRIPTION

.1 At Substantial Performance, at a time acceptable to Owner and Consultant, but not before operations and maintenance manual have been reviewed and accepted by the consultant; contractor shall give a complete demonstration in the presence of consultant; Sub-consultants, Owner and Owner's personnel of operation and maintenance of systems and equipment once they are 100% complete.

.2 Owner will provide a list of personnel to receive instructions and will coordinate their attendance at agreed-upon times.

### 1.4. COMPONENT DEMONSTRATION

.1 Manufacturer to provide authorized representative to demonstrate operation of equipment and systems.

.2 Instruct Owner's personnel, and provide written report that demonstration and instructions have been completed.

### 1.5. SUBMITTALS

.1 Submit schedule of time and date for demonstration of each item of equipment and each system one (1) week prior to designated dates, for Consultant's approval.

.2 Submit reports within forty eight (48) after completion of demonstration, that demonstration and instructions have been satisfactorily completed.

.3 Give time and date of each demonstration, with a list of persons present.

## 1.6. CONDITIONS FOR DEMONSTRATIONS

.1 Equipment has been inspected and put into operation in accordance with manufacturer's instructions and contract requirements.

.2 Testing, adjusting, and balancing have been performed in accordance with manufacturer's instructions and contract requirements, and equipment and systems are fully operational.

.3 Provide information packages as required for use in demonstrations and instructions.

## 2.0 PRODUCTS

## 2.1. NOT USED

.1 Not used.

## 3.0 EXECUTION

## 3.1. PREPARATION

.1 Verify that suitable conditions for demonstration and instructions are available.

.2 Verify that designated personnel are present.

.3 Prepare agendas and outlines.

.4 Establish seminar organization.

.5 Explain component design and operational philosophy and strategy.

.6 Develop equipment presentations.

.7 Present system demonstrations.

.8 Accept and respond to seminar and demonstration questions with appropriate answers.

## 3.2. PREPARATION OF AGENDAS AND OUTLINES

.1 Prepare agendas and outlines including the following:

.1 Equipment and systems to be included in seminar presentations.

.2 Name of companies and representatives presenting at seminars.

.3 Outline of each seminar's content.

.4 Time and date allocated to each system and item of equipment.

.5 Provide a separate agenda for each system.

## 3.3. SEMINAR ORGANIZATION

.1 Coordinate content and presentations for seminars.

.2 Coordinate individual presentations and ensure representatives scheduled to present at seminars are in attendance.

.3 Arrange for presentation leaders familiar with the design, operation, maintenance and troubleshooting of the equipment and systems. Where a single person is not familiar with all aspects of the equipment or system, arrange for specialists familiar with each aspect.

.4 Coordinate proposed dates for seminars with Owner and select mutually agreeable dates.

## 3.4. EXPLANATION OF DESIGN STRATEGY

.1 Explain design philosophy of each system. Include following information:

.1 An overview of how the system is intended to operate.

.2 Description of design parameters, constraints and operational requirements.

.3 Description of system operation strategies.

.4 Information to help in identifying and troubleshooting system problems.

## 3.5. DEMONSTRATION AND INSTRUCTIONS

.1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment.

.2 Instruct personnel in all phases of operation and maintenance using operation and maintenance manuals as the basis of instruction.

.3 Instruct personnel on control and maintenance of sensory equipment and operational equipment associated with maintaining energy efficiency and longevity of service.

.4 Review contents of manual in detail to explain all aspects of operation and maintenance.

.5 Prepare and insert additional data in operations and maintenance manuals when the need for additional data becomes apparent during instructions.

**END OF SECTION**

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Related Sections

.1 Section 01 35 43 – Hazardous Materials
.2 Section 01 35 43A - Asbestos Audit Report.

1.3 Existing Conditions

.1 Assume responsibility for demolition of structures in the condition they are at time notified of award of contract.
.2 Inspect adjacent existing rooms and buildings to extent possible to ensure that its condition and stability is recorded in a manner suitable for evaluation of possible damage caused by work of this Section.

1.4 Designated Substances

.1 Designated Substances to be removed prior to demolition by qualified trades following all regulatory requirements.

1.5 Work Included

.1 Refer to Demolition Drawings for extent and scope of demolition work.

1.6 Protection

.1 Demolition work shall be performed with adequate care being taken to prevent damage to surrounding work or material which is to remain the property of the Owner.
.2 Prevent movement, settlement or damage of adjacent structures, services, existing elements to remain. Provide bracing, shoring, underpinning, as required. Make good all damage caused by demolition.
.3 Take precautions to support affected structures, and if safety of building being demolished or adjacent structures or services appears to be endangered, cease operations and notify Consultant.
.4 Prevent debris from blocking surface drainage system and mechanical and electrical systems which must remain in operation.
.5 Provide protection from elements for all interior parts affected by demolition.
.6 Fires and burning of waste or materials are not permitted.
**.7 Do not bury waste or materials on site**.
.8 Do not dispose of waste or volatile materials such as: mineral spirits, oil, petroleum based lubricants, or toxic cleaning solutions into watercourses, storm or sanitary sewers. Ensure proper disposal procedures are maintained throughout project.
.9 Do not pump water containing suspended materials into watercourses, storm or sanitary sewers, or onto adjacent properties.
.10 Control disposal or runoff of water containing suspended materials or other harmful substances in accordance with local authorities.
.11 Protect trees, plants and foliage on site and adjacent properties where indicated.
.12 Prevent extraneous materials from contaminating air beyond application area, by providing temporary enclosures during demolition work.
.13 Cover or wet down dry materials to prevent blowing dust and debris. Control dust on all temporary roads.

1.7 Scheduling of Work

.1 Demolition of structure and appurtenances as indicated on the Drawings is to be undertaken at times and dates as directed by the Consultant or as otherwise listed in this Specification.
.2 Cooperation with subcontractors is necessary to prevent delays.

1.8 Subcontractor Qualifications

.1 Execute the work of this Section by a subcontractor who has adequate plant, equipment and skilled tradespeople to perform the work expeditiously and who is known to have been responsible for similar satisfactory work.
.2 Performance of all demolition work shall be in accordance with all regulations under the Ministry of Labour, including the Occupational Health and Safety Act, Ministry of the Environment and the Ontario Building Code.

## PART 2 - PRODUCTS

2.1 Equipment

.1 Equipment and heavy machinery to meet or exceed all applicable emission requirements.
.2 Leave machinery running only while in use, except where extreme temperatures prohibit shutting machinery down.

## PART 3 - EXECUTION

3.1 Examination

.1 Before commencing any demolition, ensure thorough examination of the site and work to be demolished so that all possible factors concerning demolition are investigated and that the following are known:
  .1 Methods and means available for materials handling, disposal, storage and transportation.
  .2 Construction of structures to be demolished.

3.2 Preparation

.1 Install protection consisting of barricades, signs and substantial constructions to provide physical protection.
.2 Erect shoring and other structures to prevent collapse, settlement and movement.
.3 Post danger signs. Barricade all access by unauthorized persons to areas in which demolition is in progress.
.4 Re-route electrical and mechanical services entering/ leaving the building and which are to be reconnected. Post warning signs and erect barricades on electrical lines and equipment which may remain energized to serve parts of the buildings during period of demolition. Refer to Drawings.
.5 Do not disrupt active or energized utilities traversing premises.
.6 Employ rodent and vermin control and comply with health regulations during any such control procedures.

3.3 General

.1 Perform all demolition under the direction of a competent foreman at all times.
.2 Water down debris frequently to prevent the spread of dust.
.3 Provide for complete and safe access at all times to areas adjacent to demolition work.

3.4 Demolition

.1 Demolish complete structures as indicated and remove existing equipments and services as indicated. Carefully review Architectural, Structural, Mechanical and Electrical Drawings for specific requirements for demolition. **Contractors are required to view prior to Bidding.**
.2 Carefully remove materials and equipment, and store, protect, and reinstall in building, using qualified tradesmen those items designated in the specifications or on Drawings to be reinstalled.
.3 Carefully remove materials and equipment to be retained by the Owner as indicated on Drawings. Refer also to Mechanical and Electrical Sections of the Specifications and Drawings for equipment to be handed over to the Owner.
.4 At the end of each day's work, leave work in a safe condition so that no part is in danger of collapse or falling.
.5 Demolish masonry and concrete walls in small sections. Carefully remove and lower structural framing and other heavy or large objects.
.6 Stockpile materials in a location within the Project Area which will not impede demolition activity. Eliminate double handling where possible.
.7 Selling or burning of materials on site is not permitted.

3.5 Disposal

.1 Unless otherwise specified in this Section, remove completely from the site, all debris resulting from demolition.
.2 Designate an area on site for the separation and storage of waste materials. Allow enough space for multiple bins.
.3 At a minimum, provide storage bins onsite for concrete, metal, wood, cardboard, plastic, gypsum board and mixed waste. Land clearing debris, asphalt and concrete can be stockpiled onsite, for further processing.
.4 Remove debris daily, or as it accumulates. Do not overload trucks, take means to prevent spillage.
.5 Remove contaminated or dangerous materials from site and dispose of in a safe manner to minimize danger on site or at any time during disposal.

3.6 Clean Up

.1 Upon completion of work, remove debris, trim surfaces and leave work site clean.
.2 Use only cleaning solutions and procedures which are not harmful to health, are not injurious to plants, and do not endanger wildlife, adjacent watercourses or ground water.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Related Sections

.1 Structural Steel – refer to Structural Drawings.
.2 Section 09 91 00 – Painting.

1.3 Quality Assurance

.1 Sub-contractor Qualifications
  .1 Provide metal fabrications specified in this Section only by a fabricator who has adequate plant, equipment and skilled tradesmen to fabricate and install metal fabrications of the highest quality.
  .2 Welder Qualifications
    .1 Weld structural components as follows:
      .1 Steel to conform to requirements of CSA Standard W59 and by a fabricator fully certified by the Canadian Welding Bureau to conditions of CSA Standard W47.1 and W55.3.
      .2 Aluminum; by a fabricator fully certified by the Canadian Welding Bureau to requirements of CSA Standard W47.2.

1.4 Requirements of Regulatory Agencies

.1 Metal fabrications which function to resist forces imposed by dead and live loads shall conform to requirements of jurisdictional authorities.
.2 Submit shop drawings stamped and sealed by a professional Engineer registered in the Province of Ontario to authorities when requested.

1.5 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM A53/ A53M – 18, Specification for Pipe, Steel, Black and Hot-Dipped, Zinc-Coated Welded and Seamless.
  .2 ASTM A269/ a269M – 15a(2019), Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service.
  .3 ASTM A307 – 14e1, Specification for Carbon Steel Bolts and Studs, 60,000 PSI Tensile Strength.
  .4 ASTM A780/ A780M – 09(2015), Standard Practice for Repair of damaged Hot Dip Coatings.
.2 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-1.40-97, Anti-corrosive Structural Steel Alkyd Primer.
  .2 CAN/CGSB-1.108-M89, Bituminous Solvent Type Paint.
  .3 CAN/CGSB-1.181-99, Ready-Mixed, Organic Zinc-rich coating.
.3 Canadian Standards Association (CSA)
  .1 CAN/CSA-G40.20/G40.21-98, General Requirements for Rolled or Welded Structural Quality Steel.
  .2 CAN/CSA-G164-M92(R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.
  .3 CAN/CSA-S16-01 (R2007), Limit States Design of Steel Structures.
  .4 CSA W47.1-09 (R2014), Certification of Companies for Fusion Welding of Steel Structures.
  .5 CSA W55.3-08 (R2018), Resistance Welding Qualification Code for Fabricators of Structural Members used in Buildings.

.6 CSA W59 - 2018, Welded Steel Construction.

1.6 Shop Drawings

.1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
.2 Indicate materials, core thicknesses, finishes, connections, joints, method of anchorage, number of anchors, supports, reinforcement, details and accessories.

1.7 Delivery, Storage and Handling

.1 Deliver, store, handle and protect materials in accordance with Section 01 61 00 - Basic Product Requirements.
.2 Label, tag or otherwise mark metal fabrications supplied for installation by other sections to indicate their function, location in building and shop drawing designation.
.3 Protect metal fabrications from damage during delivery, storage and handling. Protect prime painted and galvanized surfaces from damage.
.4 Cover exposed surfaces of stainless steel or prefinished metal which does not receive site finishing, with protective coatings or wrappings, prior to shipping to job site. Use materials recommended by finishers or manufacturers of metals, to ensure that method is sufficiently protective, easily removed and harmless to the finish.
.5 Leave protective covering in place until final cleaning of building. Provide instructions for removal of protective covering.

## PART 2 - PRODUCTS

2.1 Materials

.1 Include all materials, products, accessories and supplementary parts necessary to complete assembly and installation of metal fabrications specified in this Section.
.2 Incorporate only metals that are free from defects which impair strength or durability or which are visible.
.3 Install only new materials of best quality and free from rust, waves and buckles, that are clean, straight with sharply defined profiles conforming to requirements of the following standards and specifications:
  .1 Steel sections and plates: to CAN/CSA-G40.20/G40.21, Grade 300W.
  .2 Hollow Structural Sections: to CAN/CSA G40.21, Grade 350W.
  .3 Welding materials: to CSA W59-M1998.
  .4 Bolts and anchor bolts: to ASTM A 307.
  .5 Galvanizing: hot dipped galvanizing with zinc coating of 600 g/m2 to CAN/CSA-G164.
  .6 Stainless steel: To ASTM A 269. Type 304 (18-8), seamless with No. 4 finish.
  .7 Aluminum extrusions: Aluminum Association alloy AA6063-T5 anodizing quality.
  .8 Shop coat primer: to CAN/CGSB-1.40.
  .9 Galvanized primer: zinc-rich, ready mix to CAN/CGSB-1-181.
  .10 Bituminous paint: to CAN/CGSB-1.108.
  .11 Grout: non-shrink, non-metallic, flowable, 15 MPa at 24 hours.

2.2 Fabrication

.1 Fabricate work specified in this Section with machinery and tools specifically designed for the intended manufacturing processes and by skilled tradesmen.
.2 Fabricate work with materials, component sizes, metal gauges, reinforcing, anchors and fastenings of adequate strength to withstand intended use and within allowable design factors imposed by jurisdictional authorities.
.3 Fabricate work square, straight and accurate to required size, with joints closely fitted and properly secured.

.4 Incorporate means for fastening of other installations secured to metal fabrications. Pre-punch holes in members to allow for installation of mechanical and/ or electrical items.
.5 Ensure that metal fabrications will remain free of warping, buckling, opening of joints and seams, distortion and permanent deformation.
.6 Provide for differential movement within assemblies and at junctions of assemblies with surrounding construction.
.7 Cleanly and smoothly finish exposed edges of materials including holes. Machine or grind components to ensure level bearings.
.8 Cap open ends of sections exposed to view, such as pipes, channels, angles and other similar members.

2.3 Assembly

.1 Where possible, fit and shop assemble work, ready for erection.
.2 Accurately cut, machine and fit joints, corners, copes and mitres so that junctions between components fir together tightly and in true planes.
.3 Conceal fastenings from view unless otherwise indicated on Drawings.
.4 Weld all connections where possible; bolt where not possible and cut off bolts flush with nuts. Countersink bolt heads and provide method to prevent loosening of nuts.
.5 Use self-tapping shakeproof countersunk flat headed screws on items requiring assembly by screws or as indicated on Drawings.
.6 Weld joints tight, flush and in true planes with base metals. Ensure exposed welds are continuous for length of each joint. File or grind exposed welds smooth and flush where exposed to view.

2.4 Galvanizing

.1 After fabrication galvanize all exterior work unless noted otherwise.
.2 Fabricate items to be galvanized as recommended in Appendix A and B of CSA G164.
.3 Hot dip galvanize assemblies following their fabrication except where impossible.
.4 Paint galvanized surfaces that are cut, welded or threaded with zinc rich paint to ensure a minimum coating thickness of 0.102mm, immediately following damage to galvanized protection. Prepare and repair surfaces to meet specified requirements of ASTM A780.

2.5 Isolation Coating

.1 Isolate aluminum from following components, by means of bituminous paint:
  .1 Dissimilar metals except stainless steel, zinc or white bronze of small area.
  .2 Concrete, mortar and masonry.
  .3 Wood.

## PART 3 - EXECUTION

3.1 Installation

.1 Install metal fabrications plumb, true, square, straight, level and accurately and tightly fitted together and to surrounding construction.
.2 Provide suitable means of anchorage acceptable to the Consultant such as anchor bolts, bolts with washers and nuts, lag screws, expansion shields, toggles, straps, sleeves, brackets, clips and other items necessary for secure installation as required by loading and jurisdictional authorities.
.3 Make field connections with bolts to CAN/CSA-S16.1 or weld in accordance with CSA W59.
.4 Exposed fastening devices to match finish and be compatible with material through which they pass.

.5 Attach metal fabrications to masonry with lead plugs and galvanized steel or other corrosion resistant fastenings to support load with a safety factor of three (3).
.6 Grout metal posts, pickets, balusters, etc. in metal sleeves cast into concrete with sulphur, molten lead or quick setting anchor cement, unless detailed otherwise. Fabricate sleeves to 150mm minimum depth.
.7 Countersink pilot holes provided for wood screws where wood is attached to metal fabrications.
.8 Insulate between dissimilar metals; or between metal and masonry or concrete with bituminous paint to prevent electrolysis.
.9 Caulk to Section 07 92 10 - Joint Sealing between components installed by this Section to seal joints against passage of air, water or both.
.10 Hand items over for casting into concrete or building into masonry to appropriate trades together with setting templates.

3.2 Adjustment and Cleaning

.1 After installation, touch-up primed surfaces that are burnt, scratched or otherwise damaged with prime paint to match shop coat.
.2 Repair areas of bare metal and welds on galvanized surfaces with zinc rich paint.
.3 Do not field paint when air temperature is below 7°C.
.4 Remove damaged, dented, defaced, defectively finished or tool marked components and replace with new.
.5 Refinish shop applied finishes in field only with prior approval from Consultant.
.6 Clean off dirt on surfaces resulting from installation.

3.3 Schedule of Metal Fabrications

.1 General
  .1 Ensure that all Drawings and Specification sections including those for structural, mechanical and electrical work are consulted to establish the limits of metal fabrication installations included in this Section.
.2 Angle Lintels
  .1 Refer to Structural Drawings.
.3 Exterior Railings and Balustrades
  .1 Railings and balustrades: round galvanized steel formed to shapes and sizes as detailed on Drawings.
  .2 Set railing standards in concrete with heated liquid sulphur to fill hole where indicated. Remove overflow immediately.
.4 Exterior Guard at New Roof
  .1 Guards: round galvanized steel formed to shapes and sizes as detailed on Drawings.
  .2 Anchor to steel structure as indicted on Structural Drawings.
.5 Interior Railings (Balcony)
  .1 Repair interior railings indicated on Drawings with material matching existing diameters and profiles.
.6 Steel Access Ladders
  .1 Provide steel access ladders to roof to details on Drawings.
.7 Gratings, Covers and Frames
  .1 Gratings: Type W/DA grating by Borden Metal Products (Canada) Limited. Supply gratings in removable lengths as indicated on Drawings.
  .2 Frames: 6mm steel angle in size to suit location.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Miscellaneous wood blocking, furring – Divisions 06, 07, 08, 09, 10.

1.3 References

.1 Canadian Standards Association (CSA)
- .1 CSA B111, Wire Nails, Spikes and Staples.
- .2 CAN/CSA-G164-M, Hot Dip Galvanizing of Irregularly Shaped Articles.
- .3 CSA O121-M, Douglas Fir Plywood.
- .4 CAN/CSA-O141, Softwood Lumber.
- .5 CSA O151-M, Canadian Softwood Plywood.
- .6 CAN/CSA-O325.0, Construction Sheathing.

.2 National Lumber Grades Authority (NLGA)
- .1 Standard Grading Rules for Canadian Lumber.

1.4 Quality Assurance

.1 Lumber identification: by grade stamp of an agency certified by Canadian Lumber Standards Accreditation Board.
.2 Plywood identification: by grade mark in accordance with applicable CSA standards.
.3 Plywood, OSB and wood based composite panel construction sheathing identification: by grademark in accordance with applicable CSA standards.

## PART 2 - PRODUCTS

2.1 Lumber Material

.1 Lumber: unless specified otherwise, SPF species softwood, S4S, moisture content 19% or less in accordance with following standards:
- .1 CAN/CSA O141.
- .2 NLGA Standard Grading Rules for Canadian Lumber.

.2 Furring, blocking, nailing strips, grounds, rough bucks, cants, curbs, fascia backing and sleepers:
- .1 S2S.
- .2 Board sizes: "Standard" or better grade.
- .3 Dimension sizes: "Standard" light framing or better grade.

2.2 Panel Materials

.1 Panel standards: type, grade and thickness as indicated, in accordance with following standards:
- .1 Douglas fir plywood (DFP): to CSA O121, standard construction, exterior grade.
- .2 Canadian softwood plywood (CSP): to CSA O151, standard construction.
- .3 Poplar plywood (PP): to CSA O153, standard construction.
- .4 Waferboard and strandboard: to CAN3-O437.

2.3 Pressure Treated Lumber and Plywood

.1 Pressure treated lumber: to CSA O80.1 - "Preservative Treatment of all Timber Products by Pressure Processes".

2.4 Fasteners

.1 Nails, spikes and staples: to CSA B111.
.2 Bolts: 12.7mm diameter unless indicated otherwise, complete with nuts and washers.
.3 Proprietary fasteners: toggle bolts, expansion shields and lag bolts, screws and lead or inorganic fibre plugs, explosive actuated fastening devices, recommended for purpose by manufacturer.
.4 Galvanizing: to CSA G164, use galvanized fasteners for exterior work, interior highly humid areas, and pressure-preservative treated lumber.

2.5 Accessories

.1 Polyethylene film: to CAN 2-51.33 Type 1, 0.15mm thickness.

2.6 Wood Preservative

.1 Surface applied wood preservative: copper naphthenate or 5% pentachlorophenol solution, water repellant preservative.

## PART 3 - EXECUTION

3.1 Preparation

.1 Treat surfaces of material with wood preservative, before installation.
.2 Apply preservative by dipping, or by brush to completely saturate and maintain wet film on surface for minimum 3 minute soak on lumber and one minute soak on plywood.
.3 Re-treat surfaces exposed by cutting, trimming or boring with liberal brush application of preservative before installation.
.4 Treat material as indicated as follows:
  .1 Wood cants, fascia backing, curbs, nailers, sleepers on roof deck.
  .2 Wood furring for on outside surface of exterior masonry and concrete walls.

3.2 Installation

.1 Comply with requirements of NBC, supplemented by the following paragraphs.
.2 Install furring and blocking as required to space-out and support casework, cabinets, wall and ceiling finishes, facings, fascia, soffit, siding, washroom accessories and other work as required. Install required provisions for fastening located and secured to suit site conditions, and adequate for intended support.
.3 Align and plumb faces of furring and blocking to tolerance of 1:600.
.4 Install rough bucks, nailers and linings to rough openings as required to provide backing for frames and other work.
.5 Except when indicated otherwise, use material at least 38mm thick and secured with 9mm bolts located within 300mm from ends of members and uniformly spaced at 1200mm between.

3.3 Erection

.1 Frame, anchor, fasten, tie and brace members to provide necessary strength and rigidity.
.2 Countersink bolts where necessary to provide clearance for other work.

3.4 Schedules

.1 Provide electrical equipment backboards for mounting electrical equipment as indicated. Use 19mm thick plywood on 19mm x 38mm furring around perimeter and at maximum 300mm intermediate. Paint before installation.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Related Sections

.1 Section 09 91 10 – Painting: Painting and finishing.

1.3 References

.1 American National Standards Institute (ANSI)
  .1 ANSI A208.1-2009, Particleboard, Matformed Wood.
  .2 ANSI A208.2-2016, Medium Density Fibreboard (MDF).
.2 Architectural Woodwork Manufacturers Association of Canada (AWMAC)
  .1 AWMAC Quality Standards for Architectural Woodwork 2014.
.3 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-11.3-M87, Hardboard.
.4 Canadian Standards Association (CSA)
  .1 CSA B111-1974 (R2003), Wire Nails, Spikes and Staples.
  .2 CAN/CSA-G164-M92 (R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.
  .3 CSA O115-M1982 (R2001), Hardwood and Decorative Plywood.
  .4 CSA O121-08 (R2013), Douglas Fir Plywood.
  .5 CAN/CSA O141-05 (2014), Softwood Lumber.
  .6 CSA O151-09 (R2014), Canadian Softwood Plywood.
  .7 CSA O153-13 (R2017), Poplar Plywood.
.5 National Hardwood Lumber Association (NHLA)
  .1 Rules for the Measurement and Inspection of Hardwood and Cypress January 2015.
.6 National Lumber Grades Authority (NLGA)
  .1 Standard Grading Rules for Canadian Lumber 2017.
.7 Underwriters Laboratories of Canada (ULC)
  .1 CAN4-S104-10, Fire Tests of Door Assemblies.
  .2 CAN4-S105-09, Fire Door Frames.

1.4 Shop Drawings

.1 Submit shop drawings in accordance with General Requirements.
.2 Indicate details of construction, profiles, jointing, fastening and other related details.
.3 Indicate all materials, thicknesses, finishes and hardware.

1.5 Samples

.1 Submit samples in accordance with General Requirements.

1.6 Delivery, Storage, and Handling

.1 Deliver, handle, store and protect materials in accordance with General Requirements.
.2 Protect materials against dampness during and after delivery.
.3 Store materials in ventilated areas, protected from extreme changes of temperature or humidity.

## PART 2 - PRODUCTS

2.1 Lumber Material

.1 Softwood lumber: unless specified otherwise, S4S, moisture content 19% or less in accordance with following standards:
  .1 CAN/CSA O141.
  .2 NLGA Standard Grading Rules for Canadian Lumber.
  .3 AWMAC custom grade, moisture content as specified.
  .4 Interior wood that is painted is Poplar/ Pine.
.2 Machine stress-rated lumber is acceptable for all purposes.

2.2 Panel Material

.1 Douglas fir plywood (DFP): to CSA O121, standard construction; G1S, no knots or defects permitted.

2.3 Accessories

.1 Nails and staples: to CSA B111; galvanized to CAN/CSA-G164.
.2 Wood screws: to CSA B35.4 plain, type and size to suit application.
.3 Adhesive: recommended by manufacturer.
.4 Transparent finish: spray apply one coat clear sanding sealer, one coat interior gloss catalyzed lacquer and one coat interior semi-gloss catalyzed lacquer.

2.4 Location

.1 Refer to Drawings for location, details and material usage.

## PART 3 - EXECUTION

3.1 Installation

.1 Do finish carpentry to Quality Standards of the Architectural Woodwork Manufacturers Association of Canada (AWMAC), except where specified otherwise.
.2 Scribe and cut as required, fit to abutting walls, and surfaces, fit properly into recesses and to accommodate piping, columns, fixtures, outlets, or other projecting, intersecting or penetrating objects.
.3 Form joints to conceal shrinkage.
.4 Provide water resistant building paper between wood items and masonry or cementitious construction.

3.2 Construction

.1 Fastening.
  .1 Position items of finished carpentry work accurately, level, plumb, true and fasten or anchor securely.
  .2 Design and select fasteners to suit size and nature of components being joined. Use proprietary devices as recommended by manufacturer. Minimize and conceal exposed fastenings.
  .3 Set finishing nails to receive filler. Where screws are used to secure members, countersink screw in round cleanly cut hole and plug with wood plug to match material being secured.
  .4 Replace items of finish carpentry with damage to wood surfaces including hammer and other bruises.

.2 Wood Trim/ Moulding Profiles
  .1 Butt and cope internal joints of all trim to make snug, tight joint. Cut right angle joints of trims/ mouldings with mitred joints.
  .2 Fit backs of trims/ moulding snugly to walls.
  .3 Install in single lengths without splicing, unless length exceeds standard length of material. Only one splice permitted if length is exceeded. Use scarf joint if splicing is required.
.3 Panelling
  .1 Secure panelling and perimeter trim using adhesive recommended for purpose by manufacturer. Fill nail holes caused by temporary fixing with filler matching wood in colour.
  .2 Secure panelling and perimeter trim using concealed fasteners.

3.3 Schedules

.1 Trim/ Moulding Profiles:
  .1 Poplar; refer to Drawings for profiles and sizes.
.2 Panelling
  .1 G1S Douglas Fir; free from knots or defects for smooth finish.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01, General Requirements.
.2 REPORT IN WRITING TO THE WATERLOO REGION DISTRICT SCHOOL BOARD ANY DEFECTS OF SURFACES OR WORK PREPARED BY OTHER TRADES WHICH AFFECT THE QUALITY OR DIMENSIONS OF THIS CONTRACTOR'S WORK SHALL IMPLY COMPLETE ACCEPTANCE OF ALL WORK BY OTHER TRADES OR OF EXISTING ROOM CONDITIONS AND LOCATIONS.

1.2 Reference Standards

.1 Standard of finished carpentry, metalwork and cabinet work in accordance with the "Millwork Standards" of the Architectural Woodwork Manufacturers Association of Canada (AWMAC).

1.3 Qualifications

.1 The work of this trade shall be executed by a company having proven first class experience in this type of work and having adequate equipment and skilled personnel.

1.4 Work Included

.1 Provide all millwork and casework as shown on the drawings, including but not limited to the following: provide prefinished cabinets, display cases, shelving units, counters, vanities, window sills, panelling, wood ceiling systems and similar items where shown on Drawings as specified herein, and as needed for a complete and proper installation.
.2 Provision of rough hardware, including fastening devices required to secure in place items of carpentry and millwork.
.3 Supply and installation of finishing hardware for millwork by this millwork contractor section 06 40 00.
.4 Supply and installation of grilles, etc. on millwork items.
.5 Installation of all miscellaneous metals for millwork items including but not limited to vanities.
.6 Supply and installation miscellaneous trims, scribers, filler panels.
.7 Provide cutouts in the counter tops for the sinks, electrical outlets and all other necessary cutouts regarding the millwork.

1.5 Shop Drawings

.1 Shop drawings only required where not detailed by "AW" drawing. Copies of "AW" are to be marked up to indicate changes. “AW” drawings refer to WRDSB Millwork Standards drawings contained in Specifications/ Drawings.
.2 Before shop drawings and fabrication is started, take critical measurements at the site to facilitate installation, fitting of work and access required to move millwork into final location. Take such measurements prior to fabrication of the work of this Section and in ample time to avoid delays in the work.
.3 Draw Shop Drawings in related and/ or dimensional positions with sections. Scale minimum 1:10.
.4 Shop Drawings shall show fabrication details, materials, jointing, description of anchorage and hardware.
.5 Do not commence work until reviewed shop drawings have been returned as approved by Consultant and WRDSB.
.6 The drawings are to be photocopied, confirmed, to fit openings and sizes, mark up, in red, and returned for approval.

1.6 Delivery and Storage

.1 Give Painter sufficient notice so that untreated or unprimed carpentry items or materials can be primed immediately upon delivery to site.
.2 No equipment shall be delivered to the site until portion of the building in which it is to be installed is completely ready for equipment as approved by Consultant.
.3 Store finished work properly and keep under cover both in transit and at site. Finish woodwork shall not be delivered to site until concrete and masonry work has dried out.
.4 Cover all plastic laminate and prefinished top surfaces at shop with heavy Kraft Paper.
.5 Carefully protect from damage of any kind.

1.7 Related Sections

.1 Section 06 10 10 – Rough Carpentry.
.2 Section 09 21 16 – Gypsum Board Assemblies.
.3 Section 09 91 10 – Painting.
.4 Mechanical – refer to Mechanical Drawings.
.5 Electrical – refer to Electrical Drawings.

1.8 Shop Finish

.1 All cabinet work, including wood all other cabinet trims, to be shop finished by this Section and per Section 09 91 10.

1.9 Samples

.1 Samples melamine 305x305mm, plastic laminate, edging, hinges, pulls, bumpers, drawer slides, and shelf clip.
.2 Submit duplicate 300mm long samples of each type of moulding.
.3 Submit samples of construction methods and of all hardware.

1.10 Intent

.1 The intent of this Section is that casework shall be manufactured and finished at the plant, delivered to the Site and immediately installed by this Section including provision of necessary strapping, backings, bearers, rough hardware and finish hardware and miscellaneous support metals and stainless steel metal components. Touch up finish immediately prior to completion of the Work and leave in perfect condition.

1.11 Cooperation

.1 Water, drainage and air piping, faucets, hose cocks, retort rod and bases, traps, ventilation ducts, sinks, electric receptacles and wiring are supplied and installed by the Mechanical and Electrical Sections at all rooms. Coordinate the work with these trades and make provision in the construction of the fitments to accommodate this work. Methods of construction shall be such as to permit mechanical and electrical work being concealed in the fitments, cut and frame accordingly, provide removal access panels in the units or provide proper access for installation and repairs.
.2 Cabinet hardware, pilaster strips, locks, and finishing hardware will be supplied by this Section. Miscellaneous metals used in this section will be supplied and installed by miscellaneous metals contractor unless otherwise noted.
.3 Woodwork, not shop primed, will be primed and back painted as per painting section immediately upon delivery to the site. Care shall be taken that all surfaces cut after priming are brush coated with an approved primer before installation.

1.12 Maintenance

.1 Provide Owner with printed instructions for "Care and Maintenance of Plastic Laminate" and millwork finishes.

1.13 Warranty

.1 Warranty workmanship against manufacturing defects, including warpage or delamination, for a period of five (5) years from date of acceptance of the completed installation. Make good or replace work showing defects in this period, as requested, at no expense to the Owner.

## PART 2 - PRODUCTS

2.1 Materials

.1 Finishing Work: Materials used for finish work shall be sound, free from defects that would mar finished appearance, well seasoned and air dried and of good quality for intended purposes. Wood laminates pressure bonded.

.2 Plywoods:

.1 Select Plain Sliced Maple Architectural Grade 'A' No. 1 Face grade; as in compliance with C.S.A. 0115-M1982 with a minimum 5 ply plywood veneer waterproof core, laminated with waterproof adhesive. Plywood shall be good both sides except where concealed by construction. Exposed faces to be natural grade per AWMAC. Interior of doors to be classified as exposed.

.3 Melamine Faced Particleboard: to CAN3-0.188.1-M78, grade "H" particleboard sanded faces, 13mm, 16mm, 19mm, 28.6mm and 32mm thickness, faced with laminated plastic. Melamine resin impregnated cover sheet with coloured and/or patterned paper inner layer. Melamine shall be thermally fused to rigid particle board substrate. Melamine faces shall be 120 gram weight paper. Colour to be **205 Tobacco Cherry (Uniboard)**.

.1 Acceptable Material: Flakeboard, Uniboard or approved equal.

.4 Particleboard: CSA-0118-1975 Type 11, Grade R, minimum 690 K8/m3, 4.5 to 8% moisture content.

.5 Hardwood: shall be selected Hard White Maple, all shall be Architectural Grade (knots will not be accepted). It shall be selected for colours and graining when used for stain work.

.6 Wood Edging: 6mm hardwood to match plywood unless indicated otherwise (if maple, use hard white maple).

.7 Melamine Faced Particle Board Edge Banding: solid polyvinylchloride (PVC), 3mm thickness x full width of board, wood core, wood grain type or colour to match melamine face. Edging to be rigid PVC with a measured degree of hardness of "95 shore D" and thickness of "3mm (+0.15mm, -0.2mm)" with the primer side having a concave measuring 0.10 to 0.25mm.

Edging adhesive: ethylene vinylacetape thermalset adhesive with a temperature resistance of not less than 100°C; A Processing range of 190° - 200°C and natural in colour.

Edging is to be applied using only equipment designed for the application of thick PVC in strict accordance with the specifications of both the thick PVC and hot-melt adhesive manufactures. All edges and all corners of this 3mm PVC edgebanding are to be machined to a 3mm radius for all cabinet parts.

Care should be taken during application to achieve the thinnest glueline consistent with a good bond without causing skips or unspread areas. Final colour by Consultant.

.8 Plywood Concealed by Construction: Douglas Fir plywood shall be veneer core, waterproof, bonded, sanded, complying with C.S.A. 0121-M1978. Solid grade where concealed by construction.

.9 Concealed Framing Lumber: N.L.G.A.C. select eastern white pine, kiln dried to a 5% moisture content.

.10 Unexposed Plywood for Framing: Waterproof fir plywood minimum 12.7mm thickness unless indicated otherwise.

.11 Adhesive:

- .1 Waterproof synthetic resinous glue of approved general type conforming to CSA O112.
- .2 For plastic laminate - as recommended by plastic laminate manufacturer and to conform to CSA O112.
- .3 Approved waterproof type.

.12 Plastic Laminate:

- .1 Laminated Plastic for Flatwork: 1.27mm thick decorative, melamine surfaced, high pressure laminated plastic sheeting in suede finish to conform to CAN3-A172-M79 (R1996) Grade G.P., Type 1. Manufacturer shall thoroughly sand back of sheet to form a homogeneous bonding surface. Plastic laminates shall be as manufactured by Arborite, Formica, Wilsonart or Nevamar. Backing sheet 0.5mm thick, sanded one side. Products may be selected based upon manufacturer's full standard range of colours and patterns. The finish will be suede; the colour will be non-stock.
- .2 Laminated plastic for postforming work and preforming work: to CAN3-A172-M79 (R1996) Grade P.F., Type 3, 1.25mm thick, based on standard colours with suede finishes as selected by Consultant. Plastic laminates shall be as noted in 1. The colour will be non-stock.

.13 PVC edging for plastic laminate work: solid polyvinylchloride (PVC), 3mm thickness x full width of board, colour to match plastic laminate face by Canada Wood tape or approved colour equal. Edging to be rigid PVC with a measured degree of hardness of "95 shore D" and thickness of "3mm (+0.15mm, -0.2mm)" with the primer side having a concave measuring 0.10 to 0.25mm.

Edging adhesive Ethylene vinylacetape thermalset adhesive with a temperature resistance of not less than 100°C; A Processing range of 190° - 200°C and natural in colour.

Edging is to be applied using only equipment designed for the application of thick PVC in strict accordance with the specifications of both the thick PVC and hot-melt adhesive manufactures. All edges and all corners of this 3mm PVC edgebanding are to be machined to a 3mm radius for all cabinet parts.

.14 Nails and Staples: To C.S.A. Bill-1974. Use spiral threaded nails and barbed staples.

.15 Architectural Woodwork Finish: Refer to Section 09 91 10.

.16 Shelves: adjustable shelves longer than 950mm and fixed shelves without centre supports longer than 950mm to be 28.6mm thick wood veneer plywood or melamine faced particleboard as detailed. Shelves shorter than lengths specified above are to be 19mm thick wood veneer plywood core and melamine faced particleboard for alternate price items. Front edges of adjustable shelves to be edge-banded. Front edges of fixed shelves to edge banded, rear edge to be secured to cabinet back panel.

.17 Exposed Fasteners: All millwork units secured to walls shall be secured with Tapcon screws and cup washers. All specialty fasteners such as acorn head bolts shall be supplied and installed by this section. Submit samples for Consultant's approval.

.18 Countertops: to be to be solid surface on veneer core waterproof plywood or plastic laminate postformed on particleboard or veneer core plywood or as noted on the Drawings. Adhesives: to CSA 0112.5M, waterproof type. Counter tops are postformed D profile.

.19 Backer standard: to be 0.028 thick. Panels shown to have backer panel shall be balanced with 0.5mm backing sheet manufactured by the same manufacturer as the facing sheet. Core CSA O115-M1982 (R2001) (G/SO) or CSA O121-17 Grade "B" or CSA CAN3-O188.1-M78, Grade R.

2.2 Fabrication

.1 General

.1 Fitments shall be machined, assembled in mill where possible and delivered to job in units. Construct in accordance with details using first class cabinet construction with joints dowelled, glued and properly fastened. Machine all surfaces of finished woodwork to an even smooth surface; fit all joints and miters accurately. Frame materials with tight joints held in place. Conceal joints and connections where possible. Joints made on site shall be equal in quality of work to joints made in the shop.

.2 Check job dimensions and conditions and notify the Consultant in writing of unacceptable conditions. Design construction methods for expansion. Do not proceed until remedial instructions are received.

.3 Deliver work to the job ready for installation. Leave ample allowance for fitting and scribing on the job. Shop assemble work for delivery to site in size easily handled and to ensure passage through building openings, Design units to fit together if site assembly is required.

.4 Fabricate work square and to the required lines. Recess and conceal fasteners and anchor heads. Fill with matching wood plugs.

.5 Comply with glue manufacturer's recommendations for lumber moisture content, glue life, pot life, working life, mixing spreading, assembly time, time under pressure and ambient temperature.

.6 The interior of counters, cupboards, shelving units, desks, shall be considered "exposed". Finish all exposed edges with 3mm thick PVC edge banding material, applied by an Edge-Bander using Hot Melt adhesive. Colour to match the melamine. Radius all exposed edges and corners (PVC edging or Wood edging). Counter tops which are to receive plastic laminate coverings may be 3/4" (19mm) thick sanded veneer core plywood where specified. Particle core shall be used for shelving and gables, countertops specifically called for as solid material or as otherwise specified. Include all filler strips and to match the face colour.

.7 Refer to Drawings and Architectural Detail Sheets for location, details, number of units required and location of fittings.

.8 Interior fitments shall be complete in every respect with special fittings required and hardware.

.9 Provide exposed end grain of solid members and edges of exposed plywood with matching solid hardwood edging at least 6mm thick and thicker where specified. At melamine faced particle board provide 3mm P.V.C. edging complete with 3 mm radius on all exposed edges and corners as per millwork sections. Edging to melamine faced particle board shall be applied with an Edge-Bander using hot melt adhesive.

.10 Make all necessary cut-outs in the furniture for sinks, gas cocks, appliances, and electrical switch and outlet boxes and pre-drill all mounting holes for faucets, fittings and outlet boxes. Refer to electrical and mechanical drawings and specifications.

.11 Provide and install pipe covers, scribing pieces, top, bottom and/or closures and filler panels where necessary, including wherever units require furring out or blocking to existing conduits, pipes, etc.

.12 Service cover panels to be provided at all kneehole drawer units, kneehole front rails and knee drawer table assemblies. End closing panels to be provided at all exposed ends of service strips and island/peninsula assemblies. Front filler panels to be provided where called for on Drawings and as required by field conditions.

.13 Telephone and electrical receptacles and wiring are specified under Electrical Division. Coordinate work of this trade, make provision to accommodate this work and cut tops for and provide wood bearers for support.

.14 Cooperate with others engaged in work on the building to the end that proper unity of action will assure the orderly progress of the work. Do necessary boxing and protecting of sills, jambs, and the like. Construct scaffold, ramps, and other temporary staging necessary.

.15 Provide 19mm plywood adjustable or fixed shelving where detailed. Maximum unsupported span for shelving shall be 900mm. Fixed shelves shall be dowelled into gables and divisions. Where shelves are set on clips only, gables shall be drilled 32mm o.c. for total height of gables.

.16 The plywood used in interior fitments throughout regardless of whether for paint or stain finish, shall have exposed edges edged with solid strips 6mm wide, unless noted otherwise by full thickness of plywood. No exposed edges of plywood will be permitted. Strips shall be glued and accurately fixed to edges. Adjustable shelves shall have strips applied to front edge.

.17 Exposed framing members and trim shall be solid hard maple.

.18 Plastic laminate coverings to fitments, cupboards and counters shall be in colours selected by Consultant and applied in accordance with manufacturer's directions. Where plastic laminate occurs, exposed edges and edges around cut-outs such as sinks shall be edged in the same material. Seal remaining exposed edges of surfaces with heavy Kraft paper prior to shipment. Paper shall not be removed until final cleaning. When cutting holes in plastic laminate work, corners shall be rounded and filed smooth.

.19 When cutting holes in plastic laminate work, corners shall be rounded and filed smooth.

.20 Protection erected by this trade shall be removed, damage to this work and adjoining work due to the lack or failure of such protection, made good and debris, surplus materials, plant and equipment removed and premises and the whole left clean and tidy to Consultant's satisfaction.

.21 Melamine on all surfaces unless noted otherwise.

.22 Fabricate all plywood and melamine faced particle board backs, gables and bottoms of millwork units together by means of 8mm x 25mm hardwood dowels or with hardwood biscuits. All backs to be 12.7mm stock. Dowel all panel cabinet components using 5mm x 25mm hardwood dowels or biscuits at maximum 100mm o.c. All drawer bottoms and backs are 12.7mm stock or greater. All exposed edges on all melamine faced particle board units to be edged with solid 3mm PVC C/W 3mm radius edges and corners including drawer parts and with 6mm matching hardwood edge banding at Maple and Birch units. Kick material for normal application shall be 19mm waterproof spruce/fir plywood to be used. Resilient base by Section 09 65 16 and porcelain tile base by Section 09 30 15.

.2 Counters, Cupboards, Shelving etc.

.1 Adjustable shelves c/w clips and drilled holes at 32mm centers. Base cabinet's c/w 1 shelf, wall cabinet's c/w 2 shelves, and tall cabinet's c/w 5 shelves, the centre shelf is fixed unless Drawings show otherwise. Factory install all hardware firmly into position for long life under hard use. Install 2 hinges on doors up to 1 metre in height, 3 hinges to 1.5 metre in height and 4 hinges for doors greater than 1.5 metres in height or shown otherwise.

.2 Frame as detailed with 19mm thick, or as noted otherwise, plywood gables, tops and bottoms. House intermediate dividers and plywood backs, into gables and top and bottom shelves, for all fitments. Plywood shall be birch or oak as called for in this Section unless otherwise indicated. Cabinet backs to be 12.7mm plywood.

.3 Where melamine specified: horizontal and vertical gables; and shelving to be 19mm particle core with melamine, good 2 sides. Cabinet backs to be 13mm particle core with melamine, good 1 side.

.4 Fabricate cabinet carcass, the 32-millimeter system from 19mm thick melamine composite panel using flush frameless construction and exposed edges, to AWMAC Standard " Custom grade" c/w 3mm thick PVC edge banding on exposed edges. All exposed edge banding c/w 3mm radiuses edges and corners. Do not exceed 800mm a maximum width of cabinet without a divider or specified otherwise.
Carcass construction- Backs 16mm, bottoms, rails, doors, drawer fronts 19mm of melamine composite panels, assembled with glued hardwood dowels 8x30mm or wafers.

.5 Cut countertops for sinks and provide bearers. Provide backsplash at back of sink for entire length of the unit and at return ends where walls or other vertical surface occur within 600mm of sink or other wet location.

.6 Countertop and backsplash will be plastic laminate unless noted otherwise.

.7 Provide removable plywood access panels, screwed in place, where necessary for access to concealed wiring.

.8 Fit trim and scribe moulds to fitments as shown and as required to hide voids at walls, partitions and ceilings.

.9 Provide cut-outs for inserts, outlets, grilles, appliances, etc. occurring in fitments.

.10 Bottom of units blocked up to form a 100mm high x 75mm deep toe space and fabricated from 19mm waterproof veneer core plywood of fir or spruce

.11 Fit fillers between fitments, of same material as fitments, where necessary to fill voids between fitments and walls.

.12 Lighting fixtures and outlets to be supplied and installed under Division 26.

.13 Provide cutouts and access panels where required for Divisions 22-23 and covers over ductwork (stove exhaust fans) or piping that run exposed above counters and upper shelves.

.14 Provide extended top, bottom, and exposed gables where furring out of upper cupboards is required due to pipes, conduits, and the like behind to provide a flush face at walls.

.15 Plastic Laminate Work:

.1 Comply with CAN3-A172-M79, Appendix "A".

.2 Veneer laminated plastic to core material in accordance with adhesive manufacturer's instructions. Ensure core and laminate profiles coincide to provide continuous support and bond over entire surface. Provide cores of not less than 19mm nominal thickness solid face Douglas Fir.

.3 Form shaped profiles and bends as indicated, using postforming grade laminate to laminate manufacturer's instructions.

.4 Use straight self-edging laminate strip 1.6mm thick for flatwork to cover exposed edge of core material. Chamfer exposed edges uniformly at approximately 20°. Do not mitre laminate edges. Curved self edging shall be postformed material or bending grade.

.5 Apply laminate backing sheet to reverse side of core of plastic laminate work where specified. Provide backing sheet of sufficient thickness to compensate for stresses caused by the facing sheet.

.6 Locate joints where indicated, where not indicated at approximately 2440mm or 3660mm centres also include joints at corners, and changes in superficial area.

.7 Accurately fit decorative laminate together to provide tight, flush, butt joints. Joints in cored panels shall be made with 6mm blind splines and draw bolts, one draw bolt for widths up to 150mm two or more draw bolts at maximum 450mm o.c. for widths exceeding 150mm.

.8 Keep joints min. 600mm from sink cutouts.

.9 Seal the core at joints and exposed edges with sealer.

.10 Counter tops apply Tremco Tremsil 200 silicone sealant at junction of plastic laminate or phenolic tops when tops are joined. All joints to be over a gable or supported otherwise.

.11 Use draw bolts in counter top joints.
.12 Apply a small bead of mildew-resistant paintable silicone sealant at junction of plastic laminate counter back and adjacent wall finish.

## PART 3 - EXECUTION

3.1 Workmanship

.1 Fabricate and install work in accordance with the best practice. Finished work shall be free from drag, feathers, slivers or roughness of any kind. Remove machine marks by sanding. Give finished work smooth surfaces, ready for painting or varnish application.
.2 Mortise and tenon joints shall be glued and pinned. All panels shall be secured together with specified glued and dowelled method. Glue blind screw all fabricated component work unless otherwise specified. Set surface nails and plug countersunk screws with matching wood plugs. Use screws with cap washers where units with doors are secured to walls behind.
.3 Finished woodwork shall be free from bruises, blemishes, mineral marks, knots, shakes and other defects.
.4 All metal items such as grilles, tracks, supports, legs, brackets, etc. supplied by other trades shall be built into fitments, panelling, wood doors, etc., in strict accordance with directions of trades supplying such.
.5 Furnish rough hardware, nails, expansion shields, screws, brackets and incidentals required to assemble and install the fitments in their proper locations.
.6 Fit small scribe moulds or fillers of same materials as fitment to hide or fill voids at walls, partitions ceilings, furrings, exposed tops of millwork units, at base locations where rubber base occurs.
.7 Plywood Edging: all exposed 19mm plywood edges shall be covered with glued on 6mm thick hardwood strips.

3.2 Millwork Workmanship

.1 Fitments shall have joints dowelled and all joints shall be glued and nailed or screwed. All cabinet bases shall be of 19mm plywood, blocked at 900mm O.C. maximum and at corners.
.2 Counter tops shall have splash backs where sinks occur.
.3 Shelving shall be 19mm plywood, adjustable or fixed as detailed. Maximum unsupported span for shelving shall be 900mm. Adjustable shelves shall be set on angle clips or metal pilaster strips. Loose shelves shall have PVC edges on front edge.
.4 Laminates shall be pressure bonded to back-up board. Counter tops shall be self edged and have plastic laminate covered back splash. Back-up material for counter tops shall be particle core unless otherwise noted.
.5 Plastic laminate surface shall be level, without bubbles and core ghosting. Core edges in counter cut outs shall be sealed with asphalt compound. All exposed plastic edges shall be matched and sanded.

3.3 Installation

.1 Commencement of work implies total acceptance of surface and site conditions.
.2 Set and secure all materials and components in place, rigid plumb and square.
.3 Provide all furring strips and strapping required fixing millwork and casework to walls, etc.
.4 Provide all filler strips to seal any openings or joints at adjacent surfaces.
.5 After installation, fit and adjust operating hardware to align all doors and drawers.
.6 Clean up as the work proceeds and upon completion remove all rubbish and surplus materials resulting from the foregoing work.

.7 Plumbing
  .1 Sink installation:
    .1 Cut hole, clean the counter top with alcohol.
    .2 Use Tremco, Tremsil #200 a silicone sealant that gives protection against fungi and bacteria.
    .3 Install Tremsil around the cuts, and then place a bead of Tremsil on the top before installing the sink.
    .4 Millwork Contractor to ensure the Plumber installs as specified.

.8 Installation and assembly work on the job shall be executed by skilled forces under supervision of a competent joinery foreman.

.9 Furnish rough hardware, nails, expansion shields, screws, brackets and incidentals required to assemble and install fitments in proper locations. Units shall be adequately fastened and secured in place with concealed fixings wherever possible. Include grounds and furring where required.

.10 Fitments shall be installed level, plumb and true and complete in all respects.

.11 Provide smooth surfaces with fastenings sunk and filled over to receive stain and sealer.

.12 Use draw bolts in countertop joints.

.13 At junction of plastic laminate counter, back splash and adjacent wall finish, apply small bead of silicone sealant as per Section 07 92 10 in colour as selected by Consultant.

.14 Apply water resistant building paper over wood framing members in contact with masonry or cementitious construction.

3.4 Resilient Base

.1 Supply and installation of resilient base at millwork units as indicated is by Section 09 65 16 for rubber base locations.

END OF SECTION

## PART 1 - GENERAL

1.1 General Requirements

.1 Conform to Division 01 - General Requirements.

1.2 Work Included in Section

.1 To provide crystalline waterproofing to certain works including but not limited to the following:
- .1 Areaways.
- .2 At other location indicated on drawings or schedules.

1.3 Submittals

.1 Inspection Reports:
- .1 Submit inspection reports as the work progresses. Upon completion provide Consultant with duplicate certificates of acceptance issued by the waterproofing inspection company.

.2 Extended Warranty:
- .1 Submit a warranty covering the repair or replacement of defective work for a period of four (4) years from the expiration of the one-year warranty under the General Conditions.
- .2 Defective work shall include, but not be limited to leaking, crazing, cracking of material due to other than structural cracking or spalling.

1.4 Product Storage

.1 Store packaged materials in dry enclosed area, off the ground, in original undamaged containers with manufacturer's labels and seals intact.

.2 Prevent damage to materials during handling and storage.

## PART 2 - PRODUCTS

2.1 Materials

.1 Waterproofing Material:
- .1 A cement-based compound, free from calcium chloride and iron oxide, which waterproofs by crystalline growth through the capillary voids in the concrete substrate, "Aquafin" manufactured by Aquafin Building Product Systems, "Xypex" distributed by Peninsula Distributors and Supply, "Permaquick Super 200" distributed by Permaquick (Canada) Ltd., "Ultraseal" manufactured by Ultraseal Construction Products Ltd., W.R. Meadows "Cem-Kote CW Plus", Krystol T1 and T2 manufactured by Kryton International Inc., or other approved manufacturer.

.2 Water:
- .1 Free from matter deleterious to the waterproofing material.

## PART 3 - EXECUTION

3.1 Examination

.1 Before commencing work, examine all areas and report in writing any conditions which would adversely affect waterproofing. Commencement of work shall imply acceptance for application.

3.2 Mixing of Waterproofing

.1 Slurry Consistency
- .1 Mix materials in accordance with manufacturer's printed directions. Use water free from matter deleterious to the materials.
- .2 Prepare only as much slurry mixture as can be applied within 20-30 minutes. Do not add more water when mixture starts to thicken. Stir mixture frequently.

.2 Mortar Consistency
- .1 Mix materials in accordance with manufacturer's printed directions.
- .2 Prepare only as much mortar as can be applied within 10-15 minutes.

3.3 Surface Preparation

.1 General
- .1 Prepare surfaces in accordance with manufacturer's printed directions.
- .2 Surfaces and surrounding air temperature shall be at least 5°C for a minimum period of 72 hours before, during and after application.
- .3 Thoroughly clean all surfaces prior to application using an industrial type vacuum cleaner.
- .4 Prepare smooth surfaces and/or surfaces containing release agents, by steam cleaning, chemical etching or high pressure water blasting to achieve open capillary (fine sane paper) texture.
- .5 Produce a test area for manufacturer's review prior to full application.
- .6 Ensure concrete has waterproofing manufacturer's recommended moisture content prior to application.
- .7 Clean out all shrinkage cracks, tie holes, reveals, and construction joints and prepare to receive fill with mortar mix of the waterproofing material.
- .8 Use same mortar to create coves where horizontal and vertical surfaces meet and on inside corners and for grouting in insets and other protrusions.
- .9 Rout out all construction joints and visible cracks exceeding 0.5mm in size to minimum 19mm in depth. Remove all laitance (cement scum) dirt, dust and thoroughly rinse with water all concrete slab surfaces. Remove all free laying water the day prior to the waterproofing material application. Concrete surfaces shall have damp appearance only at the time the slurry coating is applied.
- .10 Surfaces shall have an open capillary system to assure permanent bonding of application.
- .11 Remove all from scale, oil, form release agents and any other foreign materials likely to affect the bond, penetration and performance of the waterproofing.
- .12 Leave form tie holes approximately 25mm back of surface.
- .13 Rout out honeycombed pockets and faulty construction joints to sound concrete.

3.4 Application

.1 Apply waterproofing material to concrete as soon as possible after formwork stripping.
.2 Apply waterproofing by stiff masonry brush, by trowel, or by funnel pistol sprayer. Apply at the rate of 1 kg/m². For floors broadcast dry into concrete and float at time of initial set of concrete. Coordinate timing with Section 03 30 00.
.3 Apply waterproofing material in mortar consistency to all shrinkage cracks, construction joints and reveals.
.4 Where no other protection to the waterproofing application is to be applied, apply wearing coat material at the rate of 0.5 kg/m².
.5 Allow each successive coating to reach an initial set before re-coating.
.6 Extend waterproofing a minimum of 300mm on both sides of joints.
.7 Carry waterproofing up to pipes, standards, and other items projecting through the substrate and cut back to receive sealant under Section 07 92 10.
.8 Cure applications as directed by the material manufacturer.
.9 Maintain work above 3°C until 24 hours minimum after completion. Ventilate and protect work from inclement weather and direct sunlight while curing. Moisten work during hot weather for 3 days after completion.

3.5 Protection and Cleaning

.1 When temperatures fall below freezing, cover treated surfaces with tarpaulins, etc., and maintain surface temperature above 5°C for a minimum period of two days after the completion of the application.
.2 Moisture cure all treated surfaces for a minimum period of two (2) days, starting with fine water fog spraying the day following completion of the application.
.3 During extreme hot weather, if necessary, apply light water fog spray to the freshly applied slurry application in order to prevent dehydration of the waterproof coating.

3.6 Field Quality Control

.1 Supervise the work of other Sections where such is associated with the waterproofing including the placement, finishing, and curing of the concrete substrate. Bear full responsibility for damage caused to the waterproofing by these operations.
.2 Ensure that the Waterproofing Products Manufacturer carries out full inspections during the application of products including repair work.
.3 Rout out all visible cracks exceeding 0.5mm in size to a minimum 12mm depth and width which occur in concrete slab after application of crystalline. Clean out routed channels and fill with a mortar mix of waterproofing material.
.4 Refer to Section 01 45 00 for information regarding the procedures to be followed for testing.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Section 03 30 00 – Cast-in-Place Concrete.
.2 Section 07 26 00 – Vapour Retarders.
.3 Section 07 51 12 – Built-Up Asphalt Roofing.
.4 Section 31 23 10 – Excavating, Backfilling and Rough Grading.

1.3 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM E96/ E96M -16, Test Methods for Water Vapor Transmission of Materials.
  .2 ASTM C726-17, Standard Specification for Mineral Fiber Roof Insulation Board.
.2 Canadian Gas Association (CGA)
  .1 CAN/CGA-B149.1-15, Natural Gas Installation Code.
  .2 CAN/CGA-B149.2-15, Propane Installation Code.
.3 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB 51.11-92, Rigid Insulation.
.4 Underwriters Laboratories of Canada (ULC)
  .1 CAN/ULC-S701-11, Thermal Insulation, Polystyrene, Boards and Pipe Coverings.
  .2 CAN/ULC-S702-14, Thermal Insulation, Mineral Fibre, for Buildings.

## PART 2 - PRODUCTS

2.1 Insulation

.1 Rigid cellular polystyrene; below grade insulation at vertical and horizontal underslab conditions: to CAN/ULC-S701-11, type 4, compressive strength 210 kPa, thickness 50mm and 75mm, size 2440mm x 610mm, shiplapped edge.
  .1 Acceptable material:
    .1 Styrofoam Brand XPS by Dupont.
    .2 Foamular NGX C-300 by Owens Corning Canada Inc.
.2 Rigid cellular polystytrene; cavity wall insulation: to CAN/ULC-S701-05, type 3:
  .1 Acceptable material
    .1 Styrofoam Brand CavityMate Plus XPS Ultra by Dupont.
    .2 Foamular NGX C-200 by Owens Corning Canada Inc.
.3 Refer to Section 07 51 13 – Built-Up Asphalt Roofing for roof insulation product information.

2.2 Adhesive

.1 Adhesive: as recommended by manufacturer for fully adhered application.

## PART 3 - EXECUTION

3.1 General

.1 Install materials in accordance with manufacturer's installation instructions.

3.2 Examination

.1 Examine substrates and immediately inform Consultant in writing of defects.
.2 Take measurements of the Place of Work to ensure that work is fabricated to fit structure, surrounding construction, around obstructions and projections in place, or as indicated; and to suit locations of services.
.3 Verify that backup construction is aligned for proper installation of Work before commencing erection.

3.3 Installation - General

.1 Surfaces to receive insulation shall be dry and free of dew, frost, voids, loose material, oil, grease, asphalt curing compounds and other matter detrimental to bond of adhesive. Adhesive shall be compatible with all substrate materials.
.2 Apply adhesives and install insulation in accordance with manufacturer's printed recommendations. Apply at rate as required to prevent displacement of insulation boards during construction operations.
.3 Butt joints tightly and offset vertical and horizontal joints in multi-layer applications to form an unbroken thermal envelope. Use only insulation boards free from chipped or broken edges. Use largest possible dimensions to reduce number of joints.
.4 Apply insulation to ensure total and complete coverage of surfaces indicated to be insulated, and in direct contact with such surfaces. Unless otherwise specified, apply insulation in single layer of thickness indicated.
.5 Ensure integrity and continuity of insulation at juncture with different types of materials and seal in an acceptable manner.
.6 Do not enclose insulation until it has been reviewed and accepted by Consultant.

3.4 Above Grade Insulation

.1 Secure rigid insulation boards to substrate at rate of 6 each per 610mm x 1220mm board minimum, with corrosion resistant mechanical fasteners complete with 25mm plastic washers.
.2 Apply rigid insulation at through-wall flashings as indicated on Drawings and as follows:
  .1 Over through-wall flashings at grade, prior to application of sprayed foam insulation.
  .2 Under elevated through-wall flashings, full thickness of cavity.
  .3 Over elevated through-wall flashings, prior to application of sprayed foam insulation.

3.3 Perimeter Foundation Insulation

.1 Interior application: extend boards 1220mm vertically below bottom of finish floor slab as indicated, installed on inside face of perimeter foundation walls.
.2 Under slab application (typical): extend boards 600mm in from perimeter foundation wall as indicated on Drawings. Lay boards on level compacted fill.
.3 Backfill immediately to retain panels in place and to protect insulation boards from exposure to sunlight.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 References

.1 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-51.34-M86, Vapour Barrier, Polyethylene Sheet, for Use in Building Construction.
.2 Canadian Standards Association (CSA)
  .1 CAN/CSA-ISO 9001, Requirements for Quality Assurance, Parts 1, 2 and 3.

1.3 Submittals

.1 Submit proof of manufacturer's CCMC Listing and listing number to Consultant.
.2 Manufacturer's Instructions: Provide to indicate special handling criteria, installation sequence, and cleaning procedures.

1.4 Product Data

.1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit WHMIS MSDS - Material Safety Data Sheets in accordance with Section 01 33 00 - Submittal Procedures.
.3 Submit product data sheets for sheet vapour retarders. Include:
  .1 Product characteristics.
  .2 Performance criteria.
  .3 Limitations.

1.5 Mock-Ups

.1 Submit mock-ups in accordance with Section 01 33 00 – Submittal Procedures.
.2 Construct mock-up of sheet vapour barrier installation including one lap joint, one inside corner and at one electrical box. Mock-up may be part of finished work.
.3 Allow 24 hours for inspection of mock-up by Consultant before proceeding with vapour barrier work.

## PART 2 - PRODUCTS

2.1 Sheet Vapour Barrier

.1 Polyethylene film: to CAN/CGSB-51.34, 0.15mm thick, except under slabs on grade, as Specified under Section 03 30 00.

2.2 Accessories

.1 Joint sealing tape: air resistant pressure sensitive adhesive tape, type recommended by vapour barrier manufacturer, 50mm wide for lap joints and perimeter seals, 25mm wide elsewhere.

.2 Sealant: To Section 07 92 10 - Joint Sealing.
.3 Staples: minimum 6mm leg.
.4 Moulded box vapour barrier: factory-moulded polyethylene box for use with recessed electric switch and outlet device boxes.

## PART 3 - EXECUTION

3.1 Installation

.1 Ensure services are installed and inspected prior to installation of retarder.
.2 Install sheet vapour retarder on warm side of exterior wall and ceiling assemblies prior to installation of gypsum board to form continuous retarder.
.3 Use sheets of largest practical size to minimize joints.
.4 Inspect for continuity. Repair punctures and tears with sealing tape before work is concealed.

3.2 Exterior Surface Openings

.1 Cut sheet vapour retarder to form openings and ensure material is lapped and sealed to frame.

3.3 Perimeter Seals

.1 Seal perimeter of sheet vapour barrier as follows:
  .1 Apply continuous bead of sealant to substrate at perimeter of sheets.
  .2 Lap sheet over sealant and press into sealant bead.
  .3 Install staples through lapped sheets at sealant bead into wood substrate.
  .4 Ensure that no gaps exist in sealant bead. Smooth out folds and ripples occurring in sheet over sealant.

3.4 Lap Joint Seals

.1 Seal lap joints of sheet vapour barrier as follows:
  .1 Attach first sheet to substrate.
  .2 Apply continuous bead of sealant over solid backing at joint.
  .3 Lap adjoining sheet minimum 150mm and press into sealant bead.
  .4 Install staples through lapped sheets at sealant bead into wood substrate.
  .5 Ensure that no gaps exist in sealant bead. Smooth out folds and ripples occurring in sheet over sealant.

3.5 Electrical Boxes

.1 Seal electrical switch and outlet device boxes that penetrate vapour barrier as follows:
  .1 Install moulded box vapour barrier.
  .2 Apply sealant to seal edges of flange to main vapour barrier and seal wiring penetrations through box cover.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Section Includes

.1 Materials and installation methods providing primary air/ vapour barrier materials and assemblies.
.2 Air/ vapour barrier materials to provide continuous seal between components of building envelope and building penetrations.

1.3 Related Sections

.1 Section 07 21 13 – Board Insulation.
.2 Section 07 26 00 – Vapour Retarders
.3 Section 07 51 13 – Built-Up Asphalt Roofing.
.4 Section 07 92 10 – Joint Sealing.
.5 Section 09 21 16 – Gypsum Board Assemblies.

1.4 References

.1 Canadian Construction Documents Committee
  .1 CCDC 2 - Stipulated Price Contract.
.2 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-19.13M-M87, Sealing Compound, One Component, Elastomeric Chemical Curing.
  .2 CAN/CGSB-19.18M-M87, Sealing Compound, One Component, Silicone Base Solvent Curing.
  .3 CAN/CGSB-19.24M-M90, Multi-Component, Chemical Curing Sealing Compound.
  .4 CGSB 19-GP-14M-12, Sealing Compound, One Component, Butyl-Polyisobutylene Polymer Base, Solvent Curing.
.3 NBCC 2015; Part 5 - Environmental Separation
.4 Sealant and Waterproofer's Institute - Sealant and Caulking Guide Specification.

1.5 Submittals

.1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
  .1 Provide drawings of special joint conditions.
.2 Submit manufacturer's product data sheets in accordance with Section 01 33 00 - Submittal Procedures.
.3 Submit manufacturer's installation instructions in accordance with Section 01 33 00 - Submittal Procedures.

1.6 Quality Assurance

.1 Perform Work in accordance with Sealant and Waterproofer's Institute - Sealant and Caulking Guide Specification requirements for materials and installation.
.2 Perform Work in accordance with National Air Barrier Association - Professional Contractor Quality Assurance Program and requirements for materials and installation.
.3 Maintain one copy of documents on site.

1.7 Qualifications

.1 Applicator: Company specializing in performing work of this Section with experience in the installation of air/vapour barrier systems. Completed installation must be approved by the material manufacturer.

1.8 Mock-Up

.1 Construct typical exterior wall panel, 5m long by 5m wide, incorporating window, frame and sill, insulation, building corner condition, junction with roof system; illustrating materials interface and seals.
.2 Locate where directed.
.3 Mock-up may remain as part of the Work.
.4 Allow 24 hours for inspection of mock-up by Consultant before proceeding with air/vapour barrier Work.

1.9 Delivery, Storage and Handling

.1 Deliver, store and handle materials in accordance with Section 01 61 00 - Basic Product Requirements.
.2 Deliver, store and handle materials in accordance with manufacturer's written instructions.
.3 Clean spills and leave area as it was prior to spill.

1.10 Project Environmental Requirements

.1 Maintain temperature and humidity recommended by materials manufactures before, during and after installation.

1.11 Sequencing

.1 Sequence work to permit installation of materials in conjunction with related materials and seals.
.2 Schedule installation of air barriers to coincide with the application of insulation as closely as possible. Avoid leaving air barriers exposed for long periods of time.

1.12 Warranty

.1 Provide a three year warranty under provisions of Section 01 78 00 - Closeout Submittals.
.2 Warranty: Include coverage of installed sealant and sheet materials which fail to achieve air tight and watertight seal, exhibit loss of adhesion or cohesion, or do not cure.

## PART 2 - PRODUCTS

2.1 Membrane Air Barrier

.1 Sheet membrane: 40 mil self-adhering membrane air barrier consisting of SBS rubberized asphalt compound cross laminated to a polyethylene film.
  .1 When air and/or surface temperature is above 0°C; "Blueskin SA" by Bakor, "Sealtight Air-Shield" by W.R. Meadows of Canada, "PERM-A-BARRIER" by Grace Construction Products and "Sopraseal Stick 1100" by Soprema are acceptable products.

.2 When air and/or surface temperature drops below 0°C use low temperature products, "Blueskin SA LT" by Bakor, "PERM-A-BARRIER Low Temperature Membrane" by Grace Construction Products or "Sopraseal Stick 1100 Winter Grade" by Soprema.

.3 Install in widths to suit wall condition and to minimize joints.

.2 Lap adhesive; single component rubberized mastic as recommended by manufacturer.

.3 Primer; as recommended by manufacturer.

2.2 Sealants

.1 Sealants in accordance with Section 07 92 10 - Joint Sealing.

2.3 Accessories

.1 Thinner and cleaner for Sheet Seal: As recommended by sheet material manufacturer.

## PART 3 - EXECUTION

3.1 Examination

.1 Verify that surfaces and conditions are ready to accept the Work of this Section.

.2 Ensure all surfaces are clean, dry, sound, smooth, continuous and comply with air barrier manufacturer's requirements.

.3 Report any unsatisfactory conditions to the Consultant in writing.

.4 Do not start work until deficiencies have been corrected. Commencement of Work implies acceptance of conditions.

3.2 Preparation

.1 Remove loose or foreign matter which might impair adhesion of materials.

.2 Ensure all substrates are clean of oil or excess dust; all masonry joints struck flush, and open joints filled; and all concrete surfaces free of large voids, spalled areas or sharp protrusions.

.3 Ensure all substrates are free of surface moisture prior to application of self-adhesive membrane and primer.

.4 Ensure metal closures are free of sharp edges and burrs.

.5 Fill voids in masonry substrate smaller than 6mm with a trowel application of liquid air barrier. Voids larger than 6mm to be covered by sheet seal.

.6 Prime substrate surfaces to receive sheet seal in accordance with manufacturer's instructions.

3.3 Membrane Air Barrier Installation

.1 Install materials in accordance with manufacturer's instructions. Ensure flashing materials are consistent with manufacturer’s recommendations for temperature range expected during installation.

.2 Do not install sheet membrane air barrier materials when air and/or surface temperatures drop below -10°C.

.3 Install sheet membrane air barriers only in dry, fair weather when there is no threat of precipitation.

.4 Prime all surfaces to receive membrane air barriers just prior to application of membrane in strict accordance with manufacturers instructions. Reprime surfaces if contaminated with dust.

.5 Secure sheet seal to masonry and concrete materials. Ensure that all primed surface receive membrane in same day. Lap joints 50mm minimum and seal with mastic. Position lap seal over firm bearing.

.6 Press membrane firmly into place by means of a hand roller with sufficient pressure to ensure continuous and intimate contact with substrate. Take care to avoid blisters, wrinkles, or folds in membrane.

.7 Apply sheet seal over exterior surfaces/voids, lapping masonry by a minimum of 100mm.

.8 Apply sheet seals over wall infill areas.

.9 Install sheet seal around all window, door openings, canopies/ overhangs and mechanical and electrical openings and other protrusions or wall penetrations in masonry walls.

.10 Install sheet seal at all parapet details to bridge roofing air barrier and exterior wall air barrier.

.11 Install sheet seal to bridge over all exposed steel in exterior masonry walls.

3.4 Protection of Work

.1 Protect finished Work in accordance with Section 01 61 00 - Basic Product Requirements.

.2 Do not permit adjacent work to damage work of this Section.

.3 Ensure finished Work is protected from climatic conditions.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Section 07 21 13 – Board Insulation.
.2 Section 07 27 10 – Air Barriers.
.3 Section 07 51 12 – Built-Up Asphalt Roofing.
.4 Section 07 62 00 – Sheet Metal Flashing and Trim.
.5 Section 07 92 10 – Joint Sealing.
.6 Section 09 21 16 – Gypsum Board Assemblies.

1.3 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM A446/ A446 - 93, Specification for Steel Sheet, Zinc-Coated (Galvanized) by the Hot-Dip Process, General Requirements.
  .2 ASTM A525 - 93, Specification for Steel Sheet Zinc Coated (Galvanized) by the Hot Dipped Process, General Requirements.
  .3 ASTM A780/ A780M – 09 (2015), Standard Practice for Repair of Damaged Hot-Dip Coatings.
.2 Canadian General Standards Board (CGSB)
  .1 CGSB Specification 19-GP-5M, Sealing Compound, One Component, Acrylic Base, Solvent Curing.
  .2 CAN/CGSB-19.24-M90, Sealing Compound, Multi-Component, Chemical CurinG.
.3 Canadian Standards Association (CSA)
  .1 CSA Standard G 164-M92 (R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.
  .2 CAN/CSA-S136-16, Cold Formed Steel Structural Members.
.4 Meet specified requirements of CAN/CSA-S136-M89, Cold Formed Steel Structural Members and requirements of applicable jurisdictional authorities for each preformed metal system.
.5 Requirements specified in this Section are intended to modify, supplement, or clarify specifications contained in CAN/CSA-S136-16.
.6 Recommendations contained in Standard Specifications and Technical Bulletins of the Canadian Sheet Steel Building Institute for materials and performance of system will establish minimum standards for work not specified in CAN/CSA-S136-16, by jurisdictional authorities, or in this Section.

1.4 Quality Assurance

.1 Mock-Up
  .1 Construct a 1200mm x 1200mm mock-up of total preformed metal siding system.
  .2 Include all components and examples of all mitred corners.
  .3 Allow 24 hours for inspection of mock-up by Consultant before proceeding with preformed metal siding work.

1.5 Samples

.1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit duplicate 300mm 300mm samples of siding material, of colour and profile specified.

1.6 Shop Drawings

.1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
.2 Indicate dimensions, profiles, attachment methods, schedule of wall elevations, trim and closure pieces, and related work.

1.7 Delivery, Storage and Handling

.1 Package materials to protect finished surfaces of sliding from staining and marring.
.2 Store materials flat at site under protection to prevent staining from the ground or from collection of water on material, or both; and secured against wind damage.
.3 Store insulation and adhesives in dry areas, heated as required to prevent damage to adhesives.

1.8 Warranty

.1 Extended Warranty
.1 Warranty contained in GC 12.3 is, with respect to Section 07 46 13, extended from two (2) years to five (5) years. Without restricting generality of warranty, defects shall include leaking, failure to stay in place under expansion, lifting, deformation, deterioration, etc.
.2 Contractor hereby warrants that system is suitable for use in this type of installation.

## PART 2 - PRODUCTS

2.1 Siding System

.1 Siding system shall be one system, applied to vertical surfaces.
.2 System shall consist of exterior preformed metal skin on galvanized framing and shall include all flashings, trims and closures.

2.2 Materials

.1 Metals
.1 Steel: to meet specified requirements of ASTM A446, Grade A.
.2 Galvanizing
.1 Zinc Coated Sheet: To meet specified requirements of ASTM Specification A525, zinc coating designation Z275.
.2 Accessories and Hardware: Zinc coating to meet specified requirements of CSA G 164, including Appendix A.
.2 Finishes
.1 Precoated Metal: Two coats of acrylic enamel, each baked, applied by a continuous sheet steel coating plant.
.1 WeatherX™ coating system, as provided with VicWest products.
.2 Pre-coat 8000 Series.
.2 Exterior Sheet: 0.025mm thick on exposed face, 0.00075mm thick on unexposed face.
.3 Colour: To be selected by Consultant from manufacturer's full stock colour range.
.3 Preformed Metal Siding
.1 Precoated and preformed metal wall cladding panels with base metal thickness of 0.76mm;
.1 AD-300 profile.

.4 Miscellaneous Framing, Flashings and Exposed Trim
- .1 Girts and Subgirts: Minimum 0.12mm thick zinc coated in depths and configurations noted on the Drawings; clip and girt system, separated by cork gasket as required and shall be designed to accommodate expansion and contraction, dynamic movements and design load requirements.
  - .1 Approved product: Enviroclip, as manufactured by Ontario Panelization, or approved alternate.
- .2 Closures: Minimum 0.76mm thick galvanized sheet steel where not exposed to view.
- .3 Flashings and Exposed Trim: Minimum 0.46 thick precoated sheet steel in colour to match siding, where exposed to view.

.5 Membrane Flashings
- .1 Sheet Membrane: 40 mil self-adhering membrane flashing consisting of SBS rubberized asphalt compound cross laminated to a polyethylene film.
  - .1 When air and/or surface temperature is above 0°C; "Blueskin SA" by Bakor, "Sealtight Air-Shield" by W.R. Meadows of Canada, "PERM-A-BARRIER" by Grace Construction Products and Sopraseal Stick 1100 by Soprema are acceptable products.
  - .2 When air and/or surface temperature drops below 0°C use low temperature products, "Blueskin SA LT" by Bakor, "PERM-A-BARRIER Low Temperature Membrane" by Grace Construction Products or "Sopraseal Stick 1100 Winter Grade" by Soprema.
  - .3 Install in width to suit wall thickness.
- .2 Lap adhesive: single component rubberized mastic as recommended by manufacturer.
- .3 Primer: as recommended by manufacturer.

.6 Sealant
- .1 Acrylic Solvent Release, One Part Sealant: To meet specified requirements of CGSB Specification 19-GP-5.
- .2 Two Part Polysulphide Sealant: To meet specified requirements of CAN/CGSB-19.24-M90.
- .3 Polybutene Compound: To meet fabricator's recommendations.

2.3 Accessories

.1 Exposed trim: inside corners, outside corners, cap strip, drip cap, undersill trim, starter strip and window/door trim of same material, as cladding, with fastener holes pre-punched.

2.4 Fasteners

.1 Self-drilling, Type 304 stainless steel.
.2 Head finish:
- .1 Type 304 stainless steel
- .2 Pre-painted metal, in colour to match prefinished metal panels in exposed locations.
- .3 Dissimilar materials to be separated/ isolated.

2.5 Fabrication

.1 Roll form profiled panels and other shapes unless impossible because of special design. Use other forming methods only with approval.
.2 Form metal panels with bends sharp and true.
.3 Fabricate to conform to shop drawings and to allow for structural movements within the systems.

.4 Fabricate systems for use with concealed fasteners wherever possible. Where exposed fasteners are required use fasteners with coloured screw heads to match siding colour.
.5 Fabricate miscellaneous framing members of specified materials as required to support metal siding.
.6 Fabricate systems to prevent entry of water into building and from collection within system assembly and to prevent infiltration of air through system.
.7 Join intersecting parts together to provide tight, accurately fitted joints with adjoining surfaces in true planes.
.8 Fabricate system to conform to requirements of reference standards specified.
.9 Cooperate with applicable Sections to ensure required coordination for installations specified in this Section in conjunction with masonry, structural steel framing, metal deck, sprayed foam insulation, air barriers, membrane roofing, sheet metal work, drywall and steel studs and similar installations by other Sections.

## PART 3 - EXECUTION

3.1 Examination

.1 Take site measurements to ensure that fabrications are provided to fit structure; surrounding construction; around obstructions and projections in place or as shown on Drawings and to suit locations of services.
.2 Verify backup and support construction is aligned for proper installation of preformed metal system before commencing erection of metal siding.
.3 Before proceeding with application, ensure that:
  .1 Metal support is constructed smoothly, in true planes and to match whatever is the is the design intent.
  .2 Edges of metal are supported to prevent deflection.
  .3 Adjacent construction and installation of other work to be incorporated is complete.
  .4 Work which penetrates system has been installed.

3.2 Erection of Preformed Metal

.1 Erect systems complete with flashings forming part of system, sub-girts, clips, fasteners, closures and caulking to meet same design criteria as specified for fabrication.
.2 Cut and flash system penetrations.
.3 Erect panels in straight lines that are true, level and plumb.
.4 Provide for differential thermal and structural movement between systems and structure as well as between elements of system.
.5 Attach systems to supporting structure and to other siding components with fasteners of the same material and colour as the exterior panels except where other materials are approved.
.6 Install cap flashings, drip flashings, internal flashings, copings, closures and corners, of same material and finish as cladding, brake formed to shape. Close all flute ends.
.7 Seal joints within system watertight.
.8 Caulk between preformed metal specified in this Section and installations of other Sections to meet requirements of Section 07 92 10 and to provide a watertight installation.
.9 Fasteners: concealed fasteners.
.10 Apply a continuous bead of sealant to the face of the supports at the top and bottom of the girts and perimeter of openings.
.11 Erect systems by its fabricator or approved agent.

3.3 Metal Cladding Installation Tolerances

.1 Maintain the following installation tolerances:
  .1 Maximum variation from plane or location shown on reviewed shop drawings: 20mm/ 10m of length and up to 30mm/ 10m maximum.
  .2 Maximum offset from true alignment between two adjacent members abutting end to end, in line: 1mm.

3.4 Adjustment and Cleaning

.1 After erection, touch up galvanized coatings removed or damaged during erection.
.2 Remove damaged, dented, defaced, defectively finished or tool marked components and replace with new.
.3 Refinish shop applied finishes in field only with written approval from Consultant.
.4 Clean of dirt resulting from erection from surfaces exposed to view.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Section Includes

.1 Built-up membrane roofing, hot applied rubberized method.

1.3 References

.1 ASTM C931/931M-01: Standard Specification for Exterior Gypsum Soffit Board.
.2 ASTM D4601-98: Standard Specification for Asphalt-Coated Glass Fibre Base Sheet Used In Roofing.
.3 CSA A123.4-M1979: Bitumen for Use in Construction of Built-Up Roof Coverings and Dampproofing and Waterproofing Systems.
.4 CGSB 37-GP-9Ma: Primer, Asphalt, Unfilled, for Asphalt Roofing, Dampproofing and Waterproofing.
.5 CGSB 37-GP-52M: Roofing and Waterproofing Membrane, Sheet Applied, Elastomeric.
.6 CAN/CGSB-51.33-M89: Vapour Barrier Sheet, Excluding Polyethylene, for Use in Building Construction.
.7 CAN/ULC-S704-2001: Standard for Thermal Insulation, Polyurethane and Polyisocyanurate Boards, Faced.
.8 CAN/ULC-S706-02: Standard for Wood Fibre Thermal Insulation for Buildings.

1.4 Performance Requirements

.1 Hot Applied Roof Membrane:
  .1 Roofing System: three ply hot-applied built-up roofing system with thermal barrier underlay board, vapour retarder, rigid board insulation, composite ply roofing membranes fibreglass roofing felts, roof pavers and aggregate surfacing.
  .2 Provide Products that are compatible with one another under field conditions, as demonstrated by roofing manufacturer.
  .3 Provide watertight roofing system capable of resisting specified uplift pressures, thermally induced movement and exposure to weather without failing during the specified warranty period.

1.5 Submittals

.1 Make Submittals in accordance with Section 01 33 00.
.2 Product Data
  .1 Submit Product data for each major component, including membrane, vapour retarder, rigid board insulation, adhesives and pavers. Highlight critical criteria for proper installation.
.3 Shop Drawings
  .1 Submit Shop Drawings for prefabricated work and details.
  .2 Include plans, sections, details in accordance with performance requirements, and for attachment to other portions of the Work.
  .3 Sloped Insulation: Indicate degree of slope and layout of sloping insulation on roof surfaces. Ensure positive drainage to roof drains.

1.6 Certificate

.1 Manufacturer Certificates: Signed by roofing manufacturer verifying that installer is approved, authorized or licensed by manufacturer to install specified Products.
.2 Installer Certificates: Signed by installer verifying that they have the specified qualifications described below.
.3 Copy of Manufacturer's 20 Year Warranty.

1.7 Test Reports

.1 Submit test reports as specified in Section 01 33 00.
.2 Product Test Reports: based on the evaluation of comprehensive tests conducted by an independent testing agency of the specified roofing Products.
.3 Manufacturer Field Inspection Reports: manufacturer's written acceptance of roofing installation based on daily inspections.

1.8 Quality Assurance

.1 Manufacturer: qualified manufacturer having roofing systems listed by UL and approved for use by Factory Mutual.
.2 Installer: a company and persons specializing in the application of protected elastomeric roofing, with minimum 5 years documented experience and approved to apply roofing system by manufacturer.
.3 Conform to CRCA Roofing Specifications and roofing membrane manufacturer's instructions.

1.9 Prequalified Roofing Contractors

.1 Refer to Section 01 21 14 – General Contractors, Subcontractors, Prequalified Rosters.

1.10 Pre-Installation Meetings

.1 The manufacturer is to review the specification with the Consultant prior to application.
.2 Conduct pre-installation meeting.
.3 Meeting: prior to commencement of deck installation, review and document methods and procedures related to roof deck and roofing system construction, including the following:
    .1 Participants: authorized representatives of the Contractor, Owner, Consultant, Roofing Subcontractor, roofing manufacturer, and installers of roof accessories and roof-mounted equipment.
    .2 Review methods and procedures related to roofing installation, including manufacturer's written installation instructions.
    .3 Review construction schedule and confirm availability of Products, Subcontractor personnel, equipment and facilities.
    .4 Review deck installation criteria and finishes for conformance with roofing system criteria, including issues of flatness and fastening.
    .5 Review structural loading conditions and limitations of roof deck both during and after roofing application.
    .6 Review flashing details, special roofing details, roof drainage, roof penetrations, equipment curbs, and other conditions affecting roofing installation.
    .7 Review governing regulatory requirements, and requirements for insurance and certificates as applicable.
    .8 Review safety requirements, including temporary fall-arrest measures.
    .9 Review field quality control procedures.

1.11 Delivery, Storage and Handling

.1 Manufacturer’s recommendations for handling and storing products are a minimum requirement.
.2 Do not store material on roof. Keep covered and protect stored materials from moisture, freezing and degrading effects of the sun. Elevate on raised platform minimum 100mm (4"). Remove only those required for day's operation.
.3 Materials to be delivered to site, undamaged and in their original packages, with manufacturer labels visible, attesting to their conformity to specified standards.
.4 Provide WHMIS Material Safety Data Sheets for materials supplied. General Contractor to post data sheets in an appropriate location.
.5 At temperatures below 5°C (40°F), store membrane roofing, adhesive and sealants that will be affected by temperature in dry heated storage. Remove product immediately prior to installation.
.6 Protect edges of roll goods. Stand on end to prevent flattening.
.7 Do not store aggregate on roof. Keep covered during inclement weather. Remove and replace all wet or damaged materials.

1.12 Environmental Requirements

.1 Ensure protection of building and products sensitive to damage by moisture.
.2 As governed by design intent, apply each part of roofing system only when surfaces and weather will allow for a successful application and performance of completed work. When protection is required, stop work before the onset of inclement weather or when inclement weather appears imminent.
.3 Regard minimum temperature and weather conditions set out in manufacturer's printed recommendations. Proceed with work when temperatures are below 5°C (40°F) with the mutual documented agreement between Contractor and material supplier that, with the materials and method used, the specified installation under the conditions will be successfully achieved.

1.13 Warranty

.1 Submit extended warranties in accordance with the General Conditions of the Contract.
.2 Installer's Extended Warranty: standard 2-year warranty, commencing from the date of Substantial Performance of the Work.
.3 Manufacturer's Extended Warranty: The Manufacturer shall issue a non-prorated warranty for a period of Twenty (20) Years. All components including the vapour retarder, insulation, cover board, membrane, flood coat, perimeter flashings including metal shall be covered under this warranty. Wind uplift warranty shall cover wind velocity up to a maximum wind speed of not greater than 117km/h (73 mph).
Warranty shall include inspections in years 2, 5 ,10 & 15 of the warranty. The following duties shall be carried out at no extra cost to the Owner as required, by the Manufacturer.
- Sealing of flashing seam
- Filling of pitch pockets
- Repairs to blisters and ridges
- Caulking at metal details as required
- Written inspection report
- Removal of light debris from roof
- Cleaning of drain screens.

1.14 Additional Warranty Services

.1 All pertinent details regarding this project shall be provided in the manual for the owner's database such as:
- Roof assembly types, roof inspection reports, roof specs
- Construction of the roof system including all components
- Inspection schedule (warranty requirements)
- Substantial completion date
- Progress photos on a per roof basis
- Warranty information
- Emergency Leak call service.

## PART 2 - PRODUCTS

2.1 Manufacturers

.1 All products supplied for the Multi Ply built-up asphalt roofing systems shall be from a single (one) manufacturer.

2.2 Materials

.1 Verify all materials are compatible before proceeding with the work.
.2 Base sheet: Composite Trilaminate Felts.
.3 Roofing Ply Membrane: polyester-glass-polyester tri-laminate reinforced asphalt-coated sheet, (0.055") 1.4mm thick, (31 lb/100ft2) 1.5 kg/m2 weight, to ASTM D4601, Type II
.4 Asphalt primer: to CGSB 37-GP-9Ma-83.
.5 Asphalt: rubberized hot melt to CAN/CGSB 37.50-M89. Hot applied elastomeric roof membrane adhesive providing minimum 800% elongation
.6 Plastic cement: asphalt, to CGSB 37-GP-5Ma-89.
.7 Sealing compound: to CGSB 37-GP-29Ma-89, rubber asphalt type.
.8 Insulation:
  .1 Top layer: 12.7mm thick asphalt-coated (6 sides) fiberboard, to CAN/ULC-S706, Type II, Class 1. Crickets and all tapered accessories as per drawings.
  .2 Polyisocyanurate rigid board; to CAN/ULC-S704, Type 3, Class 2, closed cell type:
    .1 Board Size: minimum 1220mm x 1220mm.
    .2 Long Term Thermal Resistance (CAN/ULC-S770): (R6.0) RSI 1.04 per 25mm thickness of board. Total minimum R-value of 45.
    .3 Compressive Strength: 140kPa minimum.
    .4 Dimensional Stability (ASTM D2126): < 2 percent linear change.
    .5 Water Absorption (ASTM C209): < 1 percent by volume.
    .6 Edges: square.
    .7 Faces: non-asphaltic, fibre-reinforced felt facers both sides.
    .8 Combustibility: meets CAN/ULC-S107-M87 and CAN/ULC-S126-M86.
    .9 Thickness: minimum two layers required, total thickness: 6 inches.
.9 Flexible elastomeric flashing: use reinforced EPDM/SBR rubber sheet.
.10a Vapour Retarder: Self-adhering sheet vapour retarder consisting of 1.0mm (40mil) thick polyethylene film laminated to layer of rubberized asphalt adhesive; maximum permeance rating of 6 ng/Pa x s x sq. m. (0.1 perm); cold applied with slip resisting surface and release paper backing ("peel and stick"). Provide primer where recommended by vapour retarder manufacturer.
.10b Vapour Retarder/ Insulation Adhesive: Solvent free single component bitumen modified polyurethane.
.11 Thermal Barrier Underlay Board: Lightweight moisture resistant fiberglass-faced 16mm Type X gypsum sheathing panel.
.12 Cant strips: refer to Section 06 10 00.

.13 Gravel: to ASTM D1863-66.
.14 Roof vents: Alumi-Flash by Portals Plus or approved alternate.
.15 Pipe pass through: Portals Plus.
.16 Accessories:
  .1 Adhesive listed by ULC under Roof Deck Construction Materials, Guide No. 360 R13 and as recommended by manufacturer of material being adhered and for use under climatic conditions to be encountered.
  .2 Nails: to CSA B111-1974.
  .3 Flat caps or discs: flat metal 32mm diameter not less than 0.25mm thick.
  .4 Mechanical fasteners; as approved by ULC or Factory Mutual, length to suit application, c/w plastic or metal disks.
  .5 Insulation joint tape: asphalt treated kraft paper, fibre reinforced, 100 to 150mm wide, self-adhering.
  .6 Sealing compound: to CAN/CGSB-19.24-M80.
  .7 Polyethylene back-up rope: extruded close cell foam, Shore A hardness 20, tensile strength 140 to 200 kPa, compatible with primers and sealants, oversized 30 to 50%.
  .8 Slip Sheet: 0.15mm thick polyethylene sheet, to CAN/CGSB-51.34-M.
  .9 Altra Metal Specialties – Model ABD-CR-X-SS: Aluminum Body Roof Drain complete with clamping ring.
  .10 Pavers: 610mm x 610mm x 50mm thick, precast concrete paver units; diamond surface pattern; colour as selected by Consultant.

## PART 3 - EXECUTION

3.1 Examination

.1 Inspect existing conditions to ensure they are suitable for roofing work to begin. Do not proceed until unacceptable conditions are corrected.
.2 Ensure substrate is solid, clean, dry and free of any contaminants prior to commencing any roofing work.
.3 Ensure Products are dry prior to installation. Replace damaged Products.

3.2 Preparation

.1 Prime metal and concrete surfaces designated to be covered with asphaltic Products.
.2 Apply primer at an average rate of 4.3 $m^2$/litre. Allow to cure.
.3 Ensure primer does not enter building through cracks and other openings.

3.3 Thermal Barrier Underlay Board

.1 Mechanically secure thermal barrier underlay board to all metal roof decks except acoustic deck and metal deck exposed to view, with screws and plates using one fastener per 0.27 $m^2$. Stagger boards 300mm. Drive fasteners flush to top surface.

3.4 Vapour Retarder

.1 Adhere roof vapour retarder over roof deck with approved adhesive at manufacturer's recommended rate.
.2 Overlap vapour retarder minimum 100mm for side laps and 150mm for end laps. Seal all laps with adhesive.
.3 Extend vapour retarder under cant strips and blocking. Extend to perimeter and deck protrusions.

.4 Seal roof vapour retarder to wall air/vapour barrier system with flexible flashing membranes to ensure continuity of building air/vapour barrier envelope.

3.5 Insulation and Overlay Board

.1 Install insulation boards to maintain continuity of thermal envelope, as specified in Section 07 21 13. Minimize joints.
.2 Adhere the base layer of insulation to the vapour retarder using low rise foam adhesive.
.3 Adhere top layer of roof insulation to base layer of roof insulation with Kettle Modified Rubberized Asphalt.
.4 Adhere roof insulation/cover board where indicated and in accordance with approved Shop Drawings.
.5 Fit insulation tight to roof penetrations.
.6 Firmly butt insulation boards. Do not jam or deform boards.
.7 Minimize lipping between adjacent boards.
.8 Stagger joints minimum 300mm.
.9 Stagger overlay board seams with insulation board seams.

3.6 Cant Strips

.1 Install cant strips at intersections of roofing and vertical surfaces.
.2 Embed in a continuous bed of approved adhesive applied to overlay boards.
.3 Lay true to line, level and with flush, butt joints and accurately mitred corners.

3.7 Roof Membrane (Hot Applied)

.1 Install 1 ply of base ply in shingle fashion, starting at roof low point. Apply membrane perpendicular to overlay board joints. Conform to manufacturer's recommended method.
.2 Install two plies of Type IV felts in shingle fashion, starting at roof low point. Apply membrane perpendicular to overlay board joints. Conform to manufacturer's recommended method.
.3 Overlap starter strips 510mm with first ply, then overlap each succeeding ply 485mm.
.4 Place ply sheets to ensure water will flow over or parallel to, but not against, exposed edges.
.5 Shingle in direction to shed water. Extend ply membranes over and terminate beyond cants and cut evenly.
.6 Embed plies in bitumen, at a minimum rate of 1.2 L/$m^2$, and solidly coating each ply for full width.
.7 Ensure complete and continuous seal and contact between bitumen and ply membranes, including ends, edges and laps without wrinkles, fish mouths or blisters.
.8 Do not step or walk on felts during or immediately after application until bitumen has set.
.9 Install each ply so that it shall be firmly and uniformly set, without voids, into bitumen. Thoroughly and effectively broom or roll each membrane application to ensure full adhesion.
.10 Lap ply membrane ends 150mm. Stagger end laps 1.0 metres minimum.
.11 Overlap previous day's work 600mm, as required.
.12 Terminate all ply layers to outer edge of roof perimeter.

3.8 Elastomeric Flashings

.1 Provide membrane flashings as specified and in accordance with manufacturer’s written installation guidelines.
.2 Install flashings to ensure the roof is watertight at the end of each Working Day.

.3 Extend flashing membrane minimum 150mm over roof membrane.
.4 Extend flashing membranes minimum 200mm up vertical surfaces.
.5 Secure flashings at 200mm OC. Secure vertical flashings through termination bar.
.6 Overcoat lap edges with end lap stripping adhesive and membrane.
.7 Tie-in leading edge of elastomeric sheet flashing with stripping ply membrane embedded between alternate courses of stripping ply adhesive.
.8 Canted Eave:
  .1 Extend reinforced elastomeric sheeting over outside face of cant and extend minimum 25mm below blocking. Mechanically fasten with 38mm common roofing nails, 200mm OC.
  .2 Extend reinforced elastomeric sheeting down over cant strip and embed in flashing adhesive from top of cant to at least 150mm beyond toe of cant onto roof.
  .3 Ensure complete bond and continuity without wrinkles or voids. Lap sheeting ends 100mm and adhere with flashing adhesive.
.9 Canted Eave with Fascia
  .1 Extend reinforced elastomeric sheeting over outside face of cant and fascia and secure to underside of fascia. Mechanically fasten with 38mm common roofing nails, 200mm OC.
  .2 Extend reinforced elastomeric sheeting down over cant strip and embed in flashing adhesive onto roof surface a minimum of 150mm.
  .3 Ensure complete bond and continuity without wrinkles or voids. Lap sheeting ends 100mm and adhere with flashing adhesive.
.10 Low Parapet Wall Flashing
  .1 Seal exposed joint between the wall and roof deck for airtight seal.
  .2 Adhere elastomeric sheeting completely to flashing surface, cant, and roofing with flashing adhesive.
  .3 Ensure complete bond and continuity without wrinkles or voids. Lap sheeting ends 100mm and adhere with flashing adhesive.
  .4 Extend elastomeric sheeting up and over parapet at least 38 mm and face nail with 38mm common roofing nails, 200mm OC.
.11 Gravel Stop
  .1 Prior to setting and nailing horizontal flanges of edge flashings, uniformly trowel a 1.5mm thick layer of cold flashing adhesive to roofing surface designated to receive metal flange.
  .2 Install metal gravel stop with formed drip edge, incorporating lock-type joints to allow expansion and contraction. Set flange in cold flashing adhesive.
  .3 Nail interior portion of flange to wood blocking 75mm OC, staggered.
  .4 Prime metal flange with asphaltic primer.
  .5 Fully adhere a sufficiently wide strip of elastomeric sheeting to flashing with flashing adhesive. Ensure complete bond and continuity without wrinkles or voids lap sheeting ends 100mm and adhere with flashing adhesive. Elastomeric sheeting to cover gravel stop completely and overlapping onto adjacent roof minimum 150mm.
  .6 Seal edge of flashing membrane at metal upturn.
.12 Flashing at Edges and Gutters
  .1 Fabricate and install new one-piece edges, gutter with downspouts. Slope gutter to downspouts.
  .2 Prior to setting and nailing horizontal flanges of gutter, uniformly trowel a 1.5 mm thick layer of cold flashing adhesive to roofing surface designated to receive metal flange.
  .3 Nail flange to wood blocking 75mm OC, staggered.
  .4 Prime metal flange with asphaltic primer.

.5 Adhere sufficiently wide strip of elastomeric sheeting completely to flashing surface with flashing adhesive. Ensure complete bond and continuity without wrinkles or voids lap sheeting ends 100mm and adhere with flashing adhesive. Elastomeric sheeting to cover gravel stop completely and overlap onto adjacent roof a minimum of 150mm.

.6 Seal edge of flashing membrane at metal upturn.

.13 Wall Flashing

.1 Seal exposed joint between the wall and roof deck for airtight seal.

.2 Adhere elastomeric sheeting completely to flashing surface, cant and roofing with flashing adhesive.

.3 Ensure complete bond and continuity without wrinkles or voids. Lap sheeting ends 100mm and adhere with flashing adhesive.

.4 Elastomeric sheeting width: sufficient to extend at least 150mm beyond toe of cant onto roof surface and 200mm above the roof surface.

.5 Secure top of elastomeric sheeting to vertical plane with termination bar. Mechanically fasten 300mm OC. Overcoat bar with end lap stripping adhesive and membrane.

.14 Building Expansion Joints

.1 Fill joint with loose insulation.

.2 Provide 13mm thick plywood to top of wood blocking, secured one side only.

.3 Apply foam rubber or 25mm thick mineral fibre insulation to top of plywood.

.4 Install elastomeric sheeting centred over expansion joint.

.5 Fully adhere sheeting to horizontal and vertical blocking surfaces with flashing adhesive. Press sheeting into adhesive. Ensure complete bond and continuity without wrinkles or voids.

.6 Elastomeric Sheeting Width: Sufficient to extend onto adjacent roofing minimum 150mm.

.7 Lap sheeting ends 100mm and adhere with flashing adhesive.

.15 Expansion Joint at Wall

.1 Extend vapour retarder from deck level up wall sufficiently and secure to wall.

.2 Fill joint with loose insulation.

.3 Install blocking, sheathing and compressible insulation as detailed on drawings.

.4 Adhere elastomeric sheeting completely to flashing surface, cant and roofing with flashing adhesive.

.5 Ensure complete bond and continuity without wrinkles or voids. Lap sheeting ends 100mm and adhere with flashing adhesive.

.6 Elastomeric Sheeting Width: sufficient to extend at least 150mm beyond toe of cant onto roof surface and 200mm above the roof surface.

.7 Secure top of elastomeric sheeting to vertical plane with a termination bar. Mechanically fasten 300mm OC. Overcoat bar with end lap stripping adhesive and membrane.

.16 Area Divider

.1 Install elastomeric sheeting centred over area divider extending onto roof membrane a minimum of 150mm beyond toe of cant on either side.

.2 Fully adhere sheeting with flashing adhesive. Press sheeting into adhesive. Ensure complete bond and continuity without wrinkles or voids.

.3 Lap sheeting ends 100mm and adhere with flashing adhesive.

.17 Control Joint

.1 Install elastomeric sheeting centred over joint.

.2 Fully adhere sheeting to horizontal and vertical blocking surfaces with flashing adhesive. Press sheeting into adhesive. Ensure complete bond and continuity without wrinkles or voids.

.3 Flashing Width: Sufficient to extend onto adjacent roofing minimum 150mm.

.4 Lap sheeting ends 100mm and adhere with flashing adhesive.

.18 Curb Flashing
- .1 Fully adhere sheeting to horizontal and vertical blocking surfaces with flashing adhesive. Press sheeting into adhesive. Ensure complete bond and continuity without wrinkles or voids.
- .2 Elastomeric Sheeting Width: Sufficient to extend from top of curb down onto adjacent roofing minimum 150mm. Mechanically fasten sheeting on top face of curb.
- .3 Lap sheeting ends 100mm and adhere with flashing adhesive.
- .4 If membrane does not completely cover sleeper, secure top edge with a termination bar. Mechanically fasten 300mm OC. Overcoat bar with end lap stripping adhesive and membrane.

.19 Projection Flashing
- .1 Apply flashing adhesive to prepared area and provide aluminium base over pipe and set into the flashing adhesive.
- .2 Select proper step of rubber cap and cut off above index ring.
- .3 Install cap onto base collar and press edge to ensure proper seal.
- .4 Provide clamp around pipe and rubber cap. Prime flange.
- .5 Install elastomeric sheeting with stripping ply adhesive and membrane.
- .6 Cover flange completely. Extend flashing minimum 100mm onto adjacent roofing. Remove wrinkles and voids. Lap flashing ply ends 100mm.

.20 Lead Plumbing Vents
- .1 Provide lead plumbing vent flashing.
- .2 Flange: minimum 100mm wide; extend completely around periphery of vent flashing. Set flange into flashing adhesive. Neatly dress flange with wood blocking.
- .3 Prime lead flange with asphaltic primer.
- .4 Pipe greater than 50mm OD: Bend lead inside pipe minimum 25mm; replace cracked lead.
- .5 Pipe 50mm OD or less: Cut lead at vent top. Provide integral lead cap.

.21 Cartwheel and Collar: Provide cartwheel and collar flashing around projection using elastomeric sheeting and flashing adhesive.

.22 Coping
- .1 Test mortar bond of coping units. Remove loose mortar from bell joint and clean surfaces.
- .2 Pack flashing adhesive into bell joint and extend up onto bell approximately 75mm and down onto shank of adjoining unit a similar distance.
- .3 Cut proper lengths of 150mm wide reinforcement membrane and dry trowel membrane into flashing adhesive; tight and wrinkle-free.
- .4 Overcoat reinforcing membrane with flashing adhesive.

.23 Equipment Stands (Pipe) Portals Plus
- .1 Provide 200mm high sleeve flashing with 100mm wide flange. Flange to extend completely around flashing periphery. Solder joints. Double solder vertical joints.
- .2 Nail flange to wood blocking minimum 75mm OC; staggered.
- .3 Prime flange with asphaltic primer.
- .4 Install elastomeric sheeting to stand and roofing with continuous 1. mm thick application of flashing adhesive.
- .5 Sandwich top edge of sheeting between two layers flashing tape.
- .6 Secure top of sheeting with stainless steel drawband. Seal top of drawband and sheeting-to-pipe interface. Provide watershed and tool neatly.
- .7 Fabricate umbrella and install drawband; cover sleeve flashing minimum 75mm. Install immediately above sleeve flashing. Tighten drawband.
- .8 Wipe clean top of umbrella and projection with metal cleaner. Prime surface with metal primer.
- .9 Seal projection-to-sheet metal interface. Provide watershed and tool neatly.

.25 Piping Through Roof Boxes Portals Plus
- .1 Install pre-manufactured Portal Plus as per manufacturers written recommendations.
- .2 Set flange in mastic, nail flange to wood blocking at 75mm OC. Prime flange.
- .3 Fill box interior with mineral fibre insulation.
- .4 Fasten top and closure detail to bottom.
- .5 Clean surfaces of box and piping with metal cleaner and then prime. Seal joint between box and piping.
- .6 Install elastomeric sheeting with flashing adhesive and membrane.

.26 Roof Drain
- .1 Install drain assembly in accordance with manufacturer's written installation guidelines.
- .2 Plug and seal drain to prevent water entry until service connection is completed.
- .3 Provide 600mm x 600mm size elastomeric sheeting reinforcement, centred over drain; and fully adhered with flashing adhesive. Remove wrinkles and entrapped air.
- .4 Apply mastic to exposed edge of membrane inside the drain opening.
- .5 Reclamp flashing collar to drain in bed of flashing adhesive.
- .6 Trim excess sheeting within drain.

.27 Roof Drain Insert
- .1 Cut 225mm OD opening through membrane and insulation; coinciding with existing drain opening.
- .2 Install roof drain insert into existing drain pipe in accordance with drain insert manufacturer’s written installation guidelines.
- .3 Adhere drain flange to membrane with flashing adhesive.
- .4 Provide 900mm x 900mm size elastomeric sheeting reinforcement, centred over drain; and fully adhere sheeting with flashing adhesive. Remove wrinkles and entrapped air.
- .5 Trim excess sheeting within drain.
- .6 Seal leading edge of sheet with reinforcing membrane embedded between alternate continuous courses of flashing adhesive.

3.9 Surfacing

- .1 Flood coat roof surface with cold-process asphalt adhesive, applied at a rate of 2.4 L/$m^2$.
- .2 Immediately broadcast aggregate ballast into cold adhesive at a rate of 20 kg/$m^2$, covering flood coat completely.
- .3 Rake out aggregate to a neat, even surface.
- .4 Install concrete pavers on pedestals where indicated on Drawings.

3.10 Field Quality Control

- .1 Contractor Inspection: Prior to application aggregate surfacing, inspect completed membrane and flashing for punctures, tears, and discontinuously sealed seams.
- .2 Apply additional layer of membrane over punctures and tears, extending minimum 50mm beyond damaged area in all directions, and seal seams.
- .3 Manufacturer's Field Service: arrange for manufacturer's technical representative to regularly inspect the roofing application (minimum twice per week) and confirm that the roofing system installation is in strict accordance with manufacturer's recommendations.

3.11 Cleaning

- .1 Clean drains, gutters and downspouts of debris, ensuring free drainage.

.2 Clean adjacent roof surfaces, levels and ground level areas of debris and excess Products.

3.12 Protection

.1 Adequately protect Products and work from damage by weather, traffic and other causes.
.2 At the end of each Working Day, seal exposed edges of roofing membrane to be watertight.
.3 Protect adjacent Work from damage. Repair damage.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Section 06 10 10 – Rough Carpentry.
.2 Section 07 51 13 – Built-Up Asphalt Roofing.
.3 Section 07 92 10 – Joint Sealing.

1.3 References

.1 Aluminum Association
  .1 Aluminum Sheet Metal Work in Building Construction.
  .2 Designation System for Aluminum Finishes.
.2 American Society for Testing and Materials (ASTM)
  .1 ASTM A 167 - 99(2004), Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip.
  .2 ASTM A591/ A591M - 98, Specification for Steel Sheet, Electrolytic Zinc-Coated, for Light Coating Mass Applications.
  .3 ASTM A 606-04, Specification for Steel, Sheet and Strip, High-Strength, Low-Alloy, Hot-Rolled and Cold-Rolled, with Improved Atmospheric Corrosion Resistance.
  .4 ASTM A653/ A653 M - 17, Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
  .5 ASTM A 792/A 792M – 10(2015), Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
  .6 ASTM B32 - 08(2014), Specification for Solder Metal.
  .7 ASTM B370 - 12, Specification for Copper Sheet and Strip for Building Construction.
  .8 ASTM D523 - 14(2018), Test Method for Specular Gloss.
  .9 ASTM D822/ D822M - 13, Practice for Conducting Tests on Paint and Related Coatings and Materials Using Filtered Open-Flame Carbon Arc Light and Water Exposure Apparatus.
.3 Canadian Roofing Contractors Association (CRCA).
  .1 Roofing Specifications Manual.
.4 Canadian Standards Association (CSA)
  .1 CSA A123.3-05 (R2015), Asphalt or Tar Saturated Roofing Felt.
  .2 CAN/CSA-A440S1-17, Windows.
  .3 CSA B111-1974 (R2003), Wire Nails, Spikes and Staples.
.5 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-37.5-M89, Cutback Asphalt Plastic Cement.
  .2 CAN/CGSB-51.32-M77, Sheathing, Membrane, Breather Type.
  .3 CAN/CGSB-93.1-M85, Sheet, Aluminum Alloy, Prefinished, Residential.

1.4 Samples

.1 Submit shop drawings in accordance with General Requirements.
.2 Submit duplicate 300mm x 300mm samples of each type of sheet metal material, colour and finish.

## PART 2 - PRODUCTS

2.1 Sheet Metal Materials

.1 Zinc coated steel sheet: 0.70mm thickness, commercial quality to ASTM A 653/A 653M, with Z275 designation zinc coating.
.2 Precoated Steel Sheet:
  .1 Base metal thickness: 0.70mm.
  .2 Finish: baked enamel, applied by a continuous sheet steel coating plant;
    .1 WeatherX™ coating system, as provided with VicWest products.
    .2 Pre-coat 8000 Series.
  .3 Colour: To be selected by Consultant from manufacturer's full stock colour range.

2.2 Accessories

.1 Isolation coating: alkali resistant bituminous paint.
.2 Plastic cement: to CAN/CGSB 37.5-M89.
.3 Underlay for metal flashing: No. 15 perforated asphalt felt to CSA A123.3.
.4 Cleats: of same material, and temper as sheet metal, minimum 50 mm wide. Thickness same as sheet metal being secured.
.5 Fasteners (exposed): #10 hex head cadmium plated with neoprene and solid washers by Atlas Bolt or approved equal complete with caps for screw heads to match colour of flashing.
.6 Fasteners (concealed): of same material as sheet metal, to CSA B111, ring thread flat head roofing nails of length and thickness suitable for metal flashing application.
.7 Masonry Fasteners: Tapcon, Gripcon or Rawl spike sized to penetrate masonry 38mm minimum.
.8 Washers: of same material as sheet metal, 1 mm thick with rubber packings.
.9 Sealant and backer rods: in accordance with Section 07 92 10 - Joint Sealing, colour to match materials being caulked.
.10 Solder: to ASTM B 32, alloy composition.
.11 Flux: rosin, cut hydrochloric acid, or commercial preparation suitable for materials to be soldered.
.12 Touch-up paint: as recommended by prefinished material manufacturer.

2.3 Fabrication

.1 Fabricate metal flashings and other sheet metal work in accordance with applicable CRCA 'FL' series details.
.2 Form pieces in 2400mm maximum lengths. Make allowance for expansion at joints.
.3 Hem exposed edges on underside 12mm. Mitre and seal corners with sealant.
.4 Form sections square, true and accurate to size, free from distortion and other defects detrimental to appearance or performance.
.5 Supply accessories for installation of sheet work of same materials to which they will be used.
.6 Apply isolation coating to metal surfaces to be embedded in concrete or mortar.
.7 Seams shall be "slip lock type" that permit adequate movement without resulting in deformation or loosening of metal flashings. Lapped joints or exposed raw edges will not be accepted. Exposed edges shall be "doubled back" at least 12.5mm. At eaves, parapets, etc., metal shall be hooked over continuous starter strips that are a minimum two (2) gauges thicker than the metal used for flashing. Secure starter strips at 300mm O.C. or closer as required.
.8 Where metal terminates under fascia boards, secure metal at 600mm O.C. using specified fasteners. At curbs to openings or at sleepers, etc., provide lock or standing seams at corners. Solder mitred corners or form standing seams.

.9 Where metal flashings enter reglets, ensure reglet is minimum 19mm deep and 10mm wide. Metal flashing portion that enters reglet shall extend the full depth and be complete with 10mm return upstand to permit proper securement in the reglet. Secure metal flashing in reglets at 600mm O.C. and further secure metal to vertical surface at locks.

2.4 Metal Flashings

.1 Form cap and counter flashings, copings and fascias from specified precoated sheet steel, to profiles indicated on Drawings.

2.5 Pans

.1 Form pans to receive roofing plastic from sheet metal with minimum 75mm upstand above finished roof and 100mm continuous flanges with no open corners. Solder joints. Make pans minimum 50mm wider than member passing through roof membrane.

2.6 Reglets

.1 Form recessed reglets of specified sheet metal to be built-in for base flashings in accordance with CRCA FL series details.
.2 Ensure reglet is minimum 19mm deep and 10mm wide.

## PART 3 - EXECUTION

3.1 Installation

.1 Sheet metal work shall be of the highest quality and installed with the best trade practice and in accordance with CRCA FL series details.
.2 All flashings shall be installed in perfectly straight lines. Irregular or badly fitted work will not be accepted. At raised eave details, starter strips will be used. Exposed fastenings will only be permitted where concealed fastening is impossible. Neoprene washers shall be used at exposed fastenings.
.3 New metal flashings and fascias shall be 26 gauge precoated steel sheet. In all cases the bottom edge of the new metal shall meet the roof surface.
.4 At wall flashing details with "through wall" metal counterflashings or Mechanical walls with "lip" metal, the upper edge of the new wall face metal shall extend to a point 6mm below the through wall metal joint. The upper edge of the new face metal counterflashing shall be fastened to the wall using appropriate fasteners 250mm O.C. Fasteners shall be placed such that they are covered by the existing through wall metal.
.5 At all curb flashing details install new metal counterflashing, with the upper edge mechanically fastened at 300mm O.C. behind the existing lip metal.
.6 At sleepers, install new metal counterflashing to envelope sleeper.
.7 Provide underlay under sheet metal. Secure in place and lap joints 100mm.
.8 Counterflash bituminous flashings at intersections of roof with vertical surfaces and curbs. Flash joints using S-lock forming tight fit over continuous hook strips.
.9 Lock end joints and caulk with sealant.
.10 Insert metal flashing into reglets and under cap flashing to form weather tight junction.
.11 Turn top edge of flashing into recessed reglet or mortar joint minimum of 20mm. Wedge flashings securely into reglets or mortar joints with lead wedges at 200mm O.C. Set wedges 6mm in from face of masonry.
.12 Caulk flashing at reglet and cap flashing with sealant to provide a continuous waterproof seal. Ensure caulking bonds to intended surface and is tooled to provide even finish. Use colour to match materials being caulked.

.13 Install pans around items projecting through roof membrane.

3.2 Scuppers

.1 Install scuppers to allow for roof drainage as indicated on Drawings.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Related Sections

.1 Section 07 51 13 – Built-Up Asphalt Roofing.
.2 Section 07 92 10 - Joint Sealing.

1.3 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM A506 - 16, Specification for Steel Sheet and Strip, Alloy, Hot-Rolled and Cold-Rolled, Regular Quality and Structural Quality.
  .2 ASTM B370 - 12(2019), Specification for Copper Sheet and Strip for Building Construction.
  .3 ASTM A653/ A653M - 20, Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated.
  .4 ASTM D2369 - 10(2015), Standard Test Method for Volatile Content of Coatings.
  .5 ASTM D2832 - 92(2016), Standard Guide for Determining Volatile and Nonvolatile Content of Paint and Related Coatings.
  .6 ASTM D5116 - 17, Standard Guide For Small-Scale Environmental Chamber Determinations of Organic Emissions From Indoor Materials/Products.
.2 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-1.105-M91, Quick-Drying Primer.
.3 Canadian Standards Association (CSA)
  .1 CSA B111-1974(R2003), Wire Nails, Spikes and Staples.

1.4 Design Requirements

.1 Roof hatches to withstand local OBC design snow loads and wind loads without damage to unit or permanent deformation of seals.

1.5 Shop Drawings

.1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
.2 Indicate size and description of components, materials, attachment devices, description of frame and finish, and construction details.

1.6 Closeout Submittals

.1 Provide maintenance data for hardware complete with pertinent details, spare parts lists and warnings against harmful maintenance materials and practices for incorporation into manual specified in 01 78 00 - Closeout Submittals.

## PART 2 - PRODUCTS

2.1 Materials

.1 Acceptable products: Bilco Canada Thermally Broken Type S Roof Hatch; size 762mm x 915mm and Ladder UP Safety Post, Model #LU-1 to Drawings and as follows:
.2 Steel sheet: regular quality alloy steel to ASTM A506.
.3 Galvanized steel sheet: commercial quality to ASTM A653, Z275 designation zinc coating.
.4 Aluminum sheet: mill finish plain utility sheet.
.5 Aluminum: extruded sections of AA6063-T5 alloy, all components one piece without splices.
.6 Gaskets: extruded resilient neoprene, with full recovery after 50% compression.
.7 Fasteners: screws to manufacturers standard.
.8 Sealants:
.1 Acceptable materials: ECP-45.
.9 Prime paint for steel: to CAN/CGSB-1.105.
.10 Isolation coating: alkali resistant bituminous paint or epoxy solution.

2.2 Hatch Cover

.1 Metal Cover:
.1 14 gauge paint bond G-90 galvanized steel with a 76mm beaded flange with formed reinforcing members. Covers shall have a heavy extruded EPDM rubber gasket that is bonded to the cover interior to assure a continuous seal when compressed to the top surface of the curb.
.2 Cover Insulation
.1 25.4mm fiberglass insulation fully covered and protected by a 22 gauge paint bond G-90 galvanized steel liner.

2.3 Curb

.1 Preformed metal curb: 305mm high, 14 gauge paint bond G-90 galvanized steel. The curb shall be formed with an 89mm flange with 11mm holes provided for securing to deck.

2.4 Lifting Mechanism

.1 Provide compression spring operators enclosed in telescopic tubes to provide smooth, easy and controlled cover operation through entire arc of opening and closing. The upper tube shall be the outer tube to prevent accumulation of moisture, grit and debris inside the lower tube assembly. The lower tube shall interlock with a flanged support shoe through-bolted to the curb assembly. Provide automatic hold-open arm with grip handle release.

2.5 Accessories

.1 Screws: galvanized steel for curb to structure and for hatch lip frame to outer attachment.
.2 Hinges: heavy duty pintle type with 9mm Type 316 stainless steel hinge pins.
.3 Latch: Slam latch with interior and exterior turn handles and padlock hasps.
.4 Securing latch: hold open operating arm with vinyl grip handle to permit one-handed release.
.5 Resilient gasket/seal to inner face of lid in contact with hatch lid support frame.

2.6 Fabrication

.1 Fabricate components free of twists, bends, or visual distortion and insulated. Weld corners and joints.
.2 Assemble roof hatch components as indicated.
.3 Ensure continuity of weather-tight seal.
.4 Design flashings to collect and lead off accumulated condensation.
.5 Zinc plate hardware and attachments and shop prime ready for field painting.

## PART 3 - EXECUTION

3.1 Installation

.1 Erect components plumb, level and in proper alignment.
.2 Ensure continuity of building envelope air barrier and vapour retarder systems.
.3 Adjust and seal assembly with provision for expansion and contraction of components.
.4 Secure prefabricated curb assembly brake formed metal curb to structure.
.5 Coat aluminum and copper in contact with dissimilar materials, with isolation coating.
.6 Secure and seal frame to curb.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Work

.1 Fire stopping and smoke seals within mechanical assemblies (i.e. inside ducts, dampers) and electrical assemblies (i.e. inside cable trays) are specified in Division 21 through 28 respectively.

1.3 References

.1 Underwriter's Laboratories of Canada (ULC)
  .1 ULC-S115-05, Fire Test of Firestop Systems.

1.4 Samples

.1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit duplicate 300mm x 300mm samples showing actual firestop material proposed for project.

1.5 Shop Drawings

.1 Submit shop drawings in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit shop drawings to show proposed material, reinforcement, anchorage, fastenings and method of installation. Construction details should accurately reflect actual job conditions.

1.6 Product Data

.1 Submit product data in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit manufacturer's product data for materials and prefabricated devices, providing descriptions are sufficient for identification at job site. Include manufacturer's printed instructions for installation.

## PART 2 - PRODUCTS

2.1 Materials

.1 Fire stopping and smoke seal systems: in accordance with ULC-S115.
  .1 Asbestos-free materials and systems capable of maintaining an effective barrier against flame, smoke and gases in compliance with requirements of ULC-S115 and not to exceed opening sizes for which they are intended.
  .2 Firestop system rating: as indicated on Drawings for each condition.
.2 Service penetration assemblies: certified by ULC in accordance with ULC-S115 and listed in ULC Guide No.40 U19.
.3 Service penetration firestop components: certified by ULC in accordance with ULC-S115 and listed in ULC Guide No.40 U19.13 and ULC Guide No.40 U19.15 under the Label Service of ULC.
.4 Fire-resistance rating of installed fire stopping assembly in accordance with NBC.

.5 Fire stopping and smoke seals at openings intended for ease of re-entry such as cables: elastomeric seal.
.6 Fire stopping and smoke seals at openings around penetrations for pipes, ductwork and other mechanical items requiring sound and vibration control: elastomeric seal.
.7 Primers: to manufacturer's recommendation for specific material, substrate, and end use.
.8 Water (if applicable): potable, clean and free from injurious amounts of deleterious substances.
.9 Damming and backup materials, supports and anchoring devices: to manufacturer's recommendations, and in accordance with tested assembly being installed as acceptable to authorities having jurisdiction.
.10 Sealants for vertical joints: non-sagging.

## PART 3 - EXECUTION

3.1 Preparation

.1 Examine sizes and conditions of voids to be filled to establish correct thicknesses and installation of materials. Ensure that substrates and surfaces are clean, dry and frost free.
.2 Prepare surfaces in contact with fire stopping materials and smoke seals to manufacturer's instructions.
.3 Maintain insulation around pipes and ducts penetrating fire separation.
.4 Mask where necessary to avoid spillage and over coating onto adjoining surfaces; remove stains on adjacent surfaces.

3.2 Installation

.1 Install fire stopping and smoke seal material and components in accordance with ULC certification and manufacturer's instructions.
.2 Seal holes or voids made by through penetrations, poke-through termination devices, and unpenetrated openings or joints to ensure continuity and integrity of fire separation are maintained.
.3 Provide temporary forming as required and remove forming only after materials have gained sufficient strength and after initial curing.
.4 Tool or trowel exposed surfaces to a neat finish.
.5 Remove excess compound promptly as work progresses and upon completion.

3.3 Inspection

.1 Notify Consultant when ready for inspection and prior to concealing or enclosing firestopping materials and service penetration assemblies.

3.4 Schedule

.1 Firestop and smoke seal at:
  .1 Penetrations through fire-resistance rated masonry, concrete, and gypsum board partitions and walls.
  .2 Top of fire-resistance rated masonry and gypsum board partitions.
  .3 Intersection of fire-resistance rated masonry and gypsum board partitions.
  .4 Control and sway joints in fire-resistance rated masonry and gypsum board partitions and walls.
  .5 Penetrations through fire-resistance rated floor slabs, ceilings and roofs.
  .6 Openings and sleeves installed for future use through fire separations.
  .7 Around mechanical and electrical assemblies penetrating fire separations.

.8 Rigid ducts: greater than 129 cm²: fire stopping to consist of bead of fire stopping material between retaining angle and fire separation and between retaining angle and duct, on each side of fire separation.

3.5 Clean Up

.1 Remove excess materials and debris and clean adjacent surfaces immediately after application.
.2 Remove temporary dams after initial set of firestopping and smoke seal materials.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 References

.1 CAN/CGSB-19.1-M87, Putty, Linseed Oil Type.
.2 CAN/CGSB-19.2-M87, Glazing Compound, Nonhardening, Modified Oil Type.
.3 CGSB 19-GP-5M-76, Sealing Compound, One Component, Acrylic Base, Solvent Curing.
.4 CAN/CGSB-19.6-M87, Caulking Compound, Oil Base.
.5 CAN/CGSB-19.13-M87, Sealing Compound, One-component, Elastomeric, Chemical Curing.
.6 CGSB 19-GP-14M-76, Sealing Compound, One Component, Butyl-polyisobutylene Polymer Base, Solvent Curing.
.7 CAN/CGSB-19.17-M90, One-Component Acrylic Emulsion Base Sealing Compound.
.8 CAN/CGSB-19.18-M87, Sealing Compound, One Component, Silicone Base, Solvent Curing.
.9 CAN/CGSB-19.20-M87, Cold-applied Sealing Compound, Aviation Fuel-resistant.
.10 CAN/CGSB-19.21-M87, Sealing and Bedding Compound Acoustical.
.11 CAN/CGSB-19.22-M89, Mildew Resistant, Sealing Compound for Tubs and Tiles.
.12 CAN/CGSB-19.24-M90, Multi-component, Chemical Curing Sealing Compound.

1.3 Samples

.1 Submit samples in accordance with General Requirements.
.2 Submit duplicate samples of each type of material and colour.

1.4 Mock-up

.1 Construct mock-up in accordance with General Requirements.
.2 Construct mock-up to show location, size, shape and depth of joint s complete with back-up material, primer, caulking and sealant. Mock-up may be part of finished work.
.3 Allow 24 hours for inspection of mock-up by Consultant before proceeding with sealant work.

1.5 Delivery, Storage and Handling

.1 Deliver, handle, store and protect materials in accordance with General Requirements.
.2 Deliver and store materials in original wrappings and containers with manufacturer's seals and labels, intact. Protect from freezing, moisture, water and contact with ground or floor.

1.6 Environmental and Safety Requirements

.1 Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials; and regarding labelling and provision of material safety data sheets acceptable to Labour Canada.
.2 Conform to manufacturer's recommended temperatures, relative humidity, and substrate moisture content for application and curing of sealants including special conditions governing use.

## PART 2 - PRODUCTS

2.1 Sealant Materials

.1 Sealants and caulking compounds must:
- .1 meet or exceed all applicable governmental and industrial safety and performance standards; and
- .2 be manufactured and transported in such a manner that all steps of the process, including the disposal of waste products arising there from, will meet the requirements of all applicable governmental acts, by laws and regulations including, for facilities located in Canada, the fisheries Act and the Canadian Environmental Protection Act (CEPA).

.2 Sealant and caulking compounds must not be formulated or manufactured with: aromatic solvents, fibrous talc or asbestos, formaldehyde, halogenated solvents, mercury, lead, cadmium, hexavalent chromium, barium or their compounds, except barium sulfate.

.3 Sealant and caulking compounds must not contain a total of volatile organic compounds (VOCs) in excess of 5% by weight as calculated from records of the amounts of constituents used to make the product.

.4 Sealant and caulking compounds must be accompanied by detailed instructions for proper application so as to minimize health concerns and maximize performance, and information describing proper disposal methods.

.5 Caulking that emits strong odours, contains toxic chemicals or is not certified as mould resistant shall not be used in air handling units.

.6 When low toxicity caulks are not possible, confine usage to areas which off gas to the exterior, are contained behind air barriers, or are applied several months before occupancy to maximize off-gas time.

.7 The manufacturing process must adhere to Lifecycle Assessment Standards as per ISO 14040/14041 LCA Standards (to be published by 1998), CSA Z760-94 LCA Standards.

.8 Sealants acceptable for use on this project must be listed on CGSB Qualified Products List issued by CGSB Qualification Board for Joint Sealants. Where sealants are qualified with primers use only these primers.

2.2 Sealant Material Designations

.1 Urethanes One Part.
- .1 Non-Sag to CAN/CGSB-19.13, Type 2, colour as selected by Consultant.

.2 Silicones One Part.
- .1 To CAN/CGSB-19.22 (Mildew resistant).

.3 Acrylic Latex One Part.
- .1 To CAN/CGSB-19.17.

.4 Acoustical Sealant.
- .1 To CAN/CGSB-19.21.

.5 Preformed Compressible and Non-Compressible back-up materials.
- .1 Polyethylene, Urethane, Neoprene or Vinyl Foam.
  - .1 Extruded closed cell foam backer rod.
  - .2 Size: oversize 30 to 50 %.
- .2 Bond Breaker Tape.
  - .1 Polyethylene bond breaker tape which will not bond to sealant.

2.3 Sealant Selection

.1 Exterior: Urethane.

.2 Interior control and expansion joints: Silicone.

.3 Perimeters of interior frames and millwork: Acrylic Latex.

.4 Perimeter of bath fixtures (e.g. sinks, tubs, urinals, stools, waterclosets, basins, vanities): Sealant type: Mildew Resistant Silicone.
.5 Exposed interior control joints in drywall: Acrylic Latex.
.6 Perimeter of walls to ensure continuity of sound proofing: Acoustical.

2.4 Joint Cleaner

.1 Non-corrosive and non-staining type, compatible with joint forming materials and sealant recommended by sealant manufacturer.
.2 Primer: as recommended by manufacturer.

## PART 3 - EXECUTION

3.1 Protection

.1 Protect installed work of other trades from staining or contamination.

3.2 Preparation of Joint Surfaces

.1 Examine joint sizes and conditions to establish correct depth to width relationship for installation of backup materials and sealants; depth ration ½ of joint width with minimum width and depth of 6mm, maximum width 12mm
.2 Clean bonding joint surfaces of harmful matter substances including dust, rust, oil grease, and other matter which may impair work.
.3 Do not apply sealants to joint surfaces treated with sealer, curing compound, water repellent, or other coatings unless tests have been performed to ensure compatibility of materials. Remove coatings as required.
.4 Ensure joint surfaces are dry and frost free.
.5 Prepare surfaces in accordance with manufacturer's directions.

3.3 Priming

.1 Where necessary to prevent staining, mask adjacent surfaces prior to priming and caulking.
.2 Prime sides of joints in accordance with sealant manufacturer's instructions immediately prior to caulking.

3.4 Backup Material

.1 Apply bond breaker tape where required to manufacturer's instructions.
.2 Install joint filler to achieve correct joint depth and shape, with approximately 30% compression.

3.5 Mixing

.1 Mix materials in strict accordance with sealant manufacturer's instructions.

3.6 Application

.1 Sealant.
  .1 Apply sealant in accordance with manufacturer's written instructions.
  .2 Mask edges of joint where irregular surface or sensitive joint border exists to provide neat joint.

.3 Apply sealant in continuous beads.
.4 Apply sealant using gun with proper size nozzle.
.5 Use sufficient pressure to fill voids and joints solid.
.6 Form surface of sealant with full bead, smooth, free from ridges, wrinkles, sags, air pockets, embedded impurities.
.7 Tool exposed surfaces before skinning begins to give slightly concave shape.
.8 Remove excess compound promptly as work progresses and upon completion.

.2 Curing.
.1 Cure sealants in accordance with sealant manufacturer's instructions.
.2 Do not cover up sealants until proper curing has taken place.
.3 Cleanup.
.1 Clean adjacent surfaces immediately and leave work neat and clean.
.2 Remove excess and droppings, using recommended cleaners as work progresses.
.3 Remove masking tape after initial set of sealant.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Work Included in This Section

.1 Supply & installation of finishing hardware by Allowance; reference Section 01 21 00.

1.3 Coordination

.1 Coordinate the hardware with other allied trades such as carpentry, millwork, aluminium door and screens, hollow metal doors and frames, electrical and others.

1.4 Handling and Storage

.1 Handle and store materials on job site in such a manner that no damage will be done to the materials.
.2 Deliver and store materials undamaged in a dry area.
.3 Wrap all hardware in separate packages complete with all trimming and screws required for each item, distinctly labelled and numbered for each opening to correspond with the final reviewed Finish Hardware Schedule.

1.5 Hardware Reinforcement

.1 Reference *Door and Frame Schedule* for typical hardware to be used on this project. Provision of hardware reinforcing required providing a firm support for hardware is under other sections of these specifications. Report any doors, frames or panels which have not been adequately reinforced.

1.6 Fire and Building Codes

.1 All hardware shall comply with applicable fire and building codes and requirements of local authority having jurisdiction over hardware. All electrical items must have CSA approval.

1.7 Barrier Free Requirements

.1 The building is designed to meet the needs of barrier free access. All hardware shall be supplied and installed in accordance with the Ontario Building Code (OBC).

1.8 Submittals

.1 Shop Drawings
  .1 Prepare and submit to the Consultant for review, 1 electronic copy of the hardware schedule & 1 electronic copy of the electrical elevation coordination drawings showing all hardware required for each opening.
.2 For Maintenance Use: Submit the following to the Consultant:
  .1 One set wrenches for locksets, exit devices and door closers.
  .2 Three sets of manufacturer's installation instructions for locksets.
  .3 Three sets of manufacturer's instructions in regard to proper care of hardware including lubrication of locksets, exit devices and door closers.
  .4 One complete set of template schedules.
  .5 Catalogue cuts of all hardware installed.

1.9 Warranty

.1 Submit a warranty in accordance with Section 01 78 00, covering the repair or replacement of defective work within specified periods.
.2 Provide total warranty of 5 years for locksets and exit devices, 10 years for door closers, and 2 years for other hardware. Hinges require a written warranty from the manufacturer for the lifetime of the hinges.
.3 State in the warranty that any defective (material and operation) item of hardware shall be replaced immediately upon notification that item is defective.

## PART 2 - PRODUCTS

2.1 Hardware by Cash Allowance – Reference Section 01 21 00.

.1 The approved finishing hardware schedule will govern final door and frame preparations.

2.2 Keying

.1 Review and establish keying system with Owner.

2.3 Templates

.1 All hardware applied to metal doors and frames shall be made to template. Furnish templates, together with instructions necessary for door and frame preparation.

2.4 Fasteners

.1 Provide screws, rivets, bolts, expansion shields, and other fastening devices as required for the satisfactory installation and operation of the hardware. Provide Robertson or Phillips heads.
.2 Fastening devices shall be of the same finish as the hardware which is to be fastened.
.3 Where a pull is scheduled on one side of the door and a push plate on the other side, issue installation directions to the trade responsible for fixing, so that the pull is secured through the door from the reverse side, and the push plate installed to cover the screws. Supply flush pulls with machine screws for attaching as specified above.
.4 For fastenings in concrete for floor stops and thresholds, use machine screws in expansion shields.

## PART 3 - EXECUTION

3.1 Installation

.1 As specified in Section 01 21 00 – supply and installation of finishing hardware is by Cash Allowance.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Section 07 92 10 – Joint Sealing.
.2 Section 09 22 14 – Metal Furring and Lathing.
.3 Section 09 22 16 – Non-Structural Metal Framing.
.4 Section 09 22 27 – Acoustical Suspension.
.5 Section 09 91 10 – Painting.
.6 Mechanical – refer to Mechanical Drawings.
.7 Electrical – refer to Electrical Drawings.

1.3 References

.1 Aluminum Association
  .1 Designation for Aluminum Finishes.
.2 American Society for Testing and Materials (ASTM)
  .1 ASTM C36, Specification for Gypsum Wallboard.
  .2 ASTM C79, Specification for Gypsum Sheathing Board.
  .3 ASTM C442, Specification for Gypsum Backing Board and Coreboard.
  .4 ASTM C475, Specification for Joint Compound and Joint Tape for Finishing Gypsum Board.
  .5 ASTM C514, Specification for Nails for the Application of Gypsum Board.
  .6 ASTM C557, Specification for Adhesives for Fastening Gypsum Wallboard to Wood Framing.
  .7 ASTM C630, Specification for Water-Resistant Gypsum Backing Board.
  .8 ASTM C840, Specification for Application and Finishing of Gypsum Board.
  .9 ASTM C931/931, Specification for Exterior Gypsum Soffit Board.
  .10 ASTM C954, Specification for Steel Drill Screws for the Application of Gypsum Board.
  .11 ASTM C960, Specification for Predecorated Gypsum Board.
  .12 ASTM C1002, Specification for Steel Drill Screws for the Application of Gypsum Board or Metal Plaster Bases.
  .13 ASTM C1047, Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base.
  .14 ASTM C1280, Specification for Application of Gypsum Sheathing Board.
  .15 ASTM C1177, Specification for Glass Mat Gypsum Substrate for Use as Sheathing.
  .16 ASTM C1178, Specification for Glass Mat Water-Resistant Gypsum Backing Board.
.3 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-51.34-M, Vapour Barrier, Polyethylene Sheet for Use in Building Construction.
  .2 CAN/CGSB-71.25-M, Adhesive, for Bonding Drywall to Wood Framing and Metal Studs.
.4 Underwriters Laboratories of Canada (ULC)
  .1 CAN/ULC-S102, Building Materials and Assemblies, Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
.5 Gypsum Association (GA)
  .1 GA-216, Application and Finishing of Gypsum Board.
  .2 GA-600, Fire Resistance Design Manual.

1.4 Samples

.1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit 300mm long samples of corner and casing beads and reveals.

1.5 Site Environmental Requirements

.1 Maintain temperature minimum 15°C, maximum 21°C for 48 hours prior to and during application of gypsum boards and joint treatment, and for at least 48 hours after completion of joint treatment.
.2 Apply board and joint treatment to dry, frost free surfaces.

1.6 Quality Assurance

.1 Subcontractor executing the Work of this Section shall have adequate plant, equipment and skilled tradesmen to provide installations of work of this type and quality indicated and specified.
.2 Single source responsibility: Obtain gypsum board products from single manufacturer, or from manufacturers recommended by prime manufacturer of gypsum boards.
.3 Fire resistance rating: Where gypsum board systems with fire resistance ratings are indicated or required, provide materials and installations that are identical with those of applicable assemblies tested by fire testing laboratories acceptable to authorities having jurisdiction.

## PART 2 - PRODUCTS

2.1 Materials

.1 Fire resistant board (GB): Type X to ULC Guide No. 40 U18.23, thickness as noted on drawings, 1220mm wide x maximum practical length, ends square cut, edges tapered, glass mat faced, water resistant treated core..
  .1 Acceptable material:
    .1 Georgia Pacific ‘ToughRock FireGuard X Mold Guard’.
    .2 CGC Sheetrock Glass Mat Mold Tough AR Firecode X.
.2 Glass mat wall board (GB): to ASTM C1177 regular, 15.9mm thick, 1220mm wide x maximum practical length, ends square cut, edges tapered, glass mat faced, water resistant treated core.
  .1 Acceptable material:
    .1 Georgia Pacific ‘DensArmor Plus High Performance Interior Panel’.
    .2 CGC Sheetrock Glass Mat Mold Tough.
.3 Impact resistant glass mat wall board (GB): to ASTM C1177 regular, 15.9mm thick, 1220mm wide x maximum practical length, ends square cut, edges tapered, glass mat faced, water resistant treated core.
  .1 Acceptable material:
    .1 Georgia Pacific ‘DensArmor Plus Impact-Resistant Interior Panel’.
    .2 CGC Sheetrock Glass Mat Mold Tough.
.4 Exterior sheathing board: to ASTM C1177/ C1177M-04e1931; thicknesses as indicated on Drawings x maximum practical length. Fibreglass mat faced on front and back sides and long edges, silicon treated water resistant core.
  .1 Acceptable materials:
    .1 CertainTeed ‘GlasRoc Exterior Sheathing 2015’.
    .2 Georgia Pacific ‘DensGlass Gold’.
    .3 CGC Securerock Glass Mat Sheathing.
.5 Metal furring runners, hangers, tie wires, inserts, anchors: to ASTM C841.
.6 Drywall furring channels: 0.5mm core thickness galvanized steel channels for screw attachment of gypsum board.

.7 Resilient clips drywall furring: 0.5mm base steel thickness galvanized steel for resilient attachment of gypsum board.
.8 Steel drill screws: to ASTM C1002.
.9 Stud adhesive: to CAN/CGSB-71.25 ASTM C557.
.10 Laminating compound: as recommended by manufacturer, asbestos-free.
.11 Casing beads, corner beads, control joints and edge trim: to ASTM C1047, Zinc metal, zinc-coated by electrolytic process, 0.5mm base thickness, perforated flanges, one piece length per location.
.12 Reveal joints: rigid PVC, sizes as indicated on Drawings.
.1 Acceptable manufacturer:
.1 Trimtex, or approved alternate.
.13 Sealants: in accordance with Section 07900 - Joint Sealers.
.14 Acoustic sealant: Refer to Section 07900.
.15 Polyethylene: to CAN/CGSB-51.34, Type 2.
.16 Insulating strip: rubberized, moisture resistant, 3mm thick closed cell neoprene strip, 12mm wide, with self sticking permanent adhesive on one face, lengths as required.
.17 Joint reinforcement tape: 50mm wide, glass fibre mesh.
.18 Joint compound: to ASTM C475, asbestos-free.

## PART 3 - EXECUTION

3.1 Erection

.1 Do application and finishing of gypsum board in accordance with ASTM C840 except where specified otherwise.
.2 Erect hangers and runner channels for suspended gypsum board ceilings in accordance with ASTM C840 except where specified otherwise.
.3 Support light fixtures by providing additional ceiling suspension hangers within 150mm of each corner and at maximum 600mm around perimeter of fixture.
.4 Install work level to tolerance of 1:1200.
.5 Frame with furring channels, perimeter of openings for access panels, light fixtures, diffusers, grilles, etc.
.6 Install furring channels parallel to, and at exact locations of steel stud partition header track.
.7 Furr for gypsum board faced vertical bulkheads within and at termination of ceilings.
.8 Furr above suspended ceilings for gypsum board fire and sound stops and to form plenum areas as indicated.
.9 Install wall furring for gypsum board wall finishes in accordance with ASTM C840, except where specified otherwise.
.10 Furr openings and around built-in equipment, cabinets, access panels, on four sides. Extend furring into reveals. Check clearances with equipment suppliers.
.11 Furr duct shafts, beams, columns, pipes and exposed services where indicated.
.12 Erect drywall resilient furring transversely across studs, spaced maximum 600mm o.c. and not more than 150mm from ceiling/wall juncture. Secure to each support with 25mm drywall screw.
.13 Install 150mm continuous strip of 12.7mm gypsum board along base of partitions where resilient furring installed.

3.2 Application

.1 Do not apply gypsum board until bucks, anchors, blocking, electrical and mechanical work are approved.
.2 Apply single layer gypsum board to metal furring or framing using screw fasteners. Maximum spacing of screws 300mm o.c.
.3 Apply single layer gypsum board to concrete/ concrete block surfaces, where indicated, using laminating adhesive.

**.4 Apply impact resistant glass mat wall board on all vertical surfaces.**
**.5 Apply glass mat board on all other surfaces.**
.6 Apply 12mm diameter bead of acoustic sealant continuously around periphery of each face of partitioning to seal gypsum board/structure junction where partitions abut fixed building components. Seal full perimeter of cut-outs around electrical boxes, ducts, etc., in partitions where perimeter sealed with acoustic sealant.

3.3 Installation

.1 Erect accessories straight, plumb or level, rigid and at proper plane. Use full length pieces where practical. Make joints tight, accurately aligned and rigidly secured. Mitre and fit corners accurately, free from rough edges. Secure at 150mm oc.
.2 Install casing beads around perimeter of suspended ceilings.
.3 Install casing beads where gypsum board butts against surfaces having no trim concealing junction and where indicated. Seal joints with sealant.
.4 Install insulating strips continuously at edges of gypsum board and casing beads abutting metal window and exterior door frames, to provide thermal break.
.5 Construct control joints of preformed units set in gypsum board facing and supported independently on both sides of joint.
.6 Provide continuous polyethylene dust barrier behind and across control joints.
.7 Locate control joints where indicated on Drawings, at changes in substrate construction, **and** at approximate 10m spacing on long corridor runs and at approximate 15m spacing on ceilings. **Submit layout of control joints to Consultant for approval prior to commencement of the Work of this Section.**
.8 Install control joints straight and true.
.9 Install access doors to electrical and mechanical fixtures specified in respective Sections.
.1 Rigidly secure frames to furring or framing systems.
.10 Finish face panel joints and internal angles with joint system consisting of joint compound, joint tape and taping compound installed according to manufacturer's directions and feathered out onto panel faces.
.11 Finish corner beads, control joints and trim as required with two coats of joint compound and one coat of taping compound, feathered out onto panel faces.
.12 Fill screw head depressions with joint and taping compounds to bring flush with adjacent surface of gypsum board so as to be invisible after surface finish is completed.
.13 Sand lightly to remove burred edges and other imperfections. Avoid sanding adjacent surface of board.
.14 Completed installation to be smooth, level, plumb, free from waves and other defects and ready for surface finish.
.15 Mix joint compound slightly thinner than for joint taping.
.16 Where required by surface imperfections, apply thin coat to entire surface using trowel or drywall broad knife to fill surface texture differences, variations or tool marks.
.17 Allow skim coat to dry completely.
.18 Remove ridges by light sanding or wiping with damp cloth.

3.4 Fire Dampers

.1 Refer to Mechanical Drawings for locations of fire dampers.
.2 Coordinate opening sizes for dampers to ULC clearance requirements.
.3 Line openings for dampers with type X board prior to damper installation.

3.5 Cleaning

.1 Clean adjacent surfaces and remove excess materials, droppings and debris.
.2 Protect unfinished work.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Section 09 21 16 – Gypsum Board Assemblies.
.2 Section 09 22 27 – Acoustical Suspension.
.3 Divisions 21-23/ 26-28: Access doors and plaster rings.

1.3 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM C841, Standard Specification for Installation of Interior Lathing and Furring.
  .2 ASTM C847, Standard Specification for Metal Lath.
  .3 ASTM C1047, Accessories for Gypsum Wallboard and Gypsum Veneer.
.2 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-51.34-M, Vapour Barrier, Polyethylene Sheet for Use in Building Construction.
.3 Canadian Standards Association (CSA)
  .1 CSA A123.3, Asphalt Saturated Organic Roofing Felt.

## PART 2 - PRODUCTS

2.1 Materials

.1 Metal furring (channels, hangers, tie wire, inserts, anchors): ASTM C841.
.2 Polyethylene film: CAN/CGSB-51.34, Type 2, 0.15mm thick.
  .1 Acceptable material: ECP-69.
.3 Metal accessories (corner beads, base screeds, cornerite, casing beads): ASTM C1047.

## PART 3 - EXECUTION

3.1 Preparation

.1 Use galvanized supports, members, angles and metal lathing in wet areas, exterior walls and exterior soffits.
.2 Do not lath over bucks, anchors, blocking, electrical and mechanical work until they are inspected and approved by Consultant.
.3 Leave finished work rigid, secure, square, level, plumb, and erected to maintain finish plaster line dimensions and contours. Make allowance for thermal movement.
.4 Provide clearance under beams and structural slabs to prevent transmission of structural loads to vertical furring.

3.2 Installation

.1 Furring and lathing work: in accordance with ASTM C841 except as specified otherwise.
.2 Ceiling Furring.
  .1 Install runners level to tolerance of 3mm over 3.5m. Provide runners at interruptions of continuity and change in direction.
  .2 Frame with furring channels, perimeter of openings to accommodate access panels, light fixtures, diffusers, grilles.
  .3 Furr for vertical bulkheads within or at termination of ceilings.
  .4 Furr above suspended ceilings for fire and sound stops and to form plenum areas indicated.
  .5 Brace suspension for exterior soffits and entrance vestibule ceilings to prevent upward movements due to wind pressure.
  .6 Provide galvanized drips continuously along edges of exterior soffits.
.3 Wall Furring.
  .1 Install steel furring for braced walls as indicated.
  .2 Frame openings and around built-in equipment, cabinets, access panels, on four sides, with channels. Extend furring into reveals. Check clearances with equipment suppliers.
  .3 Construct bulkheads and boxed-in duct shafts, for beams, columns, pipes and around exposed services where indicated. Install 19mm channels at corners and at 300mm o.c.
  .4 Build in hollow metal frames in plastered furred walls.

3.3 Construction

.1 Erect accessories straight, plumb or level, rigid and at proper plane. Use full length pieces where practical. Make joints tight, accurately aligned and rigidly secured. Mitre and fit corners accurately, free from rough edges. Secure at 200mm o.c.
.2 Install corner beads on external angles.
.3 Install casing beads at perimeter of suspended plaster ceilings; wherever plaster abuts or joins a dissimilar exposed surface such as masonry, concrete, wood, metal; where edges of plaster are exposed; where plaster on a non-structural member butts plaster on a structural member; and elsewhere as indicated.
.4 Install metal screeds at top of bases and dadoes.
.5 Construct control joints of special purpose fabrication supported independently on both sides of joint.
.6 Locate control joints where indicated at wall juncture with suspended ceilings at changes in substrate construction at line of door jambs from top of door frame to ceiling at maximum 7.5m spacing in each direction on ceilings.
.7 Install control joints straight and true.
.8 Install rings and frames for electrical and mechanical fixtures.
.9 Rigidly secure rings and frames to furring and lathing systems.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Section 07 92 10 – Joint Sealing.
.2 Section 09 21 16 – Gypsum Board Assemblies.
.3 Section 09 22 14 – Metal Furring and Lathing.

1.3 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM C645 - 14e1, Standard Specification for Nonstructural Steel Framing Members.
  .2 ASTM C754 - 18, Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products.
.2 CAN/CGSB-19.21-M87, Sealing and Bedding Compound Acoustical.

## PART 2 - PRODUCTS

2.1 Materials

.1 Non-load bearing channel stud framing: to ASTM C645, stud size as indicated on drawings, roll formed with minimum base steel thickness 0.455mm of hot dipped galvanized steel sheet, for screw attachment of gypsum board. Knock-out service holes at 460mm centres. **For walls over 3000mm in height, minimum base steel thickness to be 0.836mm.**
.2 Floor and ceiling tracks: to ASTM C645, in widths to suit stud sizes, 32mm flange height.
.3 Metal channel stiffener: 19mm x 9.5mm size, 1.4mm thick cold rolled steel, coated with rust inhibitive coating.
.4 Acoustical sealant: to CAN/CGSB-19.21. Refer also to Section 07 92 00.
.5 Insulating strip: rubberized, moisture resistant 3mm thick foam strip, 12mm wide, with self sticking adhesive on one face, lengths as required.

## PART 3 - EXECUTION

3.1 Erection

.1 Align partition tracks at floor and ceiling and secure at 600mm o.c. maximum. Allow for 20mm deflection of floor and roof slabs.
.2 Install dampproof course under stud shoe tracks of partitions on slabs on grade.
.3 Place studs vertically at 400mm o.c. and not more than 50mm from abutting walls, and at each side of openings and corners. Position studs in tracks at floor and ceiling. Cross brace steel studs as required to provide rigid installation to manufacturer's instructions.
.4 Erect metal studding to tolerance of 1:1000.
.5 Attach studs to bottom and ceiling track using screws.

.6 Co-ordinate simultaneous erection of studs with installation of service lines. When erecting studs ensure web openings are aligned.

.7 Co-ordinate erection of studs with installation of door/ window frames and special supports or anchorage for work specified in other Sections.

.8 Provide two studs extending from floor to ceiling at each side of openings wider than stud centres specified. Secure studs together, 50mm apart using column clips or other approved means of fastening placed alongside frame anchor clips.

.9 Install heavy gauge single jamb studs at openings.

.10 Erect track at head of door/ window openings and sills of sidelight/ window openings to accommodate intermediate studs. Secure track to studs at each end, in accordance with manufacturer's instructions. Install intermediate studs above and below openings in same manner and spacing as wall studs.

.11 Frame openings and around built-in equipment, cabinets, access panels, on four sides. Extend framing into reveals. Check clearances with equipment suppliers.

.12 Provide 40mm stud or furring channel secured between studs for attachment of fixtures behind lavatory basins, toilet and bathroom accessories, and other fixtures including grab bars and towel rails, attached to steel stud partitions.

.13 Install steel studs or furring channel between studs for attaching electrical and other boxes.

.14 Extend **all** partitions to underside of structural deck.

.15 Maintain clearance under beams and structural slabs to avoid transmission of structural loads to studs. Use 50mm leg ceiling deflection tracks, with 75mm leg top track within. Attach studs to 75mm track.

.16 Install continuous insulating strips to isolate studs from uninsulated surfaces.

.17 Install two continuous beads of acoustical sealant under studs and tracks around perimeter of **all** partitions.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Related Sections

.1 Section 09 21 16 – Gypsum Board Assemblies.
.2 Divisions 20-23 – Mechanical: Trim for recessed mechanical fixtures.
.3 Divisions 26-28 – Electrical: Trim for recessed electrical fixtures.

1.3 References

.1 ASTM C635/ C635M - 17, Specifications for the Manufacture, Performance and Testing of Metal Suspension Systems for Acoustical Tile and Lay-In Panel Ceilings.
.2 ASTM C636 / C636M - 13, Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels.

1.4 Design Requirements

.1 Maximum deflection: 1/360th of span to ASTM C635 deflection test.

1.5 Extra Materials

.1 Provide maintenance materials of acoustic tile ceiling panels in accordance with Section 01 78 00 - Closeout Submittals.
.2 Provide 2% of each colour, pattern and type ceiling tile required for this project for maintenance use.
.3 Extra materials to be from same production run as installed materials.
.4 Clearly identify each container of ceiling tile.
.5 Deliver to site, upon completion of the work of this section.
.6 Store where directed by Consultant.

## PART 2 - PRODUCTS

2.1 Materials

.1 Intermediate duty system to ASTM C 635.
.2 Basic materials for suspension system: commercial quality cold rolled steel zinc-coated.
.3 Suspension system: non fire rated for gypsum board ceilings, made up as follows:
  .1 main beams:
    .1 0.53mm thick cold rolled steel, double web, with peaked roof top bulb at least 42.8mm high. Fabricate with punched cross tee holes at not greater than 150mm o.c. and hanger wire holes at 50mm o.c. Flange shall be 38mm wide knurled cold rolled steel.
  .2 cross tees:
    .1 double web design with peaked roof top bulb 38mm high, web extending to form a positive interlock with main tees. Flange shall be 38mm wide knurled cold rolled steel.
  .3 Acceptable manufacturer: Armstrong or equivalent system approved by Consultant.
.4 Hanger wire: galvanized soft annealed steel wire.
  .1 3.6mm diameter to support max. weight of 110 kg/hanger.
  .2 2.6mm diameter to support max. weight of 68 kg/hanger.

.3 galvanized annealed steel rod: 4.8mm diameter to support max. weight of 250kg/ hanger.

.5 Hanger inserts: purpose made.

.6 Accessories: splices, clips, wire ties, retainers, and angle wall moulding.

## PART 3 - EXECUTION

3.1 Installation

.1 Installation: in accordance with ASTM C636 except where specified otherwise.

.2 Install suspension system to manufacturer's instructions and Certification Organizations tested design requirements.

.3 Install fire rated gid system in ceilings requiring a fire rating, as noted on Drawings.

.4 Do not erect ceiling suspension system until work above ceiling has been inspected by Consultant.

.5 Secure hangers to overhead structure. Do not use fasteners that will fracture structural members.

.6 Install hangers spaced at maximum 1200mm centres and within 150mm from ends of main tees.

.7 Lay out centre line of ceiling both ways, to provide balanced borders at room perimeter with border units not less than 50% of standard unit width if no reflected ceiling plan is provided.

.8 Ensure suspension system is co-ordinated with location of related components.

.9 Install wall moulding and trim to provide correct ceiling height.

.10 Completed suspension system to support super-imposed loads, such as lighting fixtures diffusers, grilles and speakers.

.11 Support at light fixtures and diffusers with additional ceiling suspension hangers within 150mm of each corner and at maximum 600mm around perimeter of fixtures.

.12 Interlock cross member to main runner to provide rigid assembly.

.13 Frame at openings for light fixtures, air diffusers, speakers and at changes in ceiling heights.

.14 Finished ceiling system to be square with adjoining walls and level within 1:1000.

3.2 Cleaning

.1 Touch up scratches, abrasions, voids and other defects in painted surfaces.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Related Sections

.1 Divisions 20-23 and 26-28: Floor access covers.

1.3 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM F 1066- 95a, Specification for Vinyl Composition Floor tile.
.2 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-25.20- 95, Surface Sealer for Floors.

1.4 Samples

.1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit duplicate tile in size specified, 300mm long base, nosing, treads, edge strips.

1.5 Closeout Submittals

.1 Provide maintenance data for resilient flooring for incorporation into manual specified in Section 01 78 00 - Closeout Submittals.

1.6 Environmental Requirements

.1 Maintain air temperature and structural base temperature at flooring installation area above 20°C for 48 hours before, during and for 48 hours after installation.

1.7 Extra Materials

.1 Provide maintenance materials of resilient tile flooring, base and adhesive in accordance with Section 01 78 00 - Closeout Submittals.
.2 Provide 2% of each colour, pattern and type flooring material required for this project for maintenance use.
.3 Extra materials to be from same production run as installed materials.
.4 Clearly identify each container of floor tile and each container of adhesive.
.5 Deliver to site, upon completion of the work of this section.
.6 Store where directed by Consultant.

## PART 2 - PRODUCTS

2.1 Materials

.1 Floor Patch
  .1 Portland cement-based compound that has a minimal resistance to compression of 246 kg/cm$^2$ (3,500 lbs/sq. in.) to fill, smooth or level subfloor imperfections.
  .2 Approved manufacturers:
    .1 TEC330 Feather Edge
    .2 Ardex Feather Finish.

.2 Resilient Sheet Flooring (RSF): to ASTM F 1913, 2000mm wide x 25000mm long roll, 2mm thickness homogenous sheet vinyl flooring, in standard colour selected by Consultant.
- .1 IQ OPTIMA as manufactured by Tarkett.
- .2 SPHERA ELEMENT, as manufactured by Forbo.
- .3 MIPOLAM AFFINITY, as manufactured by Gerflor.
- .4 PALETTONE, as manufactured by Polyflor.

.3 Resilient base (RB): to CAN4.102.2-M83, toeless rubber, minimum 1200mm length and 100mm high x 3.175mm thick, including premoulded end stops and external corners, of standard colour selected by Consultant.
- .1 Acceptable Material: Roppe Pinnacle/ Pinnacle Plus, Johnsonite Dura Cove/ Tight Lock.

.4 One Piece Rubber Stair Tread/ Risers (RTR)
- .1 To ASTM F2169 and as follows:
- .2 Nominal thickness: 3.5mm (0.138”) thick.
- .3 Size: one piece rubber tread, full width of stairs with integral riser, square nose, standard light colour, with visually impaired strip (black in colour).
- .4 Surface: hammered finish with integral visually impaired 50mm (2”) contrasting carborundum strip (black in colour).
- .6 Manufacturer’s warranty: Ten (10) year limited commercial warranty, free from defects.
- .7 Installation warranty: Three (3) years on installation defects to include, but not limited to, gapping, lack of adhesive transfer, improper adhesive product, improper nosing compound and cove filler strip installation and proper installation of specified adhesive.
- .8 Colour: light, contrasting with carborundum strip, as selected by Consultant from manufacturer’s complete range.
- .9 Accessories: Cove filler strips and nosing compound.
- .10 Approved manufacturers:
  - .1 Amtico Marathon Rubber Collection
  - .2 Flexco Radial II Flextone
  - .3 Johnsonite Roundel
  - .4 Roppe Raised Design

.5 Primers and adhesives: waterproof, recommended by flooring manufacturer for specific material on applicable substrate, above, at or below grade.

.6 Sub-floor filler and leveller: white premix latex requiring water only to produce cementitious paste as recommended by flooring manufacturer for use with their product.

.7 Metal edge strips: aluminum extruded, smooth, polished with lip to extend under floor finish, shoulder flush with top of adjacent floor finish.

.8 Reducer strips: wheelchair accessible rubber reducer strips by Johnsonite. Colour to be selected.

.9 Sealer: type as recommended by flooring manufacturer.

.10 Wax: type as recommended by flooring manufacturer.

## PART 3 - EXECUTION

3.1 Examination

.1 Examine the subfloor before installation to ensure that the surface is clean, dry, smooth, structurally sound, and free from foreign substances, powder, scaling that may adversely affect adhesion or cause discoloration. Furthermore, ensure that the subfloor is free of paint, varnish, adhesive, oil, grease, solvent including treatment compounds, sealers and curing compounds that may adversely affect adhesion or alter the appearance or durability of the flooring.

.2 Slabs that have been either using a curing agent or a sealer will have to be treated to ensure that the adhesion has not been impaired.
.3 Measure the humidity and pH levels in the concrete in compliance with the following standards before installation:
  .1 ASTM F2170, Relative Humidity (RH) test using in situ probes. The maximum allowable reading is 85% RH.
  .2 ASTM F710, pH levels (test procedure 5.3.1). Preferred readings between 8 & 11.
  .3 The ASTM test frequency recommendation is 3 tests for the first 92.9 sq. m and one test for each additional 92.9 sq. m.
.4 Submit test results to Consultant in writing.
.5 Report and rectify all unsatisfactory conditions. Do not start flooring installation until all rectifications have been completed.

3.2 Preparation

.1 Mechanically remove all surface contaminants such as paint, varnish, adhesive, oil, grease, solvent as well as various other products such as treatment compounds.
.2 Clean floor of dust, mold, mildew, alkaline salts, and other foreign material. Vacuum substrate.
.3 Level all rough surfaces and fill cracks and marks with floor patch as specified. Trowel and float to leave a smooth, flat hard surface.
.4 Ensure Moisture, Relative Humidity and pH tests have all been conducted and measurements meet manufacturer’s recommendations.
.5 In case of doubt, test the adhesion on the concrete subfloor or other surface that will be covered by the flooring. Do the test using the specified flooring and recommended adhesive.
.6 Where floor substrate flatness and levelness tolerances do not meet minimum requirements to begin installation, prepare substrate in accordance with NFCA Floor Covering Reference Manual.

3.3 Application: Sheet Flooring

.1 Provide a high ventilation rate, with maximum outside air, during installation, and for 48 to 72 hours after installation. If possible, vent directly to the outside. Do not let contaminated air recirculate through a district or whole building air distribution system. Maintain extra ventilation for at least one month following building occupation.
.2 Apply adhesive uniformly using recommended trowel. Do not spread more adhesive than can be covered by flooring before initial set takes place.
.3 Lay flooring to produce a minimum number of seams. Border widths to be minimum 1/3 width of full material.
.4 Run sheets in direction of traffic. Double cut sheet joints and heat weld joints according to manufacturer’s written instructions.
.5 As installation progresses, and after installation roll flooring with 45kg minimum roller to ensure full adhesion.
.6 Cut flooring neatly around fixed objects.
.7 Install flooring in pan type floor access covers. Maintain floor pattern.
.8 Continue flooring over areas which will be under built-in furniture.
.9 Terminate flooring at centreline of door in openings where adjacent floor finish or colour is dissimilar.
.10 Refer to Drawings for patterns/ insets. Patterns may include up to four different colours.
.11 Install metal edge strips at unprotected or exposed edges where flooring terminates.

3.4 Base Application

.1 Lay out base to keep number of joints at minimum. Base joints at maximum length available or at internal or premoulded corners.
.2 Clean substrate and prime with one coat of adhesive.
.3 Apply adhesive to back of base.
.4 Set base against wall and floor surfaces tightly by using 3 kg hand roller.
.5 Install straight and level to variation of 1:1000.
.6 Scribe and fit to door frames and other obstructions.
.7 Cope internal corners. Use premoulded corner units for right angle external corners. Use formed straight base material for external corners of other angles, minimum 300 mm each leg.

3.5 Initial Cleaning and Waxing

.1 Remove excess adhesive from floor, base and wall surfaces with products and procedures recommended by manufacturer, without damage.
.2 Clean, seal and wax floor and base surface to flooring manufacturer's instructions.

3.6 Protection of Finished Work

.1 Protect new floors from time of final set of adhesive to after initial waxing until final waxing to final inspection.
.2 Prohibit traffic on floor for 48 hours after installation.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 References

.1 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-4.2- 92, Textile Test Methods.
  .2 CAN/CGSB-4.129- 93, Carpets for Commercial Use.
  .3 CAN/CGSB-25.20- 95, Surface Sealer Floors.
.2 Underwriters' Laboratories of Canada
  .1 CAN/ULC-S102.2- M88, Surface Burning Characteristics of Flooring, Floor Covering and Miscellaneous Materials and Assemblies.
.3 Carpet and Rug Institute (CRI)
  .1 Contract Carpet Manual, No.001.
  .2 IAQ Carpet Testing Program.

1.3 Submittals

.1 Submit control submittals in accordance with Section 01 33 00 - Submittal Requirements.
.2 Manufacturer's Instructions: Provide to indicate special handling criteria, installation sequence, cleaning procedures and.

1.4 Product Data

.1 Submit product data in accordance with Section 01 33 00 - Submittal Requirements.
.2 Submit product data sheet for each carpet, adhesive, and subfloor filler.
.3 Submit WHMIS MSDS - Material Safety Data Sheets acceptable to Labour Canada and Health and Welfare Canada for carpet adhesive and seam adhesive. Indicate VOC content.

1.5 Samples

.1 Submit samples in accordance with Section 01 33 00 - Submittal Requirements.
.2 Submit duplicate 300mm x 300mm pieces for each carpet type colour selected, 150mm lengths of carpet gripper and binder bars and divider strips.

1.6 Closeout Submittals

.1 Submit operation and maintenance data for incorporation into manual specified in Section 01 78 00 – Closeout Submittals.
.2 Include information on recycling of carpet including manufacturer's reprocessing program. Indicate which portions of materials are recyclable.

1.7 Delivery, Storage and Handling

.1 Label packaged materials. For tile products indicate nominal dimensions of tile.
.2 Packaging, labelling, packing and marking details.
.3 Store packaged materials in original containers or wrapping with manufacturer's seals and labels intact.
.4 Store carpeting and accessories in location as directed by Consultant.

.5 Prevent damage to materials during handling and storage. Keep materials under cover and free form dampness.
.6 Maintain temperature of store room at a minimum of 20°C, for at least 24 hours immediately before the installation.

1.8 Project/Site Environmental Requirements

.1 Moisture: Ensure substrate is within moisture limits prescribed by manufacturer Submit documentation of testing prior to starting installation.
.2 Temperature: Maintain ambient temperature of not less than 18 °C from 72 hours before installation to at least 72 hours after completion of work.
.3 Relative humidity: Maintain relative humidity between 10 and 65% RH for 48 hours before, during and 48 hours after installation.
.4 Safety: Comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling, storage, and disposal of hazardous materials.

1.9 Extra Materials

.1 Provide extra materials of carpet, and adhesives in accordance with Section 01 78 00 - Closeout Submittals.
.2 Provide 2% for each colour, pattern and type of carpeting. Provide in one continuous full width roll.
.3 Extra materials to be from same production run as installed materials.
.4 Identify each package of carpet and each container of adhesive.
.5 Deliver to site and store where directed.

## PART 2 - PRODUCTS

2.1 Carpet

.1 Carpet (CP): 1830mm x 32m roll; 813g/$m^2$ face weight, 100% solution dyed, patterned loop; pile height 3.4mm, CLASS 1.
.1 Acceptable Material:
.1 Plexus Colour IV with Powerbond® hybrid carpet, as manufactured by Tandus-Centiva; Colour to be selected by Consultant.

## PART 3 - EXECUTION

3.1 Installation

.1 Install carpeting using minimum of pieces.
.2 Install in accordance with manufacturer's printed instructions.
.3 Install carpeting after finishing work is completed. Coordinate the work with other trades for timing required.
.4 Finish installation to present smooth wearing surface free from conspicuous seams, burring and other faults.
.5 Use material from same dye lot. Ensure colour, pattern and texture match within any one visual area. Maintain constant pile direction.
.6 All seams to receive seam sealing adhesive in strict accordance with manufacturer’s specifications.
.7 Fit neatly around architectural, mechanical, electrical and telephone outlets, and furniture fitments, around perimeter of rooms into recesses, and around projections.
.8 Bind edges of removable carpet runners as indicated on the Room Finish Schedule

.9 Install removable carpet runners with 50mm (2" wide) fabric tape: edges and at 500mm centres both ways.

3.2 Seams

.1 Seal edges of cut-outs with latex.
.2 Make carpet seams and joints invisible.

3.3 Protection of Finished Work

.1 Vacuum carpet clean immediately after completion of installation. Protect traffic areas.
.2 Prohibit traffic on carpet until adhesive is cured.
.3 Install carpet protection to satisfaction of Consultant.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 – General Requirements.

1.2 Related Sections

.1 Section 04 22 00 – Concrete Unit Masonry.
.2 Section 06 40 00 – Architectural Woodwork.
.3 Section 09 21 16 – Gypsum Board Assemblies.
.4 Divisions 21-23/ 26-28: Mechanical and Electrical.

1.3 References

.1 American Society for Testing and Materials (ASTM)

.1 ASTM D 3960 – 05(2013), Practice for Determining Volatile Organic Compound (VOC) Content of Paints and Related Coatings.
.2 Canadian General Standards Board (CGSB)
.1 CAN/CGSB-1.36-97, General Purpose Interior Varnish.
.2 CAN/CGSB-1.38-2000, Interior Enamel Undercoater.
.3 CAN/CGSB-1.100-99, Interior Latex Type, Flat Paint.
.4 CAN/CGSB-1.119-2000, Primer-Sealer, Wall, Interior Latex Type.
.5 CAN/CGSB-1.145-97, Solvent-Based Pigmented Stain.
.6 CAN/CGSB-1.146-99, Cold Curing, Gloss Epoxy Coating.
.7 CAN/CGSB-1.150-M91, Clear Lacquer for Wood Furniture.
.8 CAN/CGSB-1.165-2004, Cold Curing Epoxy Primer.
.9 CAN/CGSB-1.188-2004, Emulsion Type Filler Masonry Block.
.10 CAN/CGSB-1.195-99, Interior Semigloss Latex Paint.
.11 CAN/CGSB-1.198-2001, Cementitious Primer (for Galvanized Surfaces).
.12 CAN/CGSB-1.209-2003, Low Sheen Latex Interior Paint.
.13 CAN/CGSB-85.10-99, Shop Painting Structural Steel.
.3 Master Painters Institute (MPI).
.1 Architectural Painting Specification Manual.
.4 Canadian Standards Association (CSA)
.1 CSA Z760-94 (R2001), Life Cycle Assessment.
.5 Society for protective Coatings (SSPC).
.1 SSPC Painting Manual.

1.4 Description

.1 Read carefully all other Sections of the Specifications to determine the extent of prime and finish coats applied by other Sections.
.2 See Mechanical Divisions 21-23 and Electrical Division 26-28 for instructions on painting work to be done by Section 09 91 10 on surface provided by those Divisions.
.3 Gloss range: paint and varnish textures are specified by their gloss type, which is defined by the dried film sheen factor. Refer to:
.1 MPI Painting Specification Manual - GLOSSARY OF TERMS to determine Sheen Factor for various gloss types.
.2 Locations A: Vest./ Corridors/ Stairs/ Washrooms/ Custodial/ Storage Areas
(1) block - MPI Gloss Level 7 (high gloss)
(2) gypsum board - MPI Gloss Level 3 (eggshell)
(3) doors/ frames - MPI Gloss Level 5 (semi gloss)
(4) wood - MPI Gloss level 5 (semi gloss)

.3 Locations B: Remaining Areas
(1) block - MPI Gloss Level 5 (semi gloss)
(2) gypsum board - MPI Gloss Level 3 (eggshell)
(3) doors/ frames - MPI Gloss Level 5 (semi gloss)
(4) wood - MPI Gloss level 5 (semi gloss)

1.5 Product Data

.1 Submit product data in accordance with Section 01 33 00 – Submittal Procedures.
.2 Submit full records of all products used. List each product in relation to finish formula and include the following:
.1 Finish formula designation.
.2 Product type and use.
.3 CGSB number.
.4 Manufacturer's product number.
.5 Colour numbers.
.6 Manufacturer's Material Safety Data Sheets (MSDS).
.7 Maximum VOC classification.
.3 Submit manufacturer's application instructions for each product specified.

1.6 Samples

.1 Submit samples in accordance with Section 01 33 00 - Submittal Procedures.
.2 Submit duplicate 300mm x 200mm sample panels of each paint, stain, clear coating, formula, type, colour, and texture specified.
.3 Submit full range of available colours where colour availability is restricted.
.4 Use 3mm plate steel for finishes over metal surfaces. Use 12.5mm maple plywood for finishes over wood surfaces. Use 12.5mm gypsum board for finishes over gypsum board and other smooth surfaces.

1.7 Quality Assurance

.1 Retain purchase orders, invoices and other documents to prove that all materials utilized in this contract meet requirements of the specifications. Produce documents when requested by Consultant.
.2 Standard of Acceptance:
.1 Walls: No defects visible from a distance of 1000mm at 90º to surface.
.2 Ceilings: No defects visible from floor at 45º to surface when viewed using final lighting source.
.3 Final coat to exhibit uniformity of colour and uniformity of sheen across full surface area.

1.8 Delivery, Storage and Handling

.1 Deliver, store, handle and protect materials in accordance with Section 01 61 00 – Basic Product Requirements.
.2 Deliver and store materials in original containers, sealed, with labels intact.
.3 Indicate on containers or wrappings:
.1 Manufacturer's name and address.
.2 Type of paint.
.3 Compliance with applicable standard.
.4 Colour number in accordance with established colour schedule.
.4 Remove damaged, opened and rejected materials from site.
.5 Provide and maintain dry, temperature controlled, secure storage.
.6 Observe manufacturer's recommendations for storage and handling.
.7 Store materials and supplies away from heat generating devices.
.8 Store materials and equipment in a well ventilated area with temperature range 7 - 30°C.

.9 Store temperature sensitive products above minimum temperature as recommended by manufacturer.
.10 Keep areas used for storage, cleaning and preparation, clean and orderly to approval of Consultant. After completion of operations, return areas to clean condition to approval of Consultant.
.11 Remove only in quantities required for same day use.
.12 Fire Safety Requirements:
.1 Store oily rags, waste products, empty containers and materials subject to spontaneous combustion in ULC approved, sealed containers and remove from site on a daily basis.
.2 Handle, store, use and dispose of flammable and combustible materials in accordance with the National Fire Code of Canada.

1.9 Environmental Requirements

.1 Safety: comply with requirements of Workplace Hazardous Materials Information System (WHMIS) regarding use, handling storage, and disposal of hazardous materials.
.2 Apply paint finishes only when temperature at location of installation can be satisfactorily maintained within manufacturer's recommendations.
.3 Substrate and ambient temperature must be within limits prescribed in paint standard and by manufacturer to approval of Consultant.
.4 Maintain minimum substrate and ambient air temperature of 7°C for latex paints. Maximum relative humidity 85%. Maintain supplemental heating until paint has cured sufficiently.
.5 Provide temporary heating where permanent facilities are not available to maintain minimum recommended temperatures.
.6 Apply paint finish only in areas where dust is no longer being generated by related construction operations such that airborne particles will not affect the quality of the finished surface.
.7 Apply paint only when surface to be painted is dry, properly cured and adequately prepared.
.8 Provide minimum 270 lx on surfaces to be painted.

1.10 Extra Materials

.1 Submit maintenance materials in accordance with Section 01 78 00 – Closeout Submittals.
.2 Submit one - four litre can of each type and colour of finish coating. Identify colour and paint type in relation to established colour schedule and finish formula.
.3 Deliver to Site and store where directed.

## PART 2 - PRODUCTS

2.1 Paint Materials

.1 Qualified products: only paint materials listed on the MPI Qualified Products List are acceptable for use on this project.
.2 Qualified products: only varnish, stain, enamel, lacquer and filler materials listed on the MPI Approved Product Lists are acceptable for use on this project producing a flame spread rating of less 150.
.3 Paint materials for each coating formula to be products of a single manufacturer.
.4 Low odour products: Whenever possible, select products exhibiting low odour characteristics.

2.2 Paint Colours

.1 Colours will be selected by Consultant. Note: There will be up to 6 different colours used.
.2 Perform **all** colour tinting operations prior to delivery of paint to site.
.3 Second coat in a three coat system to be tinted slightly lighter colour than top coat to show visible difference between coats.

2.3 Paint Finishes - INTERIOR

.1 Concrete and Lightweight Block - Locations A – INT 4.2J Epoxy – Modified Latex, Interior, MPI Gloss Level 5 (semi-gloss)
  .1 Two coats MPI #4; spray applied and back rolled to fill **all** pin holes, and as required by block texture.
  .2 Two coats MPI #215; approved Devoe Coatings Tru-Glaze WB 4426 waterborne.
.2 Concrete and Lightweight Block - Locations B – INT 4.2D Latex, Interior, High Performance Architectural, MPI Gloss Level 5 (semi-gloss)
  .1 Two coats MPI #4; spray applied and back rolled to fill **all** pin holes, and as required by block texture.
  .2 Two coats MPI #153; Interior, Acrylic #13210.
.3 Gypsum Drywall – walls below 2400mm above finish floor – INT 9.2B Latex, Interior, High Performance Architectural, MPI Gloss Level 3 (eggshell)
  .1 One coat MPI #50; Interior, Latex #59113
  .2 Two coats MPI #153; Interior, Acrylic #13210.
.4 Gypsum Drywall – walls above 2400mm above finish floor/ bulkheads/ ceilings – INT 9.2M Latex, Interior, Institutional, Low Odour/ VOC, MPI Gloss Level 1 (flat)
  .1 One coat MPI #149; Interior, Latex #59113
  .2 Two coats MPI #143; Interior, Acrylic #59111.
.5 Plaster – RIN 9.2B; MPI Maintenance Repainting Manual; MPI Gloss Level 5 (semi-gloss)
  .1 One coat MPI #137; approved Dulux Gripper #60000
  .2 Two coats MPI #54; approved Dulux Diamond, Interior #13210
.6 Metal (Ferrous) – INT 5.1B – Light Industrial Coating, Interior, Water Based, MPI Gloss Level 5 (semi-gloss)
  .1 One coat MPI #107; approved – Pitt-Tech Int/Ext DTM Industrial #90-712
  .2 Two coats MPI #153; approved – Dulux Diamond Interior Acrylic #13210.
.7 Wood – Opaque Finish (P) – INT 6.3A – Latex High Performance Architectural, MPI Gloss Level 5 (semi-gloss)
  .1 One coat primer; MPI #39; approved – Dulux Gripper #60000
  .2 Two coats MPI #141; approved – Dulux Diamond Interior Acrylic #13210.
.8 Exposed Insulated Pipes and Ductwork – INT 10.1A – Latex, Interior, Institutional, Low Odour/ VOC, MPI Gloss Level 1 (flat)
  .1 One coat MPI #149; Interior, Latex #59113
  .2 Two coats MPI # 143; Interior Acrylic #59111
.9 Interior Copper and Aluminum (Mill Finish) – INT 5.4M - Latex, Interior, High Performance Architectural, MPI Gloss Level 5 (semi gloss)
  .1 One coat MPI #95; approved Devoe Devguard #4630, Low VOC
  .2 Two coats MPI #153; approved DULUX Diamond, Interior, Acrylic #13210
.10 High Temperature Pipe and Fittings – INT 5.2 - Heat Resistant Enamel, 205°C (400°F)
  .1 Two coats MPI #21; approved Devoe HT-4H High Temperature Silicone Acrylic.

2.4 Paint Finishes - EXTERIOR

.1 Metal (Ferrous) - EXT 5.1 – Light Industrial Coating, Exterior, Water Based, MPI Gloss Level 5 (semi gloss)
  .1 One coat MPI #107; approved Devoe Devflex #4020 DTM
  .2 Two coats MPI #156; approved Devoe Devflex #4206 QD Exterior/ Interior Waterborne.

.2 Wood Soffits & Fascia EXT 6.3P High Performance Architectural Latex Exterior, MPI Gloss Level 5 (semi-gloss)
.1 One coat MPI #6; Dulux Multi-purpose Latex Primer / Sealer #1535
.2 Two coats MPI #11; Dulux Diamond #1650.

## PART 3 - EXECUTION

3.1 General

.1 Perform all painting operations in accordance with CAN/CGSB-85.100 except where specified otherwise.
.2 Perform all painting operations in accordance with MPI Painting Specifications Manual except where specified otherwise.
.3 Apply all paint materials in accordance with paint manufacturer's written application instructions.

3.2 Preparation

.1 Remove electrical cover plates, light fixtures, surface hardware on doors, door stops, bath accessories and all other surface mounted fittings and fastenings prior to undertaking any painting operations. Store for re-installation after painting is completed.
.2 Move and cover furniture and portable equipment as necessary to carry out painting operations. Replace as painting operations progress.
.3 As painting operations progress, place "WET PAINT" signs in occupied areas to approval of Consultant.

3.3 Protection

.1 Protect existing building surfaces not to be painted from paint spatters, markings and other damage. If damaged, clean and restore such surfaces as directed by Consultant.
.2 Cover or mask floors, windows and other ornamental hardware adjacent to areas being painted to prevent damage and to protect from paint drops and splatters. Use non-staining coverings.
.3 Protect items that are permanently attached such as Fire Labels on doors and frames.
.4 Protect factory finished products and equipment.
.5 Protect passing pedestrians, building occupants and the general public in and about the building.

3.4 Conditions of Work

.1 Investigate existing substrates for problems related to proper and complete preparation of surfaces to be painted. Report all damage, defects, unsatisfactory or unfavourable conditions before proceeding with work.
.2 Investigate moisture content of surfaces to be painted and report findings. Do not proceed with work until conditions fall within acceptable range as recommended by manufacturer.
.3 Maximum moisture content as follows:
.1 Plaster and wallboard: 12%.
.2 Masonry/Concrete: 12%.
.3 Concrete Block/Brick: 12%.
.4 Wood: 15%.

3.5 Cleaning

.1 Clean all surfaces to be painted as follows:
.1 Remove all dust, dirt, and other surface debris by vacuuming, wiping with dry, clean cloths or compressed air.
.2 Wash surfaces with solution of T.S.P. and clean warm water using a stiff bristle

brush to remove dirt, oil and other surface contaminants.

.3 Rinse scrubbed surfaces with clean water until foreign matter is flushed from surface.

.4 Allow surfaces to drain completely and allow to dry thoroughly.

.5 To prepare surfaces for water-based painting, water-based cleaners should be used in place of organic solvents.

.6 Use trigger operated spray nozzles for water hoses.

.7 Many water-based paints cannot be removed with water once dried. However, minimize the use of kerosene or any such organic solvents to clean up water-based paints.

.2 Prevent contamination of cleaned surfaces by salts, acids, alkalis, other corrosive chemicals, grease, oil and solvents before prime coat is applied and between applications of remaining coats. Apply primer, paint, or pre-treatment as soon as possible after cleaning and before deterioration occurs.

.3 Sand existing surfaces with intact, smooth, high gloss coatings to provide adequate adhesion for new finishes.

3.6 Surface Preparation

.1 Prepare new wood surfaces to CGSB 85-GP-1M.

.2 Where possible, prime all surfaces of new wood surfaces before installation. Use same primers as specified for exposed surfaces.

.3 Prepare previously painted wood surfaces to CGSB 85-GP-2M.

.1 Apply vinyl sealer to CAN/CGSB-1.126 over knots, pitch, sap and resinous areas.

.2 Apply wood filler to nail holes and cracks.

.3 Tint filler to match stains for stained woodwork.

.4 Prepare stucco, brick, concrete masonry and concrete surfaces to CGSB 85-GP-31M.

.5 Prepare concrete floors to CGSB 85-GP-32M. Prepare new concrete floor by acid etching. Rinse with clean water and thoroughly dry.

.6 Prepare plaster and wallboard surfaces to CGSB 85-GP-33M.

3.7 Surface Preparation - Metal

.1 Clean new metal surfaces to be painted by: removing rust, loose mill scale, welding slag, dirt, oil, grease and other foreign substances in accordance with the following:

.1 Solvent cleaning: SSPC-SP-1.

.2 Hand tool cleaning: SSPC-SP-2.

.3 Power tool cleaning: SSPC-SP-3.

.4 Commercial blast cleaning: SSPC-SP-6.

.5 Brush-off blast cleaning: SSPC-SP-7.

.2 Touch up shop primer to CGSB 85-GP-10M with primer as specified in applicable section. Touch-up to include cleaning and painting of field connections, welds, rivets, nuts, washers, bolts, and damaged or defective paint and rusted areas.

.3 Prepare galvanized steel and zinc coated steel surfaces to CGSB 85-GP-16M.

.4 Prepare copper and copper alloys surfaces to CGSB 85-GP-20M.

.5 Prepare new steel surfaces exposed normally to dry conditions to CGSB 85-GP-14M.

.6 Prepare previously painted steel surfaces exposed normally to dry conditions to CGSB 85-GP-15M.

.7 Prepare steel surfaces exposed to industrial environments to CGSB 85-GP-13M.

.8 Prepare steel surfaces exposed to water or high humidity levels to CGSB 85-GP-11M CGSB 85-GP-18M.

.9 Ductwork:
Wash thoroughly all ductwork to be exposed and painted in completed work with mineral spirits and wipe dry with completely clean cloths. Phosphatize galvanized metal surfaces using CGSB-31-GP-116 pretreatment or prime with galvanized metal primer.

.10 Do not apply paint until prepared surfaces have been accepted by Consultant.

3.8 Mixing Paint

.1 Mix ingredients in container before and during use and ensure breaking up of lumps, complete dispersion of settled pigment, and uniform composition.
.2 Thin paint for spraying according to manufacturer's instructions. If directions are not on container, obtain instructions in writing from manufacturer and provide copy of instructions to Consultant.
.3 Do not use kerosene or any such organic solvents to thin water-based paints.

3.9 Application

.1 Method of application to be as approved by Consultant. Apply paint by brushroller except where spraying is necessary to achieve acceptable finish. Conform to paint manufacturer's application instructions unless specified otherwise.
.2 Brush/ roller application.
  .1 Work paint into cracks, crevices and corners. Paint surfaces not accessible to brushes by spray, daubers or sheepskins.
  .2 Brush out runs and sags.
  .3 Remove runs, sags and brush marks from finished work and repaint.
.3 Spray application.
  .1 Provide 6mil poly dust curtains around rooms being sprayed to prevent transfer of paint and odour to other rooms.
  .2 Provide and maintain equipment that is suitable for intended purpose, capable of properly atomizing paint to be applied, and equipped with suitable pressure regulators and gauges.
  .3 Keep paint ingredients properly mixed in containers during paint application either by continuous mechanical agitation or by intermittent agitation as frequently as necessary.
  .4 Apply paint in a uniform layer, with overlapping at edges of spray pattern.
  .5 Brush out immediately all runs and sags.
  .6 Use brushes to work paint into cracks, crevices and places which are not adequately painted by spray.
.4 Use dipping, sheepskins or daubers only when no other method is practical in places of difficult access and only when specifically authorized by Consultant.
.5 Apply each coat of paint as a continuous film of uniform thickness. Repaint thin spots or bare areas before next coat of paint is applied.
.6 Allow surfaces to dry and properly cure after cleaning and between subsequent coats for minimum time period as recommended by manufacturer.
.7 Sand and dust between each coat to remove visible defects.
.8 Finish tops of cupboards, cabinets and projecting ledges, both above and below sight lines as specified for surrounding surfaces.
.9 Finish inside of cupboards and cabinets as specified for outside surfaces.
.10 Finish closets and alcoves as specified for adjoining rooms.
.11 Finish top, bottom, edges and cutouts of doors after fitting as specified for door surfaces.
.12 Apply final coat of paint after inspection and correction of deficiencies and installation of flooring have been completed.

3.10 Mechanical and Electrical Equipment

.1 In finished areas: paint exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment. Colour and texture to match adjacent surfaces, except as noted otherwise.
.2 In boiler room, mechanical and electrical rooms: paint exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment.
.3 In other unfinished areas: leave exposed conduits, piping, hangers, ductwork and other mechanical and electrical equipment in original finish and touch up scratches and marks.
.4 Touch up scratches and marks on factory painted finishes and equipment with paint as supplied by manufacturer of equipment.

.5 Do not paint over nameplates.
.6 Keep sprinkler heads free of paint.
.7 Paint inside of ductwork where visible behind grilles, registers and diffusers with primer and one coat of matt black paint.
.8 Paint disconnect switches for fire alarm system and exit light systems in red enamel.
.9 Paint all fire protection piping red, unless directed otherwise.
.10 Paint all natural gas piping yellow, unless directed otherwise.
.11 Paint both sides and edges of backboards for telephone and electrical equipment before installation. Leave equipment in original finish except for touch-up as required, and paint conduits, mounting accessories and other unfinished items.

3.11 Field Quality Control

.1 Field inspection of painting operations to be carried out by independent inspection firm as designated by Consultant.
.2 Advise Consultant when each applied coating is ready for inspection. Do not proceed with subsequent coats until previous coat has been approved.
.3 Co-operate with inspection firm and provide access to all areas of the work.

3.12 Restoration

.1 Clean and re-install all hardware items that were removed before undertaken painting operations.
.2 Remove protective coverings and warning signs as soon as practical after operations cease.
.3 Remove paint splashings on exposed surfaces that were not painted. Remove smears and spatter immediately as operations progress, using compatible solvent.
.4 Protect freshly completed surfaces from paint droppings and dust to approval of Consultant. Avoid scuffing newly applied paint.
.5 Restore areas used for storage, cleaning, mixing and handling of paint to clean condition as approved by Consultant.

END OF SECTION

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements.

1.2 Related Sections

.1 Section 06 10 10 – Rough Carpentry.
.2 Section 09 21 16 – Gypsum Board Assemblies.

1.3 References

.1 American Society for Testing and Materials (ASTM)
  .1 ASTM A167 - 99(2009), Standard Specification for Stainless and Heat-Resisting Chromium-Nickel Steel Plate, Sheet, and Strip.
  .2 ASTM B456 - 17, Standard Specification for Electrodeposited Coatings of Copper Plus Nickel Plus Chromium and Nickel Plus Chromium.
  .3 ASTM A 653/ A653M - 17, Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
  .4 ASTM A924/ A924M - 17a, Standard Specification for General Requirements for Steel Sheet, Metallic-Coated by the Hot-Dip Process.
.2 Canadian General Standards Board (CGSB)
  .1 CAN/CGSB-1.81-M90, Air Drying and Baking Alkyd Primer for Vehicles and Equipment.
  .2 CAN/CGSB-1.88-92, Gloss Alkyd Enamel, Air Drying and Baking.
  .3 CAN/CGSB-12.5-M86, Mirrors, Silvered.
  .4 CGSB 31-GP-107Ma, Non-inhibited Phosphoric Acid Base Metal Conditioner and Rust Remover.
.3 Canadian Standards Association (CSA)
  .1 CAN/CSA-B651-12 (R2017), Barrier-Free Design.
  .2 CAN/CSA-G164-M92 (R2003), Hot Dip Galvanizing of Irregularly Shaped Articles.

1.4 Shop Drawings

.1 Submit shop drawings in accordance with Section 01 33 00 Submittal Requirements.
.2 Indicate size and description of components, base material, surface finish inside and out, hardware and locks, attachment devices, description of rough-in-frame, building-in details of anchors for grab bars.

1.5 Samples

.1 Submit samples in accordance with Section 01 33 00 Submittal Requirements.
.2 Samples to be returned for inclusion into work.

1.6 Closeout Submittals

.1 Provide maintenance data for toilet and bath accessories for incorporation into manual specified in Section 01 78 00 – Closeout Submittals.

1.7 Extra Materials

.1 Provide special tools required for accessing, assembly/disassembly or removal for toilet accessories in accordance with requirements specified in Section 01 78 00 – Closeout Submittals.
.2 Deliver special tools to Owner.

1.8 Acceptable Products

.1 Products listed are based on Bobrick model numbers, unless noted otherswise.
.2 Products manufactured by Saferail and Watrous/ ASI meeting or exceeding specified performance are acceptable.

## PART 2 - PRODUCTS

2.1 Materials

.1 Sheet steel: to ASTM A 653/A653M with G90 designation zinc coating.
.2 Stainless steel sheet metal: to ASTM A 167, Type 302, with No.4 finish.
.3 Stainless steel tubing: Type 304, commercial grade, seamless welded, 1.2mm wall thickness.
.4 Fasteners: concealed screws and bolts hot dip galvanized, exposed fasteners to match face of unit. Expansion shields fibre, lead or rubber as recommended by accessory manufacturer for component and its intended use.

2.2 Components

.1 Toilet tissue dispenser: Provided by Owner, installed by Contractor.
.2 Soap dispenser: Provided by Owner, installed by Contractor.
.3 Paper towel dispenser: Provided by Owner, installed by Contractor.
.4 Feminine napkin disposal bin: type 304 stainless steel surface mounted unit, all-welded construction, continuous hinged door, self closing.
.1 Acceptable material: Bobrick - Model # B-254.
.5 Mirror (MIR1): wall mounted unit, fixed framed mirror 6mm to CAN/CGSB-12.5, stainless steel frame.
.1 Acceptable material: Bobrick - Model No. B-165 2436.

2.3 Fabrication

.1 Weld and grind joints of fabricated components flush and smooth. Use mechanical fasteners only where approved.
.2 Wherever possible form exposed surfaces from one sheet of stock, free of joints.
.3 Brake form sheet metal work with 1.5mm radius bends.
.4 Form surfaces flat without distortion. Maintain flat surfaces without scratches or dents.
.5 Back paint components where contact is made with building finishes to prevent electrolysis.
.6 Hot dip galvanize concealed ferrous metal anchors and fastening devices to CSA G164.
.7 Shop assemble components and package complete with anchors and fittings.
.8 Deliver inserts and rough-in frames to job site at appropriate time for building-in. Provide templates, details and instructions for building in anchors and inserts.
.9 Provide steel anchor plates and components for installation on studding and building framing.

2.4 Finishes

.1 Chrome and nickel plating: to ASTM B456, satin finish.
.2 Manufacturer's or brand names on face of units not acceptable.

## PART 3 - EXECUTION

3.1 Installation

.1 Install and secure accessories rigidly in place as follows:
  .1 Stud walls: install wood blocking to/ between studs prior to plaster or drywall finish.
  .2 Hollow masonry units or existing plaster/drywall: use toggle bolts drilled into cell/wall cavity.
.2 Install grab bars on built-in anchors provided by bar manufacturer. Install rod supports provide by manufacturer for swing up grab bars in part steel stud/ gypsum board partition walls.
.3 Use tamper proof screws/bolts for fasteners.
.4 Fill units with necessary supplies shortly before final acceptance of building.

3.2 Schedule

.1 Locate accessories where indicated on Drawings. Exact locations determined by Consultant.

END OF SECTION

## PART 1 - GENERAL

1.1. General Requirements

.1 Conform to Division 01 - General Requirements.

1.2. Work Included

.1 Manufacture, deliver fixed chairs with self-lifting seats which rise automatically to a uniform fold position. Chairs will be manufactured and installed in accordance with applicable codes, the following specifications and approved drawings. The basis of design is Audience Systems Limited.

1.3. Quality Assurance

.1 Manufacturer: Company specializing in seating with a minimum of ten years' experience in manufacturing seating.
.2 Engineer Qualifications: Manufacturer to employ a registered licensed professional engineer to certify that the equipment to be supplied meets or exceeds the design criteria of this specification.
.3 Installation: Shall be handled directly by the manufacturer or by a factory certified installation sub-contractor.
.4 Product Liability: Certification of insurance coverage for the life of the product.
.5 Welding Processes: To be performed by certified professional welding contractors in accordance with AWSD1.1
.6 Product Improvements: Equipment provided shall incorporate manufacturer's design improvements and materials current at time of shipment, provided that such improvements and materials are consistent with the intent of these specifications.

1.4. Submittals

.1 Submit in accordance with Section 01 33 00 – Submittal Procedures.
  .1 Manufacturer's specifications.
  .2 Plan View and Section Drawings providing full layout details and seating capacities.
  .3 Shop drawings showing all equipment to be furnished.
  .4 Samples of material and colour finish as requested by Consultant.
  .5 Warranty, operation and maintenance instructions to the Owner upon completion.

1.5. Design Criteria

.1 Chairs
  .1 Seats shall be cantilevered, self-centering, automatic lift, maximizing seatway upon seat lift for ease of passage and janitorial access.
  .2 Seats shall be tested and certified to support and withstand an evenly distributed load of 600 lbs. (272kg.).
  .3 Seats shall be tested and certified to ASTM Designation F851-87 Test Method for Self-Rising Mechanism.
.2 Material Flammability: Shall satisfy applicable test, codes, standards, of requirements as follows:
  .1 Polyethylene or polypropylene where used shall meet the Federal Motor Vehicles Safety Standard No. 302 which specifies a burning rate of less than 4" per minute.

.2 Upholstery materials
.3 Where used meet Class 1 requirements of U.S. Department of Commerce, CS 191-52, as required by the State of California Home Furnishings bulletin 117.
.4 Cushioning and padding meet California Bulleting 117, Resilient Cellular Materials Section A & D dated February 1975 when tested in accordance with Federal Test Method Standard 191, Method 5903.2.

1.6. Warranty

.1 The manufacturer shall warrant all work performed under these specifications to be free of defects for a period of two years.
.2 Any materials found to be defective within this period will be replaced at no cost to the Owner.

## PART 2 - PRODUCTS

2.1 Manufacturers

.1 Where products are named by manufacturers, it is intended to establish a level of quality and performance which all bidders shall meet or exceed. The Specification requirements are based on those of Audience Systems Ltd.

2.2 Dimensions

.1 Chair dimensions, seatways and all other aspects of layout are as indicated on the Drawings. Dimensions must be strictly adhered to. Note: No exceptions and/ or substitution will be permitted

2.3 Fabrication

.1 Chair Type: Tread Fixed and Removable.
  .1 Chair shall be Audience Systems Espace 628 chair with upholstered seat and back. Chair shall have a gravity tip mechanism for automatically lifting the seat to uniform folded position without the need for a spring. Chairs must be grouped in quantities and locations as indicated on Drawings.
  .2 Beam mounted design, consisting of tread fixed leg and beam assemblies and chair assemblies.
    .1 Tread fixed leg and beam assembly: Consisting of a transverse beam to facilitate chair position, tubular steel legs and pressed steel feet.
  .3 Chair Assemblies: Comprising standard/ armrest assemblies, upholstered seat and upholstered back.
    .1 Cast aluminum standard/ armrest assemblies: when mounted to the transverse beam, these will support the seats and backs and coordinate the action of the armrest, seat, and back. The armrest subassembly will be spring assisted in its operation. The armrest shall be lacquered hardwood.
    .2 Upholstered seat – wood pan: Seat shall be an upholstered plywood base construction including a waterfall front edge. The plywood base shall have a 50mm (2”) ergonomically shaped polyurethane foam pad which will be adhered to the base. The upper side of the seat pan will be upholstered in the specified fabric. The specified fabric cover will be secured to the seat in full side wrap to maximize the retention means. Seats outer panel to be 12.7mm (½”) thick “A” Grade veneer Flat Cut

Hard Maple on Baltic Birch plywood cores. Seat panels to be secured to the upholstered section of the seat with non-visible fasteners.

.3 Upholstered Standard Height Back – Wood Outer Panel: Upholstered Backs shall consist of 12.7mm (½") thick cross-banded plywood padded with 45mm (1¾") polyurethane foam and upholstered in the specified fabric presenting a strong, attractive unified assembly. To consist of a Timber core, with CMHR/CME polyurethane foam, upholstered on the front face. Backs to incorporate a show timber panel to the outer back "A" Grade veneer Flat Cut Hard Maple on 12.7mm (½") curved plywood cores finished to Consultant's sample. Veneers on exposed backs to be centre balanced on the exposed side of the back fabric, to be chosen from manufacturer's standard selection.

.4 Fabric: To be chosen from manufacturer's standard selection.

.5 Seat numbers: Seat number plates shall be located on underside of seat and shall have etched aluminum finish with black numbers and letters. Dimensions: 35mm x 15.9mm x 1.5mm (1⅜" x ⅝" x 1/16").

.6 Row letters: Row letters shall consist of anodized aluminum plate with screen printed letters in black. Dimensions: 60mm x 60mm x 1.5mm (2⅜" x 2⅜" x 1/16").

.2 Chair Sizes:

.1 ESPACE 628, WITH WOOD OUTER BACK: Chairs to be 500mm (19⅝") wide.

.3 Chair Dimensions: Espace 628

.1 Seat up envelope: 150mm (6")
.2 Seat down envelope: 640mm (25¼")
.3 Seat height: 457mm (18")
.4 Armrest height: 615mm (24¼")
.5 Back height: 845mm (33¼")

.4 Finish

.1 Metal parts: Epoxy polyester powder coat finish in RAL 9005 black.
.2 Plastic parts: RAL 9005 black.
.3 Fabric: select from manufacturer's standard range.

2.4 Removable Seating

.1 Matrix Floorbar System: Fabricated four stage iron phosphate pre-treatment and epoxy polyester powder coating, colour; matt black RAL 9005.

.2 Provide sufficient floor bars to suit layout of removable seating indicated on Drawings.

2.5 Accessories

.1 Floorbar Trolley: Provide one (1) floor bar trolley.
.2 Fishbone Trolley: Provide one (1) fishbone trolley.

## PART 3 - EXECUTION

3.1 Inspection of Site

.1 Take site measurements to ensure that work is fabricated to fit surrounding construction, around obstructions and projections in place, or yet to be put in place, to suit service locations, and inaccuracies of construction.

3.2 Installation

.1 The seating plan is to be reproduced on the floor and/ or risers, all dimensions checked against reviewed shop drawings and necessary adjustments made in the layout for all discrepancies. Refer to Drawings for locations of floor mounted and removable seats.

.2 Attach seats by means of an approved type of lead shield expansion bolts and 6mm expansion bolts by not less than 50mm long, two (2) bolts per standard.

.3 Installed seats shall be level, rigid and free from defects detrimental to appearance and function.

3.3 Cleaning

.1 Remove all debris caused by this work from the premises.

END OF SECTION

## 1. GENERAL

### 1.1 General Requirements

.1 This general division, Division 20 – Mechanical, applies to the following detailed divisions:

a. Division 22 – Plumbing
b. Division 23 – Heating, Ventilating and Air Conditioning
c. Division 25 – Integrated Automation

.2 Comply with the conditions of Division 0 and Division 1.

.3 Specifications and drawings form an integral part of the contract documents. Any item omitted from one but which is mentioned or reasonably implied in the other, shall be considered as properly and sufficiently specified and shall be included as part of the work.

### 1.2 Liability and Property Insurance

.1 Comply with the requirements of Division 0, Division 1 and Section GC 11.1 of CCDC 2 - 2020.

.2 This successful Trade is to maintain adequate insurance as specified by the Owner's Standard Form of Contract. This insurance is to firmly protect both this Trade and the Owner from public liability claims and property damage, and all claims under the Workers' Compensation Act. Evidence of insurance coverage shall be filed and approved.

### 1.3 Indemnification Claims

.1 This Trade shall indemnify and save harmless the Owner and it's respective officers and agents from all claims relating to labour and material furnished or supplied in executing the contract, and from and against all claims, demands, losses, costs, damages, actions, suits or proceedings by whomsoever made, brought or prosecuted in any manner based upon, arising out of, relating to, occasioned by or attributable to the activities or omissions of this Trade or those for whom this Trade is at law responsible in performing the contract.

.2 Comply also with Section GC 12.1 of CCDC 2 - 2020.

### 1.4 Use of Electronic Files

.1 A waiver must be executed prior to release of any electronic documentation.

.2 Electronic documentation for release may consist of drawing files in formats such a Portable Document File (PDF), AutoCAD (dwg), Revit (rvt). Specifications, details, schedules, legends shall generally NOT be released.

.3 Electronic documents shall be used only for the specific use outlined in the waiver. The recipient may use this data for this purpose, at their own risk.

.4 Copyright and ownership of the data are not transferred to the recipient, or to any other party. The design professional and/or owner retain all rights to the data.

.5 Data delivered in electronic form may vary from those contained on paper copies of the documents. This information is not guaranteed to be accurate. The method of data transfer cannot be guaranteed to be error free, or compatible with the recipient's hardware, software, or systems. Contractors and subcontractors are not relieved of their normal responsibilities to independently check, coordinate, and verify information and dimensions, and to familiarize themselves thoroughly with the project. The documents may have been changed or amended by addendums, bulletins, RFI's, shop drawings, other documents, meetings, and understandings not represented on these files.

.6 The electronic files shall not be used as a substitute for the contract documents. The Author offers no warranty or guarantee, express, implied, or statutory as to the accuracy, reliability, suitability, completeness or fitness of this data for a particular purpose. The company in receipt of these files agrees, to the fullest extent permitted by law, to defend, indemnify, and hold the Author, their directors, officers, partners, employees, harmless from all losses, claims, liabilities, injuries, damages, and expenses, including attorneys' fees and costs of defense, arising out of the use, misuse, misapplication, or misinterpretation of this data.

.7 The recipient will not distribute the data to any other firm or individual, except the recipient's consultants or subcontractors.

1.5 Workplace Safety and Insurance Board

.1 This Trade shall produce a Workplace Safety and Insurance Board Certificate of Clearance Form at each monthly progress draw and prior to final payment under the contract.

1.6 Schedule

.1 Where specified in Division 0 or Division 1, all work shall be scheduled to meet the required project milestones.

.2 All work in existing facilities shall be performed at times to suit the Owner and must not interfere in any way with the carrying on of business.

.3 This Trade shall include all allowances for overtime rates in the bid price.

1.7 Extras and Credits

.1 All extras and credits must be submitted to and approved by the Consultant prior to such work commencing. They shall be priced individually with a complete breakdown clearly indicating all labour and material costs, overhead and profit mark-up and tax.

.2 Labour rates for extras and credits shall be identical. They shall be valued at payroll cost plus a percentage mark-up for burden as stipulated in Division 0.

.3 Only the net difference between an extra and a credit will be subject to overhead and profit mark-up.

1.8 Scope of Work

.1 Supply and install all equipment and materials as specified and / or shown on the drawings and required to provide complete, properly functioning, mechanical systems fit to the

intended use. Provide all labour for the satisfactory completion of the work. Supply any miscellaneous equipment and materials not herein listed necessary for the proper installation and operation of the systems.

.2 All of the equipment and materials required for the work shall be new, the best of their respective kinds and installed in a first-class manner. Similar equipment shall be of the same manufacturer unless noted otherwise.

.3 All deposits, levies or similar fees, if any, required for completion of the mechanical work shall be paid as follows:

a. Fees for approval and inspection of any portion of mechanical system by any government agency, department or authority shall be included in the bid price.
   i. This shall include all TSSA inspection fees.

.4 Unless noted otherwise, the bid price may be based on the use of products equal to those specified herein. Where 'approved equals' are listed, only products from these manufacturers may be used in the bid price. Where approved equals are not listed, any manufacturer may be used in the bid price.

.5 Unless specifically stated otherwise, this project has been designed based on the first named manufacturer of each section or that specifically listed in the schedules. If this Trade chooses to use a manufacturer other than the first named manufacturer, it will be their responsibility to ensure that all equal and alternative equipment meets the mechanical specification, is similar in dimensions, stability, quality, weight, ease of maintenance, performance, etc. and that the equipment will fit into the space allocated. This Trade shall be responsible for preparing revised design drawings (if directed by the Consultant) and shall carry all costs required to accommodate the equal / alternative equipment INCLUDING ALL COSTS INCURRED BY OTHER TRADES. The Consultant reserves the right to approve or reject any alternate based upon his evaluation of the equipment proposed. If only one manufacturer is listed, then only that manufacturer shall be acceptable.

.6 'Provide' means to supply and install the products specified. The 'work' means the total construction required by the Contract Documents and includes all labour and 'products'. 'Products' means all materials and equipment forming the completed work as required by the Contract Documents.

.7 All mechanical work shall be in accordance with the regulations of the Ontario Building Code (OBC), Canadian Gas Association (CGA), Technical Standards and Safety Authority (TSSA), Natural Gas and Propane Installation Code, National Fire Protection Association (NFPA), Canadian Standards Association (CSA), Ontario Fire Code, Ontario Electrical Safety Code (OESC), all Municipal regulations and any authorities having jurisdiction.

1.9 Examination of Site and Contract Documents

.1 It is the responsibility of this Trade to carefully review the drawings, specifications and other instructions and notify the Owner in writing of any errors, omissions and discrepancies prior to closing of tenders. This Trade shall abide by the decision given in writing. The work as shown is intended to be completed in all respects and that failure to notify the Owner of any discrepancies will not relieve this Trade of responsibility for completing the work as intended. In no case shall this Trade proceed in uncertainty.

.2 This Trade shall visit the building and become thoroughly familiar with all the existing mechanical systems and other conditions to be met in carrying out the work covered by these specifications prior to submitting the bid price. Arrangements for a site inspection may be made as described in Division 1.

.3 Examine all mechanical specification divisions and sections and all other related contract documents. The mechanical specification is to be read in conjunction with all other divisions and sections of the specification. In the event of conflict between documents, this specification shall govern.

.4 Mechanical drawings are not to be scaled. Refer to architectural drawings for all dimensions.

1.10 Intent

.1 Provide all products specified or shown in the contract documents complete with incidentals necessary for a complete operating installation. Provide all tools, instruments, equipment and labour required to do the work.

.2 The contract documents are not intended to enumerate each and every detail which may be necessary to furnish and install the complete system ready for operation. The bid price shall include all such details, and all associated labour and materials, to provide a complete and working system. The omission of any details in the contract documents shall not be a warrant for poor workmanship or the omission of such details.

.3 Where the drawings or specifications assign work to a particular Trade, this is intended to be used as a guide only to assist this Trade with the preparation of the bid price. The final decision as to which Trade provides required labour or materials rests solely with this Trade. Extra payments will not be considered based on a difference in interpretation of the contract documents as to which Trade involved provides labour or materials for specific items of work. The Consultant will not enter into such discussions.

.4 Wherever differences occur in the contract documents, the maximum conditions will govern and shall be allowed for in the bid price. The items to be incorporated will be at the option of the Consultant.

.5 All Work shall be carried out by qualified Trades and Sub-trades with established reputations for the type of work involved and performed to good industry standards.

1.11 Shop Drawings

.1 Shop drawings shall be submitted as PDF files via email. All shop drawings shall bear a signed and dated stamp indicating this Trade has reviewed and approved the submission.

.2 Shop drawings shall be submitted for all products (including all associated accessories, controls, etc.), including but not limited to:

a. Fire extinguishers and cabinets.
b. Plumbing fixtures including trim.
c. Mixing valves.
d. Plumbing specialties.
e. Pumps.

f. Expansion tanks.
g. Hydronic heating equipment.
    i. Wallfins / convectors.
    ii. Unit heaters.
h. Pressure / temperature gauges.
i. Grilles / diffusers.
j. Motorized dampers.
k. Combination fire and smoke dampers.
l. Access doors.
m. Exhaust fans.
n. Ceiling fans.
o. Air handling (HVAC) units and associated VRF system (submit one shop drawing package including AHU and VRF system – separated shop drawing packages will not be entertained).
p. Building automation system including all components, wiring diagrams, sequences and points lists.
q. Firestopping systems.

.3 For firestopping systems, shop drawings shall show construction conditions, relationships to adjoining construction, dimensions, description of materials and finishes, component connections, anchorage methods, hardware and installation procedures, plus the following:

a. Firestop design designation of testing and inspecting agency acceptable to the authorities having jurisdiction.
b. Documentation, including illustrations, from a qualified testing and inspection agency that is applicable to each firestop system configuration for construction and penetrating items. Factory or manufacturer furnished installation details are not acceptable in lieu of published documents by approved testing agencies.
c. Where conditions require modification of a qualified testing and inspecting agency's illustration to suit a particular firestop condition, submit illustration, with modifications marked, approved by the firestop system manufacturer's fire-protection Engineer.

.4 For additional shop drawing requirements, refer to other divisions and sections of this specification.

.5 Allow two weeks for Consultant's review.

1.12 Interference Drawings

.1 Interference drawings shall be produced in coordination with all other Trades to indicate all services as well as architectural and structural features present in congested spaces including but not limited to the auditorium attic and Exterior Storage 150 (mechanical room). Installations completed prior to submission of interference drawings resulting in physical interferences shall be subject to revision at no extra cost.

1.13 Questions

.1 Questions pertaining to the work shall be submitted to the Consultant in writing in the form of a Request for Information (RFI).

.2 Allow for two weeks for RFI response from the Consultant. Claims for delay within this period will not be accepted.

1.14 As-built Drawings

.1 Obtain an extra set of prints, for the job use only, on which to generate as-built drawings including the accurate recording of all deviations from the contract drawings.

.2 Take special care to indicate buried drains, inverts (shown at main reference points) and dimensioned distances from visible reference points such as walls or columns.

.3 Submit to the Consultant for approval one complete set of as-built drawings (hard copy) at project completion. The approved as-built drawings shall then be submitted to the Owner in both hard copy (one copy) and electronic (scanned) format.

.4 Prior to Substantial Performance, this Trade shall edit the electronic files to provide AutoCAD as-built drawings that incorporate all redline information. Electronic base tender plans shall be provided from the Consultant at no cost. All other associated costs shall be carried in the bid.

.5 The Consultant shall provide, at no cost, AutoCAD drawing files incorporating Changes and Instructions.

.6 Generation of AutoCAD as-built drawings may be arranged with the Consultant.

1.15 Identification

.1 Identification plates shall be engraved two-ply plastic, 0.125" (3 mm) thick, 1.0" (25 mm) high with 3/4" (19 mm) white characters on black background and length as required. Locate in a conspicuous location and secure with self-tapping sheet metal screws to equipment. All screws used outside shall be stainless steel. Nameplates which are not exposed to outdoor conditions may be secured with double sided adhesive tape. All starters shall be identified by the Electrical Trade.

.2 Where noted below, identify pipe mains by means of pressure sensitive adhesive labels. Markers and flow arrows shall be in accordance with ANSI/ASME A13.1 latest edition. Identify medium by lettered legend and direction of flow by arrows. Provide labels as follows:

a. At intervals not greater than 50 ft (15 m), changes of direction, upstream of major manually / automatically operated control valves, at all branch pipe connections, behind all access doors and on both sides where pipes pass through walls. Use approximate spacing intervals of 25 ft (7.6 m) for all piping running through suspended ceiling spaces.

b. Labels shall be sized as follows (pipe diameter includes insulation where applicable):

i. 0.75” (19 mm) to 1.25” (32 mm) piping:

1) Minimum 8” (200 mm) long label with minimum 0.5” (13 mm) letter height.

ii. 1.5” (38 mm) to 2” (50 mm) piping:

1) Minimum 8” (200 mm) long label with minimum 0.75” (19 mm) letter height.

iii. 2.5” (63 mm) to 6” (150 mm) piping:

1) Minimum 12” (300 mm) long label with minimum 1.25” (32 mm) letter height.

c. All identification labels shall be easily and accurately readable from usual operating areas, plane of legend to be approximately at right angles to most convenient line of sight.
d. Wording of all labels shall be approved by the Consultant prior to manufacture.
e. Optionally, piping may be identified using stencils and stencil marking ink. Location and sizing shall conform to pipe label specification. On insulated surfaces stencilling shall be done with black ink, on uninsulated pipe the ink shall be white. Ensure stencilling is performed in a neat, quality manner. Upon completion of project, turn over one complete set of stencils matching those used on the project to the building Owner.

.3 Valve identification shall consist of a 1.25" (32 mm) diameter brass tag with engraved black paint filled characters, secured to valve by a brass bead chain. Provide and mount for the Owner a typed valve directory in a black document type frame, listing valve number, location and service. Locate the framed directory in the main mechanical room and provide a master directory to be included in the Operation and Maintenance Manual. Individual fixture supply stops and radiation valves shall not be identified.

.4 Identify all piping having electric heat regulating / tracing cable with: ‘HEAT TRACED’.

.5 Identification of equipment / systems shall be as follows:

a. All equipment with symbols included in drawing schedules or plans shall be identified to match symbols indicated.
b. The following items shall be tagged at installed location and keyed to a control wiring diagram. Diagram shall be included in the Operation and Maintenance Manual:
   i. All components of building automation systems.
c. Provide additional miscellaneous identification labels as described on the drawings or in other divisions and sections of the specification.

.6 Verify all identification labels / tags on site with the Owner / Consultant prior to installation and adjust as directed.

1.16 Close-out Documentation – Operation and Maintenance Manual

.1 Upon project completion, this Trade shall submit an Operation and Maintenance Manual as well as as-built drawings. Submit one paper hard copy in a three-ring binder, and one .PDF electronic copy on a suitably sized USB thumb drive. Each manual shall contain the following:

a. Warranty.
b. Extended warranties.
c. Contact list (Sub-trades, suppliers, manufacturers, etc.).
d. Sign-back of latest Site Review Report (confirmation of completion).
e. Permits and approvals.
f. Test reports (water analysis/treatment, lead sampling, etc.).
g. Firestop manufacturer sign-off.
h. Shop drawings (revised as reviewed by the Consultant).
i. Equipment start-up reports.
j. Equipment operation and maintenance manuals.

k. TAB (air and water testing, adjusting and balancing) reports.

.2 This Trade shall instruct the Owner on site to the full satisfaction of the Consultant on the operation and maintenance of all mechanical systems.

1.17 Cutting, Patching and Refinishing

.1 Provide cutting and patching of building assemblies including plaster, drywall, block, concrete, etc. to support the specified work. Cutting and patching shall be performed by workers specialized in this type of work and capable of performing to good commercial standards. Refer to Architectural drawings for building assembly details or examine existing facility conditions where details are not present on the Architectural drawings. All work shall be to the approval of the Architect / General Contractor.

.2 Significant plaster construction elements are present in the space to be renovated – coordinate cutting and patching of plaster assemblies with Architect / General Contractor.

.3 No cutting of the building envelope or structural elements shall be done without permission of the Architect.

.4 Provide patching of new openings in building assemblies and openings caused by the removal of existing work. Patching shall be done to maintain existing fire separations, sound transmission class ratings, vapour retarder performance, insulation values, etc. Patching of exterior wall openings shall include filling voids and annular spaces with Roxul (not pink) batt insulation and providing a watertight seal on both sides.

.5 Finishes damaged by cutting and patching by this Trade shall be made good by this Trade with materials and colours to match existing unless noted on the architectural drawings to be refinished by the General Contractor.

.6 Cut and patch slab-on-grade floor. The General Contractor shall refinish flooring.

.7 The General Contractor shall provide structural supports or lintels for applicable openings.

.8 The General Contractor shall provide framing for openings in floors, walls and roofs.

.9 The General Contractor shall provide cutting, patching and refinishing of existing roof assembly.

.10 Conduct a photo survey of existing conditions both inside and outside the building, including of the ceiling immediately below renovation work. Immediately notify the Architect / General Contractor if any resemblance of water leakage or damage is found.

.11 Protect the existing roofing system from damage at all times. Provide plywood work platforms / walkways as required.

.12 Where wall openings caused by the removal of thermostats, sensors, etc. are not covered by new wall finishes (refer to architectural drawings) or new thermostats, sensors, etc., provide stainless steel coverplates.

.13 This Trade shall remove and reinstall existing acoustic ceiling tiles and grid, lights, etc. as required to suit own project work. Repair or replace materials damaged by this work with materials matching existing.

1.18 Concrete

.1 Where noted on the drawings, floor-mounted equipment shall be mounted on 6" (150 mm) high concrete pads supplied and installed by this Trade. All concrete shall be 25 MPa complete with a WWF152x152-MW18.7xMW18.7 welded wire mesh installed 2" (50 mm) below the surface of the concrete. Provide smooth trowel finish for all concrete surfaces. Clean and roughen existing concrete surfaces under all new pads. Where the new pad mates to the existing, scoriate sides and provide bonding agent to assure good adhesion. The concrete pads shall extend past the edges of all equipment by a minimum of 3" (75 mm).

.2 Patching of concrete floors / walls shall utilize 25 MPa concrete having a smooth trowel finish. Thickness shall match that of the existing floor / wall.

1.19 Cleaning

.1 New or affected equipment, fixtures, ductwork, piping, building finishes, building contents, etc. soiled by this Trade's work shall be cleaned to the satisfaction of the Consultant at job completion.

.2 At the completion of each day's work and at project completion, remove from the area of work all dirt, rubbish, surplus material and equipment associated with this Trade's systems installation and not required in the finished work.

.3 At project completion, replace all new / existing air filters which have been soiled by the work.

1.20 Existing Construction

.1 This Trade shall provide adequate protection to existing systems (all disciplines), pavement, curbs, walkways, sodding, shrubs, building construction, building contents, etc. throughout the project. This Trade shall be responsible for restoring to its original condition or replacing any removed or damaged item in connection with the work unless otherwise directed by the Consultant.

.2 Undertake all necessary measures required by this Trade's work to maintain adequate security of the existing building at all times.

.3 Any interruption of this Trades services to any part of the existing buildings shall come at a time agreeable to the Owner and Consultant.

1.21 Protection

.1 Where foreseeable damage of any description could result from this Trade's work, this Trade shall provide adequate protection of work previously completed, including work of others. This Trade will be responsible for restoring any damaged materials.

1.22 Demolition

.1 This Trade shall be responsible for revisions to and for the complete removal of this Trade's systems to permit the new work, all as shown on the drawings or described in the specification. This includes removal of materials from the site. All disposal costs shall be included in the bid price.

.2 Materials being removed shall become the property of the Owner unless shown otherwise, and if the Owner has no use for it, it shall be disposed of by this Trade. This Trade shall include in the bid price for the disposal of all materials. Note that the Owner shall have the first right of refusal for all demolished equipment.

.3 Demolished materials shall not be reused unless noted otherwise.

.4 Where refrigeration systems are noted to be demolished / altered, refrigerant shall be reclaimed and disposed of (where applicable) according to Ministry of Environment and any other authorities having jurisdiction.

1.23 Asbestos

.1 Where asbestos will be disturbed in the execution of this contract, comply with the regulation respecting asbestos on construction projects and in buildings and repair operations made under the Occupational Health and Safety Act, Ontario Regulation 654/85 and local requirements pertaining to asbestos. Asbestos inspection reports have been bound into this specification for use by this Trade. Employ only licensed asbestos removal Trades to execute abatement of all asbestos.

.2 Include the cost of retaining an Owner-approved Sub-trade for the abatement of all asbestos containing materials (ACM) within 24" (600mm) radius of any mechanical work. Refer to the Owner's Hazardous Materials Building Survey.

1.24 Sleeves

.1 Provide sleeves for piping and ductwork as follows:

a. For all pipe and ductwork penetrations of poured concrete structures. Pipe sleeves are not required where piping penetrates poured concrete structures provided this Trade cuts all required openings after the concrete installation and provided all openings comply with the firestop manufacturer's requirements (where applicable).
b. For all copper pipe penetrations of masonry, poured concrete and precast structures where required to prevent direct contact of the structure with the copper piping. Sleeves are not required provided that direct contact of the structure is prevented and provided the openings comply with the firestop manufacturer's requirements (where applicable).
c. Where required for proper installation of pipe firestop systems.
d. Where required for proper installation of fire dampers.

.2 Pipe sleeves shall be as follows (Trade to choose desired type):

a. Schedule 40 steel.
b. Minimum 24 gauge galvanized steel with an integral flange to secure the sleeve to the formwork.

c. Where permitted by the local authority, factory fabricated, flanged, high density polyethylene with reinforced nail bosses.

.3 Ductwork sleeves shall be manufactured of galvanized sheet steel of at least the same gauge as ductwork penetrating wall and shall be reinforced so as not to be deformed by the placement of the concrete.

.4 Floor sleeves shall have a minimum 0.5" (13mm) lip on the upper side. All other sleeves shall be flush with adjacent surfaces.

.5 Unless otherwise directed, all sleeves and openings shall provide minimum 0.25" (6 mm) clear space to ductwork, pipe or insulation. Provide space for application of firestopping for all sleeves and openings according to the fire stop manufacturer's detailed installation drawings. For sleeves used with fire dampers, comply also with the fire damper manufacturer's requirements.

.6 Provide waterproof, fire retardant, non-hardening caulking between sleeves and building construction where required for a weathertight installation.

1.25 Firestopping

.1 Firestopping shall be 3M or approved equal fire stop sealant / devices, listed in the UL fire Resistance Directory under categories XHCR (firestop devices) and XHEZ (firestop systems) and of a type to suit construction type, penetrant type, annular space requirements and fire rating involved in each separate instance. Systems shall be symmetrical for wall applications and shall be asbestos free. Install according to manufacturer's detailed installation instructions.

.2 All firestop materials shall be of the same manufacturer as that used by the General Contractor. Co-ordinate on site.

.3 Firestop systems shall comply with the required F, T and L ratings, as determined per ASTM E814 / ASTM E119 (as applicable). F ratings shall meet or exceed the fire-resistance ratings of the construction assembly. Firestop systems shall have the required flame spread and smoke developed ratings to suit the point of application and to comply with Code requirements.

.4 Provide components that are needed for fill materials and to comply with the manufacturer's detailed installation instructions. Use components specified by the manufacturer and approved by the qualified testing and inspection agency, including slag / rock-wool-fiber insulation, forming / damming / backing materials, fillers for sealants, substrate primers, collars / steel sleeves, etc.

.5 For firestop systems exposed to view, traffic, moisture and physical damage, provide products that after curing do not deteriorate when exposed to these conditions.

.6 Firestop systems shall be installed by an experienced installer who

a. Is qualified by having the necessary experience, staff and training to install the manufacturer's products.
b. Is acceptable to or licensed by the manufacturer or local authority.
c. Has established a record of successful in-service experience with firestop systems or completed a manufacturer's certified product installation training course.

.7 Deliver firestop system products to site in original, unopened containers or packages with intact and legible manufacturer's labels identifying product and manufacturer, date of manufacture, lot number, shelf life, qualified testing and inspection agency's classification marking, curing time and mixing instructions. Store and handle materials to prevent their deterioration or damage due to moisture, temperature changes, contaminants or other causes. Follow manufacturer's instructions.

.8 Verify the condition of the substrates and correct unsatisfactory conditions before installing firestop system products. Follow manufacturer's detailed installation instructions and comply with requirements for temperature and humidity conditions. Coordinate construction and sizing of sleeves, openings and penetrating items to ensure compliance with installation instructions.

.9 Upon project completion, the firestop manufacturer shall provide a letter certifying that all fire stop systems throughout the project have been installed according to their detailed installation instructions and Code requirements.

1.26 Sound Packing

.1 Where pipes and ductwork pass through non-rated walls, pack around ductwork or pipe with mineral wool filler to reduce noise transmission.

1.27 Cements and Primers

.1 All cements, primers, etc. shall be low volatile organic compound type, tested to meet the requirements of SCAQMD rule 1168, Test Method #316A (South Coast Air Quality Management District).

1.28 Pipe Escutcheons

.1 Provide proper chrome plated steel escutcheon plates for exposed uninsulated piping penetrating walls / floors / ceilings except where openings around piping have been filled to the approval of the Consultant.

.2 Pipe escutcheons shall be one-piece type with set screws for installation at plumbing fixtures.

.3 Unless noted otherwise, use chrome plated slit type with substantial hinges, positive latches and set screws. Size plates so that they are tight against the wall, floor or ceiling surface concerned; outside diameter to cover opening or sleeve and inside size to fit around finished pipe.

1.29 Access Doors for Walls and Ceilings

.1 Provide to the General Contractor for installation access doors for concealed mechanical equipment requiring accessibility for service and maintenance. These items should be grouped wherever possible in order to reduce the number of panels required. Doors shall be 12"x12" (300x300 mm) for hand access, 18"x18" (450x450 mm) for arm access, 24"x18" (600x450 mm) for head and shoulders access and 24"x24" (600x600 mm) for torso access unless noted otherwise on plans. Doors shall be complete with positive locking self-opening

screwdriver lock. The exact size of access doors shall be as recommended by the manufacturer to suit the application.

.2 Doors shall be manufactured by Acudor or approved equal and shall be of the following types (Trade to choose applicable type):

a. Drywall / Block Walls or Ceilings: Model UF-5000 having the following features:
   i. Uninsulated steel construction.
   ii. Doors up to 16"x16" (400x400 mm) shall have 16 gauge doors and 18 gauge mounting frame.
   iii. Doors over 16"x16" (400x400 mm) shall have 14 gauge doors and 16 gauge mounting frame.
   iv. Door shall be flush to frame with rounded safety corners.
   v. A one-piece outer flange shall be welded to the mounting frame.
   vi. Continuous concealed hinge.
   vii. Stainless steel screwdriver operated cam latch.
   viii. Prime coat of white alkyd baked enamel.

b. Fire Rated Drywall / Block Walls: Model FB-5050 having the following features:
   i. Insulated steel construction.
   ii. ULC 2.0 hour B label.
   iii. Doors shall be 20 gauge and mounting frames shall be 16 gauge.
   iv. Doors shall be filled with 2" (50 mm) thick fire rated insulation.
   v. Door shall be flush to frame with reinforced edges, flange to be 1" (25 mm) wide.
   vi. Self-closing and self-latching.
   vii. Inside latch release.
   viii. Concealed hinge.
   ix. Universal self-latching bolt latch, operated by a flush key.
   x. Prime coat of white alkyd baked enamel.

c. Fire Rated Ceilings: Model FW-5050 having the following features:
   i. Insulated steel construction.
   ii. Warnock Hersey International 3.0 hour B label.
   iii. Doors shall be 20 gauge and mounting frames shall be 16 gauge.
   iv. Doors shall be filled with 2" (50 mm) thick fire rated insulation.
   v. Door shall be flush to frame with reinforced edges, flange to be 1" (25 mm) wide.
   vi. Self-closing and self-latching.
   vii. Inside latch release.
   viii. Concealed hinge.
   ix. Universal self-latching bolt latch, operated by a flush key.
   x. Prime coat of white alkyd baked enamel.

1.30 Dissimilar Metals

.1 Separate dissimilar metals by means of gaskets or shims of approved material in order to prevent electrolytic action. Where piping of dissimilar metals is connected, use approved dielectric unions or flanges. A brass fitting or brass valve may also be used in making connections between copper and steel piping.

.2 Where supporting copper pipe, isolate pipe from hanger with electrolytic action tape or equivalent or use copper / plastic coated supports. Direct contact between copper piping and concrete, masonry or precast construction will not be permitted.

.3 Where installing uninsulated copper pipe for plumbing fixture rough-ins within masonry walls, provide electrolytic action tape or equivalent to prevent contact with concrete / masonry construction. Direct contact between copper piping and concrete, masonry or precast construction will not be permitted.

1.31 Installation Requirements

.1 Install equipment and services as follows:

a. Neatly following building lines and in such a manner as to permit free use of space and maximum headroom.
b. To allow free access for maintenance, adjustment and eventual replacement.
c. In accordance with the manufacturer's requirements.
d. Provide all supports, hangers and fasteners except as otherwise noted.
e. Do not support piping or ductwork from equipment.
f. Secure all products and services so as not to impose undue stresses on the structure or systems.
g. Cap off and seal all open ends of new / affected ductwork, venting, piping and conduits to prevent entrance of foreign matter.
h. Do not install piping in a location or manner which might result in freezing.
i. Layout and install piping, valves, fittings, cleanouts, etc. in conveniently accessible spaces to facilitate easy maintenance.
j. All exposed ductwork and piping shall present a neat appearance and located parallel to and centered between building structure, lights, etc.

1.32 Packaged Equipment Installation and Start-up

.1 Handle equipment carefully to prevent damage, breaking, denting and scoring. Damaged units or damaged components shall not be installed. Replace damaged parts with new supplied by the manufacturer.

.2 If equipment is to be stored prior to installation, store in a clean, dry place. Protect from weather, dirt, fumes, water, physical damage, etc.

.3 Comply with the manufacturer's rigging and installation instructions for unloading and moving into final location.

.4 Level equipment according to manufacturer's requirements, and to permit proper condensate drainage where applicable.

.5 Assemble, install and start-up equipment according to manufacturer's requirements. Complete all manufacturer start-up literature (where applicable) and include in the Operation and Maintenance Manual.

.6 Provide adequate / manufacturer's required / Code required clearances to permit servicing and maintenance of equipment.

1.33 Flashings

.1 If piping and wiring is not indicated on drawings to penetrate roof assembly through a doghouse, provide the following roof flashing system:

a. Portals Plus extra tall Aluma-Flash complete with 0.60" aluminum base, 13" high and 14" diameter. 8" collard opening shall have two sealing rings to suit EPDM cap of type to suit services. All services to be secured to cap with stainless steel clamps.
b. Roof flashing system to be supplied by this Trade and installed by the General Contractor.

1.34 Excavating and Backfilling

.1 Necessary excavation, removal, disposal, backfill and compaction of materials pertaining to this Trade's work shall be provided by this Trade. Before commencing with work, investigate locations, arrangements and conditions of all previously installed / existing underground services.

.2 Granular material shall be compacted to 98% Standard Proctor Density and all native material shall be compacted to 95% Standard Proctor Density unless otherwise directed by the General Contractor. Grade bottom of trenches to maintain design slopes.

.3 In competent undisturbed soil, lay pipes directly on the soil and shape soil to fit the lower one-third segment of all pipes and pipe bells. Ensure even bearing along the barrels. Backfill trenches 6" (150 mm) on sides and 12" (300 mm) on top with machine compacted bedding sand or limestone screening. Backfill remainder of trench with granular >B= material machine compacted in 12" (300 mm) layers. Keep sides of trenches vertical to a minimum depth of 20" (500 mm) over pipe to maintain load within pipe design limits. Minimum width of trench shall be pipe diameter plus 18" to 24" (450 to 600 mm). For trenches excavated too deep, where rock, shale or other materials may cause damage to piping or have diameters larger than 1" (25 mm) and where required by manufacturer's installation requirements to prevent damage to piping, excavate to 6" (150 mm) below pipe and backfill with machine compacted bedding sand or limestone screening.

.4 Provide timber sheeting, bracing, shoring, guard rails, etc. as required to protect all persons having access to the site from excavations. All excavation work shall comply with the latest edition of the Occupational Health and Safety Act of Ontario. Keep all excavations free of water.

1.35 Architectural Coordination

.1 Refer to Architectural drawings for details regarding the following construction elements to support Mechanical Work.

a. Furred in ductwork / pipe spaces.
b. Structural supports for equipment.
c. Mechanical areaway.
d. Paint except that painting of gas piping and refinishing of surfaces damaged by this Trade's work are defined in this specification.
e. Roof flashings for mechanical systems.
f. Cutting, Patching and Refinishing.

1.36 Paint

.1 Paint for gas piping and for patching of existing / damaged finishes shall be good quality commercial grade of a type to suit the application. Apply according to manufacturer's requirements. All painted surfaces shall have a minimum of one primer coat and two finish coats.

1.37 Inspection Certification and Review

.1 Arrange for inspection of all work by the authorities having jurisdiction. Obtain unconditional certificates of approval, acceptance and compliance with rules and regulations for authorities having jurisdiction. The work will not be considered complete until such certificates have been delivered to the Owner.

.2 Attend promptly to any deficiencies reported. Request final review when the completed installation has been checked and all deficiencies have been rectified.

1.38 Testing, Adjusting and Balancing

.1 Retain the services of an independent Balancing Trade to test, adjust and balance the systems and include for the provision of a balancing report. All work shall be performed in compliance to the requirements of the National Environmental Balancing Bureau (NEBB) or Associated Air Balance Council (AABC) and the Balancing Trade shall be certified with one of these agencies.

.2 The following is a list of the approved Balancing Trades whom may quote on the balancing of the systems:

a. Air Audit Inc., 110 Turnbull Court, Cambridge, Ontario, N1R 1K2, (519) 740-0871
b. Clark Balancing Ltd., 8094 Esquesing Line, Milton, Ontario, L9T 2X9, (905) 693-1518
c. Airwaso Canada Inc., 124-4096 Meadowbrook Drive, London, Ontario, N6L 1G4, (519) 652-4040
d. Dynamic Flow Balancing Ltd., 1200 Speers Road, Unit 36, Oakville, Ontario, L6L 2X4, (905) 338-0808
e. Air Velocities, 100 Premium Way, Mississauga, Ontario, L5B 1A2, (905) 279-4433
f. Flowset Balancing Ltd., 431 Willis Drive, Oakville, Ontario, L6L 4V6, (416) 410-9793

.3 Provide all necessary precision instruments, pressure gauges, manometers, thermometers, etc. for measuring and adjusting. Use instruments which are of correct scale and accurately calibrated.

.4 All balancing shall be done in a manner to minimize throttling losses and using speed adjustment to meet design flowrates. Final flowrates shall be within ten percent (10%) of specified value.

.5 Start balancing only when the work is essentially completed, including: installation of ceilings, doors, windows and other construction affecting testing and balancing; application of sealing, caulking and weatherstripping; normal operation of mechanical / electrical / control systems affecting testing and balancing; thermal overload protection in place for electrical equipment; air filters clean and in place; ductwork systems clean of debris; correct fan rotation; fire and volume dampers in place and open; coil fins cleaned; all ductwork outlets installed and

connected; access doors closed; ductwork installation complete; water systems flushed, filled and vented; correct pump rotation; proper strainer baskets clean and in place; service and balancing valves fully open; liquid treatment system operable.

.6 The Balancing Trade shall perform the following work in regards to air systems:

a. Test and adjust system / equipment for design air flows.
b. Equipment requiring air balancing shall be as follows:
    i. New exhaust fans.
    ii. New air handling (HVAC) units, including supply, return and outdoor air measurements.
    iii. Existing roof-mounted exhaust fan.
c. Locations of systems measurements / adjustments shall include but not be limited to the following as appropriate:
    i. Each duct run-out (or grille / diffuser) having an indicated airflow on the drawings.
    ii. Make pitot tube traverse of main supply / return / exhaust duct to verify design airflows at equipment.
d. Measurements shall include but not be limited to the following as appropriate for systems / equipment / controls:
    i. Air velocity, flow rate, static pressures (including suction and discharge), ductwork cross-sectional area, RPM, electrical power (including full load amperes), voltage, sheave diameter / setting, belt quantity / size.
e. Test and adjust blower RPM to design requirements. All required pulleys shall be supplied / installed / adjusted by the Balancing Trade.
f. Adjust grilles and diffusers to obtain optimum air distribution patterns. Also adjust to suit the Consultant.
g. Verify control system operation and report on any installation problems observed. Physical changes in the control system, such as relocating sensors or calibrating controllers, are the responsibility of the Mechanical Trade. The Balancing Trade shall work closely with Mechanical Trade to identify and correct problems.

.7 The Balancing Trade shall perform the following work in regards to water systems:

a. Test and adjust system / equipment for design water flows.
b. Equipment requiring water balancing shall be as follows:
    i. New recirculating pumps.
    ii. New air handling (HVAC) unit heating coils.
    iii. New hydronic heating equipment (convectors, unit heaters, etc.).
    iv. Existing hydronic heating equipment (convectors, unit heaters, etc.).
c. Locations of systems measurements / adjustments shall include but not be limited to the following as appropriate:
    i. Each circuit balancing valve.
d. Measurements to include but not limited to the following as appropriate for systems, equipment, components, controls:
    i. Flow rate, head pressure / pressure drop, temperature, RPM, electrical power (including full load amperes), voltage.
e. Measure pump impeller size by measuring pump "dead head".
f. Fluid flow quantities shall be measured using the installed devices provided by Others.

g. The Balancing Trade shall not continue the water balancing if at any time hazardous conditions are observed. These conditions shall be reported before proceeding further.
h. The Balancing Trade shall apply any necessary correction factors to the indicated values to account for the density of the fluid flowing in the system.
i. If specified, pitot tube traverse shall be taken where required on the drawings, provided valved openings are properly installed.
j. Where circuit balancing valves are not installed or do not provide accurate flow indication, measure pump capacities by differential pressure measurements, amperage and brake horsepower method using the pump manufacturer's capacity curve.
k. Position all automatic control valves and balancing / isolation for full flow through equipment during initial pump adjustment.

.8 Upon balancing completion, the Balancing Trade shall submit the final system balancing report (TAB Report) to the Mechanical Trade for inclusion in the Operation and Maintenance Manual. One paper hard copy and one .PDF electronic copy is required. Report shall include index page, index tabs and shall be certified by the Balancing Trade. Handwritten data will not be accepted. Include types, size, manufacturer, serial numbers and dates of calibration of all instruments used. The format shall be in accordance with the Canadian AABC or NEBB Report Form and approved by the Consultant. In addition, the report shall include:

a. Project record drawings.
b. System schematics.
c. All measured / adjusted values (include initial and final readings).
d. All pertinent information regarding balanced equipment shall be listed, such as:
    i. Designation of equipment.
    ii. Manufacturer.
    iii. Type.
    iv. Size.
    v. Motor nameplate characteristics.

.9 During the system testing, adjusting and balancing, the Mechanical Trade shall fully demonstrate the operation of all controls. The Mechanical Trade shall be present during the testing, adjusting and balancing and make modifications as often as necessary to satisfy the Balancing Trade.

1.39 Commissioning

.1 The commissioning function involves:

a. Activation of all systems.
b. Calibration, testing and verification of all systems.
c. Demonstration and instruction to Owner's staff.

.2 Be responsible for commissioning of all work provided under this division and as further defined in this section.

.3 Supply the services of a trained specialist to thoroughly explain each mechanical system, its operation and its maintenance to the full satisfaction of the Consultant and Owner. Allow for

one technician to spend one day for training for each system unless more time is indicated in the specifications for a particular system.

.4 Where requested by the Consultant, provide acceptance tests to demonstrate that the equipment and systems meet the specified requirements. Tests may be conducted as soon as conditions permit. Make all changes, adjustments or replacements required as the preliminary tests may indicate prior to final tests.

.5 All commissioning shall be video recorded by the Mechanical Contractor. Submit video thumb drive with close out documentation.

1.40 Substantial Performance Certificate

.1 Before the Contractor can make application for a Certificate of Substantial Performance the Mechanical Trade will be required to provide the following as detailed within this section:

a. Maintenance and Instruction Manuals.
b. As-Built drawings.
c. Testing.
d. Commissioning.
e. Training and Demonstrations.
f. Warranty cards.

1.41 Discount Pricing

.1 The Waterloo Region District School Board receives discount pricing from Noble Trade. This Trade is encouraged to contact Noble Trade for pricing on this project.

1.42 Warranty

.1 This Trade shall furnish a written guarantee stating that all work executed under this contract will be free from defects of workmanship and materials for a period of two (2) year from the date of Ready-for-Takeover. The period shall in no way supplement any other warranty of a longer period.

.2 This Trade will at their own expense, repair and replace all such defective work and other work damaged thereby which fails or becomes defective during the term of the warranty provided that such failure is not caused by improper use.

.3 Refer to the Division 01 specifications for additional warranty details.

.4 Include for completion of the WRDSB Project Warranty Card prior to Substantial Performance.

## 2. THERMAL INSULATION

2.1 General Requirements

.1 All insulation shall be applied in general accordance with TIAC National Insulation Standards Manual, manufacturer's published instructions and requirements, and these specifications.

.2 Apply covering in a neat workmanlike manner so that finished job is uniform and smooth in finish.

.3 All insulation and components shall have maximum flame and smoke spread ratings of 25 and 50, respectively.

.4 Ensure that all piping (including valves and fittings), ductwork and equipment are dry and clean before applying covering.

.5 Do not apply insulation until the items to be covered have been tested against leakage.

.6 Butt joints firmly together. Stagger joints in multiple layer construction. All joints shall be taped unless noted otherwise.

.7 Locate longitudinal seams so as to be invisible.

.8 Cover all joints with self-sealing 3" (75mm) wide butt strips provided by the insulation manufacturer or vapour barrier tape.

.9 Install pipe insulation continuous through barriers (walls, ceilings, floors, etc.).

.10 Install duct insulation continuous through barriers (walls, ceilings, floors, etc.) except at fire dampers.

.11 For domestic cold water and metallic condensate piping as well as for all duct thermal insulation, maintain integrity of vapour barrier jacket over all insulation, taking special precaution at fittings, valves, strainers, etc. For these systems:

a. Install insulation directly over pipes and not over hangers, supports, etc.
b. Protect pipe insulation with metal shields at all supports where such piping is 1.5" (38mm) NPS and larger. Shields shall be as follows:
    i. Shields shall be formed to fit the insulation and shall extend up to the centerline of the pipe. They shall be of the length specified for the insulation hanger inserts less 4" (100mm) to allow for vapour retarding butt joints on each side of the shields.
    ii. Shield gauges shall be as follows:
        1) 1.5" (38mm) to 3" (75mm) pipe: 20 gauge
c. Ensure duct and pipe insulation is not broken at supports, hangers and standing duct seams. Where required, provide vapour barrier tape to maintain the integrity of the vapour barrier jacket at these locations.
d. Finish insulation ends with self-sealing 3" (75mm) wide butt strips provided by the insulation manufacturer or vapour barrier tape.

.12 Protect insulation as follows:

a. Protect insulation passing through floors, walls and similar barriers to prevent damage.
b. Provide high density insulation inserts at all supports where insulation is protected by metal shields as follows (Trade to choose desired type):
    i. Johns Manville Thermo-12 Gold or approved equal calcium silicate, rigid, sectional pipe and block type.

ii. Koolphen K-block having a density to suit load, complete with vapour barrier all service jacket and factory applied metal shield.
iii. Insulation thickness shall match that of the adjacent insulation.
iv. Insert lengths shall be as follows:
1) 1.5" to 2.5" (38 to 63mm) pipe size: 10" (250mm) long
v. For domestic cold water and metallic condensate piping, inserts shall be provided with vapour retarder seals and / or coatings.

c. Provide expansion and contraction joints in piping insulation for adequate movement without damage to insulation or finishes. Terminate single layer and each layer of multiple layer in straight cut at intervals recommended by manufacturer. Leave void of 1" (25mm) between terminations and pack with light density Fiberglas AF-300 Type 1.

.13 Install insulation over equipment which may require service or replacement by maintenance staff (valves, strainers, unions, flanges, etc.) to be easily removable or replaceable without damage to adjacent insulation (use only pre-fabricated type insulation).

.14 Valves, strainers, unions, flanges, etc. which are 1" (25mm) and smaller are not required to be insulated.

.15 Existing pipe and duct insulation shall remain unchanged except that all existing insulation damaged during installation of new work shall be repaired.

.16 Where asbestos insulation has been removed to permit new connections, provide new fiberglass insulation.

2.2 Pipe Insulation

.1 Rigid (excluding refrigerant) Piping: Johns Manville Micro-Lok or approved equal, pre-moulded, glass fibre, rigid, sectional sleeve insulation with a K factor of 0.23 Btu-in/hr-ft$^2$-˚F (0.033 W/m-˚C) at a mean temperature of 75˚F (24˚C) and jacketed with a factory applied reinforced vapour retarder facing having a longitudinal acrylic adhesive closure system. Thickness and application shall be as specified below.

.2 Refrigerant Piping: Armacell AP Armaflex Tube unslit flexible elastomeric cellular pipe insulation or approved equal with a AK@ factor of 0.27 Btu-in/hr.-sq.ft.-deg.F (0.039 W/m.-deg.C) at a mean temperature of 75 deg. F. (24 deg. C.). All insulation and associated components shall have maximum flame spread and smoke developed ratings of 25 and 50 respectivelyThickness and application shall be as specified below.

.3 Valves and Fittings: Pre-formed fittings or mitred segments to match adjacent pipe insulation. Where insulation is to be provided with PVC covers, insulation may be revised to Johns Manville Microlite Standard Type 150 or approved equal formaldehyde-free, flexible glass fibre, blanket insulation with a K factor of 0.24 Btu-in/hr-ft$^2$-˚F (0.035 W/m-˚C) at a mean temperature of 75˚F (24˚C) and a factory applied FSK vapour barrier facing having a 2" (50mm) stapling tab.

.4 Install rigid fiberglass type insulation according to manufacturer's requirements and as follows:

a. Apply the SSL II Positive Closure System smoothly and securely as per the manufacturer's requirements, ensuring all contacting surfaces are kept clean.
b. Apply insulation on valves, backflow preventers, strainers, unions, flanges, fittings, etc. prior to straight run insulation.
c. Insulation on fittings shall be cut in proper segments to provide a tight fit or pre-formed fittings shall be used. Insulation on valves, backflow preventers, strainers, unions, flanges, etc. shall be pre-formed type only.
d. All insulation for fittings shall be cut to suit the length of the body plus 2" (50mm) at each end.
e. Any void between the insulation on fittings, valves, backflow preventers, strainers, unions, flanges, etc. and the straight run insulation shall be filled with insulation segments cut to fit the gap.
f. If a continuous vapour barrier is specified, finish insulation ends with self-sealing 3" (75mm) wide butt strips provided by the insulation manufacturer or vapour barrier tape.

.5 Install flexible foam type insulation according to manufacturer's requirements and as follows:

a. All butt joints shall be sealed using Armaflex 520 adhesive. Both surfaces to be joined shall be completely coated with adhesive and butted firmly together.
b. Provide jacketing for exterior piping as specified below.
c. Apply using slip-on method unless not possible due to site conditions. Where required to use slit type insulation, seal all joints using Armaflex 520 adhesive.
d. Insulation shall be neatly cut to fit snuggly around obstacles. Seal all joints using Armaflex 520 adhesive.
e. Comply with manufacturer's recommendations regarding required ambient temperatures.

.6 Finish Covering for Insulation (Interior of Building):

a. Leave as All Service Jacket (ASJ) or FRK finish except as otherwise noted below.
b. All interior exposed pipe insulation shall be provided with PVC jacketing, Proto or approved equal as follows:
    i. Insulation located within suspended ceiling spaces, cabinet spaces and walls will not be considered exposed.
    ii. System shall consist of one piece and two piece pre-moulded high impact LoSMOKE PVC pipe and fitting covers with all required accessories, which include elbows, tees, valves, end caps, mechanical line couplings, specialty fittings, tank end panels, tack fasteners, tapes and specialty items. Jacket shall be bright high-gloss white colour.
    iii. Jacket shall have flame spread rating and smoke developed classification of 25 and 50, respectively.
    iv. Jacket shall not promote the growth of fungi or bacteria.
    v. Where desired by Trade, fibreglass inserts which comply with the insulation specifications may be provided.
    vi. Jacket shall be 0.02" (0.5mm) thick with standard one piece fitting cover.
    vii. Apply according to manufacturer's requirements and as follows:
        1) Apply on clean, dry surfaces.
        2) Do not apply jacket too tightly. Install slide joints and jacket to prevent cracks and puckering.

3) Jacket shall be cut and rolled to fit the circumference of pipe plus a 2" (50mm) overlap.
4) Apply PVC adhesive bead (Red Devil Inc. Celulon or approved equal, water based, clear) along longitudinal edge, approximately 1" (25mm) in from edge, and apply jacket over adhesive using firm pressure for attachment. Temporarily hold PVC jacket in place using masking tape until firmly attached.
5) Provide PVC end caps at all insulation endpoints (caulked joints will not be permitted).
6) Any corners or cracks shall be neatly finished with a white silicone caulking bead.
7) Secure throats of fitting, valve, etc. covers by either tack fastening or taping (do not use tacks where a vapour barrier insulation system is specified). For insulation systems required to have a vapour barrier insulation, use Proto PVC tape with a minimum 2" (50mm) downward overlap.

c. Flexible foam insulation shall not be provided with a finish covering material.

.7 Finish Covering for Insulation (Exterior of Building):

a. All exterior pipe insulation shall be provided with 0.016" (0.40mm) stucco embossed aluminum jacketing as follows:
i. The jacket shall be cut to fit the circumference of the insulation with a 2" (50mm) overlap.
ii. Position all joints to shed water.
iii. The longitudinal joint shall be secured with 0.5" (13mm) long #8 stainless steel screws installed at maximum 6" to 8" (150 to 200mm) centres except that screws will not be permitted for piping which is electrically heat traced. For piping equipped with electric heat trace cable, secure jacket with 0.5" (13mm) wide by 0.020" (0.5mm) thick stainless steel banding installed as follows:
1) At maximum 18" (450mm) centres.
2) On either side of each transverse joint in the jacketing.
iv. Provide a safety edge for all exposed longitudinal edges.
v. End caps shall have a 0.125" (3.1mm) male bead to insert into the female end of the straight run jacket. The edge of the straight run jacket shall be hammered down over the end cap.
vi. The jacket at valve handles shall be neatly cut around the protrusion and the resulting opening shall be caulked.
vii. Provide aluminum jacketing elbow fitting covers as follows:
1) Jacket shall be 0.016" (0.40mm) minimum thickness.
2) Overlap with straight run jacket by minimum 2" (50mm) and position all joints to shed water.
viii. All unfinished edges, cut-outs, transverse joints, longitudinal joints, screws or other locations where water infiltration is possible shall be sealed with aluminum coloured silicone caulking. For jacket overlaps, the caulking shall be applied between the overlaps, 1" (25mm) from the edges.

.8 Pipe insulation thicknesses shall be as follows:

a. Copper Potable Cold Water: 0.5" (13mm) with the following exceptions:

i. Heat trap and cold water piping downstream of heat trap to domestic water heater shall be provided with 1" (25mm) insulation.
ii. Cold water piping downstream of check valve to domestic hot water system shall be provided with 1" (25mm) insulation.

b. Copper Potable Hot Water: 1" (25mm) with the following exception:
i. Hot water piping 1.5" (38mm) and larger shall be provided with 1.5" (38mm) insulation.

c. Hydronic Heating Water (Supply and Return):
i. Heating water piping 1.25" (32mm) and smaller shall be provided with 1.5" (38mm) insulation.
ii. Heating water piping 1.5" (38mm) and larger shall be provided with 2" (50mm) insulation.

d. Metal Cooling Coil Condensate: 0.5" (13mm).

e. Plastic Cooling Coil Condensate: No insulation required.

f. Refrigerant Piping:
i. Indoor piping: 0.5" (13mm).
ii. Outdoor piping: 0.75" (19mm)

g. Piping with Electric Heat Trace Cable:
i. Piping 0.5" to 1" (13 to 25mm) shall be provided with 1" (25mm) insulation.
ii. Piping 1.25" to 2" (32 to 50mm) shall be provided with 1.5" (38mm) insulation.
iii. Piping 2.5" to 6" (63 to 150mm) shall be provided with 2" (50mm) insulation.
iv. For piping 1.25" (32mm) and smaller, use 0.25" (6mm) larger diameter insulation to allow room for installation over cable.

2.3 Duct Insulation (Interior of Building)

.1 Johns Manville Microlite XG Type 75 or approved equal formaldehyde-free, flexible glass fibre, blanket insulation with a K factor of 0.27 Btu-in/hr-ft$^2$-˚F (0.039 W/m-˚C) at a mean temperature of 75˚F (24˚C) and a factory applied FSK vapour barrier facing having a 2" (50mm) stapling tab. Provide as follows:

a. In concealed locations, where insulation is required on rectangular ductwork. Concealed locations include ceiling spaces (including suspended), bulkheads, walls, attics, etc.
b. In exposed locations, where insulation is required on round ductwork. Ductwork shall be provided with 1.5" (38mm) insulation unless otherwise noted. Thermal insulation will not be required where 1" (25mm) acoustic insulation is used.

.2 Johns Manville 800 Series Spin Glas or approved equal 3.0 lb/ft$^3$ (48.1 kg/m$^3$) density rigid board insulation with a K factor of 0.23 Btu-in/hr-ft$^2$-˚F (0.035 W/m-˚C) at a mean temperature of 75˚F (24˚C) and a factory applied FSK vapour barrier facing. Provide as follows:

a. In exposed locations, where insulation is required on rectangular ductwork.
b. Ductwork shall be provided with 2" (50mm) insulation unless otherwise noted. Thermal insulation will not be required where 1" (25mm) acoustic insulation is used.

.3 Insulation fasteners shall be 12 gauge (2mm) zinc coated steel pins at 16" (400mm) to 18" (450mm) on center complete with minimum 1.5" (38mm) square plastic or zinc plated steel self-locking washers. Alternatively, use Continental spindle anchors held in place with Tac Two or approved equal adhesive at 16" (400mm) to 18" (450mm) on center.

.4 Insulation self-adhesive tape shall be MacTac Canada Ltd. or Venture Tape, ULC listed.

.5 Flexible insulation shall be applied as follows:

a. Cut to have a 3" (75mm) minimum overlap.
b. On round ductwork, provide one row of welded or glued on spindle anchored pins on top or side section at 12" (300mm) centers (length of pins shall suit ductwork). Proper washers shall be pressed on the pins and the ends of the pins cut before sealing with a piece of 4" (100mm) tape. On round ductwork 14" (350mm) and smaller, 0.5" (13mm) wide 20 gauge stainless steel banding may be used as an alternate to the anchoring pins (install bands at 12" (300mm) on center).
c. On rectangular ductwork, apply as specified for round ductwork where dimensions do not exceed 16" (400mm) in total on the four sides. On larger ductwork, the sides and bottom shall have stud welded pins or spindle anchored pins glued on at 16" (400mm) to 18" (450mm) on center.
d. All pin penetrations or punctures and all circumferential and longitudinal joints in jacket shall be sealed with a 4" (100mm) vapour barrier tape.
e. Refer also to manufacturer's requirements.
f. All exposed flexible insulation on round ductwork shall be covered with PVC jacketing, Proto or approved equal as follows:
    i. System shall consist of one piece and two piece pre-moulded high impact LoSMOKE PVC duct and fitting covers with all required accessories, which include elbows, tees, end caps, specialty fittings, tack fasteners, tapes and specialty items. Jacket shall be bright, high-gloss white colour.
    ii. Jacket shall have flame spread rating and smoke developed classification of 25 and 50, respectively.
    iii. Jacket shall not promote the growth of fungi or bacteria.
    iv. Jacket shall be 0.02" (0.5mm) thick with standard one piece fitting cover.
    v. Apply according to manufacturer's requirements and as follows:
        1) Apply on clean, dry surfaces.
        2) Do not apply jacket too tightly. Install slide joints and jacket to prevent cracks and puckering.
        3) Jacket shall be cut and rolled to fit the circumference of pipe plus a 2" (50mm) overlap.
        4) Apply PVC adhesive bead (Red Devil Inc. Celulon or approved equal, water based, clear) along longitudinal edge, approximately 1" (25mm) in from edge, and apply jacket over adhesive using firm pressure for attachment. Temporarily hold PVC jacket in place using masking tape until firmly attached.
        5) Provide PVC end caps at all insulation endpoints (caulked joints will not be permitted).
        6) Any corners or cracks shall be neatly finished with a white silicone caulking bead.
        7) Secure throats of fitting covers by taping. Use Proto PVC tape or equivalent with a minimum 2" (50mm) downward overlap.
    vi. Where desired by Trade, fibreglass inserts which comply with the insulation specifications may be provided.

.6 Rigid insulation shall be applied as follows:

a. Cut to fit between standing seams and stiffeners.

b. Apply welded or glued on pins installed at maximum 18" (450mm) on center. Apply pins with reduced clearances where necessary to properly secure insulation.
c. Apply to top of duct first, with edges of insulation even with edges of ductwork.
d. Next apply to sides of duct by cutting board to cover the top edge of insulation and to be even with the bottom edge of the duct.
e. Next apply to bottom of duct by cutting board to be even with the outside edges of the side insulation.
f. Mechanical washers shall be applied as the board is being installed. Cut the remainder of the unnecessary pins.
g. At corner, joints and washers, a 4" (100mm) tape shall be used to seal all joints and maintain integrity of vapour barrier.
h. Where elbows occur, slit board at 1" (25mm) centers in a AV@ type cut where necessary to soften the board.
i. Provide drywall type metal corner beads on edges of insulation, secured in place with tape.
j. Refer also to manufacturer's requirements.

.7 Insulation shall be provided as indicated on drawings and as per the following:

a. Ductwork in unconditioned spaces (not air-conditioned) including ceiling spaces, attic, bulkheads, walls, etc.
b. First 8'-0" (2.4m) of exhaust ductwork on interior side of exterior wall, roof, etc. penetrations.
c. Intake (outdoor air) ductwork located in interior of building.
d. Thermal insulation is not required where 1" (25mm) acoustic insulation is provided.

## 3. ELECTRICAL

### 3.1 Electrical Wiring

.1 Unless noted otherwise, power wiring for mechanical equipment shall be provided according to the Electrical drawing and specifications. Provide all controls complete with all low voltage wiring (less than 50V) according to Mechanical drawings and specifications.

.2 Provide starters, overload protection and disconnects for mechanical equipment according to the Wiring for Equipment Schedule on Electrical drawings.

.3 Line and low voltage electrical work specified in the Mechanical drawings and specifications shall be done in accordance with and to the standards outlined in the electrical specification.

.4 Control wiring and transformers shall be class 1 or 2 as required by the Ontario Electrical Safety Code (OESC) to suit system operating voltages and currents.

.5 Control wiring shall be the shielded type and of a type as recommended by the manufacturer. Wiring running concealed shall not run in conduit unless otherwise required by the OESC. Take all necessary precautions to ensure electromagnetic interference from other wiring systems within the building does not affect the operation of the mechanical control systems.

.6 Where control wiring is installed in return air plenums, use wiring having maximum flame and smoke ratings of 25 and 50 respectively.

.7 Wiring sizes and transformer capacities shall be suitable to service all control equipment and to accommodate voltage drops in wiring systems.

.8 Control wiring shall run concealed in the Auditorium and all other locations (exposed wiring, conduit, wiremold, etc. not permitted). The following instances are exempt from this requirement:

a. In the following locations, wiring may run exposed on surface in conduit. Provide conduit where required.
   i. Wiring running on walls or ceilings in Mechanical / Electrical Rooms.
   ii. Wiring running on walls or ceilings in the attic.
   iii. Wiring running on walls or ceilings in the stage. Paint exposed conduit in stage to match architectural finishes (black).
   iv. Wiring running on walls or ceilings in dressing rooms and/or projection booth.

b. Exposed control wiring will not be permitted (run in conduit as described above).

.9 Additional details regarding the electrical wiring are as follows:

a. Control transformers for Building Automation System / motorized dampers shall be supplied and wired by the Mechanical Contractor from power sources provided by the Electrical Contractor where indicated on the drawings. All low voltage wiring to the Building Automation System / motorized dampers shall be by the Mechanical Contractor.

b. Removal of all power / control wiring greater than 50V for demolished mechanical equipment shall be by the Electrical Contractor. Removal of control wiring less than 50V by the Mechanical Contractor.

c. For additional wiring requirements for the building automation systems, refer to Division 25.

**END OF SECTION**

## 1. GENERAL

1.1 General Requirements

.1 Refer to Division 20 – Mechanical.

## 2. PLUMBING AND DRAINAGE

2.1 Supports

.1 Provide all of the required pipe hangers and supports.

.2 Pipe and equipment supports shall be Taylor Walraven or approved equal of spacing and type as recommended by manufacturer, in accordance with Code requirements and in accordance with good commercial standards.

.3 Provide supports to secure pipes, prevent pipe vibration, maintain required grading, allow for expansion and contraction and produce a neat appearance. Design for strength and rigidity to suit loading and services, prevent undue stress to structural members and with provision for vertical adjustment after piping is erected.

.4 Clamp vertical pipes solidly at every other floor level (intervals not to exceed 25'-0" (7.6m)) in such a manner that expansion can take place in an upward direction.

.5 Anchor / support risers so that weight is not transferred to the underground piping / connected horizontal piping.

.6 Offset hanger pipe and structural attachments in such a manner that rod is vertical when piping is hot and is subject to tensile loading only.

.7 Adjust hanger rods to equalize load.

.8 Provide supplementary structural steelwork where structural bearings do not exist.

.9 For all piping systems specified to have insulation with a continuous vapour barrier, oversize pipe hangers and supports to accommodate insulation.

.10 Special care shall be taken to ensure all plastic piping is supported according to the recommendations of the pipe manufacturer.

2.2 Domestic Water Piping

.1 Above Ground (Contractor to choose desired type):

a. Type "L" hard copper tubing with sweat wrought copper pressure type solder joint fittings.

.2 Connections

a. Lead-free solder for Type L copper.

2.3 Sanitary Drain and Vent Piping

.1 Below Ground (Contractor to choose desired type):

a. 2" and under: type "L" hard copper with cast brass or wrought copper fittings.
b. Over 2": Cast iron with "MJ" fittings.
c. All sizes inside the building: ABS DWV or PVC-SDR-35 pipe with injection-molded socket fittings.

.2 Above Ground (Contractor to choose desired type):

a. 2" and under: type DWV hard drawn copper tube with cast brass alloy drainage fittings.
b. Over 2": Cast iron pipe with "MJ" fittings or DWV copper tubing with cast alloy drainage fittings.
c. All sizes: PVC DWV pipe with injection-molded socket fittings. Pipe shall be suitable for use in non-combustible building construction (IPEX System 15 or approved equal). For piping running through return air ceiling plenums or the attic, piping shall have a maximum smoke developed rating of 50 (IPEX System XFR 15-50 or approved equal).

.3 Connections:

a. 50-50 lead-tin solder for DWV copper.
b. Stainless steel screw clamps and elastomer sleeve for mechanical joint cast iron soil pipe, Bibby-Ste-Croix series 2000 or approved equal.
c. Solvent weld all socket fittings according to manufacturer's recommendations.
d. For PVC pipe using gasketed connections, use manufacturer approved PVC pipe lubricant.

.4 All piping shall conform to or be certified by the appropriate CSA standard according to OBC requirements.

.5 Exposed piping will not be permitted at fixture connections (piping within cabinet spaces is not considered exposed). Use only fixture trim components as specified in the Equipment Schedule or, if not specified, copper piping.

.6 Un-insulated plastic piping will not be permitted to run exposed in any location. Use only copper or cast iron piping in these locations.

.7 Plastic piping will not be permitted to run exposed less than 8'-0" (2400mm) above the finished floor in any location (unless approved by Owner or where protected by equipment, block enclosure, etc.) to prevent pipe from being damaged. Use only cast iron piping in these locations including where piping runs within Mechanical / Electrical / Storage / Custodial Rooms.

.8 Plastic piping will not be permitted for individual piping branches to floor drains which could receive discharge from hot water relief valves (to prevent pipe damage from extreme temperatures of waste discharge). Use only copper or cast iron piping for these applications for a minimum distance of 15'-0" (4.5m) from the floor drain outlet.

2.4 Condensate Drain / Relief Piping

.1 For condensate drains, provide schedule 40 CPVC pipe suitable for 180 degree F (82 degree C) maximum working temperature with socket fittings unless noted otherwise on the drawings.

.2 For relief valve piping, provide type M copper, hard drawn with sweat wrought copper pressure type solder joint fittings. Connections shall be made using lead-free solder.

.3 Solvent weld all plastic piping socket fittings according to manufacturer's recommendations. Use lead-free solder for Type M copper.

.4 Provide trap seals on all cooling coil condensate piping according to manufacturer recommendations to suit fan total pressure.

.5 Install relief valves where indicated / required and as follows:

a. Install in a vertical position only where directed by the manufacturer.
b. Do not install an isolation valve between the relief valve and the system, or in the discharge line.
c. Keep discharge line as short as possible and slope down in direction of flow. The pipe size shall match the outlet size on the valve.
d. The discharge line shall terminate plain, not threaded.
e. The discharge line shall have a maximum length of 30'-0" (9.1m) and shall have a maximum of 4 elbows.

2.5 Plastic Piping

.1 Prior to installation of any plastic piping:

a. Obtain ULC approved installation instructions from the firestop manufacturer for all firestops throughout the complete project. Where ULC approved products cannot be obtained to suit all pipe configurations and building constructions, use copper or cast iron piping only.
b. Verify that the proposed types and locations of plastic piping are acceptable to the local authority and modify work as required without extra cost.

.2 Do not store plastic piping in direct sunlight.

2.6 Sanitary Cleanouts

.1 Zurn or approved equal of the following types (Contractor to choose applicable type):

a. In unfinished floor areas, provide ZXN-1612 with dura coated cast iron body, neoprene body sleeve, polished nickel bronze adjustable head and heavy duty scoriated top. For floor cleanouts in the Warehouse, provide ZN-1400-HD, adjustable floor cleanout with dura coated cast iron body, neoprene body sleeve, polished nickel bronze adjustable head and heavy duty cast iron scoriated top.

.2 Cleanouts have been indicated where desired in specific locations. In all other locations, provide cleanouts according to Ontario Building Code requirements and/or where directed by the local authority. Cleanouts shall be installed tight to walls where indicated on the drawings.

.3 Install floor cleanouts where shown on the drawings and where required with top edge flush or maximum 0.125" (3.1mm) below finished floor elevation.

2.7 Floor Drains

.1 Zurn or approved equal of the following types (Contractor to choose applicable type):

a. In unfinished concrete floor areas, provide ZX-211-A5-P complete with dura coated cast iron body, bottom outlet, adjustable with 5" (127mm) diameter 0.5" (13mm) thick cast iron heavy duty round strainer and trap primer connection.
b. Funnel floor drains shall be provided where indicated on the drawing(s) and installed next to equipment where only one (1) pipe has to relieve to drain. Unless noted otherwise, provide ZN-211-BE-P complete with dura coated cast iron body, bottom outlet, adjustable polished nickel bronze round strainer with round 4" (100mm) funnel and trap primer connection.
c. Funnel floor drains shall be provided where indicated on the drawing(s) and shall be installed next to equipment where more than one (1) pipe has to relieve to drain. Unless noted otherwise, provide ZN-211-BF-P complete with dura coated cast iron body, bottom outlet, adjustable polished nickel bronze round strainer with secured open throat oval funnel and trap primer connection.

.2 Install floor drains where shown on the drawings with top edge flush or maximum 0.125" (3.1mm) below finished floor elevation. Co-ordinate the exact location of all floor drains on site and adjust to suit the floor slopes as directed by the General Contractor.

2.8 Valves

.1 General

a. All valves shall have a pressure rating suitable for the system operating pressure. All valves shall meet MSS-SP-25, the manufactures name and pressure ratings are clearly marked on the body of the valve. Valves to meet current MSS specifications.
b. Similar valves shall be of the same manufacturer.
c. All valves supplied for this project shall have a current and valid Canadian Registration Number for the Province of Ontario with TSSA. Suppliers shall provide a copy of the Statutory Declaration for valves, stamped, signed and dated by TSSA as validation of the CRN registration. This shall be provided along with the shop drawing submittal package.
d. Provide stem extensions / extended necks as required to suit insulation thickness.
e. All domestic water valves shall be lead-free compliant containing less than 0.25% lead by weight copper alloy bodies. Valves to be certified to NSF 372: Use only original manufactured valves meeting ANSI, ASTM, ASME and applicable MSS standards.
f. Provide lead free paste when soldering lead free valves.

.2 Fixtures:

a. Each fixture supply shall have a shut-off valve. Exposed valves and piping to be chrome plated.

.3 Isolation Valves (Domestic Hot and Cold Water):

a. Sizes 0.5" (13mm) to 2" (50mm): 1034 kPa (150 psig) / 600 W.O.G., Brass Body to ASTM C49300 (Lead Free Brass), Full Port, PTFE Seats, Double "O" Ring, Stainless Steel Ball, Blowout Proof Stem, Lever Handle.
   i. Threaded valves: Kitz 858 or approved equal.
   ii. Soldered valves: Kitz 859 or approved equal.

.4 Check Valves (Domestic Hot and Cold Water):

a. Sizes 0.5" (13mm) to 2" (50mm): 860 kPa (125 psig) / 200 W.O.G. bronze body to ASTM C89530 (Lead Free Bronze), Screwed Cap C49300 (Lead Free Brass), Integral Seat, Bronze or PTFE Disk.
   i. Threaded valves: Kitz 822 or approved equal.
   ii. Soldered valves: Kitz 823 or approved equal.

.5 Balancing Valves (Domestic Hot Water):

a. Victaulic / IMI TA Series 790 STAD-Zero. Sizes ½" to 2", Brass CC768S body (<.01% lead content), valves for precise flow measurement, balancing, and positive shut-off. Each valve to be wye pattern, globe style variable orifice design with self-sealing EPDM measurement points, EPDM seat, and handwheel with locking tamper-proof setting. Valves shall be selected based on flow requirement. Suitable for operating temperatures to 248°F (120°C). IAPMO Certified in accordance with ANSI/NSF 61 for cold (+73°F/+23°C) and hot (+180°F/+82°C) potable water service, and ANSI/NSF 372. Maximum working pressure 400 psi with female threaded ends.

.6 Drain Valves:

a. 860 kPa (125 psig) / 200 W.O.G. bronze body to ASTM C89530 (Lead Free Bronze), Screwed Cap C49300 (Lead Free Brass), Integral Seat, Bronze or PTFE Disk.
   i. Threaded valves: Kitz 868C or approved equal.
   ii. Soldered valves: Kitz 869C or approved equal.
b. Where required by the local authority, provide tamper proof vacuum breaker.

.7 Strainers:

a. Sizes 0.5" (13mm) to 2" (50mm): 860kpa (125PSIG) / 200wog Rating, Lead free Bronze Body less than .25% Screwed Cap, Y-Pattern, SS Screen, 20 mesh Perforation.
   i. Threaded strainers: Mueller Steam Specialty LF351 or approved equal
   ii. Soldered strainers: Mueller Steam Specialty LF358S or approved equal

.8 Temperature and Pressure Relief Valves:

a. Watts M series or approved equal having pressure setting and relieving capacity to suit application. Selection of valve shall be by the valve manufacturer.

2.9 Shock Absorbers

.1 Shock absorbers shall be located and sized in accordance with Plumbing and Drainage Institute standard no. WH201-PD-1. Absorbers shall be Zurn Wilkins or approved equal, 1250XL series.

2.10 Thermometers

.1 Winters 91T or approved equal, industrial variable angle type, complete with 9" (225mm) scale length, dual scale (imperial and metric - deg. F. / deg. C.), aluminum case, glass lens, cast aluminum bulb chamber with graphite fill and organic fluid. Provide standard range so that operation is at mid point of scale and brass thermometer well complete with extension where installed through insulation.

.2 Locate thermometers so that they can be easily read from the floor.

2.11 Pressure Gauges

.1 Winters PCT or approved equal complete with 4.5" (113mm) white aluminum dial, acrylic lens, dual scale (imperial and metric - Psi / Kpa), bronze tube, brass socket, type 304 stainless steel case and adjustable pointer. Provide standard range so that operation is at midpoint of scale. Provide brass stop cock.

.2 Locate gauges so that they can be easily read from the floor.

2.12 Trap Seal Primers

.1 Traps and trap seal primers shall be provided for all floor drains / standing wastes according to OBC requirements (traps and primers not shown on drawings).

.2 Provide Precision Plumbing Products Inc. model MPB-500-115V or approved equal electronic primer designed to serve one to four drains. The primer shall be 120-1-60 and shall be complete with model DU distribution unit, cabinet enclosure, circuit breaker, test switch, UL listed timer solenoid valve and plug-in power cord. The electrical assembly shall be listed to UL #73.

.3 Install units according to manufacturer's recommendations and as follows:

a. With a minimum elevation above the floor drain as directed by the manufacturer.
b. With an isolation valve immediately upstream of each primer.
c. For electric priming systems, all wiring from the 120V power sources shall be by This Contractor.120V power sources shall be provided by the Electrical Contractor where indicated on the HVAC drawings. These have been designated for use with the automatic temperature control / building automation systems but may also be used as a power source for trap seal primer valves.
d. Headers (where used): provide 0.5" (13mm) header piping and 0.5" (13mm) branch piping from header to each floor drain. Arrangement piping for equal water flowrates to all drains.
e. Electric primer panels shall be located to the approval of the Consultant.

.4 All under floor trap seal primer piping shall be polybutylene tubing having an SDR of 11 or less and all above ground piping shall be copper / PEX tubing. The minimum size of all trap seal piping shall be 0.5" (13mm).

2.13 Piping Installation Requirements

.1 Piping shall be installed according to good commercial standards and approximately as follows:

a. All piping running vertically shall run concealed in wall construction / furred enclosures unless noted otherwise on the drawings.
b. Use compression joints, unions, flanged or grooved joints in sufficient quantities to facilitate removal of equipment, fixtures, etc. without removal of long lengths of pipe.
c. Install eccentric reducers in horizontal piping to permit drainage and eliminate air pockets.
d. Where pipe sizes differ from connection sizes of equipment, install reducing fittings close to equipment. Reducing bushings are not permitted.
e. All valves and other pipe accessories shall match the associated pipe size unless noted otherwise.
f. Cut ends of pipes square, ream, clean scale and dirt and assemble without binding.
g. Install copper tubing so that it is not in contact with dissimilar metal and will not be kinked or collapsed.
h. Plug or cap pipe and fittings to keep out debris during construction.
i. Run buried drains minimum 8" (200 mm) clear below bottom of concrete slab unless not permitted by invert of building drain.
j. All piping shall be laid straight and in true alignment to the slopes of the pipe, as indicated on the drawings and / or as directed.
k. Install piping free from strains and with proper allowance and off-sets for thermal expansion and contraction.
l. Pipe bedding for exterior underground piping shall be according to applicable OPSD details.

.2 Piping shall be graded as follows:

a. Water Piping: Minimum 1/20" per foot (0.43mm/100mm) length. Insure all piping can be drained and provide drain valves at all low points.
b. Sanitary Drains: Minimum slopes as required by Code or as otherwise noted on the drawings.
c. Condensate Drains / Relief Piping: Minimum 2%.

.3 Keep all sanitary and water piping clear of outside walls and combustion air openings unless otherwise noted on the drawings / unless otherwise required by site conditions / unless otherwise approved by the Consultant. It is the responsibility of this Contractor to ensure that water lines in outside walls are run on warm side of building insulation and adequately covered with insulation. It is the responsibility of this Contractor to ensure that plumbing piping is installed so that freezing conditions within the pipe do not occur.

.4 Outside piping shall have the following minimum cover measured to the top of the pipe:

a. Sanitary: 3' - 0" (0.91 m)

.5 Where minimum cover cannot be achieved longitudinally centre over the pipe 3" (75mm) thick Plastispan H.D. below grade rigid insulation or approved equal with overlapping joints. Insulation width shall be 6'-5" (1925mm).

.6 Install a minimum of 24" (600mm) straight run piping between pipe elbows, valves, pumps or other fittings in recirculating water systems.

.7 Install check valves in horizontal or vertical upflow piping only. Locate minimum 8 pipe diameters downstream of pump outlets.

.8 All drainage piping exposed in accessible pipe chases, utility and similar rooms shall be cast iron or copper only.

.9 Install plastic piping in accordance with manufacturers product data, including product technical bulletins, installation instructions and product carton instructions for installation.

2.14 Fire Extinguishers

.1 Fire extinguishers indicted on the drawings shall be of the following types:

a. Type FE: Multi-purpose powder, Wilson and Cousins model ABC-050HW, 5 lb. (2.27 Kg) capacity having a 3-A, 40-B,C rating. Provide wall mounting bracket.

.2 Verify all locations on site with the local authority prior to installation and adjust as directed. Mount the handle of the extinguisher at 3'-11" (1175mm) above finished floor.

2.15 Plumbing Fixtures

.1 Plumbing fixtures complete with trim shall be of the manufacturer's listed in the Schedule on the drawings or approved equal. Colour of fixtures (except stainless steel fixtures) shall be white.

.2 Connect plumbing fixtures and equipment to the water supplies, wastes, traps and vents in accordance with the Ontario Building Code. Traps and vents are not shown on the drawings. All fixtures shall be served from wall unless noted otherwise on the drawings.

.3 Set fixtures level, square and centered with relation to floors, walls, and partitions, a standard height from floor to rim unless otherwise shown on drawings and / or directed by the Consultant. All fixtures designated for handicap use shall be mounted at the required height (refer to Architectural drawings for additional information regarding required mounting heights)

.4 Attach plumbing fixtures in an approved manner complete with all required flanges, gaskets, bolts, nuts, etc. Seal around all fixtures.

.5 Branch piping to individual plumbing fixtures shall be sized as shown in the Plumbing Branch Piping Schedule on the drawings.

.6 Approximate mounting heights of fixtures, as measured from finished floor/grade level shall be as follows unless noted otherwise on the drawings:

a. Wall-hung lavatory: 31" (775 mm) to overflow rim.
b. Water closet: 15" (375 mm).

2.16 Recirculating Pumps

.1 Taco 00 series or approved equal having the following features / construction details:

a. Suitable for a maximum working pressure of 125 PSI (860 kPa) at 220 degrees F (104 degrees C) fluid temperature. Minimum operating temperature shall be 40 degrees F (4 degrees C).
b. Bronze casing.
c. Steel stator housing (aluminum on sizes 009 - 0014).
d. Stainless steel cartridge.
e. Non-metallic impeller.
f. Ceramic shaft.
g. Carbon bearings.
h. EPDM o-ring and gaskets.
i. Self lubricating.
j. No mechanical seal.
k. Permanent split capacitor, impedance protected motor.
l. Replaceable cartridge design, field serviceable.
m. Direct drive.
n. Anti-condensate baffle to protect motor windings (sizes 0011, 0012 and 0013).

.2 Support piping at or near the pumps flanged connections. Ensure that pump body does not support piping or equipment.

.3 Check motor bearing lubrication points are accessible.

.4 Check rotation and flow direction arrows.

.5 Install a minimum of 24" (600mm) straight run piping between elbow and pump.

.6 Lubricate motor and bearings according to manufacturers recommendations prior to start-up.

.7 For model, accessories and performance requirements, refer to Equipment Schedule on the drawings.

2.17 Domestic Water Expansion Tank

.1 Units shall be Amtrol ST series or approved equal having the following features:

a. Stainless steel connector.
b. Deep drawn steel domes.
c. Rigid polypropylene liner for corrosion resistant reservoir.
d. Butyl diaphragm.
e. Diaphragm hoop ring mechanically grooved for permanent air-tight seal.
f. Welded steel construction.
g. Welded air charge fitting with protective plastic cap.

.2 For model, accessories and performance requirements, refer to Equipment Schedule on the drawings.

2.18 Draining Water Systems

.1 Drain and refill as applicable all existing water systems as required to permit revisions as indicated on the drawings.

2.19 Testing and Inspection

.1 Test drainage, vent and domestic water piping to Plumbing Code requirements. Repair all leaks to the inspection authority and / or the Consultant's approval.

.2 All leaks shall be repaired by remaking the joint. After piping systems have been tested and repaired, repeat tests.

.3 All equipment / devices which may be damaged by test pressures shall be isolated during testing procedures.

2.20 Cleaning and Flushing

.1 Disinfect all new domestic water piping as follows:

a. Inject Quatic Chemicals Q-CHLOR or approved equal cleaning agent into the water system at a rate of 20 lbs (9.1 Kg.) per 1000 USG (3785 L).
b. Operate valves, faucets and similar appurtenances while the piping contains chlorine solution.
c. Measure chlorine residuals at the extreme end of each piping circuit. After a chlorine residual of not less than 50ppm has been obtained, leave the system for 24 hours.
d. Flush completely, test for residual and flush again as necessary to remove all cleaning solution.
e. Perform a water quality / bacteria analysis prepared by an independent lab to verify that the system is clean and suitable for consumption, and certifying that the chlorine content is less than 10ppm.

.2 During flushing and cleaning maintain all isolating and control valves in the open position.

2.21 Approved Products List

.1 Pipe Hangers

a. Taylor Walraven
b. Crane
c. Unistrut
d. Myatt

.2 Valves and Strainers

a. Kitz
b. Crane
c. Watts
d. Toyo
e. M.A. Stewart
f. Apollo
g. Mueller
h. Victaulic

.3 Plumbing Fixtures

a. Fiat
b. Stern Williams
c. Zurn

.4 Plumbing Trim

a. Delta Commercial
b. Moen Commercial
c. Sloan
d. Chicago

.5 Plumbing Specialties

a. Zurn
b. Ancon
c. Mifab
d. Jay R. Smith
e. Precision Plumbing Products

.6 Recirculating Pumps

a. Taco
b. Grundfos
c. Xylem B&G
d. Armstrong

.7 Domestic Water Expansion Tanks

a. Amtrol
b. Watts
c. Taco
d. Xylem B&G
e. Wessels
f. Armstrong

**END OF SECTION**

## 1. GENERAL

1.1 General Requirements

.1 Refer to Division 20 – Mechanical.

## 2. HOT WATER HEATING

2.1 Supports

.1 Provide all of the required pipe hangers and supports.

.2 Pipe and equipment supports shall be Taylor Walraven or approved equal of spacing and type as recommended by manufacturer, in accordance with Code requirements and in accordance with good commercial standards.

.3 Provide supports to secure pipes, prevent pipe vibration, maintain required grading, allow for expansion and contraction and produce a neat appearance. Design for strength and rigidity to suit loading and services, prevent undue stress to structural members and with provision for vertical adjustment after piping is erected.

.4 Clamp vertical pipes solidly at every other floor level (intervals not to exceed 25'(7.6m)) in such a manner that expansion can take place in an upward direction. Support piping independent of connected horizontal pipework.

.5 Offset hanger pipe and structural attachments in such a manner that rod is vertical when piping is hot and is subject to tensile loading only.

.6 Adjust hanger rods to equalize load.

.7 Provide supplementary structural steelwork where structural bearings do not exist.

2.2 Hot Water Heating Piping

.1 Above Ground Metal Piping (Contractor to choose desired type):

a. Piping to NPS 6" (150mm) shall be ERW or seamless schedule 40, Grade B black steel complying with ASTM A53 / A53M.
b. Piping to NPS 3" (75mm) may be type L hard copper complying with ASTM B88.
c. Fittings shall be to the following as applicable:
    i. Malleable iron screwed fittings, Class 150 to ASME B16.3.
    ii. Steel pipe flanges and flanged fittings, Class 150 to ASME B16.5. Welding neck flanges shall be bored to match the same inside dimension as the attached pipe.
    iii. Steel butt-welding fittings to ASME B16.9 and with the same wall thickness as the attached pipe.
    iv. Malleable iron unions, Class 150 to ASME B16.3. Unions 2.5" (63mm) and larger shall be made with flanges.
    v. Sweat wrought copper or cast brass soldered fittings for Type ‘L’ copper piping.

vi. All fittings shall be long radius type.
vii. Grooved pipe couplings and fittings may be used as specified elsewhere in this specification.

d. Connections shall be to the following as applicable:
i. Piping NPS 2" (50mm) and under: screwed or soldered.
1) For screwed piping connections, use teflon tape (pipe thread taper to ASME B2.1).
2) Where copper piping is used joints shall be 95-5 hard solder.
ii. Piping NPS 2.5" (63mm) and over:
1) Welded fittings to CSA W47.1
2) Flanged:
I Flanges shall be flat or raised face as required to match the mating flange.
II Nuts and bolts shall be carbon steel square head machine bolts and heavy hex head nuts, to ASME B18.2.1 and ASME B18.2.2.
III Gaskets shall be to ASME B16.21, ASME B16.20 or ASME A21.11 and shall be spirally wound type 316L stainless steel with non-asbestos filler material and carbon steel outer ring, 0.125" (3.1mm) thick, conforming to the flange face on which they are used.
3) Grooved pipe couplings and fittings may be used as specified elsewhere in this specification. **Grooved pipe couplings recommended in attic space to eliminate hot work (welding) for piping in attic.**

2.3 Valves

.1 General

a. All valves shall have a pressure rating suitable for the system operating pressure.
b. Similar valves shall be of the same manufacturer.
c. All valves supplied for this project shall have a current and valid Canadian Registration Number for the Province of Ontario with TSSA. Suppliers shall provide a copy of the Statutory Declaration for valves, stamped, signed and dated by TSSA as validation of the CRN registration. This shall be provided along with the shop drawing submittal package.
d. Provide stem extensions / extended necks as required to suit insulation thickness.
e. Use only commercial grade valves meeting ANSI, ASTM, ASME and applicable MSS standards. Specification MSS-SP-80, MSS-SP-110, MSS-SP-70, 85, 71, MSS-SP-72, MSS-SP-67, API 602, API 598, API 609, API 600.

.2 All valves shall be to the following or approved equal:

a. Up to and including NPS 2" (50 mm), bronze valves as follows:
i. Isolation:
1) Ball valve complete with 2 piece forged brass body, stainless steel trim, blowout proof stem, PTFE seats, maintenance free double o-ring stem seals and full port design. Valves shall be pressure rated to

150 WSP / 600 WOG and conform to MSS-SP 110 and certified to CSA.

I Threaded valves: Kitz 68AMLL or approved equal.

II Soldered valves: Kitz 869AMLL or approved equal.

b. NPS 2.5" (63 mm) and over, cast iron valves follows:

i. Isolation:

1) Butterfly valve, 1380 KPA / 200WOG Rating. Butterfly valves shall be lugged type, Epoxy Coated Ductile iron body, with 2" extended neck to allow for insulation, stainless steel disc, PTFE (with EPDM backing) bonded seat, stainless steel stem with top and bottom bushings of dissimilar material. Valve shall have bubble tight shut-off to 200PSI when downstream flange is removed (Full dead-end service). Valves 150MM (6") and smaller shall have locking lever operator, valves 200MM (8") and larger shall have locking Manual Gear operator.

I MAS L-D-4-S-PE-LH (Lever) or approved equal.

II MAS L-D-4-S-PE-G (Gear) or approved equal.

ii. Grooved end valves as described elsewhere in this specification.

c. Circuit Balancing Valves: Victaulic / IMI TA Hydronics valves for precise flow measurement, balancing, and positive shut-off. Each valve to be variable orifice, wye pattern, globe style with self-sealing EPDM measurement points, EPDM seat, and digital handles with locking hidden tamper-proof setting. Valves shall be selected based on flow requirement. Suitable for operating temperatures to 248°F (120°C).

i. ½" through 2": 400 psi, non-ferrous Ametal® DZR brass copper alloy body, EPDM O-ring seals. 4-turn digital readout handwheel for balancing, hidden memory feature with locking tamper-proof setting. Brass shall be ISO 6509 compliant. Victaulic / IMI TA Series 786H/787H/78KH. Install Victaulic Koil-Kits including Series 78Y strainer/ball valve/drain (or Series 78T ball valve/drain where strainer not required), with Series 78U union port fitting and coil hoses to complete terminal hookup.

ii. Valves shall be installed as follows:

1) With flow in the direction fo the arrow on the valve body.
2) At least five pipe diameters downstream from any fitting.
3) At least 10 pipe diameters downstream from any pump.
4) Two pipe diameters upstream of any fitting.
5) With easy and unobstructed access to the valve handwheel and metering ports.
6) To prevent sediment build-up in the metering ports.

d. Drain valves:

i. Two piece forged brass body, chrome plated ball, blowout proof stem, PTFE seats / seals, PP or brass cap and chain, full port design. Valves shall be pressure rated to 150 WSP / 600 WOG.

1) Threaded / hose valves: Kitz 68C or approved equal.
2) Soldered / hose valves: Kitz 69C or approved equal.

ii. Provide tamper proof vacuum breaker.

2.4 Strainers

.1 For sizes to 2" (50mm), Kitz 15 (threaded ends) / 16 (soldered ends) or approved equal Y-pattern type complete with cast bronze body, threaded brass cap with plug and type 304

stainless steel having 0.031" (0.8mm) perforations. Valves shall be pressure rated to 150 WSP / 300 WOG.

.2 Grooved joint strainers as described elsewhere in this specification.

2.5 Grooved Piping

.1 As an alternate to the fittings / connections / valves specified above for piping 2.5" (63mm) and larger, grooved mechanical pipe couplings, fittings, valves and components manufactured by Victaulic or approved equal may be used.

.2 All grooved components shall be of one manufacturer and conform to local codes. Grooving tools shall be of the same manufacturer as the grooved components.

.3 Grooved couplings shall conform to (or meet the intent of) ASTM F-1476.

.4 Roll or cut grooved ends as appropriate to pipe material, wall thickness, pressures, size and method of joining. Pipe ends shall be grooved in accordance with Victaulic current listed standards conforming to ASME / AWWA C-606.

.5 Couplings 2" (50mm) through 24" (600mm):

a. Two coupling housings shall be cast of ductile iron.
b. Mechanical couplings shall be Victaulic style 107V 'installation ready' stab-on design, or Victaulic Style W07 AGS design, providing system support and hanging requirements in accordance with ASME B31.1 and ASME B31.9. Victaulic Style Style 177 'installation ready' stab-on coupling, Style 77 or 75 standard coupling or Style W77 AGS design shall be installed at mechanical equipment / pump connections (a minimum of three flexible couplings shall be installed between the equipment / pump and the first rigid coupling).
    i. 107V Housings cast with torque-absorber and shift-limiting slant bolt pad design to provide piping system rigidity and support and hanging in accordance with ANSI B31.1 and B31.9, and to prevent mis-assembly due to overshift. Housings cast with alignment indicator notch for visual proper alignment to adjoining fitting. Basis of Design: Victaulic Installation-Ready™ Style 107V.
c. Provide Victaulic style 750 reducing couplings and Victaulic style 72 outlet couplings as required to suit piping installation.
d. Coupling fasteners (bolts, nuts, etc.) shall be zinc plated heat treated carbon steel track head conforming to physical properties of ASTM A-183 and A-449, minimum tensile strength of 110,000 Psi (758450 Kpa). All fasteners shall be provided by Victaulic.

.6 Flange adapters:

a. Vic-Flange adapter style 741 and W741 shall be used for connection to ASME class 125 / 150 flanged components. Style 743 shall be used for connection to ASME class 300 flanged components. Adapters shall be cast of ductile iron.
b. Number 41 / 45 flanged adapter nipples shall be used for connection to ASME class 125 / 150 flanged components. Nipples shall be of carbon steel , schedule 30 or 40,

ASTM A-53, type E, F or S, Grade B. Class 125 flanges shall be cast iron to ASME B-16.1 and Class 150 flanges shall be carbon steel to ASME B-16.5.

.7 Fittings and coatings:

a. Fittings shall be full flow ductile iron, steel or factory segmentally welded type with grooves or shoulders designed to accept Victaulic stab-on, standard, or AGS grooved end couplings.
b. All fittings and couplings shall be provided with an alkyd enamel finish.

.8 Miscellaneous components:

a. Provide Vic-Let style 923 and Vic-O-Well style 924 for vent, drain, pressure, temperature, taps, etc.
b. Branch reductions on 2.5" through 8" (63 through 200mm) header piping shall be made with Victaulic hole cut products, style 920 / style 920N mechanical AT@ outlet with locating collar engaging into hole or style 72 outlet coupling for use in joining grooved pipe with a branch connection at the joint.
c. Dielectric Waterway: Fittings shall be a copper-silicon casting conforming to UNS C87850, and UL classified in accordance with ANSI / NSF-61 for potable water service. Fittings shall have threaded ends, grooved ends, or a combination. Victaulic Style 647.

.9 Gaskets:

a. Standard and AGS coupling gaskets shall be Grade E EPDM compound conforming to ASTM D-2000 designation 2CA615A25B24F17Z. Temperature operating range shall be -30 to 230 deg. F. (-34 to 110 deg. C.)
b. 'Installation Ready' stab-on coupling center-leg gasket with pipe stop to ensure proper groove engagement, alignment, and pipe insertion depth, shall be Grade 'EHP' EPDM compound conforming to ASTM D-2000 designation 2CA615A25B24F17Z. Temperature operating range shall be -30 to 250 deg. F. (-34 to 121 deg. C).

.10 Butterfly valves:

a. Up to 12" (300mm): Victaulic Vic-300 MasterSeal, 300 Psig (2065 Kpa), grooved ends complete with ductile iron body coated with black enamel, electroless nickel coated ductile iron disc, offset from the stem centerline to provide continuous 360 degree seating, and memory stop, with pressure-responsive elastomer seat. Valves shall be capable of bi-directional shut-off and dead-end service at full rated pressure. Valve shall have lever handle, gear operator, or power actuator.

.11 Ball valves:

a. Up to 6" (150mm): Victaulic series 726 Vic-Ball standard port complete with ductile iron body, chrome plated carbon steel ball / stem, TFE seats, minimum 800 Psig (5515 Kpa).

.12 Strainers:

a. Victaulic style 732 and W732 Vic-strainer, Y-type complete with ductile iron body, type 304 stainless steel cylindrical removable baskets, 300 Psig (2065 Kpa). Sizes 2.5" (63mm) and 3"(75mm) shall be complete with 1/16" (1.6mm) diameter perforations and 41% open area. Sizes 4" (100mm) to 12" (300mm) shall be complete with 1/8" (3.2mm) diameter perforations and 40% open area. Size 14" (350mm) to 24" (600mm) shall be complete with 4mm diameter perforations and 41% open area.

.13 Installation:

a. Grooved joint piping systems shall be installed in accordance with the manufacturer's guidelines and recommendations.
b. All grooved couplings, fittings, valves, and specialities shall be supplied by a single manufacturer. Grooving tools shall be supplied by the same manufacturer as the grooved components.
c. The gasket style and elastomeric material (grade) shall be verified as suitable for the intended services as specified. Gaskets shall be molded and supplied by Victaulic or approved equal.
d. Grooved end shall be clean and free from indentations, projections, and roll marks in the area from pipe end to groove for proper gasket sealing.
e. A grooved joint manufacturer factory-trained field representative shall provide the on-site training to contractor's field personnel in the proper use of grooving tools and installation of grooved piping products.
f. A factory trained representative shall periodically review the product installation. Contractor shall remove and replace any improperly installed products.
g. Install the Victaulic Advanced Grooved System (AGS) or approved equal in accordance with the latest Victaulic installation instructions. Use grooving tools with AGS roll sets to groove the pipe. Follow grooved joint manufacturer’s guidelines for tool selection and operation. Coupling installation shall be complete when visual metal-to-metal contact is reached. AGS products shall not be installed with standard grooved end pipe or components. Installing AGS products in combination with standard grooved end products could result in joint separation and/or leakage.

2.6 Air Vents

.1 Automatic air vents shall be Taco model 400 Hy-Vent or approved equal. Install air vents and collecting chambers at high points of heating system, where indicated on the drawings and in all locations where air can be trapped including unit heaters and heating coils. Provide stop cock to facilitate removal of vent without draining the heating system.

.2 Convectors, cabinet heaters and other heating units fed from supply and return mains or branches that are located below radiation units shall be vented with a manual air vent. Manual vents shall be Taco model 417 or approved equal.

2.7 Thermometers

.1 Winters 91T or approved equal, industrial variable angle type, complete with 9" (225mm) scale length, dual scale (imperial and metric - deg. F. / deg. C.), aluminum case, glass lens, cast aluminum bulb chamber with graphite fill and organic fluid. Provide standard range so that operation is at midpoint of scale and brass thermometer well complete with extension where installed through insulation.

.2 Locate thermometers so that they can be easily read from the floor.

2.8 Pressure Gauges

.1 Winters PCT or approved equal complete with 4.5" (113mm) white aluminum dial, acrylic lens, dual scale (imperial and metric - Psi / Kpa), bronze tube, brass socket, type 304 stainless steel case and adjustable pointer. Provide standard range so that operation is at midpoint of scale. Provide brass stop cock.

.2 Locate gauges so that they can be easily read from the floor.

2.9 Piping Installation Requirements

.1 Piping shall be installed according to good commercial standards and approximately as follows:

a. All piping running vertically shall run concealed in wall construction / furred enclosures unless noted otherwise on the drawings. Under no condition is any piping to be installed in concealed spaces in outside walls.
b. Use unions, flanged or grooved joints in sufficient quantities to facilitate removal of equipment without removal of long lengths of pipe.
c. Install eccentric reducers in horizontal piping to permit drainage and eliminate air pockets.
d. Where pipe sizes differ from connection sizes of equipment, install reducing fittings close to equipment. Reducing bushings are not permitted.
e. All valves and other pipe accessories shall match the associated pipe size unless noted otherwise.
f. Cut ends of pipes square, ream, clean scale / dirt and assemble without binding.
g. Install copper tubing so that it is not in contact with dissimilar metal and will not be kinked or collapsed.
h. Plug or cap pipe and fittings to keep out debris during construction.
i. All piping shall be laid straight and in true alignment to the slopes of the pipe, as indicated on the drawings and / or as directed.
j. Install piping free from strains and with proper allowance and off-sets for thermal expansion and contraction.
k. Slope piping up in direction of flow at a minimum rate of 1/20" per foot (0.43mm/100mm) length and provide drain at low points. The entire hot water heating system shall be capable of being drained.
l. Take heating branches off piping mains at 45 degrees looking up when feeding above and 45 degrees looking down when feeding below.
m. Provide all piping connections to all mechanical equipment, including air handlers, pumps, convectors, unit heaters, automatic control valves, etc. with valves and unions located so that removal of equipment is possible without disconnecting more than a minimum amount of pipework, shutting down other pieces of equipment or draining the entire system.
n. Install a minimum of 14" (350mm) straight run piping between pipe elbows, valves, pumps or other fittings unless noted otherwise on the drawings.
o. Provide clearance for maintenance of equipment, valves and strainers.

2.10 Pumps

.1 Where listed in the Equipment Schedule, pumps shall be Taco 1900 series or approved equal having the following features / construction details:

a. Maximum operating pressure: 175 PSI (1200 Kpa).
b. Mechanical seal temperature rating: 250 deg. F. (121 deg. C.).
c. Cast iron casing.
d. Dynamically balanced stainless steel impeller.
e. Type 21 ceramic mechanical seal.
f. Pressure tappings to allow differential pressure readings across the pump.
g. Non-corrosive shaft sleeve.
h. NEMA standard 56 frame C face motor.
i. The complete pump shall have a hydrostatic and performance test before shipment.

.2 Support piping at or near the pumps flanged connections. Ensure that pump body does not support piping or equipment.

.3 Check rotation and flow direction arrows.

.4 For model, accessories and performance requirements, refer to Equipment Schedule on the drawings.

2.11 Draining and Refilling the Hot Water Heating System

.1 This Contractor shall be responsible for draining and refilling the heating system to permit revisions as noted on the drawings.

.2 All new and affected existing piping system (mains and branch piping) shall be flushed and cleaned as follows, in the specified order:

a. Flush using raw water to ensure removal of heavy debris and excessive oil or dirt.
b. During flushing, maintain all isolating and control valves in the open position.
c. Do not flush piping through equipment which could be damaged by pipe debris (coils, boilers, radiant heaters, etc.). Provide necessary bypass piping.
d. All strainers shall then be cleaned.
e. Clean with Quatic Chemicals Series 6002 neutral pH cleaner or approved equal. The cleaner shall be introduced into system at a dosage of 2 gallons per 100 gallons (9.0 litres per 455 litres) of water in the system and circulated for 24 hours at ambient temperature.
f. The complete system shall then be drained as quickly as possible using all available drain valves.
g. Immediately refilled with fresh water and circulate for a minimum of 60 minutes.
h. The complete system shall then be drained and refilled. If any foaminess or discolouration is still present, the system will require repeated draining and refilling. Ensure that all residual cleaner has been removed to the approval of the chemical treatment manufacturer.
i. Following cleaning / flushing procedures, clean strainers and immediately fill system.
j. Make all necessary provisions in the piping system for the introduction of the cleaning chemicals.

.3 Chemically treat the heating water according to the existing chemical treatment manufacturer's recommendations. All chemicals shall be supplied by Owner and installed by This Contractor.

.4 Chemically treat the heating water according to the existing chemical treatment manufacturer's recommendations.

.5 Adjust PH levels according to water treatment supplier recommendations so that damage does not occur to the aluminium boilers.

2.12 Hydronic Heating Equipment

.1 General:

a. All heating units shall be Sigma or approved equal of the types listed in the Schedules on the drawings.
b. Provide for noiseless expansion of all components.
c. Radiation output and air / water operating temperatures shall be as indicated on the drawings.
d. Installation shall be in strict accordance with the manufacturer's recommendations.
e. All cabinets / enclosures shall be complete with primer finish suitable for field painting.

.2 Wallfin (enclosure only):

a. Enclosure:
   i. The enclosure shall be of a type indicated on the drawings.
   ii. Enclosures shall be manufactured from 16 gauge steel and finished with a primer finish suitable for field painting.
   iii. The enclosure shall be suitable reinforced to withstand a loading of 150 pounds per linear foot (223 kg. / meter).
   iv. The enclosure shall be continuous wall to wall or as shown on the drawings.
   v. Panels shall have a 0.75" (19mm) return edge around the perimeter to provide rigidity.
   vi. Covers shall be removable by hand without any tools.
   vii. The top outlet of the enclosures shall have stamped louver grilles that extend the entire length of the panels.
   viii. The inlet of the enclosure shall be open.
   ix. Manufacturer shall provide all accessories (endcaps, trim pieces, corners, hanger strips, brackets, joiner pieces, etc.) for a complete installation.

.3 Unit Heaters:

a. Casing shall be constructed of minimum 18 gauge cold rolled steel and shall be complete with a factory mounted four way adjustable louvered diffuser and integral 3/8" (10mm) threaded hanger connections.
b. The copper-aluminum heating element shall consist of rippled aluminum fins mechanically bonded to 0.5 (13mm) copper tubes.
c. Headers shall be provided with steel MPT pipe connections located at the back of the unit.

d. The fan shall be aluminum blade type, factory dynamically and statically balanced, direct connected to the motor shaft and complete with a fan guard.
e. Motors shall incorporate sleeve bearings and automatic reset overload protection.

.4 Provide accessories as listed in the Schedule on the drawings.

2.13 Flow Switches

.1 Watts or approved equal model FS10-C complete with copper paddle. Paddle length shall suit pipe size and shall be trimmed as required.

.2 Install where indicated on the drawings. Install in horizontal pipe or in vertical pipe with upward water flow. Do not install in vertical piping where the water flow is downward. Maintain a straight run of at least five pipe diameters on each side of the switch (do not locate adjacent to valves, elbows, etc.).

2.14 Testing and Inspection

.1 Test hot water heating piping at 1.5 times the system operating pressure or 125 Psig (860 Kpa), whichever is greater for a minimum 4 hour period or as may be necessary to determine if there is leakage. Repair all leaks to the Consultants approval.

.2 All leaks shall be repaired by remaking the joint. After piping systems have been tested and repaired, repeat tests.

.3 All equipment / devices which may be damaged by test pressures shall be isolated during testing procedures.

.4 Lines containing check valves shall have the source of test pressure located on the upstream side.

2.15 Approved Products List

.1 Hydronic Heating Equipment

a. Engineered Air
b. Sigma
c. Rosemex
d. Kampmann

.2 Pumps

a. Taco
b. Armstrong
c. Xylem B&G
d. Grundfos

.3 Expansion Tanks

a. Amtrol

b. Armstrong
c. Xylem B&G
d. Taco
e. Wessels

.4 Air Vents

a. Crane
b. Maid-O-Mist
c. Sparco
d. Watts
e. Taco
f. Armstrong

.5 Pipe Hangers

a. Taylor Walraven
b. Crane
c. Unistrut
d. Myatt

.6 Valves and Strainers

a. Kitz
b. Crane
c. Watts
d. Toyo
e. M.A. Stewart
f. Apollo
g. Mueller
h. Victaulic

.7 Pressure Gauges / Thermometers

a. Trerice
b. Dwyer
c. Baker
d. Taylor
e. Ashcroft
f. Winters

## 3. HEATING, VENTILATING AND AIR CONDITIONING

### 3.1 Ductwork

.1 All ductwork shall be G-60 galvanized steel unless noted otherwise, in accordance with ASTM A-653 and A-924. Thickness and fabrication shall be to ASHRAE and SMACNA standards.

.2 Fittings and joints shall be fabricated and installed to ASHRAE and SMACNA standards. Proprietary duct joints as manufactured by Ductmate Canada Ltd. or approved equal may be used where desired by the Contractor.

.3 All exposed above ground circular ductwork shall be spiral type as follows:

a. Ductwork shall be constructed of Satin Coat steel.
b. Duct and fittings shall be constructed in accordance with the latest SMACNA HVAC Duct Construction Standard.
c. Straight Duct:
    i. The straight duct shall be constructed with an interlocking 4-ply helical seam that runs the complete length of the duct. The grooved seam shall be located entirely on the outside, resulting in a smooth interior for a low friction loss.
    ii. The straight duct shall be smooth type (corrugations / grooves to increase rigidity are not required).
d. Fittings:
    i. Fittings shall be standing seam or pressed / stamped type.
    ii. Fittings shall be '1.5D' type unless not possible due to space restrictions.
e. Straight duct sections and fittings shall utilize slip-joint connections. Provide couplings where joining straight duct sections. .

.4 Non-metallic flexible ductwork shall be Thermaflex S-LP or approved equal, non-collapsible woven and coated fibre glass fabric permanently bonded to a coated spring steel wire helix. Where flexible ductwork is connected to thermally insulated rigid ductwork, flexible ductwork shall be thermally insulated type, Thermaflex G-KM or approved equal. Flame and smoke developed ratings not to exceed 25 and 50 respectively. Ducts shall comply with ULC, NFPA and SMACNA standards.

.5 Maximum length of flexible ductwork shall be 5'-0" (1500mm).

.6 All duct runnouts shall have a diameter the same size as the diffuser neck size unless noted otherwise.

.7 All rectangular supply / return / exhaust ducts shall connect to main ducts complete with 45 degree entry. This shall include branches serving grilles mounted directly to the duct except that for grilles mounted to exposed spiral duct work a square entry is permitted.

.8 All supply / return / exhaust elbow fittings shall have a centreline radius equal to 1.5 times the duct width for rectangular ducts or 1.5 times the diameter for round ducts. Where absolutely not possible due to space constraints, a centreline radius of 1 times the width (or diameter) shall be permitted or square elbows complete with turning vanes shall be permitted.

.9 All supply, exhaust and return air ductwork shall be complete with sealed joints as follows:

a. Supply, return and exhaust ductwork shall be Seal Class A in accordance with ASHRAE 90.1-2022 and as defined in SMACNA standards (transverse joints / connections, longitudinal seams and duct wall penetrations made airtight with sealing compound).
b. Note that spiral ductwork having a sealing gasket requires no sealing compound.
c. Exposed ductwork shall be neatly sealed to the approval of the Consultant, without excess caulking.

.10 Provide suitable sheet metal angle collar for ductwork running exposed through walls, ceilings or floors. Install collar tight against the wall, ceiling or floor and duct, sized to cover opening.

3.2 Ductwork Leakage Testing

.1 Perform ductwork leakage testing for ductwork where static pressure exceeds 3" WC (0.75 kPa) and for all ductwork located outdoors in accordance with ASHRAE 90.1-2022. Perform leakage testing in accordance with procedures outlined in SMACNA. System static pressure shall be defined by the associated fan external static pressure.

.2 Perform testing on representative sections of ductwork totaling no less than 25% of total installed duct area for each system being tested.

.3 Repair and re-seal ductwork, and re-test system(s) as required such that measured leakage does not exceed the maximum permitted duct leakage for each system tested. Maximum permissible pressure shall be calculated for each system tested according to ASHRAE 90.1-2022.

.4 Provide report of leakage testing result for submission to Consultant / Owner / Local Authority and include in closeout documentation. Indicate maximum permissible duct leakage for each system tested.

3.3 Turning Vanes

.1 Factory or shop fabricated single or double thickness to recommendations of SMACNA.

3.4 Supports

.1 All ducts shall be adequately supported. Maximum size to be supported by a strap hanger shall be 36" (900mm) wide. All other ducts shall be supported by steel angles complete with threaded rods, locking nuts and washers. Threaded rods shall be sized according to the recommendations of Taylor Walraven to suit the application. Hanger spacing shall comply with SMACNA standards.

.2 Ducts cannot in any location be supported from the furring or ceiling construction. Also, ducts cannot be supported in any location from metal floor or roof decks.

.3 All pipe and equipment supports shall be as follows:

a. Supports shall be Taylor Walraven or approved equal of spacing and type as recommended by manufacturer, in accordance with Code requirements and in accordance with good commercial standards.
b. Provide supports to secure equipment, prevent pipe vibration, maintain required grading, allow for expansion and contraction and produce a neat appearance. Design for strength and rigidity to suit loading and services, prevent undue stress to structural members and with provision for vertical adjustment after piping is erected.
c. Offset hanger and structural attachments in such a manner that rod is vertical when equipment is at operating temperature and is subject to tensile loading only.
d. Adjust hanger rods to equalize load.

e. Provide supplementary structural steelwork where structural bearings do not exist.

.4 Supports for exposed spiral ductwork shall consist of a steel rod centered over the duct and attached to a continuous band around the duct.

.5 Where desired by the Contractor, the spiral ductwork may be supported using the Gripple Hangfast system as follows:

a. The system manufacturer shall supply the locking mechanism (gripple) and the wire rope. Rope not supplied by the manufacturer shall not be used with the locking mechanism.
b. The locking mechanism shall be fully adjustable, manually in an ascending movement and descending by the way of a setting key.
c. The release mechanism shall not be accessible and will only be operable by the use of a key system.
d. The wire rope shall be galvanized steel wire manufactured in accordance to BS 302 (1987). The rope shall have a ferrule loop at one end.
e. The wire rope shall not have any paint or other coating applied to it. This specifically includes lubricant.
f. Manufacturer's weight loading recommendations shall be adhered to for selecting system components.
g. The system shall conform and be approved by all local, Provincial and Federal authorities.
h. The wire rope may be looped directly around the bottom cord of the roof structural members or other appropriate supports.

3.5 Roof Curbs

.1 All curbs for roof mounted exhaust fans, rooftop units, goosenecks, etc. shall be supplied and installed by the Mechanical Contractor.

.2 Roof curbs shall be galvanized steel with wood nailer strip, turndown flange and shall be capable of supporting the entire unit weight. Curbs may be bolted together on site where required for ease of transporting to site.

.3 Provide a closed cell curb gasket with adhesive on one side to seal between the ductwork / roof mounted equipment and the top of curb.

.4 Suitably secure curbs to the roof deck and level according to manufacturer's recommendations. The sides of curbs shall be insulated on the exterior with insulation of the same type and having the same thickness as the new / existing roof insulation.

.5 Roof curbs shall be 24" (610mm) high unless noted otherwise.

3.6 Duct Access Doors

.1 Provide duct mounted access doors to service all mechanical equipment requiring maintenance access (including fire dampers, motorized dampers, heating coils, etc.). Provide doors on one or both sides of device as required to permit full service / cleaning. Doors shall be Nailor-Hart series 0800 or approved equal, insulated sandwich construction complete with

sheet metal angle frame, 1" (25mm) thick insulation, gaskets and camlocks. Sizing to manufacturer's recommendations to suit application.

3.7 Duct Sealant

.1 Interior duct sealant shall be Bakor Duck-Seal or approved equal having a maximum flame and smoke rating of 25 and 50 respectively. Exterior duct sealant shall be Bakor 530-09 or approved equal having a maximum flame and smoke rating of 25 and 50 respectively.

3.8 Flexible Duct Connections

.1 Unless noted otherwise, duct connections to air handling (HVAC) units and exhaust fans shall be made using flexible duct connections, Duro-Dyne "Super Metal-Fab" or approved equal having the following features:

a. 24 gauge (0.7mm) galvanized steel frame.
b. Each frame shall be 3" (75mm) wide and the fabric shall be 6" (150mm) wide.
c. Seams: Grip Loc
d. Fabric: woven fiberglass complete with a neoprene coating, -40 to 200 deg. F. (-40 to 82 deg. C.) continuous operating temperatures.
e. Suitable for pressures from -10" wc. to 15" wc. (-2.5 to 3.7 Kpa) with no tearing or visible separation.
f. Airtight and waterproof.
g. Designed to meet NFPA 701, 90A and 90B.

.2 Flexible duct connections are not required to serve the following equipment:

a. Supply / exhaust fans having capacities less than 150 CFM (70 L/S).

.3 Flexible connectors used for plastic duct systems shall be fabricated from flexible plasticized PVC material (not less than 0.094" (2.4mm) thick)r having corrosion resistance and temperature compatibility suitable for the envionment. Longitudinal seams shall be sealed by machine fusion welding.

3.9 Combination Fire / Smoke Dampers

.1 Combination fire/smoke dampers shall be Nailor series 1270 series or approved equal constructed as follows:

a. Frame shall be constructed of 16 gauge galvanized steel hat channel with mitered corners reinforced with die-formed corner gussets for strength.
b. Blades shall be of triple-vee design, 16 gauge galvanized steel, on 5.5" (138mm) centers and shall be parallel configuration.
c. Blade axles shall be 0.5" (13mm) diameter plated steel, double bolted at each end of blade to ensure positive locking connection. Hex or square friction-fit or press-fit axles are not acceptable.
d. Bearings shall be self-lubricating oilite bronze type.
e. Blade linkage shall be zero-maintenance, concealed in frame, out of airstream.
f. Jamb seals shall be compression type stainless steel. Blade seals shall be silicone.

.2 Dampers shall meet the requirements of NFPA 90A, 92A and 92B and shall be classified by UL and labeled as a 1.5 hour fire damper under UL 555 and as a Class II Leakage Rated smoke damper under UL555S at an elevated temperature of 350 deg. F. (177 deg. C.).

.3 Dampers shall be qualified for use in dynamic or static Smoke Control Systems.

.4 Dampers shall be supplied with factory installed sleeves (optional field supplied sleeves may be supplied where desired by the Contractor) of minimum 16" (400mm) length, to be field verified by Contractor to suit the wall thickness. Sleeves shall be caulked to UL requirements and shall be 20 gauge through 84" (2100mm) wide, and 18 gauge above 84" (2100mm) wide. Provide type A, B or C sleeve to suit installation.

.5 A Honeywell or approved equal model ML4115, 120 volt actuator (power open, spring close) shall be installed by the damper manufacturer in the factory and shall have been tested and classified under UL555S with the damper at an elevated temperature of 350 deg. F. (177 deg. C.). Actuators shall incorporate an OEM internal spring return mechanism. External after-market spring mechanisms are not acceptable. Damper and actuator assembly shall be factory cycled a minimum of three times to ensure correct operation.

.6 Each damper shall be equipped with a UL Classified heat responsive device that will cause the damper to close in a controlled manner and lock in a closed position by means of an over center / knee lock linkage, when the duct temperature reaches the maximum degradation temperature of the damper / actuator assembly as required by UL555S. Closure devices that cause instantaneous closure are not acceptable.

3.10 Motorized Dampers

.1 For dampers exposed to outdoor conditions, Tamco series 9000 BF or approved equal, opposed blade action having the following features:

a. Extruded aluminum damper frame shall be 4" (100mm) deep, not less than .080" (2.03mm) thickness, with mounting flanges on both sides of the frame.
b. The entire frame shall be thermally broken by means of polyurethane resin pockets complete with thermal cuts.
c. Blades shall be of extruded aluminum profiles, internally insulated with expanded polyurethane foam and shall be thermally broken. The complete blade shall have an insulating factor of R-2.29 and a temperature index of 55.
d. Blade and frame seals shall be of extruded silicone, for reduced air leakage at colder temperatures. Blade and frame seals shall be secured in an integral slot within the aluminum extrusions and shall be mechanically fastened to prevent shrinkage and movement over the life of the damper.
e. Bearings shall be composed of a celcon inner bearing fixed to a 7/16" (11.1mm) aluminum hexagon blade pivot pin, rotating within a polycarbonate outer bearing inserted in the frame.
f. An adjustable 7/16” (11.1mm) hexagonal drive rod, u-bolt fastener, and hexagonal retaining nuts shall be zinc-plated steel.
g. Aluminum and corrosion-resistant zinc plated steel linkage hardware shall be installed in the frame side, complete with cup-point trunnion screws for a slip-proof grip.

h. Dampers shall be designed for operation in temperatures ranging from -40 deg. F. (-40 deg. C.) to 212 deg. F. (100 deg. C.).
i. Dampers shall be leakage Class 1A at 1" w.c. (0.25 Kpa) static pressure differential. Standard air leakage data shall be certified under the AMCA Certified Ratings Program.
j. Dampers shall be opposed blade action.
k. Dampers shall be made to the sizes indicated on the drawings without blanking off free area. Mounting type shall be Aflanged to duct@ only.
l. Dampers shall be installed according to the manufacturers installation guidelines.

3.11 Manual Dampers

.1 For round ductwork 20" (500mm) diameter and less, provide single blade butterfly dampers, Nailor model 1890 or approved equal. Dampers shall be constructed and configured to the recommendations of SMACNA. Provide the following construction features:

i. 22 guage (0.86mm) galvanized steel frame with roll-formed stiffening beads up to 12" (300mm) diameter, 20 guage (0.91mm) over 12" (300mm) diameter.
ii. 22 gauge (0.86mm) galvanized steel blade up to 12" (300mm) diameter, 20 guage (1.0mm) over 12" (300mm) diameter.
iii. Blade axle / drive shaft shall be 0.25" (6mm) square plated steel.
iv. Hand locking quadrant.
v. Where dampers are installed in thermally insulated ductwork, provide 2" (50mm) stand-off bracket for hand quadrant.

.2 For rectangular ductwork, provide single blade dampers for ducts sizes up to 24" x 12" (600x300mm), Nailor model 1870 or approved equal. Dampers shall be constructed and configured to the recommendations of SMACNA. Provide the following construction features:

i. 18 gauge (1.3mm) galvanized steel frame with structural ribs for maximum strength and low profile for maximum free area.
ii. 20 gauge (1.0mm) galvanized steel blades up to 24"x12" (600x300mm) complete with structural ribs for extra strength.
iii. Blades shafts shall be 0.25" (6mm) square plated steel complete with a hand locking quadrant.
iv. Where dampers are installed in thermally insulated ductwork, provide 2" (50mm) stand-off bracket for hand quadrant.
v. For dampers installed in aluminum ductwork, provide aluminum frame and blades with stainless steel linkage, bearings, axles and related hardware.

.3 For rectangular ductwork, provide multi-blade were duct sizes exceed 24" x 12" (600x300mm), Nailor model 1820 or approved equal. Dampers shall be constructed and configured to the recommendations of SMACNA. Provide the following construction features:

i. 16 gauge (1.6mm) galvanized steel hat channel frame with die-formed corner gussets.
ii. 16 gauge (1.6mm) galvanized steel vee groove design blades on maximum 6" (150mm) centers in opposed configuration.
iii. Blade axles shall be 0.5" (13mm) diameter plated steel, double bolted to blades.

iv. Bearings shall be 0.5" (13mm) Celcon molded synthetic type
v. Plated steel blade linkage shall be concealed type, totally enclosed within the frame and out of airstream.
vi. Provide 6" (150mm) long by 0.5" (13mm) diameter lock-on drive shaft on each damper section complete with a hand locking quadrant.
vii. Where dampers are installed in thermally insulated ductwork, provide 2" (50mm) stand-off bracket for hand quadrant.
viii. For dampers installed in aluminum ductwork, provide stainless steel construction.

.4 Rectangular backdraft dampers shall be Nailor model 1370 or equal. Dampers shall be constructed and configured to the recommendations of SMACNA. Provide the following construction features:

a. Frame shall be constructed of type 6063-T5 extruded aluminum of minimum 0.090" (2.3mm) thickness. Provide welded metered corners and concealed reinforcing brackets.
b. Blades shall be constructed of type 6063-T5 extruded aluminum of minimum 0.050" (1.3mm) thickness. Provide extruded PVC blade seals mechanically fastened to blade edge. Adhesive type seals are not acceptable.
c. Bearings shall be long life synthetic type.
d. Blade linkage shall be concealed in frame for low pressure drop.
e. Counterbalances shall be of plated steel, mounted on rear of blades (in the airstream) and shall be field adjustable.
f. Provide frame type to suit duct configuration.

.5 Where manual balancing dampers are installed in exposed locations, the damper operator shall be installed on the top of the duct.

3.12 Grilles and Diffusers

.1 Krueger or approved equal. Refer to Diffuser and Grille Schedule on drawings for model and type.

.2 All aluminum grilles shall be fastened with stainless steel screws.

3.13 Duct Acoustic Insulation

.1 Johns Manville Linacoustic RC or approved equal flexible duct liner made with glass fibers bonded with a thermosetting resin. The airstream surface shall be protected with a Permacote acrylic coating with a flexible glass cloth reinforcement. A factory applied coating shall be applied to the edges of the liner core.

.2 Unless noted otherwise on the drawings, provide 1" (25mm) thickness having an R value of 4.2 hr.-sq.ft.-deg.F / Btu (0.74 sq.m.-deg.C/W) for all ductwork where indicated on the drawings. NOTE: WHERE ACOUSTIC LINING IS INSTALLED, SIZE OF DUCTWORK IS ACTUAL OUTSIDE DIMENSION OF DUCT.

.3 All portions of duct designated to receive duct liner shall be completely covered with liner. Transverse joints shall be neatly butted and there shall be no interruptions or gaps. The liner

surface designed to be exposed shall face the air stream. Duct liner shall be adhered to the sheet metal with 100% coverage of adhesive and all exposed leading edges and all transverse joints coated with adhesive. The liner shall be additionally secured with weld-on pins which shall compress the duct liner sufficiently to hold it firmly in place.

.4 Duct liner shall be cut to assure overlapped and compressed longitudinal corner joints. For velocities to 2,500 ft./min. (762 m/min.) the weld-on pins shall start within 3" (75 mm) of the transverse edges of the liner. Space with a maximum separation of 12" (300 mm) around the perimeter of the duct except that pins shall be a maximum of 4" (100mm) from a corner break. Elsewhere they shall be a maximum of 18" (450 mm) o.c.. All transverse edges shall be coated with adhesive.

.5 All insulation shall be applied according to manufacturer's recommendations.

.6 All insulation and components shall have maximum flame and smoke spread ratings of 25 and 50 respectively.

3.14 In-line Exhaust Fans

.1 Where listed in the Equipment Schedule, fans shall be PennBarry Zephyr or approved equal complete with permanently lubricated motor, built-in overload protection, backdraft damper, molded white plastic grille having 85% free area and held in place with quick attach springs (for ceiling mounted fans), dynamically balanced fan wheel, acoustically insulated galvanized steel housing and insulated access door (for in-line fans). The fan shall be capable of being changed from right angle discharge to top discharge or into an inline configuration in the field.

.2 Suspended units shall be complete with vibration isolation pads at all support points.

.3 For model, accessories and performance requirements, refer to Equipment Schedule on the drawings.

3.15 Downblast Roof Mounted Exhaust Fans

.1 Fans shall be PennBarry Domex or approved equal having the following features: Units shall have the following features:

a. Weatherproof housing utilizing heavy gauge spun aluminum construction with a large rolled bead for strength, a galvanized base and rigid galvanized steel internal support structures. The housing shall not provide any of the internal structural support.
b. Oversized electrical conduit chase through the curb cap and into the motor compartment.
c. Pre-wired to a junction box mounted in the motor compartment and equipped with an electrical disconnect device.
d. Statically and dynamically balanced, backward inclined, centrifugal wheels shall be aluminum, spark-resistant, non-overloading, matched to deeply spun venturis.
e. Belt drive fan assemblies shall be as follows:
    i. Motors shall be continuous duty, ball bearing design, permanently lubricated, mounted out of the main airstream.
    ii. Shafts shall be turned, ground, polished, and rust protected.

iii. Heavy duty ball bearings shall be selected for a minimum L50 life exceeding 200,000 hours.
iv. Pulleys shall be adjustable, cast iron, machined, keyed, securely attached and sized for 150% of the horsepower at its rated maximum speed.

.2 Each fan shall bear the AMCA Licensed Ratings Seal for Air and Sound Performance, and shall be UL and CSA listed.

.3 For model, accessories and performance requirements, refer to Equipment Schedule on the drawings.

3.16 Variable Refrigerant Flow (VRF) System Refrigeration Piping

.1 General

a. Submittals:
i. Submit product data sheets for all products specified in of this specification, except for pipe and fittings.
ii. Submit in shop drawing form, a schematic piping diagram for each refrigerant piping system indicating pipe size, slopes, valves, traps and piping specialties. Piping schematic must be reviewed, approved and signed by the refrigeration equipment manufacturer prior to being submitted to the consultant for review.
iii. Submit details from the equipment supplier outlining proper installation and startup.

b. Regulatory Compliance and Quality Assurance:
i. Installing Contractor must be TSSA certified and shall register all projects sized at 5 tons or greater for air conditioning application.
ii. A copy of the TSSA registration shall be submitted to the mechanical consultant of record.
iii. All components of a refrigeration piping system must have a Canadian Registration Number or CSA certification acceptable to TSSA.
iv. All systems shall display appropriate Ozone Depletion Prevention (ODP) tags prior to commissioning. Manufacturer shall not commission any system not displaying proper ODP tag.
v. Pressure relief valves shall be installed in pairs (two valves per refrigeration circuit) using a purpose built “Y” fitting similar or equal to Superior Products model 3155W. Relief valve assembly must be complete with an integrated ball valve. Assembly shall be supplied and installed on both the liquid and suction line, or liquid and discharge line as per drawing details. Pressure relief valves shall be individually isolated to allow for maintenance and replacement every five years as mandated by the code (refer to CSA B52 section 8.4.2).

c. Special Considerations for VRF Refrigerant Piping Systems
i. Refrigerant piping contractors must be trained and certified by VRF equipment supplier. Proof of training certification must be made available upon request.
ii. There shall be minimal use of refrigeration specialties (filter driers, accumulators, receivers, check valves, etc.) in the VRF piping system. Refer and follow Manufacturer’s recommendations in this regard.

iii. As noted above, pressure relief valves shall be 650 PSI rated and installed in pairs (two valves per circuit).
iv. Y style piping joints and headers provided by the manufacturer shall be used to ensure proper refrigerant balance and flow for optimum system capacity and performance.
v. T style joints and/or joints provided by the installing contractor, or Y joints not purchased from the manufacturer are not acceptable.
vi. Approved R-410a flaring block, and approved torque wrenches, both available from VRF manufacturer, shall be used for all flare connections.
vii. Refrigerant piping shall be insulated according to Division 20.
viii. Pipe clamps shall fasten around the piping insulation. Pipe clamps that compress the copper directly shall be installed a minimum of 36" away from RefNet joints, and shall be loosely tightened to allow for copper expansion.
ix. Contractor shall provide VRF manufacturer with all actual pipe lengths installed for calculation of refrigerant charge. Refrigerant piping contractor shall supply and charge VRF system with required quantity of R-410a prior to VRF manufacturer commissioning. Refrigerant charging shall be done in the liquid state.

.2 Products

a. Pipe, Fittings and Joints:
i. Copper Tubing:
1) Provide hard drawn copper piping of air conditioning / refrigerant grade ASTM B280. Soft annealed copper tubing not permitted.
2) All joints shall be brazed. Joints and fittings for brazed joint shall be wrought-copper or forged-brass sweat fittings. Cast sweat-type joints and fittings shall not be allowed for brazed joints. Brass or bronze adapters for brazed tubing may be used for connecting tubing to flanges and to threaded ends of valves and equipment.
3) Brazing Filler Metal:
I Filler metal shall be type BAg-5 with AWS Type 3 flux, except Type BCuP-5 or BCuP-6 may be used for brazing copper-to-copper joints.
II Brazing rods for all joints shall be 15% Lucas Milhaupt "sil-Fos".

b. Valves:
i. Valves shall be designed, manufactured, and tested specifically for refrigerant service. Valve bodies shall be of brass, bronze, steel, or ductile iron construction. Valves 25 mm (1 inch) and smaller shall have brazed or socket welded connections. Valves larger than 25 mm (1 inch) shall have butt welded end connections. Threaded end connections shall not be used, except in pilot pressure or gauge lines where maintenance disassembly is required and welded flanges cannot be used. Internal parts shall be removable for inspection or replacement without applying heat or breaking pipe connections. Valve stems exposed to the atmosphere shall be stainless steel or corrosion resistant metal plated carbon steel. Direction of flow shall be legibly and permanently indicated on the valve body. Purge, charge and receiver valves shall be of manufacturer's standard configuration.

ii. Refrigerant access valves and hose connections shall be in accordance with ARI 720.

iii. Isolation valves shall be installed where shown on the schematics. Isolation valves shall be bi-flow self-seating with operating pressures up to 650 PSI. Valves shall be complete with brass schrader connections located on the valve body only.

iv. Check Valves shall be Mueller Industries Inc. "Checkmaster" straight through type for valves 6.4mm to 16 mm (1/4" to 5/8") diameter, globe type for valves 22mm (7/8") diameter and larger, each complete with extended tubing for brazing connections, and as follows:

1) Straight through type check valves are to be complete with a machined brass gasketed body, phosphor bronze spring, and neoprene seat.
2) Globe type check valves are to be complete with a cast bronze body, forged brass cap, phosphor bronze spring, Teflon seat disc, and neoprene O-ring seal.

v. Liquid Solenoid Valves

1) Ball type valves as specified above, each in accordance with ARI 760 and be suitable for continuous duty with applied voltages 15 percent under and 5 percent over nominal rated voltage at maximum and minimum encountered pressure and temperature service conditions, direct-acting or pilot-operating type, moisture-proof, UL approved, totally encapsulated or encapsulated and metal jacketed as required. Valves shall have an operating pressure differential suitable for the refrigerant used.

vi. Expansion Valves

1) Valve shall be the diaphragm and spring-loaded type with external equalizers, and bulb and capillary tubing. Valve shall be equipped with an external superheat adjustment along with a seal cap. Internal equalizers may be utilized where flowing refrigerant pressure drop between outlet of the valve and inlet to the evaporator coil is negligible and pressure drop across the evaporator is less than the pressure difference corresponding to 1°C (2°F) of saturated suction temperature at evaporator conditions. Pilot-operated valves shall have a characterized plug to provide required modulating control.
2) Electronic expansion valves shall be brass body, needle valve with floating needle and machined seat, stepper motor drive.

vii. Safety Relief Valves

1) As noted in Section 1.2.5 of Regulatory Compliance, pressure relief valves shall be installed in pairs (two valves per circuit). Suction lines shall be rated at 350 PSI and liquid at 650 PSI or liquid and discharge lines at 650 PSI respectively.

viii. Evaporator Pressure Regulators, Direct-Acting

1) Valve shall include a diaphragm/spring assembly, external pressure adjustment with seal cap, and pressure gauge port. Valve shall maintain a constant inlet pressure by balancing inlet pressure on diaphragm against an adjustable spring load. Pressure drop at system design load shall not exceed the pressure difference corresponding to a 1°C (2°F) change in saturated refrigerant

temperature at evaporator operating suction temperature. Spring shall be selected for indicated maximum allowable suction pressure range.

ix. Refrigerant access valves and hose connections shall be in accordance with ARI 720.

c. Piping Accessories:

i. Filter Driers

1) Sizes 15 mm (5/8 inch) and larger shall be the full flow, replaceable core type. Sizes 15 mm (1/2 inch) and smaller shall be the sealed type. Cores shall be of suitable desiccant that will not plug, cake, dust, channel, or break down, and shall remove water, acid, and foreign material from the refrigerant. Filter driers shall be constructed so that none of the desiccant will pass into the refrigerant lines. Minimum bursting pressure shall be 10.3 MPa (1,500 psi).

ii. Discharge Line Oil Separator

1) Discharge line oil separator shall be provided in the discharge line from each compressor. Oil return line shall be connected to the compressor as recommended by the compressor manufacturer.

iii. Accumulator

1) Accumulators shall be provided in the suction line to protect the compressor from liquid refrigerant damage. Accumulator shall be CUL listed under the required operating pressures and must be installed as close to the compressor as possible.

iv. Refrigerant Moisture and Liquid Indicators

1) Indicators shall be single or double port, ULC listed. Body shall be copper or brass with flared or soldered ends. Sight glass shall have color coded paper moisture indicator with removable element cartridge and plastic cap. Maximum working pressure shall be kPa (500 psig). Maximum working temperature shall be 93.3 Deg. C. (200 Deg. F.).

v. Pressure and Vacuum Gauges

1) Gauges shall conform to ASME B40.100 and shall be provided with throttling type needle valve or a pulsation dampener and shut-off valve. Gauge shall be a minimum of 85 mm (3-1/2 inches) in diameter with a range from 0 kPa (0 psig) to approximately 1.5 times the maximum system working pressure. Each gauge range shall be selected so that at normal operating pressure, the needle is within the middle-third of the range.

vi. Insulation

1) Liquid, suction and hot gas lines shall be individually insulated. All indoor and outdoor refrigerant lines shall be insulated according to Division 20. Outdoor refrigerant piping insulation shall be equipped with cladding according to Division 20.

.3 Execution

a. Consider the piping shown on the Drawings as diagrammatic, for clearness in indicating the general runs and connections and that the piping may, or may not, in all parts be shown in the true position. This does not relieve the responsibility of the

Contractor for the proper erection of the systems of piping in every respect suitable for the work intended.

b. Install all piping in the best workmanlike manner and in accordance with the best practices of the trade. Piping shall be pitched 13mm (½ inch) for every 3000mm (10 feet) of length in the direction of flow to ensure adequate oil drainage. Open ends of refrigerant lines or equipment shall be properly capped or plugged during installation to keep moisture, dirt, or other foreign material out of the system. Piping shall remain capped until installation. Equipment piping shall be in accordance with the equipment manufacturer's recommendations and the contract drawings.

c. Pipe supports shall be a maximum of six feet apart. Pipe clamps shall fasten around the piping.

d. Installation shall be in accordance with CSA B52 and ASME B31.5 Mechanical Refrigeration Code guidelines.

e. Safety pressure relief valves shall be field supplied and installed in the piping as per TSSA mandate and Section 7 of CSA B52 code. All pressure relief valves and brazed joints shall be suitably sized.

f. Nitrogen purging / sweeping shall be used when brazing and welding to minimize oxidization.

g. Isolation valves shall be installed where shown on the schematics or where indicated on manufacturer installation requirements.

h. Piping supports and guides using steel, reinforced polytetrafluoroethylene (PTFE) or graphite slides shall be provided where required to allow longitudinal pipe movement. Lateral restraints shall be provided as required. Slide materials shall be suitable for the system operating temperatures, atmospheric conditions, and bearing loads encountered.

i. Anchors shall be provided wherever necessary or indicated to localize expansion or to prevent undue strain on piping. Anchors shall consist of heavy steel collars with lugs and bolts for clamping and attaching anchor braces, unless otherwise indicated. Anchor braces shall be installed in the most effective manner to secure the desired results using turnbuckles where required. Supports, anchors, or stays shall not be attached where they will injure the structure or adjacent construction during installation or by the weight of expansion of the pipeline. Where pipe and conduit penetrations of vapor barrier sealed surfaces occur, these items shall be anchored immediately adjacent to each penetrated surface, to provide essentially zero movement within penetration seal.

j. The Contractor shall, at all times during the installation and testing of the refrigeration system, take steps to prevent the release of refrigerants into the atmosphere.

k. Pipe shall be cut accurately to measurements established at the jobsite, and worked into place without springing or forcing, completely clearing all windows, doors, and other openings. Pipe or tubing shall be cut square, shall have burrs removed by reaming, and shall permit free expansion and contraction without causing damage to the building structure, pipe, joints, or hangers.

l. Layout and install piping, valves, and fittings to facilitate easy maintenance. Do not locate any valves, couplings, or flanged/union connections directly above electrical panels, motor starters or MCC’s.

m. Ensure that all pipe brazing is done by TSSA certified workers.

n. A liquid line filter dryer shall be provided on each refrigerant circuit located such that all liquid refrigerant passes through a filter dryer. Dryers shall be sized in accordance with the manufacturer's recommendations for the system in which it is installed.

o. A moisture indicating sight glass shall be installed in all refrigerant circuits down stream of all filter dryers and where indicated. Site glasses shall be full line size.
p. Supply miscellaneous piping accessories specified above as required by and install according to manufacturer installation requirements.

3.17 Air Handling (HVAC) Units with VRF Heating / Cooling Coils

.1 General

a. Submittals:
i. Submit shop drawings and product data in accordance with Division 20.
ii. Indicate the following: complete specifications; weight; performance details.
iii. Provide data for inclusion in the Operating and Maintenance manuals in accordance with Division 20.

.2 Products

a. General:
i. Air handling units shall be ETL-Canada safety listed to conform to UL Standard 1995 and CAN/CSA Standard C22.2 No. 236. Air handling unit water heating & cooling coils shall be certified in accordance with the forced circulation air cooling and air heating coils certification program, which is based on ARI Standard 410.
b. Casing:
i. Fabricate unit with 16 gauge nominal channel posts and panels secured with mechanical fasteners. All panels and access doors shall be sealed with bulb-type gasket.
ii. Panels and access doors shall be constructed as a 2-inch (50-mm) nominal thick, thermal broke double wall assembly, injected with foam insulation for an R-value of not less than R-13. The outer casing shall be constructed of G60 galvanized steel, phosphatized and painted with baked on enamel.
iii. The inner liner shall be constructed of G90 galvanized steel. Panel deflection shall not exceed L/240 at 125% of design static pressure, minimum +/- 8”. Deflection shall be measured at the midpoint of the panel height.
iv. The casing leakage rate shall not exceed 0.5 cfm per square foot of cabinet area at 6 inches of negative static pressure or 5 inches of positive static pressure
v. Construct drain pans from stainless steel with cross break and pitch to drain connection. Provide drain pans under cooling coil section.
vi. Provide unit with a factory installed 6-inch high full perimeter channel base rail.
vii. Floor plate shall be constructed of 20-gauge galvanized steel.
c. Mixing Section:
i. Provide mixing box sections with factory mounted airfoil outside and return air dampers of galvanized steel in galvanized frame. Outside air damper shall be low leakage and insulated type (Tamco 9000); and return air damper shall be low leakage type (Tamco 1000). Dampers shall be hollow core airfoil blades, fully gasketed. Provide continuous vinyl seals between damper blades. Provide stainless steel end seals along end of dampers. Provide linkage and ABS plastic end caps provided.

ii. Damper leakage rate shall be less than two tenths of one percent leakage at 2 inches static pressure differential. Leakage rate shall be tested in accordance with AMCA Standard 500.

d. Filters:
   i. Provide filter section with filter guides, hinged and latching access doors on one side, for side loading of filters.
   ii. Filter media shall be UL 900 listed.
   iii. Provide flat arrangement with 2-inch deep MERV 13 pleated panel filters. Supply fan shall be sized to account for mid-loading of filters.
   iv. Provide Magnehelic filter gauges for each filter bank flush mounted into unit casing with factory mounted probes.

e. Fans:
   i. Provide ECM direct drive airfoil plenum fan as scheduled.
      1) Inverter shall be integral to the motor and come as an assembly from the fan manufacturer. Motor shall be brushless DC type with a permanent magnet rotor.
      2) Fan section shall come equipped with a motor control panel mounted on the AHU casing. Both line voltage and low voltage wiring shall be done at the factory. Each fan shall have an isolation switch.
      3) Motor control panel shall come equipped with a fused disconnect switch.
      4) Motor control panel shall come with a low voltage terminal strip and shall include terminals for Fan ON/OFF, 0-10v signal and fan fault.
      5) ECM motor control panel SCCR shall be at least 65kA.

f. Coils:
   i. Provide access to coils from connection side of unit for service and cleaning. Enclose coil headers and return bends fully within unit casing. Fabricate coil connections, vents and drains to extend beyond unit casing including grommets for an airtight unit casing. Coils shall be removable through side panels and/or top panels of unit without removal and disassembly of entire section.
   ii. Provide stainless steel drain pan located underneath and extending downstream of coil and intermediate drain pans.
   iii. Coil performance shall be as per schedule. Coil performance data shall be certified in accordance with ARI Standard 410 where applicable.
   iv. Heating Coil Construction:
      1) Tubes: Copper.
      2) Fins: Aluminum mechanically bonded to tubes.
      3) Headers: Seamless copper with vent and drain connections.
   v. DX Coil Construction:
      1) Tubes: Copper.
      2) Fins: Aluminum mechanically bonded to tubes.
      3) Headers: Seamless copper with vent and drain connections.
      4) Casing: 16 gauge, stainless steel channels with 16 gauge center and end supports.
      5) Reheat Coil Construction:
      6) Tubes: Copper.
      7) Fins: Aluminum mechanically bonded to tubes.
      8) Headers: Seamless copper with vent and drain connections.

9) Casing: 16 gauge, galvanized steel channels with 16 gauge center and end supports.

vi. Water heating coils shall be circuited drainable with a vent connection at the highest point and a drain connection at the lowest point. Coil headers shall be copper with steel male pipe connections.

vii. VRF systems, where indicated, are to be integrated with air handing unit utilizing a VRF DX coil, VRF Hot Gas Reheat Coil (HGRH), branch selector box, electronic expansion valves and appropriate refrigeration system controls. VRF manufacturer shall provide the DX & HGRH coil(s), electronic expansion valves and associated air-source heat pump (AHSP) controllers. ASHP controllers shall include terminal strip for integration of ASHP sequence with field supplied AHU controller.

viii. Refrigerant coils shall be provided with round seamless 3/8" O.D. copper tubes on 1-1/2" centers, staggered in the direction of airflow. All joints shall be brazed. Sweat type copper suction connections located at the bottom of the suction headers for gravity oil drainage. Coils shall be uniformly circuited in a counterflow manner for interlaced face split capacity reduction. Pressure type liquid distributors used. Coils shall be tested with 315 pounds air pressure under warm water, and suitable for 250 psig working pressure.

g. Split-System VRF Air-Source Heat Pumps

i. Split-system air source heat pump units shall be Daikin VRV systems (Variable Refrigerant Volume) distributed by DXS Ontario (416-661-3400).

ii. The VRF System serving the AHUs shall comply with its dedicated specification section below (Section 3.18). The following clauses, which are part of the Air Handling (HVAC) Unit specification, present a condensed version of this specification section with details pertaining to the AHUs. Where there is a discrepancy, the VRF System specification (Section 3.18) shall govern.

iii. Each air handling unit shall be served by a minimum of three independent refrigeration circuits for system redundancy.

iv. VRF system shall automatically vary the target evaporating and condensing temperatures based on building load and weather conditions to increase part load efficiency (Variable Refrigerant Temperature). The condensing unit shall also feature customizable operating modes which allows for the manual setting of target evaporating and condensing temperatures.

v. System shall permit simultaneous heating and cooling for dehumidification purposes.

vi. Installing contractor must be certified by VRF manufacturer. The bidders shall be required to submit training certification proof with bid documents and submittal documents. Untrained contractors who wish to bid this project may contact DXS Ontario (416-661-3400) to arrange training prior to bid day. The manufacturer shall provide a factory trained service technician to start-up each unit. Manufacturer shall provide instruction to the owners' personnel on proper unit operation and maintenance.

vii. The warranty period on all parts and compressors shall commence on the date of initial start-up and shall continue for a period of Ten (10) years not to exceed one hundred and twenty six (126) months from date of shipment. Proper maintenance of the equipment shall be conducted by certified technicians as per the manufacturer or manufacturer's representative requirements. Maintenance logs shall be supplied by the owner upon

request. All manufacturer warranty shall be for parts only. All diagnosis and labour warranty shall be carried out by installing contractor as per the warranty requirements of this project.

viii. Installing Contractor must be TSSA certified and shall register all projects sized at 5 tons or greater for air conditioning. A copy of the TSSA registration shall be submitted to the mechanical consultant of record. All components of a refrigeration piping system must have a Canadian Registration Number or CSA certification acceptable to TSSA. All systems shall display appropriate Ozone Depletion Prevention (ODP) tags prior to commissioning. Manufacturer shall not commission any system not displaying proper ODP tag.

ix. Pressure relief valves shall be installed in pairs (two valves per refrigeration circuit) using a purpose built "Y" fitting similar or equal to Superior Products model 3155W. Relief valve assembly must be complete with an integrated ball valve. Assembly shall be supplied and installed on both the liquid and suction line, or liquid and discharge line as per drawing details. Pressure relief valves shall be individually isolated to allow for maintenance and replacement every five years as mandated by the code (refer to CSA B52 section 8.4.2). Pressure relief valves shall be 650 PSI rated and installed in pairs.

x. VRF refrigeration piping systems shall be installed with the following considerations:

1) There shall be minimal use of refrigeration specialties (filter driers, accumulators, receivers, check valves, etc.) in the VRF piping system. Refer and follow Manufacturer's recommendations in this regard.
2) Y-style piping joints and headers provided by the manufacturer shall be used to ensure proper refrigerant balance and flow for optimum system capacity and performance. T-style joints and/or joints provided by the installing contractor, or Y-joints not purchased from the manufacturer shall not be acceptable.
3) Piping shall be type L hard copper. Soft copper tubing not permitted.
4) Contractor shall provide VRF manufacturer with all actual pipe lengths installed for calculation of refrigerant charge. Refrigerant piping contractor shall supply and charge VRF system with required quantity of R-410a prior to VRF manufacturer commissioning. Refrigerant charging shall be done in the liquid state.

xi. The condensing unit shall be factory assembled in North America and pre-wired with all necessary electronic and refrigerant controls. The refrigeration circuit of the condensing unit shall consist of Daikin inverter scroll compressors, motors, fans, heat exchanger, electronic expansion valves, solenoid valves, 4-way valve, distribution headers, capillaries, filters, shut off valves, oil separators, service ports, liquid receiver and suction accumulator.

xii. The Daikin inverter scroll compressors shall be high efficiency reluctance DC (digitally commutating), hermetically sealed, variable speed type. Temperatures and pressures shall be read every 20 seconds and calculated. With each reading, the compressor capacity (INV frequency) shall be controlled to eliminate deviation from target value. Non inverter-driven compressors shall not be accepted. Neodymium magnets shall be adopted in the rotor construction to yield a higher torque and efficiency in the compressor instead of the normal ferrite magnet type. Upon complete stop

of the compressor, the neodymium magnets will position the rotor into the optimum position for a low torque start. The compressors' motors shall have a cooling system using discharge gas, to avoid sudden changes in temperature resulting in significant stresses on winding and bearings.

xiii. The variable speed inverter compressors in Air-Cooled systems shall also use Flash Vapor injection technology with back pressure control for reduced leakage and additional balancing weights on main shaft for increased for increased compressor lifetime.

xiv. The fan motor shall have inherent protection and permanently lubricated bearings. The motor shall be provided with a fan guard to prevent contact with moving parts. The condensing unit shall consist of one or more propeller type, direct-drive 600 W fan motors that have multiple speed operation via a DC (digitally commutating) inverter. The condensing unit shall have configurable settings for intermittent fan operation to help minimize snow accumulation on fan blades when the system is off. Night setback control for low noise operation shall automatically limit the maximum speed of the fan motor.

xv. The heat exchanger on the condensing units shall be manufactured from Hi-X seamless copper tubes with N-shape internal grooves mechanically bonded on to aluminum fins to an e-Pass Design. The heat exchanger coil shall be of a waffle louver fin and rifled bore tube design to ensure high efficiency performance. The fins are to be covered with an anti-corrosion hydrophilic blue coating as standard with a salt spray test rating of 1000hr (ASTM B117 & Blister Rating:10), Acetic acid salt spray test of 500hr (ASTM G85 & Blister Rating:10).

xvi. The outdoor unit shall be capable of heating operation down to -13°F ambient temperature. Tested factory data on heating capacity and efficiency shall be available. Continuous heating shall be provided during defrost mode for multi-module systems. The outdoor unit shall be capable of cooling operation down to +23°F without any additional low ambient controls.

xvii. The outdoor coil shall have a three-circuit heat exchanger design. The lower part of the coil shall be used for inverter cooling, enhancing defrost during heating operation.

xviii. Branch selector box cabinets shall have a galvanized steel plate casing and shall house multiple electronic expansion valves and a sub-cooling loop. The unit shall contain sound absorption thermal insulating material made of flame and heat resistant foamed polyethylene. Branch selector boxes shall not require drain pan and drain connections. Manufacturers with branch selector boxes requiring secondary drain pans and drain connections shall coordinate with the installing contractor at no extra cost to the owner.

h. Controls:

i. With the exception of the ASHP safety controls, all required system controls shall be field supplied and installed. This shall include all required sensors (temperature and humidity), actuators, valves and and associated microprocessor controllers.

.3 Execution

a. Install unit flat and level on house keeping pad and in accordance with manufacturer's installation literature.

b. Provide piping connections to coils such that individual coils can be isolated, drained and removed. Provide valved pressure gauge connections and thermometer wells on the entering and leaving piping.
c. Provide valved drain connections with hose end, cap and chain for all coils.
d. Pipe all drain pan connections the nearest floor drain with appropriately sized trap.
e. Coordinate ASHP controls integration with controls contractor to ensure all required control points are managed as per VRV manufacturer recommendations.
Coordinate installation of VRF ASHP system including all shipped loose accessories. A 208/1/60 field power connection is required at each VRF ASHP branch selector box. A 208/1/60 field power connection is required at each VRF ASHP refrigeration controller. VRV ASHP branch selector boxes, refrigeration controllers, and electronic expansion valve kits shall be installed inside the mechanical room within close proximity to the ASHP DX and HGRH coils.

3.18 Variable Refrigerant Flow (VRF) System

.1 General

a. Submit shop drawings and product data in accordance with Division 20.
b. Submittals shall include the following:
    i. Performance and capacity details of all units at specified indoor and outdoor conditions, piping schematics outputted from manufacturer specific software including pipe sizes and estimated piping lengths, refrigerant charge per system including CSA B-52 analysis, wiring diagrams, and 10-year parts only warranty information.
    ii. unit selections, refrigerant piping layout, refrigerant charge with ASHRAE 15 analysis, branch selector box layout and locations, heating and cooling capacities at design temperatures and including capacity losses from piping lengths, defrost cycles, and combination ratios, dimensional and weight differences, and any other aspect of the system that differs from the system specified if approved alternate products are used.
c. Submittal shall include a copy of the installing contractor's certification of VRF manufacturer approved training.

.2 Products

a. General:
    i. This section includes the design, performance, refrigerant details, controls and installation requirements for Daikin VRV systems (Variable Refrigerant Volume) distributed by DXS Ontario (416-661-3400).
    ii. All units shall be listed and rated by ANSI/AHRI Standard 1230-2010 and meet all minimum IEER performance requirements as scheduled.
    iii. The units shall be ANSI/UL STD 1995 listed and listed by Electrical Testing Labs (ETL) and bear the cETL label.
    iv. All wiring shall be in accordance with the National Electric Code (NEC).
    v. The system will be produced in an ISO 9001 and ISO 14001 facility, which are standards set by the International Standard Organization (ISO). The system shall be factory tested for safety and function.
    vi. The system and the design shall be in compliance with CSA B52 Mechanical Refrigerant Code.

b. System Description:
   i. VRF system shall automatically vary the target evaporating and condensing temperatures based on building load and weather conditions to increase part load efficiency (Variable Refrigerant Temperature). The condensing unit shall also feature customizable operating modes which allows for the manual setting of target evaporating and condensing temperatures.
   ii. Heat Recovery:
      1) System shall permit simultaneous heating and cooling of each indoor unit. Multiple indoor units connected to a single branch selector port shall operate in the same mode (heating or cooling), similar to a two pipe heat pump system. Refer to the controls section of this specification for any central controller and/or mode switchover sequence that may be required.

c. Start-up and Warranty:
   i. Installing contractor must be certified by VRF manufacturer. The bidders shall be required to submit training certification proof with bid documents and submittal documents. Untrained contractors who wish to bid this project may contact DXS Ontario (416-661-3400) to arrange training prior to bid day.
   ii. The manufacturer shall provide a factory trained service technician to start-up each unit. Manufacturer shall provide instruction to the owners' personnel on proper unit operation and maintenance.
   iii. The warranty period on all parts and compressors shall commence on the date of initial start-up and shall continue for a period of Ten (10) years not to exceed one hundred and twenty six (126) months from date of shipment. Proper maintenance of the equipment shall be conducted by certified technicians as per the manufacturer or manufacturer's representative requirements. Maintenance logs shall be supplied by the owner upon request.
   iv. All manufacturer warranty shall be for parts only. All diagnosis and labour warranty shall be carried out by installing contractor as per the warranty requirements of this project.

d. Refrigerant Piping:
   i. Refer and comply to the refrigerant piping specifications (Section 3.16), including the special considerations for VRF refrigerant piping section.
   ii. Standard T style joints are not acceptable for a variable refrigerant volume system. Manufacturer specific Y joints shall be supplied by the VRF manufacturer.

e. Air Handling (HVAC) Unit Integration:
   i. Direct Expansion (DX) Coil:
      1) Certification - Acceptable refrigerant coils are to be certified in accordance with AHRI Standard 410 and bear the AHRI label. Coils exceeding the scope of the manufacturer's certification and/or the range of AHRI's standard rating conditions will be considered provided the manufacturer is a current member of the AHRI Air-Cooling and Air-Heating Coils certification programs and that the coils have been rated in accordance with AHRI Standard 410. Manufacturer must be ISO 9002 certified.
      2) VRF systems, where indicated, are to be integrated with air handling unit(s), utilizing VRF DX coil(s), electronic expansion valves and

appropriate controls. VRF manufacturer shall provide the DX coil(s), electronic expansion valves and controllers.

3) Coils designed for use with Refrigerant R-410A. Fins shall have a minimum thickness of 0.0075" of aluminum plate construction with full drawn collars to provide a continuous surface cover over the entire tube for maximum heat transfer. Tubes shall be mechanically expanded into the fins to provide a continuous primary-to-secondary compression bond over the entire finned length for maximum heat transfer rates. Bare copper tube shall not be visible between fins.
4) Refrigerant coils shall be provided with round seamless 3/8" O.D. copper tubes on 1-1/2" centers, staggered in the direction of airflow. All joints shall be brazed.
5) Sweat type copper suction connections located at the bottom of the suction headers for gravity oil drainage. Coils shall be uniformly circuited in a counterflow manner for interlaced face split capacity reduction. Pressure type liquid distributors used. Coils shall be tested with 315 pounds air pressure under warm water, and suitable for 250 psig working pressure.

ii. Expansion Valve:

1) VRF system shall monitor and maintain the unit superheat (cooling mode) or subcooling (heating mode) using a computerized PID control. Internal unit components shall be factory wired and piped, and complete with electronic proportional expansion valve, flare connections, condensate drain pan, self-diagnostics, and auto-restart function.
2) Electronic expansion valves shall be brass body, needle valve with floating needle and machined seat, stepper motor drive and compatible with R410A and PVE oil.
3) Electronic expansion valves shall have a temperature operation of -40F to 300F.
4) Electronic expansion valves shall have a working pressure of 550 psig and should be able to handle up to 700psig
5) The access port of the expansion valve must be on the valve body and not on the piping
6) Electronic expansion valves shall be able to handle the flow without any pressure drop
7) Electronic expansion valves shall be able to work with bi-directional flows

iii. Hot Gas Reheat (HGRH):

1) Appropriate VRF equipment and accessories shall be provided for fully modulating hot gas reheat:
   - I 3-pipe VRF heat recovery condensing unit
   - II DX coil
   - III Reheat coil
   - IV Expansion valve kit
   - V VRF branch box
   - VI AHU-integration control box with re-heat control features
2) The reheat coil capacity index shall not exceed 50% of the DX coil capacity index.

3) The DX coil capacity index shall be within 50% to 105% range of the outdoor unit capacity index for all outdoor unit nominal sizes, with the exception of 6-ton nominal size which shall be within 70% to 105% range of the outdoor unit capacity index.
4) The combined capacity indexes for the DX coil and the RH coil shall be within appropriate range relative to the outdoor unit capacity index and number of module.

| Outdoor unit type | Combined Capacity Index | |
|---|---|---|
| | 6T Outdoor Unit | Outdoor units 8T and over |
| Single outdoor module | 70% - 150% | 50% - 150% |
| Double outdoor modules | 70% - 140% | 50% - 140% |
| Triple outdoor modules | 50% - 130% | 50% - 130% |

f. Condensing Units:

i. The condensing unit shall be factory assembled in North America and pre-wired with all necessary electronic and refrigerant controls. The refrigeration circuit of the condensing unit shall consist of Daikin inverter scroll compressors, motors, fans, heat exchanger, electronic expansion valves, solenoid valves, 4-way valve, distribution headers, capillaries, filters, shut off valves, oil separators, service ports, liquid receiver (heat recovery only) and suction accumulator.

ii. The system will automatically restart operation after a power failure and will not cause any settings to be lost.

iii. The unit shall incorporate an auto-charging feature to ensure proper refrigerant charge.

iv. The following safety devices shall be included on the condensing unit: high pressure sensor and switch, low pressure sensor, control circuit fuses, crankcase heaters, fusible plug, overload relay, inverter overload protector, thermal protectors for compressor and fan motors, over current protection for the inverter, and anti-recycling timers.

v. The Daikin inverter scroll compressors shall be high efficiency reluctance DC (digitally commutating), hermetically sealed, variable speed type. Temperatures and pressures shall be read every 20 seconds and calculated. With each reading, the compressor capacity (INV frequency) shall be controlled to eliminate deviation from target value. Non inverter-driven compressors shall not be accepted.

vi. Neodymium magnets shall be adopted in the rotor construction to yield a higher torque and efficiency in the compressor instead of the normal ferrite magnet type. Upon complete stop of the compressor, the neodymium magnets will position the rotor into the optimum position for a low torque start.

vii. The compressors' motors shall have a cooling system using discharge gas, to avoid sudden changes in temperature resulting in significant stresses on winding and bearings.

viii. Inverter board shall be refrigerant-cooled to prevent inefficient and unstable operation that can result from air-cooled inverter boards due to varying ambient conditions.

ix. The compressor shall be internally isolated to avoid the transmission of vibration.

x. In the case of multiple condenser modules, operation hours of the compressors shall be balanced by means of the Duty Cycling Function.

xi. Air Cooled:

1) The variable speed inverter compressors in Air-Cooled systems shall also use Flash Vapor injection technology with back pressure control for reduced leakage and additional balancing weights on main shaft for increased for increased compressor lifetime.

2) The fan motor shall have inherent protection and permanently lubricated bearings. The motor shall be provided with a fan guard to prevent contact with moving parts. The condensing unit shall consist of one or more propeller type, direct-drive 600 W fan motors that have multiple speed operation via a DC (digitally commutating) inverter.
3) Motors shall be capable of delivering design air at high external static pressures up to 0.32 in WG (factory set as standard at 0.12 in. WG) to accommodate field applied condensing unit discharge ductwork.
4) The condensing unit shall have configurable settings for intermittent fan operation to help minimize snow accumulation on fan blades when the system is off.
5) Night setback control for low noise operation shall automatically limit the maximum speed of the fan motor.
6) The heat exchanger on the condensing units shall be manufactured from Hi-X seamless copper tubes with N-shape internal grooves mechanically bonded on to aluminum fins to an e-Pass Design. The heat exchanger coil shall be of a waffle louver fin and rifled bore tube design to ensure high efficiency performance.
7) The fins are to be covered with an anti-corrosion hydrophilic blue coating as standard with a salt spray test rating of 1000hr (ASTM B117 & Blister Rating:10), Acetic acid salt spray test of 500hr (ASTM G85 & Blister Rating:10).
8) The connection ratio of indoor units to condensing unit shall be permitted and optimized for operation up to 200% of nominal capacity.
9) The outdoor unit shall be capable of heating operation down to -13°F ambient temperature. Tested factory data on heating capacity and efficiency shall be available.
10) Continuous heating shall be provided during defrost mode for multi-module systems.
11) The outdoor unit shall be capable of cooling operation down to +23°F without any additional low ambient controls.
12) The outdoor coil shall have a three-circuit heat exchanger design. The lower part of the coil shall be used for inverter cooling, enhancing defrost during heating operation.

g. Branch Selector Box:
   i. Branch Selector box cabinets shall have a galvanized steel plate casing and shall house multiple electronic expansion valves and a sub-cooling loop. The unit shall contain sound absorption thermal insulating material made of flame and heat resistant foamed polyethylene.
   ii. Branch selector boxes shall not require drain pan and drain connections. Manufacturers with branch selector boxes requiring secondary drain pans and drain connections shall coordinate with the installing contractor at no extra cost to the owner.
   iii. Branch selector boxes shall allow for field selectable LEFT/RIGHT/PASS THROUGH piping configurations. Refrigerant piping connections shall follow the configurations in the plans to minimize space requirements and piping elbows.

iv. Branch selector boxes shall allow multiple branch selector boxes to be connected downstream of the first branch selector box in series using a pass through configuration and no additional Y-joints / REFNETs.

v. The electrical box of the 4-port branch selector box shall be field re-locatable to left, right, and back side of the main cabinet. Electrical box location shall follow planned access door locations. Manufacturers than require different unit or access door locations shall coordinate with the installing contractor at no extra cost to the owner.

vi. Branch selector box height shall be 9 1/2". Branch selector boxes shall be designed to fit within 12" ceiling plenums. Manufacturers with branch selector box sizes, arrangements, or locations that differ from what is specified shall make the necessary arrangements to ensure their alternative branch selector boxes both fit in the space and that CSA B52 compliance is still met (CSA compliance shall include the life-safety maximum refrigerant charge allowance). See unit sizes below.

vii. Manufacturers shall provide sound data for all branch selector boxes. If sound data is unavailable or exceeds the values below, or if branch boxes make use of solenoid valves instead of electronic expansion valves, necessary precautions shall be taken. Precautions shall include the supply and install of sound blankets, or the relocation of branch boxes away from the occupied spaces, or extra insulation to the ceilings and walls around the branch selector boxes, all at no extra cost to the owner.

| **Model** | **Voltage** | **MCA** | **Operating Sound** | **Max Sound** | **W x H x D** | **Weight** |
|---|---|---|---|---|---|---|
| | | **A** | **dB(A)** | **dB(A)** | **inch** | **lbs** |
| BSF4Q54TVJ | 208-230V 1ph | 0.4 | 37 | 47 | 13.8 x 9.5 x 23.8 | 27 |
| BSF6Q54TVJ | 208-230V 1ph | 0.6 | 40.5 | 50 | 23.4 x 9.5 x 23.8 | 73 |
| BSF8Q54TVJ | 208-230V 1ph | 0.8 | 40.5 | 50 | 23.4 x 9.5 x 23.8 | 81 |

h. Local Controls:

i. VRF systems, where indicated, are to be integrated with air handling unit(s), utilizing a VRF DX coil, electronic expansion valves and appropriate controls. VRF manufacturer shall provide the DX coil(s), electronic expansion valves and controllers.

ii. Expansion valves, expansion valve controller, and thermistors shall be field mounted, powered, and wired on the make-up air unit(s).

iii. Systems intended for discharge air temperature control shall be provided with the appropriate expansion valve controller (D-Control):

1) Expansion valve controller shall regulate the discharge air tempearture in response to the Modbus input from a field-supplied DDC controller.

2) Air handling unit's DDC controller shall be directly wired to the VRF condensing unit (ABC board) for control of mode of operation (between heating and cooling) via Modbus input.

3) Expansion valve controller shall have terminals equivalent to the T1, T2 terminals for receiving dry (voltage-free) contact for ON/OFF control.

4) Expansion valve controller shall provide both power and communication/control to the expansion valve.

5) Expansion valve controller shall provide Modbus output signal for alarm/error status.
6) Expansion valve controller shall provide Modbus output signal for various operation status including compressor on/off operation and defrost cycle.
7) Expansion valve controller shall provide Modbus output signal for fan ON/OFF control.
8) Expansion valve controller shall be wired to and communicate with the VRF condensing units via the F1, F2 terminals

iv. Expansion valve controller shall be provided with all required thermistors for proper electronic control of expansion valve. Thermistors shall be field mounted in the appropriate airstream and both liquid and suction refrigerant lines.
v. Connection of air handling unit DX coils to non-VRF condensing units (which do not include inverter compressors) shall not be acceptable.
vi. All VRF condensing units on the project, for the VRF indoor units and for the air handling units, shall be from the same manufacturer.

i. Modbus to BACnet Gateway:
i. Provide Modbus to BACnet gateway Intesis model IN7004851000000 or approved equal to allow integration of Modbus TCP or Modbus RTU device(s) with a BACnet IP or MS/TP compatible BMS.
ii. Install, power and wire Modbus to BACnet gateway (including any Modbus TCP or RTU and BACnet IP or MS/TP connections).
iii. Provide programming for monitoring and control of VRF system via the Modbus to BACnet gateway according to 25 90 00.
iv. Install gateway within an enclosure to prevent electrostatic discharge to the unit.

j. Electrical:
i. Independent electrical power for branch selector boxes shall be 208/230 volts, 1 phase, 60 hertz. The unit shall be capable of operating within the limits of 187 volts to 253 volts.
ii. Unless limited by local electrical codes and standards, multiple branch selector boxes can be connected to the same breaker. Field provided individual disconnect switches for each fan coil are required.
iii. Electrical power for condensing units shall be 575 volts, 3 phase, 60 hertz.
iv. The control voltage between the indoor and outdoor unit shall be 16VDC. The control wiring shall be communication type stranded non-shielded 18-2 AWG.
v. Control wiring shall be installed in a daisy chain configuration between all VRF components as per Manufacturer.

.3 Execution

a. Delivery, Storage and Handling:
i. Units shall be stored and handled according to the manufacturer's recommendations. Units shall be kept clean and isolated from dust and debris.
ii. Contractor shall inspect all equipment upon delivery and notify shipping company and manufacturer immediately of any damage.

b. Installation:

i. Install condensing units on a flat surface level within 1/8 inch and elevated a minimum of 18" from ground or roof surface. Provide intermediate supports as recommended by the equipment manufacturer.
ii. Provide EcoFoot support system for mounting condensing units complete with condensate drip trays. Entire drip tray and condensate piping shall be heat traced and insulated. Refer to electrical specifications for heat trace requirements and Division 20 for insulation requirements (drain pan insulation shall be equal to that required for piping).
iii. Provide all necessary control wiring as recommended by the manufacturer.
iv. High/low pressure gas line, liquid, and suction lines must be individually insulated between the outdoor and indoor units.
v. Contact DXS (416-661-3400) prior to installation to review and confirm piping layout and lengths.
vi. Use refrigeration best practice to allow pipes to expand and contract freely. Review manufacturer installation instructions to ensure expansion joints are properly designed.
vii. Pressure test ALL systems to 550 PSI after system was vacuumed and held to below 500 microns for at least one hour. Review manufacturer installation instructions for proper pressure test procedures.

3.19 Silencers

.1 General

a. Reference Standards:
i. AABC (NSTSB) - AABC National Standards for Total System Balance, 7th Edition 2016.
ii. ANSI/ASA S1.4 PART 3 - American National Standard Specification for Electroacoustics Sound Level Meters - Part 3: Periodic Tests 2014.
iii. ANSI S1.8 - American National Standard Reference Values for Levels Used in Acoustics and Vibrations 2016.
iv. ANSI S1.13 - American National Standard Measurement of Sound Pressure Levels in Air 2005 (R2010).
v. ASHRAE Std 62.1 - Ventilation for Acceptable Indoor Air Quality Most Recent Edition Adopted by Authority Having Jurisdiction, Including All Applicable Amendments and Supplements.
vi. NEBB (STDS) - Procedural Standard for Measurement of Sound and Vibration 2015, with Errata (2017).
vii. SMACNA (DCS) - HVAC Duct Construction Standards Metal and Flexible 2005 (Revised 2009).
b. Performance Requirements:
i. Provide acoustical system path calculations for all duct systems with silencers to demonstrate the submitted silencers will reduce mechanical fan noise to required NC-Levels in the occupied space. Use sound power levels of actual equipment to be installed on project. Analysis shall include breakout noise calculations.
ii. Supplier shall include system effect pressure loss of the installed silencer based on duct conditions upstream and downstream of the silencer to ensure required airflow is provided. Supplier shall submit detailed pressure drop analysis for the installation and detailed procedure outlining

methodology for site measurement of overall system pressure loss for approval prior to manufacture.

iii. Maintain NC-20 (as defined in the ASHRAE Handbook-HVAC Applications) for the Auditorium.

iv. Source quality-control reports:

1) Silencer manufacturer to provide a copy of their laboratory NVLAP accreditation certificate for the ASTM E-477-06a test standard with the submittals. Data from non-NVLAP accredited test facilities will not be accepted.

v. The pressure loss of silencers shall not exceed those scheduled at the specified design flow rates. Airflow measurements shall be made in accordance with ASTM specification E-477 and applicable portions of ASME, AMCA, and ADC airflow test codes.

c. Submittals:

i. The manufacturer shall supply submittals project specific to the silencer installed conditions. The submittals shall include the overall silencer dimensions and module quantity and sizes, an actual picture detailing baffle location and quantities, dynamic insertion loss (DIL) and generated noise levels (GNL), silencer pressure loss (PD) and construction. The DIL values shall account for the differences between unlined and lined fill. The DIL, GNL and PD values listed on the submittal shall be per the project specific, actual airflow and face velocities.

ii. Acoustical and pressure drop calculations must be supplied with P.Eng. stamp from the Province of Ontario at the time of submittal.

iii. Silencer manufacturer to provide a copy of their laboratory NVLAP accreditation certificate for the ASTM E-477-06a test standard with the submittals. Data from non-NVLAP accredited test facilities will not be accepted.

iv. Alternate manufacturers must submit to the project engineer HVAC silencer test reports for a silencer tested in accordance with ASTM E477-13 in a test facility that is NVLAP-accredited for ASTM E477-13.

.2 Products

a. Description: Duct section with solid, sheet metal outer casing, sound absorbing fill material, and inner splitter (baffle) of perforated sheet metal; incorporating interior splitter, baffles of similar construction. Fabricate in accordance with SMACNA HVAC Duct Construction Standards. Silencers shall include double retainers between each splitter (baffle).

b. Silencer manufacturer to provide submittal drawings detailing all duct silencer data specified in the mechanical drawing schedule.

c. General Requirements:

i. Silencers shall be of the size, configuration, capacity, and acoustic performance as scheduled on the drawings. All silencers shall be factory fabricated and supplied by the same manufacturer.

ii. Silencer inlet and outlet connection dimensions must be equal to the duct sizes shown on the drawings. Duct transitions at silencers are not permitted unless shown on the contract drawings.

iii. Silencers shall be constructed in accordance with ASHRAE and SMACNA standards for the pressure and velocity classification specified for the air

distribution system in which it is installed. Material gauges noted in other sections are minimums. Material gauges shall be increased as required for the system pressure and velocity classification. The silencers shall not fail structurally when subjected to a differential air pressure of 8 inches water gauge.

iv. All casing seams and joints shall be lock-formed, lock-formed and sealed, or stitch welded and sealed. Airtight construction shall be achieved by use of a duct-sealing compound supplied and installed by the contractor at the jobsite.

v. All perforated steel shall be adequately stiffened to insure flatness and form. All spot welds shall be located on maximum, 3-inch, spacing and factory protected with a corrosion resistant (zinc rich) coating.

vi. Fire-Performance Characteristics: Silencer assemblies, including acoustic media fill, film liner, sealants, and acoustical spacer, shall have flame-spread index not exceeding 25 and smoke-developed index not exceeding 50 when tested according to ASTM E 84, NFPA 255 or UL 723.

vii. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1-2016.

d. Rectangular Silencers as Scheduled shall be ASTM A 653/A 653m, G90 galvanized sheet steel, 22 gauge, unless otherwise noted on drawings or silencer schedule. All acoustical splitters (baffles) shall be internally radiused and aerodynamically designed for efficient turning of the air. Half and full splitters (baffles) are required as necessary to achieve the scheduled insertion loss. All elbow silencers with a turning cross-section dimension greater than 48" shall have at least two half splitters and one full splitter. Silencers shall include double retainers between each splitter (baffle).

e. Transitional Silencers as Scheduled, Outer casing shall be ASTM A 653/A 653M, G90 galvanized sheet steel, 22 gauge, unless otherwise noted on drawings or silencer schedule. Transitioning shall occur internal to the silencer such that the height of the gap or air passage is uniformly changing with the length of the splitters (baffles).

f. Inner perforated metal liner: ASTM A 653/A 653M, G90 galvanized sheet steel.
   i. Rectangular Straight Silencers: 22 gauge.
   ii. Rectangular Elbow Silencers: 22 gauge.
   iii. Transitional Silencers: 22 gauge.
   iv. Round Silencers: 22 gauge.

g. Principal Sound-Absorbing Mechanism:
   i. Dissipative and Film Lined/Encapsulated Silencers
      1) Media shall be of acoustic quality, shot-free glass fiber insulation with fibers bonded with a thermosetting resin. Glass fiber density and compression shall be as required to insure conformance with laboratory test data. Glass fiber shall be packed with a minimum of 10% compression during silencer assembly. Media shall be resilient such that it will not crumble or break and conform to irregular surfaces. Media shall not cause or accelerate corrosion of aluminum or steel. Mineral wool will not be permitted as a substitute for glass fiber.
      2) Where indicated on the silencer schedule, media shall be lined/encapsulated in glass fiber cloth to help prevent shedding, erosion, and impregnation of the glass fiber
      3) The acoustic media shall be lined/encapsulated with polymer film (Tedlar) to help prevent shedding, erosion, and impregnation. The

film shall be separated from the perforated metal by a factory-installed acoustically transparent spacer.

4) The spacer shall be flame retardant and erosion resistant.

5) Mesh, screen or corrugated perforated liner will not be acceptable as a substitute for the specified spacer.

.3 Execution

a. Field Quality Control:

i. Provide services of an independent testing agency to take noise measurements in accordance with provisions of NEBB (STDS). Use meters meeting requirements of ANSI/ASA S1.4 PART 3.

ii. After start-up, final corrections and balancing of systems take octave band sound measurements over full audio frequency range in areas adjacent to mechanical equipment rooms, duct and pipe shafts, and other critical locations, as directed.

iii. Provide one-third octave band measurements of artificial sound sources in areas indicated as having critical requirements.

iv. Submit complete report of test results including sound curves.

b. Installation of Silencers:

i. Provide silencers where shown. Ensure that silencers are installed with airflow directional arrows in the direction of airflow.

ii. Support each silencer independent of connecting ductwork.

iii. Properly layout ductwork for silencer locations to provide a minimum of five diameters of straight duct upstream of the silencer and ten diameters of straight duct downstream of the silencer.

iv. Unless otherwise shown, do not install silencers in walls or slabs.

v. Where crosstalk silencers penetrate partition walls, seal the joint between the perimeter of the silencer and the wall, on both sides of the wall, with proper acoustic caulking.

vi. Seal all silencer connections to ducts with proper fire/smoke rated duct sealer.

vii. When silencer installations are complete, arrange and pay for the silencer manufacturer to examine the silencer installations. Do any corrective work required by the manufacturer, then obtain from the manufacturer and submit a signed letter certifying proper installation and operation of all silencers.

c. System Startup

i. Inspect installation periodically. Prepare and start systems.

3.20 Approved Products List

.1 Air Handling (HVAC) Units and VRF System

a. Daikin Applied AHU c/w Daikin VRV

b. Envent AHU c/w LG VRF

c. Trane AHU c/w Mitsubishi VRF

d. Engineered Air AHU may be combined with one of the above VRF manufacturers (Daikin, LG or Mitsubishi) provided the refrigerant coils are selected according to the VRF manufacturer requirements and the AHU c/w VRF shop drawings are submitted

as one complete package. The VRF system shall be installed by a VRF manufacturer approved installer (provide certification documentation).

.2 Exhaust Fans

a. Twin City
b. Cook
c. Greenheck
d. PennBarry

.3 Ceiling Fans

a. Big Ass Fans
b. MacroAir
c. Envira-North

.4 Silencers

a. VAW Systems
b. Vibro-Acoustics
c. Kinetics
d. IAC Acoustics
e. E.H. Price

.5 Diffusers / Grilles

a. Titus
b. E.H. Price
c. Krueger
d. Nailor
e. MetalAire

.6 Manual Dampers

a. Tamco
b. Nailor
c. Ruskin
d. Controlled Air
e. Alumavent

.7 Combination Fire / Smoke Dampers

a. Controlled Air
b. Nailor
c. Ruskin
d. Alumavent

.8 Access Doors

a. Nailor

b. Controlled Air
c. Ruskin

.9 Flexible Connectors

a. Duro-Dyne
b. Dyn-Air
c. American Elgen

.10 Flexible Ductwork

a. Thermaflex
b. Flexmaster
c. Wiremold

**END OF SECTION**

## 1. GENERAL

1.1 General Requirements

.1 Refer to the following related sections:

a. Division 20 – Mechanical.
b. Division 22 – Plumbing.
c. Division 23 – HVAC.
d. Section 25 90 00 – CONTROL SEQUENCES

.2 Comply with the conditions of Division 0 and 1.

## 2. BUILDING AUTOMATION SYSTEM

2.1 Description of System

.1 Furnish and install all components, devices and control wiring for a fully integrated energy management and building control system incorporating Direct Digital Control (DDC), and equipment monitoring. The system shall control/monitor HVAC and plumbing equipment and systems as specified in this section. The work shall include but is not limited to the following:

a. All necessary hardware, software, control panels, web access modules, control wiring, field devices, installation, documentation and owner training as specified.
b. The installed system shall incorporate electronic and digital control devices to perform the control sequences and monitoring outlined herein. Specific control sequence requirements are as detailed elsewhere in this section of the specification.
c. Control valves shall be installed in the piping system complete with transitions and unions as required.
d. Testing, debugging, calibrating, adjustment, programming and confirmation of total system operation.

.2 Distech System Integration (SI) Partners

a. The fundamental purpose of BAS integration at the WRDSB consist of four primary objectives:
   i. to maintain continuity of the Central Command Structure (a.k.a. Global/Local)
   ii. to allow for future expansion of centrally adjusted network variables/parameters
   iii. to maximize the administrative efficiency in which we can optimize the functionality and performance of the BAS systems inside 125+ buildings.
   iv. Maintain Web Security of entire BAS Infrastructure.
b. Distech BAS SI Partners must incorporate the integration of the WRDSB NIAGARA BAS server as specified in this document. Upgrading or circumventing the functionality of the existing central WRDSB NIAGARA BAS server will not be considered. No unequivocal or irrevocable substitutions of the WRDSB BAS server allowed.

.3 Central Command Structure: (two servers during transition period to Niagara-based software)

a. WRDSB Vista BAS Server
   i. Update name to VISTA (formerly EC-TACBAS) on the WRDSB network.

ii. is based on the Lonworks (LNS) Based Interface
iii. utilizes Remote Network Interfaces (RNI) Ethernet adapters at each site to communicate to the Lonworks network at each site.
iv. distributes all network variables via the RNI using the LNS protocol and Loytec NIC-IP to each site.
v. used to administer the TAC Xenta and Lonworks based BAS devices with the Echelon Lonmaker Network configuration tool, Schneider Electric TAC Vista System Plug-in Tool, and Schneider TAC Menta programming software.

b. WRDSB Niagara BAS Server
i. Update name to NIAGARA (formerly EC-TACBAS-T) on the WRDSB network
ii. is based on the Niagara N4-based Distech EC-NET server software to administer the EC-BOS networking devices at each site
iii. utilizes Niagara N4-based Distech EC-BOS networking servers complete with adapters at each site to communicate to the BACnet and Lonworks (where applicable) network at each site.
iv. distributes all network variables via the Tridium Niagara FOX protocol to each site
v. used to administer the Distech BACnet and Lonworks (where applicable) based BAS devices with the Distech GFX programming/controller configuration and Tridium Niagara WorkBench software
vi. utilizes Baudrate Schneider Electric TAC driver software (where applicable) to support the Lon-based TAC Xenta Controllers.

.4 Network Variables

a. Over 30 network variables (as detailed in Appendix I) are distributed from the central WRDSB BAS server to all 125 sites at varying intervals:
i. for the purpose of zone temperature setpoint adjustment
ii. to place lockouts on heating/cooling systems in response to changing seasonal conditions
iii. to manage setpoints for night setback heating and cooling modes
iv. to manage minimum outside air setpoints for ventilation requirements
v. to adjust the beginning and end of heating season
vi. to manage boiler water temperature setpoint outdoor reset parameters
vii. to set the morning warmup and night setback offset for boiler water temperature.
viii. to place lockouts on ventilation based on building use requirements.
ix. to place restrictions on ventilation based on humidity for additional energy savings measures.
x. to distribute humidity information from one of the three WRDSB humidity averaged zones
xi. to distribute the central holiday schedule for setback mode operation
xii. for Outdoor Lighting Astroclock Control adjustments to sundown and sunset times
xiii. for the purpose of after-hours alarms and troubleshooting
xiv. a dashboard is used at the central server to provide a user interface for all the variables and corresponding time/calendar schedules used in the BAS system.
xv. a central alarm display is used to capture all incoming BAS alarms from each site.

.5 Quality Assurance

a. The system components shall be listed by Underwriters Laboratories Inc. and Canadian Standards Association.
b. The system control products shall be stored and handled according to manufacturer's recommendations.
c. The work shall be performed by skilled technicians all of whom shall be properly trained and qualified for this work.

2.2 Products

.1 Hardware requirements:

a. LON board inside Distech EC-BOS: Installed on site, interfaces between site BAS system, Distech Lonworks Controller and Loytec NIC-IP.
b. Loytec NIC-IP RNI: Installed at each site, interfaces between site BAS system and WRDSB NIAGARA server via Ethernet and Lonworks networks.
c. a LON-based Distech controller: Must be current version. Installed on site, holds the network variables for use by both the WRDSB NIAGARA server and the site BAS system, and also the switching logic between local and global variable selection.
d. Licensing for LON board, Baudrate Schneider TAC Xenta driver for the Distech EC-BOS: Allows access to TAC Xenta controllers points, time schedules and alarms for use in the EC-BOS. Licensing confirmation of LON boards, Schneider TAC Xenta Driver, current Distech BAS SI Partner confirmation as a minimum.
e. Distech BACnet MS/TP based controllers are accepted for use with all the remaining systems.
f. WRDSB Ethernet Drops: Installed on site, to be co-ordinated with WRDSB IT department, fixed IP address to be assigned by IT.
g. All existing functioning BAS devices within each of the 125+ WRDSB buildings including but not limited to Lonworks, BACnet controllers as well as other field controls including sensors, valve or damper actuators, VFD drives, chiller systems, unit vents, air handlers, accessories or others, shall remain integrated. Approaches that require the replacement of existing functioning BAS devices other than the required LAN interfaces for proper integration (EC-BOS / NIC-IP) will not be considered.

.2 Software requirements:

a. Loytec Lconfig: Used as setup tool to configure IP address on the Loytec NI-IP for use on WRDSB Ethernet network.
b. Distech gfx: Used as setup tool to program the Distech Lonworks controller to accept the network variables.
c. Distech Workbench N4: Used as a setup tool for the Distech EC-BOS

.3 The system shall integrate the operation of intelligent building management controllers distributed into the network.

.4 Provide web based access. Two ethernet connections for communication shall be provided by the Electrical Trade.

.5 The DDC system shall be generally comprised of the following devices to achieve the control functions described in this section:

a. Distech 200, 300, 400 and 600 series programmable controllers.
b. Distech input/output programmable controllers.
c. Network repeaters as required by network lengths.
d. Control relays.
e. Control dampers and valves.
f. Sensors, actuators and other input/output devices.

.6 Controllers shall execute the application programs, calculations, and commands to provide the control function specified for that unit. Each controller shall include its own micro-computer controller, power supply, input/output modules, termination modules and real time clock.

.7 Controllers shall be capable of full control functionality and alarm reporting independently or as a part of the DDC network.

.8 The system shall be stored in flash ram so no batteries are required.

.9 Each control device shall be modular and expandable to provide additional inputs and outputs and control functionality for that device.

.10 Each controller shall be able to transfer and receive data via the network for performance of control functions.

.11 The system shall be modular, permitting expansion by adding hardware and software without changes in communication or processing equipment.

.12 The controllers shall monitor the status of all overrides and include this information in logs and summaries to inform the operator that automatic control has been inhibited.

.13 Controllers shall continuously perform self-diagnostics, communication diagnosis and diagnosis of all subsidiary equipment and provide both local and remote annunciation of any component failures.

.14 Controllers shall activate an orderly shutdown of their operation in the event of loss of normal electrical power. Non-volatile memory shall be incorporated for all controller configuration data. The controllers shall automatically resume full operation without manual intervention.

.15 The controllers shall have sufficient memory to support their own operating system and data bases including:

a. Control processes.
b. Energy management applications.
c. Alarm management.
d. Trend data.
e. Operator input/output.
f. Remote communications.
g. Manual override monitoring.

.16 Controllers shall incorporate the following software features:

a. Energy management:
   i. Time of day scheduling.
   ii. Calendar based scheduling.
   iii. Holiday scheduling.
   iv. Optimal start and stop.
   v. Demand limiting.
   vi. Heating/cooling interlock.

b. Alarm management:
   i. Alarm management shall be provided to monitor, buffer and direct alarm reports to operator devices and memory files. The controllers shall perform alarm analysis and filtering to minimize operator interruptions due to non-critical alarms, minimize network traffic and prevent alarms from being lost.
   ii. All alarm or point change reports shall include the points' English language description and the time and date of occurrence.
   iii. The user shall be able to define the specific reaction for each point, the priority level (three in total) and ability to inhibit alarm reporting for each point.
   iv. The user shall be able to define conditions under which point changes need to be acknowledged by an operator and logged for analysis at a later date.
   v. The user shall be able to print, display or store a unique sixty character alarm message to more fully describe the alarm condition or direct operator response. The message shall be customizable to describe each individual alarm.
   vi. In web access applications, only critical alarms shall initiate a call to a remote operator device, otherwise call activity shall be minimized by time stamping and saving reports until a manual request is received or until the buffer space (minimum fifty alarms) is full.

c. Trend logs:
   i. Controllers shall provide an automatic roll-over trend log, which stores records up to an operator-selected number at an operator-selected sampling rate and then overwrites the oldest record with each new record.
   ii. Sample intervals shall be from one minute to twenty-four hours.
   iii. Provide graphical and tabular displays.

d. Runtime totalization:
   i. The controllers shall automatically accumulate and store runtime hours for binary points with a sampling resolution of one minute. The user shall have the ability to define a warning limit to trigger maintenance or user-defined messages.

e. Event totalization:
   i. Controllers shall have the ability to count events (such as on/off) and store up to ten million events before reset with a user-defined limit used to trigger a user-defined message.

f. Custom programming:
   i. The controllers shall permit user defined custom control processes based on:
      1) Any system measured data or status.
      2) Any calculated data.
      3) Any results from other processes.
      4) Boolean logic.

g. The custom processes may be triggered by:

i. Time-of-day.
ii. Calendar date.
iii. Events (point, alarm, etc.).

.17 The control strategy for each control loop shall be performed by software within the controller. The sequence of events required for each control loop is described for each system in the control sequence.

.18 Outdoor air temperature indication shall be available at each controller as an integral part of the control strategies for that controller. Should the network transmission of the common outdoor air temperature (or any other common value) fail, then each controller shall use the last good value received.

.19 Control Panels

a. Control panels shall be fully enclosed cabinets with all steel construction. Cabinets shall have a hinged door with locking latch or bolt-on cover plate. All cabinet locks shall be common keyed. Cabinets shall be finished with two coats of paint.

.20 Temperature Sensors

a. Provide thermistor temperature sensors, not requiring transmitters, to measure temperature.
b. Accuracy shall be +/-0.2°C from 0 to 70°C.
c. Space sensors in occupied areas shall be Greystone TE200 series, type AE or equal having an integral push button for unoccupied override and an integral slider to adjust set point (LED display not required).
d. In corridors and where noted on the drawings, provide stainless steel plate type sensors (push button override and LED display not required), Greystone TE200 series, type AS or equal.
e. Duct temperature sensors shall be Greystone TE200 series, type B or equal having a stainless steel probe length to suit application and ABS enclosure. Duct averaging temperature sensors shall be Greystone TE200 series, type FD or equal having an element length to suit application, copper probe and ABS enclosure.
f. Outdoor temperature sensors shall be Greystone TE200 series, type F or equal having an ABS gasketed cover. A thermal radiation cover shall limit the sensor to solar radiation exposure.

.21 Humidity Sensors

a. Sensors shall have 0-100% RH operating range, 0.01% RH resolution, +/- 0.8% RH hysteresis at 25°C (77°F) and 8 second response time.
b. Space sensors shall be Greystone HRC series room humidity transmitter or equal complete with +/- 2% accuracy and 0°C to 50°C (32°F to 122°F) ambient temperature operating range.
c. Duct mounted sensors shall be Gerystone HSDT series duct humidity transmitter or equal complete with stainless steel probe length to suit application, ABS enclosure, +/- 2% accuracy and -40°C to 60°C (-40°F to 140°F) ambient temperature operating range.

.22 Carbon Dioxide Sensors

a. Sensors shall Greystone CDD series or equal having the following features:
   i. 0-2000 ppm factory default detection range, field adjustable.
   ii. Non-dispersive infrared sensing element with self-calibration algorithm.
   iii. Guaranteed five year calibration interval.
   iv. Powered by either AC or DC source.
   v. Accuracy: within 50 ppm or 3% of reading (whichever is greater).
   vi. Operating humidity range: 0-95% RH.
   vii. Operating temperature range: 0 to 50°C or greater.
   viii. Stability: less than 2% full scale in 15 years.
   ix. Response time: less than 2 minutes for 90% step change.
b. Duct mounted sensors shall be complete with ABS enclosure complete with sampling tube.

.23 Water Control Valves

a. Heating and cooling control valves shall be Belimo CCV series characterized ball valves, complete with chrome plated brass trim and NPT female pipe connections. Radiation valves shall be complete with non-spring return modulating actuators. Control valves for coils heating a portion of outdoor air shall have spring return modulating actuators.
b. Control valves shall be sized to provide approximately one half the circuit branch pressure drop to obtain good modulation control but they shall be no smaller than two pipe sizes less than the pipe they are installed in.

.24 Motorized Damper Actuators

a. Belimo or approved equal as follows:
   i. Modulation proportional control (2-10VDC / 4-20mA with 500 ohm resistor)
      1) Model LF24-MFT(-S) US, 24 volt for dampers up to 6 sq. ft. (0.56 sq. m.).
      2) All actuators shall be direct coupled, spring return.
   ii. Where required by damper size, provide multiple actuators to serve one damper.
   iii. Provide all accessories required for mounting and balancing, including angle of rotation limiter where required, and end switches where required by control configuration.
b. Provide damper actuators where indicated on the floor plan, details, equipment schedules or control sequences.

.25 Freezestats

a. Freezestats shall be complete with a vapour filled 20 foot bulb and 4 foot capillary. Wire freezestats to shut down the respective fans should temperature over any 12 in of sensor length drop below the adjustable setpoint (2°C). Freezestats shall have manual resets.
b. Provide freezestats where indicated on the floor plan, details, equipment schedules or control sequences.

2.3 Execution

.1 Installation

a. All controllers and components in the system and on the network shall be installed according to manufacturer recommendations, general installation standards for digital controls and in accordance with the approved shop drawings.
b. Locate room sensors in the locations shown on the mechanical drawings. All sensors shall be mounted at barrier free height (3'-11" above finished floor).
c. All control components for off site system access shall be located where noted on the drawings. The Electrical Trade shall provide all required connections / cabling for off site access to the web access components.
d. All programmable controllers, web access components, relays and other control components shall be located within control panels. Control panels shall be wall mounted and shall be located within suspended ceiling spaces or other locations approved by the Consultant.
e. The supply of all motorized temperature control dampers complete with actuators shall be by this section, except for dampers and actuators supplied with packaged air handlers.
The supply of all automatic control valves shall be by This Section.

.2 Security and serviceability:

a. Supply username and password.
b. Source programming software tools with never expiring licenses
c. Source files and databases for all BAS controllers, networking hardware to be able to network, initialize and replace BAS controllers.
d. Remote access to school BAS system will not be via VPN or similar method. It will be a managed firewall when available. WRDSB IT firewall and networking rules will need to be followed when integrating the BAS system to the WRDSB NIAGARA BAS Server.

.3 Reporting requirements:

a. Network Transfer Diagram: List in a matrix format, all Distech BAS controllers and associated the network variables, indicating the source and destination for each network variable.
b. Version Control: Maintain a variable for version number for each Distech BAS controller's software with a description of what changes and updates to the controller software were made, initialled, and dated by the programmer in the source code of the controller.
c. Graphical User Interface:
    i. MAIN graphic: Display all the global network variables, the adjustable local network variables, the adjustable local/global mode switch and the actual network variables in current use, which are actually sent to all the controllers on the local BAS network. Refer to attached sample graphic.
    ii. SYSTEMS graphics (e.g., AC1, AHU1, RTU3): Indicate the current status of the heating enable, cooling enable, adjustable Holiday Exemption flag, final zone setpoint, Minimum Outside Damper position, Maximum Outside Damper position, Minimum Outside Air Schedule status. Night setback heating and cooling setpoints.
    iii. MAIN graphic: A link to a notepad file application where an operator can maintain a running day and timestamp in logbook format for any changes/adjustments made to the system, noting any issues that may arise.


.4 Implementation:

a. Chain of Data Custody Sequence:
   i. Network Variables/Parameters are written to the Distech Lonworks Controller by the WRDSB NIAGARA server via the Loytec NIC-IP adapter.
   ii. The Distech EC-BOS reads the network variables and then stored on the Lon controller and then distributes them to each controller on the local BAS network for use in its sequence of operations.
   iii. These network variables are to have a parallel set of local network variables stored in the Distech EC-BOS to be used in the local mode. The local mode when selected will transfer the use of the local network variables from the Distech EC-BOS to each controller on the local BAS network instead of the global network variables written to it by the WRDSB EC-TACBAS server.
   iv. The local/global mode switch will be adjustable by the WRDSB NIAGARA server and shown on the main page graphic also adjustable by the operator.


b. Data Functionality and Persistence:
   i. All network variables/parameters must be backed up into non-volatile RAM so that the network variables are automatically restored after a reboot/cold start.
   ii. Local/Global Mode Flag to be read/writeable from the WRDSB NIAGARA Server.
   iii. Critical Alarms reported back to WRDSB NIAGARA server.
   iv. If site is designated to have an outdoor humidity sensor, the real time value is to be sent back to the WRDSB EC-TACBAS server.


c. Overview:
   i. Service office within 1 hour of all WRDSB Facilities during school hours and after hours.
   ii. Written confirmation of Distech SI partnership for WRDSB territory.
   iii. Written confirmation of Schneider/TAC Xenta License for NIAGARA Server for WRDSB territory.

d. Sample:
   i. Typical MAIN graphic for each site representing the expected functionality and data representation of the local/global system:


Clear Overrides
A.R.Kaufman
LEGEND
0.0 °C Adjustable Setpoint
0.0 °C Calculated Value
0.0 °C Measurement
Multi-Zone 1
Multi-Zone 2
Multi-Zone 5
AC 1 (Office)
HV 1 (Gym)
Floor Plan
Exterior Lighting
Sunrise
Sunset
Sunrise/Sunset
Disabled
Lights off 0 Min after sunrise
Lights on 0 Min before sunset
Lights On
Domestic Cold Water
Flush valve Close
Outside Air Temp 0.0 °C
Fire Alarm Normal
Ventilation Lockout Normal
Critical Alarm Normal
Lowest Space Temperature 0.0 °C
Setpoint 0.0 °C
Reset 0.0 °C
Local
OAT Heating Enable
OAT Cooling Enable
Zone Setback Heating
Zone Setback Cooling
Zone Setpoint Adjust
Holiday Schedule
MinOA Schedule
Status Disabled Disabled
Local 0.0 °C 0.0 °C 0.0 °C 0.0 °C 0.0 °C Holiday Disabled
Global 0.0 °C 0.0 °C 0.0 °C 0.0 °C 0.0 °C Holiday Disabled
Actual 0.0 °C 0.0 °C 0.0 °C 0.0 °C 0.0 °C Normal Enabled
Electric Heating
Entrance Vestibules Start
OAT Enable Setpoints
Occupied 0.0 °C
Unoccupied 0.0 °C
Outdoor Air Humidity 0 %RH
Free Cooling Setpoint 0 °C
Free Cooling Max 0 %

e. From Remote Access PC to WRDSB BAS Server to Site – General Architecture:




- Network Variables are received at each site via the NIC-IP and onto the Distech ECL-300 or TAC Xenta 401B Controller and distributed for use at each BAS controller by the EC-BOS.

.5 All carbon dioxide levels which are measured by the carbon dioxide sensors shall be made available to the Owner in the form of trend logs. Record readings at 10 minute intervals and keep them for at least 30 days.

.6 Freezestats shall be installed so that their sensing element runs horizontally across the coil face (not diagonally) with no more than 12" vertical drops at the outside coil frame. The full face of the coil shall be covered with no horizontal runs being more than 12" apart. The top and bottom horizontal run shall be within 6" of the coil frame. If more than one freezestat is required they shall be wired in series in order to detect a low temperature in portion of the

coil. The sensing elements shall be firmly secured in place to avoid vibration without added air restriction.

.7 System Start-up and Acceptance

a. Upon completion of installation, test, adjust and calibrate controls provided under this Section.
b. On system completion, a demonstration of complete system operation shall be made to the Owner's authorized representative and Consultant.
c. The Consultant shall verify through the Owner's representatives that the entire system is complete and operating to the satisfaction of the Owner before final acceptance is approved.

.8 Close-out Documentation

a. Provide master schedule of all BAS controlled mechanical equipment affected by work indicating equipment tag and brief description. Master equipment schedule shall be expanded in future projects.
b. Demonstrate full functionality of the integration from the WRDSB server altering the settings on each of the BAS controllers on site.
c. Database files: to be backed up and given to WRDSB facilities on USB drive.
    i. Loytec NIC-IP: Configuration File
    ii. Distech EC-BOS with Lonworks board and 5-year software updates license: database file
    iii. Distech Lonworks controller: controller program file
    iv. Menta: controller program file for the existing TAC Xenta controllers (supplied by WRDSB to integrator)
d. Complete and submit WRDSB commissioning sheets for all equipment (new and existing) upgraded to BAS control as part of this project.
e. Refer to Division 20 for additional requirements.

.9 Training

a. The Controls Trade shall provide competent instructors to give full instruction to designated personnel in the adjustment, operation and maintenance of the system installed rather than a general training course. Instructors shall be thoroughly familiar with all aspects of the subject matter they are to teach. All training shall be held during normal work hours of 8:00 a.m. to 4:30 p.m. weekdays as follows:
b. Provide 4 hours of training for Owner's operating personnel. Training shall include:
    i. Explanation of drawings, operations and maintenance manuals.
    ii. Explanation of web access program.
    iii. Explanation of adjustment procedures.
    iv. Trend analysis.

.10 Identification

a. Provide system identification and provide nameplates identifying the following (nameplates shall be keyed to the wiring diagrams):
    i. Duct mounted sensors.
    ii. Control panels (identify as to equipment / systems controlled). Each panel shall include an as-built drawing showing all the connected control points.

.11 Testing and Balancing

a. During the system testing and balancing by the Balancing Trade, demonstrate the operation of all controls. During balancing procedures, set controls to a fixed mode (bypass damper locked fully closed and all zone dampers locked fully open) to prevent any changes during the balancing procedure.
b. To ensure excessive noise is not generated by the VVT systems, the following shall be performed:
    i. For each VVT system, the Balancing Trade shall measure the static pressure in the main duct using a manometer when the system has been stabilized (all zone dampers are full open and the bypass damper is full closed). This information shall be given to the Controls Trade for verification that the VVT system is properly calibrated.
    ii. For each VVT system, 10% of the dampers shall be set to the full open position and 90% shall be set at their minimum position (fully closed). When operating with these damper positions, the static pressure in the main duct shall again be measured by the Balancing Trade using a manometer to ensure it remains at the value measured when in the stabilized mode. This information shall be given to the Controls Trade for verification that the VVT system is operating correctly and is properly calibrated.

.12 Electrical Wiring

a. Control transformers for the building automation systems shall be supplied and wired by the Controls Trade from 120 V power sources in junction boxes (at least one at each end of each floor accessible above ceiling tile in a corridor). All low voltage wiring (below 50 V) to the building automation systems shall be by the Controls Trade.
b. All wiring shall be installed to the standards specified in the Electrical Division.
c. Use Echelon recommended orange jacket cable for all network wiring.
d. Run all wiring in EMT conduit where exposed, where running within concrete block walls and where required by the Ontario Electrical Code (conduit supplied and installed by the Controls Trade). Plenum rated cable shall be used in return air ceiling plenums.
e. Where wiring runs through corridor suspended ceiling spaces, run in wall hooks where possible. The wall hooks shall be provided by the Electrical Trade where indicated on the electrical drawings.
f. Control relays necessary for BAS operation shall be provided by the Controls Trade but all contactors and their power supplies handling power wiring to the equipment shall be by the Electrical Trade.

2.4 Appendix: WRDSB BAS Network Variables

.1 Globally Distributed Variables from Central BAS Server to Each Site: Each controller on the BAS network on each site will use the following network variables/parameters to integrate into their sequence of operations.

.2 For all Air Handling/Rooftop/Unit Vent Systems:

a. Heating Outside Air Temperature Enable
b. Cooling Outside Air Temperature Enable
c. Zone Temperature Night Setback Heating Temperature Setpoint
d. Zone Temperature Night Setback Cooling Temperature Setpoint
e. Zone Temperature Setpoint Adjust
f. Holiday Scheduling
g. Minimum Outside Air Enable Schedule (Zone 1)
h. Minimum Outside Air Setpoint (Zone 1)
i. Minimum Outside Air Setpoint (Zone 2)
j. Minimum Outside Air Setpoint (Zone 3)
k. Minimum Outside Air Setpoint (Zone 4)
l. Outdoor Air Humidity (Zone 1 calculated average from 3 local sites)
m. Outdoor Air Humidity (Zone 2 calculated average from 3 local sites)
n. Outdoor Air Humidity (Zone 3 calculated average from 3 local sites)
o. Outdoor Air Humidity Maximum Damper Position (Zone 1 Free Cooling Maximum)
p. Outdoor Air Humidity Maximum Damper Position (Zone 2 Free Cooling Maximum)
q. Outdoor Air Humidity Maximum Damper Position (Zone 3 Free Cooling Maximum)
r. Outdoor Air Humidity Maximum Damper Position (Zone 4 Free Cooling Maximum)
s. Free Cooling Maximum Mode (Zone 1)
t. Free Cooling Maximum Mode (Zone 2)
u. Free Cooling Maximum Mode (Zone 3)
v. Free Cooling Maximum Mode (Zone 4)\

.3 For Outdoor Lighting Astroclock Control:

a. Lights Off After Sunrise Offset (in minutes) Area 1
b. Lights Off After Sunrise Offset (in minutes) Area 2
c. Lights Off After Sunrise Offset (in minutes) Area 3
d. Lights Off After Sunrise Offset (in minutes) Area 4
e. Lights On Before Sunset (in minutes) Area 1
f. Lights On Before Sunset (in minutes) Area 2
g. Lights On Before Sunset (in minutes) Area 3
h. Lights On Before Sunset (in minutes) Area 4

.4 For Boiler Systems:

a. Boiler Systems Area 1:
    i. Outside Air Temperature 1
    ii. Hot Water Temperature High Setpoint
    iii. Outside Air Temperature 2
    iv. Hot Water Temperature High Setpoint
    v. Morning Warmup Hot Water Temperature Offset
    vi. Night Setback Hot Water Temperature Offset

vii. Gas and Boiler Systems Heating Enable/Disable Dates (4 variables):
1) Heating On Month
2) Heating On Day
3) Heating Off Month
4) Heating Off Day

b. Boiler Systems Area 2:
i. Outside Air Temperature 1
ii. Hot Water Temperature High Setpoint
iii. Outside Air Temperature 2
iv. Hot Water Temperature High Setpoint
v. Morning Warmup Hot Water Temperature Offset
vi. Night Setback Hot Water Temperature Offset
vii. Gas and Boiler Systems Heating Enable/Disable Dates (4 variables):
1) Heating On Month
2) Heating On Day
3) Heating Off Month
4) Heating Off Day

c. Boiler Systems Area 3:
i. Outside Air Temperature 1
ii. Hot Water Temperature High Setpoint
iii. Outside Air Temperature 2
iv. Hot Water Temperature High Setpoint
v. Morning Warmup Hot Water Temperature Offset
vi. Night Setback Hot Water Temperature Offset
vii. Gas and Boiler Systems Heating Enable/Disable Dates (4 variables):
1) Heating On Month
2) Heating On Day
3) Heating Off Month
4) Heating Off Day

d. Boiler Systems Area 4:
i. Outside Air Temperature 1
ii. Hot Water Temperature High Setpoint
iii. Outside Air Temperature 2
iv. Hot Water Temperature High Setpoint
v. Morning Warmup Hot Water Temperature Offset
vi. Night Setback Hot Water Temperature Offset
vii. Gas and Boiler Systems Heating Enable/Disable Dates (4 variables):
1) Heating On Month
2) Heating On Day
3) Heating Off Month
4) Heating Off Day

.5 Additional Parameters used to calculate final values for distribution from Central Server:

a. Winter Outside Air Temperature Heating Enable Setpoint
b. Summer Outside Air Temperature Heating Enable Setpoint
c. Summer Winter Heating Schedule
d. Winter Outside Air Temperature Cooling Enable Setpoint
e. Summer Outside Air Temperature Cooling Enable Setpoint
f. Summer Winter Cooling Enable Schedule
g. Normal Night Setback Temperature Heating Enable Setpoint

h. Economy Night Setback Temperature Heating Enable Setpoint Calculated
i. Comfort/Economy Night Setback Heating Schedule
j. Outside Air Low Reset for Economy Night Setback Reset Heating Setpoint
k. Night Setback Low for Economy Night Setback Reset Heating Setpoint
l. Outdoor Air High Reset for Economy Night Setback Reset Heating Setpoint
m. Night Setback High for Economy Night Setback Reset Heating Setpoint
n. Normal Night Setback Temperature Cooling Enable Setpoint
o. Economy Night Setback Temperature Cooling Enable Setpoint Calculated
p. Comfort/Economy Night Setback Cooling Schedule
q. Normal Setpoint Adjust
r. Economy mode Setpoint Adjust
s. Comfort Economy Setpoint Adjust Schedule
t. Minimum Outside Air Damper Position Setpoint Schedule to Send Area 1
u. Minimum Outside Air Damper Position Setpoint Schedule to Send Area 2
v. Minimum Outside Air Damper Position Setpoint Schedule to Send Area 3
w. Minimum Outside Air Damper Position Setpoint Schedule to Send Area 4
x. Astroclock Lights Off After Sunrise /On Before Sunset Send Schedule Area 1
y. Astroclock Lights Off After Sunrise /On Before Sunset Send Schedule Area 2
z. Astroclock Lights Off After Sunrise /On Before Sunset Send Schedule Area 3
aa. Astroclock Lights Off After Sunrise /On Before Sunset Send Schedule Area 4
bb. Heating Systems Send Schedule Area 1
cc. Heating Systems Send Schedule Area 2
dd. Heating Systems Send Schedule Area 3
ee. Heating Systems Send Schedule Area 4

.6 Locally Distributed Network Variables Distributed between Master controller and each Controller within each site: These Network Variables are centrally managed and distributed to each controller. A local copy of these variables are maintained and are adjustable when the site is set to local mode operation.

a. Outside Air Temperature
b. Local Holiday Schedule
c. Fire Alarm Status
d. Ventilation Lockout Status
e. Heating Outside Air Temperature Enable/Disable
f. Cooling Outside Air Temperature Enable/Disable
g. Zone Temperature Night Setback Heating Temperature Setpoint
h. Zone Temperature Night Setback Cooling Temperature Setpoint
i. Zone Temperature Setpoint Adjust
j. Holiday Scheduling
k. Minimum Outside Air Enable Schedule

.7 Additional calculated parameters used in the sequence of operations and shared across the site network:

a. Minimum Zone Temperature per Controller
b. Maximum Zone Temperature per Controller
c. Minimum Zone Temperature per Site (data is aggregated across all the controllers and concentrated at the single master controller that triggers the low temperature alarm contacts)

d. Maximum Zone Temperature per Site (data is aggregated across all the controllers and concentrated at the single master controller)

**END OF SECTION**

## 1. 26 05 00 COMMON WORKS

1.1 General Requirements

.1 The Procurement and Contracting Requirements as outlined under Division 00, and the General Requirements as outlined under Division 01, and all addenda thereto shall apply to and govern all portions of the electrical work.

.2 Reference Division 27 and Division 28 for additional requirements.

.3 Points not specifically mentioned shall be in strict accordance with the Ontario Electrical Safety Code (OESC) and regulations of the Electrical Inspection Department from which the permit was obtained. The latest revisions and/or amendments to this Code, with applicable date restrictions, shall also govern work on this contract.

.4 It is the intent of these specifications to supply and install all materials and equipment as herein specified, and/or shown on the drawings in such a manner as to leave each of the systems of the electrical trades complete and in satisfactory operating condition. Provide all products and methods specified or shown complete with incidentals necessary for a complete operating installation. The contract documents are not intended to enumerate each and every detail which may be necessary to furnish and install the complete system connected up ready for service operation. The bid shall include all such details, and all associated labour and materials, to provide a complete and working system. The omission of any details in the contract documents shall not be a warrant for the installation of poor workmanship or materials, or the omission of such details. The scope of the work to be performed by the Contractor shall be obtained by a careful examination of these specifications and all electrical drawings.

.5 These specifications are to be considered as an integral part of the plans which accompany them, neither the plans nor the specifications shall be used alone. Any item or subject omitted from one but which is mentioned or reasonably implied in the other shall be considered as properly and sufficiently specified and must, therefore, be provided by the Contractor. Misinterpretation of either the plans or the specifications shall not relieve the Contractor of responsibility.

.6 The Electrical Subcontractor shall be held responsible for the satisfactory completion of all work bearing upon their trade.

.7 The Electrical Subcontractor must make note of any inaccuracies or inconsistencies in the drawings and/or specifications. Prior to bid close, any such items shall be disclosed, following the procedure outlined in the Invitation to Proponents.

.8 Within this design, the term “provide” is defined as “supply and install”.

.9 Extra charges for premium time labour shall be included in the bid price as required to comply with the construction schedule and the restrictions on when work will be permitted in the existing building. Allow for after hours, weekend and holiday labour requirements.

.10 Re-mobilization of any resources or sub-trades as required to maintain schedule or construction sequencing shall be included.

1.2 Codes, Permits and Submissions

.1 All work shall comply with the OESC (current edition, including all bulletins and amendments) and all local and municipal codes and Government agencies having jurisdiction.

.2 It is understood that the Subcontractor has examined and checked all drawings and specifications with the local authorities and the equipment and materials supplied by the Subcontractor shall have the approval of CSA, ULC, Factory Mutual (FM) and any other authority having jurisdiction.

.3 The Electrical Subcontractor shall obtain and pay for all necessary permits and inspection fees as may be required by the public administrative authorities having jurisdiction. Any changes or alterations required by an authorized inspector shall be rectified by the Electrical Subcontractor without charge to the Owner.

.4 Plans have not been submitted to the Electrical Safety Authority (ESA) Plans Approval Department. In accordance with the requirements of 2-010 of the OESC, plan submission is not required for this project.

.5 All new electrical equipment must conform to the regulations of the Ontario Electrical Safety Code (OESC). Anything necessary to make the equipment comply with these requirements shall be provided without additional cost to the Owner.

.6 Submit all required documentation to the authorities for their approval and comment before starting any work. Provide all additional drawings, details or information as may be required.

.7 Inform the Consultant in writing if modifications to the work are requested by the authorities. Provide complete written description of the concerns raised.

1.3 Standards of Workmanship and Materials

.1 All materials supplied by the Contractor shall be new and of the quality specified. All such materials shall be certified by CSA or other organization approved by the ESA. For any material not so certified, the Electrical Subcontractor shall obtain special approval of the local Inspection Authority and shall bear all inspection charges levied and any modification cost required.

1.4 Quality Assurance and Regulatory Agencies

.1 All materials, installations supplied and performed by the Electrical Subcontractor shall be new and meet the standards of quality as specified herein:

a. Canadian Standards Association - CSA.
b. Ontario Regulation 163/24 (2024 Ontario Building Code) - OBC with amendments.
c. Local Fire Codes.
d. Ontario Ministry of Labour.
e. Ministry of the Environment.
f. Ontario Electrical Safety Code.
g. Local Electrical Inspection Department.

1.5 Contractor's Shop

.1 Each Subcontractor shall provide their own office, workshop, tools and materials storage as required, and be responsible for any loss or damage thereto.

1.6 Setting Out of the Work

.1 The electrical trade shall be responsible for correcting all work completed contrary to the intent of the drawings and specifications and shall bear all costs for same. Where the intent of the documents is not clear the electrical trade shall obtain the clarification of the Engineer before proceeding with the work.

.2 Where any equipment supplied by the electrical trade must be built-in with work of the other Subcontractors, the Electrical Subcontractor shall be responsible for the supplying of the equipment to be built-in or measurements to allow necessary openings to be left so as not to hold up the work.

.3 The electrical trade, in setting out of the work, shall reference Architectural, Structural, Fire Suppression and Mechanical drawings. Electrical shall consult with the respective trades in setting out locations for conduit runs, lighting fixtures, panel assemblies, etc. so that conflicts are avoided and symmetrical even spacing is maintained. Being there first is not a permissible excuse.

.4 Do not scale drawings for installation purposes. Obtain all dimensions from Architectural plans, manufacturers Shop Drawings and onsite inspections.

.5 Before submitting bid, carefully examine the site of the proposed work so as to ascertain all existing conditions affecting the work. No extras will be allowed for work necessitated by conditions ordinarily evident on the site.

.6 Installation of conduits, outlets and equipment in mechanical areas shall not proceed until the installation of mechanical equipment is far enough progressed to avoid conflicts. Position of electrical equipment and outlets shall be adjusted in these areas to coordinate with mechanical equipment.

1.7 Preparation

.1 Cutting and Patching

a. The Electrical Subcontractor shall be responsible for all cutting and patching of any building construction made necessary by the installation of the work except in such instances as may be otherwise assigned by the specifications or shown on the drawings. All cutting and patching shall be to the satisfaction of the Consultant.
b. Finishing shall be by General trades.

.2 In areas otherwise unaffected by the work of this contract, trades that are required to disturb existing finishes shall patch the existing surfaces and provide new finishes to the area of the wall or ceiling surface affected. Paint colour shall be selected to match existing. Repainting of entire walls or surfaces is not required unless a reasonable paint match cannot be obtained.

.3 Existing ceiling tiles and grids shall be removed and replaced as required to permit the work. Ceiling tiles and grids that are damaged, or left with holes shall be replaced with new to match existing.

.4 All devices required to be removed in existing walls shall have suitable blank cover plates installed.

.5 Existing structure may contain concealed conduits. The Electrical Subcontractor shall retain the services of a qualified concrete imaging company to scan for existing buried services prior to cutting/coring/drilling.

.6 The Electrical Subcontractor shall provide all sleeves, inserts, hangers, flashings, back boxes, tubs, junction boxes, etc. required for the completion of the work. Locations shall be coordinated with the respective subtrade into whose materials they are being installed.

.7 Structural members shall not be cut without the consent of the Structural Engineer. For all necessary cutting, channelling, core drilling, sleeving etc., the Electrical Subcontractor shall provide their own forces and necessary equipment required to complete the electrical installation.

.8 All floor mounted electrical equipment such as boards shall be mounted on 4" (100mm) high concrete pads supplied and installed by this Contractor. All concrete shall be 25MPa complete with a WWF152x152-MW18.7xMW18.7 welded wire mesh installed 2" (50mm) below the surface of the concrete. Provide smooth trowel finish for all concrete surfaces. Clean and roughen existing concrete surfaces under all new pads. The concrete pads shall extend past the edges of all equipment by a minimum of 3" (75mm).

1.8 Temporary Construction Service and Construction Lighting

.1 Secure construction service from existing building distribution system.

.2 Provide construction lighting throughout to meet or exceed Occupational Health and Safety Act requirements. Lamps shall be screw-in LED.

.3 Connections to site trailers shall be at the expense of those requesting the connections.

.4 Provide ESA inspection of all temporary services.

.5 Maintain all electrical connections and lighting throughout the construction period.

.6 Remove all electrical services at project completion.

1.9 Continuity of Services

.1 Service and distribution system power interruptions shall be kept to an absolute minimum.

a. Power interruptions must be coordinated with the Owner and all other trades by the Electrical Subcontractor.
b. Written application for electrical interruptions must be received from the Contractor indicating the date, time and estimated duration of the interruption.
c. Application for approval of the power interruptions must be submitted to the Owner and Consultant at least two weeks prior to the requested shutdown date.
d. Once work starts, there must be planned activity toward completion every working day following the first power outage.

.2 All service work to be performed shall be coordinated to be performed during regular business hours to avoid premium time charges.

.3 No Electrical work of any description will be permitted during normal school hours in areas inside the building that are normally accessible to students.

.4 All barricades as required shall be by the Contractor.

.5 All work shall be coordinated so that there is complete and continuous life safety protection throughout the entire facility (fire alarm and detection, emergency and exit lighting). System down times shall be kept to an absolute minimum.

.6 Access control, intrusion detection, fire alarm and detection, and emergency lighting systems must be operational at all times when the contractor is not physically on site. Failure to keep these safety features operational may result in the contractor performing after-hours and weekend fire watch at their own cost.

.7 At times when the fire alarm and detection system must be in a non-functional state, the following procedure shall be followed:

a. Contact the monitoring company to inform them of the shutdown.
b. Contact the local fire department to inform them of the shutdown.
c. Establish an alternate source of alarm, i.e., telephone, siren, etc.
d. Carefully monitor all high risk fire areas such as kitchens and mechanical rooms.
e. Ensure all building occupants are aware of the shutdown, the alternate source of alarm, and the time at which the system will be back on line.

.8 All necessary system interruptions shall occur at a time suitable to the Owner and may be required to be at times that the building is not occupied or outside of regular business hours.

.9 If overtime work or temporary wiring provisions are required to maintain services as required herein such work shall be included in the bid.

1.10 Demolition

.1 Existing lighting shall remain for construction purposes. Provide temporary support for existing fixtures to permit demolition. Ensure that there is adequate lighting for construction throughout the entire process.

.2 The Electrical Subcontractor shall visit the site to examine the existing conditions and make necessary allowances in the bid for removal, rerouting, relocation, and reconnecting of equipment as may be necessary for the execution and completion of this project.

.3 Wiring, conduits, etc., located in areas being altered or demolished, but feeding outlets or equipment required to remain in service shall be rerouted as required to maintain the continuity of these services, to the satisfaction of the Engineer.

.4 In areas requiring installation of new risers for roof-mounted mechanical equipment, include for relocating conduits that may interfere with new openings. Confirm exact extent of work on site prior to close of bids.

.5 Include for strapping existing conduits and cables that are not properly supported and are required to remain above ceilings. Determine exact extent of work on site.

.6 The Electrical Subcontractor shall provide adequate protection to existing equipment throughout the project and particularly where wiring, piping, equipment, etc., have become exposed to mechanical injury or moisture.

.7 Existing distribution equipment shall be permitted to be reused only as indicated on the drawings and if the existing equipment is compatible and equal to the new equipment specified.

.8 Existing equipment being reused shall be checked for proper operation. Reused equipment shall not have any sign of physical abuse or corrosion. Any knockouts removed in existing equipment being reused shall be plugged.

.9 All wiring made redundant due to demolition/renovation work shall be disconnected and removed to the nearest distribution point upstream that is not affected by demolition/renovation work. All concealed conduit made redundant due to demolition/renovation work may remain provided it does not adversely affect any new installations, unless it is noted to be removed on the drawings. All exposed conduit in finished areas made redundant due to demolition/renovation work shall be removed and the surface patched.

.10 Existing wiring devices shall not be permitted to be reused. Existing outlet boxes may be reused if in "as new" condition. Existing branch circuit wiring will only be permitted to be reused in existing non accessible walls/ceilings where the existing wiring is of adequate size, has acceptable bonding conductor and is in as new condition.

.11 Asbestos Containing Material (ACM) is not expected to be disturbed in the execution of this contract. Refer to the Owner's Designated Substances Report. However, should ACM be uncovered during the work, notify the Consultant immediately so that appropriate instruction can be given.

.12 Include the cost of retaining an owner-approved subcontractor for the abatement of all ACM within a 600mm radius of any electrical work. Refer to the Owner's Designated Substances Report.

.13 All existing panel directories, zone legends and distribution equipment identification shall be reworked to reflect any changes made by the work. All existing wiring device tags shall be replaced to reflect any changes made to the upstream distribution designations.

.14 The Electrical Subcontractor shall be responsible to ensure that all existing communications and security systems are undamaged during the course of demolition and renovations.

1.11 Disposal

.1 The Electrical Subcontractor will be responsible for the complete removal of all electrical equipment and systems to permit alterations, all as shown and noted on the plans. This includes removal of all such equipment from the site.

.2 All miscellaneous equipment being removed shall become the property of the Owner unless shown otherwise. If the Owner has no use for it, all material shall be responsibly disposed of, in a timely manner, by the subcontractor in accordance with all applicable federal, provincial and municipal acts, bylaws and regulations.

.3 All appropriate measures to the health and safety of employees and WRDSB personnel shall be observed.

.4 Care must be taken to prevent fluorescent lamps from breaking. Intact lamps must be packaged as listed below without foreign debris or objects. Lamps must not be taped together. Broken lamps to be placed into a separate sealed container.

.5 Leather Gloves, CSA approved safety glasses with side shields and respirators shall be worn. Respirators shall be CSA approved with activated carbon filters suitable for removing mercury vapours with life span indicators. In the event of a large quantity of lamps breaking or imploding suddenly, stop work and evacuate area. Don proper respiratory protection and immediately clean area. Collect bulk material using broom and place into sealed containers. Spray floor/surface area with mercury-neutralizing agent that is capable of minimizing the continual release of mercury vapours.

.6 All mercury-bearing lamps shall be packed in suitable lamp containers (rigid plastic, or other puncture resistant material), and consolidated in the secure location outlined on the drawings. Container capacity shall not exceed 100 lamps. Lamps shall not be exposed during storage. A mercury spill kit must be available and a sealable container for broken lamps. Provide a typed and signed transmittal for each transfer of lamps indicating the quantity, type (length) of lamps, as well as the date of transfer.

1.12 Shop Drawings

.1 The Electrical Subcontractor shall submit Shop Drawings to the Project Manager and/or Engineer for review. They shall show in detail the design, construction and performance of all apparatus.

.2 Shop Drawings shall be submitted electronically in editable Portable Document Format (.PDF). Hard copy (paper) format Shop Drawings shall not be processed and shall be recycled.

.3 Submissions shall be made in a timely manner after award of the contract. The first Application for Payment may not be approved unless all Shop Drawings have been received.

.4 The Engineer's and/or Project Manager's review of Shop Drawings and manufacturer's specifications is general and is not intended to serve as the final check. It shall not relieve the Contractor from responsibility for errors.

.5 Before submission, the subcontractor shall check all Shop Drawings for accuracy of details, dimensions etc. Do not proceed with work on any item for which shop drawing review has not been performed by the Engineer.

.6 Any deviations whatsoever from the materials and methods specified herein must be clearly outlined in writing and such an outline must accompany the Shop Drawings of the proposed deviation.

.7 All Shop Drawings shall be arranged so that all drawings of a particular system are in one file and are in logical order. Shop Drawings that are submitted individually or are not arranged by system shall be rejected. For example, the lighting system Shop Drawings shall be submitted to include each fixture in order as listed in the "LIGHTING FIXTURE SCHEDULE".

.8 Any materials that require a colour selection shall have colour samples submitted for Architect review and acceptance. Arbitrary colour selection by the supplier is not acceptable. Any item for which a formal colour selection is not submitted and approved will not be permitted on site.

.9 Shop Drawings outlining all components shall be submitted for the following:

a. Power distribution equipment including the following:
   i. Boards.
   ii. Panels.
   iii. Breakers in Panel SE.
b. Lighting fixtures.
c. Emergency lighting and exit signage.
d. Lighting controls.
e. Fire alarm and detection components.
f. Integrated Testing Plan for fire protection and life safety systems.
g. Wiring devices (refer to Section below).
h. Fire stopping systems.
i. Electric heat trace cable.
j. Audio/video system.
k. Assistive listening system.
l. Public address components.
m. Intrusion alarm components.

1.13 Use of Electronic Files

.1 A waiver must be executed prior to release of any electronic files or digital data.

.2 Electronic documentation for release may consist of drawing files in formats such as Portable Document Format (.PDF), AutoCAD (.DWG), or Revit (.RVT). Specifications, details, schedules, legends, etc. shall generally not be released.

.3 Electronic documents shall be used only for the specific use outlined in the waiver. The recipient may use this data for this purpose, at their own risk.

.4 Copyright and ownership of the data are not transferred to the recipient, nor to any other party. The design professional and/or owner retain all rights to the data.

.5 Data delivered in electronic form may vary from that contained on copies of previous issues. This information is not guaranteed to be accurate. The method of data transfer cannot be guaranteed to be error free, or compatible with the recipient's hardware, software, or systems. Contractors and subcontractors are not relieved of their normal responsibilities to independently check, coordinate, and verify information and dimensions, and to familiarize themselves thoroughly with the project. The documents may have been changed or amended by addendums, bulletins, supplemental instructions, shop drawings, other documents, meetings, and understandings not represented on these files.

.6 The electronic files shall not be used as a substitute for the contract documents. The author offers no warranty or guarantee, express, implied, or statutory as to the accuracy, reliability, suitability, completeness or fitness of this data for a particular purpose. The company in receipt of these files agrees to the fullest extent permitted by law, to defend, indemnify, and hold the author, their directors, officers, partners, employees, harmless from all losses, claims, liabilities, injuries, damages, and expenses, including attorneys' fees and costs of defense, arising out of the use, misuse, misapplication, or misinterpretation of this data.

.7 The recipient will not distribute the data to any other firm or individual. Redistribution and copying of the digital data without written authorization from the author writing is prohibited.

1.14 As-Built Drawings for WRDSB remove references to Record Drawings

.1 The Contractor shall provide redline drawings that accurately record the location of all outlets and conduit runs etc., and all circuiting of devices, as installed on site.

.2 The Consultant shall provide, at no cost, AutoCAD drawing files incorporating Changes and Instructions.

.3 Prior to Substantial Performance of the work, the Contractor shall edit the electronic files to provide AutoCAD as-built drawings that incorporate all redline information. Associated costs shall be carried in the bid.

1.15 Closeout Documentation

.1 Upon Ready-for-Takeover, the Contractor shall submit a Maintenance and Instruction Manual as well as as-built drawings. Submit two paper hard copies in a three-ring binder, and one .PDF electronic copy on a suitably sized USB thumb drive. Each manual shall contain one copy of the following:

a. Shop Drawings (revised as reviewed by the Engineer).
b. Megger Test Results.
c. Updated panel directories.
d. ESA Final Inspection Certificate.
e. Fire Alarm System Verification Report(s).
f. Integrated Testing Report for fire protection and life safety systems.
g. Emergency Lighting and Exit Sign Test Report.
h. Lighting Control System operating Instructions.
i. Written Guarantee (Warranty).
j. Sign back of the latest Site Review Report to confirm completion.

.2 Include for updating the Owner's Continuous Safety Services (CSS) ESA log book for all electrical work.

1.16 Testing

.1 At the date when Ready-for-Takeover has been attained, the Electrical Subcontractor shall provide acceptance tests to demonstrate that the equipment and systems actually meet the specified requirements. Tests may be conducted as soon as conditions permit. These shall include but shall not be limited to the following:

a. Lighting system control.
b. Emergency lighting function.
c. 3000VDC Megger tests on all XLPE insulated feeders, 60A and larger, 15s duration.
d. 1000VDC Megger tests on all PVC insulated feeders, 60A and larger, 15s duration.
e. Fire alarm and detection system function.
f. Voltage drop measurements.
g. Proper phase rotation.
h. Existing communications and security equipment and associated cabling.

.2 Concurrently, written approvals or acceptances by local authorities shall be presented. In testing, vary loads to illustrate start-up, sequence, normal shut down and simulate emergency conditions. Final tests may be conducted in the presence of the Consultant.

1.17 Training and Demonstrations

.1 The Electrical Subcontractor shall arrange for onsite instruction and training to the Owner on the operation and maintenance of the following:

a. Lighting control system.
b. Electric heating control.
c. Fire alarm and detection system.

.2 All such training sessions shall be video recorded by the Contractor. Media to be handed over to the Owner upon project completion.

.3 Provide for a minimum of two training sessions of four hours each with the Owner.

.4 Demonstration of remaining systems shall be covered under Allowances.

1.18 Commissioning

.1 The Electrical Subcontractor shall retain the services of an Integrated Testing Coordinator (ITC) for all systems that are designed to operate together to achieve an overall fire protection and life safety objective, in accordance with OBC 3.2.10.

.2 Refer to Division 01 for additional commissioning details.

1.19 Warranty

.1 The electrical trade shall furnish a written guarantee stating that all work executed under this contract will be free from defects of workmanship and materials for a period of one (1) year from the date when Ready-for-Takeover has been attained. The period shall in no way supplement any other warranty of a longer period.

.2 The Electrical Subcontractor will at their own expense, repair and replace all such defective work and other work damaged thereby which fails or becomes defective during the term of the warranty provided that such failure is not caused by improper use.

.3 Refer to the Division 01 specifications for additional warranty details.

.4 Include for completion of the WRDSB Project Warranty Card prior to Substantial Performance of the work.

1.20 Electrical Equipment Approved Equals

.1 Unless specifically stated otherwise, this project has been designed based on the first named manufacturer of each section in the "ALTERNATE MANUFACTURERS LIST" or that specifically listed in the schedules. If the Electrical Subcontractor chooses to use a manufacturer other than the first named manufacturer, it will be their responsibility to ensure that the alternate is equal in all respects to that of the first named manufacturer. The Engineer reserves the right to approve or reject any alternate based upon an evaluation of the equipment proposed. If only one manufacturer is listed then only that manufacturer shall be acceptable.

1.21 Alternate Manufacturers List

.1 Distribution Equipment

a. Eaton
b. Schneider Electric (Square D)
c. Siemens

.2 Switches, Receptacles and Wiring Devices

a. Hubbell
b. Eaton Wiring Devices
c. Pass and Seymour
d. Leviton

.3 Lighting Controls

a. Acuity
b. Lutron
c. Hubbell
d. Cooper Lighting Solutions
e. Wattstopper

.4 Support Channels, Cable Tray and Hangers

a. Cooper (B-Line)
b. Hubbell
c. Unistrut
d. Canstrut
e. Caddy (Erico)
f. T.J. Cope (Tyco)

.5 Surface Raceway

a. Hubbell
b. Wiremold
c. Panduit

.6 Fire Stopping

a. 3M
b. Hilti
c. AD Firebarrier
d. STI

.7 Lighting Fixtures (Luminaires)

a. Refer to "LIGHTING FIXTURE SCHEDULE"
b. Lithonia
c. Hubbell
d. Signify (Cooper/Philips)

.8 Emergency Lighting and Exit Signage

a. Refer to “LIGHTING FIXTURE SCHEDULE”
b. Stanpro
c. BeLuce
d. AimLite
e. Emergi-Lite/Ready-Lite/Lumacell (Thomas & Betts)
f. Dual-Lite (Hubbell)

.9 Fire Alarm and Detection

a. Edwards

.10 Electric Heat Trace Cable

a. nVent Thermal Management (Raychem, Nuheat, Pentair, Pyrotenax)
b. Chromalox
c. Serge Baril
d. Thermon (3M)
e. Drexan

1.22 Access Doors

.1 Supply access doors to the Contractor for installation for all concealed electrical equipment requiring accessibility for service and maintenance such as junction boxes, pull boxes, relay enclosures, controls, etc. All doors shall be a minimum size of 8" x 8" (200mm x 200mm) and a minimum size of 24" x 18" (600mm x 450mm) where human access is required unless otherwise noted and shall be complete with positive locking self-opening screwdriver lock. The exact size of all access doors shall be as recommended by the manufacturer to suit the application.

1.23 Equipment Supplied By Others

.1 The Electrical Subcontractor is to supply all wiring, disconnect switches, motor starters, etc., for all Owner-supplied and mechanical equipment, unless noted otherwise. Detailed equipment information is given on drawings "WIRING FOR EQUIPMENT SCHEDULE".

.2 Coordinate exact electrical requirements for all equipment with Shop Drawings and actual nameplate data. Revise electrical requirements to suit.

1.24 Allowances

.1 Refer to Section 01 21 00 for allowance details.

.2 Any ESA inspection charges shall be included in the project cost and shall be paid for by the Contractor.

1.25 Provisional, Itemized, Alternate, Separate Prices and Unit Rates

.1 Refer to Bid Form for details.

1.26 Substantial Performance Certificate

.1 Before the Contractor can make application for a Certificate of Substantial Performance of the work, the Electrical Subcontractor will be required to provide the following as detailed within this section:

a. Maintenance and Instruction Manuals.
b. As-Built drawings.
c. Testing.
d. Commissioning.
e. Training and Demonstrations.

1.27 Contractor's Liability Insurance

.1 The successful bidder is to maintain adequate insurance as specified by the Owner's Standard Form of Contract. This insurance is to firmly protect both himself and the Owner from public liability claims and property damage, and all claims under the Workman's Compensation Act. Evidence of insurance coverage shall be filed and approved.

1.28 Payment Certification

.1 Submit monthly draws to the consultant for review and certification. Draws shall provide a complete breakdown of project in a manner acceptable to the consultant. Submit sample Application for Payment and a proper invoice template to the consultant four weeks prior to first draw for review.

1.29 Extras and Credits

.1 Only extras and credits approved by the Electrical Engineer or their representative will be allowed and must be submitted for approval before such work commences. They shall be priced individually with a complete breakdown clearly indicating labour costs, material cost, mark-up and taxes. Labour rates and material costs for extras and credits shall be identical. Material shall be valued at current trade prices incorporating all discounts. Only the net difference between an extra and a credit will subject to overhead and profit mark-up.

## 2. 26 05 14 EQUIPMENT IDENTIFICATION

2.1 General

.1 Provide all nameplates for equipment such as panels, starters, disconnect switches, etc.

.2 Nameplates shall indicate Equipment Name, Source and Electrical characteristics (ampacity, voltage, phases, number of conductors), i.e., Panel “12B” fed from Board “12S”, 100A, 120/208V, 3-phase, 4-wire.

.3 All equipment/circuits/devices that reference room names or numbers shall be modified as required to reflect the finalized Owner designated room names/numbers. Do not duplicate the room numbers indicated on the drawings.

.4 Nameplates shall be a stock white lamacoid, with black lettering and with beveled edges. Letters shall have a minimum 0.06", (1.5mm) stroke.

.5 Nameplate engraving shall be as follows:

a. Electrical equipment name: 0.5", (13mm) high.
b. Electrical equipment characteristics: 0.25", (6mm) high.

.6 Equipment nameplates shall be mechanically fastened with tamperproof screws. Equipment nameplates that are fastened with adhesives shall not be acceptable.

.7 Provide clear adhesive labeling with black letters for wiring devices such as receptacles, switches, speed controllers, etc. Labels shall indicate the circuit(s) that serve the device, i.e., “32B41".

.8 Provide all warning signs and labels as required by the ESA.

.9 Provide typed directory cards in all new and revised distribution panels. Hand written directory cards are not acceptable.

.10 Provide preprinted slip on conductor identification tags for all conductors as they enter electrical enclosures, equipment, and outlet boxes (switches, receptacles, light fixtures, etc). Tags shall be Thomas and Betts “EZCode” SMC series or approved alternate. Cloth or vinyl markers are not acceptable.

.11 All empty or spare conduit shall be identified with black indelible marker.

.12 All junction boxes shall be identified with black indelible marker showing the systems with which they are associated, i.e., lighting, receptacles, fire alarm and detection, etc. Where boxes are exposed, identification shall be on the inside of the cover.

.13 Colour code outlet boxes, pull boxes and junction boxes by applying a small dab of paint to the inside and outside of each item during installation. Use the following paint colour code:

| | | |
|---|---|---|
| a. | White: | 208/120V Power. |
| b. | Yellow: | 600/347V Power. |
| c. | Red: | Fire alarm and any other emergency control systems. |

.14 Repaint or refinish all damaged factory applied finishes.

## 3. 26 05 21 RACEWAYS, WIRE AND CABLE

3.1 General

.1 All wiring in noncombustible areas, unless otherwise noted, to be CSA approved soft copper, type T90/TWN75 in conduit, unless otherwise required by the Electrical Code for specific areas or environmental conditions.

.2 Only in combustible construction shall branch wiring circuits utilizing standard combustible construction wiring practices (i.e., NMD90, NMWU, types of cables) be permitted. The use of NMD90 types of wiring in metal studs shall not be permitted under any circumstances. NMD-90 shall not permitted in the ceiling spaces being used as a return air plenum.

.3 Maximum voltage drop at most remote outlet not to exceed 3% in accordance with OESC #8-102. The minimum wire size shall be #12 AWG.

.4 All low voltage (0-10V) dimming cabling shall be CSA approved soft copper, type T90 installed in raceway or metal armour. The minimum wire size shall be #16 AWG. Wiring colours to be violet and grey. Insulation rating shall be equivalent to the phase conductors serving the lighting fixtures. A cable that combines power conductors with control conductors under one armour may be used.

.5 There shall be one neutral conductor for each phase conductor in a branch circuit. Sharing of neutrals shall not be permitted.

.6 Where conductor cables are installed in free air, they shall be spaced minimum one cable diameter apart based upon the largest cable.

.7 Armored cable (BX) may be used in metal stud partition walls, in concrete block walls, and for final drops to fixtures in accessible ceiling spaces. Cable length shall not exceed 3.1m (120") horizontally in accessible ceilings. BX cable shall under no circumstances be run exposed.

.8 EMT shall be used in dry concrete slabs and for interior exposed surface applications (where permitted). Surface mounted EMT may be permitted on existing finished walls only in areas where there is existing surface mounted EMT within 24" (600mm).

.9 Rigid PVC (IPEX Scepter or approved alternate) raceways shall be used in or below concrete slabs, for direct burial, or exposed exterior surface applications. Conduit shall be FT4 rated.

.10 Raceways in concrete block walls shall be installed vertically within in block cavities. Horizontal installations shall not be permitted.

.11 Rigid Threaded Aluminum (RTA) conduit shall be used for exterior exposed surface applications. Conduit to be complete with weatherproof threaded ends and couplings.

.12 Provide hot-galvanized, colour-coded EMT to identify branch circuit types. Conduit shall be by Atkore/Tyco or approved alternate. Use the following colour coding:

a. Red: Fire alarm and any other emergency control systems.

.13 All conduit and wiring is to be concealed in all finished areas unless otherwise approved. EMT conduit shall be permitted above and below surface mounted panels.

.14 In areas with exposed ceilings, conduit and wiring shall be run concealed if possible. If not possible, conduits shall be EMT, surface mounted or suspended to suit the application.

.15 Exposed or concealed conduits above ceilings shall be run in straight lines parallel to building structure. Diagonal runs will not be permitted.

.16 Provide 9mm (3/8") polypropylene pull rope and pull tape in all empty conduits 53mm (2") and larger.

.17 Provide nylon pull tape in all empty conduits smaller than 53mm (2").

.18 Securely fasten pull rope/tape in empty conduits/raceways at each end.

.19 Pull tape shall be Neptco WP900P, 0.5" (13mm) wide, 900lb (409kg) pull strength, lubricated, with sequential metric distance markings.

.20 Conduits and cables shall not enter an exit stair shaft, unless they serve devices/fixtures within the exit stair, i.e., route all conduits and cables around the stair to maintain the integrity of the exit.

.21 Install flexible conduit section in all locations on either side of an expansion joint where rigid conduit is fastened to structure.

.22 All wiring serving rotating or vibrating equipment shall be stranded and shall be in a flexible raceway. Raceway length shall not exceed 1.5m (60").

.23 Connections to equipment shall be flexible and of sufficient length to permit the equipment to be moved for servicing or housekeeping.

.24 Coordinate with HVAC trades to run feeders to rooftop equipment through the curb or alongside refrigerant lines. Separate roof penetrations/cones for feeders shall not be permitted.

.25 Provide strain relief grips and bus drop grips for all hanging cables and flexible metallic conduit. Grips shall be stainless steel mesh, corrosion resistant with suitable connectors. Grips shall be Hubbell Kellems or approved alternate.

.26 Standard trade conduit connectors and fittings are acceptable unless noted on the drawings or specification to be a specific manufacturer trade name, catalogue no. or series.

.27 In general, all outlet boxes shall be metal. The use of nonmetallic boxes shall not be permitted.

.28 Outlet boxes located in areas normally accessible to building occupants shall have no exposed knockouts. Support all boxes independently of connecting conduits.

.29 In areas where it is not possible to run conduits concealed in existing structures, surface mounted raceways shall be permitted. The Electrical Subcontractor shall verify the proposed locations of all surface mounted conduits with the Engineer prior to installation.

.30 Where permitted, all surface mounted raceways shall be "Wiremold" series 2000, 500, or 700, as required to match the quantity and size of conductors. Surface mounted raceways shall be complete with all "Wiremold" fittings and accessories (couplings, bushings, clips, straps, elbows, outlet boxes etc.) to form a complete installation.

.31 All exposed surface mounted raceways shall be painted by the Electrical Subcontractor to match the colour of the surface upon which it is installed if the surface is not specified to be painted by general trades.

.32 All wiring situated in a return air plenum shall be totally enclosed in a non-combustible raceways or shall be FT6-rated (also known as Communications Media Plenum, or CMP).

.33 All conduits and raceway systems shall be provided complete with plastic bushings on both ends.

3.2 Fire stopping

.1 Provide fire stop sealant / devices of a type to suit piping, building construction, opening size, etc. Supply and install according to manufacturers detailed installation instructions.

.2 Combustible outlet boxes recessed in an assembly required to have a fire-resistance rating, shall be sealed at the penetration by a firestop that has an FT rating not less than the fire-resistance rating for the separation.

.3 Noncombustible outlet boxes recessed in vertical fire separation forming part of an assembly required to have a fire-resistance rating shall be fire stopped to match the rating of the assembly. Exceptions are permitted only as follows:

a. The boxes do not exceed 0.016m² in area, and do not exceed an aggregate area of 0.065m² in any 9.3m² of surface area.
b. The annular space between the membrane and noncombustible electrical outlet boxes does not exceed 3mm.

.4 Firestop behind panels and enclosures recessed in fire rated separations using 3M Interam Endothermic Mat E-5A-4.

.5 Firestop behind outlet boxes recessed in fire rated separations using Hilti CP617 or CFS-PA Firestop Putty Pads.

.6 Coordinate with General Trades to be consistent with the fire stopping manufacturer throughout the project.

## 4. 26 27 26 WIRING DEVICES

4.1 General

.1 Provide all wiring devices and their associated fittings as indicated in the "Wiring Device Schedule" in this specification or as specifically noted on the drawings.

.2 Wiring devices shall be black unless noted otherwise. Verify colour with Owner prior to ordering and adjust if required.

.3 Wiring devices for general purpose shall be of heavy-duty specification grade.

.4 Devices shall be manufactured and tested in accordance with CSA and EEMAC standards. Attachment plugs and receptacles to conform to CSA configurations.

.5 In areas being renovated where existing devices are to remain, all new devices shall be coloured to match existing.

.6 All 15A and 20A receptacles (CSA 5-15R and 5-20R) shall be tamper resistant.

4.2 Wiring Device Schedule

.1 Hubbell or Acuity serves as the basis for this specification. If the Contractor chooses to use an Approved Alternate manufacturer, as listed above, it will be their responsibility to ensure that the alternate is equal in all respects to that named herein. The Engineer reserves the right to approve or reject any alternate based upon an evaluation of the equipment/device proposed.

.2 120V Switches

- a. Decorator Style - 20A
  - i. DS120, DS320, DS420

.3 120V Receptacles

- a. Ground Fault Circuit Interrupter (Weather and Tamper Resistant) - 15A
  - i. GFTWRST15
- b. Ground Fault Circuit Interrupter (Weather and Tamper Resistant) - 20A
  - i. GFTWRST20
- c. Decorator Style, Tamper Resistant - 15A
  - i. DR15xTR
- d. Decorator Style, Tamper Resistant - 20A
  - i. DR20xTR

.4 250V Devices

- a. Range Receptacles - 50A
  - i. HBL9450

.5 Power Distribution Unit (PDU)s

- a. PDUs shall feature a minimum of twenty-four 5-20R outlets.

i. Eaton Tripp Lite Series, Model No. PDUV20-60 for 20A circuits.

b. Mount vertically to the wall adjacent to the AV equipment. Coil and tie-wrap extra cord.

.6 Wood, Multi-Service, Rectangular, Recessed Floor Boxes as manufactured by Hubbell:

a. 1-AFB2G25 stamped steel floor box. Two gang.
b. 1-2GAFBCVRBKC black die cast cover with insert.
c. 1-FBMPREC decora face plate. Provide duplex receptacle.
d. 1-FBMPREC decora face plate. Confirm with AV supplier prior to order.
e. Provide conduit as indicated elsewhere in this specification.

.7 Clocks

a. Typical 300mm clock shall be American Time Model No. E56BADD304BP.
b. All shall feature round, high impact plastic case with shatter-resistant safety crystal and bold black numerals and minutes markers on a non-yellowing white dial. Provide four AA alkaline batteries for each clock.
c. Include for custom logo.

.8 Control Relays (BAS system, HVAC system)

a. Relays shall be Functional Devices Inc, type RIB, SPDT, contacts rating to suit connected load (minimum 10A at 120V), Coil voltage: 10-30VAC/DC or 120VAC, LED on indicator, open/closed/auto manual over ride switch. Relays shall have adequate number of poles to suit the loads being controlled.

.9 Wall Switch Occupancy/Vacancy Sensors

a. Sensor Switch Model No. WSXA PDT, microphonics and passive infrared.
b. Sensor Switch Model No. WSXA PDT MWO for multi-location control.
c. The sensor shall operate at 120V. No control unit required.
d. Rated 800W at 120V.
e. Single gang box.
f. 180 degree coverage.
g. Effective range for small hand movements: 6m (20").
h. Sensors may be wired in parallel to allow coverage of larger areas.
i. Sensors shall be wall mounted, located and adjusted per manufacturer's instructions to provide detection within the defined area.
j. Coordinate desired time delay with the Owner. Set to minimum 20 minute operation.
k. Colour to match wiring devices.
l. Occupancy sensors shall be field programmed for auto ON, auto OFF.
m. Vacancy sensors shall be field programmed for manual ON, auto OFF.

.10 Cabled Lighting Controls for Dimming Environments (0-10V)

a. Small motion occupancy sensor nCM PDT 9 RJB.
b. Large motion occupancy sensor nCM PDT 10 RJB.
c. Wall mounted occupancy sensor nWV PDT 16. Provide mounting kits and guards where indicated.
d. Single channel dimmer with on/off and raise/lower nPODMA DX.

e. Two channel dimmer with on/off and raise/lower nPODMA 2P DX.
f. Four channel dimmer with on/off and raise/lower nPODMA 4P DX.
g. Colour to match wiring devices.
h. Bridge kit nBRG 8.
i. Utility power/relay pack nPP16D EFP.
j. Emergency power/relay pack nPP16D ER EFP.
k. External signal control nIO 1S.
l. Provide non-booted CAT5e connections.
m. Provide quantity of bridges, power/relay packs as required.
n. All luminaires shall come on automatically via occupancy sensor(s) to 50% illumination. Manual control of light levels by the dimmer after detection of occupancy.
o. All luminaires to automatically dim to off 20 minutes after no occupancy is detected.
p. Sensors shall be located and adjusted per manufacturer's instructions to provide detection within the defined area.
q. Manufacturer shall commission and test the entire system. Provide verification report.

.11 Wireless Lighting Controls for Dimming Environments (0-10V)

a. Single channel dimmer with on/off and raise/lower rPODU DX G2. Single CR2032 coin cell battery included and rated for ten years of use.
b. Colour to match wiring devices.
c. Power/relay pack rPP20 D EFP G2. Provide quantity of power/relay packs as required.
d. All luminaires shall come on automatically via occupancy sensor(s) to 50% illumination. Manual control of light levels by the dimmer after detection of occupancy.
e. All luminaires to automatically dim to off 20 minutes after no occupancy is detected.
f. Sensors shall be located and adjusted per manufacturer's instructions to provide detection within the defined area.
g. Adjust radio frequency channels as required and group devices together during commissioning to prevent interference from devices in nearby spaces.
h. Manufacturer shall commission and test the entire system. Provide verification report.

.12 Cover plates

a. Plates shall be specification grade type 304 brushed stainless steel.
b. Surface Exterior While-In-Use Weatherproof Covers:
    i. Die-cast metal construction, gasketed.
    ii. Lockable open or closed.
    iii. Hubbell (Taymac) MX3300.
    iv. Use only for mechanical equipment or other areas where recessed installation is not possible.
c. Sheet steel utility box cover for wiring devices installed in surface-mounted utility boxes.

4.3 Execution

.1 All wiring devices to be flush mounted in all finished areas.

.2 All switches shall be rated 20A minimum.

.3 Where GFCI devices are shown on the drawings, an actual GFCI device must be installed. Feed through type arrangements are not acceptable.

.4 Receptacles connected to 20A branch circuits shall be CSA 5-20R configuration.

.5 Install boxes so as to be accessible after building is complete, set to be flush with finished lines of building structure, where recessed, and lined and leveled where surface mounted.

.6 Coordinate device installations in Dressing Rooms to suit existing mirrors.

.7 Coordinate device installations associated with the audio-video upgrade with Sherwood Systems.

.8 Switch and receptacle mounting heights shall be coordinated with Architectural details and shall be adjusted, if required to the satisfaction of the Architect/Engineer at no additional cost to Owner.

.9 Where outlets occur in exterior walls, the electrical trade shall ensure that there is insulation and a vapour barrier behind the outlet box to prevent condensation through the boxes.

.10 Receptacles for maintenance of HVAC and similar equipment shall be mounted on the exterior of the equipment.

.11 Outlet boxes on opposite sides of a vertical fire separation having a fire-resistance rating shall be separated by one of the following:

a. A horizontal distance of not less than 600 mm,
b. A suitable fire block material, or,
c. Firestop installed on each outlet box that has an FT rating not less than the fire-resistance rating of the fire separation.

.12 Install switches with handle in the "Up" position when the switch is in the "On" position.

.13 Outlets located in masonry, textured or otherwise uneven wall/surfaces shall be mounted such that the cover plate is flush with the wall/surface. Grind or modify the face of the material so that the cover plate fits flush. The cover plate shall have an opening no larger than 1/8" (3.0mm) from the surface. Caulking shall not be permitted as a method of filling gaps larger than 1/8" (3.0mm).

.14 Install switches and/or receptacles in ganged type outlet boxes, with matching wall plate when more than one switch or receptacle is required in one location.

.15 Remove plastic protective film on stainless steel plates only after painting and other work has been completed in that area.

.16 Do not use cover plates designed for flush outlet boxes on surface mounted boxes. Do not use outlet boxes designed for flush mounting in surface mount applications.

.17 Install decorator style devices in all areas of the building.

.18 Locate BAS system relays in location to suit the mechanical trades.

.19 Locate power connections to Mechanical Power Supplies (MPS) in accessible location.

.20 All low voltage lighting controls shall be provided with an appropriately sized outlet box and a 0.5" (16mm) conduit to the accessible ceiling space. In cases where the ceilings are not accessible, extend conduit to within 6.0" (150mm) of the nearest associated power/relay pack.

.21 Adjust floor boxes so that they are perfectly flush with top of adjacent flooring.

.22 Unless specifically stated otherwise, rooms with ceiling mounted occupancy sensors shall control all lighting in the room. If additional local controls are shown, they shall also be controlled by the occupancy sensor.

4.4 Mounting Heights

.1 Mounting heights to centre of box above finished floor (AFF), unless noted otherwise:

a. 5", (125mm): range outlets, flush mounted.
b. 18", (450mm): receptacles, communications outlets, microphone jacks.
c. 30", (750mm): exterior receptacles above finished grade/roof.
d. 41.5", (1050mm): light controls, push buttons, public address call switches, power door push buttons, proximity readers.
    i. Minimum height is 36" (900mm), maximum height is 43" (1100mm).
    ii. At locations with multiple power door operators, mount minimum 180mm horizontally apart on centre. Mount minimum 24" (600mm) and maximum 60" (1500mm) beyond door swing.
e. 47", (1200mm): fire alarm manual stations, thermostats, end of line devices. Situate all fire alarm manual stations such that there is a minimum of 2" (50mm) of flat wall space on each side, and a minimum of 4" (100mm) of flat wall space above and below to allow for the installation of a future manual station protective guard.
f. 92", (2340mm): fire alarm visual and audible devices without silencing means. Install at least 6", (150mm) below ceiling to the top edge of the device. Visual devices shall not be lower than 78", (2000mm).
g. 96", (2440mm): wall speakers.
h. 126", (3200mm) or maximum height: wall mounted occupancy sensors.
i. Devices above counter shall be 4" above millwork/back splash. Coordinate with Architectural details.
j. Devices in kick space shall be mounted horizontally. Coordinate with Architectural details.
k. Fire alarm device modules and zone isolators shall be recessed in walls at 92" (2.34m) AFF or 6", (150mm) clear below ceiling, whichever is lowest. Clearly indicate location of modules on as-built drawings. Verify locations on site with Architect.

.2 Lighting controls shall be located within 150mm (6") from latch side of the door where possible. Do not mount on hinge side of door or behind door swing.

.3 Where devices are to be mounted in new block walls, outlet boxes shall be cut into the top or bottom of the nearest block course that is lower than the height specified.

.4 Where a conflict of device mounting occurs, the Contractor shall contact the Engineer for clarification.

## 5. 26 24 02 DISTRIBUTION EQUIPMENT

### 5.1 General

.1 The Electrical subcontractor shall provide the distribution equipment required for the complete installation.

.2 All distribution equipment shall be complete with drip shields suitable for use in a sprinklered environment.

.3 Equipment shall be delivered to the site and shall be protected all around with a plastic covering. Additional onsite protection must be provided to keep the equipment protected from the elements and other trades. If there is any sign of rusting or corrosion or severe physical abuse on the equipment, the affected parts shall be replaced at no cost to the Owner.

.4 All distribution equipment shall have tested and approved series ratings for fault currents and shall have identifying labels.

.5 All distribution equipment shall have lugs with termination temperatures rated at 75 deg C minimum.

### 5.2 Panels

.1 Provide surface or recessed panels of type, voltage, ampere capacity, number of poles, branch circuit, capacity, etc., as indicated.

.2 All panel bus bars shall be tin plated aluminum unless specifically noted otherwise.

.3 Panels shall have a hinged door with flush lock for access only to the breakers.

.4 Panel interior shall be centered within the tub.

.5 Balance all panels to give as near as possible equal current in all phases under full load conditions.

.6 Provide 200% rated neutral lugs where outlined.

.7 Provide a minimum of two 1.5", (41mm) spare conduits from each recessed panel to the nearest accessible ceiling space or utility space. Cap conduits and label as “spare.”

### 5.3 Load Centers

.1 Load centers shall not be permitted for use on this project.

### 5.4 Disconnect Switches

.1 Disconnect switches shall have visible blades in the off position, quick make, quick break mechanism and shall have steel reinforced clips. Fuses shall be easily removable when the switch is in the off position. All switches shall have ample gutter space for top or bottom wiring.

.2 Provision for padlocking in on-off switch position by one lock.

.3 Switch mechanically interlocked door with front accessible defeat to prevent opening when handle in ON position.

.4 Provide relocatable fuse holders suitable for use without adaptors, for type and size of fuse indicated.

.5 Fuse holders shall be suitable for Class J.

.6 Switches with pull out style contact devices shall not be permitted.

.7 Coordinate with HVAC equipment to procure a suitably sized disconnect switch for the rooftop condensing units.

5.5 Fuses and Breakers

.1 Fuses shall be Class J (600A and under) as appropriate dual element time delay as manufactured by Bussmann unless otherwise specified. Fuse rating shall be as noted or as required for proper protection. Fuses shall be rated for 200kAIC minimum.

.2 Unless indicated otherwise, breakers shall be moulded case type, thermal-magnetic, ambient temperature compensated, of the frame size and with trip settings as indicated on the drawings. Breakers mounted in panels shall be bolt-on type.

.3 All breakers identified with “ET”, shall be electronic, with modular plug, fully adjustable trip and time settings, LSI.

.4 All breakers shall have tested and approved series ratings for fault current levels indicated and shall have identifying labels.

.5 Unless otherwise noted all breakers shall be rated minimum 10kA symmetrical interrupting capacity at 208V and 25kA at 600V.

.6 New breakers in Panel SE shall be by Schneider as follows:

a. Model LJA36400U31X, 400A 25kA@600V LI adjustable.
b. Model JJA36250, 250A 25kA@600V thermal mag 80%.

.7 All breakers indicated as “spare” shall be installed in the “OFF” position.

.8 Breaker supplier shall allow for up to 10% of breakers to be returned and traded for equal breakers of two standard ampacity sizes higher or lower than that originally provided at no additional cost to the project.

.9 The manufacturer shall arrange breakers in panels, boards, load centres as applicable, in the order indicated on the schedules. Rearrangement of breakers on site is not recommended.

5.6 Bonding

.1 Include bonding as required by OESC, ESA Inspection Department, and as shown on drawings.

5.7 Motor Protection and Control

.1 Each starter shall include manual reset thermal overload elements, one for each power supply line, i.e., three for three-phase motors. Overloads shall be sized to suit the connected load.

.2 All starters and disconnects shall be listed as "Suitable as Motor Disconnects".

.3 All starters shall be NEMA rated with a minimum Size 0 and be rated at minimum 15A continuous current. IEC design starters shall not be permitted.

.4 Motor starters shall be rated for minimum 10kA withstand rating and shall not be less than the available fault current.

.5 Manual Motor Starters

a. Heavy duty toggle mechanism.
b. Thermal overload relay and red neon pilot light.
c. Rated to match the motor requirements.
d. In finished areas, starters shall be flush mounted with cover plates coloured to match other wiring devices. In other areas provide enclosures to suit specific application.

.6 Magnetic and Combination Starters

a. Provide combination starters complete with fused disconnect switch protection suitable for use with Class J fuses.
b. Provide two sets of normally open and normally closed extra auxiliary contacts in each starter for connection to the building automation system by the controls subcontractor.
c. Integral control voltage transformer with fused secondary, rated for min 50VA. All control wiring and devices shall function on a 120VAC control circuit unless indicated otherwise.
d. Thermal overload protection.
e. Red pilot lamp indicating starter is energized.
f. Door mount overload reset switch.

5.8 Execution

.1 Wall mounted distribution equipment shall be mounted in an approved manner. The equipment shall be mounted in a well-organized and planned arrangement.

.2 Install disconnecting means within sight and less than 9m from motor loads.

.3 Install disconnecting means within sight and less than 3m from air conditioning and refrigeration equipment.

.4 Starters and disconnect switches installed in areas that are accessible by the public shall be lockable in the on and off positions.

.5 Panels shall generally be wall mounted. Provide strut standoffs or strut frame where required if wall surface is not uniform, or where wall structural capacity is not adequate to support weight of panel.

## 6. 26 50 00 LIGHTING

6.1 General

.1 Supply and install lighting with all accessories and lamps as shown in "LIGHTING FIXTURE SCHEDULE," and as described.

.2 Submit Shop Drawings containing the following information:

a. Picture of fixture, fixture model number, fixture colour.
b. Lens data, mounting details, photometric data.
c. Fixture manufacturer (include address and telephone number).

.3 No allowance or change in fixture type will be permitted for the failure of the Electrical Subcontractor to allow sufficient time for the delivery of the fixtures when required to the site. Should the approved fixtures not arrive on time, this subcontractor shall supply and install temporary fixtures at no cost to the Owner and shall replace same with the approved fixtures when they arrive and make good all surfaces disturbed by this operation.

.4 Coordinate with Division 01 to provide new louvres/grilles for new EDA and A-series luminaires.

6.2 Solid State (LED) Lighting

.1 Quality Assurance

a. Luminaires shall be of uniform quality and appearance.
b. Manufacturers of LED luminaires shall demonstrate a suitable testing program incorporating high heat, high humidity and thermal shock test regimens to ensure system reliability and to substantiate lifetime claims.
c. The LED fixture assembly/manufacturing facility shall be ISO 9001 certified and produce product in compliance to RoHS.
d. At time of manufacture, electrical and light technical properties shall be recorded for each luminaire. At a minimum, this should include lumen output, CCT, and CRI. Each luminaire shall utilize a unique serial numbering scheme. Technical properties must be made available for a minimum of 7 years after the date of manufacture.
e. Luminaires shall be provided with a 5 year warranty covering, LEDs, drivers, paint and mechanical components.

.2 Material and specifications for each luminaire are as follows:

a. Each luminaire shall consist of an assembly that utilizes LEDs as the light source. In addition, a complete Luminaire shall consist of a housing, LED array, and electronic driver (power supply).
b. Each luminaire shall be rated for a minimum operational life of 60,000 hours of operations at an average operating time of 10.5 hours.
c. The rated operating temperature range shall be -40°C to +40°C.
d. Photometry must be compliant with IES LM-79-19 and shall be conducted at 25°C ambient temperature.
e. Each luminaire shall meet all parameters of this specification throughout the minimum operational life when operated at the average nighttime temperature.

f. The individual LEDs shall be constructed such that a catastrophic loss or the failure of one LED will not result in the loss of the entire Luminaire.
g. Luminaires shall be constructed such that LED modules may be replaced or repaired without replacement of whole Luminaire.
h. Each luminaire shall be listed with CSA or cUL under UL1598 for luminaires.

.3 Electrical Requirements

a. Maximum power consumption allowed for the Luminaire shall be determined by application. The Luminaire shall not consume power in the off state.
b. The luminaire shall operate from a 60Hz ±3Hz AC line over a voltage ranging from 108VAC to 350VAC. The fluctuations of line voltage shall have no visible effect on the luminous output.
c. The luminaire shall have a power factor of 0.90 or greater.
d. Total harmonic distortion (current and voltage) induced into an AC power line by a luminaire shall not exceed 20 percent.
e. The luminaire on-board circuitry shall include surge protection devices (SPD) to withstand high repetition noise transients as a result of utility line switching, nearby lightning strikes, and other interference.
f. The LED circuitry shall prevent visible flicker to the unaided eye over the voltage range specified above.
g. LED drivers must meet Class A emission limits referred in Federal Communications Commission (FCC) Title 47, Subpart B, Section 15 regulations concerning the emission of electronic noise.
h. Drivers shall have a Class A sound rating.

.4 Photometric Requirements

a. Optical assemblies shall have a minimum efficiency of 85% regardless of distribution type. All optical assemblies will be mounted parallel to the ground, aimed in the same direction and shall provide the same optical pattern such that catastrophic failures of individual LEDs will not constitute a loss in the distribution pattern.
b. All photometric data will be measured by the IES LM-79-19 standard and formatted per IES LM-63-19 as an electronic .ies file.
c. The illuminance shall not decrease by more than 30% over the expected operating life. The measurements shall be calibrated to standard photopic calibrations.
d. The luminaire shall have a Correlated Colour Temperature (CCT) range of 3,000K to 4,500K as indicated in the Lighting Fixture Schedule. The colour rendition index (CRI) shall be 80 or greater.
e. Exterior luminaires shall not allow more than 10 percent of the rated lumens to project above 80 degrees from vertical. The luminaire shall not allow more than 2.5 percent of the rated lumens to project above 90 degrees from vertical. Backlight and Glare ratings calculated as per IES TM-15-20.

.5 Thermal Management

a. The thermal management (of the heat generated by the LEDs) shall be of sufficient capacity to assure proper operation of the Luminaire over the expected useful life.
b. The LED manufacturer’s maximum thermal pad temperature for the expected life shall not be exceeded.

c. Thermal management shall be passive by design. The use of fans or other mechanical devices shall not be allowed.
d. The luminaire shall have a minimum heat sink surface such that LED manufacturer's maximum junction temperature is not exceeded at maximum rated ambient temperature of 40 degrees Celsius (supply Heat test).
e. The heat sink material shall be aluminum.

.6 Physical and Mechanical Requirements

a. The luminaire shall be a single, self-contained device, not requiring on-site assembly for installation. The power supply for the luminaire shall be integral to the unit.
b. The assembly and manufacturing process for the LED Luminaire shall be designed to assure all internal components are adequately supported to withstand mechanical shock and vibration from high winds and other sources.

6.3 Exit Signage

.1 New exit signs shall conform to the performance of internally lighted exit signs standards as outlined in the Ontario Electrical Safety Code.

.2 New exit signs shall conform to the visibility and symbol specifications referred to in ISO 3864-1 and ISO 7010.

.3 New exit signs shall be supplied complete with integral batteries.

.4 Refurbished exit signs shall be supplied by a battery-backed 120V source.

.5 New fixture Features

a. Running man pictoral signs. Field modify pictograms as outlined.
b. Double-sided signs shall have two pictograms.
c. White, baked powder coat finish.
d. External LED status indicator and test switch.
e. Sealed Ni-Cad batteries for emergency illumination.
f. 16 gauge steel backed with impact resistant polycarbonate face plates
g. Tamper resistant screws.

6.4 Execution

.1 Provide all fastenings, supports etc. to install in an appropriate and approved manner. Adequately support all ceiling mounted fixtures, from the building structure. Use safety chains. The requirement for independent support for fixtures may be waived only if the ceiling manufacturer provides written confirmation that the ceiling has been designed to carry the load.

.2 Fasten fixtures to studs, joists, furring channel or other structural ceiling framing with screws. Drill holes in fixtures if required for alignment to ceiling structure. Coordinate with ceiling installed to ensure sufficient structure is provided for the fixtures. Toggle bolts or drywall anchors alone is insufficient.

.3 All fixtures recessed into ceilings serving as fire-rated separations shall be approved for such use, and shall be provided with suitable enclosures. The Electrical Subcontractor shall be responsible for providing the enclosures. Suggested products may be procured from GlobalNgineering https://globalngineering.com or Tenmat https://www.tenmatusa.com

.4 Any boxes around any recessed fixture shall be constructed to provide the necessary clearances to suit the manufacturer's recommendations. The Electrical Subcontractor shall verify the necessary clearances with the manufacturer and shall pass this information to the constructor of the drywall boxes.

.5 Recessed fixtures shall not be installed in an insulated ceiling unless approved for that installation.

.6 Adjust fixture location onsite as required to avoid interference with swing of adjacent doors.

.7 Coordinate fixture installations in Dressing Rooms to suit existing mirrors.

.8 All cabling associated with lighting control system shall be CMP CAT5e green. Performance shall meet or exceed that of Nexans HyperPlus 5e Plenum Part Number 10032232.

.9 Exit signs shall be wall or ceiling mounted to suit site conditions. Wall mounted exit signs shall be mounted at 96" (2430mm) above finished floor or 12" (300mm) above doors. Exit signs may be ceiling mounted if the ceiling height does not exceed 144" (3658mm). Exit signs location and mounting arrangements shall be coordinated onsite so that the fixture is visible from the exit approach. Modify location as required to ensure visibility.

.10 Wall mounted light fixtures installed in corridors shall not protrude more than 4.0" (100mm) if any portion of the fixture is mounted below 78" (1.98m) above finished floor.

.11 Coordinate position of lighting fixtures in mechanical areas with mechanical duct work and equipment. Modify installation to suit.

.12 Suspended light fixtures in areas near ceiling fans or supply air diffusers shall be rigidly mounted, or suspended with two chains, set at an angle so as to eliminate sway.

.13 Provide an adjustable hanger system for areas requiring fine adjustment of fixture suspensions. System shall be Gripple, or approved alternate, rated for fixture mass with minimum 5:1 safety factor.

.14 The location of fixtures as shown on the drawings are approximately correct, but the Consultant reserves the right to alter the location of any number of them up to 120", (3.0m) without incurring extra costs, provided the request is made before the fixture is installed.

## 7. 26 52 13 EMERGENCY LIGHTING (UNIT EQUIPMENT)

### 7.1 General

.1 Supply and install an emergency lighting system consisting of the following, to activate and provide egress lighting in the event of a power failure:

a. Battery unit(s), AC power inverter, conduit, wiring etc.
b. Battery-backed lighting fixtures, conduit, wiring etc.

.2 Batteries to automatically recharge after normal power is restored.

.3 Provide complete working system utilizing products as outlined in "LIGHTING FIXTURE SCHEDULE."

.4 Equipment shall conform to CAN/CSA-C22.2 No. 141-10 (or latest edition).

### 7.2 Products

.1 Self-Contained

a. High quality, corrosion, flame and vandal resistant, polycarbonate housing.
b. Vandal resistant latch clips.
c. Ceiling or wall mounted. Adjust the position of the LED board for all wall mount applications to direct lighting down.
d. IP65 rating. Suitable for wet location installations.
e. Auto-test circuitry. External test switch for momentary test operation.
f. Sealed Ni-MH batteries for minimum 90 minute emergency illumination.
g. Nine year pro-rata warranty on the assembly. Ten year battery warranty.

.2 Battery Units

a. 18 gauge, ventilated steel enclosure.
b. Low gloss beige enamel corrosion resistant painted finish.
c. AC “ON” light (charging).
d. High charge light.
e. Test switch.
f. 60 cycle input, voltage as indicated, c/w fuse.
g. 120mm minimum u-ground plug and power cord for 120V systems.
h. The battery shall be long life lead calcium type (maintenance free).
i. The capacity of the battery shall be in accordance with that shown in the "LIGHTING FIXTURE SCHEDULE."
j. Battery to provide power to the fixtures for 90 minutes without dropping below ninety-one percent voltage drop.
k. Provide self-diagnostic circuitry option for units in generator rooms and rooms containing automatic transfer switches.
l. Charger to be solid state, with HI/LO charge indicator and capable of recharging in 24 hours.
m. Provide suitable mounting hardware for safe and permanent mounting of the battery.

### 7.3 Execution

.1 DC System

a. Battery pack to mount at 90", (2.3m) or above doors. Power feed for battery packs shall be mounted at 98", (2.5m) wherever practical.
b. Wall mounted heads shall be mounted at 96", (2.5m) AFF or 12", (300mm) below ceiling whichever is lowest. Verify locations on site with Architect.
c. Battery packs possessing multiple output circuits shall divide the connected load as equally as possible between all output circuits.
d. Wire size shall limit voltage drop to five percent to the most remote fixtures.
e. Provide T90 wiring in EMT. Use min #10AWG copper.
f. Provide lamicoid nameplate on each battery pack indicating area served. Refer to "LIGHTING FIXTURE SCHEDULE" for suggested labeling.
g. Rooms required to contain emergency lighting shall have a minimum of two heads installed.

.2 Self-Contained

a. Procure recessed back boxes in advance to permit suitable rough-ins.

.3 Perform an Emergency Lighting and Exit Sign test as soon as the systems are operational. Test shall indicate the following in chart form on Company letterhead:

a. Building name and location.
b. Physical location of each remote device.
c. The device designation, i.e, EDA, EXA, etc.
d. Battery pack designation, manufacturer and name plate data.
e. Proper operation under normal AC power.
f. Duration of operation under emergency DC power.
g. Current load check on each output circuit.
h. Location and voltage at most remote fixture.
i. Charging current at the end of the test.
j. Date of testing.
k. Signature and name of testing individual.

.4 Once system is free of defects, remove all AC and DC power sources at a time suitable to the Owner, so as to schedule subsequent self-diagnostic Auto-Tests for minimal distraction to building occupants.

## 8. 26 42 01 ELECTRIC HEAT TRACING

8.1 General

.1 The Electrical Subcontractor shall supply and install a complete heat tracing system made up of self-regulating heating cable with all required power connection kits, tees, splices and fasteners as required for a complete water temperature maintenance system.

.2 Submit manufacturer's catalogue cuts showing materials and performance data. Submit a copy of UL file indicating that the heating cable is specially listed to provide supplementary heating to hot water service supply systems using thermally insulated metal or plastic piping.

8.2 Products

.1 The equipment and all related devices specified herein shall be manufactured by Raychem Canada Limited. All sizes, types and lengths of heat trace shall be as per the drawings.

.2 Freeze Protection cable shall consist of the following:

a. XL-TRACE Heat Cable (40 degree F - freeze protection)
b. 8XL1-CR (120V)
c. Power Connection Kit - Rayclic-PC
d. End Kit - Rayclic-E
e. Fibre Glass Tape - GT-66 (metal piping)
f. Aluminum Tape - AT180 (Plastic piping)
g. "Electric Traced" labels - ETL
h. Line Sensing Thermostat AMC-F5

.3 The heat trace shall be a self-regulating polymer core with 2-16AWG tinned copper bus wires embedded in radiation-cross linked polyolefin core. The polymer core will allow its resistance to vary - thus regulating its power output for temperature response. The entire heater shall be covered by a radiation cross-linked modified polyolefin dielectric jacket, and flexible metallic over shield.

.4 The cable shall have a minimum cut-through resistance of 600lb per CSA 22.2 0.3 Cutting test 4.14.

8.3 Installation

.1 Provide all power connection kits, end kits, "Electrically Traced" labels, etc to form a complete installation.

.2 The heat cable system shall operate on a 120V system.

.3 Provide BAS relays with the ambient thermostat connected to Auto mode.

.4 All power connection, end seal, splice and tee kits shall be installed in the field with a complete inspection performed by the Consultant prior to power up of the system.

.5 All equipment, cable and devices shall be UL listed and CSA approved.

.6 Install ambient sensing thermostat so that the heat trace cable is energized when the exterior temperature drops below 2°C. Thermostat shall switch the load through the use of a contactor or power relay.

8.4 Execution

.1 Cable shall be laid inside the equipment pan and drain piping of the rooftop equipment.

.2 Coordination with Division 23 to install prior to insulation wrap.

.3 All installations shall conform to the manufacturer's recommended installation practices and supplemented information herein and on drawings.

.4 Power connection kits shall be installed in a surface mounted junction box suitable to house the connection kit in the location as shown on the drawings.

.5 A sign reading "ELECTRIC TRACED" shall be installed on the outside of the thermal insulation at intervals of 8" spacing. Signs shall be supplied and installed by the Electrical Subcontractor.

.6 The heat trace cables shall be protected by overcurrent protection that contains a ground fault detection device set at 30mA (Class B). The use of 5mA trip breakers (Class A) shall not be permitted.

.7 Following cable installation on pipe, heat trace shall be subject to a test using a 2500VDC. Megger prior to and following installation of thermal insulation. Insulation resistance should be 20-1000 MEGA OHMS regardless of length. The Consultant shall be given two weeks notice prior to testing and the Consultant may or may not wish to witness the tests.

**END OF SECTIONS**

## 1. 27 05 13 COMMON WORKS

1.1 General Requirements

.1 The Procurement and Contracting Requirements as outlined under Division 00, and the General Requirements as outlined under Division 01, and all addenda thereto shall apply to and govern all portions of the communications work.

.2 Reference Division 26 and Division 28 for additional requirements.

1.2 Work to be Included in the Bid

.1 The electrical subcontractor shall supply and install and/or modify the following systems:

a. Pathways for Communications and Security.

.2 The subcontractors shall ensure that all cabling in spaces being used as a return air plenum is totally enclosed in non-combustible raceways, or is Communications Media Plenum (CMP), or FT6 rated.

.3 All systems and components shall be ULC listed.

1.3 Work by Allowance

.1 The following systems shall be supplied and installed and/or modified under the specified allowance(s):

a. Structured cabling.
b. Passive data (Information Technology) devices.
c. Passive voice (Telephone) devices.
d. Public address.
e. Assistive listening.
f. Audio/Video.

.2 The work shall include all equipment, cabling, terminations, testing, programming, integration and commissioning as applicable.

.3 The electrical subcontractor shall coordinate with the successful Division 27 subcontractor(s) to provide all rough-in work, including power and pathways.

## 2. 27 05 28 PATHWAYS FOR COMMUNICATIONS AND SECURITY SYSTEMS

### 2.1 General

.1 This section will generally refer to empty conduits, sleeves, junction boxes, etc. associated with the following systems:

a. Communications, i.e., Division 27.
b. Electronic Safety and Security, i.e., Division 28

.2 Provide all material and labour necessary for a complete installation of pathways.

### 2.2 Installation - Interior

.1 Provide duplex receptacles as indicated on the drawings.

.2 Unless otherwise noted, all outlets shall be single gang deep boxes. Each single gang box shall be provided with 0.75" (21mm) conduits. Outlets that indicate more than two drops shall feature 1.0" (27mm) conduits. Allow for punching holes in metal outlet boxes if available knockouts cannot meet this specification.

.3 All conduit runs shall originate at the wire way, pull box or splice box.

.4 All conduit runs shall follow building grid lines and shall be concealed.

.5 EMT bushings shall be Arlington AL-EMTxx series, size to suit conduit specified.

.6 If the conduit lengths/bends exceed that listed above, a pull box shall be installed.

### 2.3 Specific Rough-ins

.1 Rough-in for microphone outlets shall be compatible with specified remote line/microphone mixer.

.2 Coordinate with the Communications Subcontractor to procure public address speaker back boxes for any wall or drywall ceiling installations.

.3 Unless otherwise noted, boxes for audio/video inlets/outlets shall be two-gang.

.4 Unless otherwise noted, new computer drops for Wireless Access Points shall be ceiling mounted. The data drops shall be powered over the network (POE).

### 2.4 Cabling Hangers

.1 Multiple use “J” shaped hanger to provide secure containment of low voltage communications cables.

a. Pre-galvanized finish.
b. 4" (100mm) size capable of supporting 300 4-pair UTP, CAT5e or 2-strand fibre cable, or 185 CAT6.
c. Quick release cable retainer.

.2 Hangers shall be Cooper B-Line Catalog No. BCH64 series, or approved alternate, complete with Qwik-Latch cable retainers.

.3 Units shall be wall mounted (-1D) where ever possible. Where not possible, units shall be suspended from the structure (-2D).

.4 Installation of power wiring in hangers shall not be permitted.

.5 Hangers shall be spaced at 60" (1.5m) intervals

.6 Coordinate exact location of hangers onsite with Mechanical Contractor to avoid conflicts with piping, ductwork etc.

2.5 Execution

.1 Provide a conduit from each outlet box to the nearest accessible ceiling space. Conduit shall extend minimum of 6.0" (150mm) above ceiling and shall have smooth 90 degree bends. Do not terminate conduits above non-accessible ceiling systems.

.2 All empty conduits and raceway systems shall be provided complete with nylon pull tapes and plastic bushings.

.3 Pull tapes shall be suitably fastened to the ends of each conduit to prevent accidental pull outs.

**END OF SECTIONS**

## 1. 28 05 00 COMMON WORKS

### 1.1 General Requirements

.1 The Procurement and Contracting Requirements as outlined under Division 00, and the General Requirements as outlined under Division 01, and all addenda thereto shall apply to and govern all portions of the electronic safety and security work.

.2 Reference Division 26 and Division 27 for additional requirements.

### 1.2 Work to be Included in the Bid

.1 The electrical subcontractor shall supply and install and/or modify the following systems:

a. Pathways. Refer to Division 27.
b. Intrusion detection and alarm.
c. Fire detection and alarm.

.2 The work shall include all equipment, cabling, terminations, testing, programming, integration and commissioning as applicable.

.3 The electrical subcontractor shall obtain the services of qualified security subcontractor(s) for the satisfactory completion of the work, and shall carry all such subcontractor costs in the bid.

.4 All rough-in work, including power and pathways, shall be performed by Division 26.

.5 The security subcontractor shall warrant any equipment installed under this specification to be free from defects for a period of two years from the date when Ready-for-Takeover has been attained.

.6 The subcontractors shall ensure that all cabling in spaces being used as a return air plenum is totally enclosed in non-combustible raceways, or is Communications Media Plenum (CMP), or FT6 rated.

.7 All systems and components shall be ULC listed.

### 1.3 Work by Allowance

.1 The following systems shall be supplied and installed and/or modified under the specified allowance(s):

a. Access control.
b. Video surveillance.

.2 The work shall include all equipment, cabling, terminations, testing, programming, integration and commissioning as applicable.

.3 The electrical subcontractor shall coordinate with the successful Division 28 subcontractor(s) to provide all rough-in work, including power and pathways.

## 2. 28 31 00 INTRUSION DETECTION

2.1 Scope of Work

.1 The subcontractor shall be responsible for relocating and reinstalling the intrusion detectors.

.2 The subcontractor is to coordinate with Owners staff for any system modifications.

2.2 Execution

.1 Relocate and reinstall area detectors as indicated and reconnect alarm circuit cabling.

.2 Do not mount detectors less than 600mm from light fixtures, air handling or heating outlets.

.3 Modify end-of-line devices at end of initiating circuits as required.

2.3 Conduit and Cabling

.1 Conceal all cables in conduit risers, sleeves and hangers.

.2 Size and quantity of conductors shall be in accordance with manufacturer's requirement for cabling.

.3 All new cabling shall be run concealed inside walls, ceiling spaces and within raceways where applicable. Provide riser conduits as required.

.4 All cabling run exposed above accessible ceilings shall be tie wrapped together at intervals not exceeding 1.2m.

## 3. 28 46 00 FIRE ALARM AND DETECTION

### 3.1 Scope of Work

.1 This specification provides the requirements for the modification of the addressable fire alarm and detection system. The system includes a control panel, annunciator(s), alarm initiating and indicating peripheral devices, conduit, wire and all accessories.

### 3.2 Quality Assurance

.1 Edwards is the existing manufacturer and as such, sets the standard of quality and type of equipment to be provided.

.2 All components of the fire alarm and detection system shall be covered by a one-year parts and labour warranty covering defects resulting from faulty workmanship and materials.

.3 All components shall be new and unused. All components and systems shall be designed for uninterrupted duty. All equipment, materials, accessories, devices, and other facilities covered by this specification or noted on contract drawings and installation specifications shall be the best suited for the intended use and shall be provided by a single manufacturer or if provided by different manufacturers recognized as compatible by both manufacturers and ULC.

.4 Installing contractor shall be certified by a program or course acceptable to the Office of the Fire Marshal. Evidence of membership in the ECAO Fire Alarm and Protection Certification Program, or proof of registration as a CFAA Fire Alarm Technician may be requested.

### 3.3 Control Panel (FACP)

.1 The existing fire alarm control panel is an Edwards model EST3 setup as follows:

a. A hybrid configuration of addressable and conventional zones.
b. A data loop on each floor.

.2 The consultant understands the control panel has capacity for the following:

a. Twenty (20) additional alarm initiating zones.
b. Twelve (12) additional supervisory initiating zones.

### 3.4 Remote Annunciators

.1 The annunciator(s) shall continue to indicate the system alarm, supervisory, monitor and trouble status.

.2 The annunciator shall feature one led for each new zone as outlined.

### 3.5 Passive Graphic

.1 An updated passive zoning graphic shall be provided by others above/adjacent to the annunciator(s).

### 3.6 Addressable Initiating Devices

.1 Addressable Devices

a. Each remote device shall have a microprocessor with non-volatile memory to support its functionality and serviceability.
b. Each device shall be capable of electronic addressing, either automatically or application programmed assigned, to support physical/electrical mapping and supervision by location.

.2 Addressable Detectors

a. The system addressable detectors shall be capable of full digital communications using both broadcast and polling protocol.
b. Each detector shall have an integral microprocessor capable of making alarm decisions based on parameter information stored in the detector head.
c. Each detector shall have a separate means of displaying communication and alarm status.
d. The detectors shall be suitable for mounting on any Signature Series detector mounting base.
e. The addressable detectors and devices shall be as follows:
    i. Smoke, SIGA-OSD.
    ii. Duct Smoke, SIGA-SD. Provide sampling tube and remote alarm LED.
    iii. Zone Isolator, SIGA-IM2.
f. All addressable detectors shall be suitable for use with the following bases:
    i. Standard, SIGA-SB.

.3 Addressable Modules

a. It shall be possible to address each Intelligent Signature Series module without the use of DIP or rotary switches.
b. The personality of multifunction modules shall be programmable at site to suit conditions and may be changed at any time using a personality code downloaded from the Analog Loop Controller.
c. Input and output circuit wiring shall be supervised for open and ground faults.
d. The addressable module devices shall be as follows:
    i. Single Input, SIGA-CT1.
    ii. Dual Input, SIGA-CT2.
    iii. Single Input Signal, SIGA-CC1S.
    iv. Control Relay, SIGA-CR (form C contacts, 2A @24VDC, 0.5A @120VAC).
    v. Control Relay, SIGA-CRH (form C contacts, 6A @24VDC, 7A @120VAC).
    vi. Manual Station, SIGA-270.

3.7 Conventional Initiating Devices

.1 The system shall possess the capability of incorporating the following conventional system devices:

3.8 System Accessories

.1 Provide independent devices as follows:

a. Manual Station Cover without horn, Model No. STI-1200.

b. End of line device cover plates, Model No. EOL-P1, white.

3.9 Signaling Devices

.1 All appliances shall be ULC Listed for Fire Protective Service.

.2 All appliances shall be of the same manufacturer as the Fire Alarm Control Panel to ensure absolute compatibility between the appliances and the control panels, and to ensure that the application of the appliances is done in accordance with the single manufacturer's instructions.

.3 Signaling pattern and sound shall be consistent throughout the facility. Mixing of different sounding devices shall not be permitted.

.4 Bells

a. MB6-24 motor driven.

.5 Bell/Strobe Combination

a. 403-7A-R LKW-1 complete with Bell as specified above.

3.10 Ancillary Devices

.1 Addressable (Booster) Power Supply Model No. SIGA-APS.

a. Six independent circuits.
b. 24VDC complete with batteries sized to suit load.

3.11 Fire Alarm Monitoring Equipment (FAME)

.1 Existing equipment shall remain to allow for offsite monitoring of the fire alarm and detection system.

.2 At time of occupancy, coordinate with Owners to provide a certificate indicating compliance with offsite monitoring facilities.

3.12 Sequence of Operation

.1 The system shall continue to function so that operation of any alarm initiating device shall cause the following:

a. Signal devices to operate throughout building at the alarm
b. Transmit an alarm signal to remote monitoring agency.
c. Display an event type, alarm time, and a location message for each active device or zone at control panel and at remote annunciators.

.2 The system shall continue to function so that operation of any supervisory initiating device shall cause the following:

a. Internal signal to sound at the control panel and remote annunciators.

b. Display a location message for active device(s) at the control panel and remote annunciators.
c. Transmit a supervisory signal to remote monitoring agency.

.3 Program interlocks with all ancillary equipment as follows:

a. Power door operators:
   i. If the power door operator is of a type that does not close under power failure, then the door should be disconnected from the operator and caused to close under fire conditions.
   ii. If the power operator is to close the door under fire conditions, its logic circuit should be such that, upon a signal from the fire detection system, it closes under power operation.
b. Fire smoke dampers: Close on alarm or any smoke detector associated with the damper.
c. Air handling system: Shut down on alarm or local duct smoke detector.
d. For equipment and system interlocks not referenced above, contact consultant for clarification.

.4 Program initiating devices as follows:

a. Alarm:
   i. Smoke detectors.
   ii. Manual stations.
   iii. Sprinkler Flow Switches (FS), (60s delay).
   iv. Deluge fire suppression.
b. Supervisory:
   i. Sprinkler Electronically Supervised Valves (ESV).
   ii. Sprinkler Low pressure Switches (LPS).
   iii. Sprinkler heat trace (60s delay).
c. For equipment system interlocks not referenced above, contact consultant for clarification.

.5 Indicate trouble condition at control panel and remote annunciator(s) for the following conditions:

a. Field wiring open circuit.
b. Field wiring ground fault.
c. Battery disconnect.
d. Low battery.
e. AC power failure.

.6 Program signal devices as follows:

a. Single stage operation.
b. Set at maximum volume unless noted otherwise. Adjust to lower volume settings only if maximum permitted threshold is exceeded.

.7 Provide signals to offsite monitoring facility for a supervisory, trouble and alarm condition.

.8 Duct detectors and smoke detectors associated with adjacent smoke dampers shall be programmed to activate the initiating zone on the floor where the device is located.

3.13 Installation

.1 General Installations

a. The new components shall be installed in accordance with CAN/ULC-S524-19 and approved manufacturers manuals and wiring diagrams. The Electrical Subcontractor shall furnish all conduit, wiring, outlet boxes, junction boxes, cabinets and similar devices necessary for the complete installation. All wiring shall be of the type recommended by the OESC, approved by local authorities having jurisdiction for the purpose, and shall be installed in dedicated conduit throughout.
b. All penetration of floor slabs and fire walls/separations shall be fire stopped in accordance with all local fire codes.
c. Install new initiating circuit wiring and new signal circuit wiring in separate, red raceways.
d. End of Line resistors shall be furnished as required for mounting as directed by the manufacturer.
e. Panel and annunciator zone labels shall be typed. Hand written labels shall not be permitted.
f. Provide all programming and labels that reference room names or numbers to reflect the finalized Owner designated room names/numbers. Do not duplicate the room names/numbers indicated on the drawings.
g. All wiring shall be minimum #14 AWG copper with 300V insulation rating, unless specifically noted otherwise.
h. All device outlet boxes shall be selected to suit manufacturer's equipment and shall be coordinated prior to rough in. Outlet boxes for manual stations shall be 100mmx100mm (4"x4") with single gang plaster ring and depth to suit manufacturer's requirements.
i. If fire alarm remote booster power supplies are provided in lieu of extension of the power supply in the main panel, it shall be provided with internal back up batteries. The breaker shall be painted red and locked on.

.2 Initiating Installations

a. Locate and install new isolation modules and connect to data loop wiring.
b. Locate and install new initiating circuits and detectors and connect to zone wiring.
c. Install spot type fire detectors on ceiling unless otherwise specified herein with minimum and maximum distances as required for the respective type of detector.
    i. Mount at highest point where variations in ceiling height exist.
    ii. Maintain a clear space of at least 18" (450mm) on the ceiling, below and around the fire detector.
    iii. Maintain a horizontal minimum of 36" (900mm) between a fire detector and the peak of a sloped ceiling.
    iv. Fire detectors shall not be located a direct air flow or within 18" (450mm) from an air supply or exhaust outlet.
d. Install duct detector sampling tubes in straight section of duct to manufacturer's recommendation. Install so that the smoke detector and sampling tube are accessible for servicing. Obtain actual duct dimensions onsite prior to ordering air sampling tubes.

e. Manual stations shall be located within 1500mm (60") of an exit door. Where possible, locate on the latch side of a single door.
f. Connect new waterflow alarm switches and sprinkler supervisory devices, supplied by Division 21, to zone wiring. Coordinate exact device locations and quantities on site.
g. Verify the exact locations and names of all sprinkler system switches and valves with the Fire Protection Subcontractor onsite and modify zone names to suit.
h. All Electronically Supervised Valves (ESV), Flow Switches (FS), and Low-Pressure Switches (LPS) shall be supplied and installed by the Fire Protection Subcontractor and wired by the Electrical Subcontractor. Coordinate exact quantities on site.

.3 Signaling Installations

a. Locate and install new signaling devices and connect to notification circuits. Provide suitable back boxes and back plates for signaling appliances, surface or recessed type to suit the specific application.
b. Provide adequate signal circuit wiring so that circuits are not loaded beyond 65%, regardless of the zoning arrangement indicated on the plans.
c. Provide a dedicated signal circuit for motorized bells when used in combination with strobes.
d. Provide rough-in and wiring to suit a future conversion to horn/strobes.
e. Notification devices shall be set to match existing pattern at maximum volume unless noted otherwise. Changes to a temporal 3-3-3 pattern will be implemented at a later date.
f. Programming for signal silence inhibit at 1.0 minutes, and automatic signal silence at 20 minutes.
g. Audible and visual notification appliances shall be affected by signal silence features.
h. Configure notification circuits to synchronize output signals.
i. Visual notification devices shall be set for 30cd, unless noted otherwise.

.4 Ancillary Installations

a. Integrate the fire alarm and the audio video system(s) such that the performance audio is muted during an alarm condition.

3.14 Addressable System Notes

.1 Locate and install new isolation modules and connect to data loop wiring. Locate zone isolators directly adjacent to zone separation at the point where it enters and exits the zone. There shall be a minimum of two zone isolators for each initiating zone. The location of the isolators may be adjusted onsite to optimize wiring. Clearly indicate isolator location on as-built drawings.

.2 New data loop wiring shall be ULC S524 Style C.

.3 Data loop wiring shall exit/enter the control panel separate raceways and shall be separated 1.2m horizontally and 0.3m vertically thereafter.

.4 The following OBC zones need not have zone isolators:

a. Sprinkler ESV, FS, LPS.
b. Duct smoke detectors.

c. Other devices that are situated completely within a floor area.

.5 Data loop home run shall be permitted to pass through OBC zone/floor area/shafts without zone isolators. If devices are installed on the home run data loop, additional zone isolators shall be provided. Floor plans assume additional isolators will not be required.

.6 Addressable sensors and modules shall be connected directly to the data loop wiring. T-tapping off the data loop to form a Class "B" (zone wiring) circuit shall not be permitted.

.7 Zone wiring shall be #14/2 copper in a metallic raceway. AC90 (BX) cable is acceptable where specified. In all cases, the sensors and modules shall be located between the isolators serving the particular zone.

.8 Ensure data loop device count does not exceed 80%. Provide additional data loops if required. Proposed zone layout shall be prepared by the manufacturer and submitted to the Consultant for review.

.9 The address of each sensor and module shall be assigned by means of computer polling of the data loop(s) once installations are complete. The Electrical Subcontractor shall ensure that each addressable detector and module is assigned an identifying name in accordance with its installed location upon project completion.

.10 All new signaling devices shall be fed direct from the booster power supply using Notification Appliance Circuits (NAC)s. NAC wiring shall be #14/2 copper in metallic raceway. AC90 (BX cable is acceptable where specified.

.11 Connect addressable relay module outputs to the data loop nearest the module.

.12 Field measure all loads connected to addressable relay modules where the ratings on contacts is exceeded, provide additional relay suitable for the connected load.

3.15 Field Quality Control and Programming

.1 Perform verifications in accordance with CAN/ULC-S537-19 Standard for the Verification of Fire Alarm Systems. Include inspections and testing as outlined in CAN/ULC-S536 latest addition.

.2 Perform audibility tests if required by the local Building officials or if requested by the consultant.

.3 Check annunciator panels to ensure zones are shown correctly.

.4 The system shall be installed and fully tested under the supervision of trained manufacturer's representative. The system shall be demonstrated to perform all the functions as specified.

.5 Verification(s) shall be performed by the manufacturer's representative authorized by the CFAA. Verification by the Contractor shall not be permitted.

.6 Include for multiple verifications and integrated tests where the construction schedule warrants. Coordinate exact requirements with General trades.

.7 System installation and operations shall be verified by the manufacturer's representative and a verification document presented upon completion. The manufacturer's representative shall be responsible for an on-site demonstration of the system operation and initial staff training as required by the Architect and/or Consulting Engineer.

.8 Changes made to an existing fire alarm system shall require the following:

a. Verification of all new and modified devices.
b. Testing of all devices on the data loops affected. Software polling of devices on modified data loops shall not be acceptable.
c. Testing of one device on each zone data loop not affected.

.9 System changes shall be verified by the manufacturer's representative and a verification document presented upon completion.

3.16 Integrated Systems Testing of Fire Protection and Life Safety Systems

.1 The Electrical Subcontractor shall retain the services of an Integrated Testing Coordinator (ITC) for all systems that are designed to operate together to achieve an overall fire protection and life safety objective, in accordance with OBC 3.2.9.

.2 The Contractor shall not act as the ITC. The ITC shall be an independent provider that has been certified by ULC to perform this function and shall provide proof of certification prior to proceeding.

.3 The Electrical Subcontractor shall cover the costs of the ITC and shall be responsible for coordinating and scheduling all affected parties including owners, operators, occupants, inspectors, consultants, installing subcontractors and verifying parties to participate in the testing.

.4 The ITC shall be knowledgeable and experienced in the design, installation and operation of fire protection and life safety systems as well as associated building systems.

.5 The ITC shall provide a project-specific, written report outlining the testing procedure and necessary functional results in accordance with CAN/ULC-S1001. A cause and effect matrix shall be used to outline the sequence of operation for the systems integration. The matrix shall be prepared by the ITC based on sequence of operation and fire alarm drawings and schematics. Specifically, this integrated testing plan shall outline the fire alarm system's integration with the following equipment and systems:

a. Sprinkler.
b. Freeze Protection.
c. Power Door Operators.
d. Smoke Control, including Air Handling.
e. Audio/Visual.
f. Notification.
g. Signals to Fire Department.

.6 Submit the integrated testing plan to the Engineer concurrently with shop drawings. Prior to testing, the Contractor shall provide all occupancy-related documentation to the ITC.

.7 Unless otherwise outlined, the testing procedure shall consist of the functional operation of the device or system, i.e., testing of relay contacts alone is insufficient. Sample testing is also insufficient.

.8 Once testing is completed, the ITC shall provide a signed report documenting the implementation of the systems integration. Include the report in the project close out for subsequent periodic systems testing as required.

**END OF SECTIONS**

## PART 1 - GENERAL

1.1 General

.1 Conform to Division 01 - General Requirements

1.2 References

.1 Canadian Standards Association (CSA).
  .1 CAN/CSA-A23.1-14, Concrete Materials and Methods of Concrete Construction.
.2 Canadian General Standards Board (CGSB).
  .1 CAN/CGSB-1.2-98, Boiled Linseed Oil.
  .2 CAN/CGSB-3.3-99, Kerosene.
.3 American Society for Testing and Materials (ASTM).
  .1 ASTM D698-12, Test Method for Laboratory Compaction Characteristics of Soil Using Standard Effort.
.4 Accessibility for Ontarians with Disabilities Act (AODA).

## PART 2 - PRODUCTS

2.1 Materials

.1 Concrete mixes and materials: OPS mix to 30MPa at 28 days.
.2 Fibre Expansion Joints: Manufactured commercial type meeting requirements of ASTM D1751; 13mm thick.
.3 Granular base: to OPSS 1010 for Granular A and Granular B.
.4 Non-staining mineral type form release agent: chemically active release agents containing compounds that react with free lime to provide water soluble soap.
.5 Fill material: OPSS Granular B to 98% SPMDD.

## PART 3 - EXECUTION

3.1 Grade Preparation

.1 Place Granular “B” Type 1 fill in maximum 150mm layers and compact to at least 98% of maximum density to ASTM D698.

3.2 Granular Base

.1 Obtain Consultant's approval of subgrade before placing granular base.
.2 Place Granular “A” base material to lines, widths, and depths as indicated.
.3 Compact granular base to at least 98% of maximum density to ASTM D698.

3.3 Concrete

.1 Obtain Consultant's approval of granular base and reinforcing steel prior to placing concrete.
.2 Slip-form pavers equipped with string line system for line and grade control may be used if quality of work acceptable to Consultant can be demonstrated. Hand finish surfaces when directed by Consultant.

3.4 Concrete Walks

.1 Concrete walks to be 100mm thick, **unless noted otherwise on Drawings**, on minimum 150mm thick base of Granular “A” compacted to 98% Standard Proctor maximum dry density.
.2 Immediately after floating, give sidewalk surface uniform broom finish to produce regular corrugations not exceeding 2mm deep, by drawing broom in direction normal to centre line. Refer to Architectural Drawings for other finishes required by municipal accessibility standards.
.3 Provide edging as indicated with 10mm radius edging tool.
.4 Slope concrete walks to one side, away from building, 1:50, or as indicated on Drawings.

3.5 Concrete Curbs

.1 Curb design to be as indicated on Drawings, on 300mm minimum Granular “B” compacted to 98% Standard Proctor maximum dry density.

3.6 Tolerances

.1 Finish surfaces to within 3mm in 3m as measured with 3m straightedge placed on surface.

3.7 Expansion and Contraction Joints

.1 Install tooled, transverse contraction joints after floating, when concrete is stiff, but still plastic, at intervals of 1.5m.
.2 Install expansion joints as indicated on Drawings at intervals of 6m.
.3 Install expansion joints around manholes and catch basins and along length adjacent to concrete curbs, catch basins, buildings, or permanent structure.
.4 When sidewalk is adjacent to curb, make joints of curb, gutters and sidewalk coincide.
.5 Install joint filler in expansion joints as indicated.
.6 Seal expansion joints with sealant approved by Consultant.
.7 Refer to Drawings for saw cut patterns.

3.8 Curing

.1 Cure concrete by adding moisture continuously in accordance with CAN/CSA-A23.1 to exposed finished surfaces for at least 1 day after placing or sealing moisture in by curing compound approved by Consultant.
.2 Where burlap is used for moist curing, place two prewetted layers on concrete surface and keep continuously wet during curing period.
.3 Apply curing compound evenly to form continuous film in accordance with manufacturer's requirements.

3.9 Backfill

.1 Allow concrete to cure for 7 days prior to backfilling.
.2 Backfill to designated elevations with material approved by Consultant.

END OF SECTION

# 26-7849-RFT - Galt Collegiate Institute Exterior/Interior Upgrades to Tassie Hall

Opening Date: February 12, 2026 6:00 PM

Closing Date: March 4, 2026 2:00 PM

---

## Schedule of Prices

* Denotes a "**MANDATORY"** field

Do not enter $0.00 dollars unless you are providing the line item at zero dollars to the Board.

## Bid Price Form

The amounts stipulated on the Bid Price Form(s) are intended to cover the cost of the complete Work as described in this Procurement and must remain fixed and firm for the term of the Contract unless otherwise specified in this Procurement.

All prices shall be in Canadian Funds, Free On Board (FOB) Destination, and Freight Prepaid (Board locations). and shall be exclusive of Harmonized Sales Tax (HST) but shall include all materials, labour, equipment, disbursements, expenses, insurance, bonding, customs charges, freight, shipping and handling costs, travel costs and all other charges of every kind attributable to the Work and Services provided.

**Bid Price includes Cash Allowance**

| Line Item | Description | Unit of Measure | Quantity | Bid Price * | Total |
|---|---|---|---|---|---|
| 1 | As per scope of work outlined in 26-7849-RFT Galt Collegiate Institute Exterior/Interior Upgrades to Tassie Hall | Lump Sum | 1 | | |
| | | | | Subtotal: | |

## Optional Price Form

Optional Price Form

Such Optional Work and amounts are NOT included in the Base Bid Price.

The amounts stipulated on the Optional Work Bid Price Form are intended to cover the cost to complete this Work as described and must remain fixed and firm for the term of the Contract unless otherwise specified.

The Board reserves the right to choose none, one, more than one or all options in any order. These options are not in any priority.

All prices shall be in Canadian Funds, Free On Board (FOB) Destination, and Freight Prepaid (Board locations). and shall be exclusive of Harmonized Sales Tax (HST) but shall include all other charges of every kind attributable to this Work and Services provided.

| Line Item | Description | Unit of Measure | Quantity | Bid Price * | Total |
|---|---|---|---|---|---|
| 1 | All costs associated, including labour and materials with the deletion of the existing Teck feeders between ‘DP-BBB’ and ‘STL’; and the provision of 4-#3/0 T90 in 53mm EMT between ‘DP-BBB’ and ‘P32B’. | Lump Sum | 1 | | |
| | | | | Subtotal: | |

## Summary Table

| Bid Form | Amount |
|---|---|
| Bid Price Form | |
| HST (13%) | $ 0.00 |
| Total Contract Amount: | |

## Bid Questions

Bidder Instructions

Answer all questions marked Mandatory.

Bill S-211 - This enactment enacts the Fighting Against Forced Labour and Child Labour in Supply Chains Act, which imposes an obligation on certain government institutions entities to ensure measures are taken to prevent and reduce the risk that forced labour or child labour is used by suppliers or in their supply chains. The Board principles align with Bill S-211. Please confirm that your organization will comply with this Act. YES or NO. If no, please explain.

As per the “Ontario Business” definition as per the BOBI Act is a supplier, manufacturer or distribution of any business structure; conducts its activities on a permanent basis in Ontario; and has either a) its headquarters or main office in Ontario, or b) at least 250 full-time employees in Ontario at the time of the applicable procurement process. Does your company qualify as an Ontario Business under the BOBI Act? YES or NO

Is your company a Canadian business? YES or NO *

Is your company a U.S. business, as defined by the Ontario Treasury Board / Management Board of Cabinet (TB/MBC) as a supplier, manufacturer or distributor of any business structure (includes a sole proprietorship, partnership, corporation or other business structure) that: has its headquarters or main office located in the U.S., and has fewer than 250 full-time employees in Canada at the time of the applicable procurement process? Yes or No. (Comments are allowed). *

## Specifications

## Bidder's Contact Information

A Site Supervisor and Project Manager, assigned to manage and supervise the Work, must be named in this form. Personnel will be subject to approval by the Board and cannot be changed without prior written approval from the Board.

Note: resumes are required to be uploaded in the document section.

| Title | Name * | E-mail * | Cell Phone Number * | |
|---|---|---|---|---|
| Project Manager | | | | * |
| Site Supervisor | | | | * |
| Optional – Alternative Site Supervisor | | | | |

### Documents

It is your responsibility to ensure the uploaded file(s) is/are not defective or corrupted and are able to be opened and viewed by the Owner. If the attached file(s) cannot be opened or viewed, your Bid Submission may be rejected.

### Instructions to Bidders

- Upload a resume for each person named in the Specification section.
- **Certificate of Recognition (COR) Certification (General Contractors)**

  All bidders must possess and maintain a valid Certificate of Recognition (COR) issued by a recognized certifying partner at the time of bid submission.
  Bidders shall upload proof of current COR Certification with their tender submission. Failure to provide acceptable documentation may render the bid non-compliant and subject to rejection.
  The WRDSB reserves the right to verify the validity and status of COR Certification at any time during the procurement process and throughout the term of the contract.
  If a bidder's COR Certification expires, is suspended, or is revoked during the contract period, the Board may, at its sole discretion, require immediate corrective action or terminate the contract without penalty

- Project Manager Resume * (mandatory)
- Site Supervisor Resume * (mandatory)
- Optional - Alternative Site Supervisor (optional)
- Certificate of Recognition (COR) Certification (General Contractors) * (mandatory)

### BONDING UPLOAD SECTION

Refer to the Bonding Requirements Section of the Terms and Conditions.

Bonding is required if the project is equal to or greater than $200,000.00. Note: The Bidding System has flagged these fields as mandatory. If your bid is less than $200,000.00, please upload a pdf document stating: Not Applicable.

Bidders shall upload their electronically verifiable and enforceable (e-Bond) format for Bid Deposit Bond and Agreement to Bond separately in this section. If both Bonds are in the same file, please upload it in both fields and indicate one is a copy.

Tender # and Project Title must be included on the Bonds

- Bid Deposit Bond * (mandatory)
- Agreement to Bond * (mandatory)

## Addenda, Terms and Conditions

I/We have read and understand this Bid Solicitation document, and agree to perform the Work required in accordance with this Bid

Solicitation document, including all addenda, at the price(s) detailed in the Bid.

I/We confirm that:

1. The person named in this Bid is authorized to sign and electronically submit this Bid through the Bidding System.

2. I/We meet all mandatory requirements of the Bid Solicitation document.

3. The bid will remain open for a specified acceptance period after the Closing Time. The Board may, at any time within this period, accept the Bid whether or not any other Bid has previously been accepted.

4. All prices provided in the Bid will remain fixed and firm for the duration of the term of the agreement, unless specified otherwise.

5. All prices provided in my/our Bid are in Canadian funds and include all charges of every kind attributable to the Work. Harmonized Sales Tax will be extra and not shown, unless specified otherwise.

6. To the best of my/our knowledge and belief:

a) the information provided in the Bid is correct; and

b) the Bid is made without any comparison of figures or arrangement with any other individual, corporation or person submitting a Bid for the same Work and is in all respects fair and without collusion or fraud.

7. I/We comply with the all applicable Board policies, provincial, and federal laws, and are aware of the Board's "Principles of Business Conduct" and will comply.

8. I/We agree and understand that the recommendation to award the Work may be subject to the approval from the Board as well as availability of funds.

9. I/We agree to be bound by the terms and conditions of the Bid Solicitation document and submit this Bid on behalf of the Bidder.

☐ I have the authority to bind the Bidder.

The Bidder/Proponent is to declare any actual, potential or perceived conflict of interest that could arise from submitting the Bid/Proposal.

Do you have a potential conflict of interest?

○ **Yes** ○ **No**

The Bidder acknowledges and agrees that the addendum/addenda below form part of the Bid Solicitation Document.

Please check the box in the column "**I have reviewed this addendum"** below to acknowledge each of the addenda.

| File Name | I have reviewed the below addendum and attachments (if applicable) | Pages |
|---|---|---|
| **There have not been any addenda issued for this bid.** | | |