

Project Manual for the
Construction of the
T. A. BLAKELOCK H.S. RENOVATIONS - PHASE E

at

1160 Rebecca Street
Oakville, Ontario

for



The Halton District School Board
2050 Guelph Line
Burlington, Ontario

Project No.: 2215E

HDSB RFT # 26-075

sn/derarchitects

*100 Broadview Avenue, Suite 301
Toronto, Ontario M4M 3H3
Tel.: 416.966.5444*

1 General

1.1 OWNER

.1 Owner for the Project is:

The Halton District School Board
2050 Guelph Line
Burlington, Ontario
L7R 3Z2

1.2 CONTRACTOR

.1 Contractor for the Project is:

Golden Gate Contracting
1038 Cooke Boulevard, Unit #1
Burlington, Ontario
L7T 4A8
Telephone: 905.844.1122
Fax: 905.844.0051

1.3 CONSULTANTS

.1 Document Responsibility: Refer to Section 00 01 10 - Table of Contents for indication of document responsibility. Abbreviations for entity responsible for document preparation are as indicated below in parentheses.

.2 The following firms comprise the Consultant team for the Project:

.1 Architect (A)

Snyder Architects, Inc.
100 Broadview Avenue, Suite 301
Toronto, Ontario
M4M 3H3
Telephone: 416.966.5444

.2 Designated Substance Abatement Consultant (DS)

Arcadis Canada Inc.
121 Granton Drive, Suite 12
Richmond Hill, Ontario
L4B 3N4
Telephone: 905.764.9380

.3 Structural Engineer (S)

Kalos Engineering Inc.
300 York Boulevard
Hamilton, Ontario
L8R 3K6
Telephone: 905.333.9119

.4 Hardware Consultant (H)

ABDP Consulting Ltd.
1910 Port Davidson Road
Smithville, Ontario
L0R 2A0
Telephone: 905.327.1374

.5 Mechanical Engineer (M)

EXP Services, Inc.
1266 South Service Road, Unit C1-1
Stoney Creek, Ontario
L8E 5R9
Telephone: 905.573.4000

.6 Electrical Engineer (E)

EXP Services, Inc.
1266 South Service Road, Unit C1-1
Stoney Creek, Ontario
L8E 5R9
Telephone: 905.573.4000

END OF DOCUMENT

PROCUREMENT AND CONTRACTING REQUIREMENTS GROUP

**Document
Responsibility**

Division 00 - Procurement and Contracting Requirements

Introductory Information

00 01 03	Project Directory	A
00 01 10	Table of Contents	A

Procurement Requirements

00 21 13	Instructions to Bidders	A
00 31 00	Available Project Information.	A

Contracting Requirements

00 52 03	Cost-Plus Agreement	A
00 52 11	Subcontract Agreement.	A
00 71 03	Cost-Plus Contracting Definitions	A
00 71 11	Subcontracting Definitions.	A
00 72 03	General Conditions	A
00 72 11	Subcontract Conditions	A
00 73 03	Supplementary Conditions.	A
00 73 11	Supplementary Subcontract Conditions.	A

SPECIFICATIONS GROUP

GENERAL REQUIREMENTS SUBGROUP

Division 01 - General Requirements

01 12 00	Multiple Contract Summary	A
01 14 00	Work Restrictions	A
01 21 00	Allowances	A
01 23 00	Alternates	A
01 25 00	Substitution Procedures.	A
01 26 00	Contract Modification Procedures	A
01 31 00	Project Management and Coordination	A
01 32 00	Construction Progress Documentation.	A
01 33 00	Submittal Procedures	A
01 35 00	Special Procedures	A
01 40 00	Quality Requirements	A
01 50 00	Temporary Facilities and Controls.	A
01 60 00	Product Requirements.	A
01 71 00	Examination and Preparation	A
01 73 00	Execution	A
01 73 29	Cutting and Patching	A
01 74 00	Cleaning and Waste Management.	A
01 75 00	Starting and Adjusting	A
01 76 00	Protecting Installed Construction	A
01 77 00	Closeout Procedures	A
01 78 00	Closeout Submittals	A
01 79 00	Demonstration and Training	A

FACILITY CONSTRUCTION SUBGROUP

Division 02 - Existing Conditions

02 41 19	Selective Demolition	A
----------	--------------------------------	---

Division 03 - Not Used

Division 04 - Masonry

04 00 00	Masonry	A
----------	-------------------	---

Division 05 - Metals

05 50 00	Metal Fabrications.	A
----------	-----------------------------	---

Division 06 - Wood, Plastics and Composites

06 10 00	Rough Carpentry	A
06 16 43	Gypsum Sheathing	A
06 20 00	Finish Carpentry	A
06 24 00	High Pressure Decorative Laminate	A
06 41 00	Architectural Wood Casework	A

Division 07 - Thermal and Moisture Protection

07 21 00	Thermal Insulation	A
07 21 19.13	Foamed-in-Place Urethane Insulation	A
07 26 00	Vapour Retarders	A
07 27 00	Air Barriers	A
07 42 43	Composite Wall Panels	A
07 81 00	Applied Fireproofing	A
07 84 00	Firestopping	A
07 92 00	Joint Sealants	A
07 92 21	Sprayed Foam Sealant	A

Division 08 - Openings

08 12 13	Hollow Metal Frames	A
08 13 13	Hollow Metal Doors	A
08 31 00	Access Doors and Panels	A
08 51 13	Aluminum Windows	A
08 71 00	Door Hardware	A
	Hardware Groups	H
08 80 00	Glazing	A

Division 09 - Finishes

09 21 16	Gypsum Board Assemblies	A
09 51 23	Acoustical Tile Ceilings	A
09 65 13	Resilient Base and Accessories	A
09 65 19	Resilient Tile Flooring	A
09 65 66	Resilient Athletic Flooring	A
09 66 13	Portland Cement Terrazzo Flooring	A
09 81 00	Acoustic Insulation	A
09 84 13	Fixed Sound-Absorptive Panels	A
09 90 00	Painting and Coating	A
09 96 13	Abrasion-Resistant Coatings	A

Division 10 - Specialties

10 11 00	Visual Display Surfaces	A
10 14 00	Signage	A

Division 11 - Not Used

Division 12 - Furnishings

12 24 13.16	Manual Roller Window Shades	A
12 56 34	Music Room Furniture	A

Division 13 to 19 - Not Used

FACILITY SERVICES SUBGROUP

Divisions 20 to 25 - Not Used

Division 26 - Electrical

26 05 00	Electrical Basic Materials and Methods	E
26 05 19	Low Voltage Cables.	E
26 05 19.01	Appendix to Low Voltage Cables	E
26 05 26	Grounding and Bonding.	E
26 05 46	Vibration Isolation and Seismic Restraints.	E
26 05 70	Electrical Work Analysis and Testing.	E
26 09 00	Lighting Control.	E
26 27 19	Surface Raceways.	E
26 27 26	Wiring Devices	E
26 28 00	Low Voltage Circuit Protective Devices.	E
26 50 00	Lighting	E

Division 27 - Communications

27 10 00	Structured Cabling.	E
----------	-----------------------------	---

Division 28 - Electronic Safety and Security

28 31 00	Existing Fire Alarm Work.	E
----------	-----------------------------------	---

Division 29 - Not Used

SITE AND INFRASTRUCTURE SUBGROUP

Divisions 30 to 39 - Not Used

PROCESS EQUIPMENT SUBGROUP

Divisions 40 to 49 - Not Used

END OF TABLE OF CONTENTS

1 Invitation

1.1 BID CALL

- .1 Offers will be received electronically through the designated e-procurement services provider at:
<https://snyderarchitects.bidsandtenders.ca>.
- .2 Offers to perform the following trade Subcontracts will be received by Owner before 3:00:00 pm local time on the 11th day of June, 2026 (hereinafter referred to as 'bid closing time'):
 - .1 SC02 - Mechanical.
 - .2 SC03 - Electrical.
 - .3 SC04 - Metal Wall Panels.
 - .4 SC05 - Flooring.
 - .5 SC06 - Drywall and Acoustics.
 - .6 SC07 - Demolition.
- .3 The official bid closing time will be determined by the e-procurement services provider's web clock.
- .4 Bids cannot be submitted after the specified bid closing time.
- .5 Owner reserves the right to extend the bid closing time or cancel the bid call by addendum.
- .6 Bids are by invitation only from a list of preselected bidders. Bids received from unsolicited bidders will not be considered by Owner.
- .7 Bidders must have an active bidding system vendor account and be registered as a plan taker with the designated e-procurement services provider for this bid opportunity, which will enable the bidder to:
 - .1 Download Bid Documents,
 - .2 Receive email notifications,
 - .3 Download addenda, and
 - .4 Submit a bid electronically.
- .8 To ensure receipt of latest information and updates via email regarding this Bid, or if a bidder has obtained Bid Documents from a third party, it remains bidder's responsibility to create a bidding system vendor account and register as a plan taker with the designated e-procurement services provider for this bid opportunity.
- .9 Bids will not be opened publicly with bidders present.
- .10 Bid results will be disclosed promptly to all bidders. Such disclosure will not imply that the bids received are compliant or that a contract will be awarded to the lowest or any bidder.

1.2 INTENT

- .1 The intent of this bid call is to obtain offers to perform identified portions of the Work to complete construction of the Construction of the T. A. BLAKELOCK H.S. RENOVATIONS - PHASE E located at 1160 Rebecca Street, Oakville, Ontario.
- .2 Contract C00 is identified as a CCDC 3 Cost Plus a Fee Contract based on the Contract Documents.
- .3 Subcontracts are identified as CCA 1 Stipulated Sum Subcontracts. Successful Subcontractors will enter into written agreements with successful Contractor holding Contract C00, based on Contract Documents.

1.3 CONTRACT DOCUMENTS IDENTIFICATION

- .1 Contract Documents are identified as Project No.: 2215E as prepared by Consultant, Snyder Architects, Inc. located at 100 Broadview Avenue, Suite 301, Toronto, Ontario.

1.4 BID DOCUMENT AVAILABILITY

- .1 Bid Documents are only available to registered plan takers in electronic form from the designated e-procurement services provider.
- .2 Bid Documents are made available only for the purpose of obtaining offers for this Project. It does not confer a license to use the Bid Documents for any other purpose.

1.5 EXAMINATION OF BID DOCUMENTS

- .1 Examine Bid Documents and promptly notify Consultant of any perceived errors, omissions, conflicts or discrepancies in Bid Documents.

1.6 SITE EXAMINATION

- .1 Bidders shall visit Place of the Work and familiarize themselves with conditions affecting the Work before submitting a bid.
- .2 Bidders visiting Place of the Work will be required to obtain a visitor badge. Upon completion of visit, sign out and return visitor badge to Owner.
- .3 Bidders visiting Place of the Work shall provide their own personal protective equipment.
- .4 Bidders visiting Place of the Work will be required to be accompanied at all times by a representative of Owner.
- .5 Refer to Section 00 31 00 - Available Project Information which identifies available information pertaining to the Project.
- .6 In accordance with General Conditions of the Contract, bidders will include in their bid price for non-concealed and known conditions that are either visible or can be reasonably inferred from a site examination at Place of the Work and a review of available project information before bid submission.

1.7 BID FORM SUPPLEMENTS

- .1 Submit the following Bid Form Supplements together with the Bid Form:
 - .1 All bidders: WSIB Certificate.
 - .2 Subcontract bidders: List of Sub-subcontractors (as applicable).
- .2 Owner may, after bid closing time and before contract award, require any bidder to submit additional supplementary information about any aspect of the bidder's bid to verify compliance with the Bid Documents.

1.8 TAXES

- .1 Include in bid price all taxes and customs duties in effect at the time of bid closing, except for Value Added Taxes as defined in the Contract.

1.9 WORKPLACE SAFETY & INSURANCE BOARD CERTIFICATE

- .1 Submit a signed certificate from Workplace Safety & Insurance Board (WSIB), confirming that, at the date of the certificate, the bidder maintains an account with WSIB, and is in good standing.

1.10 CONTRACT TIME

- .1 The bidder, in submitting a bid, agrees to attain Substantial Performance of the Work by the date specified in Section 01 77 00 - Closeout Procedures, which will become the Contract Time under the Contract.

1.11 SUBSTITUTIONS

- .1 Where the Bid Documents specify particular Products by proprietary name, Consultant will consider bidder requests for approval of substitutions during the bid period, as long as such requests are received, in writing, at least 7 days before the bid closing time and are in accordance with the requirements specified in Section 01 25 00 - Substitution Procedures. If Consultant accepts a substitution, the substitute Product will be named in an addendum. Otherwise bidders shall consider the request for approval of the substitution to be rejected.

1.12 SUB-SUBCONTRACTORS

- .1 Refer to CCDC 3, GC 3.8 - Subcontractor and Supplier; and CCA 1, SCC 3.4 - Sub-subcontractors.
- .2 Indicating Sub-subcontractors as "OWN FORCES" is not considered acceptable and may be rejected by Owner, unless the bidder can adequately prove they have sufficiently trained personnel and experience to undertake those portions of the Work.
- .3 Owner reserves the right to reject a proposed Sub-subcontractor for reasonable cause. Upon such rejection, bidder will be required to propose an alternate Sub-subcontractor with a resulting change to submitted Bid Price. This change can effect the status of low bid, and may result in a different bid becoming low.

1.13 BID FORM SIGNING

- .1 Electronic signatures for signing of requested documents are considered acceptable.
- .2 Acceptable forms of electronic signature include, but are not limited to, typing of the bidder's authorized signing officer's name or inclusion of a graphic image of the bidder's authorized signing officer's signature, so long as the electronic signature is sufficient to identify the bidder's authorized signing officer.
- .3 The bidder's authorized signing officer agrees that whatever form of electronic signature is used constitutes a signature for the purpose of executing requested documents.

1.14 BID SUBMISSION

- .1 Bids will be received in electronic form only. Submit bid in compliance with the rules and procedures established by the designated e-procurement services provider.
- .2 Verbal, telephone, fax, e-mail, text message, or hand delivered bids will not be accepted or acknowledged.
- .3 Bidders wishing to submit prices for more than one Contract or Subcontract may do so separately, in accordance with the rules and procedures described above. Do not combine information pertaining to multiple Contracts or Subcontracts in a single bid submission.
- .4 Subcontract bids must include the appropriate reference to Subcontract number and title. Refer to Section 01 12 00 for summary of Subcontract numbers and titles.

1.15 BID MODIFICATION AND WITHDRAWAL

- .1 Bidders shall comply with procedures for electronic bid modification and withdrawal established by the designated e-procurement services provider.

- .2 If a bid is withdrawn, a new bid may be submitted in accordance with specified bidding requirements, as long as it is received before the bid closing time.
- .3 Owner assumes no responsibility or liability for modifications or withdrawals that are, for any reason, delayed, illegible, unclear as to intent, ambiguous, contrary to these instructions, or otherwise improperly received. Owner may disregard improperly received modifications or withdrawals.

1.16 BIDDING IRREGULARITIES

- .1 Bidders are cautioned that the timing of bid submission is based on when their bid is received by the e-procurement services provider, and not when their bid is submitted by bidder. Bid transmission can be delayed in an 'internet traffic jam' due to file transfer size, transmission speed and other electronic considerations. It is recommended that bidders allow sufficient time to upload their bid with required attachments and to resolve any issues that may arise before bid closing time.
- .2 The e-procurement services provider will send a confirmation email to bidder advising their bid was submitted successfully. In the event a confirmation email is not received, bidder is urged to contact the designated e-procurement services provider's technical support department via email at: support@bidsandtenders.ca.
- .3 Bids with Bid Forms or required Bid Form Supplements that are improperly prepared, signed or submitted contrary to these Instructions to Bidders, or that contain added conditions or other irregularities of any kind, may, at Owner's discretion, be rejected as non-compliant.
- .4 Owner may accept or waive a minor and inconsequential irregularity. The determination of what is, or is not, a minor and inconsequential irregularity, the determination of whether or not to accept or waive such an irregularity, and the final determination of whether the bid is compliant, will be at Owner's sole discretion.
- .5 The following irregularities relate to what are considered mandatory bidding requirements. These will not be considered minor and inconsequential and will cause the bid to be rejected as non-compliant:
 - .1 Bid or Bid Form Supplement is received after the specified bid closing time.
 - .2 Required Bid Form or Bid Form Supplement is missing.
 - .3 Bid Form or Bid Form Supplement is not in the form provided or required.
 - .4 Bid price is illegible, ambiguous, or unclear.
 - .5 One or more conditions are added to or submitted with the bid, the effect of which is a material modification of the Bid Documents.
 - .6 Failure to indicate in the Bid Form the addendum number(s) of all addenda received.
 - .7 Failure to comply with any other bidding requirement expressly characterized as mandatory elsewhere in the Bid Documents.

1.17 BID ACCEPTANCE PERIOD

- .1 Bids shall remain open to acceptance by Owner and shall be irrevocable until another bidder enters into a contract with Owner for performance of the Work or until expiry of the bid acceptance period stated in the Bid Form, whichever occurs first.
- .2 After bid closing and before expiry of the bid acceptance period stated in the Bid Form, Owner may request all bidders to agree to an extension of the originally specified bid acceptance period. In such case the bid acceptance period will be extended subject to the bidder, whose bid the Owner wishes to accept, having agreed in writing to the extension.

1.18 BID ACCEPTANCE

- .1 The lowest or any bid will not necessarily be accepted and Owner may reject any and all bids.
- .2 A contract will be established if and when the successful bidder receives from Owner a written notification accepting the bid without any conditions. If Owner's written notification accepting the bid contains, or is subject to, any conditions, a contract will be established if and when the bidder accepts all such conditions in writing or when the parties execute the agreement.
- .3 If the lowest compliant bid exceeds Owner's budget, and Owner is unwilling or unable to award a contract at the bid price, Owner may:
 - .1 Negotiate, with lowest compliant bidder only, changes to the Bid Documents and a reduced bid price acceptable to Owner, or
 - .2 Invite the three lowest compliant bidders to re-bid on modified Bid Documents under a new bid call.

1.19 INTERPRETATION AND MODIFICATION OF BID DOCUMENTS

- .1 If an inquiry requires an interpretation or modification of the Bid Documents, the response to that inquiry will be issued in the form of a written addendum only, to ensure that all bidders base their bids on the same information.
- .2 Replies to inquiries or interpretations or modifications of the Bid Documents made by e-mail, verbally, or in any manner other than a written addendum, will not form part of the Bid Documents and will not be binding.

1.20 ADDENDA

- .1 Addenda may be issued to modify the Bid Documents in response to inquiries or as may be considered necessary.
- .2 Addenda issued during the bidding period will become part of the Bid Documents.
- .3 No addenda will be issued later than two Working Days before the bid closing time.
- .4 Each bidder shall ascertain before bid submission that it has received all addenda issued during the bid period. Bidders must acknowledge receipt of each addendum by checking a box for each addendum and any applicable attachments issued before they can submit their bid.

1.21 INQUIRIES

- .1 Inquiries must be submitted through the e-procurement services provider by selecting the "SUBMIT QUESTION" button.
- .2 Submit inquiries as early as possible in the bid period and not less than 7 Working Days before the bid closing time. Inquiries received after this time may not receive a response.

END OF DOCUMENT

1 General

1.1 STATUS OF AVAILABLE PROJECT INFORMATION

- .1 Available Project information means information of any type and in any form that is expressly identified as available project information relevant to Place of the Work, that have been prepared by third-parties, and are intended strictly as additional information for consideration by Bidders.
- .2 No available Project information forms part of Contract Documents unless copied or transcribed into Drawings or Specifications, or is expressly listed in the agreement as a Contract Document.

1.2 USE AND RELIANCE UPON AVAILABLE PROJECT INFORMATION

- .1 Available Project information is made available to Bidders to fulfill Owner's duty to disclose all relevant Project information to Bidders.
- .2 Bidders shall interpret and draw their own conclusions about available Project information, including consideration of the time when it was created. Available Project information may be time sensitive. Owner and Consultant assume no responsibility for such interpretations and conclusions.
- .3 Available Project information, or any part thereof, shall not be construed as contract requirements unless also reflected in Drawings or Specifications, and in case of conflict, Drawings or Specifications shall govern.
- .4 Bidders, acting reasonably, may rely on available Project information in preparing their bids, subject to any qualifications stated in such available Project information and unless expressly stated otherwise.
- .5 Bidders are cautioned that such documents, by their nature, cannot reveal all conditions that exist or can occur at Place of the Work.
- .6 Should conditions at Place of the Work, in Consultant's opinion, be found to substantially vary from those identified in available Project information, then changes in the Work may need to be made, with appropriate adjustments being made to Contract Price and Contract Time.
- .7 Direct questions pertaining to available Project information by contacting issuing organization.

1.3 DESIGNATED SUBSTANCE SURVEYS AND AUDITS

- .1 A copy of a designated substance audit report with respect to Place of the Work is being made available as part of Bid Documents; described as follows:
Titled: Revised Pre-Renovation Designated Substances and Hazardous Materials Survey, Thomas A. Blakelock High School, 1160 Rebecca Street, Oakville, Ontario;
Project No.: 30217738;
Dated: April 9, 2024;
Prepared by: Arcadis Canada Inc.
- .2 Such reports identify locations and types of designated substances found to be present at Place of the Work, and may include recommendations for their safe removal and disposal.
- .3 Conditions at Place of the Work identified in the report are relevant only at time of survey.
- .4 The condition of some building materials may have changed.
- .5 Items discovered during execution of the Work that are not itemized within the report should be analytically tested by an accredited laboratory before further disturbance.

1.4 DOCUMENTS DESCRIBING EXISTING FACILITY

- .1 Documents describing existing facility and Place of the Work are being made available as part of Bid Documents; as described on the Cover Sheet of the Drawings.
- .2 These documents were prepared by others and neither Owner nor Consultant take responsibility for the accuracy of information, nor verify they represent actual conditions at Place of the Work.

END OF SECTION

- 1 General
- 1.1 AGREEMENT
 - .1 CCDC 3-2016 Cost Plus Contract, as amended below, forms the basis of Agreement between Owner and Contractor.
- 1.2 AMENDMENTS TO THE AGREEMENT
 - .1 Article A-4 - Cost of the Work
 - .1 Delete Paragraph A-4.1 in its entirety and replace with the following: *"The Cost of the Work, which excludes Value Added Taxes, shall be comprised of the stipulated sum costs of subsequently awarded Subcontracts, as nominated by the Owner, and the following:*
 - .1 *deposits lost;*
 - .2 *the costs to the Contractor that result from any Subcontractor's or Supplier's insolvency or failure to perform;*
 - .3 *royalties, patent license fees and damages for infringement of patents and cost of defending suits therefor subject always to the Contractor's obligations to indemnify the Owner as provided in paragraph 10.3.1 of GC 10.3 - PATENT FEES;*
 - .4 *losses and expenses sustained by the Contractor for matters which are the subject of insurance under the policies prescribed in GC 11.1 - INSURANCE when such losses and expenses are not recoverable because the amounts are in excess of collectible amounts or within the deductible amounts;*
 - .5 *legal costs, incurred by the Contractor, in relation to the performance of the Work provided that they are not caused by negligent acts or omissions of the Contractor and the Work is performed in accordance with the Contract Documents; and*
 - .6 *the cost of auditing when requested by the Owner.*

Notwithstanding the foregoing and any provisions contained in the General Conditions of the Contract, it is the intention of the parties that the Cost of the Work referred to herein shall cover and include any and all contingencies other than those which are the result of or occasioned by any failure on the part of the Contractor to exercise reasonable care and diligence in the Contractor's attention to the Work. Any cost due to failure on the part of the Contractor to exercise reasonable care and diligence in the Contractor's attention to the Work shall be borne by the Contractor."
 - .2 Article A-5 - Contractor's Fee
 - .1 Delete Paragraph A-5.1.1 in its entirety.
 - .3 Article A-7 - Options
 - .1 Delete Paragraph A-7.2 in its entirety.
 - .2 Delete Paragraph A-7.3 in its entirety.
 - .4 Article A-8 - Payment
 - .1 Revise Subparagraph A-8.1.1 to insert the phrase *"... make progress payments to Contractor subject to GC 5.4 - Progress Payment..."*.

END OF DOCUMENT

- 1 General
- 1.1 AGREEMENT
 - .1 CCA 1-2008 Stipulated Price Subcontract, as amended below, forms the basis of Agreement between Contractor and Subcontractor.
- 1.2 AMENDMENTS TO THE AGREEMENT
 - .1 Delete Article 1B in its entirety.
 - .2 Delete Article 2B in its entirety.
 - .3 Delete Article 3B in its entirety.
 - .4 Article 5 - SUBCONTRACT PRICE, delete Paragraph 5.5 in its entirety.
 - .5 Article 6 - PAYMENT, Paragraph 6.2, Third Sentence; revise to read as follows: *"The Contractor shall pay the Subcontractor, in accordance with the payment procedures required by the Contract Documents, no later than thirty (30) days after the date of the Consultant's certificate of payment, 90 percent of the amount applied for or such other amount as the Consultant determines to be properly due."*
 - .6 Article 6 - PAYMENT, Paragraph 6.4; revise to read as follows: *"... and for which the Contractor or Owner might in any way be held responsible ..."*
 - .7 Article 6 - PAYMENT, Paragraph 6.4; delete Subparagraph 6.4.2 in its entirety.

END OF DOCUMENT

- 1 General
- 1.1 AGREEMENT
 - .1 CCDC 3-2016 Cost Plus Contract, includes Definitions of specific words and terms.
- 1.2 SUPPLEMENTARY DEFINITIONS
 - .1 Amend the Definition of Contract Documents by inserting the words "*in writing*" after the words "*agreed upon*".
 - .2 Amend the Definition of Contractor's Fee by adding the following: "*... and including amounts for all overhead and profit, bond and insurance premiums, and any costs for labour and Products required by the Contractor to undertake portions of the Work identified in the Contract Documents and not included in an Owner-nominated Subcontract.*"
 - .3 Delete the Definition of Guaranteed Maximum Price ("GMP") in its entirety.
 - .4 Delete the Definition of Target Contract Price in its entirety.
 - .5 Add a new Definition for Bid Documents, as follows: "*The Bid Documents shall consist of the Contract Documents, Instructions to Bidders, Bid Form, and other available project information issued for the benefit of Bidders.*"

END OF DOCUMENT

1 General

1.1 AGREEMENT

- .1 CCA 1-2008 Stipulated Price Subcontract includes the Definitions of specific words and terms.

1.2 SUPPLEMENTARY SUBCONTRACT DEFINITIONS

- .1 Add a new Definition for Bid Documents, as follows: *"The Bid Documents shall consist of the Contract Documents, Instructions to Bidders, Bid Form, and other available project information issued for the benefit of bidders."*

END OF DOCUMENT

- 1 General
- 1.1 GENERAL CONDITIONS
 - .1 CCDC 3-2016, The General Conditions of the Cost Plus Contract is the General Conditions between Owner and Contractor.
- 1.2 SUPPLEMENTARY CONDITIONS
 - .1 Refer to Section 00 73 03 - Supplementary Conditions for amendments and supplements to General Conditions.
 - .2 Where a General Condition of the Contract or a paragraph of the General Conditions of the Contract is deleted by Supplementary Condition, the numbering of the remaining General Conditions or paragraphs shall remain unchanged, and the numbering of the deleted item will be retained, unused.

END OF DOCUMENT

1 General

1.1 SUBCONTRACT CONDITIONS

- .1 CCA 1-2008, The Subcontract Conditions of the Stipulated Price Subcontract are the Subcontract Conditions between Contractor and Subcontractors.

1.2 SUPPLEMENTARY SUBCONTRACT CONDITIONS

- .1 Refer to Section 00 73 11 - Supplementary Subcontract Conditions for amendments and supplements to Subcontract Conditions.
- .2 Where a Subcontract Condition of the Contract or a paragraph of the Subcontract Conditions of the Contract is deleted by Supplementary Subcontract Condition, the numbering of the remaining Subcontract Conditions or paragraphs shall remain unchanged, and the numbering of the deleted item will be retained, unused.

END OF DOCUMENT

1 Supplements to General Conditions

1.1 GC 1.1 - CONTRACT DOCUMENTS

- .1 Delete Paragraph 1.1.8 and replace with the following: *"The Contractor will be given one electronic-copy set of the Contract Documents without charge. The Contractor may produce as many hard-copy sets of the Contract Documents from the electronic-copy as they deem necessary to undertake the Work, at their own expense."*
- .2 Add new Paragraph 1.1.11 as follows: *"The location of fixtures, outlets, conduit, piping and any other locations shown or specified but not dimensioned shall be considered approximate. The actual location shall be as approved by the Consultant and as required to suit job conditions."*

1.2 GC 2.2 - ROLE OF THE CONSULTANT

- .1 Add new Subparagraph 2.2.7.1 as follows: *"Verbal instructions, regardless of the source, will not be binding on the parties to the Contract, unless otherwise confirmed in writing by the Owner or the Consultant ."*

1.3 GC 2.4 - DEFECTIVE WORK

- .1 Add new Paragraph 2.4.3 as follows: *"Where defective work or work not performed as provided in the Contract Documents is the responsibility of a Subcontractor or Supplier, the Contractor shall require the responsible Subcontractor or Supplier to Make Good the defective work or work not performed as provided in the Contract Documents so as to conform with the Contract Documents."*

1.4 GC 3.2 - CONSTRUCTION BY OWNER OR OTHER CONTRACTORS

- .1 Delete Paragraph 3.2.2 in its entirety.
- .2 Add new Subparagraph 3.2.2.5 as follows: *"Notify the Contractor no later than 2 Working Days prior to any other contractor or their own forces being on site. The Contractor will make all necessary arrangements to accommodate access and maintain compliance with applicable health and construction safety legislation at the Place of the Work".*
- .3 Revise Subparagraph 3.2.3.4 to read as follows: *"Assume overall responsibility for the separate contractors and Owner's own forces and for compliance with applicable health and construction safety legislation at the Place of the Work".*

1.5 GC 3.5 - CONSTRUCTION SCHEDULE

- .1 Add new Paragraph 3.5.2 as follows: *"Where portions of the Work are performed by Subcontractors or Suppliers, the Contractor shall coordinate with, and arrange for the Subcontractors and Suppliers to provide detailed construction schedules for their portion of the Work, to be submitted along with the construction schedule described herein."*
- .2 Add new Paragraph 3.5.3 as follows: *"No change in Contract Time resulting from a change in the Work will be accepted, if, in the Consultant's opinion, such change in the Work can reasonably be accommodated within the approved schedule."*
- .3 Amend Paragraph 3.5.1.1 by deleting the phrase *"... the first application for payment ..."* and replacing it with *"... commencing the work ..."*.

1.6 GC 3.7 - SUBCONTRACTORS AND SUPPLIERS

- .1 Revise Subparagraph 3.7.1.1 to read as follows: *"enter into contracts or written agreements with Subcontractors or Suppliers, including those nominated by the Owner, to require them to perform their work as provided in the Contract Documents;*
 - .1 *The Consultant will prepare the written agreements between the Contractor and each Subcontractor or Supplier, based upon a modified CCA 1-2008, Stipulated Price Subcontract, similar in content and intent of this Contract."*
- .2 Add new Subparagraph 3.7.1.4 as follows: *"immediately notify the Consultant of any acts or omissions of Subcontractors or Suppliers and of persons directly or indirectly employed by them."*
- .3 Add new Subparagraph 3.7.2.1 as follows: *"The Contractor shall not change or terminate Subcontractors or Suppliers without the prior written permission of the Owner."*
- .4 Add new Paragraph 3.7.6 as follows: *"The Owner may direct the Contractor to terminate the contract of a Subcontractor or Supplier and the Owner shall nominate a replacement Subcontractor or Supplier to complete that part or portion of the Work. The Contractor shall enter into a contract with the nominated Subcontractor or Supplier for the completion of that portion of the Work. In the event of such an instance, the Contract Time and the Contractor's Fee is to be adjusted by an appropriate amount. The Contractor may reasonably refuse to terminate the contract of a Subcontractor or Supplier if to comply with the Owner's direction would result in a breach of any of the Contractor's obligations under GC 9.4 - CONSTRUCTION SAFETY."*
- .5 Add new Paragraph 3.7.7 as follows: *"The Contractor shall involve the Consultant in any communications with the Subcontractors or Suppliers related to GC 3.5 - CONSTRUCTION SCHEDULE and PART 6 - CHANGES IN THE WORK. The Consultant may discuss issues directly with the Subcontractors and Suppliers related to GC 3.5 - CONSTRUCTION SCHEDULE and PART 6 - CHANGES IN THE WORK, however, the Consultant shall not direct or supervise the Work."*
- .6 Add new Paragraph 3.7.8 as follows: *"The Contractor shall enter into contracts or written agreements with Subcontractors for the Subcontracts identified in the Contract Documents. Such Subcontractors may be union or non-union affiliated. The Contractor shall not be party to any agreement that would prevent them from entering into such Subcontracts."*

1.7 GC 3.8 - LABOUR AND PRODUCTS

- .1 Add new Paragraph 3.8.3 as follows: *"The Contractor will cooperate with the Owner to avoid labour complications and will employ workers whose presence and work will be acceptable to, and be in harmony with, other workers employed on the Work, and under conditions satisfactory to the Owner. In the event of labour difficulties resulting from the employment of workers by the Contractor or by the presence of the Contractor on the Project, the Contractor will make any necessary arrangements as required by the Owner in order to prevent delays and additional expense to the Owner."*
- .2 Add new Paragraph 3.8.4 as follows: *"The Contractor is responsible for the safe on-site storage of Products and their protection (including Products supplied by the Owner) in such a way to avoid dangerous conditions or contamination to the Products or other person or property."*

1.8 GC 4.1 - CASH ALLOWANCES

- .1 Delete Paragraph 4.1.1 in its entirety.
- .2 Revise Paragraph 4.1.6 by deleting the phrase *"... and the Guaranteed Maximum Price ..."*.

- .3 Add new Paragraph 4.1.8 as follows: *"Unexpended Cash Allowances will be deducted from the Contract Price."*
- 1.9 GC 5.2 - ACCOUNTING AND AUDIT
 - .1 Revise Paragraph 5.2.1 by replacing the phrase "... Cost of the Work as in accordance with Article A-3 - CONTRACT DOCUMENTS." with *"... payments under the Contract."*
 - .2 Revise Paragraph 5.2.2 by replacing the phrase "... Cost of the Work ..." with *"... payments under the Contract ..."*.
- 1.10 GC 5.3 - APPLICATIONS FOR PROGRESS PAYMENT
 - .1 Revise Paragraph 5.3.1 to read as follows: *"The Contractor shall make monthly applications for payment on account as provided in Article A-8 of the Agreement - PAYMENT as the Work progresses."*
- 1.11 GC 5.4 - PROGRESS PAYMENT
 - .1 Revise Subparagraph 5.4.1.3 to read as follows: *"The Owner shall make payment to the Contractor on account as provided in Article A-8 of the Agreement - PAYMENT no later than fourteen calendar days after the date of a certificate for payment by the Consultant."*
 - .2 Add a new Paragraph 5.4.2 as follows: *"The Contractor shall make payments to the Subcontractors and Suppliers in the amounts certified as payable by the Consultant, no later than twenty calendar days after the date of the certificate for payment."*
- 1.12 GC 5.5 - SUBSTANTIAL PERFORMANCE OF THE WORK
 - .1 Add new Paragraph 5.5.4 as follows: *"The Contractor's application for a Certificate of Substantial Performance of the Work shall, without limiting the foregoing, include the following:*
 - .1 *A written statement to the Owner and the Consultant stating that:*
 - .1 *The Contract is substantially performed,*
 - .2 *The performance of the balance of the Contract is in process, and identifying the date when this Work will be completed. Where portions of the Contract can not be completed forthwith for reasons beyond the Contractor's control, the Contractor shall indicate completion dates for each outstanding portion of the Work."*
 - .2 *A statement showing the amount of holdback monies due for release and payment following the issue of the Certificate of Substantial Performance of the Work.*
 - .3 *A statement of completion with the cost value of:*
 - .1 *the portion of the Work to be completed, including any defective work or work not performed as provided in the Contract Documents.*
 - .2 *portions of the Work which can not be performed for reasons beyond the control of the Contractor.*
 - .4 *The submission of all data, operating instructions, maintenance manuals, record drawings, spare parts and materials, evidence of all tests, instructions to Owner's representatives, warranties and any other such documents to enable the Owner to operate and maintain the Project."*
 - .2 Add new Paragraph 5.5.5 as follows: *"When making an application for Substantial Performance of the Work, the Contractor shall submit to the Consultant all specified warranties, bonds, maintenance manuals, records, certificates and a Statutory Declaration in a form acceptable to the Consultant, signed by the Contractor, stating that all material, work and services in connection with the Contract have been paid in full, up to the holdback, and that no liens exist, including a receipt from each Subcontractor and Supplier, stating that it has been paid in full up to the holdback for all services and materials supplied in connection with this Contract, and such other statements as the Owner and Consultant may require."*

- 1.13 GC 5.8 - FINAL PAYMENT
- .1 Revise Paragraph 5.8.4 by replacing the words "... five calendar days ..." to read "... fourteen calendar days ...".
 - .2 Add new Paragraph 5.8.5 as follows: *"Subject to the lien legislation applicable to the Place of the Work, the Contractor shall make payments to the Subcontractors and Suppliers in the amounts certified as payable by the Consultant, no later than twenty calendar days after the date of the certificate for payment."*
- 1.14 GC 6.2 - CHANGE ORDER
- .1 Revise Paragraph 6.2.1 by deleting the phrase "... GMP or the Target Contract Price; ..." and replacing it with "... Contract Price; ...".
 - .2 Revise Paragraph 6.2.2 by deleting the phrase "... GMP, Target Contract Price, ..." and replacing it with "... Contract Price ...".
 - .3 Add new Paragraph 6.2.3 as follows: *"The value of a change to the Contractor's Fee shall be charged as a percentage of the actual increase to the Cost of the Work, as follows:*
 - .1 *On additional work performed by the Contractor's own forces: 5 percent;*
 - .2 *On additional work performed by Owner-Nominated Subcontractors and Suppliers: 0 percent; and*
 - .3 *On additional work performed by Contractor-appointed Subcontractors and Suppliers: 5 percent."*
- 1.15 GC 6.3 - CHANGE DIRECTIVE
- .1 Revise paragraph 6.3.1 by deleting the phrase "... in the GMP, in the Target Contract Price, ..." and replacing it with "... in the Contract Price, ...".
 - .1 Revise paragraph 6.3.7 by deleting the phrase "... to the GMP, to the Target Contract Price, ..." and replacing it with "... to the Contract Price, ...".
 - .2 Add new Paragraph 6.3.8 as follows: *"The value of a change to the Contractor's Fee shall be charged as a percentage of the actual increase to the Cost of the Work, as follows:*
 - .1 *On additional work performed by the Contractor's own forces: 5 percent;*
 - .2 *On additional work performed by Owner-Nominated Subcontractors and Suppliers: 0 percent; and*
 - .3 *On additional work performed by Contractor-appointed Subcontractors and Suppliers: 5 percent."*
- 1.16 GC 7.2 - CONTRACTOR'S RIGHT TO TERMINATE CONTRACT
- .1 Add new Paragraph 7.2.6 as follows: *"If the Contractor stops the Work or terminates the Contract as provided for in the preceding paragraphs, he shall ensure that the Place of the Work and the Work are left and maintained in a secure and safe condition as required by authorities having jurisdiction and these Contract Documents."*
- 1.17 GC 9.1 - PROTECTION OF WORK AND PROPERTY
- .1 Add new Paragraph 9.1.5 as follows: *"Should there be a stoppage of the Work, for any cause, the Contractor shall assume all responsibility for protecting the Work and Provide and maintain security to the Work and the Place of the Work during such periods, with appropriate adjustments being made to the Contractor's Fee and Contract Time when it can be proven that the stoppage of the Work was not caused by any action or lack of action on the part of the Contractor."*

1.18 GC 9.4 - CONSTRUCTION SAFETY

- .1 Amend Paragraph 9.4.1 by deleting the phrase "*Subject to paragraph 3.2.3.4 of GC 3.2 - CONSTRUCTION BY OWNER OR OTHER CONTRACTORS*".
- .2 Add new Paragraph 9.4.2 as follows: "*The Contractor shall comply and cause all of its Subcontractors and Suppliers to comply with all applicable provisions, requirements, and safety standards of the Ontario Occupational Health and Safety Act and regulations thereto. The Contractor shall be designated and hereby accepts the responsibilities and designation as "constructor" under the Occupational Health and Safety Act on the project and hereby assumes all liabilities and obligations imposed on a "constructor" by the Occupational Health and Safety Act*".
- .3 Add new Paragraph 9.4.3 as follows: "*Prior to commencement of the Work, the Contractor shall submit to the Owner:*
 - .1 *Documentation of a valid Workplace Safety and Insurance Board clearance certificate and confirmation of the Contractor's WSIB CAD-7 performance rating.*
 - .2 *Documentation of the Contractor's insurance coverage.*
 - .3 *Documentation of the Contractor's safety-related programs for the Project.*
 - .4 *A copy of the Notice of Project filed with the Ministry of Labour.*"
- .4 Add new Paragraph 9.4.4 as follows: "*The Contractor hereby represents and warrants to the Owner that appropriate health and safety instruction and training has been provided and will be provided to the Contractor's employees before the Work is commenced and agrees to provide to the Owner and Consultant satisfactory proof of such instruction and training. The Contractor further undertakes to verify that other contractors and the Owner's own forces have received appropriate health and safety instruction and training in accordance with GC 3.2.*"
- .5 Add new Subparagraph 9.4.4.1 as follows: "*The Contractor shall require proof from the Subcontractors and Suppliers that appropriate health and safety instruction and training has been provided to the Subcontractor's and Supplier's employees before the Work is commenced. This information will be kept on file at the site.*"
- .6 Add new Paragraph 9.4.5 as follows: "*The Contractor shall tour the appropriate area to familiarize itself with the job site prior to the commencement of the Work*",
- .7 Add new Paragraph 9.4.6 as follows: "*The Contractor shall never work in a manner that may endanger anyone*".
- .8 Add new Paragraph 9.4.7 as follows: "*The Contractor shall indemnify and save harmless the Owner, together with the Owner's agents, officers, directors, employees, consultants, successors and assigns, from and against any and all safety infractions under the Ontario Occupational Health and Safety Act, and regulations thereto including the payment of all legal fees on a solicitor and client basis.*"
- .9 Add new Paragraph 9.4.8 as follows: "*The Contractor shall ensure that its employees, Subcontractors and Suppliers comply with the foregoing conditions*".

1.19 GC 10.1 - TAXES AND DUTIES

- .1 Add new Paragraph 10.1.2 as follows: "*With respect to taxes and duties, the Contractor shall, at the request of the Owner, assist, join in, or at the Owner's expense, make application on behalf of the Owner for any exemption, recovery or refund. The Contractor shall provide the Owner with copies, or, where required original of records, invoices, purchase orders or other documentation as may be necessary to support such application.*"

- .2 Add new Paragraph 10.1.3 as follows: *"Any amount included in the Contract or any Subcontract for tax or duty, whether or not paid, which is found to be inapplicable or for which a refund is obtained shall become the sole and exclusive property of the Owner."*

1.20 GC 10.2 - LAWS, NOTICES, PERMITS & FEES

- .1 Add to Paragraph 10.2.2 as follows: *"The Contractor shall take all necessary steps to obtain the occupancy permit, including delivering any notice of completion of the building required by the authorities having jurisdiction."*
- .2 Add new Paragraph 10.2.8 as follows: *"The Contractor's or its Subcontractor's or Supplier's compliance with statutes or regulations made thereunder or by-laws shall not relieve them of obligations set out in the Contract Documents which may be more extensive than the requirements of those statutes, regulations or by-laws."*

1.21 GC 11.1 - INSURANCE

- .1 Delete Subparagraph 11.1.1.1 in its entirety and replace with the following: *"General liability insurance shall be in the joint names of the Contractor, the Owner, the Consultant, and any and all Subcontractors and subconsultants involved in the Work, with limits not less than \$10,000,000 per occurrence and with a property damage deductible not exceeding \$10,000. The insurance coverage shall include at least the following extensions: Premises, Property and Operations; Occurrence basis, Owners/Contractors protective, Products and Completed Operations; Blanket Contractual; Employees as Additional Insureds; Broad Form Property Damage; Broad Form Loss of Use; Personal Injury; Incidental Malpractice; Contingent Employers Liability; Cross Liability/Severability of Interests; Non-Owned Automobile Liability including Endorsement Form 96; Intentional Injury to protect persons or property, X-plate/unlicensed/specially licensed vehicles; Attached Machinery; Hostile fire exception to any pollution exclusion; Voluntary Medical Payments. To achieve the desired limit, umbrella or excess liability insurance may be used. All liability coverage shall be maintained for the completed operations hazard from the date of Substantial Performance of the Work, for 24 months following. The Policy shall be endorsed to provide the named insureds with not less than 30 days notice in writing in advance of any cancellation or change or amendment restricting coverage."*
- .2 Delete Subparagraph 11.1.1.2 in its entirety.
- .3 Delete Subparagraph 11.1.1.3 in its entirety.
- .4 Delete Subparagraph 11.1.1.4 in its entirety.
- .5 Delete Subparagraph 11.1.1.5 in its entirety.
- .6 Delete Subparagraph 11.1.1.6 in its entirety.
- .7 Delete Subparagraph 11.1.1.7 in its entirety.
- .8 Add new Paragraph 11.1.7 as follows: *"Notwithstanding the fact that a claim has been made under any insurance policy described in GC 11.1, the Contractor shall continue to perform its obligations under the Contract ."*

1.22 GC 11.2 - CONTRACT SECURITY

- .1 Add new Paragraph 11.2.3 as follows: *"The Contractor shall obtain and submit a Performance Bond in the name of the Owner for Fifty Percent (50%) of the Contract Price, to assure the faithful performance of the Contract, including corrections to the Work required under GC 12.3 - Warranty; on Ontario Construction Act Form 32, Performance Bond Under Section 85.1 of the Act."*

- .2 Add new Paragraph 11.2.4 as follows: *"The Contractor shall also obtain and submit a Labour and Material Payment Bond in the name of the Owner for Fifty Percent (50%) of the Contract Price, to assume faithful payment of monies to parties in contract with the Contract; on Ontario Construction Act Form 31, Labour and Material Payment Bond Under Section 85.1 of the Act."*

1.23 GC 12.3 - WARRANTY

- .1 Add new Paragraph 12.3.7 as follows: *"Should the Work be delayed due to conditions beyond the control of the Contractor, the warranty period shall commence at the time of acceptance of the Work by the Owner."*
- .2 Add new Paragraph 12.3.8 as follows: *"Where warranty repairs on such parts or portions of the Work become necessary, the Consultant will notify the Contractor which Subcontractor or Supplier is responsible to rectify the defective work or work not performed as provided in the Contract Documents."*

END OF DOCUMENT

- 1 Supplements to Subcontract Conditions
- 1.1 SCC 1.1 - DOCUMENTS
 - .1 Delete Subparagraph 1.1.7.2 in its entirety.
 - .2 Revise Paragraph 1.1.8 as follows: *"The Consultant shall make available to the Subcontractors, without charge, ..."*
 - .3 Add new Paragraph 1.1.9 as follows: *"The location of fixtures, outlets, conduit, piping and any other locations shown or specified but not dimensioned shall be considered approximate. The actual location shall be as approved by the Consultant and as required to suit job conditions."*
- 1.2 SCC 2.2 - REVIEW AND INSPECTION OF THE WORK
 - .1 Revise Paragraph 2.2.2 as follows: *"... the Subcontractor shall give the Contractor and Consultant timely notice requesting inspection."*
- 1.3 SCC 2.3 - DEFECTIVE WORK
 - .1 Revise Paragraph 2.3.1 as follows: *"The Subcontractor shall within 5 Working Days remove from the Place of the Work and Make Good defective work that has been rejected by the Contractor or Consultant as failing to conform to the Contract Documents ..."*
- 1.4 SCC 3.4 - SUB-SUBCONTRACTORS
 - .1 Revise Subparagraph 3.4.1.3 as follows: *"be as fully responsible to the Contractor, Owner and Consultant for acts and omissions of Sub-Subcontractors and of persons directly or indirectly employed by them as for acts and omissions of persons directly employed by the Subcontractor."*
 - .2 Revise Paragraph 3.4.6 as follows: *"The Contractor or Consultant may provide to a Sub-Subcontractor information as to the percentage ..."*
- 1.5 SCC 3.5 - SHOP DRAWINGS
 - .1 Revise Paragraph 3.5.2 as follows: *"The Consultant shall determine the number of copies of Shop Drawings ...the Subcontractor shall notify the Contractor and Consultant in writing of any deviations ..."*
- 1.6 SCC 3.7 - CUTTING AND REMEDIAL WORK
 - .1 Revise Paragraph 3.7.3 as follows: *"... nor alter the work of any others without the Contractor's and Consultant's written consent, where such member, existing work or other work is apparent from the Subcontract Documents, reasonable examination or instruction of the Consultant."*
 - .2 Add a new Paragraph 3.7.6 as follows: *"Each Subcontractor shall make allowances in his own work to accommodate other Subcontractor's work. The Contractor shall coordinate the cutting and remedial work amongst Subcontractors such that all pieces come together properly."*
- 1.7 SCC 4.1 - CASH ALLOWANCES
 - .1 Revise Paragraph 4.1.3 to read as follows: *"Expenditures under cash allowances shall be authorized by the Consultant."*
- 1.8 SCC 5.1 - APPLICATIONS FOR PAYMENT
 - .1 Revise Paragraph 5.1.2 as follows: *"The Subcontractor shall submit to the Contractor for the Consultant's approval before the first application ..."*

- .2 Revise Paragraph 5.1.3 as follows: "... supported by such evidence as the Consultant may reasonably direct and when accepted by the Contractor, with the approval of the Consultant, shall ..."
 - .3 Add new Paragraph 5.1.6 as follows: "Each application for payment must include the Subcontractor's HST Registration number."
 - .4 Add new Paragraph 5.1.7 as follows: "The Subcontractor shall submit with every application for payment, a "Certificate of Standing" from the Workplace Safety & Insurance Board (WSIB) stating that the Subcontractor has complied with the requirements of the Workers' Compensation Act and is in good standing as of the date of the Certificate."
- 1.9 SCC 6.1 - CONTRACTOR'S RIGHT TO MAKE CHANGES
- .1 Revise Paragraph 6.1.1 as follows: "The Contractor, with the approval of the Consultant, and without invalidating the Subcontract, may make changes ...".
 - .2 Add new Paragraph 6.1.3 as follows: "The Subcontractor shall respond to requests for information pertaining to changes within 10 Working Days of receipt of such requests."
- 1.10 SCC 6.2 - CHANGE ORDER
- .1 Revise Paragraph 6.2.2 as follows: "When the Contractor, with the approval of the Consultant, and the Subcontractor agree ..."
 - .2 Add new Paragraph 6.2.3 as follows: "The value of a change shall be determined by actual credits and cost to the Subcontractor. Where additional work is required, the value of the change shall be the actual cost plus a percentage covering overhead and profit, after all credits included in the change have been deducted. The following percentage fee for overhead and profit shall be applied to additional work:
 - .1 On work performed by the Subcontractor's own forces: the Subcontractor may charge a maximum of 5 percent combined percentage for overhead and profit;
 - .2 On work performed by Sub-Subcontractors, the Sub-Subcontractors may charge a maximum of 5 percent combined percentage for overhead and profit; and
 - .3 On work performed by Sub-Subcontractors, the Subcontractor may charge a maximum of 5 percent combined percentage for overhead and profit on work performed by the Sub-Subcontractors."
- 1.11 SCC 6.3 - CHANGE DIRECTIVE
- .1 Revise Paragraph 6.3.1 as follows: Insert "... prior to the Contractor receiving the approval of the Consultant..."
 - .2 Revise Paragraph 6.3.6 as follows: "The value of a change shall be determined by actual credits and cost to the Subcontractor. Where additional work is required, the value of the change shall be the actual cost plus a percentage covering overhead and profit, after all credits included in the change have been deducted. The following percentage fee for overhead and profit shall be applied to additional work:
 - .1 On work performed by the Subcontractor's own forces: the Subcontractor may charge a maximum of 5 percent combined percentage for overhead and profit;
 - .2 On work performed by Sub-Subcontractors, the Sub-Subcontractors may charge a maximum of 5 percent combined percentage for overhead and profit; and
 - .3 On work performed by Sub-Subcontractors, the Subcontractor may charge a maximum of 5 percent combined percentage for overhead and profit on work performed by the Sub-Subcontractors."
 - .3 Revise Subparagraph 6.3.7.1 as follows: "... under a salary or wage schedule approved by the Contractor and the Consultant, or in the absence ..."

- .4 Revise Paragraph 6.3.12 as follows: *"If the Contractor, does not have the approval of the Consultant or the Contractor and the Subcontractor do not agree ..."*.
 - .5 Revise Paragraph 6.3.13 as follows: *"When the Contractor, with the approval of the Consultant, and the Subcontractor reach an agreement on the adjustment to the Subcontract Price and to the Subcontract Time...."*
- 1.12 SCC 6.4 - CONCEALED OR UNKNOWN CONDITIONS
- .1 Revise Paragraph 6.4.1 as follows: *"... shall notify the other party and the Consultant ..."*.
 - .2 Revise Paragraph 6.4.2 as follows: *"The Contractor and the Consultant will promptly investigate such conditions and the Consultant will make a finding...."*
 - .3 Revise Paragraph 6.4.3 as follows: *"If the Consultant finds that the conditions ... are not materially different ... the Consultant shall report the reasons for his finding to the Contractor and Subcontractor in writing."*
- 1.13 SCC 6.5 - DELAYS
- .1 Revise Paragraph 6.5.1 as follows: *"... then the Subcontract Time shall be extended for such reasonable time as the Contractor, with the approval of the Consultant and the Subcontractor shall agree that the Subcontract Work was delayed. The Subcontractor shall be reimbursed for reasonable costs incurred by the Subcontractor as a result of such delay."*
 - .2 Revise Paragraph 6.5.2 as follows: *"... then the Subcontract Time shall be extended for such reasonable time as the Contractor, with the approval of the Consultant and Subcontractor shall agree that the Subcontract Work was delayed. The Subcontractor shall be reimbursed for reasonable costs incurred by the Subcontractor as a result of such delay."*
 - .3 Revise Paragraph 6.5.4 as follows: *"... unless notice in writing of claim is given to the Contractor and Consultant not later than ..."*.
 - .4 Revise Paragraph 6.5.5 as follows: *"... no request for extension shall be made as a result of failure of the Contractor or Consultant to furnish instructions ..."*.
- 1.14 SCC 7.2 - SUBCONTRACTOR'S RIGHT TO STOP THE SUBCONTRACTS WORK OR TERMINATE THE SUBCONTRACTS
- .1 Revise Paragraph 7.2.1 as follows *"...terminate the Subcontract and such notice shall be provided to the Consultant."*
 - .2 Revise Paragraph 7.2.2 as follows: *"...terminate the Subcontract and such notice shall be provided to the Consultant."*
 - .3 Revise Paragraph 7.2.3 to read as follows: *"The Subcontractor may notify the Contractor in writing that the Contractor is in default of their contractual obligation if payment is not received as stated in Article 4 of the Subcontract Agreement - PAYMENT and the Subcontractor shall deliver a copy of such notice to the Consultant"*
 - .4 Revise Paragraph 7.2.4 by deleting the phrase *"... to the Contractor ..."*. Add a new Sentence to read as follows: *"The Owner may remedy the Contractor's default and the Subcontractor agrees to continue to complete the Subcontract Work for the Owner or a new Contractor nominated by the Owner"*.

1.15 SCC 9.2 - TOXIC OR HAZARDOUS SUBSTANCES AND MATERIALS

- .1 Revise the last sentence in Paragraph 9.2.2 as follows: *"The expert's report shall be delivered to the Consultant, the Contractor and the Subcontractor."*
- .2 Revise Subparagraph 9.2.3.3 as follows: *"extend the Subcontract Time for such reasonable time as the Contractor, with the approval of the Consultant, and in consultation with the Subcontractor ..."*.

1.16 SCC 9.4 - CONSTRUCTION SAFETY

- .1 Add new Paragraph 9.4.2 as follows: *"Prior to commencement of the Work, the Subcontractor shall submit to the Contractor:*
 - .1 *Documentation of a valid Workplace Safety and Insurance Board clearance certificate and confirmation of the Subcontractor's WSIB CAD-7 performance rating.*
 - .2 *Documentation of the Subcontractor's insurance coverage.*
 - .3 *Documentation of the Subcontractor's safety-related programs for the Project.*
 - .4 *A copy of the Subcontractor's Form of Notification."*

1.17 SCC 9.5 - MOULD

- .1 Revise the last sentence in Subparagraph 9.5.1.3 as follows: *"The expert's report shall be delivered to the Consultant, the Contractor and the Subcontractor."*
- .2 Revise Subparagraph 9.5.2.3 as follows: *"extend the Subcontract Time for such reasonable time as the Contractor, with the approval of the Consultant, and in consultation with the Subcontractor ..."*.

1.18 SCC 10.1 - TAXES AND DUTIES

- .1 Revise Paragraph 10.1.1 by replacing the original term "taxes and customs duties" with the new term *"taxes, duties and tariffs"*.
- .2 Revise Paragraph 10.1.2 by replacing the original term "taxes and duties" with the new term *"taxes, duties and tariffs"*.
- .3 Add new Paragraph 10.1.3 as follows: *"To the extent that the Subcontractor is importing Products, and new taxes, duties and tariffs are placed upon such Products after the time of the bid closing, then the following shall apply:*
 - .1 *"The Subcontractor shall notify the Owner, Consultant, and Contractor of the price impact of new taxes, duties and tariffs (whether imposed directly by Canada or indirectly by another Country on the necessary supply chain imports prior to coming into Canada). Such notice shall include:*
 - .1 *A detailed description of the new taxes, duties and tariffs, including the rates, amounts, and specific Products affected; and*
 - .2 *Supporting documentation demonstrating the direct impact of the new taxes, duties and tariffs on the Subcontract.*
 - .2 *"The Subcontractor shall take reasonable measures to mitigate the impact of the new taxes, duties and tariffs, including but not limited to:*
 - .1 *Identifying and proposing cost-effective substitute Products available in Canada or other jurisdictions that comply with the Subcontract Documents. If no acceptable substitute Products are available, the Subcontractor shall submit a written explanation to the Owner, Consultant and Contractor, supported by evidence of the Subcontractor's efforts to source acceptable substitute Products.*
 - .2 *Advancing importation of the Products across the border prior to the enactment of the new taxes, duties and tariffs, where reasonably feasible; and*
 - .3 *Exploring and implementing other reasonable measures to avoid or minimize related costs.*

- .3 *"The Subcontractor shall prepare and submit a New Taxes, Duties and Tariffs Proposal, that shall include:*
 - .1 *Documentation of the direct costs or savings reasonably incurred solely due to the new taxes, duties and tariffs;*
 - .2 *A proposed adjustment to the Subcontract Price, limited to such documented costs, if the Subcontractor continues with the imported Products;*
 - .3 *A cost-benefit analysis comparing the use of imported Products with proposed substitute Products, if available;*
 - .4 *Any proposed adjustment to the Subcontract Price and Subcontract Time if a proposed substitute Product is approved for use by the Owner and Consultant; and*
 - .5 *Any additional information reasonably requested by the Owner, Consultant, or Contractor.*
 - .4 *"On receipt of the New Taxes, Duties and Tariffs Proposal, the Owner, through the Consultant, shall promptly deliver a Notice in Writing to the Contractor and Subcontractor, instructing them to:*
 - .1 *Proceed with the imported Products with the change to the Subcontract Price recorded in a Change Order; or*
 - .2 *Proceed with the proposed substitute Products, with the change to the Subcontract Price and Subcontract Time recorded in a Change Order; or*
 - .3 *Submit additional information or clarification to facilitate the Owner's decision.*
 - .5 *"Any adjustment to the Subcontract Price on account of new taxes, duties and tariffs shall be strictly limited to the actual, demonstrable, substantiated, and auditable direct costs or savings reasonably incurred by the Subcontractor due to the new taxes, duties and tariffs."*
 - .4 Add new Paragraph 10.1.4 as follows: *"With respect to taxes, duties and tariffs, the Subcontractor shall, at the request of the Contractor, assist, join in, or at the Contractor's expense, make application on behalf of the Contractor for any exemption, recovery or refund. The Subcontractor shall submit to the Contractor copies, or, where required original of records, invoices, purchase orders or other documentation as may be necessary to support such application."*
 - .5 Add new Paragraph 10.1.5 as follows: *"Any amount included in the Subcontract for taxes, duties and tariffs, whether or not paid, which is found to be inapplicable or for which a refund is obtained shall become the sole and exclusive property of the Contractor."*
- 1.19 SCC 10.2 - LAWS, NOTICES, PERMITS & FEES
- .1 Revise Paragraph 10.2.5 as follows: *"... the Subcontractor shall notify the Contractor and Consultant in writing requesting direction immediately upon such variance or change becoming known. The Consultant will make the changes required to the Contract Documents..."*
 - .2 Revise Paragraph 10.2.6 as follows: *"If the Subcontractor fails to notify the Contractor and the Consultant in writing; and ..."*
 - .3 Add new Paragraph 10.2.8 as follows: *"The Contractor's and Subcontractor's compliance with statutes or regulations made thereunder or by-laws shall not relieve them of obligations set out in the Contract Documents which may be more extensive than the requirements of those statutes, regulations or by-laws."*
- 1.20 SCC 11.1 - INSURANCE
- .1 Revise Paragraph 11.1.1 as follows: *"Without restricting the generality of SCC 12.1 - INDEMNIFICATION, the Contractor will arrange for a project specific 'Wrap-up Liability' policy in the amounts of not less than \$10,000,000 per occurrence with a property damage deductible not exceeding \$10,000 on behalf of, and indemnification of the Owner, the*

Consultants, *the Contractor, the Subcontractors, and any other parties as instructed by the Owner. The Subcontractor shall be responsible for the following insurance policies:*

- .1 *"Subcontractor's Equipment Insurance covering construction machinery and equipment used by the Subcontractor for the performance of the Work. Such insurance shall be on an 'all risks' basis and be endorsed to provide the Consultant and the Owner with not less than 30 days notice in writing in advance of any cancellation, and of any change or amendment restricting coverage.*
- .2 *"Automobile liability insurance in respect of licensed vehicles with limits of not less than \$10,000,000 inclusive per occurrence for bodily injury, death and damage to property, and covering all licensed vehicles owned or leased by the Subcontractor. This automobile liability insurance shall be endorsed to provide the Consultant and the Owner with not less than 30 days notice in writing in advance of any cancellation, and of any change or amendment restricting coverage. Where the policy has been issued pursuant to a government-operated automobile system, the Subcontractor shall provide the Owner with confirmation of automobile insurance coverage for all automobiles registered in the name of the Subcontractor."*

1.21 SCC 11.2 - CONTRACT SECURITY

- .1 Delete Paragraph 11.2.2 in its entirety.

1.22 SCC 12.1 - INDEMNIFICATION

- .1 Add new Paragraph 12.1.7 as follows: *"The Subcontractor shall indemnify and hold harmless the Contractor, the Owner, and the Consultant, their agents and employees from and against claims, demands, losses, costs, damages, actions, suits, or proceedings (hereinafter called "claims"), suffered or incurred on account of any obligation or a provision in the Subcontract Documents, or attributable to, the Subcontractor's performance of the Subcontract. The Subcontractor assumes towards the Contractor all the obligations and responsibilities that Contractor assumes towards Owner as set forth in the Contract Documents, insofar as applicable, generally or specifically, to the materials to be furnished and the Subcontract Work to be performed under this Subcontract"*.

1.23 SCC 12.3 - WARRANTY

- .1 Add new Paragraph 12.3.7 as follows: *"Should the Work be delayed due to conditions beyond the control of the Subcontractor, the warranty period shall commence at the time of acceptance of the Work by the Owner."*

END OF DOCUMENT

1 General

1.1 PROJECT DESCRIPTION

- .1 Work of Contractor package and several separate Subcontract packages to be performed under a single Cost Plus Contract comprises the Project, known as:

Construction of the
T. A. BLAKELOCK H.S. RENOVATIONS - PHASE E

located at:
1160 Rebecca Street,
Oakville, Ontario;

and further identified as:
HDSB RFT # 26-075, and
SAi Project No.: 2215E.

1.2 CONTRACT DOCUMENTS

- .1 Refer to CCDC 3, GC 1.1 and CCA 1, SCC 1.1.
- .2 Contract Documents were prepared by Consultant for the account of Owner. Information contained herein reflects Consultant's best judgement in light of information available to Consultant at time of preparation. Any use which a third party makes of Contract Documents, or any reliance on or decisions to be made based on them, are the responsibility of such third parties. Consultant accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions based on Contract Documents.
- .3 Specifications are written in imperative mood in an abbreviated form. Imperative language of the Specifications is directed to Contractor, unless specifically noted otherwise. Incomplete sentences shall be completed by inserting "shall", "Contractor shall", and "shall be", and similar mandatory phrases by inference in the same manner as they are applied to notes on Drawings. The words "shall be" will be supplied by inference where a colon (:) is used within sentences and phrases. Except where worded to the contrary, fulfil and perform indicated requirements whether stated imperatively or otherwise.

1.3 CONTRACT METHOD

- .1 Single Construction Contract: Contractor shall construct the Work under a CCDC 3, Cost Plus contract.
- .2 Throughout execution of the Project, Consultant may bid portions of the Project and nominate Subcontractors, whose parts or portions of the Project will be incorporated as part of this Contract to make up the Work.
- .3 Consultant will prepare stipulated price CCA 1 Subcontracts for execution between Contractor and Subcontractors.
- .4 Refer to Supplementary Conditions and Supplementary Subcontract Conditions for information pertaining to contractual relationship between Contractor and Subcontractors.

1.4 ADMINISTRATIVE / PROCEDURAL SECTIONS APPLICABLE TO ALL CONTRACTS AND SUBCONTRACTS

- .1 Section 01 12 00 - Multiple Contract Summary.
- .2 Section 01 14 00 - Work Restrictions.
- .3 Section 01 21 00 - Allowances.

- .4 Section 01 23 00 - Alternatives.
 - .5 Section 01 25 00 - Substitution Procedures.
 - .6 Section 01 26 00 - Contract Modification Procedures.
 - .7 Section 01 31 00 - Project Management and Coordination.
 - .8 Section 01 32 00 - Construction Progress Documentation.
 - .9 Section 01 33 00 - Submittal Procedures.
 - .10 Section 01 35 00 - Special Procedures.
 - .11 Section 01 40 00 - Quality Requirements.
 - .12 Section 01 60 00 - Product Requirements.
 - .13 Section 01 71 00 - Examination and Preparation Procedures.
 - .14 Section 01 73 00 - Execution.
 - .15 Section 01 73 29 - Cutting and Patching.
 - .16 Section 01 74 00 - Cleaning and Waste Management.
 - .17 Section 01 75 00 - Starting and Adjusting.
 - .18 Section 01 76 00 - Protecting Installed Construction.
 - .19 Section 01 77 00 - Closeout Procedures.
 - .20 Section 01 78 00 - Closeout Submittals.
 - .21 Section 01 79 00 - Demonstration and Training.
- 1.5 CONTRACT C00 - CONTRACTOR
- .1 Assume total control of the Works of the Project. Be responsible for coordination, sequencing and scheduling of work of all Subcontracts, ensure conformity with Contract Documents.
 - .2 Assume sole responsibility for construction means, methods, techniques, sequences and procedures, including site usage; provision of temporary utilities, facilities and services; quality control and coordination of testing and inspection services; and site administration.
 - .3 Fulfill role of "constructor" as defined by Ontario Occupational Health and Safety Act (Construction Projects). File required Notice of Project and carry out and enforce the provisions of the Act and requirements of Project Health and Safety Policy.
 - .4 Report directly to Consultant.
 - .5 Conduct site management duties for duration of the Project, including field engineering services necessary to layout Project and ensure accurate working lines and levels for Subcontract Work. Refer to Section 01 71 00.
 - .6 Appoint a single supervisor for duration of Contract, until completion of Contract. Refer to GC 3.6 - Supervision.
 - .7 Arrange for minimum one labourer to be present at Place of the Work each Working Day until completion of Contract.
 - .8 Arrange and pay for publication of Project's Certificate of Substantial Performance of the Work.

- .9 Monitor site cleanliness on a daily basis and ensure conformance to requirements of authorities having jurisdiction with respect to waste audits and waste reduction work plans. Provide waste containers at Place of the Work, and arrange for periodic waste removal as necessary until completion of Contract.

1.6 COMMON REQUIREMENTS APPLICABLE TO SUBCONTRACTORS

- .1 Report directly to Contractor on matters pertaining to execution of the Work.
- .2 Provide and perform the following:
 - .1 Electrical extension cords from distribution sources, work lights and any special power required for Subcontract Work.
 - .2 Separate telephone service required for Subcontract Work.
 - .3 Water hoses required for Subcontract Work.
 - .4 Field offices and sheds required for Subcontract Work.
 - .5 Cleaning of Subcontract Work; delivery of debris to collection.
- .3 Maintain site cleanliness on a daily basis as applicable to Subcontract and ensure conformance to requirements of authorities having jurisdiction with respect to waste audits and waste reduction work plans.
- .4 Sections listed as part of a particular Subcontract package may include work described under other Sections. When referenced as a Related Section, include such portions of the Work as part of that particular Subcontract.
- .5 Include the following:
 - .1 Division 00 - Procurement and Contracting Requirements
 - .1 00 52 11 - Subcontract Agreement
 - .2 00 71 11 - Subcontracting Definitions
 - .3 00 72 11 - Subcontract Conditions
 - .4 00 73 11 - Supplementary Subcontract Conditions.
 - .2 Division 01 - General Requirements
 - .1 Administrative / procedural sections applicable to all contracts as listed above.

1.7 SUBCONTRACT SC01 - GENERAL

- .1 Provide and maintain Project temporary utilities, temporary facilities, and temporary controls as specified in Section 01 50 00.
- .2 Perform Project final cleaning as specified in Section 01 74 00.
- .3 Retain and pay for integrated system testing agency to conduct integrated system testing of fire protection and life safety systems as specified in Section 01 77 00.
- .4 Provide cast-in-place concrete elements, complete with concrete forming, accessories, reinforcement, and finishing as specified on Drawings.
- .5 Provide structural steel framing, steel joists, and steel decking as specified on Drawings.
- .6 Include the following:
 - .1 Division 04 - Masonry
 - .1 04 00 00 - Masonry
 - .2 Division 05 - Metals
 - .1 05 50 00 - Metal Fabrications
 - .3 Division 06 - Wood, Plastics and Composites
 - .1 06 10 00 - Rough Carpentry
 - .2 06 16 43 - Gypsum Sheathing
 - .3 06 20 00 - Finish Carpentry
 - .4 06 24 00 - High Pressure Decorative Laminate
 - .5 06 41 00 - Architectural Wood Casework

- .4 Division 07 - Thermal and Moisture Protection
 - .1 07 21 00 - Thermal Insulation
 - .2 07 21 19.13 - Foamed-in-Place Urethane Insulation
 - .3 07 26 00 - Vapour Retarders
 - .4 07 27 00 - Air Barriers
 - .5 07 81 00 - Applied Fireproofing
 - .6 07 84 00 - Firestopping
 - .7 07 92 00 - Joint Sealants
 - .8 07 92 21 - Sprayed Foam Sealants
- .5 Division 08 - Openings
 - .1 08 12 13 - Hollow Metal Frames
 - .2 08 13 13 - Hollow Metal Doors
 - .3 08 31 00 - Access Doors and Panels
 - .4 08 51 13 - Aluminum Windows
 - .5 08 71 00 - Door Hardware
 - .6 08 80 00 - Glazing
- .6 Division 09 - Finishes
 - .1 09 90 00 - Painting and Coating
 - .2 09 96 13 - Abrasion-Resistant Coatings
- .7 Division 10 - Specialties
 - .1 10 11 00 - Visual Display Surfaces
 - .2 10 14 00 - Signage
- .8 Division 12 - Furnishings
 - .1 12 24 13.16 - Manual Roller Window Shades
 - .2 12 56 34 - Music Room Furniture.
- 1.8 SUBCONTRACT SC02 - MECHANICAL
 - .1 Mechanical Subcontract scope of work is noted on Drawings.
- 1.9 SUBCONTRACT SC03 - ELECTRICAL
 - .1 Include the following:
 - .1 Division 26 - Electrical
 - .1 26 05 00 - Electrical Basic Materials and Methods
 - .2 26 05 19 - Low Voltage Cables
 - .3 26 05 19.01 - Appendix to Low Voltage Cables
 - .4 26 05 26 - Grounding and Bonding
 - .5 26 05 46 - Vibration Isolation and Seismic Restraints
 - .6 26 05 70 - Electrical Work Analysis and Testing
 - .7 26 09 00 - Lighting Control
 - .8 26 27 19 - Surface Raceways
 - .9 26 27 26 - Wiring Devices
 - .10 26 28 00 - Low Voltage Circuit Protective Devices
 - .11 26 50 00 - Lighting
 - .2 Division 27 - Communications
 - .1 27 10 00 - Structured Cabling
 - .3 Division 28 - Electronic Safety and Security
 - .1 28 31 00 - Existing Fire Alarm Work.
- 1.10 SUBCONTRACT SC04 - METAL WALL PANELS
 - .1 Include the following:
 - .1 Division 07 - Thermal and Moisture Protection
 - .1 07 42 43 - Composite Wall Panels.

1.11 SUBCONTRACT SC05 - FLOORING

- .1 Include the following:
 - .1 Division 09 - Finishes
 - .1 09 65 13 - Resilient Base and Accessories
 - .2 09 65 19 - Resilient Tile Flooring
 - .3 09 65 66 - Resilient Athletic Flooring
 - .4 09 66 13 - Portland Cement Terrazzo Flooring
 - .5 09 68 13 - Tile Carpeting.

1.12 SUBCONTRACT SC06 - DRYWALL AND ACOUSTICS

- .1 Provide loadbearing lightweight metal framing systems as specified on Drawings.
- .2 Include the following:
 - .1 Division 09 - Finishes
 - .1 09 21 16 - Gypsum Board Assemblies
 - .2 09 51 23 - Acoustical Tile Ceilings
 - .3 09 81 00 - Acoustic Insulation
 - .4 09 84 13 - Fixed Sound-Absorptive Panels.

1.13 SUBCONTRACT SC07 - DEMOLITION

- .1 Include the following:
 - .1 Division 02 - Existing Conditions
 - .1 02 41 19 - Selective Demolition.

END OF SECTION

- 1 General
- 1.1 CONTRACTOR ACCESS TO AND USE OF PLACE OF THE WORK
 - .1 Contractor shall limit use of existing facility, including Place of the Work, for execution of the Work, for storage, and for access, to allow:
 - .1 Owner occupancy,
 - .2 Work by other contractors, and
 - .3 Public usage.
- 1.2 OWNER OCCUPANCY OF EXISTING FACILITIES
 - .1 Owner will occupy existing facilities during entire construction period for execution of normal operations.
 - .2 Cooperate with Owner in scheduling operations to minimize conflict, and to facilitate Owner usage.
- 1.3 PARTIAL OWNER OCCUPANCY OF THE WORK
 - .1 Owner may temporarily occupy designated areas of the Work for purpose of storing furnishings and equipment, and for installing equipment.
 - .2 In accordance with GC 5.10 - Non-Conforming Work, partial Owner occupancy will not be considered an acceptance of the Work, nor in any way relieve Contractor of responsibility to complete the Work.
- 1.4 WORK SEQUENCE
 - .1 Construct the Work in stages to accommodate Owner's continued use of premises during construction.
 - .2 Each construction stage must be completed and ready for Owner occupancy before next stage may commence.
 - .3 Coordinate construction progress schedule, and coordinate with Owner occupancy during construction.
 - .4 Required Stages: As indicated on Drawings.
- 1.5 SPECIAL PROCEDURES FOR CONTRACTORS WORKING IN EXISTING FACILITY
 - .1 Comply with Owner's procedures and requirements for construction personnel working in existing facilities.
 - .2 Conform to latest edition of "Guidelines For Maintaining Fire Safety During Construction in Existing Buildings", as issued by Office of the Fire Marshal.
 - .3 Coordinate requirements with local fire department. Discuss fire safety planning issues and alternative measures.
- 1.6 TIME OF WORK RESTRICTIONS IN EXISTING FACILITY
 - .1 When performing portions of the Work within existing facility, coordinate with Owner's representative to ensure operational program of existing facility is not disrupted. Conduct such coordination not less than 48 hours prior to commencing such portions of the Work.
 - .2 Work performed within existing facility is restricted to the following times:
 - .1 July 1 to August 31: Mondays to Fridays, between the hours of 7:30 am and 4:00 pm.
 - .2 September 1 to June 30: Mondays to Fridays, between the hours of 4:00 pm and 10:30 pm.

- .3 Make special arrangements with Owner to perform any parts of the Work in existing facility outside of these hours. Submit requests for special arrangements not less than 48 hours in advance.
 - .4 Submit written notice to Owner and Owner's representative within 24 hours of any potential disruptions to continuing operations of existing facility.
 - .5 Schedule the Work so as to avoid potential disruptions to continuing operations of existing facility. Notify Owner in writing at least 24 hours in advance of any potential disruption to any adjoining areas to Place of the Work. Cooperate with Owner when scheduling such portions of the Work.
- 1.7 FOOD AND BEVERAGE RESTRICTIONS IN EXISTING FACILITY
- .1 There shall be no food or beverages allowed within existing facility.
 - .2 Only water will be permitted to be consumed within existing facility.
 - .3 No sunflower seeds, peanuts, nuts, or similar foods are permitted at Place of the Work.
 - .4 Workers found to be in violation of this requirement will be required to leave Place of the Work and will be replaced by Contractor.
- 1.8 FIRE ALARMS IN EXISTING FACILITY
- .1 Fire and smoke sensors are installed throughout existing facility. These devices may be triggered by jarring either directly or indirectly while working in adjacent areas.
 - .2 Determine nature and exact locations of existing fire and smoke sensors prior to commencement of the Work.
 - .3 Notify Owner prior to commencement of any part of the Work in the vicinity of fire and smoke sensor devices.
 - .4 Owner reserves the right to charge Contractor for costs incurred as a result of false fire alarms activated as a result of execution of the Work.

END OF SECTION

- 1 General
- 1.1 CASH ALLOWANCES
 - .1 Refer to GC 4.1 - Cash Allowances.
 - .2 Upon request, submit to Consultant before submission of final application for payment, certified copies of invoices and statements from Suppliers and Sub-subcontractors furnishing Products or services under a cash allowance.
 - .3 When a cash allowance is described as including supply only of a Product, affected Subcontractor is responsible for ensuring cost of installation, including connections to facility services, has been included in Subcontract Price.
 - .4 Amount of each allowance, for Work specified in respective specification Sections:
 - .1 Subcontract SC01: Include in Subcontract Price the stipulated sum of \$130,000 for the following parts of the Work:
 - .1 Inspection and testing services as described in Section 01 40 00.
 - .2 Completion of architectural CAD as-built drawings as described in Section 01 78 00.
 - .3 Supply and installation of signage as specified in Section 10 14 00.
 - .4 Supply and installation of musical instrument storage cabinets as specified in Section 12 56 34.
- 1.2 CONTINGENCY ALLOWANCE
 - .1 A Subcontract Price may include a contingency allowance when stated in the Contract Documents.
 - .2 A contingency allowance includes a Subcontractor's overhead and profit in connection with such contingency allowance.
 - .3 Expenditures under a contingency allowance shall be authorized and valued as provided in SCC 6.1 - Contractor's Right to Make Changes, SCC 6.2 - Change Order and SCC 6.3 - Change Directive.
 - .4 A Subcontract Price shall be adjusted by Change Order to provide for any difference between the authorized expenditures and the contingency allowance.
 - .5 Subcontract SC01: Include in Subcontract Price a contingency allowance in the amount of \$300,000.

END OF SECTION

1 General

1.1 INSTRUCTIONS

- .1 Drawings stipulate pertinent requirements for Products and methods to achieve work stipulated under each alternative.
- .2 Coordinate affected parts of the Work and modify surrounding construction to integrate each alternative.

1.2 DEFINITIONS

- .1 In accordance with CCDC 23-2018 - A Guide to Calling Bids and Awarding Construction Contracts, the following terms are defined as follows:
 - .1 Alternate Price: The amount stipulated by the bidder for an alternative, which can be stated as an addition, a deduction, or no change to the base Bid Price. Unless incorporated by written agreement prior to the execution of the Agreement, an Alternate Price is not included in the Contract Price.
 - .2 Itemized Price: The bidder's price for a specific item of the Work included in the base Bid Price, and is identified for information purposes only. An Itemized Price will not be used to modify the scope of the Work or adjust the base Bid Price.
- .2 The out-dated term "Separate Price" is considered synonymous with Alternate Price.

1.3 AWARD / SELECTION OF ALTERNATIVES

- .1 Indicate variation to Bid Price for alternatives described below on the bid form supplements. Note that this form requests a difference in cost by adding to or deducting from the Bid Price.
- .2 Do not include Value Added Taxes in alternatives.
- .3 Owner may accept any of the alternatives and corresponding alternate prices in any order or combination, including all or none.
- .4 Alternatives and corresponding alternate prices are open for acceptance by Owner for same period of time as Bid Price.
- .5 In accordance with CCDC 23-2018 - A Guide to Calling Bids and Awarding Construction Contracts, the low bid will be determined by adjusting each bidder's Bid Price by the identified amounts to incorporate those alternatives for which prices have been invited and which are to be incorporated in the Work.

END OF SECTION

1 General

1.1 PRODUCT SUBSTITUTION PROCEDURES

- .1 Requests for substitution will only be considered when submitted in sufficient time to permit proper evaluation by Consultant.
- .2 When requesting Consultant review of a proposed Product substitution, demonstrate the proposed substitute will perform equally as well or better as the specified Product.
- .3 Accompany each request for substitution with a list of properties for both the specified Product and the proposed substitute, including the following information:
 - .1 Product identification, including manufacturer's name, address, telephone and fax numbers, and web site address where available.
 - .2 Manufacturer's Product data sheets, including material descriptions, compliance with applicable reference standards, and performance and test data.
 - .3 A summarized comparison of physical properties and performance characteristics for the specified Product and the proposed substitution, and clearly highlighting significant variations.
 - .4 Indication of availability of maintenance services and sources of replacement materials and parts, including associated costs and time frames.
 - .5 Indication of cost savings and reduction of construction schedule.
 - .6 Verification that the substitute will not result in additional costs or a reduction in performance to other portions of the Work.
 - .7 Reason for requesting the substitution.
- .4 The clauses "or equal", "or approved equal", or other similar clauses, will not be construed as an invitation to submit requests for substitution or to unilaterally substitute Products in place of specified Products and systems.
- .5 The abbreviation "eg." means "for example", and a Product listed thereafter is named as an example of the Product upon which the Specification is based. Similar Products from other listed manufacturers are acceptable for use, provided they meet specified criteria.
- .6 Failure to order specified Products in adequate time to meet the approved construction schedule will not be a valid reason to submit a request for substitution. In accordance with GC 6.5 - Delays, such delays remain the responsibility of Contractor, and will not result in an extension to Contract Time or be subject to reimbursement by Owner.
- .7 Owner is under no obligation to consider Product or system substitutions recommended by Contractor.
- .8 Remove and replace substitutions incorporated into the Work without Consultant's written approval.

END OF SECTION

1 General

1.1 CLARIFICATIONS

- .1 Request written clarifications when meaning of Contract Documents is unclear.
- .2 Do not proceed with related parts of the Work until clarification is received.
- .3 Failure to notify Consultant when Contract Documents are unclear or inconsistent will result in Contractor incurring responsibility for resulting deficiencies and additional costs.
- .4 Clarifications issued by Consultant are deemed to supercede the relevant parts of Contract Documents, regardless whether those documents are cited in the written clarification.

1.2 REQUESTS FOR INFORMATION

- .1 Contractor may, after exercising due diligence to locate the required information, request from Consultant clarification or interpretation of Contract Documents, hereinafter referred to as a request for information (RFI).
- .2 Submit RFI on a form acceptable in content to Consultant, including a detailed description of Contractor's review of Contract Documents leading up to issuance of RFI. Requests for information that fail to include a detailed review description, or whose description is insufficient in Consultant's opinion, may not be considered and may be rejected.
- .3 Maintain a log of RFI sent to and responses received from Consultant, complete with corresponding dates. Submit updated RFI log with each application for payment.
- .4 Submit RFI to Consultant sufficiently in advance of affected parts of the Work so as not to cause delay in the Work. Additional costs incurred as a result of failure to submit RFI in sufficient time will not be reimbursed by Owner.
- .5 Submit one RFI per RFI form, numbered consecutively in a single sequence, in order submitted.
- .6 Consultant will review and respond to RFI with reasonable promptness.
- .7 Consultant's response to RFI will not be considered a Changer Order or Change Directive, nor does it authorize changes in the Work, Contract Price and Contract Time.
- .8 If, at any time, Contractor submits a large quantity of RFI, such that Consultant cannot process them within a reasonable period of time, then Consultant will notify Contractor of such in writing. In this event, Contractor and Consultant will jointly prepare an estimate of time necessary for processing RFI, as well as determining an order of priority among submitted RFI. Contractor will accommodate such necessary time at no increase in Contract Time and Contract Price.
- .9 If information requested in an RFI is apparent from field observations, is contained in Contract Documents or is reasonably inferable from them, Contractor shall be responsible to Owner for reasonable costs charged by Consultant for additional services required to prepare and issue such information.
- .10 A request for information (RFI) will not constitute a notice of claim for a delay.

1.3 CONTRACT MODIFICATION PROCEDURES

- .1 Refer to GC 6.1 - Owner's Right to Make Changes, GC 6.2 - Change Order and GC 6.3 - Change Directive.
- .2 Once a Proposed Change has been issued by Consultant, ensure that no work is carried out that may increase the cost of the contemplated variation.

- .3 Consultant will assess the fair market cost of each change before issuing a Change Order. Assist Consultant with this task by quoting variations in a complete manner, listing:
 - .1 Quantity of each material,
 - .2 Unit cost of each material,
 - .3 Man hours involved,
 - .4 Cost per hour, and
 - .5 Subcontractor quotations.
- .4 Consultant may require further quotations in order to show a breakdown of costs.
- .5 Owner and Consultant will not be responsible for delays to the Work resulting from late, incomplete, or inadequately broken down valuations submitted by Contractor.
- .6 Minor variations may be made in the Project from time to time as approved by Consultant. Such alterations or adjustments shall not constitute a change in cost unless a request is made at that time. No extra will be contemplated except where a clear indication is made that extra payment is claimed, in which case a Proposed Change or Change Directive will be issued by Consultant in accordance with GC 6.1 - Owner's Right to Make Changes, or GC 6.3 - Change Directive. Unless this procedure is followed, no claims for extras will be allowed.

END OF SECTION

- 1 General
- 1.1 COORDINATION
 - .1 Coordinate the Work to ensure the Project proceeds safely and expeditiously.
 - .2 Ensure adequate communication among involved parties.
 - .3 Allocate mobilization areas at Place of the Work; for field offices and sheds, for access, for traffic, and for parking facilities.
 - .4 Coordinate use of Place of the Work and facilities through procedures for submittals, reports and records, schedules, coordination of Drawings, recommendations, and resolution of ambiguities and conflicts.
 - .5 Submit information required for preparation of coordination and interference drawings. Review and approve revised drawings for submission to Consultant.
- 1.2 DOCUMENTS AT PLACE OF THE WORK
 - .1 Maintain an up-to-date copy of the following documents at Place of the Work:
 - .1 Contract Documents, including Drawings, Specifications, addenda, bid revisions, Notices in Writing, Supplemental Instructions, proposed changes, Change Orders, Change Directives, and other modifications to the Contract.
 - .2 Accepted Shop Drawings, Product data, and samples.
 - .3 Quality control submittals, including test and evaluation reports.
 - .4 Manufacturer's instructions, including installation and maintenance guidelines.
 - .5 Construction progress schedule.
 - .6 Additional requested schedules.
 - .7 Consultant's field review reports and deficiency reports.
 - .8 Reports from authorities having jurisdiction.
 - .9 Permits.
 - .10 Construction daily log.
 - .11 Record as-built documents as described in Section 01 78 00.
 - .2 Make documents available to Consultant for review at Place of the Work.
 - .3 Construction Daily Log: Maintain a construction log, recording on a daily basis the following information:
 - .1 Number of workers actively working at Place of the Work, organized on a Subcontract basis.
 - .2 Subcontractors working at Place of the Work.
 - .3 Identify the parts of the Work being worked on.
 - .4 Identify the working hours being kept at Place of the Work.
 - .5 Activities with intermittent progress.
 - .6 Time lost with an explanation as to cause.
 - .7 Difficulties encountered, such as construction activity delays, labour inefficiencies, labour shortages, etc.
 - .8 Product deliveries.
 - .9 Equipment mobilization and de-mobilization.
 - .10 Demolition conditions.
 - .11 Start and finish dates for each part of the Work.
- 1.3 OTHER CONTRACTORS
 - .1 Cooperate with any separate contractor employed by Owner and, if necessary, co-ordinate with their work.
 - .2 Submit necessary information to Owner to assist in required scheduling of other contractors.

1.4 CONTINUANCE OF OWNER OPERATIONS IN OCCUPIED FACILITIES

- .1 Coordinate and schedule the Work to minimize disruption of normal functions at existing facility.
- .2 Changes to traditional scheduling of construction may be required, and certain portions of the Work may not be able to proceed in continuous sequence.
- .3 Every reasonable effort will be made to cooperate with construction process.
- .4 Owner may modify proposed scheduling where such changes are in Owner's best interests regarding operation of existing facility.

1.5 GENERAL REQUIREMENTS FOR PROJECT MEETINGS

- .1 Schedule and administer project meetings in consultation with Consultant, throughout progress of the Work.
- .2 Prepare agenda for meetings.
- .3 Distribute written notice of each meeting 4 days in advance of meeting date to Consultant and Owner.
- .4 Provide physical space and make arrangements for meetings.
- .5 Preside at meetings.
- .6 Record meeting minutes. Include significant proceedings and decisions. Identify required actions by affected parties.
- .7 Reproduce and distribute copies of minutes within 5 days after meeting, and transmit to meeting participants, affected parties not in attendance, Consultant, and Owner.
- .8 Representative of Contractor, Subcontractors, and Suppliers attending meetings shall be qualified and authorized to act on behalf of the party each represents.
- .9 Schedule meetings at regular 14 day intervals, on a day that is determined to be convenient by Contractor and Consultant.

1.6 PRE-CONSTRUCTION MEETING

- .1 Within 15 days after award of Contract, request a meeting with Owner to discuss and resolve administrative procedures and responsibilities.
- .2 Conduct meetings with Subcontractors and Suppliers to discuss and resolve administrative procedures and responsibilities.
- .3 Owner, Consultant, Contractor, Subcontractors, field inspectors, and supervisors will be in attendance.
- .4 Establish time and location of meeting, and notify parties concerned a minimum of 5 days before meeting date.
- .5 Incorporate mutually agreed variations to Contract Documents into Agreement, prior to signing.
- .6 Pre-construction Meeting Agenda: include the following:
 - .1 Appointment of official representative of participants in the Work;
 - .2 Schedule of Work, progress scheduling;
 - .3 Schedule of submissions of Shop Drawings, samples, colour chips;
 - .4 Requirements for temporary facilities, Project identification sign, field offices, storage sheds, utilities, fences, and protective enclosures;

- .5 Delivery schedule of specified equipment;
- .6 Site security;
- .7 Proposed changes, Change Orders, Change Directives, procedures, approvals required, mark-up percentages permitted, time extensions, overtime, administrative requirements;
- .8 Owner-supplied Products;
- .9 As-built drawings;
- .10 Operation and maintenance manual;
- .11 Take-over procedures, acceptance, warranties, extra stock materials;
- .12 Monthly progress claims, administrative procedures, photographs, holdbacks;
- .13 Procedures for publishing Certificate of Substantial Performance of the Work, including identification of publisher, and notification of Subcontractors and Suppliers;
- .14 Appointment of inspection and testing agencies or firms; and
- .15 Insurances, transcripts of policies.

1.7 PREINSTALLATION MEETINGS

- .1 During course of the Work, schedule preinstallation meetings as required by Contract Documents.
- .2 Wherever possible, schedule preinstallation meetings on same date as regularly scheduled progress meetings.
- .3 Contractor, affected Subcontractors and Suppliers, manufacturer's representatives, field inspectors, and supervisors, Consultant and any other specified parties are to be in attendance.
- .4 Preinstallation Meeting Agenda: Include the following:
 - .1 Review of existing conditions and affected parts of the Work, and any testing thereof;
 - .2 Review of installation procedures and requirements;
 - .3 Review of environmental and field condition requirements;
 - .4 Schedule of the applicable parts of the Work;
 - .5 Schedule of submission for samples and other items requiring Consultant's selection;
 - .6 Requirements for Temporary Work;
 - .7 Requirements for notification for reviews. Allow a minimum of 48 hours notice for Consultant to review the affected parts of the Work;
 - .8 Requirements for inspections and tests as applicable. Schedule and undertake inspections and tests;
 - .9 Delivery schedule for Products; and
 - .10 Special safety requirements and procedures.

1.8 PROGRESS AND PROGRESS DRAW MEETINGS

- .1 During course of the Work, and two weeks prior to completion of the Contract, schedule progress meetings biweekly.
- .2 During course of the Work, schedule progress draw meetings monthly.
- .3 Submit to Consultant one copy of application for payment not less than two Working Days before scheduled progress draw meeting. Consultant may require changes to application for payment prior to progress draw meeting.
- .4 Contractor, major Subcontractors involved in Work, Consultant, and Owner are to be in attendance.
- .5 Progress Meeting Agenda: include the following:
 - .1 Review, approval of minutes of previous meeting;
 - .2 Review of Work progress since previous meeting;
 - .3 Field observations, problems, conflicts;
 - .4 Problems impeding construction schedule;
 - .5 Review of off-site fabrication delivery schedules;

- .6 Corrective measuring and procedures to regain project schedule;
- .7 Revision of construction schedule;
- .8 Progress, schedule, during succeeding work period;
- .9 Review submittal schedules, record drawings: expedite as required;
- .10 Maintenance of quality standards;
- .11 Review of proposed changes for affect on construction schedule and on completion date;
- .12 Other business.

END OF SECTION

- 1 General
- 1.1 SUBMISSION REQUIREMENTS
 - .1 Submit initial schedules within 15 days after award of Contract.
 - .2 Re-submit updated schedules with each application for payment.
 - .3 Submit schedules electronically in the form of portable document format (.pdf) files.
- 1.2 CONSTRUCTION PROGRESS SCHEDULE
 - .1 Prepare construction progress schedule using critical path method.
 - .2 Include complete sequence of construction activities.
 - .3 Include dates for commencement and completion of each major element of construction.
 - .4 Show projected percentage of completion of each item as of first day of month.
 - .5 Indicate progress of each activity to date of submission of the schedule.
 - .6 Update schedule monthly and resubmit with each application for progress payment. Consultant will not review an application for payment that does not include an updated construction progress schedule.
 - .7 Show changes occurring since previous submission of schedule:
 - .1 Major changes in scope.
 - .2 Activities modified since previous submission.
 - .3 Revised projections of progress and completion.
 - .4 Other identifiable changes.
 - .8 Provide a narrative report to define:
 - .1 Problem areas, anticipated delays, and impact on schedule.
 - .2 Corrective action recommended and its effect.
 - .3 Effect of changes on schedules of other contractors.
- 1.3 ADDITIONAL SCHEDULES
 - .1 Concurrently with construction progress schedule, prepare and submit a schedule of values, a cash flow schedule, a submittal schedule, an inspection and testing schedule, and an equipment delivery schedule; prepared in formats acceptable to Consultant.
 - .2 Schedule of Values: To CCDC 24-2022, A Guide to Model Forms and Support Documents.
 - .3 Cash Flow Schedule: Broken down on a monthly basis, indicating anticipated monthly progress billings for duration of Contract.
 - .4 Submittal Schedule:
 - .1 Refer to GC 3.10 - Shop Drawings.
 - .2 Indicate anticipated submission dates and review periods for Shop Drawings, samples, lists of materials, and other documentation.
 - .3 Highlight critical items, including latest date for submittal review by Consultant.
 - .4 Design sequence of submissions to reflect requirements of construction schedule.
 - .5 Inspection and Testing Schedule:
 - .1 Schedule inspection and testing in consultation with Owner's appointed inspection and testing agency.
 - .2 Identify time required for the performance of tests and inspections, and for the preparation and distribution of reports.

- .6 Equipment Delivery Schedule: Indicate list of manufactured equipment complete with order dates and anticipated delivery dates.

1.4 PROGRESS PHOTOGRAPHS

- .1 Concurrently with each monthly application for payment, and with final application for payment, submit sufficient quantity of colour photographs, clearly illustrating progress of the Work.
- .2 Format photographs as bitmap (bmp) or JPEG (jpg) image files, with minimum resolution of 10 megapixels.
- .3 Ensure photographs are taken by a person experienced in photography.
- .4 Submit additional photographs showing special conditions when requested by Consultant.
- .5 Photographs will be properly exposed and in focus, with unobstructed views.
- .6 Identify each photograph with:
 - .1 Name of Project,
 - .2 Name of photographer,
 - .3 Description of view, and
 - .4 Date photograph was taken.

END OF SECTION

1 General

1.1 ADMINISTRATIVE

- .1 Collect submittals requested by Contract Documents, as required by authorities having jurisdiction, and as may be reasonably requested by Consultant from relevant Subcontractors, Suppliers, and manufacturers.
- .2 Make submissions with reasonable promptness and in an orderly sequence so as not to delay the Work. Be responsible for delays and pay additional costs as a result of failure to make submissions in due time to allow proper reviews.
- .3 Submittals containing unauthorized substitutions will be rejected. Refer to Section 01 25 00 for substitution procedures.
- .4 Ensure submissions are complete for each particular submittal required.
- .5 Where submissions are not complete, indicate which submittal components are not included, and stating when they will be made available. Consultant reserves the right to delay their review of the submittal until submission is complete.
- .6 Do not proceed with parts of the Work affected by a submittal, including ordering Products, until relevant submittal has been reviewed and accepted by Consultant.
- .7 Prepare submittals in units of measurement consistent with those used on Drawings.
- .8 Digital files are to be electronically created from original files. Scanned images will be rejected.

1.2 SUBMISSION PROCEDURES

- .1 Coordinate each submittal with Contract Documents.
- .2 Include with each submission a duplicate transmittal document indicating:
 - .1 Date of initial submission,
 - .2 Date of each resubmission, and
 - .3 Project title and Consultant's Project number.
- .3 Indicate on each submission, the following information:
 - .1 Name of Contractor,
 - .2 Name of Subcontractor,
 - .3 Name of Supplier (as applicable),
 - .4 Name of manufacturer (as applicable),
 - .5 Name of person responsible for preparation of submission, and
 - .6 Relevant specification Section numbers.
- .4 Identify submittals numerically by Section number, numeric indicator, revision number, and a brief worded description. For example, a submittal for masonry wall ties might be identified as "04 05 19-01-R0-Wall Ties".
- .5 When required by Consultant's review, make necessary changes to submittal and resubmit for final acceptance.
- .6 Notify Consultant in writing of any additional revisions made to submittal beyond those required by Consultant's review.
- .7 Upon acceptance of submittal by Consultant, distribute copies to affected parties.

1.3 REVIEW BY CONTRACTOR

- .1 Before making submissions to Consultant, review submittals for conformity to Contract Documents.

- .2 Contractor's review of submittals must be conducted by authorized representative familiar with the Work.
 - .3 Check each submittal and make necessary notations before forwarding submittals to Consultant.
 - .4 Distribute copies of submittals to affected Subcontractors for their comment prior to submitting them to Consultant.
 - .5 Verify noted dimensions with actual constructed measurements at Place of the Work.
 - .6 Confirm fabrication techniques and installation means and methods.
 - .7 Where submittal does not conform to Contract Documents, reject submittal and return to source for revisions. Do not forward rejected submittals to Consultant.
 - .8 Contractor assumes sole responsibility for conflicts that may arise in execution of the Work as a result of failure to properly review and coordinate submittals.
 - .9 Submittals forwarded to Consultant must bear Contractor's review stamp, signed, and dated by authorized representative.
 - .10 Submittals received by Consultant that fail to include Contractor's review stamp, date, and signature will be returned without review.
 - .11 Notify Consultant in writing of changes made on submittals to Contract Documents. Consultant's review of submittals does not relieve Contractor of responsibility for unauthorized changes made to Contract Documents.
 - .12 Keep copies of accepted submittals at Place of the Work in a neat, orderly condition.
 - .13 Perform the Work in conformance with accepted submittals. Remove and replace Products not matching accepted submittals.
- 1.4 REVIEW BY CONSULTANT
- .1 Review of submittals by Consultant is only for general conformity to Contract Documents.
 - .2 Consultant review does not imply approval of construction means, methods, techniques, or detailing, responsibility for which remains with Contractor.
 - .3 Consultant review does not relieve Contractor of responsibility for errors or omissions in submittals, or responsibility for meeting requirements of Contract Documents.
 - .4 Consultant markings on submittals and resulting required actions:
 - .1 Submittals requiring no changes will be marked 'REVIEWED', and will be submitted for as-built purposes.
 - .2 Submittals requiring some minor changes will be marked 'REVIEWED AS NOTED', and will be revised and submitted for as-built purposes.
 - .3 Submittals requiring substantial changes will be marked as 'REVISE AND RESUBMIT' and will be revised and resubmitted until Consultant subsequently marks them as 'REVIEWED' or 'REVIEWED AS NOTED'.
 - .5 Consultant's review and markings on submittals do not authorize changes in the Work.
 - .6 If, in Contractor's opinion, Consultant's review of a submittal constitutes a change in the Work, then Contractor will notify Consultant in writing, and request an interpretation as specified in Section 01 26 00.
 - .7 If Consultant determines that a change in the Work is justified, then a Change Order itemizing the change in Contract Price and Contract Time will be issued.

- .8 Submittals not requested by Contract Documents or Consultant, or not required by authorities having jurisdiction, will not be reviewed by Consultant, and will be returned marked as NOT REVIEWED.

1.5 ENGINEERED SUBMITTALS

- .1 Submittals required to be sealed by a professional engineer are to be prepared, sealed, signed, and dated under direct control and supervision of a qualified professional engineer licensed to practice at Place of the Work.
- .2 Upon written request from Consultant, submit proof of professional liability insurance with minimum limit of liability of \$5,000,000 per claim, and identifying insurer, policy number, and policy term on duly signed certificate of insurance.
- .3 Design includes life safety, sizing of supports, anchors, framing, connections, spans, and as additionally required to meet or exceed requirements of applicable codes, standards, regulations, authorities having jurisdiction, and design requirements of Contract Documents.
- .4 Engineered submittals are to include design calculations, complete with references to codes and standards used in such calculations, supporting the proposed design represented in the submittal. Prepare calculations in a clear and comprehensive manner so they can be properly reviewed.
- .5 Submittal engineer shall undertake periodic field review, including review of associated mock-ups when applicable. Such reviews will include review during fabrication at the point of manufacture, and during installation at Place of the Work. Prepare and submit a field review report for each review undertaken.
- .6 Conduct field reviews at intervals appropriate to the progress of the parts of the Work relevant to engineered submittal. Report on progress and quality of the affected parts of the Work. Determine if installation is in general conformity with Contract Documents and in strict conformance with accepted engineered submittal.
- .7 Upon completion of the parts of the Work affected by engineered submittal, submittal engineer shall prepare and submit a 'Letter of General Conformity' to Contractor, Consultant, and authorities having jurisdiction. Certify that the parts of the Work affected by engineered submittal have been designed, fabricated, and installed in accordance with Contract Documents and applicable regulatory requirements.
- .8 Include costs of submittal engineer's services in Contract Price.

1.6 SUBMITTALS PRIOR TO START OF WORK

- .1 Submit the following documents within the time stipulated, or, if not stipulated, prior to first application for payment:
 - .1 Insurance certificates,
 - .2 Surety Bonds (as applicable),
 - .3 Workplace Safety and Insurance Board certificates,
 - .4 Construction progress schedule,
 - .5 Interference drawings,
 - .6 Schedule of values,
 - .7 Cash flow schedule,
 - .8 Submittal schedule,
 - .9 Inspection and testing schedule, and
 - .10 Equipment delivery schedule.

1.7 PRODUCT DATA

- .1 Submit Product data sheets and brochures electronically in the form of portable document format (.pdf) files for requirements requested in Specifications and as Consultant may reasonably request where Shop Drawings will not be prepared due to standardized manufacture of Product.
- .2 Include sufficient space for application of review stamps by Contractor and Consultant.
- .3 After review, Consultant will return marked-up Product data sheets to Contractor. Produce and distribute necessary copies to affected parties.
- .4 Retain one set of accepted Product data sheets for inclusion in operation and maintenance manual. Refer to Section 01 78 00.

1.8 SHOP DRAWINGS

- .1 Refer to GC 3.10 - Shop Drawings.
- .2 Unless specified otherwise, submit Shop Drawings electronically in the form of portable document format (.pdf) files for each requirement requested in Specifications and as Consultant may reasonably request.
- .3 Include sufficient space for application of review stamps by Contractor and Consultant.
- .4 Shop Drawings are to be legible, and basically include the following information:
 - .1 Fabrication and erection dimensions.
 - .2 Plans, Sections, Elevations, arrangements and sufficient full-size details indicating complete construction, components, methods of assembly and interconnections with adjacent parts of the Work.
 - .3 Design and engineering calculations, substantiating member sizes and connections, based on design loads.
 - .4 Clear assignment of responsibility for the parts of the Work described thereon. Do not include phrases such as; "by others" or "by purchaser". Shop Drawings marked in this manner will be rejected.
 - .5 Location and type of exposed anchors and fasteners, including any concealed reinforcements for attachment of same.
 - .6 Adhesives, joinery methods and bonding agents.
 - .7 Grades and Types of Products, including their physical characteristics, finishes, and other fabrication information.
 - .8 Configurations, sizes, and styles of Product required.
 - .9 Mechanical and electrical characteristics of equipment.
 - .10 Data verifying superimposed loads will not affect function, appearance, or safety of installed components and adjacent construction.
 - .11 Chases, sleeves, cuts, and holes required, including those required in adjacent structural building elements.
 - .12 Locations and types of welded connections. Include AWS symbols and indicate net weld lengths and sizes.
 - .13 Product and manufacturer names, complete with model numbers.
 - .14 Installation guidelines.
 - .15 Operation and maintenance guidelines.
- .5 Refer to Product Specifications for material-specific requirements of Shop Drawings.
- .6 After review, Consultant will return marked-up Shop Drawings to Contractor. Produce and distribute necessary copies to affected parties.
- .7 Retain one set of accepted Shop Drawings for inclusion in operation and maintenance manual. Refer to Section 01 78 00.

1.9 SAMPLES

- .1 Submit samples to Consultant as requested in Contract Documents.
- .2 Deliver samples prepaid to Consultant's business office.
- .3 Identify samples with Project name and number, Consultant's name, Contractor's name, Subcontractor's name, date of submission, specification Section number, manufacturer's name, Product name and model number, and colour name and number.
- .4 Upon request of Consultant, prepare representative panels of Products, illustrating selected textures, patterns, and colours.

1.10 INTERFERENCE DRAWINGS

- .1 Prepare a set of interference drawings, identifying and resolving potential conflicts among various parts of the Work, including sprinkler systems, HVAC ductwork, plumbing and drainage lines, lighting, and electrical systems.
- .2 Submit interference drawings electronically to Consultant in the form of portable document format (.pdf) files prior to commencement of the Work.
- .3 Coordinate and review interference drawings with affected Subcontractors prior to commencement of their portions of the Work.

1.11 CERTIFICATES AND CERTIFICATION SUBMITTALS

- .1 Submit written statements, as requested in Contract Documents, certifying installed Products meet specified criteria.
- .2 Include signature of person responsible for preparing certification.

1.12 TEST AND EVALUATION REPORTS

- .1 Submit manufacturers' test and evaluation reports electronically in the form of portable document format (.pdf) files for requirements requested in Specifications and as Consultant may reasonably request.
- .2 Ensure results are expressed in SI (metric) units of measurement. Test and evaluation reports recording results only in Imperial units of measurement may be rejected.
- .3 Clearly indicate compliance with specified performance criteria, tested in accordance with specified test methods, and conducted by independent testing agency.
- .4 Test results achieved through the use of alternative test methods will be rejected.

END OF SECTION

- 1 General
- 1.1 CONSTRUCTION SAFETY
 - .1 Refer to GC 9.4 - Construction Safety.
 - .2 C00 - Contractor will assume role of "Constructor" as defined by applicable regulatory requirements.
 - .3 Prepare and submit one copy of Registration Forms of Construction and Employers of Workers to authority having jurisdiction.
 - .4 Hold regular, scheduled safety meetings.
- 1.2 SPECIAL PROCEDURES FOR INFECTION CONTROL
 - .1 Conform to latest edition of CCA COVID-19 - Standardized Protocols for All Canadian Construction Sites.
- 1.3 PROPER CONDUCT OF WORKERS
 - .1 Ensure workers conduct themselves in a proper and civilized manner at all times.
 - .2 Workers are required to be properly attired at all times.
 - .3 Workers wearing clothing exhibiting hateful or offensive images or language will be required to replace or cover such clothing. Workers refusing to do so will be required to leave Place of the Work and will be replaced by Contractor.
 - .4 Workers using improper language, cat calls, lewd comments, or improper behaviour will be required to leave Place of the Work and will be replaced by Contractor.
 - .5 Smoking or vaping of any substance is not permitted at Place of the Work.
 - .6 Consumption of alcohol and use of controlled substances is not permitted at Place of the Work.
- 1.4 LABOUR CONDITIONS
 - .1 Ensure rates of wages, working hours, and working conditions at Place of the Work are in accordance with applicable regulatory requirements.
- 1.5 EMERGENCY CONTACT INFORMATION
 - .1 Submit emergency contact information for site superintendent to authority having jurisdiction, for their use 24 hours a day, 7 days a week, 52 weeks a year.
 - .2 Immediately notify authority having jurisdiction when emergency contact information changes.
- 1.6 NOISY WORK RESTRICTIONS
 - .1 Conform to applicable noise regulations and legislation.
 - .2 Schedule noisy work, or work requiring use of pneumatic tools, in a manner to avoid disturbance to existing facility occupants.
 - .3 This may require portions of the Work to be performed outside normal working hours.
- 1.7 SPILL RESPONSE
 - .1 Prepare and initiate spill response procedure in accordance with appropriate regulatory requirements prior to commencing the Work.

- .2 Supply and maintain spill kit at Place of the Work.
- 1.8 SPECIAL PROCEDURES FOR WORKING IN CONFINED SPACES
- .1 Perform work in confined spaces in accordance with applicable legislation.
 - .2 Work in confined spaces must be supervised and performed by licenced confined space and hazardous materials personnel.
- 1.9 SPECIAL PROCEDURES FOR WORKING WITH DESIGNATED SUBSTANCES
- .1 Prepare and initiate a Health and Safety Plan in accordance with authorities having jurisdiction prior to commencing work involving excavating and transporting or handling potentially contaminated materials.
 - .2 Keep an up-to-date copy of Health and Safety Plan at Place of the Work.
 - .3 Adhere to Health and Safety Plan for duration of removal and disposal of contaminated material from Place of the Work.
 - .4 Provide and maintain a safe working environment for on-site personnel and minimize the impact of construction activities on the general public and surrounding environment.
 - .5 Verify workers and visitors to Place of the Work have and are adequately trained in the use of appropriate personal protective equipment.
 - .6 Should any unforeseen, or site-peculiar safety related factor, hazard, or condition become evident during performance of the Work, notify authority having jurisdiction and Consultant immediately, and take prudent temporary action to establish and maintain safe working conditions until suitable permanent action can be implemented. Safeguard workers, the public and surrounding area from contamination.
 - .7 Perform routine air monitoring at Place of the Work, testing for organic vapours, explosive conditions and oxygen deficient conditions. Evacuate affected areas immediately and implement corrective measures if unsatisfactory conditions are discovered.
 - .8 Guidelines by Authorities Having Jurisdiction: Conform to the following guideline documents issued by Province of Ontario:
 - .1 Silica on Construction Projects.
 - .2 Lead on Construction Projects.
 - .9 Mercury Precautions: Ensure workers handling, removing and disposing of mercury-containing materials have been properly trained by a competent and qualified person.
 - .10 In the event of injury to on-site personnel, contact designated hospital and describe injury prior to or during transport of injured personnel. Transport injured personnel to defined medical facility along predefined route.
 - .11 Take appropriate measures to minimize contact of vehicles and equipment with potentially contaminated materials. Vehicles, equipment and workers which do contact contaminated materials shall be decontaminated in an approved manner prior to leaving Place of the Work.
- 1.10 SECURITY DEPOSITS
- .1 When Owner has submitted security deposits to authorities having jurisdiction prior to award of a particular Subcontract, responsible Subcontractor shall reimburse deposit amount to Owner. Failure to reimburse Owner the required amount will result in postponement of payment of Subcontractor's first application for payment.

END OF SECTION

1 General

1.1 REGULATORY REQUIREMENTS

- .1 Perform the Work in accordance with latest editions of applicable regulatory requirements.
- .2 Conform to requirements of authorities having jurisdiction.
- .3 Nothing contained in Contract Documents shall be construed to be in conflict with any law, by-law, or regulation of municipal, regional, provincial, federal, or other authority having jurisdiction.

1.2 PERMITS AND FEES

- .1 Refer to GC 10.2 - Laws, Notices, Permits and Fees.
- .2 Determine detailed requirements of authorities having jurisdiction.
- .3 Pay construction damage deposits levied by municipality in connection with issuing a building permit.

1.3 REFERENCES

- .1 Where edition date is not specified, consider references to manufacturer's data, and published codes, standards and specifications are made to latest edition or revision, approved by issuing organization.
- .2 Reference standards and specifications are quoted to establish minimum standards. Work which in quality exceeds the specified minimum will be considered to conform.
- .3 Requirements of Contract Documents govern over requirements of reference standards and specifications.
- .4 Standards, specifications, associations and regulatory agencies are referred to throughout Contract Documents by abbreviated designations, as listed below:
 - .1 AA The Aluminum Association;
 - .2 AABC Associated Air Balance Council;
 - .3 AAMA American Architectural Manufacturers Association;
 - .4 ACI American Concrete Institute;
 - .5 AISC American Iron and Steel Construction;
 - .6 AMCA Air Movement and Air Control Association;
 - .7 ANSI American National Standards Institute;
 - .8 ARI Air Conditioning and Refrigeration Institute;
 - .9 ASCC American Society of Concrete Contractors;
 - .10 ASME American Society of Mechanical Engineers;
 - .11 ASTM American Society for Testing and Materials;
 - .12 ASHRAE American Society of Heating, Refrigeration and Air Conditioning Engineers, Inc.;
 - .13 AWMAC Architectural Woodwork Manufacturers' Association of Canada;
 - .14 AWPA American Wire Producers Association;
 - .15 BHMA Builders Hardware Manufacturers Association;
 - .16 BIA Brick Industry Association;
 - .17 CaGBC Canadian Green Building Council;
 - .18 CCMPA Canadian Concrete Masonry Producers Association;
 - .19 CFCA Concrete Floor Contractors Association of Canada;
 - .20 CGA Canadian Gas Association;
 - .21 CGSB Canadian General Standards Board;
 - .22 CHPVA Canadian Hardwood Plywood and Veneer Association;
 - .23 CISC Canadian Institute of Steel Construction;
 - .24 CISCA Ceiling & Interior Systems Construction Association;

.25	CKCA	Canadian Kitchen Cabinet Association;
.26	CLFMI	Chain Link Fence Manufacturers' Institute;
.27	CPC	Concrete Polishing Council;
.28	CPCI	Canadian Precast Concrete Institute;
.29	CPCQA	Canadian Precast Concrete Quality Assurance;
.30	CPSC	Consumer Product Safety Commission;
.31	CRCA	Canadian Roofing Contractors' Association;
.32	CRI	Carpet and Rug Institute;
.33	CSA	Canadian Standards Association;
.34	CSC	Construction Specifications Canada;
.35	CSDMA	Canadian Steel Door Manufacturers' Association;
.36	CSSBI	Canadian Sheet Steel Building Institute;
.37	CUFCA	Canadian Urethane Foam Contractors Association Inc.;
.38	CWB	Canadian Welding Bureau;
.39	CWC	Canadian Wood Council;
.40	CWTA	Canadian Wood Truss Association;
.41	DASMA	Door & Access Systems Manufacturers' Association, International;
.42	DHI	Door and Hardware Institute;
.43	DIN	Deutsches Institut für Normung E.V.;
.44	GA	Gypsum Association;
.45	GANA	Glass Association of North America;
.46	HPVA	Hardwood Plywood and Veneer Association;
.47	ICEA	Insulated Cable Engineers Association;
.48	ICRI	International Concrete Repair Institute;
.49	IEEE	Institute of Electrical and Electronics Engineers;
.50	IGMA	Insulating Glass Manufacturers Association;
.51	ISCA	Interior Systems Contractors Association of Ontario;
.52	IWFA	International Window Film Association;
.53	LEED	Leadership in Energy and Environmental Design;
.54	MPI	Master Painters' Institute;
.55	MSS	Manufacturers Standardization Society of the Valve and Fittings Industry;
.56	NAAMM	National Association of Architectural Metal Manufacturers;
.57	NCMA	National Concrete Masonry Association;
.58	NEMA	National Electrical Manufacturers Association;
.59	NFPA	National Fire Protection Association;
.60	NFRC	National Fenestration Rating Council Incorporated;
.61	NHLA	National Hardwood Lumber Association;
.62	NLGA	National Lumber Grades Authority;
.63	OIRCA	Ontario Industrial Roofing Contractors' Association;
.64	OMCA	Ontario Masonry Contractors' Association;
.65	OPSD	Ontario Provincial Standard Drawings;
.66	OPSS	Ontario Provincial Standard Specifications;
.67	OWTFA	Ontario Wood Truss Fabricators Association;
.68	PCI	Precast Concrete Institute;
.69	PEI	Porcelain Enamel Institute;
.70	RSIC	Reinforcing Steel Institute of Canada;
.71	SEFA	Scientific Equipment & Furniture Association;
.72	SMACNA	Sheet Metal and Air Conditioning Contractors' National Association;
.73	SSPC	The Society for Protective Coatings;
.74	SWI	Sealant and Waterproofer's Institute;
.75	TPIC	Truss Plate Institute of Canada;
.76	TSSA	Technical Standards and Safety Authority;
.77	TTMAC	Terrazzo, Tile and Marble Association of Canada;
.78	ULC	Underwriters' Laboratories of Canada;
.79	ULI	Underwriters' Laboratories Incorporated;
.80	WDMA	Window and Door Manufacturers' Association; and
.81	WHI	Warnock-Hersey International.

1.4 QUALITY ASSURANCE

- .1 Quality of work shall be best quality, executed by workers experienced and skilled in the respective duties for which they are employed.
- .2 Maintain good order and discipline among workers engaged on Project. Do not employ on the Work anyone not skilled in their assigned tasks.
- .3 Immediately notify Consultant if required Work is such as to make it impractical to produce required results.
- .4 Decisions as to the quality or fitness of work in cases of dispute rest solely with Consultant, whose decision is final.

1.5 QUALITY CONTROL

- .1 Refer to GC 2.3 - Review and Inspection of the Work.

1.6 TESTING AND INSPECTION SERVICES

- .1 Independent inspection and testing agencies will be engaged by Owner for the purpose of inspecting and testing portions of the Work.
- .2 Cost of testing and inspection by inspection and testing agencies shall be paid from the stipulated sum cash allowances specified in Section 01 21 00.
- .3 Supply equipment required for executing inspection and testing by appointed agencies.
- .4 Employment of inspection and testing agencies does not relax the responsibility to perform Work in accordance with Contract Documents.
- .5 If defects are revealed during inspection and testing, the appointed agency will request additional inspection and testing to ascertain full degree of defect. Correct defect and irregularities as advised by Consultant at no additional cost to Owner. Pay costs for retesting and reinspection.
- .6 Allow inspection and testing agencies access to the Work, off-site manufacturing and fabrication plants.
- .7 Cooperate to provide reasonable facilities for such access.
- .8 Notify appropriate agency and Consultant in advance of the requirement for tests, in order that attendance arrangements can be made.
- .9 Submit samples or materials required for testing, as specifically requested in Specifications. Submit with reasonable promptness and in an orderly sequence so as not to cause delay in the Work.
- .10 Provide labour and facilities to obtain and handle samples and materials at Place of the Work. Provide sufficient space to store and cure test samples.

1.7 DEFECTIVE WORK

- .1 Refer to GC 2.4 - Defective Work.

1.8 QUALITY CONTROL REPORTS

- .1 Submit identified quantity of quality control reports promptly to each of the following:
 - .1 Consultant: Two copies.
 - .2 Owner: One copy.
 - .3 Authorities having jurisdiction: One copy each.

- .2 Forward copies of quality control reports promptly to each affected Subcontractor.
- 1.9 TESTS AND MIX DESIGNS
- .1 Furnish test results and mix designs as may be required.
 - .2 Costs of tests and mix designs beyond those called for in Contract Documents or beyond those required by laws at Place of Work shall be appraised by Consultant and may be authorized as recoverable.
- 1.10 MANUFACTURER FIELD REVIEW
- .1 When required by Contract Documents, arrange for a qualified manufacturer's representative to review relevant parts of the Work and verify those portions of the Work are being executed in accordance with manufacturer's written recommendations and installation guidelines.
 - .2 Manufacturer field review services are intended to ensure specified Products are being used and are being installed on substrates that have been prepared in accordance with manufacturer's written recommendations.
 - .3 Unless specified otherwise, manufacturer's representative will undertake minimum one field review, with additional reviews being conducted as deemed necessary by manufacturer.
 - .4 Within two Working Days of a field review, manufacturer will submit a field review report recording manufacturer representative's observations and recommendations.
 - .5 Distribute copies of manufacturer's field review reports to affected Subcontractors, Consultant and authorities having jurisdiction.
- 1.11 MOCK-UPS
- .1 Prepare mock-ups for portions of the Work specifically requested in Contract Documents. Include all Product and labour necessary to construct each mock-up.
 - .2 Construct mock-ups in locations acceptable to Consultant.
 - .3 Prepare mock-up for Consultant review with reasonable promptness and in an orderly sequence, so as not to cause delay in the Work.
 - .4 Failure to prepare mock-up in ample time is not considered sufficient reason for an extension of Contract Time and no claim for extension by reason of such default will be allowed.
 - .5 If requested, Consultant will assist in preparing a schedule fixing the dates for preparation.
 - .6 Specifications identify whether mock-up may remain as part of the Work or must be removed.
- 1.12 MILL TESTS
- .1 Submit mill tests certificates as may be requested.
- 1.13 EQUIPMENT AND SYSTEMS
- .1 Submit adjustment and balancing reports for facility services.
 - .2 Refer to facility services Sections for definitive requirements.

END OF SECTION

- 1 General
- 1.1 ADMINISTRATIVE REQUIREMENTS
 - .1 Provide temporary utilities, facilities and controls in order to execute the Work expeditiously.
 - .2 Maintain temporary utilities, facilities and controls in a neat and tidy condition.
 - .3 Remove temporary utilities, facilities and controls from Place of the Work when no longer required.
- 1.2 TEMPORARY WORK
 - .1 Refer to GC 3.3 - Temporary Supports, Structures and Facilities.
- 1.3 TEMPORARY UTILITIES
 - .1 Temporary Electricity
 - .1 Owner will designate an existing source, and pay usage costs for temporary power during construction to ensure adequate temporary lighting; operation of power tools; temporary heating and ventilation; and to ensure proper completion of the Work.
 - .2 Arrange for connection to designated source, and pay costs for installation, maintenance and removal.
 - .3 Ensure use of existing power source does not interrupt or affect continuing operations of existing facility.
 - .4 Provide and maintain temporary electrical systems to latest edition of CSA C22.1, Canadian Electrical Code, Part 1 - Safety Standard for Electrical Installations.
 - .2 Temporary Heating, Cooling and Ventilating
 - .1 Provide temporary heating and cooling required during construction period, including attendance, maintenance and fuel.
 - .2 Unless specified otherwise, maintain temperatures between 10 degrees C and 35 degrees C in areas where construction is in-progress.
 - .3 Temporary heaters will be forced hot air type, operated in a well ventilated location. Vent direct fired heaters directly to exterior and extend vent beyond wall face to avoid staining. Open flame heaters or salamanders are not permitted.
 - .4 Uniformly distribute heat to avoid hot and cold areas and to prevent excessive drying.
 - .5 Upon approval of Owner, the existing permanent heating system, or portions thereof, may be used when available. Be responsible for damage thereto.
 - .6 On completion of the Work, replace filters in permanent heating system and clean ducts.
 - .7 Ventilation: Provide minimum one air change per hour for enclosed areas receiving architectural finishes.
 - .8 Ensure adequate ventilation whenever using hazardous or volatile adhesives, coatings or substances.
 - .9 Do not allow excessive build up of moisture in the Work.
 - .3 Temporary Lighting: Provide and maintain suitable lighting during hours of darkness at danger points.
 - .4 Temporary Communications: Provide temporary telephones, and wireless internet service at Place of the Work, for own use and use of the Consultant.
 - .5 Temporary Water:
 - .1 Owner will designate an existing source, and pay the usage costs, for a continuous supply of potable water for construction use.
 - .2 Arrange for connection to designated source, and pay costs for installation, maintenance and removal.
 - .3 Ensure use of existing water sources does not interrupt or affect continuing operations of existing facility.

1.4 CONSTRUCTION FACILITIES

- .1 Field Offices
 - .1 Provide and maintain in clean condition during progress of Work, an adequately lighted, heated and ventilated construction office with sufficient space and furnishings to accommodate holding meetings, filing documents and laying out Contract Documents.
 - .2 Subcontractors may provide their own field offices as necessary. Direct location of Subcontractor field offices.
- .2 Storage Facilities
 - .1 Provide and maintain, in a clean and orderly condition, lockable weatherproof sheds for storage of Products and Construction Equipment.
 - .2 Do not store Products or Construction Equipment in field office.
- .3 First Aid
 - .1 Provide appropriate emergency and first aid equipment in accordance with authorities having jurisdiction.
 - .2 Mount emergency and first aid equipment in a prominent and easily accessible location with easily identifiable labels.
 - .3 A minimum of one person trained in basic first aid must be present at Place of the Work at all times during execution of the Work. This person may perform other duties, but must be immediately available to render first aid when needed.
- .4 Sanitary Facilities
 - .1 Provide sufficient quantity of separate temporary sanitary facilities for male and female workers in accordance with authorities having jurisdiction.
 - .2 Keep sanitary facilities clean and fully stocked with necessary supplies.
 - .3 New and existing permanent sanitary facilities may not be used.
 - .4 Except where connected to municipal sewer system, periodically remove wastes from Place of the Work.

1.5 TEMPORARY HOISTS AND CRANES

- .1 Provide, operate, and maintain temporary hoists and cranes required for moving construction personnel, Products, and Construction Equipment.
- .2 Make financial arrangements with Subcontractors for use thereof.
- .3 Temporary hoists and cranes must be operated by properly trained and qualified operators.

1.6 CONSTRUCTION PARKING

- .1 Limited parking will be permitted at Place of the Work, as long as it does not disrupt Owner's continuing operations of existing facility.

1.7 VEHICULAR ACCESS

- .1 Provide and maintain adequate access to Place of the Work, ensuring continuous access by emergency vehicles.
- .2 Construct and maintain temporary access roads as required or where indicated on Drawings.
- .3 Existing private roadways at Place of the Work may be used for access to Place of the Work. Contractor assumes responsibility for any damage caused by construction traffic and agrees to prevent or promptly clean up mud tracking or material spillage.
- .4 Clean municipal roadways located immediately adjacent to Place of the Work, regardless of cause, as follows:
 - .1 At least once per week on Friday afternoons, just before end of Working Day,
 - .2 After construction equipment or vehicles have left Place of the Work, resulting in soil or debris being deposited on roadway surfaces,

- .3 As directed by authorities having jurisdiction, and
 - .4 As directed by Consultant.
 - .5 Municipal Road Closures: Conform to requirements of authorities having jurisdiction.
- 1.8 TEMPORARY BARRIERS AND ENCLOSURES
- .1 Protective Enclosures:
 - .1 Erect 1 800 mm high temporary modular metal fencing system around Place of the Work.
 - .2 Protect public and workers from injury.
 - .3 Protect public and private property from damage.
 - .4 Provide locking gates to restrict access to only authorized personnel and vehicles.
 - .5 Provide and maintain full safety protection at open shafts in floors, roof decks and other working surfaces.
 - .6 Provide and maintain suitable warning signs as required by applicable regulatory requirements.
 - .2 Weather Enclosures:
 - .1 Provide weather tight closures to unfinished door and window openings, tops of shafts and other openings in floors and roofs.
 - .2 Close off floor areas where walls are not finished; seal off other openings; enclose building interior work for temporary heat.
 - .3 Dust Barriers:
 - .1 Provide dust tight screens or partitions to localize dust generating activities, and for the protection of workers, finished areas of Work and existing facility occupants.
 - .2 Maintain and relocate protection until such Work is complete.
 - .4 Security Measures:
 - .1 Maintain security at Place of the Work by controlling access through enclosing fences, barricades and hoardings during times the Work is in progress, and by locking hardware otherwise.
 - .2 After the Work is enclosed, maintain its security by adequate barriers to entry, and by temporary doors equipped with locking hardware.
 - .3 Maintain security at all times construction is shut down due to strikes or lockouts.
 - .4 Make Good damage resulting from vandalism or other breaches of security.
 - .5 Replace stolen and damaged Products resulting from breaches of security.
 - .5 Existing Building Entrances and Exits:
 - .1 Maintain existing building entrances and exits to ensure public safety.
 - .2 Where existing entrances and exits are blocked or adversely affected by construction activities, Provide temporary entrances and exits in accordance with regulatory requirements.
- 1.9 TEMPORARY CONTROLS
- .1 Erosion and Sediment Control: Provide erosion and sedimentation fencing with filter mat as required by authorities having jurisdiction.
 - .2 Temporary Dewatering:
 - .1 Provide temporary drainage and pumping as necessary to keep excavations and Place of the Work free from water.
 - .2 Dispose of water containing silt-in-suspension in accordance with authorities having jurisdiction.
 - .3 Maintain existing drainage, above ground and underground, adjacent to the Work or affected by the Work.

- .4 Before commencing any portion of the Work likely to affect the drainage of water from existing facility or Place of the Work, Provide necessary alternative drainage systems to ensure water will be conducted to alternative outlets. Do not block or impede any drain, roof outlet or rainwater leader after such safety precautions have been made.
- .3 Clean catch basins and storm lines at Place of the Work as required to ensure their continuous operation during execution of the Work.

1.10 PROJECT IDENTIFICATION

- .1 Owner will supply and install one Project identification sign.
- .2 Project identification sign will be approximately 2 440 x 6 100 mm in size; constructed of wood framing and plywood, and mounted to 4 wooden posts set in concrete pier foundations.
- .3 Maintain Owner's Project identification sign in clean condition for duration of the Contract.
- .4 Remove and dispose of Owner's Project identification sign, including concrete pier foundations, when directed by Consultant.
- .5 Make Good surrounding landscaping to match.

END OF SECTION

1 General

1.1 DEFINITIONS

- .1 Not In Contract (NIC) means an item that requires coordination for its later installation, and which is not Provided as part of the Work.
- .2 Owner-supplied Product means an item that will be supplied by Owner to SC01 - General Subcontractor for installation as part of the Work.

1.2 BASIC PRODUCT REQUIREMENTS

- .1 Refer to GC 3.8 - Labour and Products.
- .2 Products referred to in the singular implies the supply and installation of as many Products as necessary to complete the Work.
- .3 Unless specified otherwise, Consultant may select colours from manufacturer's complete range of available colours, textures and patterns, including those considered to be premium.
- .4 Conceal trademarks and labels, including applied labels, in finished areas of the Work. Trademarks and labels that are essential for identifying Products for maintenance purposes, and for identifying life safety, fire resistance and temperature rise ratings may remain visible.

1.3 OWNER-SUPPLIED PRODUCTS

- .1 Owner Responsibilities
 - .1 Order and pay for Owner-supplied Products not already in Owner's possession.
 - .2 Arrange and pay for delivery of Owner-supplied Products F.O.B. Place of the Work, within time frames required by Contractor's construction progress schedule. If delivered sooner than required by Contractor's latest construction progress schedule submitted to Owner, arrange and pay for delivery to a temporary storage location and subsequent delivery to Place of the Work.
 - .3 Advise Contractor in writing of the value of Owner-supplied Products for Contractor's insurance purposes.
 - .4 Arrange and pay for delivery to Contractor of reviewed Shop Drawings, Product data, samples, and manufacturer's instructions and certificates.
 - .5 Inspect deliveries jointly with Contractor.
 - .6 Submit claims for transportation damage.
 - .7 Arrange for replacement of damaged, defective or missing items identified at time of delivery.
 - .8 Arrange for manufacturer's field services.
 - .9 Arrange for delivery of manufacturer's warranties to Contractor for inclusion in operation and maintenance manuals.
- .2 Contractor Responsibilities
 - .1 Designate in construction progress schedule, time frames for delivery of Owner-supplied Products to Place of the Work and for receipt of related submittals. If Place of the Work is not ready to receive delivery of Owner-supplied Products within the time frame indicated in the latest construction progress schedule submitted to Owner, arrange and pay for delivery to a temporary storage location and subsequent delivery to Place of the Work.
 - .2 Review required submittals and notify Consultant of any observed discrepancies or anticipated problems.
 - .3 Ensure that course of construction insurance is adequate to cover Owner-supplied Products.
 - .4 Receive and unload Owner-supplied Products at Place of the Work.
 - .5 Inspect deliveries jointly with Owner. Record and notify Owner and Consultant of shortages and visibly damaged or defective items.

- .6 Handle Owner-supplied Products at Place of the Work, including uncrating and storage. Dispose of waste materials and debris.
- .7 Take appropriate precautions to protect Owner-supplied Products from loss or damage.
- .8 Repair or replace items damaged at Place of the Work.
- .9 Assemble, install, connect, adjust and finish Owner-supplied Products.
- .10 Arrange for inspections required by authorities having jurisdiction.
- .11 Arrange for or perform testing required by authorities having jurisdiction.
- .12 Workmanship warranty for installation.
- .13 Make Good Owner-supplied Products damaged by Contractor or Subcontractors at Place of the Work.

1.4 PRODUCT DELIVERY REQUIREMENTS

- .1 Ensure Products are packaged, delivered and stored to prevent damage and to ensure their moisture content is not increased beyond manufactured or specified installation limits.
- .2 Label packaged goods to completely describe contents.
- .3 Immediately review Product delivery requirements and anticipate foreseeable supply delays for any items.
- .4 In the event Contractor fails to notify Consultant of foreseeable supply delays at commencement of the Work, Consultant reserves the right to substitute more readily available Products of similar character, at no increase in Contract Price.

1.5 PRODUCT STORAGE AND HANDLING REQUIREMENTS

- .1 Handle and store Products in a manner to prevent damage, adulteration, deterioration, and soiling, and in accordance with manufacturer's instructions when applicable.
- .2 Provide necessary protection for those materials that require it.
- .3 Store Products in a neat and tidy manner.
- .4 Store packaged or bundle Product in original and undamaged condition with manufacturer's seal and labels intact. Do not remove from packaging or bundling until required in the Work.
- .5 Do not allow Product to be placed in contact with ground nor with other materials that could stain them. Store Product subject to damage from weather in weatherproof enclosures.
- .6 Store paint and other volatile substances in a separate structure located at least 15 metres from existing facility, and equipped with a suitable size and type of fire extinguisher.
- .7 Store Products within existing facility only as approved by Owner. Move Products stored within existing facility should they become a hindrance to Owner's operations, performance of the Work, or to delivery of other Products.
- .8 Receive, handle, protect, and store furniture, fitments, and equipment (FF&E) purchased by Owner for use in the Project as they are delivered to Place of the Work.
- .9 Remove flammable rubbish and packing materials from Place of the Work.

END OF SECTION

- 1 General
- 1.1 CONCEALED CONDITIONS
 - .1 Refer to GC 6.4 - Concealed or Unknown Conditions.
- 1.2 EXAMINATION AND ACCEPTANCE OF CONDITIONS
 - .1 Verify conditions are ready to receive installation.
 - .2 Ensure substrate surfaces are clean, dimensionally stable, cured and free of contaminants such as oil, sealers and curing compounds.
 - .3 Notify Consultant in writing of unacceptable conditions.
 - .4 Commencement of installation means acceptance of conditions.

END OF SECTION

1 General

1.1 EXECUTION REQUIREMENTS

- .1 Unless noted otherwise, install, apply, or erect Products in strict accordance with manufacturer's written installation instructions and guidelines.
- .2 Specifications requiring installation, erection, or application of Products to conform to a consensus standard does not replace or supercede the requirement to also conform to manufacturer's written installation instructions and guidelines.
- .3 Where manufacturer's installation instructions and requirements of a specified consensus standard are contradictory, manufacturer's written installation instructions and guidelines will govern.
- .4 Improper installation, application, or erection of Products will result in Consultant requiring their complete removal and replacement with new Products at no increase in Contract Price.
- .5 In finished areas, conceal facility service components within construction assemblies, except where indicated otherwise.
- .6 Extra payment for incidental furring or other enclosure will not be approved.
- .7 Prevent electrolytic and galvanic reactions from occurring between dissimilar metals and materials.
- .8 Make holes and voids required for facility service penetrations of correct size to accommodate penetrating items plus any fill material such as backer rods and joint sealants, insulation, firestops and smoke seals.
- .9 Remedial Work: Refer to GC 3.12 - Cutting and Remedial Work, and Section 01 73 29.

1.2 COLD WEATHER REQUIREMENTS

- .1 Perform the Work continually and avoid weather delays.
- .2 Provide temporary heating and cold weather working measures during cold weather periods and winter months. Refer to Section 01 50 00.
- .3 Construction delays, whether the responsibility of Contractor or otherwise, which result in unanticipated or extended winter work will not be considered justification for claims for additional payments.
- .4 Uniformly distribute heat to avoid hot or cool areas or excessive drying.

1.3 SITE STORAGE AND OVERLOADING

- .1 Refer to GC 3.11 - Use of the Work.
- .2 Unless specifically indicated, do not cut, drill or sleeve any load bearing structural member without prior written approval of Consultant.

1.4 EXISTING UTILITIES

- .1 Refer to GC 9.1 - Protection of Work and Property.
- .2 When breaking into or connecting to existing facility or utility services, execute Work at times directed by authorities having jurisdiction, with minimum disturbance to the Work, and to pedestrian and vehicular traffic.
- .3 Protect, relocate or maintain existing active services.

- .4 When existing services are encountered, cap off in a manner approved by authority having jurisdiction and stake or otherwise record location of capped service.

1.5 INTERFERENCES

- .1 Prior to commencement of the Work, coordinate placement of Products to ensure components are properly accommodated within designed spaces. Prepare and submit interference drawings as specified in Section 01 33 00.
- .2 Be responsible for additional work and costs necessitated by failure to coordinate the parts of the Work.
- .3 Provide adequate access and clearances around Products as required by authorities having jurisdiction, and as required for maintenance purposes by manufacturers.
- .4 Notify Consultant if Contract Documents are in conflict with access and clearance requirements.

1.6 LOCATION OF FIXTURES AND FITMENTS

- .1 Locations of fixtures and fitments indicated on Drawings are approximate only.
- .2 Locate fixtures and fitments precisely in the Work after consultation with affected installer and Consultant.

1.7 INSERTS, ANCHORS AND FASTENERS

- .1 Provide metal fastenings and accessories in same texture, colour and finish as adjacent materials, unless indicated otherwise.
- .2 Provide fasteners to the full required complement. Products with missing fasteners will be rejected by Consultant.
- .3 Use non-corrosive hot dip galvanized steel fasteners and anchors for securing exterior work, unless stainless steel or other material is specifically requested in affected Specification.
- .4 Use only factory made, threaded or toggle type inserts for supports and anchors, properly sized for load being carried.
- .5 Where inserts cannot be placed, use factory made expansion shields for light weights only.
- .6 Provide inserts, holes, anchor bolts and sleeves during placement or fabrication of structural elements.
- .7 Fasteners stressed in withdrawal will be rejected.
- .8 Metal fasteners are to be of a material that will not set up a galvanic reaction with the materials being fastened.
- .9 Powder-actuated fasteners are to be a system suitable for the specific application, corrosion-resistant, and capable of sustaining without failure a load equal to 10 times the design load when tested to ASTM E1190.
- .10 Do not use powder-actuated fasteners stressed in withdrawal for finished work.
- .11 Do not use powder-actuated fasteners within 100 mm of concrete or masonry edges.
- .12 Do not use powder-actuated fasteners in post-tensioned concrete.

1.8 TEMPLATES, BUILT-INS AND DIMENSIONS

- .1 Take dimensions necessary for the proper execution of the Work.

- .2 Assume responsibility for accuracy and completeness of dimensions.
- .3 Provide forms, templates, anchors, inserts and accessories to be fixed to or inserted as part of the Work.
- .4 Prepare and submit setting drawings, templates and other information necessary for placement and installation of Products, holes, sleeves, inserts, anchors, accessories, fastenings, connections and access panels.
- .5 Supply items in sufficient time, complete with templates and other necessary information, to accommodate installation without causing delay to the Work. Failure to do so will not result in an increase in Contract Price and Contract Time.
- .6 Verify that the Work, as it proceeds, is executed in accordance with dimensions and positions indicated, which maintain levels and clearances to adjacent work, as set out in Contract Documents.
- .7 Ensure defective and rejected work is corrected before subsequent construction commences. Refer to Section 01 71 00.
- .8 Verify details and measurements at Place of the Work prior to fabricating Products of special design to ensure fit.

END OF SECTION

1 General

1.1 SUBMITTALS

.1 Submit written request in advance of cutting or alteration which affects:

- .1 Structural integrity of any element of Project.
- .2 Integrity of weather-exposed or moisture-resistant elements.
- .3 Efficiency, maintenance or safety of any operational element.
- .4 Visual qualities of sight-exposed elements.
- .5 Work of Owner or other contractor.

.2 Include in request:

- .1 Identification of Project.
- .2 Location and description of affected work.
- .3 Statement on necessity for cutting or alteration.
- .4 Description of proposed work, and products to be used.
- .5 Alternatives to cutting and patching.
- .6 Effect on work of Owner or other contractor.
- .7 Written permission of affected other contractors.
- .8 Date and time work will be executed.

1.2 MATERIALS

- .1 Required for original installation.
- .2 Change in Materials: Submit requests for substitutions as specified in Section 01 25 00.

1.3 PREPARATION

- .1 Inspect existing conditions, including elements subject to damage or movement during cutting and patching.
- .2 After uncovering, inspect conditions affecting performance of work.
- .3 Beginning of cutting and patching means acceptance of existing conditions.
- .4 Provide supports to assure structural integrity of surroundings; devices and methods to protect other portions of project from damage.
- .5 Provide protection from elements for areas which may be exposed by uncovering work; maintain excavations free of water.

1.4 EXECUTION

- .1 Execute cutting, fitting, and patching including excavation and fill to complete the Work.
- .2 Fit the several parts together, to integrate with other work.
- .3 Uncover work to install ill-timed work.
- .4 Remove and replace defective and non-conforming work.
- .5 Remove samples of installed work for testing.
- .6 Provide openings in non-structural elements of the Work for penetrations by facility services.
- .7 Execute work by methods to avoid damage to other work, and which will provide proper surfaces to receive patching and finishing.
- .8 Employ properly trained labourers to perform cutting and patching for weather-exposed and moisture-resistant elements, and for visually-exposed surfaces.

- .9 Cut rigid materials using masonry saw or core drill. Pneumatic or impact tools are not allowed with masonry materials without prior written approval.
- .10 Restore work with new Products in accordance with requirements of Contract Documents.
- .11 Fit work airtight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
- .12 At penetration of fire-rated assemblies, completely seal voids with firestopping and smoke seal materials, for full thickness of assembly. Conform to Section 07 84 00.
- .13 Refinish surfaces to match adjacent finishes, as follows:
 - .1 Continuous Surfaces: Refinish to nearest intersection.
 - .2 Assemblies: Refinish entire unit.

END OF SECTION

- 1 General
- 1.1 REGULATORY REQUIREMENTS
 - .1 Comply with applicable regulatory requirements when disposing of waste materials.
 - .2 Obtain permits from authorities having jurisdiction and pay disposal fees where required for disposal of waste materials and recyclables.
- 1.2 GENERAL CLEANING REQUIREMENTS
 - .1 Provide adequate ventilation during use of volatile or noxious substances. Do not rely on building ventilation systems for this purpose.
 - .2 Use only cleaning materials recommended by manufacturer of surface to be cleaned, and as recommended by cleaning material manufacturer.
 - .3 Owner's cleaning equipment and supplies may not be used during construction.
 - .4 Prevent cross-contamination during cleaning process.
 - .5 Notify Consultant of the need for cleaning caused by Owner or other contractors.
 - .6 Assign cleaning duties to special dedicated crew with own foreman and of sufficient size and skill to prevent accumulation of waste, debris and dirt at Place of the Work.
- 1.3 PROGRESSIVE CLEANING AND WASTE MANAGEMENT
 - .1 Maintain the Work in tidy and safe condition, free from accumulation of waste materials and construction debris.
 - .2 Provide appropriate, clearly marked, containers for collection of waste materials and recyclables. Locate containers where they will not hinder the progress of the Work and Owner's continuing operations.
 - .3 Owner's existing waste containers at Place of the Work may not be used during construction.
 - .4 Remove waste materials and recyclables from work areas, separate, and deposit in designated containers at end of each Working Day. Collect packaging materials for recycling or reuse.
 - .5 Remove waste materials and recyclables from Place of the Work at regular intervals.
 - .6 Clean interior building areas prior to start of finish work and maintain free of dust and other contaminants during finishing operations.
 - .7 Schedule cleaning operations so that resulting dust, debris and other contaminants will not fall on wet, newly finished surfaces nor contaminate building systems.
 - .8 Clear snow and ice from public sidewalks affected by the Work to comply with applicable regulatory requirements of authority having jurisdiction.
- 1.4 FINAL CLEANING
 - .1 Before final cleaning, arrange a meeting at Place of the Work to determine the acceptable standard of cleaning. Ensure Owner, Consultant, Contractor and cleaning Subcontractor are in attendance.
 - .2 Remove from Place of the Work surplus Products, waste materials, recyclables, Temporary Work and Construction Equipment not required to perform any remaining work.
 - .3 Provide professional cleaning by a recognized, established cleaning company.

- .4 Lock or otherwise restrict access to each room or area after completing final cleaning in that area.
 - .5 Re-clean as necessary areas that have been accessed by Contractor's workers prior to Owner occupancy.
 - .6 Remove stains, spots, marks and dirt from finished surfaces, mechanical and electrical fixtures, furniture, fitments, walls, and floors.
 - .7 Clean and polish glass, mirrors, hardware, wall tile, stainless steel, chrome, porcelain enamel, baked enamel, plastic laminate and all other finished surfaces, including mechanical and electrical fixtures. Replace broken, scratched or otherwise damaged glass.
 - .8 Remove dust from lighting reflectors, lenses, lamps, bulbs, and other lighting surfaces.
 - .9 Vacuum clean and dust exposed wall, floor, and ceiling surfaces, above suspended ceiling tiles, and behind grilles, louvres and screens.
 - .10 Clean mechanical, electrical, and other equipment. Replace filters for mechanical equipment if equipment has been used during construction.
 - .11 Remove waste materials and debris from crawlspaces and other accessible concealed spaces.
 - .12 Remove stains, spots, marks, and dirt from exterior facades.
 - .13 Clean exterior and interior window glass and frames.
 - .14 Clean and sweep roofs, and clear roof drains.
 - .15 Wax, seal, shampoo or prepare floor finishes, as recommended by manufacturer.
 - .16 Power wash exterior paved surfaces.
 - .17 Use leaf blower to clean landscaped surfaces.
- 1.5 WASTE MANAGEMENT AND DISPOSAL
- .1 Conform to CCA 81-2001, A Best Practices Guide to Solid Waste Reduction.
 - .2 Fire and burning of waste and debris at Place of the Work is not permitted.
 - .3 Burying of waste and debris at Place of the Work is not permitted.
 - .4 Disposal of waste or volatile materials, such as kerosene, mineral spirits, oil or paint thinner into storm or sanitary sewers is prohibited. Collect such waste in appropriate containers and dispose of in accordance with applicable regulatory requirements.
 - .5 Provide on-site disposal service for rubbish accumulated by Subcontractors and Suppliers, in accordance with authorities having jurisdiction.
 - .6 Prevent extraneous materials from contaminating air beyond application areas by constructing temporary enclosures as specified in Section 01 50 00.
 - .7 Cover or wet down dry materials and rubbish to prevent blowing dust and debris.
 - .8 Deposit packaging materials in appropriate container at Place of the Work for recycling or reuse.
 - .9 Avoid using landfill waste disposal procedures when recycling facilities are available.

- .10 Keep discarded packaging away from children.
- 1.6 HAZARDOUS WASTE DISPOSAL
- .1 If and when required, remove and dispose of contaminated material in accordance with applicable regulatory requirements.
 - .2 Transport contaminated material using a licensed waste hauling company.
 - .3 Submit one copy of waste hauling company's Certificate of Approval to authority having jurisdiction prior to transporting contaminated materials.
 - .4 Stockpile suspected contaminated material temporarily in neat and secure stockpiles overlying a double layer of 0.20 mm thick high density polyethylene.
 - .5 Isolate stockpiles from remainder of Place of the Work and cover with a single layer of 0.20 mm thick polyethylene to prevent entry, wind disturbance or collection of surface water.
 - .6 Do not transport potentially contaminated material until such material has been identified by authority having jurisdiction.

END OF SECTION

- 1 General
- 1.1 REFERENCES
 - .1 AABC National Standards for Field Measurements and Instrumentation, Total Systems Balance, Air Distribution Hydronics Systems.
- 1.2 QUALITY ASSURANCE
 - .1 Testing Organization: Current member in good standing of AABC certified to perform specified services.
 - .2 Perform services under direction of supervisor qualified under certification requirements of sponsoring association.
- 1.3 SUBMITTALS
 - .1 Prior to commencement of the Work, submit names of specialty personnel proposed to perform services.
 - .2 Submit three copies of final reports on applicable forms.
- 1.4 SYSTEM START-UP PROCEDURES
 - .1 Comply with procedural standards of certifying associations under whose standards these services will be performed.
 - .2 Arrange for affected Subcontractors to send senior and capable personnel for demonstrations, training, and start-up instructions prior to system start-up.
 - .3 Start-up equipment and systems, bringing them to expected operational levels.
 - .4 Report to Consultant any deficiencies or defects noted during start-up.
 - .5 Prepare each system for testing and balancing.
- 1.5 TESTING, ADJUSTING AND BALANCING PROCEDURES
 - .1 Test equipment, balance distribution systems, and adjust devices.
 - .2 Cooperate with testing organization, ensuring adequate access to equipment and systems.
 - .3 Notify testing organization 7 days prior to when Project will be ready for testing, adjusting, and balancing.
 - .4 Provide instruments required for testing, adjusting, and balancing operations.
 - .5 Verify systems installation is complete and in continuous operation.
 - .6 Verify lighting is turned on when lighting is included in cooling load.
 - .7 Verify equipment is in full operation.

END OF SECTION

1 General

1.1 DEFINITIONS

- .1 Make Good means to restore new or existing work after being damaged, cut, patched, or rejected by Consultant. Use materials identical to original materials, with visible surfaces matching appearance of original surfaces in all respects, and with no apparent junctions between new and original surfaces.

1.2 PROTECTING INSTALLED CONSTRUCTION AND ADJACENT PROPERTY

- .1 Refer to GC 9.1 - Protection of Work and Property.
- .2 Refer to Product Specifications for material-specific protection requirements.
- .3 Adequately protect parts of the Work that are either completed or in-progress.
- .4 Unless specified otherwise, maintain protection until Substantial Performance of the Work.
- .5 Provide protective coverings at walls, projections, corners and jambs, sills, and soffits of openings in and adjacent to traffic areas.
- .6 Remove protection and protective coverings upon expiry of specified duration.
- .7 Protect Products from frost during construction.
- .8 Remove snow and ice from the uncompleted roof and from any floors.
- .9 As soon as the Work is sufficiently advanced, and in order to prevent delay, enclose the Work using tarpaulins, plastic sheeting or glazing, and temporary lockable doors.
- .10 Provide protection for completed and partially completed finishes and equipment during performance of the Work.
- .11 Protect prefinished Products from damage caused by subsequent construction operations.
- .12 Protect existing trees and vegetation designated to remain as part of Project to OPSS.MUNI 801. Provide snow fencing or other protection where directed by Consultant.

1.3 UNDERGROUND AND CONCEALED SERVICES

- .1 Protect facility and utility services from damage during performance of the Work.
- .2 Take necessary precautions to locate underground and concealed utility services. Protect concealed utility services from damage.

1.4 WATERPROOFING AND ROOFING

- .1 Restrict traffic from using waterproofed and roofed surfaces and restrict material storage on these surfaces.
- .2 Keep waterproofed and roofed surfaces free of debris.

1.5 MAKING GOOD

- .1 Make Good defective and damaged portions of the Work.
- .2 Make Good damage to property adjacent to Place of the Work.
- .3 Make Good damage to existing surfaces designated to remain as part of the Work.
- .4 Make Good damage to the Work resulting from lack of adequate heating protection.

- .5 Make Good damaged utility or facility services in accordance with authorities having jurisdiction.

END OF SECTION

- 1 General
- 1.1 ADMINISTRATIVE REQUIREMENTS
 - .1 Conform to OAA-OGCA Document 100-2025, Recommended Procedures Concerning Substantial Performance, Ready-for-Takeover, and Completion of Construction Projects.
 - .2 Additional Reviews Required of Consultant: In the event Consultant must undertake additional reviews and assessments beyond those described, and resulting from either Contractor's lack of preparation or their inability to correct deficiencies within the time prescribed, then Contractor shall reimburse Consultant for such additional reviews and assessments, paid for at Consultant's standard hourly rate.
- 1.2 VIDEO INSPECTION OF UNDERGROUND UTILITY SERVICES
 - .1 Prior to requesting Substantial Performance of the Work, conduct a video inspection of the interior condition of underground utility services, including water mains, storm sewers, and sanitary sewers.
 - .2 Pay for video inspection as Cost of the Work.
 - .3 Submit video record to Consultant.
- 1.3 ABOVE-CEILING WORK
 - .1 Prior to installation of gypsum board ceilings and placement of acoustical lay-in ceiling tiles, advise Consultant that above-ceiling work is complete and ready for review. Allow minimum 72 hours notice for any cancellation or changes; failure to do so may result in back charges to Contractor for costs of Owner's personnel.
 - .2 Owner, Consultant, and affected subconsultants will conduct above-ceiling review and prepare list of deficiencies.
 - .3 Correct deficiencies and advise Consultant when they have been corrected.
 - .4 Do not install gypsum board ceilings or acoustical ceiling panels until Consultant has verified that above-ceiling deficiencies have been corrected.
 - .5 Substantial performance inspection may not proceed until above-ceiling deficiencies have been corrected.
- 1.4 INTEGRATED SYSTEM TESTING OF FIRE PROTECTION AND LIFE SAFETY SYSTEMS
 - .1 Prior to requesting Substantial Performance of the Work, perform integrated system testing of fire protection and life safety systems as required by applicable regulatory requirements.
 - .2 Perform integrated system testing to CAN/ULC-S1001.
 - .3 In the event of a failed test, correct the failure, and re-test the unsuccessful integration at no additional cost to Owner.
 - .4 Upon successful completion of integrated system testing, submit integrated testing report to Consultant and Owner.
- 1.5 SUBSTANTIAL PERFORMANCE OF THE WORK
 - .1 Refer to GC 5.5 - Substantial Performance of the Work.
 - .2 Substantial Performance of the Work is required on or before November 30, 2026.
 - .3 Complete the Work, except SC04 - Metal Wall Panels, and ensure areas are fit for Owner occupancy on or before September 3, 2026.

- .4 Prior to requesting Substantial Performance of the Work, prepare and submit a complete deficiency list.
 - .5 Owner, Consultant, and affected subconsultants will review the Work, and may require additional items be added to deficiency list.
 - .6 Prior to requesting Substantial Performance of the Work, submit the following:
 - .1 Written statement that the Work has been substantially performed in accordance with Contract Documents, and is ready for use.
 - .2 Verification that operation of systems has been demonstrated to Owner.
 - .3 Two copies of complete and reviewed operation and maintenance manual.
 - .4 Inspection and acceptance certificates required from authorities having jurisdiction.
 - .5 Fire protection and life safety systems verification.
- 1.6 FINAL PAYMENT
- .1 When deficiencies have been corrected, and not later than 60 days after the date of Substantial Performance of the Work, request a final review of the Work.
 - .2 Owner, Consultant, and affected subconsultants will review the Work, and notify Contractor of outstanding deficiencies.
 - .3 After expiry of 60 day period, Owner may elect to correct outstanding deficiencies and deduct resulting costs from final payment. Deficient work shall be valued at 150 percent of normal cost with no item less than \$50.00.
 - .4 Prior to claiming final payment, submit:
 - .1 As-built drawings.
 - .2 A complete set of reviewed Shop Drawings, folded to 8-1/2" x 11" size, contained in heavy duty manila envelopes, numbered and labelled. Follow specification format with no more than one Section per envelope.
 - .3 Operation and maintenance manual.
 - .4 A final accounting of approved changes to Contract Price, including adjustments to cash allowances.

END OF SECTION

- 1 General
- 1.1 OPERATION AND MAINTENANCE MANUAL
 - .1 Prepare a comprehensive operation and maintenance manual, in the language of the Contract, using personnel qualified and experienced for this task.
 - .2 Submit an initial draft of operation and maintenance manual for Consultant's review. If required by Consultant's review comments, revise manual contents and resubmit for Consultant's review. If required, repeat this process until Consultant accepts draft manual in writing.
 - .3 Submit final version of operation and maintenance manual to Owner in both hard copy and electronic formats. Submit two hard copies.
- 1.2 OPERATION AND MAINTENANCE MANUAL FORMAT
 - .1 Organize data in the form of an instructional manual.
 - .2 Arrange content by systems, under Section numbers and sequence of Table of Contents.
 - .3 Hard Copy Requirements:
 - .1 Binders: Vinyl, hard covered, three D-rings, loose leaf, 215 x 280 mm size, with spine and face pockets.
 - .2 When multiple binders are used, correlate data into related consistent groupings. Identify contents of each binder on spine and front cover.
 - .3 Cover: Identify each binder with typed or printed title "Operation and Maintenance Manual", name of Project, and subject matter of contents.
 - .4 Include tabbed fly leaf for each separate Product or system, with typed description of Product and major component parts of equipment.
 - .5 Text: Manufacturer's printed data, or typewritten data.
 - .6 Drawings: With reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.
 - .4 Electronic Copy Requirements:
 - .1 Prepare electronic copy of operation and maintenance manual as a portable document format (.pdf) file.
 - .2 When multiple files are used, correlate data into related consistent groupings. Identify contents of each file in file name.
 - .3 Submit electronic copy of operation and maintenance manual on electronic media type acceptable to Owner.
 - .4 Include electronic bookmarks for each separate Product and system, with description of Product and major component parts of equipment.
 - .5 Include electronic copy of Shop Drawings in manual as portable document format (.pdf) files.
- 1.3 OPERATION AND MAINTENANCE MANUAL - GENERAL CONTENT
 - .1 Table of Contents for each volume.
 - .2 Introductory information, including:
 - .1 Date of manual submission.
 - .2 Complete contact information for Consultant, subconsultants, other consultants, and Contractor, with names of responsible parties identified for each.
 - .3 Schedule of Products and systems indexed to content of volume.
 - .3 For each Product or system, include complete contact information for Subcontractors, Suppliers and manufacturers, including local sources for supplies and replacement parts.

- .4 Product Data: Mark each sheet to clearly identify specific Products, options, and component parts, and data applicable to installation. Delete or strike out inapplicable information. Supplement with additional information as required.
 - .5 Reviewed Shop Drawings.
 - .6 Permits, certificates, letters of assurance, and other relevant documents issued by, or required by, authorities having jurisdiction.
 - .7 Warranties.
 - .8 Operating and maintenance procedures, incorporating manufacturer's operating and maintenance instructions, in a logical sequence.
 - .9 Training materials as specified in Section 01 79 00.
- 1.4 OPERATION AND MAINTENANCE MANUAL - EQUIPMENT AND SYSTEMS CONTENT
- .1 Each Item of Equipment and System: Include description of unit or system and component parts. Give function, normal operation characteristics, and limiting conditions. Include performance curves, with engineering data and tests, and complete nomenclature and commercial number of replaceable parts.
 - .2 Panel Board Circuit Directories: Include electrical service characteristics, controls, and communications.
 - .3 Include installed colour coded wiring diagrams.
 - .4 Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter and any special operating instructions.
 - .5 Maintenance Requirements: Include routine procedures and guide for trouble-shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing and checking instructions.
 - .6 Include servicing and lubrication schedule, and list of lubricants required.
 - .7 Include manufacturer's printed operation and maintenance instructions.
 - .8 Include sequence of operation by controls manufacturer.
 - .9 Include original manufacturer's parts list, illustrations, assembly drawings and diagrams required for maintenance.
 - .10 Include Contractor's coordination drawings, with installed colour coded piping diagrams.
 - .11 Include charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
 - .12 Include list of original manufacturer's spare parts, current prices and recommended quantities to be maintained in storage.
 - .13 Include testing and balancing reports.
 - .14 Include additional content as specified in Product Specifications.
- 1.5 OPERATION AND MAINTENANCE MANUAL - PRODUCTS AND FINISHES CONTENT
- .1 Include Product data, with catalogue number, options selected, size, composition, and colour and texture designations. Include information for re-ordering custom manufactured Products.

- .2 Include instructions for cleaning agents and methods, precautions against detrimental cleaning agents and methods, and recommended schedule for cleaning and maintenance.
 - .3 Include an outline of requirements for routine and special inspections and for regular maintenance to ensure that on-going performance of building envelope will meet the initial building envelope criteria.
 - .4 Include additional content as specified in Product Specifications.
- 1.6 OPERATION AND MAINTENANCE MANUAL - WARRANTIES CONTENT
- .1 Separate each warranty with index tab sheets keyed to Table of Contents listing.
 - .2 List each warrantor with complete contact information.
 - .3 Verify documents are in proper form and contain full information. Ensure warranties are for correct duration and are in Owner's name.
- 1.7 AS-BUILT DOCUMENTS
- .1 Promptly record revisions, omissions and additions on one set of black line opaque Drawings and in Specifications.
 - .2 Keep as-built documents up-to-date at all times. Failure to do so may result in postponement of payment.
 - .3 Record information concurrently with construction progress.
 - .4 Do not conceal work until required information is recorded.
 - .5 Legibly mark each item to record actual construction, including manufacturer name, trade name, and catalog number of each Product actually installed, particularly optional items and substitutions.
 - .6 Maintain manufacturers' certifications, inspection certifications, hardware schedules, colour schedules, and field test records as required by Specifications.
 - .7 Mark revised documents as "AS-BUILT".
 - .8 Include revisions, with special emphasis on mechanical, electrical, structural steel, and reinforced concrete.
 - .9 Prior to Substantial Performance of the Work, collect marked-up drawings from Subcontractors and have information electronically transferred to a master set of drawing files by Consultant. Pay Consultant for electronic transfer of as-built information from cash allowance specified in Section 01 21 00.
- 1.8 SPARE PARTS, SPECIAL TOOLS AND EXTRA MAINTENANCE MATERIALS
- .1 Two weeks prior to requesting Substantial Performance of the Work, submit to Consultant special tools or equipment required for maintenance purposes.
 - .2 Spare parts and maintenance materials shall be new, not damaged or defective, and of same quality and manufacture as Products incorporated in the Work. If requested, furnish evidence as to type, source and quality of spare parts and maintenance materials.
 - .3 Defective Products will be rejected, regardless of previous inspections. Replace defective Products.
 - .4 Store spare parts and extra maintenance materials in a manner to prevent damage or deterioration.

- .5 Submit spare parts, special tools, maintenance materials, and extra stock materials in specified quantities.

END OF SECTION

- 1 General
- 1.1 ADMINISTRATIVE REQUIREMENTS
 - .1 Demonstrate and train Owner's personnel on operation and maintenance of equipment, building envelope and systems prior to scheduled date of Substantial Performance of the Work.
 - .2 Owner will prepare a list of personnel to receive training, and will coordinate their attendance at agreed upon times.
 - .3 Coordinate and schedule demonstration and training given by Subcontractors and Suppliers.
- 1.2 SUBMITTALS
 - .1 Submit proposed dates, times, durations, and locations for demonstration and training of each item of equipment and each system for which demonstration and training is required. Allow sufficient time for training and demonstration for each item of equipment or system, or time as may be specified in Product Specifications.
 - .2 Consultant and Owner will review submittal and advise Contractor of any necessary revisions.
 - .3 Submit reports within 5 Working Days after completion of demonstration and training:
 - .1 Identifying time and date of each demonstration and training session.
 - .2 Summarizing the demonstration and training performed.
 - .3 Including a list of attendees.
 - .4 Submit video recordings of demonstration and training sessions together with reports.
- 1.3 PREREQUISITES TO DEMONSTRATION AND TRAINING
 - .1 Ensure testing, adjusting, and balancing has been performed in accordance with Contract Documents.
 - .2 Ensure equipment and systems are fully operational.
 - .3 Ensure a copy of completed operation and maintenance manual is available for use in demonstration and training.
 - .4 Ensure conditions for demonstration and training comply with requirements specified in Product Specifications.
- 1.4 DEMONSTRATION AND TRAINING
 - .1 Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, and maintenance of each item of equipment and system.
 - .2 Review operation and maintenance manual in detail to explain all aspects of operation and maintenance.
 - .3 Prepare and insert additional data in operation and maintenance manual if required.

END OF SECTION

- 1 General
 - 1.1 REFERENCES
 - .1 CSA Z783-12 (R2021): Deconstruction of Buildings and Their Related Parts.
 - 1.2 SEQUENCING
 - .1 Schedule deconstruction activities to minimize disruption to existing facility operations.
 - .2 Verify deconstruction schedule with Consultant prior to commencement of the Work.
 - .3 Protect existing facility occupants from dust, and from any danger arising from deconstruction operations. Refer to Section 01 50 00.
 - 1.3 SPECIAL PROCEDURE SUBMITTALS
 - .1 Submit three copies of each photograph taken of existing conditions to Consultant.
 - 1.4 QUALIFICATIONS
 - .1 Demolition Supervisor: An individual experienced in building deconstruction, capable of ensuring deconstruction is carried out safely, expeditiously, and without unnecessary damage to materials and surfaces designated to remain.
 - 1.5 FIELD CONDITIONS
 - .1 Inspect and photograph existing adjacent surfaces and assemblies.
 - .2 Record conditions and stability in a manner suitable for evaluation of possible damage caused by deconstruction operations.
 - .3 Approximate locations of existing facility services may be indicated on Drawings. Owner and Consultant assume no responsibility for accuracy of such information.
- 2 Products
 - 2.1 REGULATORY REQUIREMENTS
 - .1 Permits and Fees: Include tipping charges and other related fees necessary for completion of deconstruction operations.
 - .2 Utilities: Obtain approval from authorities having jurisdiction prior to commencing deconstruction operations.
 - .3 Hazardous Waste: Conform to authorities having jurisdiction.
 - 2.2 EQUIPMENT
 - .1 Deconstruction: Appropriate equipment for type of deconstruction being contemplated.
 - .2 Do not use heavy equipment for making openings in existing walls or in confined spaces where damage to other parts of the Work or adjacent property may result.
- 3 Execution
 - 3.1 EXAMINATION
 - .1 Refer to Section 01 71 00.
 - .2 Verify locations and construction of structures to be demolished.

- .3 Verify construction and details of other existing and adjacent property.
- .4 Verify location of utility and facility services.
- .5 Undertake x-ray investigations of existing building elements designated for selective demolition to determine locations of concealed components, utility services and facility services.

3.2 PREPARATION

- .1 Erect shoring, bracing and other temporary structures to prevent collapse, settlement, and movement of property. Refer to Section 01 50 00.
- .2 Provide and maintain dust protection screens as specified in Section 01 50 00.
- .3 Provide and maintain weather enclosures as specified in Section 01 50 00.
- .4 Barricade access by unauthorized persons to areas in which deconstruction is in-progress.
- .5 Post danger signs in conspicuous locations to warn persons that deconstruction is in-progress.
- .6 Erect protection to ensure safe access that must be maintained to existing areas still occupied by public.
- .7 Protect adjacent property from damage caused by deconstruction operations.
- .8 Remove flammable and contaminated materials, and refuse from area before deconstruction operations commence.
- .9 Arrange for disconnection, capping, and plugging of facility services that may be affected by deconstruction operations.

3.3 DECONSTRUCTION

- .1 Perform deconstruction work in an expeditious and safe manner.
- .2 Conform to CSA Z783.
- .3 Confine deconstruction operations to only those areas required.
- .4 Prevent and contain spread of dust.
- .5 Do not drop debris more than one storey unless in an enclosed chute. Lower large components carefully, under control, and fully supported at all times.
- .6 Withdraw or flatten protruding nails as deconstruction operations proceed.

3.4 SALVAGE

- .1 Carefully remove materials scheduled for salvage to CSA Z783.
- .2 Clean and prepare salvaged items for use by others.
- .3 Store salvaged materials in secure locations, protected from damage.
- .4 Items not scheduled for salvage become property of Contractor.

3.5 CLEANING

- .1 Leave Place of the Work in a clean and orderly condition, ready for use by others.
- .2 Remove waste and debris in accordance with authorities having jurisdiction.

- .3 Remove protections, barricades, and other temporary constructions on completion of deconstruction operations.
- .4 Make Good property and materials damaged during deconstruction operations.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 05 50 00 - Metal Fabrications.
- .2 Section 06 20 00 - Finish Carpentry.
- .3 Section 07 92 00 - Joint Sealants.
- .4 Section 08 12 13 - Hollow Metal Frames.

1.2 REFERENCES

- .1 ASTM A123/A123M-24: Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- .2 ASTM A153/A153M-23: Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
- .3 ASTM A641/A641M-19(2025): Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire.
- .4 ASTM A951/A951M-22: Standard Specification for Steel Wire for Masonry Joint Reinforcement.
- .5 ASTM A1011/A1011M-18a: Standard Specification for Steel, Sheet and Strip, Hot-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability and Ultra-High Strength.
- .6 CSA A165 SERIES-14 (R2019): CSA Standards on Concrete Masonry Units.
- .7 CAN/CSA-A179:14 (R2024): Mortar and Grout for Unit Masonry.
- .8 CSA A370:14 (R2023): Connectors for Masonry.
- .9 CAN/CSA-A371-14 (R2019): Masonry Construction for Buildings.
- .10 CSA A3001:23: Cementitious Materials for Use in Concrete.
- .11 CSA A3002:23: Masonry and Mortar Cement.
- .12 CSA G30.18:21: Carbon Steel Bars for Concrete Reinforcement.
- .13 CSA S304:24: Design of Masonry Structures.
- .14 NCMA TEK 3-2A-2005: Grouting Concrete Masonry Walls.
- .15 NCMA TEK 10-2C-2010: Control Joints for Concrete Masonry Walls - Empirical Method.

1.3 PRODUCT DATA

- .1 Submit Product data as specified in Section 01 33 00.
- .2 Product Data: Manufacturer's standard data sheets for mortar and grout design mixes, indicating required environmental conditions and admixture limitations.

1.4 QUALIFICATIONS

- .1 Manufacturers: A firm specializing in manufacturing concrete masonry units, having minimum 5 years documented experience, and a member of CCMFA.
- .2 Installers: A firm specializing in installing commercial masonry, having minimum 5 years documented experience, and a member of OMCA.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver mortar and grout materials in original unbroken and undamaged packages, with manufacturer's name and brand name distinctly marked.
- .3 Store mortar and grout materials in a shed until ready for use.
- .4 Store or pile sand on a plank platform, and protect from dirt and rubbish.
- .5 Store mortar materials and sand in a manner to prevent deterioration or contamination by foreign materials.
- .6 Deliver masonry units in an approved protective film.
- .7 Store masonry units off ground with care to avoid damage. Damaged units will not be acceptable for face work.

1.6 AMBIENT CONDITIONS

- .1 Environmental Requirements: To CAN/CSA-A371.
- .2 Do not use anti-freeze, liquid salts, or other substances to lower the freezing point of mortar or grout.

1.7 EXISTING CONDITIONS

- .1 Existing conditions at Place of the Work may require adjustment to counteract variations resulting from inaccuracies in previous construction.
- .2 The restricted availability of imperial-sized Products may also require that adjustments be made.
- .3 Make necessary adjustments to ensure proper fit and coursing of masonry.

2 Products

2.1 MORTAR AND GROUT MATERIALS

- .1 Portland Cement: To CSA A3001, Type GU; Grey colour.
- .2 Masonry Cement: To CSA A3002, Type S.
- .3 Mortar Aggregate: To CAN/CSA-A179, standard masonry type; clean, dry, protected against dampness, freezing, and foreign matter.
- .4 Grout Coarse Aggregate: To CAN/CSA-A179, maximum 10 mm OD; 27 percent by volume.
- .5 Grout Fine Aggregate: To CAN/CSA-A179, clean well graded sharp sand; 54 percent by volume.
- .6 Water: Potable, clean, and free of deleterious amounts of acids, alkalies, or organic materials.
- .7 Plasticizer: Water reducing type, reducing porosity and absorption to increase bond strength.

2.2 MASONRY MATERIALS

- .1 Concrete Masonry Unit (CMU): To CSA A165.1, using N aggregate; 190 mm face height, 390 mm face length, bed depths as indicated on Drawings; types as follows:
 - .1 Hollow: H/15/A/M.
 - .2 Solid (75 percent): S/15/A/M.
 - .3 Solid (100 percent): S_c/15/A/M.

2.3 REINFORCEMENT AND ANCHORAGES

- .1 Horizontal Joint Reinforcement: To CSA A370; Ladder-type, Standard Duty, fabricated from steel wire to ASTM A951/A951M; mill galvanized; BL-10 by Blok-Lok.
- .2 Steel Reinforcing Bars: To CSA G30.18, Grade 400R; new billet steel deformed bars; sizes as indicated on Drawings.
- .3 Rigid Strap Anchors: 6.0 mm thick, 38 mm wide steel plate with 50 mm long Z-shaped bends; hot dipped galvanized; lengths to suit application; eg. BLT-11Z by Blok-Lok.
- .4 Anchors: To CSA A370; purpose made for substrate; hot dipped galvanized steel.

2.4 MASONRY ACCESSORIES

- .1 Joint Filler: Closed cell polyurethane or polyethylene oversized by 50 percent; self-expanding.
- .2 Building Paper: No. 15 asphalt saturated felt.
- .3 Joint Sealant: Interior general purpose sealant, Type SEAL-INT-GP as specified in Section 07 92 00.

2.5 MORTAR MIXES

- .1 Mortar for Use with Concrete Unit Masonry: To CAN/CSA-A179, Type S using Proportion specification method; masonry cement-sand mix.

2.6 MORTAR MIXING

- .1 Thoroughly mix materials in proper measured quantities needed for immediate use, to CAN/CSA-A179.
- .2 Provide uniformity of mix and colouration.
- .3 Take representative samples for testing consistency of strength and colour to CAN/CSA-A179.
- .4 Use mortar within 1-1/2 hours after mixing at temperature of 25 degrees C or higher, or 2-1/2 hours after mixing at temperatures less than 25 degrees C.
- .5 Discard mortars exceeding time limits specified above.

2.7 GROUT MIXES

- .1 Grout for Use in Spaces 50 mm or Wider: To CAN/CSA-A179, Coarse Grout using Property Specification method; Portland cement-sand-coarse aggregate mix.
- .2 Grout for Use in Spaces Narrower than 50 mm: To CAN/CSA-A179, Fine Grout using Property Specification method; Portland cement-sand mix.
- .3 Match grout's 28 day compressive strength to compressive strength of concrete masonry unit being filled.

2.8 GROUT MIXING

- .1 Thoroughly mix materials in proper measured quantities needed for immediate use, to CAN/CSA-A179.
- .2 Use grout within 1-1/2 hours after mixing.
- .3 Discard grout exceeding time limit specified above.

2.9 FINISHES

- .1 Hot Dipped Galvanized Coating: To ASTM A123/A123M and ASTM A153/A153M, Class B2; minimum 458 g/m² zinc coating on all surfaces, except as specified below:
 - .1 Strap Anchors: To ASTM A123/A123M, Coating Grade 75; minimum 503 g/m² zinc coating on all surfaces.
- .2 Mill Galvanized Coating: To ASTM A641/A641M, Regular; minimum 30 g/m² zinc coating on all surfaces.

3 Execution

3.1 PREPARATION

- .1 Supply metal anchors to appropriate Subcontractors for placement. Direct correct placement.
- .2 Verify anchorages embedded in concrete or attached to structural steel members are properly placed. Embed anchorages in every second joint.
- .3 Apply bonding agent to existing concrete surfaces.
- .4 Plug clean-out holes with masonry units to prevent leakage of grout materials. Brace masonry for wet grout pressure.

3.2 COORDINATION WITH OTHERS

- .1 Securely install frames, louvres, sleeves, chases, reglets, and other equipment supplied by other Sections.
- .2 Anchor frames with backs of jambs solidly packed with mortar. Where mortar additives have been used to prevent freezing, coat metal frames with bitumen paint before installation.
- .3 Provide openings wherever required, including those required by facility services Subcontractors. Locating openings remains responsibility of component installer.
- .4 Accurately locate chases and openings, and neatly finish to required sizes.
- .5 No pipe, conduit chases, or enclosures shall be covered until advised that such portions of the Work have been inspected and tested.
- .6 Coordinate placement of steel and concrete anchors with appropriate Subcontractor.

3.3 COURSING

- .1 Place masonry to lines and levels indicated.
- .2 Maintain masonry courses to uniform width.
- .3 Lay concrete masonry units in half-running bond.
- .4 Maintain 10 mm thick mortar joints in both directions.
- .5 When thumbprint hard, tool mortar joints to a smooth, tightly compressed, concave profile.

3.4 PLACING AND BONDING

- .1 Lay masonry in full bed of mortar, properly jointed with other work. Buttering corners of joints, and deep or excessive furrowing of mortar joints are not permitted.
- .2 Fully bond intersections and external corners.
- .3 Strike mortar joints flush where resilient base is scheduled.
- .4 Isolate masonry partitions from vertical structural framing members with a control joint.
- .5 Extend and anchor non-loadbearing partitions to underside of structural deck.
- .6 Use bull-nosed concrete masonry units at exposed corners.

3.5 REINFORCEMENT AND ANCHORAGES

- .1 Conform to CSA A370.
- .2 Place masonry joint reinforcement continuous in every second bed joint.
- .3 Place masonry joint reinforcement in first and second bed joints above and below openings. Extend 400 mm minimum each side of opening.
- .4 Place joint reinforcement continuous in first and second bed joint below top of walls.
- .5 Install reinforcing bars supported and secured against displacement.
- .6 Reinforce joint corners and intersections of concrete unit masonry walls and partitions with strap anchors 400 mm OC.

3.6 LINTELS

- .1 Install loose steel lintels as scheduled. Set steel lintels dry to permit movement.
- .2 Install reinforced unit masonry lintels over openings where steel or precast concrete lintels are not scheduled. Construct lintels using grout fill and reinforcing. Maintain minimum 200 mm bearing on each side of opening.

3.7 GROUTED COMPONENTS

- .1 Install masonry grout to NCMA TEK 3-2A.
- .2 Fill masonry cores located within 300 mm of a wall opening solid with masonry grout.

3.8 CONTROL JOINTS

- .1 Provide control joints in concrete unit masonry to NCMA TEK 10-2C.
- .2 Do not continue horizontal joint reinforcing across control joints.
- .3 Size joints as specified in Section 07 92 00 for sealant performance.

3.9 TOLERANCES

- .1 Variation from Unit to Adjacent Unit: ≤ 1.5 mm.
- .2 Variation of Joint Thickness: ≤ 3 mm in 1 000 mm.

3.10 CLEANING

- .1 Clean masonry as work progresses.
- .2 Allow mortar droppings on masonry to partially dry, then remove by means of brushing with a stiff fibre brush.
- .3 Post-Construction: Clean a 10 m² area of wall designated by Consultant as described below, and leave for one week. If no harmful effects appear and after mortar has set and cured, clean masonry as follows:
 - .1 Protect windows, sills, doors, trim and other work from damage.
 - .2 Remove large particles with stiff fiber brushes or wood paddles without damaging surface. Saturate masonry with clean water and flush off loose mortar and dirt.
 - .3 Scrub with solution of 25 mL trisodium phosphate and 25 mL household detergent dissolved in 1 Litre of clean water using stiff fibre brushes, then clean off immediately with clean water using hose.
 - .4 Repeat cleaning process as often as necessary to remove mortar and other stains.
- .4 Use alternative cleaning solutions and methods for difficult to clean masonry only after consultation with masonry unit manufacturer.

3.11 FIELD QUALITY CONTROL

- .1 Perform field inspection and testing as described in Section 01 40 00.
- .2 Submit sample cubes of mortar and grout for laboratory testing as specified in Section 01 40 00, and to CSA S304.
- .3 Report on compressive strength and water content of mortar and grout mixes.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 07 84 00 - Firestopping.
- .3 Section 09 90 00 - Painting and Coating.

1.2 REFERENCES

- .1 AAMA 2604-22: Voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels (With Coil Coating Appendix).
- .2 ASTM A123/A123M-24: Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- .3 ASTM A153/A153M-23: Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
- .4 ASTM A240/A240M-22b: Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications.
- .5 ASTM A269/A269M-22: Standard Specification for Seamless and Welded Austenitic Stainless Steel Tubing for General Service.
- .6 ASTM A276/A276M-25: Standard Specification for Stainless Steel Bars and Shapes.
- .7 ASTM A307-21: Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength.
- .8 ASTM A385/A385M-22: Standard Practice for Providing High-Quality Zinc Coatings (Hot-Dip).
- .9 ASTM A449-14(2020): Standard Specification for Hex Cap Screws, Bolts and Studs, Steel, Heat Treated, 120/105/90 ksi Minimum Tensile Strength, General Use.
- .10 ASTM A563/A563M-24: Standard Specification for Carbon and Alloy Steel Nuts (Inch and Metric).
- .11 ASTM A653/A653M-23: Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
- .12 ASTM A780/A780M-20: Standard Practice for Repair of Damaged and Uncoated Areas of Hot-Dip Galvanized Coatings.
- .13 ASTM A1008/A1008M-23e1: Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Required Hardness, Solution Hardened, and Bake Hardenable.
- .14 ASTM D6386-22: Standard Practice for Preparation of Zinc (Hot-Dip Galvanized) Coated Iron and Steel Product and Hardware Surfaces for Painting.
- .15 ASTM D7803-25: Standard Practice for Preparation of Zinc (Hot-Dip Galvanized) Coated Iron and Steel Product and Hardware Surfaces for Powder Coating.
- .16 ASTM F436/F436M-24: Standard Specification for Hardened Steel Washers Inch and Metric Dimensions.

- .17 ASTM F593-24: Standard Specification for Stainless Steel Bolts, Hex Cap Screws, and Studs.
 - .18 ASTM F594-22: Standard Specification for Stainless Steel Nuts.
 - .19 ASTM F3125/F3125M-25a: Standard Specification for High Strength Structural Bolts and Assemblies, Steel and Alloy Steel, Heat Treated, Inch Dimensions 120 ksi and 150 ksi Minimum Tensile Strength, and Metric Dimensions 830 MPa and 1040 MPa Minimum Tensile Strength.
 - .20 CSA G40.20-13 (R2023): General Requirements for Rolled or Welded Structural Quality Steel.
 - .21 CSA G40.21-13 (R2023): Structural Quality Steel.
 - .22 CSA S136-16 (R2021): North American Specification for the Design of Cold-Formed Steel Structural Members.
 - .23 CSA W47.1:19: Certification of Companies for Fusion Welding of Steel.
 - .24 CSA W55.3-08 (R2023): Certification of Companies for Resistance Welding of Steel and Aluminum.
 - .25 CSA W59:24: Welded Steel Construction.
- 1.3 SHOP DRAWINGS
- .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, prepared for each required custom-fabricated metal item, illustrating profiles, sizes, connection attachments, reinforcing, anchorage, size and type of fasteners, and accessories.
- 1.4 QUALIFICATIONS
- .1 Fabricator: A firm specializing in fabricating custom metal components, having minimum three years documented experience.
 - .2 Welders: Workers certified by CWB to CSA W47.1 and CSA W55.3; as applicable.
- 2 Products
- 2.1 DESIGN CRITERIA
- .1 Design cold-formed steel fabrications to CSA S136.
 - .2 Design galvanized metal fabrications to accommodate venting and drainage during hot dip galvanizing process, to ASTM A385/A385M.
- 2.2 MATERIALS
- .1 Galvanized Sheet Steel: To ASTM A653/A653M, Structural Steel (SS) Grade 230, Types 1 and 2; cold-rolled sheet steel, galvanized; thicknesses as indicated.
 - .2 Sheet Steel: To ASTM A1008/A1008M, Structural Steel (SS) Grade 230, Types 1 and 2; cold-rolled sheet steel, thicknesses as indicated.
 - .3 Steel Sections and Plates: To CSA G40.20 and CSA G40.21, Grade 300W; profiles and sizes as indicated.
 - .4 Hollow Structural Steel Sections: To CSA G40.20 and CSA G40.21, Grade 350W, Class H; sizes as indicated.

- .5 Stainless Steel Sheet, Sections and Plates: To ASTM A240/A240M, Type 304L for welded applications and Type 304 for other applications; thicknesses and sizes as indicated.
- .6 Stainless Steel Tubing: To ASTM A269/A269M, Grade TP316L; thicknesses, diameters, and sizes as indicated.
- .7 Stainless Steel Bars and Shapes: To ASTM A276/A276M, Type 304L for welded applications and Type 304 for other applications; sizes and profiles as indicated.

2.3 ACCESSORIES

- .1 Stainless Steel Bolts: To ASTM F593, Group 1.
- .2 Stainless Steel Nuts and Washers: To ASTM F594, Group 1.
- .3 High-Strength Bolts: To ASTM F3125/F3125M, Type 1; quenched and tempered steel heavy hex structural bolts.
- .4 Medium-Strength Bolts: To ASTM A449, Type 1; quenched and tempered steel hex bolts.
- .5 Machine Bolts: To ASTM A307, Grade A; carbon and alloy steel, galvanized where noted.
- .6 Steel Nuts: To ASTM A563/A563M, Grade A, Heavy Hex Style for use with high strength bolts, and Hex Style for use with medium strength bolts and machine bolts; carbon and alloy steel; galvanized where noted.
- .7 Steel Washers: To ASTM F436/F436M, Type 1; hardened steel washers, circular, bevelled, and clipped types as required.
- .8 Welding Materials: To CSA W59 and CSA W59.2.

2.4 PRIMERS

- .1 Primer for Ferrous Metal Surfaces: Red oxide type.
- .2 Primer for Galvanized Surfaces: Zinc-rich paint type.

2.5 FABRICATION

- .1 Prior to fabrication, verify existing conditions and take field measurements to ensure perfect fit.
- .2 Fabricate cold-formed steel components to CSA S136.
- .3 Shop weld steel components to CSA W59.
- .4 Fit and shop assemble components in largest practical sections to accommodate delivery to Place of the Work.
- .5 Seal joints with continuous welds.
- .6 Grind visually-exposed joints flush and smooth with adjacent finish surface.
- .7 Make visually-exposed joints butt tight, flush, and hairline.
- .8 Exposed Mechanical Fastenings: Flush countersunk screws or bolts; except where specifically noted otherwise.
- .9 Supply components required for anchorage of fabrications.

2.6 FINISHES

- .1 Shop Priming:
 - .1 Clean surfaces of rust, scale, grease, and foreign matter prior to shop priming.
 - .2 Do not prime surfaces designated to come into direct contact with concrete, or where field welding is required.
 - .3 Prime components using minimum two coats primer.
- .2 Galvanizing:
 - .1 Galvanized Coating on Steel Components: To ASTM A123/A123M, Coating Grade 55; hot dipped zinc alloy coating.
 - .2 Galvanized Coating on Steel Hardware: To ASTM A153/A153M, Classes B3, C or D; hot dipped zinc alloy coating.
 - .3 Galvanized Coating on Sheet Steel: To ASTM A653/A653M, Coating Designation Z275; hot dipped zinc alloy coating.
 - .4 Prepare hot dip galvanized coatings to ASTM D6386 for subsequent paint application.
 - .5 Prepare hot dip galvanized coatings to ASTM D7803 for subsequent powder coating application.
- .3 Stainless Steel: To AISI No. 4 - Brushed.
- .4 Powder Coated Finish on Metal Components: To AAMA 2604; electrostatically sprayed polymer powder, factory-applied to 0.05 mm dry film thickness; colour as selected by Consultant.
- .5 Monochromatic Paint Coating on Sheet Steel: Two-coat silicone modified polyester coil coating, factory-applied to 0.028 mm dry film thickness; eg. WeatherXL by The Sherwin-Williams Company, colour as selected by Consultant.

3 Execution

3.1 PREPARATION

- .1 Make provision for erection loads with temporary bracing.
- .2 Clean and strip primed steel items to bare metal where field welding is required.
- .3 Supply items required to be cast into concrete and or embedded in masonry with setting templates, to appropriate Sections.

3.2 INSTALLATION

- .1 Install Products plumb, level, and accurately fitted.
- .2 Install Products free from distortion or defects.
- .3 Provide fasteners and anchors necessary to secure components rigidly in place.
- .4 Field weld steel components to CSA W59.
- .5 Field bolt and weld to match shop bolting and welding.
- .6 Mechanically fasten joints butted tight, flush, and hairline.
- .7 Grind welds smooth and flush.
- .8 After erection, prime welds, abrasions, and surfaces not yet shop primed or galvanized, except surfaces designated to come into direct contact with concrete.
- .9 Make Good damaged or defective galvanized coatings to ASTM A780/A780M.

3.3 SCHEDULE

- .1 The following schedule is a list of principal items only. Refer to Drawings for items not specifically scheduled.
 - .1 Sleeves and Openings: Including templates and required information, supplied to appropriate Sections.
 - .2 Attachments: Anchor bolts, washers, nuts, lag screws, expansion shields, toggles, straps, sleeves, and brackets; secured with sufficient self-tapping shake-proof screws with flat countersunk heads.
 - .3 Brackets: Fabricated from mild steel plate, sizes and configurations as required to support countertops, shelving, seating, benches, valances, coat hooks, and other similar components; pre-drilled for fastening of other components.
 - .4 Lateral Support Brackets for Masonry Partitions: 75 x 75 mm steel angles, 6 mm thick, as follows:
 - .1 Concealed Conditions: 200 mm long and spaced at 3 000 mm OC; minimum two anchors each.
 - .2 Exposed Conditions: Continuous lengths, anchored at 1 000 mm OC.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 06 20 00 - Finish Carpentry.
 - .2 Section 06 41 00 - Architectural Wood Casework.
- 1.2 REFERENCES
 - .1 ASTM A153/A153M-23: Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
 - .2 ASTM F1667-21: Standard Specification for Driven Fasteners: Nails, Spikes and Staples.
 - .3 CSA O80 Series:21: Wood Preservation.
 - .4 CSA O86:19: Engineering Design in Wood.
 - .5 CSA O112.9:21: Evaluation of Adhesives for Structural Wood Products (Exterior Exposure).
 - .6 CSA O141:23: Canadian Standard Lumber.
 - .7 CSA O151:17 (R2022): Canadian Softwood Plywood.
 - .8 NLGA Standard Grading Rules for Canadian Lumber (2022 Edition).
 - .9 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- 1.3 QUALITY ASSURANCE
 - .1 Lumber Identification: Grade stamp clearly identifying assigned grade, mill of origin, moisture content at time of manufacture, species or species group, and grading authority having jurisdiction over mill of origin.
 - .2 Plywood Identification: Face or edge stamp depending on appearance requirement, clearly identifying panel grade, species designation, mill identification, certifying agency and waterproof glue bond designation.
- 1.4 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Deliver and store Products under waterproof cover.
 - .3 Prevent damage to Products, existing properties and to the Work.
 - .4 Store Products where it does not hinder progress of the Work.
- 1.5 EXISTING CONDITIONS
 - .1 The Work involves renovations and alterations to an existing facility.
 - .2 Include re-blocking or re-framing as required.
 - .3 Make minor adjustments from Drawings wherever existing conditions dictate.

2 Products

2.1 MATERIALS

- .1 Dimension Lumber: To CSA O141, S4S; SPF species, kiln dried to S-DRY moisture content; preservative treated for exterior applications where noted on Drawings, sizes as indicated on Drawings; NLGA Light Framing Grade Category, Standard and Better Common Grade Mix.
- .2 Plywood: To CSA O151, CSP species, SHG Grade, Exterior waterproof glue bond; veneer core, butt edge, unsanded faces; flame retardant treated where noted; thicknesses as indicated on Drawings.
- .3 Nails: To ASTM F1667, Type I (NL); galvanized steel, common wire type for general use and spiral type for structural connections; sizes necessary to ensure adequate securement.
- .4 Spikes: To ASTM F1667, Type III (SP); galvanized steel, common wire type for general use and spiral type for structural connections; sizes necessary to ensure adequate securement.
- .5 Staples: To ASTM F1667, Type IV (ST); galvanized steel, common wire; leg length necessary to ensure adequate securement.
- .6 Screws: Galvanized steel, bugle head, power driven type, sizes necessary to ensure adequate securement.
- .7 Adhesive: To CSA O112.9.
- .8 Anchors: Toggle bolt type for anchorage to hollow masonry, expansion shield and lag bolt type for anchorage to solid masonry or concrete, or bolts or ballistic fasteners for anchorages to steel.
- .9 Touch-Up Wood Preservative: To CSA O80; brush-applied copper azole (CBA-A or CA-B) or alkaline copper quaternary (ACQ) preservative.
- .10 Touch-up Flame Retardant Coating: To CSA O80; brush-applied Dricon by Lonza.

2.2 FINISHES

- .1 Galvanized Coating on Steel Fasteners: To ASTM A153/A153M, Classes C or D; hot dipped zinc alloy coating.
- .2 Flame Retardant Treatment
 - .1 Flame Retardant Treatment: To CSA O80; chemically treated and pressure impregnated; as follows:
 - .1 Surface Burning Characteristics (CAN/ULC-S102): Flame spread index ≤ 25 .
 - .2 Manufacturer and Product Name: eg. Dricon by Lonza.
 - .2 Flame retardant treated materials must bear a ULC classification label.
- .3 Wood Preservative Treatment:
 - .1 Wood Preservative Treatment: To CSA O80; chemically treated and pressure impregnated using copper azole (CBA-A or CA-B) or alkaline copper quaternary (ACQ) preservative.
 - .2 Preservative treated materials must bear CSA classification label.
 - .3 Make preservative treated materials available for inspection by Consultant at place of treatment, before shipment to Place of the Work.

3 Execution

3.1 SITE APPLIED WOOD TREATMENT

- .1 When wood in contact with exterior cementitious materials, roofing and related metal flashings has not been previously preservative treated, brush apply two coats of touch-up wood preservative.
- .2 Apply two coats of touch-up wood preservative to sawn ends of preservative treated material.
- .3 Apply two coats of touch-up flame retardant coating to sawn ends of flame retardant treated material.
- .4 Apply touch up coatings to CSA O80.

3.2 INSTALLATION

- .1 Erect wood framing members level and plumb.
- .2 Place horizontal members laid flat, crown side up.
- .3 Construct framing members full length without splices.
- .4 Secure plywood sheets perpendicular to framing members, with ends staggered and sheet edges secured directly over firm bearing.
- .5 Provide wood blocking required for attachment of fitments and equipment by other Sections.
- .6 Provide 19 mm thick flame retardant treated plywood backer board on wood blocking for mounting electrical equipment where indicated on Drawings.
- .7 Construct curb and cant members of single pieces per location. Form corners by lapping side members alternately.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 07 21 00 - Thermal Insulation.
- .2 Section 07 21 19.13 - Foamed-in-Place Urethane Insulation.
- .3 Section 07 27 00 - Air Barriers.
- .4 Section 07 92 00 - Joint Sealants.

1.2 REFERENCES

- .1 ASTM C475/C475M-17(2022): Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board.
- .2 ASTM C954-22: Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs From 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness.
- .3 ASTM C1002-20: Standard Specification for Steel Self-Piercing Tapping Screws for Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs.
- .4 ASTM C1177/C1177M-24: Standard Specification for Glass Mat Gypsum Substrate for Use as Sheathing.
- .5 ASTM C1264-19(2024): Standard Specification for Sampling, Inspection, Rejection, Certification, Packaging, Marking, Shipping, Handling, and Storage of Gypsum Panel Products.
- .6 ASTM C1280-25: Standard Specification for Application of Exterior Gypsum Panel Products for Use as Sheathing.
- .7 CGC Gypsum Construction Handbook.
- .8 CAN/CGSB-71.25-M88: Adhesive, for Bonding Drywall to Wood Framing and Metal Studs.
- .9 GA-214-2021: Levels of Finish for Gypsum Panel Products.
- .10 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .11 ULC List of Equipment and Materials.

1.3 QUALIFICATIONS

- .1 Applicators: A firm specializing in applying gypsum sheathing, having minimum 5 years documented experience.

1.4 DELIVERY, STORAGE AND HANDLING

- .1 Conform to ASTM C1264.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 CertainTeed Canada, Inc.
 - .2 CGC Inc.
 - .3 G-P Gypsum Corporation.

- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 MATERIALS

- .1 Gypsum Sheathing Board (GSB-1): To ASTM C1177/C1177M; as follows:
 - .1 Thickness 12.7 mm.
 - .2 Edges: Square.
 - .3 Core: Silicone-treated gypsum.
 - .4 Facers: Glass fiber mesh, both sides.
 - .5 Manufacturer and Product Name: eg. DensGlass Exterior Sheathing by G-P Gypsum Corporation.
- .2 Gypsum Sheathing Board (GSB-2): To ASTM C1177/C1177M, Type X; as follows:
 - .1 Thickness: 15.9 mm.
 - .2 Edges: Square.
 - .3 Core: Silicone-treated gypsum.
 - .4 Facers: Glass fiber mesh facers, both sides.
 - .5 Flame Spread Index (CAN/ULC-S102): ≤ 10 .
 - .6 Manufacturer and Product Name: eg. DensGlass Fireguard Sheathing by G-P Gypsum Corporation.
- .3 Steel Drill Screws: To ASTM C954; galvanized steel, sheet metal type.
- .4 Self-Tapping Screws: To ASTM C1002, Type S, Fine Thread; galvanized steel.
- .5 Adhesive: To CAN/CGSB-71.25-M.
- .6 Joint Materials: To ASTM C475/C475M; reinforcing tape, joint compound, adhesive, and water.
- .7 Joint Sealant: Exterior weatherseal sealant, Type SEAL-EXT as specified in Section 07 92 00.

3 Execution

3.1 INSTALLATION

- .1 Install Products to ASTM C1280.
- .2 Install boards perpendicular to supports with ends staggered.
- .3 Secure board edges over firm bearing.
- .4 Screw fasten boards to furring or framing.
- .5 Finish boards to GA-214, Level 1.
- .6 Finished work shall be plane and free from depressions.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 06 10 00 - Rough Carpentry.
 - .2 Section 06 24 00 - High Pressure Decorative Laminate.
 - .3 Section 06 41 00 - Architectural Wood Casework.
 - .4 Section 07 92 00 - Joint Sealants.
 - .5 Section 08 71 00 - Door Hardware.
 - .6 Section 09 90 00 - Painting and Coating.
- 1.2 REFERENCES
 - .1 ANSI A135.4-2004: Basic Hardboard.
 - .2 ANSI A208.1-2009: Particleboard.
 - .3 ASTM B456-17(2022): Standard Specification for Electrodeposited Coatings of Copper Plus Nickel Plus Chromium and Nickel Plus Chromium.
 - .4 ASTM F1667-21: Standard Specification for Driven Fasteners: Nails, Spikes and Staples.
 - .5 AWMAC NAAWS 4.0-2021: North American Architectural Woodwork Standards.
 - .6 CSA O141:23: Canadian Standard Lumber.
 - .7 CSA O151:17 (R2022): Canadian Softwood Plywood.
 - .8 ANSI/HPVA HP-1-2020: American National Standard for Hardwood and Decorative Plywood.
 - .9 NHLA Grading Rules.
- 1.3 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Verification Samples: Duplicate samples, as follows:
 - .1 Melamine Composite Panel: 300 x 300 mm size, illustrating laminate-clad face colour, pattern and texture; core materials; and quality of PVC edgebanding.
 - .2 Hardwood Plywood: 300 x 300 mm size, illustrating full thickness of sheet, number of plies, edge and joint trim, and quality of wood grain.
 - .3 Hardwood Trim: 300 mm long, illustrating size and shape of profiles, and quality of wood grain.
- 1.4 QUALIFICATIONS
 - .1 Trim and Finish Carpenter: A firm employing workers specializing in finish carpentry work, having minimum three years documented experience.
- 2 Products
- 2.1 LUMBER
 - .1 Dressed Softwood Lumber (DL-SWD): To CSA O141, S4S; SPF species, kiln dried to maximum 7 percent moisture content, with mixed grain capable of receiving high quality opaque finish; sizes as indicated on Drawings.

- .2 Dressed Hardwood Lumber (DL-HWD): To NHLA Select and Better Grade; Maple species, kiln dried to maximum 7 percent moisture content, with vertical mixed grain capable of receiving high quality transparent finish; sizes as indicated on Drawings.
- .3 Dimension Lumber: As specified in Section 06 10 00.

2.2 PLYWOOD

- .1 Softwood Plywood (PLY-SWD): To CSA O151, CSP species, SEL TF Grade; softwood veneer core of minimum 9 plies bonded with waterproof glue; thicknesses as indicated on Drawings; capable of receiving high quality opaque finish.
- .2 Softwood Plywood - Moisture-Resistant Core (PLY-SWD-MR): To CSA O151, CSP species, SEL TF Grade; composite core of moisture-resistant particle board to ANSI A208.1, Grade M-3 - Exterior Glue; thicknesses as indicated on Drawings; capable of receiving high quality opaque finish.
- .3 Hardwood Plywood (PLY-HWD): To ANSI/HPVA HP-1, Architectural G1S, thicknesses as indicated on Drawings; as follows:
 - .1 Core: Hardwood veneer core, minimum 9 plies, bonded with waterproof glue.
 - .2 Face Veneers: Maple species; Face Grade A; Plain-Sliced; of clear Pleasing match grain capable of receiving high quality transparent finish.
- .4 Hardwood Plywood - Moisture-Resistant Core (PLY-HWD-MR): To ANSI/HPVA HP-1, Architectural G1S, thicknesses as indicated on Drawings; as follows:
 - .1 Core: Composite core, moisture-resistant particle board to ANSI A208.1, Grade M-3 - Exterior Glue.
 - .2 Face Veneers: Maple species; Face Grade A; Plain-Sliced; of clear Pleasing match grain capable of receiving high quality transparent finish.

2.3 COMPOSITE BOARDS AND PANELS

- .1 Particleboard (PB): To ANSI A208.1, Grade M-2; made from 100 percent post-industrial wood fibres; minimum 635 kg/m³ density and maximum 6 percent moisture content; no added urea formaldehyde (nauf); certified EPP by Composite Panel Association; thicknesses as indicated on Drawings.
- .2 Melamine Composite Panel (MCP): Particleboard core with factory-applied low pressure laminate thermo-fused to both faces; Premium quality; thicknesses as indicated on Drawings; colours, textures, and patterns as selected by Consultant.
- .3 Hardboard (HB): To ANSI A135.4, Class 1 - Tempered; inter-felted ligno-cellulosic fibers consolidated under heat and pressure; minimum 500 kg/m³ density; S1S surface finish; thicknesses as indicated on Drawings.

2.4 ACCESSORIES

- .1 Metal Tube Closet Rod System: 27 mm OD, heavy wall steel tube rod, with heavy duty metal flanges and brackets; chrome-plated finish.
- .2 Coat Hook: Two-prong heavy duty design, 4.5 mm thick flat steel bar, 108 mm high, 19 mm wide; pre-drilled for screw attachment; zinc plated finish; Model 209Z by Royal Arch Inc.
- .3 Decorative Laminate: High pressure decorative laminate, Type HPDL as specified in Section 06 24 00.
- .4 Contact Adhesives: Water base type.
- .5 Wall Adhesive: Solvent release, cartridge type, compatible with wall substrate, capable of achieving durable bond.

- .6 Nails: To ASTM F1667, Type I (NL), galvanized steel, common wire; sizes necessary to ensure adequate securement.
- .7 Staples: To ASTM F1667, Type IV (ST); galvanized steel, common wire; leg length necessary to ensure adequate securement.
- .8 Screws: Galvanized steel, tapered head suitable for counter sunk applications; sizes necessary to ensure adequate securement.
- .9 Bolts, Nuts, Washers, Lags, and Blind Fasteners: Size and type to suit application; plain finish.
- .10 Primer: Alkyd primer sealer type.
- .11 Wood Filler: Solvent base, tinted to match surface finish colour.
- .12 Joint Sealant: Interior general purpose sealant, Type SEAL-INT-GP as specified in Section 07 92 00.

2.5 FINISHES

- .1 Chrome/Nickel Plating on Metal Components: To ASTM B456, Type SC 2; electrodeposited nickel plus chromium coating; Satin.

3 Execution

3.1 INSTALLATION

- .1 Install Products to AWMAC NAAWS 4.0, Custom Grade.
- .2 Set and secure Products in place, straight, plumb, and level.
- .3 Unless noted otherwise, install Products with nails, screws, or bolts with blind fasteners; spaced at 400 mm OC. Alternately, adhesive may be used as required by specific installation requirements.
- .4 Finish exposed edges of veneer-clad panels with 3.2 mm thick hardwood edge trim, glued and nailed.
- .5 Finish exposed edges of laminate-clad panels with 1.0 mm thick decorative laminate edgebanding, applied using hot melt adhesive.
- .6 Apply decorative laminate to core materials as specified in Section 06 24 00.
- .7 Install MCP shelf and metal tube closet rod in closets where indicated on Drawings.
- .8 Install coat hooks where indicated on Drawings.
- .9 Install door hardware as specified in Section 08 71 00.
- .10 Seal gaps and joints as specified in Section 07 92 00.

3.2 ADJUSTING AND CLEANING

- .1 Set exposed fasteners.
- .2 Apply wood filler over exposed nail and staple indentations. Allow to dry and sand smooth.
- .3 Conceal countersunk fasteners with matching hardwood dowels, sanded smooth, and flush to adjacent surface.

- .4 Clean and prepare surfaces for site finishing. Coordinate with Section 09 90 00.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 06 20 00 - Finish Carpentry.
 - .2 Section 06 41 00 - Architectural Wood Casework.
- 1.2 REFERENCES
 - .1 AWMAC NAAWS 4.0-2021: North American Architectural Woodwork Standards.
 - .2 CAN/CGSB-71.20-M88: Adhesive, Contact, Brushable.
 - .3 ANSI/NEMA LD 3-2005: High Pressure Decorative Laminates.
- 1.3 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Selection Samples: Duplicate chains of laminate samples, illustrating available colours, patterns, and textures.
- 1.4 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Deliver decorative laminate with heavy kraft paper protection, and in cartons during shipping.
 - .3 Store Products protected from damage.
 - .4 Do not store or install Products in areas where relative humidity is less than 25 percent RH or greater than 60 percent RH at 22 degrees C.
- 1.5 WARRANTY
 - .1 Submit extended warranty in accordance with General Conditions of the Contract.
 - .2 Extended Warranty: For a period of two years, covering against warping, splitting, or delamination, subject to normal usage excluding excessive moisture or heat.
- 2 Products
- 2.1 MANUFACTURERS
 - .1 Manufacturers having Product considered acceptable for use:
 - .1 Arborite.
 - .2 Formica.
 - .3 Nevamar.
 - .4 Octolam.
 - .5 Pionite.
 - .6 Tafisa.
 - .7 Wilsonart.
 - .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 MATERIALS

- .1 High Pressure Decorative Laminate (HPDL): To ANSI/NEMA LD 3; decorative surface papers impregnated with melamine resins, bonded under heat and pressure to kraft papers impregnated with phenolic resins; colours, textures, and patterns as selected by Consultant; NEMA Types, Grades, and thicknesses as listed below:
 - .1 General Purpose Type: Grade HGS; 1.2 mm thick.
 - .2 Vertical Surface Type: Grade VGS; 0.7 mm thick.
 - .3 Postforming Type: Grade HGP; 1.0 mm thick.
 - .4 Vertical Postforming Type: Grade VGP; 0.7 mm thick.
 - .5 Cabinet Liner Type: Grade CLS; 0.5 mm thick.
 - .6 Backer Type:
 - .1 Grade BKL; 0.5 mm thick.
 - .2 Grade BKV; 0.7 mm thick.
 - .3 Grade BKM; 1.0 mm, thick.
 - .4 Grade BKH; 1.2 mm thick.
- .2 Core Materials: As indicated on Drawings.
- .3 Sealer: Water-resistant type.
- .4 Draw Bolts and Splines: Suitable for new core bases, and acceptable to fabricator.
- .5 Contact Adhesive: To CAN/CGSB-71.20-M.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify cutouts in core materials are prepared for faucets, sinks, and other penetrating components.

3.2 PREPARATION

- .1 Make joints in core materials tight, flush, and hairline. Use draw bolts and splines.
- .2 Round internal corners, chamfer edges, and seal exposed edges in core materials.

3.3 INSTALLATION

- .1 Comply with ANSI/NEMA LD 3, Annex A and AWMAC NAAWS 4.0.
- .2 Install Products plumb, true, and square.
- .3 Install Products neatly scribed and fitted to adjoining surfaces.
- .4 Ensure adjacent laminate sheets match in colour, texture, and pattern.
- .5 Ensure decorative laminate and core profiles coincide to ensure full continuous support, and bond over entire surface.
- .6 Use continuous lengths to minimize joints.
- .7 Locate joints no closer than 600 mm from cutouts.
- .8 Offset joints in decorative laminate from joints in core material.
- .9 Apply decorative laminate to exposed edges of core material for straight self-edging strips or flat work.

- .10 Chamfer exposed edges of decorative laminate uniformly at 20 degrees.
 - .11 Do not mitre decorative laminate edges.
 - .12 Apply backer sheets where required to conceal and balance core material. Match thickness of decorative face sheets.
 - .13 Apply cabinet liner sheets to interior of cabinets where indicated on Drawings.
- 3.4 FIELD QUALITY CONTROL
- .1 Gaps at corners, and gaps between laminate and core materials will be rejected by Consultant.
- 3.5 CLEANING
- .1 Refer to Section 01 74 00.
 - .2 Remove kraft paper protective covering.
 - .3 Visually inspect each installed item.
 - .4 Wash and thoroughly polish surfaces.
- 3.6 PROTECTION
- .1 Refer to Section 01 76 00.
 - .2 Protect completed installation from damage with removable, temporary protective coverings.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 06 10 00 - Rough Carpentry.
- .2 Section 06 20 00 - Finish Carpentry.
- .3 Section 06 24 00 - High Pressure Decorative Laminate.
- .4 Section 07 92 00 - Joint Sealants.
- .5 Section 08 71 00 - Door Hardware.

1.2 REFERENCES

- .1 ANSI A135.4-2004: Basic Hardboard.
- .2 ANSI A208.1-2009: Particleboard.
- .3 ANSI A208.2-2009: Medium Density Fiberboard (MDF) for Interior Applications.
- .4 ASTM A240/A240M-22b: Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications.
- .5 ASTM A276/A276M-25: Standard Specification for Stainless Steel Bars and Shapes.
- .6 ASTM B456-17(2022): Standard Specification for Electrodeposited Coatings of Copper Plus Nickel Plus Chromium and Nickel Plus Chromium.
- .7 ASTM F1667-21: Standard Specification for Driven Fasteners: Nails, Spikes and Staples.
- .8 AWMAC NAAWS 4.0-2021: North American Architectural Woodwork Standards.
- .9 ANSI/BHMA A156.1-2016: Butts and Hinges.
- .10 ANSI/BHMA A156.9-2015: Cabinet Hardware.
- .11 ANSI/BHMA A156.11-2014: Cabinet Locks.
- .12 ANSI/BHMA A156.26-2017: Continuous Hinges.
- .13 CSA O112.9:21: Evaluation of Adhesives for Structural Wood Products (Exterior Exposure).
- .14 CSA O112.10-08 (R2022): Evaluation of Adhesives for Structural Wood Products (Limited Moisture Exposure).
- .15 CSA O141:23: Canadian Standard Lumber.
- .16 CSA O151:17 (R2022): Canadian Softwood Plywood.
- .17 ANSI/HPVA HP-1-2020: American National Standard for Hardwood and Decorative Plywood.
- .18 NHLA Grading Rules.

1.3 SHOP DRAWINGS

- .1 Submit Shop Drawings as specified in Section 01 33 00.
- .2 Shop Drawings: Project-specific drawings, illustrating layouts, dimensions, materials, component profiles and sizes, jointing details, factory-applied finishes, accessories, locations of outlets, methods of attachment, and hardware.

1.4 SAMPLES

- .1 Submit samples as specified in Section 01 33 00.
- .2 Verification Samples: Duplicate 300 x 300 mm size samples of each selected melamine composite panel, illustrating laminate-clad face colour, pattern, and texture; core material; and quality of PVC edgebanding.

1.5 QUALIFICATIONS

- .1 Fabricator and Installer: A firm specializing in fabricating and installing architectural wood casework, having minimum three years documented experience, and a member of AWMAC.

1.6 MOCK-UPS

- .1 Construct mock-ups as specified in Section 01 40 00.
- .2 Mock-up: Full-size, 450 mm wide mock-up of each type of architectural wood casework, including materials, finishes, hardware, and countertops.
- .3 Accepted mock-ups will be used as the standard for acceptance of the Work.
- .4 Remove and replace installed Product that does not conform to accepted mock-up.
- .5 Remove mock-ups from Place of the Work upon Ready-for-Takeover.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Store Products under waterproof cover both in transit and at Place of the Work in a manner to prevent damage to Products, to existing property, and to the Work.
- .3 Store completed Products in a dry, clean area where it does not hinder progress of the Work.
- .4 Do not store or install Products in the Work until building is dry and heated.

1.8 WARRANTY

- .1 Submit extended warranty in accordance with General Conditions of the Contract.
- .2 Manufacturer's Extended Warranty: A two year AWMAC Guarantee Certificate, covering replacement, re-working, and refinishing of deficient Product resulting from faulty workmanship or defective materials.

2 Products

2.1 LUMBER

- .1 Dressed Lumber - Hardwood (DL-HWD): To NHLA Select and Better Grade; Maple species, kiln dried to maximum 7 percent moisture content, capable of receiving high quality transparent finish; sizes as indicated on Drawings.
- .2 Dressed Lumber - Softwood (DL-SWD): To CSA O141, S4S; AWMAC Custom grade; SPF species, kiln dried to maximum 7 percent moisture content, with mixed grain capable of receiving high quality opaque finish; sizes as indicated on Drawings.
- .3 Dimension Lumber: As specified in Section 06 10 00; sizes as indicated on Drawings.

2.2 PLYWOOD

- .1 Plywood - Hardwood (PLY-HWD): To ANSI/HPVA HP-1, Architectural G2S; thicknesses as indicated on Drawings; as follows:
 - .1 Core: Hardwood veneer core, minimum 9 plies.
 - .2 Face Veneers: Maple species; Face Grade A; Plain-Sliced; of clear Book match grain capable of receiving high quality transparent finish.
- .2 Plywood - Hardwood, Moisture-Resistant Core (PLY-HWD-MR): To ANSI/HPVA HP-1, Architectural G2S; thicknesses as indicated on Drawings; as follows:
 - .1 Core: Composite core, moisture-resistant particle board to ANSI A208.1, Grade M-3 - Exterior Glue.
 - .2 Face Veneers: Maple species; Face Grade A; Plain-Sliced; of clear Book match grain capable of receiving high quality transparent finish.

2.3 COMPOSITE BOARDS AND PANELS

- .1 Melamine Composite Panel (MCP): Particleboard core with factory-applied low pressure laminate thermo-fused to both faces; Premium quality; colours, textures and patterns as selected by Consultant; thicknesses as indicated on Drawings.
- .2 Medium Density Fiberboard (MDF): To ANSI A208.2, Grade MD; minimum 740 kg/m³ density and moisture content between 4.5 - 8.0 percent; thicknesses as indicated on Drawings.
- .3 Particleboard (PB): To ANSI A208.1, Grade M-2; made from 100 percent post-industrial wood fibres; minimum 635 kg/m³ density and maximum 6 percent moisture content; no added urea formaldehyde (nauf); certified EPP by Composite Panel Association; thicknesses as indicated on Drawings.
- .4 Hardboard (HB): To ANSI A135.4, Class 1 - Tempered; inter-felted ligno-cellulosic fibers consolidated under heat and pressure; minimum 500 kg/m³ density; S1S surface finish; complete with factory-applied low pressure laminate thermo-fused to one face; colours, textures, and patterns as selected by Consultant; thicknesses as indicated on Drawings.

2.4 MANUFACTURED UNITS

- .1 Closet Doors: Solid core flush wood doors to ANSI/WDMA I.S. 1A, Heavy Duty, 44 mm thick; 5-ply construction, as follows:
 - .1 Perimeter Construction: Solid lumber lock blocks, vertical stiles and top and bottom rails, bonded to core material.
 - .2 Core: AWMAC Particleboard Core Type; 448 kg/m³ solid particleboard core to ANSI A208.1.
 - .3 Face Assembly Adhesive: Type I - Waterproof.
 - .4 Core Assembly Adhesive: Type II - Water-resistant.
 - .5 Cross-banding: 1.6 mm thick hardwood veneer.
 - .6 Edges: To AWMAC NAAWS 4.0, D - Solid Wood edgeband, veneer face edge shows.
 - .7 Door Faces: AWMAC Custom grade; Maple veneer, Plain-sliced with Book match grain, suitable for transparent finish.

2.5 ACCESSORIES

- .1 Adhesive for Wet Area Exposures: To CSA O112.9.
- .2 Adhesive for Dry Area Exposures: To CSA O112.10.
- .3 Nails: To ASTM F1667, Type I (NL); galvanized steel, common wire; sizes necessary to ensure adequate securement.

- .4 Spikes: To ASTM F1667, Type III (SP); galvanized steel, common wire; sizes necessary to ensure adequate securement.
- .5 Staples: To ASTM F1667, Type IV (ST); galvanized steel, common wire; leg length necessary to ensure adequate securement.
- .6 Screws: Galvanized steel, bugle head, power driven type, sizes necessary to ensure adequate securement.
- .7 Anchors: Galvanized steel, drilled and epoxy-fastened types; sizes necessary to ensure adequate securement.
- .8 Stainless Steel Sheet and Plate: To ASTM A240/A240M, Type 304; sizes and thicknesses as indicated on Drawings.
- .9 Stainless Steel Bar and Shape: To ASTM A276/A276M, Type 304; sizes and profiles as indicated on Drawings.
- .10 Decorative Laminate: High pressure decorative laminate, Type HPDL as specified in Section 06 24 00.
- .11 Solid Plastic Edgebanding: 3 mm thick PVC edgebanding with eased edge, colour and pattern to match cabinet panel faces, unless noted otherwise.
- .12 Eggcrate Lay-in Panel: 13 mm thick acrylic eggcrate grating, White colour; percentage opening and dimensions as indicated on Drawings.
- .13 Metal Grille: Extruded aluminum to ASTM B221M, 6061-T5 alloy; anodized finish; linear design with percentage opening and dimensions as indicated on Drawings.
- .14 Joint Sealants: As specified in Section 07 92 00, types as follows:
 - .1 Dry Areas and Food Preparation Wet Areas: Interior general purpose sealant, SEAL-INT-GP.
 - .2 Other Wet Areas: Interior mildew-resistant sealant, SEAL-INT-MR.

2.6 CASEWORK HARDWARE

- .1 Unless specified otherwise, Provide cabinet hardware to ANSI/BHMA A156.9, Grade 1.
- .2 Casework Hinges: Fully-concealed, adjustable, articulated, screw on type metal hinges; accommodating 100 degree, 110 degree, 125 degree, and 170 degree openings, and complete with soft-closing mechanism.
- .3 Pull: Stainless steel, 10 mm OD handle, 185 mm overall length with 128 mm centre-to-centre fastening and 35 mm projection; eg. Contemporary Stainless Steel Handle Pull - 2102 by Richelieu.
- .4 Drawer Box and Slides: Full extension for 60 kg load at 500 mm; roller runners for bottom mounting, steel construction with baked enamel finish, ball bearing rollers, and complete with soft-closing mechanism.
- .5 Continuous Hinges: To ANSI/BHMA A156.26; continuous stainless steel hinges, heavy duty type, length to suit full door height; eg. Roton 790-900 by Hager, with US32D finish.
- .6 Cupboard and Drawer Lock: To ANSI/BHMA A156.11, Operational Class, Grade 1; chrome-plated finish, and keyed to Owner's existing master keying system.
- .7 Padlock Hasp: Stainless steel, Type 304; with countersunk screw holes.
- .8 Slide Bolt For Inactive Leaf: 60 mm long barrel bolt, nickel plated.
- .9 Elbow Catch: Heavy duty type, nickel finish; eg. Model 5540180 by Richelieu.

- .10 Door Bumper: Nylon, eg. Model MP303-11 by Richelieu.
- .11 Pilaster Strip: 16 mm wide, 4 mm deep perforated metal strip, zinc plated; length as required; Model 2332GXX by Richelieu.
- .12 Pilaster Clip: Heavy duty bent metal clips, zinc plated; eg. Model CP2562G by Richelieu.
- .13 Shelf Support for Drilled Gable: 5 mm OD metal pin, plastic-clad; eg. Model 34004011 by Richelieu.
- .14 Support Housing and Bolt: Nickel-plated metal, 9.5 mm mounting centre, suitable for 19 mm thick panels; complete with matching connecting bolt; eg. Rafix-SE Housing Model 263.15.705 by Hafele.
- .15 Cable Grommet: Plastic counter top fitting for computer / telephone / power cables; two-part cable set with spring closure top, 50 mm OD; Black colour; Model 60.2700.90 by Richelieu, or Type SG by Doug Mockett.
- .16 Magnetic Catch: Magnetic catch, automatic opening.
- .17 Automatic Door Bolt: Model 245.58.754 by Hafele.
- .18 Base Cabinet Leveller: 100 mm size, adjustable to minus 5 mm and plus 10 mm; eg. Model 637.45.326 by Hafele.
- .19 Collapsible Coat Hook: Magnetic safety release type, fabricated from high strength polycarbonate; 11.8 kg release weight; Safety Release Coat Hook by HenkelHook, colours as selected by Consultant.
- .20 Fixed Coat Hook: As specified in Section 06 20 00.
- .21 Closet Rod and Flanges: As specified in Section 06 20 00.

2.7 CLOSET DOOR HARDWARE

- .1 Butt Hinges: To ANSI/BHMA A156.1, Grade 1; 1-1/2 pair per leaf; 75 x 75 mm size, 5-knuckle ball bearing standard weight full mortise butt hinges, with brushed chrome finish; eg. Model FBB179 by Stanley.
- .2 Slide Bolt For Inactive Leaf: Type as specified above, two required for top and bottom attachment to inactive door leaf.
- .3 Lockable Handset: As specified in Section 08 71 00.

2.8 FABRICATION

- .1 Prior to fabrication, verify existing conditions and take field measurements necessary to ensure perfect fit.
- .2 Fabricate Products to AWMAC NAAWS 4.0, Custom Grade.
- .3 Manufacture casework as individual cabinets in standard width increments, or in custom widths where indicated on Drawings.
- .4 Fabricate each module to be self-supporting with both exterior gables finished to allow removal and relocation without alterations to casework.
- .5 Pre-drill and cut mounting holes for sinks, faucets and electrical receptacles.
- .6 Finish exposed edges of veneer-faced components with 3.2 mm thick hardwood edgebanding, glued, and nailed.

- .7 Finish exposed edges of laminate-faced components with solid plastic edgebanding, applied with edge-bander using hot melt adhesive.
- .8 Secure wall case and floor case bottoms to casework with three locking mechanical fasteners at each end.
- .9 Secure fixed shelves, toe space rails, bottom rails, and top rails to casework with two locking mechanical fasteners at each end.
- .10 Limit unsupported span of shelving to AWMAC NAAWS 4.0.
- .11 Rabbet gables and insert pilaster strips for flush, recessed appearance. Screw fasten pilaster strips in place.
- .12 Construct joints to have a good fit, fully glued and rigid in final construction.
- .13 Hardware Preparation - Casework Doors: Factory install cabinet hinges, runners and hardware, anchored firmly into position for long life under hard use. Provide hinges on each door leaf in the following quantities:
 - .1 Doors up to 1 000 mm High: Two.
 - .2 Doors up to 1 500 mm High: Three.
 - .3 Doors greater than 1 500 mm High: Four.
- .14 Hardware Preparation - Closet Doors: Machine cut relief for hinges and core doors for handsets and cylinders.
- .15 Equally space banks of drawers, minimum 120 mm high.
- .16 Apply decorative laminate to core materials as specified in Section 06 24 00.
- .17 Factory seal cutouts and service fitting openings in countertops with moisture-resistant epoxy.
- .18 Drill holes in gables to receive adjustable shelving pins. Provide ferow sleeves in drilled holes.
- .19 Install neoprene or rubber bumpers at top and bottom of doors and drawers.
- .20 Adjust doors and drawers to proper operation prior to installation.

2.9 FINISHES

- .1 Transparent Finish on Hardwood and Hardwood Veneer-clad Products: To AWMAC NAAWS 4.0, System 12 - POLYURETHANE, WATER-BASED, Custom Grade for Transparent finish; colour and sheen as selected by Consultant.
- .2 Opaque Finish on Unfaced Composite Panel and Softwood Products: To AWMAC NAAWS 4.0, System 4 - LATEX ACRYLIC, WATER-BASED, Custom Grade for Opaque finish; colour and sheen as selected by Consultant.
- .3 Chrome/Nickel Plating on Metal Components: To ASTM B456, Type SC 2; electrodeposited nickel plus chromium coating; Polished.
- .4 Stainless Steel: To AISI No. 5 - Satin or No. 6 - Matte.

2.10 SOURCE QUALITY CONTROL

- .1 Arrange for AWMAC appointed inspector to inspect casework at point of fabrication.
- .2 Pay costs of AWMAC inspection.
- .3 Make Good rejected Products and workmanship.

3 Execution

3.1 INSTALLATION

- .1 Install Products to AWMAC NAAWS 4.0, Custom Grade.
- .2 Where practical, assemble finished casework at mill and deliver to Place of the Work ready for installation.
- .3 Accurately fit joints and miters, and set nail heads ready for finishing.
- .4 Set and secure materials and components in place, rigid, square, and plumb.
- .5 Provide wood blocking, framing, or furring shown on Drawings as part of casework fabrication or erection.
- .6 Accurately scribe and closely fit compounds to irregularities of adjacent surfaces.
- .7 Use draw bolts and splines to form tight, flush, hairline joints. Accurately fit joints in true plane, and locate joints over firm bearing or supporting surfaces.
- .8 Provide appropriate heavy duty fasteners, securely anchoring casework to floor, ceiling, and wall surfaces. Use only concealed type fasteners.
- .9 Where permitted, secure concealed elements with small headed finishing nails. Countersink nail heads with nail setter.
- .10 Provide sinks, service fittings, and electrical outlets. Coordinate with other Sections for connection to facility services.
- .11 Where access is required to valves and other facility service components located behind casework, Provide removable wood access panels, each secured with minimum four brass screws.
- .12 Install laminate-clad countertops, as specified in Section 06 24 00.
- .13 Provide closers and filler strips in matching finish as required to ensure a neat and complete finished assembly.
- .14 Seal gaps and joints in wet areas with mildew-resistant joint sealer, and in non-wet areas with general purpose interior sealant. Conform to Section 07 92 00.
- .15 Install closet doors complete with door hardware.

3.2 FIELD QUALITY CONTROL

- .1 Arrange for AWMAC appointed inspector to inspect completed installation.
- .2 Pay costs of AWMAC inspection.
- .3 Make Good rejected Products and workmanship.

3.3 ADJUSTING

- .1 Adjust doors and drawers to proper operation after installation.
- .2 Fill and touch up damaged finishes to match factory finish.
- .3 Replace damaged Product that can not be repaired.

3.4 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect completed installation from damage with protective coverings.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 07 21 19.13 - Foamed-in-Place Urethane Insulation.
- .3 Section 07 26 00 - Vapour Retarders.
- .4 Section 07 27 00 - Air Barriers.
- .5 Section 07 42 43 - Composite Wall Panels.
- .6 Section 07 81 00 - Applied Fireproofing.
- .7 Section 07 84 00 - Firestopping.
- .8 Section 09 21 16 - Gypsum Board Assemblies.
- .9 Section 09 81 00 - Acoustic Insulation.
- .10 Section 22 07 19 - Plumbing Piping Insulation.
- .11 Section 23 07 13 - Duct Insulation.
- .12 Section 23 07 19 - HVAC Piping Insulation.

1.2 REFERENCES

- .1 ASTM C167-25: Standard Test Methods for Thickness and Density of Blanket or Batt Thermal Insulations.
- .2 ASTM C518-21: Standard Test Method for Steady-State Thermal Transmission Properties by Means of the Heat Flow Meter Apparatus.
- .3 ASTM C1104/C1104M-19(2025): Standard Test Method for Determining the Water Vapor Sorption of Unfaced Mineral Fiber Insulation.
- .4 ASTM D1621-16(2023): Standard Test Method for Compressive Properties of Rigid Cellular Plastics.
- .5 ASTM D2842-25: Standard Test Method for Water Absorption of Rigid Cellular Plastics.
- .6 ASTM E96/E96M-24: Standard Test Methods for Water Vapor Transmission of Materials.
- .7 CGSB 71-GP-24M: Adhesive, Flexible, for Bonding Cellular Polystyrene Insulation.
- .8 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .9 CAN/ULC-S114-2018: Standard Method of Test for Determination of Non-Combustibility in Building Materials.
- .10 CAN/ULC-S701.1-2017: Standard for Thermal Insulation, Polystyrene Boards.
- .11 CAN/ULC-S702.1:2021: Standard for Mineral Fibre Thermal Insulation for Buildings, Part 1: Material Specification.
- .12 ULC-S702.2-15: Standard for Mineral Fibre Thermal Insulation for Buildings, Part 2: Installation.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Store, handle and protect Products as specified in Section 01 60 00.
- .2 Minimize time plastic-type insulation Products are stored or exposed to sunlight at Place of the Work.
- .3 Store Products away from construction activity and sources of ignition.
- .4 Protect Products from damage during handling, installation, and at point of installation.

1.4 AMBIENT CONDITIONS

- .1 Apply Products only when surfaces and ambient temperatures are within manufacturer's prescribed limits.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers of extruded polystyrene rigid board insulation having Product considered acceptable for use:
 - .1 DuPont de Nemours, Inc.
 - .2 Owens-Corning Canada Inc.
- .2 Manufacturers of mineral fibre batt and blanket insulation having Product considered acceptable for use:
 - .1 CertainTeed Canada, Inc.
 - .2 Knauf Insulation.
 - .3 Owens-Corning Canada Inc.
 - .4 Rockwool.
- .3 Substitution Procedures: Refer to Section 01 25 00.

2.2 REGULATORY REQUIREMENTS

- .1 Conform to applicable regulatory requirements for combustibility and surface burning characteristic requirements of polystyrene insulations.
- .2 Ensure foamed plastic insulations contain zero HFC and HCFC blowing agents, and conform to Global Warming Potential (GWP) values required by The Montreal Protocol.

2.3 RIGID BOARD INSULATION

- .1 Rigid Board Insulation (INS-RB-1): To CAN/ULC-S701.1, Type 4; extruded polystyrene (XPS) rigid board insulation, closed cell type, with integral high density skin; and as follows:
 - .1 Aged Thermal Resistance (ASTM C518): $RSI \geq 0.88$ per 25 mm of thickness.
 - .2 Board Size: 600 x 2 400 mm.
 - .3 Board Edges: Shiplapped.
 - .4 Compressive Strength (ASTM D1621): 207 kPa.
 - .5 Water Absorption (ASTM D2842): ≤ 0.3 percent by volume.
 - .6 Water Vapour Permeance (ASTM E96/E96M): 50 ng/Pa•s•m².
 - .7 Thickness: As indicated on Drawings.
 - .8 Manufacturer and Product Name: eg. Styrofoam Brand SM30 by DuPont de Nemours, Inc.

2.4 BATT AND BLANKET INSULATION

- .1 Batt Insulation (INS-BB-1): To CAN/ULC-S702.1, Type 1; mineral fibre non-rigid, friction fit thermal batt insulation, manufactured from glass, rock, or slag fibers; and as follows:
 - .1 Aged Thermal Resistance (ASTM C518): $RSI \geq 0.75$ per 25 mm of thickness.
 - .2 Batt Facing: Unfaced.
 - .3 Batt Size: 413 x 1 219 mm.
 - .4 Density (ASTM C167): ≥ 32 kg/m³.
 - .5 Combustibility (CAN/ULC-S114): Noncombustible.
 - .6 Thickness: As indicated on Drawings.
 - .7 Manufacturer and Product Name: eg. ComfortBatt by Rockwool.

2.5 ACCESSORIES

- .1 Mechanical Fasteners: Stainless steel screw type fastener, complete with 75 mm OD moulded plastic disc washer.
- .2 Adhesive for Use with Polystyrene: To CGSB 71-GP-24M, Type 1.
- .3 Adhesive for Use with Other Materials: Mastic type, synthetic rubber base, fungi resistant, gun or trowel application.
- .4 Tape: 50 mm wide polyester self-adhering tape.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Ensure air seals and vapour retarders are in place.

3.2 RIGID AND SEMI-RIGID BOARDS

- .1 Unless specified otherwise, secure rigid board insulation with adhesive, applied in three continuous beads per board length.
- .2 Install insulation boards on wall surface either horizontally or vertically as required. Place membrane surface of insulation solidly against substrate and securely fasten.
- .3 Do not crush insulation face when fastening with mechanical fasteners.
- .4 Stagger side and end joints.
- .5 Butt edges and ends tight to adjacent board and to protrusions.

3.3 BATTES AND BLANKETS

- .1 Install mineral fibre batts and blankets to ULC-S702.2.
- .2 Install batt insulation in spaces without gaps and voids.
- .3 Fit insulation tight in spaces and tight to exterior side of facility services within plane of insulation.

3.4 FIELD QUALITY CONTROL

- .1 Notify Consultant and independent inspection company to inspect thermal insulation before, during, and upon completion of installation.

3.5 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect insulation edges at end of each Working Day.
- .3 Protect insulation in areas where welding will be carried out.
- .4 Replace insulation damaged by other Sections.
- .5 Protect insulation requiring a thermal barrier in accordance with applicable regulatory requirements.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 06 16 43 - Gypsum Sheathing.
- .3 Section 07 21 00 - Thermal Insulation.
- .4 Section 07 26 00 - Vapour Retarders.
- .5 Section 07 27 00 - Air Barriers.
- .6 Section 07 81 00 - Applied Fireproofing.
- .7 Section 07 92 21 - Sprayed Foam Sealant.

1.2 REFERENCES

- .1 ASTM D1621-16(2023): Standard Test Method for Compressive Properties of Rigid Cellular Plastics.
- .2 ASTM D1622-20: Standard Test Method for Apparent Density of Rigid Cellular Plastics.
- .3 ASTM D1623-17(2023): Standard Test Method for Tensile and Tensile Adhesion Properties of Rigid Cellular Plastics.
- .4 ASTM D2240-15(2021): Standard Test Method for Rubber Property-Durometer Hardness.
- .5 ASTM D2842-25: Standard Test Method for Water Absorption of Rigid Cellular Plastics.
- .6 ASTM D6226-21: Standard Test Method for Open Cell Content of Rigid Cellular Plastics.
- .7 ASTM E96/E96M-24: Standard Test Methods for Water Vapor Transmission of Materials.
- .8 ASTM E2178-21a: Standard Test Method for Determining Air Leakage Rate and Calculation of Air Permeance of Building Materials.
- .9 CUFCA Manual for Installers of Spray Polyurethane Foam Thermal Insulation.
- .10 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .11 CAN/ULC-S705.1-18: Standard for Thermal Insulation - Spray Applied Rigid Polyurethane Foam, Medium Density - Material Specification.
- .12 CAN/ULC-S705.2-2020: Standard for Thermal Insulation - Spray Applied Rigid Polyurethane Foam, Medium Density - Application.
- .13 CAN/ULC-S718-2018: Standard for Site Quality Assurance Program for Spray Applied Polyurethane Foam.
- .14 CAN/ULC-S770-15 (R2020): Standard Test Method for Determination of Long-Term Thermal Resistance of Closed-Cell Thermal Insulating Foams.

1.3 CERTIFICATES

- .1 Submit certificates as specified in Section 01 40 00.
- .2 Submit copy of foam contractor's license under a recognized third-party quality assurance program.
- .3 Submit copy of applicator certification issued by third-party.

1.4 TEST AND EVALUATION REPORTS

- .1 Submit test reports as specified in Section 01 33 00.
- .2 Test Reports: Manufacturer's standard test results indicating Products meet specified performance criteria, prepared by independent testing agency, and current within past 5 years.
 - .1 Include results of CCMC air barrier system tests.

1.5 QUALIFICATIONS

- .1 Applicator: A firm employing persons certified as approved applicators in accordance with CAN/ULC-S718.
- .2 Independent Inspection Agency: A urethane foam insulation and air barrier system inspector certified in accordance with CAN/ULC-S718.

1.6 MOCK-UPS

- .1 Construct mock-up as specified in Section 01 40 00.
- .2 Mock-Up: One 3 000 x 3 000 mm size mock-up panel, demonstrating typical conditions, including window corner condition, door corner condition, inside corner and outside corner.
- .3 Conduct the following tests on mock-up panel and report results for the following criteria:
 - .1 Core density,
 - .2 Adhesion between transition sheet membrane and substrate,
 - .3 Adhesion between sprayed insulation and transition sheet membrane, and
 - .4 Cohesion or adhesion between sprayed insulation and substrate.
- .4 Verify results comply with inspector's daily report.
- .5 Accepted mock-ups will be used as the standard for acceptance of the Work.
- .6 Remove and replace installed Product that does not conform to accepted mock-up.
- .7 Remove mock-ups from Place of the Work upon Ready-for-Takeover.

1.7 DELIVERY STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver and store Product in original packaging, bearing manufacturer's name, quantity, expiry date, CCMC numbers, and other appropriate technical indicators and references.
- .3 Cold Weather Storage: Store Products during cold weather in heated storage area.

1.8 AMBIENT CONDITIONS

- .1 Apply Product when surface and ambient air temperatures are within manufacturer's prescribed limits.
- .2 Ventilate area as specified in Section 01 51 00.
- .3 Ventilate area to receive insulation by introducing fresh air and exhausting air continuously during and 24 hours after application to maintain non-toxic, unpolluted, safe working conditions.

1.9 FIELD CONDITIONS

- .1 Provide temporary enclosures to prevent spray and noxious vapours from contaminating air beyond application area.

- .2 Protect workers as recommended by insulation manufacturer.
- .3 Protect adjacent surfaces and equipment from damage by overspray, fall-out, and dusting of insulation materials.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 BASF Canada.
 - .2 Carlisle Spray Foam Insulation.
 - .3 Elastochem Specialty Chemicals, Inc.
 - .4 Genyk Inc.
 - .5 Huntsman Building Solutions.
 - .6 Soprema Inc.
- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 PERFORMANCE CRITERIA

- .1 Foamed-in-Place Urethane Insulation: Meeting the following properties:
 - .1 Density (ASTM D1622/D1622M): $\geq 28 \text{ kg/m}^3$.
 - .2 Open Cell Content (ASTM D6226): ≤ 10 percent.
 - .3 Long-Term Thermal Resistance (CAN/ULC-S770): $\text{RSI} \geq 1.80 @ 50 \text{ mm thick}$.
 - .4 Air Permeance (ASTM E2178): $\leq 0.02 \text{ L/s}\cdot\text{m}^2 @ 75 \text{ Pa}$.
 - .5 Flame Spread Index (CAN/ULC-S102): < 500 .
 - .6 Compressive Strength (ASTM D1621, 10% parallel to rise): $\geq 170 \text{ kPa}$.
 - .7 Tensile Strength (ASTM D1623): $\geq 200 \text{ kPa}$.
 - .8 Water Absorption by Volume (ASTM D2842): ≤ 4 percent.
 - .9 Water Vapour Permeance (ASTM E96/E96M): $\leq 60 \text{ ng/Pa}\cdot\text{s}\cdot\text{m}^2$ with outer skin in place.
 - .10 Product Global Warming Potential: $\text{GWP} \leq 1.0 \text{ kg CO}_2 \text{ eq / m}^2 @ \text{RSI } 1$.
- .2 Ensure continuity of building enclosure thermal and air barriers in conjunction with materials specified in other Sections.
- .3 Seal gaps between building enclosure components and wall and roof opening frames.

2.3 MATERIALS

- .1 Foamed-in-Place Insulation (INS-FIP-1): To CAN/ULC-S705.1, Type 2; two-component, closed cell polyurethane cellular plastic foam, containing zero HFC blowing agent; eg. Walltite v.5 by BASF Canada.
- .2 Primers: As recommended for specific substrate by CUFCA Manual for Installers of Spray Polyurethane Foam Thermal Insulation.
- .3 Transition Sheet Membrane: Air/vapour barrier sheet membrane, as specified in Section 07 27 00.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Ensure surfaces are free of frost, oil, grease, oxidation, dirt, loose paint, loose scale, or other deleterious material that would impair bond.

- .3 Ensure penetrating items are installed before applying sprayed insulation.

3.2 PREPARATION

- .1 Mask and cover adjacent areas to protect from overspray.
- .2 Apply primers for special conditions as recommended by manufacturer.
- .3 Cover wide joints with transition sheet membrane as specified in Section 07 27 00.
- .4 Clean area of work prior to application of sprayed insulation.

3.3 APPLICATION

- .1 Spray apply Product to CAN/ULC-S705.2, and CUFCA Manual for Installers of Spray Polyurethane Foam Thermal Insulation.
- .2 Apply foamed-in-place insulation in consecutive layers of not less than 12 mm and not more than 25 mm thick each. Apply sufficient layers to achieve total thickness indicated.
- .3 Avoid formation of sub-layer air pockets.
- .4 Apply Product in overlapping layers, so as to obtain a smooth, uniform surface.
- .5 Maintain 75 mm clearance around chimneys, heating vents, steam pipes, recessed lighting fixtures, and other heat sources.
- .6 Do not apply Product to inside of exit openings or electrical junction boxes.

3.4 FIELD QUALITY CONTROL

- .1 Manufacturer's Field Service: Arrange for manufacturer's technical representative to regularly inspect application (minimum twice per week) and confirm insulation and air barrier system is in strict accordance with CCMC requirements.
- .2 Conduct field inspection and testing in accordance with CAN/ULC-S718.
- .3 Test completed application daily for core density and cohesion/adhesion to substrate. Record results in daily report forms.
- .4 After Product has properly cured, conduct test to verify adhesion between the membrane and the substrate using CUFCA recommended equipment.
 - .1 Conduct adhesion tests on all corners and building angles, at wall-to-slab junctions, and at wall-to-roof junctions.
 - .2 Perform one test for every wall less than 30 metres in length. Perform two tests for every wall greater than 30 metres and less than 60 metres in length, with an additional test conducted for every additional 30 metres, or part thereof, in wall length.
 - .3 Where adhesion is lower than 110 kPa, adjust membrane mechanically and re-test.
- .5 Verify adhesion of transition sheet membranes at perimeters of openings. Conduct adhesion tests randomly on 15 percent of wall openings, and at every tenth column or beam.

3.5 TOLERANCES

- .1 Maximum Variation in Applied Thickness: Plus or minus 6 mm.

3.6 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Remove overspray from non-prescribed surfaces without causing damage to surfaces.
- .3 Remove protective covers from adjacent surfaces.

3.7 WASTE MANAGEMENT

- .1 Refer to Section 01 74 00.
- .2 On a daily basis, dispose of waste foam, and decontaminate empty drums. Conform to authorities having jurisdiction.

3.8 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect completed installation from damage.
- .3 Make Good damage.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 04 00 00 - Masonry.
 - .2 Section 07 21 00 - Thermal Insulation.
 - .3 Section 07 21 19.13 - Foamed-in-Place Urethane Insulation.
 - .4 Section 07 27 00 - Air Barriers.
 - .5 Section 07 92 00 - Joint Sealants.
 - .6 Section 09 21 16 - Gypsum Board Assemblies.
- 1.2 REFERENCES
 - .1 ASTM E96/E96M-24: Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials.
 - .2 CAN/CGSB-51.34-M86: Vapour Barrier, Polyethylene Sheet for Use In Building Construction.
 - .3 SWI Sealant and Caulking Guide Specification.
- 1.3 SEQUENCING
 - .1 Sequence installation of Products in conjunction with other vapour retarder materials and seals.
- 1.4 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating Product physical properties, performance criteria, and limitations.
- 1.5 MANUFACTURER'S INSTRUCTIONS
 - .1 Submit manufacturer's instructions as specified in Section 01 33 00.
 - .2 Manufacturer's Instructions: Manufacturer's standard installation guidelines, indicating preparation and installation requirements and techniques.
- 2 Products
- 2.1 PERFORMANCE CRITERIA
 - .1 Ensure continuity of building enclosure vapour retarder in conjunction with materials specified in other Sections.
 - .2 Seal gaps between building enclosure components and opening frames.
- 2.2 MATERIALS
 - .1 Plastic Sheet Vapour Retarder: To CAN/CGSB-51.34-M; polyethylene sheet, as follows:
 - .1 Thickness: 0.15 mm.
 - .2 Water Vapour Permeance (ASTM E96/E96M): $\leq 2.2 \text{ ng/Pa}\cdot\text{s}\cdot\text{m}^2$.
 - .3 Manufacturer and Product Name: eg. Super Six by Polytarp Products.
 - .2 Adhesive: Compatible with sheet barrier and substrate, permanently non-curing.

- .3 Joint Sealant: Interior general purpose sealant, Type SEAL-INT-GP ss specified in Section 07 92 00.
- 3 Execution
- 3.1 PREPARATION
- .1 Ensure surfaces to receive vapour retarder are clean, dry, and free of oil, grease, dirt, excess mortar, and other contaminants.
 - .2 Cure new concrete for minimum two weeks.
- 3.2 INSTALLATION
- .1 Install Products to SWI Sealant and Caulking Guide Specification.
 - .2 Position joints or laps of sheets over firm bearing to achieve an effective and permanent seal.
 - .3 Seal laps, joints, and terminations with an approved sealant to ensure complete, continuous seal of building envelope.
- 3.3 FIELD QUALITY CONTROL
- .1 Inspect vapour retarders prior to concealment and identify gaps, holes, and punctures.
 - .2 Seal gaps, holes, and punctures in vapour retarder membranes with joint sealant, as specified in Section 07 92 00.
 - .3 Request Consultant inspection of vapour retarders prior to concealment. Work that has been concealed prior to Consultant inspection will be exposed while Consultant remains at Place of the Work, inspected, and then only concealed upon Consultant acceptance.
- 3.4 CLEANING
- .1 Refer to Section 01 74 00.
 - .2 Clean extra materials from adjacent surfaces.
 - .3 Leave a suitable substrate for subsequent installations.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 06 16 43 - Gypsum Sheathing.
- .3 Section 07 21 00 - Thermal Insulation.
- .4 Section 07 21 19.13 - Foamed-in-Place Urethane Insulation.
- .5 Section 07 26 00 - Vapour Retarders.
- .6 Section 07 42 43 - Composite Wall Panels.
- .7 Section 07 92 00 - Joint Sealants.
- .8 Section 07 92 21 - Sprayed Foam Sealant.
- .9 Section 08 12 13 - Hollow Metal Frames.
- .10 Section 08 51 13 - Aluminum Windows.

1.2 REFERENCES

- .1 ASTM D412-16(2021): Standard Test Methods for Vulcanized Rubber and Thermoplastic Elastomers - Tension.
- .2 ASTM D882-18: Standard Test Method for Tensile Properties of Thin Plastic Sheeting.
- .3 ASTM E96/E96M-24: Standard Test Methods for Gravimetric Determination of Water Vapor Transmission Rate of Materials.
- .4 ASTM E154/E154M-08a(2025): Standard Test Methods for Water Vapor Retarders Used in Contact with Earth Under Concrete Slabs, on Walls, or as Ground Cover.
- .5 ASTM E2178-21a: Standard Test Method for Determining Air Leakage Rate and Calculation of Air Permeance of Building Materials.
- .6 SWI Sealant and Caulking Guide Specification.
- .7 CAN/ULC-S741-2008 (R2016): Standard for Air Barrier Materials - Specification.
- .8 CAN/ULC-S742-2011 (R2016): Standard for Air Barrier Assemblies - Specification.

1.3 SEQUENCING

- .1 Sequence installation in conjunction with other air and vapour barrier materials and seals.

1.4 PRODUCT DATA

- .1 Submit Product data as specified in Section 01 33 00.
- .2 Product Data: Manufacturer's standard data sheets, indicating Product physical properties, performance criteria, and limitations.

1.5 MANUFACTURER'S INSTRUCTIONS

- .1 Submit manufacturer's instructions as specified in Section 01 33 00.
- .2 Manufacturer's Instructions: Manufacturer's standard installation instructions, indicating substrate preparation, and Product installation requirements and techniques.

1.6 QUALIFICATIONS

- .1 Applicators: A firm recognized by manufacturer as suitable for applying specified air barrier Products.

1.7 DELIVERY STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver Products in undamaged containers and original packaging, indicating names of manufacturer and Product.
- .3 Store roll materials on end in original packaging.
- .4 Store adhesives and primers at 5 degrees C to facilitate handling.
- .5 Keep solvent away from open flame or excessive heat.
- .6 Protect rolls from direct sunlight until ready for use.

1.8 AMBIENT CONDITIONS

- .1 Apply sheet membranes when ambient air temperature is above 5 degrees C.
- .2 Apply membranes only during dry conditions and to dry substrates that are free of snow, ice, and water.
- .3 Apply only dry Products, during weather that will not introduce moisture into assembly.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers of air barrier membranes having Product considered acceptable for use:
 - .1 Dörken Systems, Inc.
 - .2 Henry (a Carlisle Company).
 - .3 SRP Canada, Inc.
 - .4 VaproShield.
 - .5 W. R. Meadows of Canada Limited.
- .2 Manufacturers of air/vapour barrier membranes having Product considered acceptable for use:
 - .1 Carlisle Construction Materials.
 - .2 Henry (a Carlisle Company).
 - .3 IKO Industries Ltd.
 - .4 Soprema Inc.
 - .5 Tremco Construction Products Group.
 - .6 W. R. Meadows of Canada Limited.
- .3 Substitution Procedures: Refer to Section 01 25 00.

2.2 PERFORMANCE CRITERIA

- .1 Ensure continuity of building enclosure air barrier in conjunction with adjacent Products.
- .2 Seal gaps between building enclosure components and opening frames.

2.3 MATERIALS

- .1 Air Barrier Sheet Membrane: To CAN/ULC-S741 and CAN/ULC-S742, Class A1; vapour permeable, water resistive, air barrier sheet membrane, self-adhering grade; and as follows:
 - .1 Thickness: ≥ 0.55 mm.
 - .2 Air Leakage (ASTM E2178): ≤ 0.02 L/s•m² @ 75 Pa.
 - .3 Water Vapour Permeance (ASTM E96/E96M, Method A): $\geq 1\ 655$ ng/Pa•s•m².
 - .4 Tensile Strength (ASTM D882): 182 N.
 - .5 Product and Manufacturer Name: eg. Blueskin VP 160 by Henry (a Carlisle Company).
- .2 Air/Vapour Barrier Sheet Membrane: To CAN/ULC-S741 and CAN/ULC-S742, Class A1; SBS rubberized asphalt sheet membrane, self-adhering grade; and as follows:
 - .1 Thickness: ≥ 1.0 mm.
 - .2 Air Leakage (ASTM E2178): ≤ 0.02 L/s•m² @ 75 Pa.
 - .3 Water Vapour Permeance (ASTM E96/E96M, Method A): ≤ 1.71 ng/Pa•s•m².
 - .4 Elongation (ASTM D412 - Modified): 200 percent.
 - .5 Tensile Strength (ASTM D412 - Modified): 3.45 MPa.
 - .6 Puncture Resistance (ASTM E154/E154M): 178 N.
 - .7 Product and Manufacturer Name: eg. Blueskin SA by Henry (a Carlisle Company).
- .3 Air/Vapour Barrier Patching Compound: To CAN/ULC-S741 and CAN/ULC-S742, Class A1; single-component, trowel- or brush-applied solvent type synthetic rubber; and as follows:
 - .1 Air Leakage (ASTM E2178): ≤ 0.02 L/s•m² @ 75 Pa.
 - .2 Water Vapour Permeance (ASTM E96/E96M, Method A): ≤ 1.7 ng/Pa•m²•s.
 - .3 Solids Content by Weight: 72 percent.
 - .4 Product and Manufacturer Name: eg. Air-Bloc 21 by Henry (a Carlisle Company).

2.4 ACCESSORIES

- .1 Attachments: Galvanized steel bars and anchors.
- .2 Adhesive: Compatible with sheet barrier and substrate, permanently non-curing.
- .3 Air Barrier Tape: 76 mm wide, self-adhesive polypropylene tape; as recommended by membrane manufacturer.
- .4 Primer: As recommended by self-adhering membrane manufacturer.
- .5 Joint Sealant: Exterior flashing sealant, Type SEAL-EXT-FL as specified in Section 07 92 00.

3 Execution

3.1 PREPARATION

- .1 Ensure surfaces are clean, dry, and free of oil, grease, dirt, excess mortar, and other contaminants.
- .2 Cure new concrete for minimum two weeks.
- .3 Fill spalled concrete or open mortar joints to provide an even plane.
- .4 Apply primer to porous surfaces designated to receive self-adhered sheet membranes.
- .5 Tape unfinished joints and gaps in sheathing boards.

3.2 INSTALLATION

- .1 Install Products to SWI Sealant and Caulking Guide Specification.
- .2 Provide air tight joints.

- .3 Seal Products completely around projections and penetrations.
- .4 Fully adhere sheet membranes to primed substrate, using consecutive weatherboard method.
- .5 Eliminate wrinkles, gaps, bubbles, air pockets, and fishmouths.
- .6 Apply transition sheet membranes at openings and transitional connections.
- .7 Leave a sufficient amount of excess membrane over top of parapet walls and around wall openings for tie-in by other Sections.
- .8 Cut membrane neatly around penetrations. Use a heated trowel to soften and form membrane. Seal with air/vapour barrier patching compound.
- .9 Do not leave installed membranes exposed to UV or weather for more than 42 days.

3.3 FIELD QUALITY CONTROL

- .1 Inspect air barriers prior to concealment and identify gaps, holes, and punctures.
- .2 Seal gaps, holes, and punctures with air/vapour barrier patching compound.
- .3 Request Consultant inspection of air barriers prior to concealment. Work that has been concealed prior to Consultant inspection will be exposed while Consultant remains at Place of the Work, inspected, and then only concealed upon Consultant acceptance.

3.4 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Clean extra material from adjacent surfaces.
- .3 Leave a suitable substrate for subsequent construction.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 06 16 43 - Gypsum Sheathing.
- .3 Section 07 21 00 - Thermal Insulation.
- .4 Section 07 21 19.13 - Foamed-in-Place Urethane Insulation.
- .5 Section 07 26 00 - Vapour Retarders.
- .6 Section 07 27 00 - Air Barriers.
- .7 Section 07 92 00 - Joint Sealants.

1.2 REFERENCES

- .1 AAMA 2605-22: Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (With Coil Coating Appendix).
- .2 ASTM A123/A123M-24: Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- .3 ASTM A153/A153M-23: Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
- .4 ASTM A792/A792M-23: Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
- .5 ASTM B209/B209M-21a: Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate.
- .6 ASTM B221M-21: Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric).
- .7 ASTM D1781-98(2021): Standard Test Method for Climbing Drum Peel for Adhesives.
- .8 ASTM E283/E283M-26: Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Skylights, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen.
- .9 ASTM E331-00(2023): Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference.
- .10 CSA S136-16 (R2021): North American Specification for the Design of Cold-Formed Steel Structural Members.
- .11 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.

1.3 SHOP DRAWINGS

- .1 Submit Shop Drawings as specified in Section 01 33 00.
- .2 Shop Drawings: Project-specific drawings, illustrating:
 - .1 Large scale details of members and materials, schedule of elevations, trim and closure pieces, soffits, fascia; detail and location of joints and gaskets, including joints necessary to accommodate thermal movement;
 - .2 Large scale details of brackets and anchorage devices and of connection details;

- .3 Fully dimensioned layouts for positioning of brackets and anchorage devices to structures;
 - .4 Dimensions and thicknesses;
 - .5 Description of materials including catalogue numbers, Products' names, and manufacturer's name;
 - .6 Finish specifications; and
 - .7 Other pertinent data.
- .3 Submit documentation of:
- .1 Thicknesses, profiles, and descriptions of components used in assembly;
 - .2 Engineering calculations verifying assembly has been designed, constructed, and attached to withstand forces anticipated for Project and will meet specified performance criteria.
- .4 Shop Drawings, including engineering calculations, are to be stamped, signed, and dated by fabricator's design engineer.

1.4 SAMPLES

- .1 Submit samples as specified in Section 01 33 00.
- .2 Selection Samples: Duplicate 90 x 90 mm size prefinished metal samples, illustrating full range of available colours.
- .3 Verification Samples: Duplicate 90 x 90 mm size samples for each panel type, illustrating selected finish, fabrication, and anchorage methods.

1.5 QUALIFICATIONS

- .1 Fabricator's Design Engineer: A professional structural engineer experienced in designing composite panel systems, licensed to practice at Place of the Work.
- .2 Fabricator and Installer: A firm specializing in fabricating and erecting composite panel assemblies, having minimum 5 years documented experience.

1.6 MOCK-UPS

- .1 Construct mock-ups as specified in Section 01 40 00.
- .2 Mock-Up Panel: A 1 220 x 1 220 mm size mock-up panel, demonstrating panel profiles, textures and colours; jointing and gasketing techniques; metal flashings; method of attachment to substrate. Include wall components such as air/vapour barrier membrane, through-wall flashing membranes, thermal wall insulation, and methods of drainage.
- .3 Accepted mock-ups will be used as the standard for acceptance of the Work.
- .4 Remove and replace installed Product that does not conform to accepted mock-up.
- .5 Remove mock-ups from Place of the Work upon Substantial Performance of the Work.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver and store Products in original wrappings, cartons, or containers; clearly marked as to type, colour, and manufacturer.
- .3 Stack on wood blocking, clear of ground, and tilted sufficiently to ensure no water remains on Products.
- .4 Open bundles on underside to allow drainage from leaks or condensation.

1.8 WARRANTY

- .1 Submit extended warranty in accordance with General Conditions of the Contract.
- .2 Extended Warranty: For a period of 20 years, covering failure of factory-applied exterior finish.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers of aluminum composite material having Product considered acceptable for use:
 - .1 3A Composites USA Inc.
 - .2 Alcoa Cladding Systems.
 - .3 Alcotex, Inc.
 - .4 Alucoil North America.
 - .5 Architectural Metals North America Corporation.
 - .6 Mitsubishi Chemical Composites America, Inc.
- .2 Manufacturers of thermal isolation clips having Product considered acceptable for use:
 - .1 Exterior Technologies Group.
 - .2 Northern Facade.
 - .3 Soprema Inc.
- .3 Substitution Procedures: Refer to Section 01 25 00.

2.2 DESCRIPTION

- .1 Aluminum Composite Panels (ACP): A dry-joint panel assembly, comprised of panels fabricated from aluminum composite material, and supported from a panel load transfer grid.

2.3 DESIGN CRITERIA

- .1 Design panel assembly to accommodate wind loading, weight carrying requirements and wind deflection limitation of L/800. Conform to CSA S136.
- .2 Design panel assembly as drained rain screen.
- .3 Design panel assembly to meet MMA Supplementary Standard SB-10, Nonresidential Category, Climate Zone 5.
- .4 Deflection Limits: Maintain integrity of panels and seals at design loading. Prevent permanent deformation of members caused by applied loads. Prevent deflection that could result in noise, breaking of adhesives or sealants, to cause them to touch other building components, or to break the integrity of the insulation thermal blanket or air/vapour barrier seal.
- .5 Design anchors, fasteners and braces so as to limit their structural stress to not more than 50 percent of the allowable stress when maximum load conditions are applied.
- .6 Panel Removal: Designed as a non-progressive system, allowing removal of any individual panel without necessitating removal of adjacent components.
- .7 Structural Movement: Design system to accommodate movement of supporting structural framing without causing bowing, buckling, delamination, oil canning, excessive stress on fasteners, or any other detrimental effects.
- .8 Thermal Movements: Design system to accommodate thermal movements from ambient and surface temperature changes. Prevent buckling, opening of joints, overstressing of

components, failure of connections and other detrimental effects. Base calculations on surface temperatures of materials due to both solar heat gain and nighttime sky heat loss.
.1 Temperature Change: 20 degrees C ambient, and 40 degrees C material surfaces.

2.4 PERFORMANCE CRITERIA

- .1 Aluminum Composite Panels (ACP): Meeting the following performance criteria:
 - .1 Air Infiltration (ASTM E283/E283M): Maximum air leakage of 0.3 L/m² when tested at pressure difference of 75 Pa.
 - .2 Water Penetration (ASTM E331): No water penetration when tested at pressure difference of 300 Pa.

2.5 MATERIALS

- .1 Sheet Aluminum: To ASTM B209/B209M, 3105-H14 alloy; 0.51 mm thick.
- .2 Extruded Aluminum: To ASTM B221M, 6063 alloy, T5 temper.
- .3 Sheet Steel: To ASTM A792/A792M, Structural Steel (SS) Grade 230, Types 1 and 2; galvalumed cold-rolled sheet steel.
- .4 Bituminous Coating: Fibrous asphalt emulsion.
- .5 Joint Sealant: Exterior weatherseal sealant, SEAL-EXT as specified in Section 07 92 00.

2.6 COMPONENTS

- .1 Aluminum Composite Material (ACM): Front and rear faces of sheet aluminum, factory bonded to fire-rated inorganic (FR) core; and having the following physical properties:
 - .1 Thickness: 4 mm.
 - .2 Surface Burning Characteristics (CAN/ULC-S102):
 - .1 Flame Spread Index = 0.
 - .2 Smoke Developed Index \leq 30.
 - .3 Bond Integrity (ASTM D1781): No adhesive failure of bond between core and skins.
 - .4 Finish: Monochromatic paint coating, both faces.
 - .5 Product and Manufacturer Name: eg. Alucobond Plus by 3A Composites USA Inc.
- .2 Panel Load Transfer Grid: 1.2 mm thick galvanized steel hat bars, adjustable Z-bars or combination clip and Z-bar.
- .3 Sills: Matching thickness and finish as panels; complete with reinforced back-up splice plates at joints and directional changes.
- .4 Prefinished Metal Trim and Flashing: 1.5 mm thick aluminum, finish to match panels.
- .5 Fasteners: Stainless steel; concealed type; as recommended by panel manufacturer.
- .6 Thermal Isolation Clips: 1.9 mm thick galvalumed sheet steel, complete with integral glass fibre reinforced polyamide thermal isolator pad; capable of supporting vertical and horizontal subgirts; sizes as indicated on Drawings; eg. ISO Clip by Northern Facade.

2.7 FABRICATION

- .1 Shop fabricate Products as far as possible.
- .2 Fabricate panels from aluminum composite material to sizes, depths, and thicknesses as indicated on accepted Shop Drawings.
- .3 Layout cutting, punching, and forming at Shop Drawing stage to avoid cutting at Place of the Work.

- .4 Fabricate system with straight lines, square corners or smooth bends, free from twists or warps, kinks, dents, and other imperfections which may affect appearance or serviceability of installed system.
- .5 Fabricate system to have flush appearance from exterior, with no surface attachments or other irregularities, and with no reveal other than module joint width.
- .6 Align panels with no lap or reveal other than joint width to permit expansion and contraction.
- .7 Use metal of sufficient thickness, configured to adequate detail and sufficiently supported to ensure adequate strength and stiffness to resist distortion of finished surfaces.
- .8 Dress exposed edges and ends smooth and free of sharp edges.
- .9 Fabricate panels with flanges on all sides, framed with aluminum extrusions. Include uniformly radiused corners with factory welded connections. Grind smooth.
- .10 Accommodate panel drainage at base of each panel.
- .11 Coordinate and Provide openings for protrusions required by other Sections. Reinforce openings greater than 300 mm square.
- .12 Panel lines, breaks, and angles to be sharp, true, and surfaces free from warp or buckle.

2.8 FABRICATION TOLERANCES

- .1 Panel Flatness: Maximum deviation in any direction of 0.2 percent.
- .2 Panel Bow Tolerance: Maximum 0.8 percent of panel dimension in width and length.

2.9 FINISHES

- .1 Monochromatic Paint Coating on Aluminum: To AAMA 2605; three-coat thermosetting fluoropolymer PVDF liquid extrusion and coil coating, factory-applied to 0.04 mm dry film thickness; eg. Duranar XL by PPG Industries, Inc., 4 colours, including one custom colour, as selected by Consultant.
- .2 Galvalumed Coating on Sheet Steel: To ASTM A792/A792M, Coating Designation AZ180; hot dipped aluminum-zinc alloy coating.
- .3 Galvanized Coating on Steel Components: To ASTM A123/A123M, Coating Grade 55; hot dipped zinc alloy coating.
- .4 Galvanized Coating on Steel Hardware: To ASTM A153/A153M, Classes B3, C or D; hot dipped zinc alloy coating.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify substrates are plumb within 1:1000 of overall height, and are plus or minus 3 mm within designed location.

3.2 PREPARATION

- .1 Maintain uniform temperature in work area, adequate for work being performed, as recommended by manufacturer.
- .2 Securely install thermal isolation clips to substrate at spacing indicated on accepted Shop Drawings.

- .3 Secure panel load transfer grid to thermal isolation clips.
- .4 Construct panel load transfer grid using interlocking clips as indicated on accepted Shop Drawings. Transmit design loads to structural supports.

3.3 INSTALLATION

- .1 Install Product plumb, true, level, and in alignment.
- .2 Install Product to established lines and elevations.
- .3 Securely anchor panels onto panel load transfer grid with concealed mechanical fasteners, clips, and perimeter framing extrusions.
- .4 Completed installation to be free of distortion and surface imperfections, uniform in colour and gloss.
- .5 Isolate dissimilar metals with bituminous coating to prevent electrolytic action.
- .6 Install flashings to divert moisture to exterior.
- .7 Provide proper weatherproof seals at perimeter junctions. Seal joints as specified in Section 07 92 00.

3.4 TOLERANCES

- .1 Deviation from Vertical and Horizontal Alignment: ≤ 6 mm in 6 000 mm.
- .2 Deviation from Panel Flatness: ≤ 3 mm in 1 500 mm panel in any direction for assembled units (non-accumulative).

3.5 ADJUSTING

- .1 Touch up marks or abrasions as installation proceeds.
- .2 Discard dented panels.
- .3 Defective Products or workmanship, whenever found at any time prior to final acceptance of the Work, will be rejected regardless of previous acceptance.

3.6 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Clean panels free of grime and dirt.

3.7 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect completed installation from damage.
- .3 Make Good damage.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 07 84 00 - Firestopping.
 - .2 Section 09 21 16 - Gypsum Board Assemblies.
- 1.2 REFERENCES
 - .1 ASTM C612-25: Standard Specification for Mineral Fiber Block and Board Thermal Insulation.
 - .2 ASTM C847-18(2024): Standard Specification for Metal Lath.
 - .3 ASTM E84-26a: Standard Test Method for Surface Burning Characteristics of Building Materials.
 - .4 ASTM E119-26: Standard Test Methods for Fire Tests of Building Construction and Materials.
 - .5 ASTM E605/E605M-19: Standard Test Methods for Thickness and Density of Sprayed Fire-Resistive Material (SFRM) Applied to Structural Members.
 - .6 ASTM E736/E736M-19: Standard Test Method for Cohesion/Adhesion of Sprayed Fire-Resistive Materials Applied to Structural Members.
 - .7 ASTM E759/E759M-92(2020): Standard Test Method for Effect of Deflection on Sprayed Fire-Resistive Material Applied to Structural Members.
 - .8 ASTM E760/E760M-92(2020): Standard Test Method for Effect of Impact on Bonding of Sprayed Fire-Resistive Material Applied to Structural Members.
 - .9 ASTM E761/E761M-92(2020): Standard Test Method for Compressive Strength of Sprayed Fire-Resistive Material Applied to Structural Members.
 - .10 ASTM E859/E859M-93(2020): Standard Test Method for Air Erosion of Sprayed Fire-Resistive Materials (SFRMs) Applied to Structural Members.
 - .11 ASTM E937/E937M-93(2020): Standard Test Method for Corrosion of Steel by Sprayed Fire-Resistive Materials (SFRMs) Applied to Structural Members.
 - .12 ASTM E1513/E1513M-93(2020): Standard Practice for Application of Sprayed Fire-Resistive Materials (SFRMs).
 - .13 AWCI Standard Practice for the Testing and Inspection of Field Applied Sprayed Fire-Resistive Materials.
 - .14 CAN/ULC-S101-14 (REV1): Standard Method of Fire Endurance Tests of Building Construction and Materials.
 - .15 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
 - .16 CAN/ULC-S114-2018: Standard Method of Test for Determination of Non-Combustibility in Building Materials.
 - .17 ULC List of Equipment and Materials.
- 1.3 SEQUENCING
 - .1 Perform fire protection work on a given floor prior to proceeding with fire protection work on next floor.

- .2 Coordinate and schedule fire protection work to avoid delays in progress of the Work.
 - .3 Do not install board fire protection on structural members until piping and other construction behind fire protection has been completed, uninterrupted coverage can be provided, and need for subsequent cutting and patching can be eliminated.
- 1.4 PRODUCT DATA
- .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, certifying compliance with specified performance criteria.
- 1.5 TEST AND EVALUATION REPORTS
- .1 Submit test reports as specified in Section 01 33 00.
 - .2 Test Reports: Manufacturer's standard test results indicating Products meet specified performance criteria, prepared by independent testing agency, and current within past 5 years.
- 1.6 QUALIFICATIONS
- .1 Installer: A firm specializing in applying spray-applied fire resistive coatings, and licensed or certified as an installer by Product manufacturer.
- 1.7 DELIVERY, STORAGE AND HANDLING
- .1 Refer to Section 01 60 00.
 - .2 Deliver Products to Place of the Work in manufacturer's unopened packages, fully identified as to name, type, and other identifying data. Packaging shall bear UL labels for fire hazard and fire-resistance classifications.
 - .3 Store Products above ground, in a dry location, protected from weather. Remove damaged packages found unsuitable for use from Place of the Work.
- 1.8 AMBIENT CONDITIONS
- .1 When prevailing outdoor temperature at Place of the Work is less than 4 degrees C, maintain minimum substrate and ambient air temperature of 4 degrees C prior to, during, and minimum 24 hours after application of spray-applied fire resistive material.
 - .2 When required to maintain progress of the Work, Provide heated protective enclosures to maintain temperatures. Refer to Section 01 56 00.
 - .3 Provide adequate ventilation of not less than 4 air changes per hour to allow proper drying of spray-applied fire resistive material during and subsequent to application.
- 2 Products
- 2.1 MANUFACTURERS
- .1 Manufacturers having Product considered acceptable for use:
 - .1 AD Fire Protection Systems.
 - .2 Grace Canada Inc.
 - .3 Isolatek International.
 - .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 PERFORMANCE CRITERIA

- .1 Spray-Applied Fire Resistive Coating
 - .1 Deflection (ASTM E759/E759M): Material shall not crack or delaminate when non-concrete topped galvanized deck to which it is applied is subjected to a one time vertical centerload resulting in a downward deflection of 1/120th of the span.
 - .2 Bond Impact (ASTM E760/E760M): Material shall not crack or delaminate from concrete topped galvanized deck to which it is applied.
 - .3 Cohesion / Adhesion (ASTM E736/E736M): Material applied over uncoated or galvanized steel shall have an average bond strength greater than 7.2 kPa.
 - .4 Air Erosion (ASTM E859/E859M): $\leq 0.27 \text{ g/m}^2$.
 - .5 Compressive Strength (ASTM E761/E761M): Material shall not deform more than 10 percent when subjected to a crushing force of 68.9 kPa.
 - .6 Corrosion Resistance (ASTM E937/E937M): Material shall not promote corrosion of steel.
 - .7 Combustibility (CAN/ULC-S114): Noncombustible.
 - .8 Surface Burning Characteristics (ASTM E84 or CAN/ULC-S102): Class A
 - .1 Flame Spread Index = 0.
 - .2 Smoke Developed Index = 0.
 - .9 Density (ASTM E605/E605M): Material shall meet minimum individual and average density values as listed in appropriate UL/ULC design or as required by authority having jurisdiction, or shall have a minimum average density of 240 kg/m^3 .
- .2 Conduct tests and report tested values to CAN/ULC-S101.

2.3 MATERIALS

- .1 Spray-Applied Fire Resistive Material (SFRM): Inorganic Portland cement-based dry mix spray-applied fire resistive material; eg. Cafco Blazeshield II by Isolatek International.
- .2 Refractory Mineral Wool Board Fire Protection: To ASTM C612, Class 4; rigid boards produced from asbestos free materials by combining refractory mineral wool manufactured from slag with thermosetting resin binders; and having the following physical properties:
 - .1 Thermal Resistance: $\text{RSI} \geq 0.76 @ 24 \text{ degrees C}$.
 - .2 Surface Burning Characteristics (ASTM E84):
 - .1 Flame Spread Index ≤ 15 .
 - .2 Smoke Developed Index ≤ 5 .
 - .3 Density: $\geq 144 \text{ kg/m}^3$.
 - .4 Manufacturer and Product Name: eg. Cafco-board Mineral Wool Board Fire Protection by Isolatek International.
- .3 Fastening Accessories: For each fire resistive assembly in which mineral wool board fire protection serves as rigid fire protection, Provide board fastening system complying with applicable UL design or other acceptable testing and inspecting organization's report.
- .4 Metal Lath: To ASTM C847; 1.4 kg/m^2 steel lath, galvanized.
- .5 Water: Potable.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Ensure surfaces to receive fire protection are free of oil, grease, loose mill scale, dirt, paints and primers (other than those listed and tested), and other foreign materials that could impair satisfactory bonding to substrate.

- .3 Ensure clips, hangers, supports, sleeves, and other attachments to substrate are installed prior to application of spray-applied fire resistive materials.
- .4 Ensure installation of suspended equipment shall not occur until application of sprayed fire protection is complete in affected area.

3.2 PREPARATION

- .1 Prepare substrates to ULC Sprayed-Applied Fire-Resistive Materials New Requirements for the Use of Sprayed-Applied Fire-Resistive Materials on Primed Steel Surfaces.
- .2 Provide bonding agents and metal lath as required.

3.3 APPLICATION

- .1 Apply Products to ASTM E1513/E1513M.
- .2 Apply Products to required thicknesses and densities necessary to achieve fire resistance ratings indicated on Drawings.
- .3 Do not apply Products to steel floor decks prior to application of concrete.
- .4 Do not apply Products to underside of roof deck until roof is completely installed and tight, penthouses are complete, mechanical units have been placed, and roof traffic has ceased.
- .5 Provide masking, drop cloths, or other suitable coverings to prevent overspray from coming in contact with surfaces not intended to be sprayed.
- .6 Apply bonding materials as per identified ULC fire resistance design and manufacturer's written recommendations.
- .7 Topcoat materials shall be type recommended and approved by manufacturer of each spray-applied fire resistive material required by Contract Documents.
- .8 Install mineral wool board fire protection to comply with requirements for thicknesses, number of layers, construction of joints and corners, and fastening methods referenced in appropriate fire resistance design assembly noted in Contract Documents.
- .9 Coordinate installation of board fire protection with other construction to minimize cutting into, or removal of, already installed board material.

3.4 FIELD QUALITY CONTROL

- .1 Refer to Section 01 40 00.
- .2 Test spray-applied fire resistive material for thickness and density to ASTM E605/E605M or AWCI Standard Practice for the Testing and Inspection of Field-Applied Sprayed Fire-Resistive Materials.

3.5 ADJUSTING

- .1 Make Good damaged fire protection.

3.6 PROTECTION

- .1 Protect completed installation as specified in Section 01 76 00.
- .2 Provide final protection and maintain conditions in a manner acceptable to Consultant and authorities having jurisdiction.
- .3 Ensure installed Products are not damaged at time of final inspection.

- .4 Make Good damaged Products immediately prior to Ready-for-Takeover.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 05 50 00 - Metal Fabrications.
- .3 Section 07 81 00 - Applied Fireproofing.
- .4 Section 07 92 00 - Joint Sealants.
- .5 Section 09 21 16 - Gypsum Board Assemblies.

1.2 REFERENCES

- .1 ASTM C303-21: Standard Test Method for Dimensions and Density of Preformed Block and Board-Type Thermal Insulation.
- .2 ASTM C1104/C1104M-19(2025): Standard Test Method for Determining the Water Vapor Sorption of Unfaced Mineral Fiber Insulation.
- .3 ASTM E119-26: Standard Test Methods for Fire Tests of Building Construction and Materials.
- .4 ASTM E2174-24: Standard Practice for On-Site Inspection of Installed Firestop Systems.
- .5 ASTM E2393-20a: Standard Practice for On-Site Inspection of Installed Fire Resistive Joint Systems and Perimeter Fire Barriers.
- .6 ASTM E3456-25: Standard Practice for On-Site Identification of Firestop Systems and Judgments.
- .7 CAN/ULC-S101-14 (REV1): Standard Method of Fire Endurance Tests of Building Construction and Materials.
- .8 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .9 CAN/ULC-S114-2018: Standard Method of Test for Determination of Non-Combustibility in Building Materials.
- .10 CAN/ULC-S115:2023: Standard Method of Fire Tests of Firestop Systems.
- .11 CAN/ULC-S129-15 (REV1): Standard Method of Test for Smoulder Resistance of Insulation (Basket Method).
- .12 CAN/ULC-S702.1:2021: Standard for Mineral Fibre Thermal Insulation for Buildings, Part 1: Material Specification.
- .13 ULC List of Equipment and Materials.

1.3 PREINSTALLATION MEETINGS

- .1 Prior to commencing installation of firestopping and smoke seals, arrange and conduct preinstallation meeting as specified in Section 01 31 00.
- .2 Preinstallation Meeting: Discuss proposed methods and materials to be used in each instance.
- .3 Representatives of Owner, Contractor, Consultant, Subcontractor, manufacturer, and authority having jurisdiction are to be in attendance.

- .4 Do not conduct meeting unless identified parties are present.
- 1.4 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Sealant manufacturer's standard installation instructions and standard drawings, indicating ULC or WHI test designations.
- 1.5 SHOP DRAWINGS
 - .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, illustrating sizes of openings, nature of penetrations, and tested method of firestop and smoke seal protection being proposed.
 - .1 Shop Drawings are to be stamped, signed, and dated by manufacturer's design engineer.
 - .2 Submit Shop Drawings to Consultant and authority having jurisdiction for review and acceptance.
- 1.6 CERTIFICATES
 - .1 Submit certification as specified in Section 01 33 00.
 - .2 Certificate: Sealant manufacturer's letter of certification verifying Products meet or exceed specified requirements.
- 1.7 TEST AND EVALUATION REPORTS
 - .1 Submit test reports as specified in Section 01 33 00.
 - .2 Test Reports: Manufacturer's standard test results indicating Products meet specified performance criteria, prepared by independent testing agency, and current within past 5 years.
- 1.8 FIELD QUALITY CONTROL SUBMITTALS
 - .1 Submit field quality control submittals as specified in Section 01 40 00.
 - .2 Manufacturer's Field Inspection Reports: Manufacturer's written acceptance of installation based on regular inspections.
 - .3 Engineered Judgements: Where completed installations deviate from tested design assembly, submit engineered judgements prepared by manufacturer's design engineer verifying compliance with applicable regulatory requirements.
- 1.9 QUALIFICATIONS
 - .1 Manufacturer's Design Engineer: A professional engineer having minimum 10 years documented experience designing firestop and smoke seal systems, licensed to practice at Place of the Work.
 - .2 Installer: A firm specializing in installing firestop and smoke seal systems, approved or certified as an installer by manufacturer.
- 1.10 MOCK-UPS
 - .1 Construct mock-ups as specified in Section 01 40 00.
 - .2 Mock-ups: One full-size mock-up of each penetration firestop system, fire-resistive joint system, perimeter fire containment system, and continuity head-of-wall joint system, complete with smoke seals required on Project. Include representative substrates and

penetrating components, for each fire rating required at each type of wall, floor, and roof construction.

- .3 Comply with Project requirements as to thickness and density of application to achieve required fire rating.
- .4 Accepted mock-ups will be used as the standard for acceptance of the Work.
- .5 Remove and replace installed Product that does not conform to accepted mock-up.
- .6 Remove mock-ups from Place of the Work upon Ready-for-Takeover.

1.11 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver Products to Place of the Work in original unopened packages.
- .3 Store Products in an enclosed shelter, preventing damage to containers.

1.12 AMBIENT CONDITIONS

- .1 Do not apply sealants when temperature of substrate material and surrounding air is below 5 degrees C.
- .2 Maintain sealant at minimum 18 degrees C for best workability.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 3M Company Canada.
 - .2 AD Fire Protection.
 - .3 Hilti Canada.
 - .4 Nuco Inc.
 - .5 Specified Technologies Inc.
 - .6 Tremco Construction Products Group.
 - .7 The Rectorseal Corporation.
- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 DESIGN AND PERFORMANCE CRITERIA

- .1 Seal empty holes and penetrations at floors, fire rated walls, and smoke barrier walls.
- .2 Seal holes accommodating penetrating items such as cables, cable trays, pipes, ducts, and conduits.
- .3 Design firestopping system to maintain integrity of time rated construction by providing a seal against spread of heat, flame, and smoke.
- .4 Systems shall be ULC or ULI classified or listed by WHI for appropriate required time rating.
- .5 Provide firestop and smoke seal systems to CAN/ULC-S115 and as described below:
 - .1 Asbestos free materials and systems fully capable of maintaining an effective barrier against gases, flame, and smoke in compliance with CAN/ULC-S115, not exceeding opening sizes stated.
 - .2 Service Penetration Assemblies: Certified by CAN/ULC-S115 and used by ULC Guide 40 U19. Service components listed as certified in this guide are noted under Label Service of ULC.

- .6 Fire resistance rating of firestopping assembly must meet or exceed fire resistance rating of floor or wall being penetrated.
- .7 Provide elastomeric seal at openings around penetrations for pipes, ductwork, and other mechanical items requiring sound and vibration control. Do not use cementitious or rigid seals at such locations.
- .8 Damming and back up materials, supports, and anchoring devices shall be to manufacturer's recommendations, and in strict accordance with tested assembly being installed as acceptable to authorities having jurisdiction.
- .9 Firestopping compounds shall not contain volatile solvents or require special application to protect plastic pipe from firestopping compound.

2.3 MATERIALS

- .1 Primer: As recommended by sealant manufacturer for specific material, substrate and end use.
- .2 Firestop Accessories: Firestop foams, boards, blocks, collars, wraps, puttys, and plugs; to CAN/ULC-S115; ULC labelled; types as listed in tested assemblies.
- .3 Firestop Insulation: To CAN/ULC-S702.1, Type 2; mineral fibre manufactured from rock or slag, suitable for manual application; and having the following physical properties when tested to the identified standard:
 - .1 Density (ASTM C303): $> 72 \text{ kg/m}^3$.
 - .2 Combustibility (CAN/ULC-S114): Noncombustible.
 - .3 Melt Temperature: > 1175 degrees C.
 - .4 Surface Burning Characteristics: To CAN/ULC-S102, as follows:
 - .1 Flame Spread Index ≤ 0 .
 - .2 Smoke Developed Index ≤ 0 .
 - .5 Moisture Sorption (ASTM C1104/C1104M): 0.04 percent.
 - .6 Smoulder Resistance (CAN/ULC-S129): 0.01 percent.
- .4 Firestop Sealants: To CAN/ULC-S115; ULC labelled; non-sagging type for vertical applications; types as listed in tested assemblies.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Confirm compatibility of surfaces to receive sealant materials.
- .3 Verify surfaces of openings are sound, clean, dry, and ready to receive application.
- .4 Verify penetrating elements are securely fixed, and properly located.

3.2 PREPARATION

- .1 Protect adjacent surfaces and equipment from damage.
- .2 Clean contact surfaces of dirt, dust, grease, oil, loose material, or other matter which may impair sealant bond.
- .3 Remove incompatible materials which affect bond by scraping, brushing, water cleaning, solvent cleaning, or sandblasting.

3.3 APPLICATION

- .1 Install firestop insulation in compacted thicknesses required by ULC design. Compress insulation approximately 33 percent.
- .2 Apply sealant in strict accordance with ULC certification.
- .3 Coordinate and cooperate with adjacent, contiguous, and related Subcontractors to ensure a proper and timely installation.
- .4 Seal holes and voids made by penetrating items to ensure an effective fire and smoke barrier.
- .5 Seal intersections and penetrations of floors, ceilings, walls, and columns.
- .6 Seal around cutouts for facility services.
- .7 Wrap non-insulated heated pipes that may be subject to movement with non-combustible smooth material to permit pipe to move without damaging firestopping and smoke seal.
- .8 Maintain integrity of insulation and vapour retarders on insulated pipes and ducts at fire separation.
- .9 Where floor openings exceed 100 mm in width and may be subjected to traffic or loading, install cover plate systems capable of supporting same loading as floor.
- .10 Identify installed penetration firestop systems, fire-resistive joint systems, perimeter fire containment systems, and continuity head-of-wall joint systems to ASTM E3456.
 - .1 Affix firestop identification labels/tags to, or adjacent to, each installed system.

3.4 FIELD QUALITY CONTROL

- .1 Perform field inspection as specified in Section 01 40 00.
- .2 Inspect penetration firestop systems to ASTM E2174.
- .3 Inspect fire-resistive joint systems and perimeter fire containment systems to ASTM E2393.
- .4 Examine finished penetrations to ensure proper installation before concealing or enclosing any areas of work.
- .5 Keep areas of work accessible until inspection has been completed.
- .6 Manufacturer's Field Service: Inspect and confirm completed installation is in strict accordance with ULC requirements.
- .7 Correct defective work and re-inspect to verify compliance with requirements.

3.5 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Immediately remove spots, smears, stains, residues, adhesives, and other disfigurements from installation, including from adjacent surfaces.
- .3 Do not use Products containing volatile solvents.
- .4 Leave the Work in a clean and satisfactory condition.

3.6 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect firestop and smoke seal assemblies from damage.
- .3 Make Good damaged firestop and smoke seal assemblies immediately prior to Ready-for-Takeover.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 06 20 00 - Finish Carpentry.
- .3 Section 06 41 00 - Architectural Wood Casework.
- .4 Section 07 42 43 - Composite Wall Panels.
- .5 Section 07 84 00 - Firestopping.
- .6 Section 07 92 21 - Sprayed Foam Sealant.
- .7 Section 08 12 13 - Hollow Metal Frames.
- .8 Section 08 51 13 - Aluminum Windows.
- .9 Section 08 80 00 - Glazing.
- .10 Section 09 21 16 - Gypsum Board Assemblies.
- .11 Section 09 51 23 - Acoustical Tile Ceilings.
- .12 Section 09 66 13 - Portland Cement Terrazzo Flooring.

1.2 REFERENCES

- .1 ASTM C919-24: Standard Practice for Use of Sealants in Acoustical Applications.
- .2 ASTM C920-18(2024): Standard Specification for Elastomeric Joint Sealants.
- .3 ASTM C1193-25: Standard Guide for Use of Joint Sealants.
- .4 ASTM C1330-23: Standard Specification for Cylindrical Sealant Backing for Use with Cold Liquid-Applied Sealants.
- .5 ASTM C1521-19(2025): Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints.
- .6 CAN/CGSB-19.13-M87: Sealing Compound, One Component, Elastomeric, Chemical Curing.
- .7 CAN/CGSB-19.17-M90: One Component Acrylic Emulsion Base Sealing Compound.

1.3 SAMPLES

- .1 Submit samples as specified in Section 01 33 00.
- .2 Selection Samples: Duplicate samples of each specified joint sealant, illustrating available colour selections.

1.4 MANUFACTURER REPORTS

- .1 Submit manufacturers' reports as specified in Section 01 40 00.
- .2 Manufacturers' Reports: Manufacturer field review reports, as specified below.

1.5 QUALIFICATIONS

- .1 Applicators: Workers experienced with applying joint sealants, having minimum three years documented experience.

1.6 MOCK-UPS

- .1 Construct mock-ups as specified in Section 01 40 00.
- .2 Mock-ups: One full-size, 300 mm long mock-up of each required joint sealant applied to each required substrate, demonstrating joint width and tooled appearance. Allow to cure
- .3 Conduct adhesion pull tests on mock-ups to ASTM C1521, Method A - Destructive Procedure. Sealant adhesion pull tests to fail only cohesively, not adhesively.
- .4 Replace failed mock-ups, and re-test until successful results are achieved.
- .5 Accepted mock-ups will be used as the standard for acceptance of the Work.
- .6 Remove and replace installed Product that does not conform to accepted mock-up.
- .7 Remove mock-ups from Place of the Work upon Ready-for-Takeover.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver Products in manufacturer's sealed packages.
- .3 Store Products in warm, dry conditions.

1.8 AMBIENT CONDITIONS

- .1 Do not install solvent curing sealants in enclosed building spaces.
- .2 Maintain temperature and humidity recommended by sealant manufacturer during and after installation.

1.9 WARRANTY

- .1 Submit extended warranty in accordance with General Conditions of the Contract.
- .2 Extended Warranty: For a period of two years, including coverage of installed sealants and accessories which fail to achieve air tight and watertight seal, exhibit loss of either adhesion or cohesion, or do not cure.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers of exterior weatherseal sealants, glazing sealants, interior general purpose sealants, and interior mildew-resistant sealants having Product considered acceptable for use:
 - .1 Dow Chemical Company.
 - .2 General Electric.
 - .3 Master Builders Solutions Canada, Inc.
 - .4 Tremco Construction Products Group.
- .2 Manufacturers of exterior flashing sealants having Product considered acceptable for use:
 - .1 Henry (a Carlisle Company).
 - .2 Tremco Construction Products Group.
 - .3 W. R. Meadows of Canada Limited.
- .3 Substitution Procedures: Refer to Section 01 25 00.

2.2 PERFORMANCE CRITERIA

- .1 Seal gaps between dissimilar Products, visible or otherwise.
- .2 Protect building components from air infiltration and moisture penetration.

2.3 MATERIALS

- .1 Exterior Weatherseal Sealant (SEAL-EXT): To ASTM C920, Type S, Grade NS, Class 35, Use NT, M, A and O; one-part, moisture curing, low modulus polyurethane sealant; accommodating joint movement of plus or minus 35 percent, with 30- to 90-minute skin time; eg. Dymonic FC by Tremco Construction Products Group, colours as selected by Consultant.
- .2 Exterior Flashing Sealant (SEAL-EXT-FL): To ASTM C920, Type S, Grade NS, Class 35, Use NT; one-part, silyl-terminated polyether (STPE) polymer-based sealant; accommodating joint movement of plus or minus 35 percent; eg. 925 BES Sealant by Henry (a Carlisle Company), colour as selected by Consultant.
- .3 Glazing Sealant (SEAL-GLZ): To CAN/CGSB-19.13-M, Type MG-2-25-A-L; one-part, moisture curing, acetoxy silicone sealant; eg. Proglaze by Tremco Construction Products Group, Clear colour.
- .4 Interior General Purpose Sealant (SEAL-INT-GP): To CAN/CGSB-19.17-M; one-part, siliconized acrylic latex, mildew-resistant, accommodating joint movement of plus or minus 12-1/2 percent; eg. Tremflex 834 by Tremco Construction Products Group, colours as selected by Consultant.
- .5 Interior Mildew-Resistant Sealant (SEAL-INT-MR): To ASTM C920, Type S, Grade NS, Class 25, Use NT, G, A, and O; one-part, acetoxy silicone sealant, complete with integral fungicide; eg. Tremsil 200 by Tremco Construction Products Group, colours as selected by Consultant.

2.4 ACCESSORIES

- .1 Primer: Non-staining type, recommended by sealant manufacturer to suit application.
- .2 Joint Cleaner: Isopropyl alcohol or xylene; non-corrosive and non-staining type, as recommended by sealant manufacturer; compatible with joint forming materials.
- .3 Backer Rod: To ASTM C1330, Type B - Bi-cellular; rod diameter sized 130 - 150 percent larger than designated joint width.
- .4 Bond Breaker Tape: Pressure-sensitive tape recommended by sealant manufacturer to suit application.

3 Execution

3.1 PREPARATION

- .1 Clean and prime joints to requirements of manufacturer's instructions.
- .2 Remove loose materials and foreign matter which might impair adhesion of sealant.
- .3 Mask joint edges where irregular surface or sensitive joint border exists to ensure neat application.

3.2 APPLICATION

- .1 Install joint sealants to ASTM C1193.
- .2 Install acoustical sealants to ASTM C919.

- .3 Apply sealant with pressure gun having proper size nozzle and extrusion nozzle where required.
- .4 Use sufficient pressure to fill joints solid to joint filler.
- .5 Shape nozzle to finish sealant in a neat, concave bead.
- .6 Apply sealant sufficiently in from normal face of joints to form a positive shadow line.
- .7 Tool sealant smooth and slightly concave, free from ridges, wrinkles, air pockets, and embedded impurities.
- .8 Ensure proper configuration and depth achieved. Depth of sealant at point of adhesion shall be not more than one-half joint width.

3.3 FIELD QUALITY CONTROL

- .1 Inspect completed sealant joints for adhesion and cohesion to ASTM C1521.
- .2 Inspect completed sealant joints for holes, gaps, and areas where leaks could become present.
- .3 Reject failed joints, joints filled with only skin bead, and joints having insufficient volume of sealant.
- .4 Remove material from rejected joints, clean, and re-seal to attain proper width-to-depth joint coverage.

3.4 MANUFACTURER SERVICES

- .1 Arrange for sealant manufacturer's representative to be present during mock-up adhesion pull tests, and prior to commencement of sealant installation.
- .2 Consult with manufacturer's representative as to joint conditions.
- .3 Arrange for manufacturer's representative to regularly inspect joint sealant application (minimum twice per week).
- .4 Submit written field review reports, confirming sealant installation is in strict accordance with manufacturer's recommendations.

3.5 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Remove excess sealant and droppings using cleaner which will not damage adjacent surfaces.
- .3 Make Good surfaces defaced or disfigured as a result of sealant application.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 04 00 00 - Masonry.
 - .2 Section 06 10 00 - Rough Carpentry.
 - .3 Section 07 92 00 - Joint Sealants.
 - .4 Section 08 12 13 - Hollow Metal Frames.
 - .5 Section 08 51 13 - Aluminum Windows.
- 1.2 REFERENCES
 - .1 SWI Sealant and Caulking Guide Specification.
 - .2 CAN/ULC-S710.1-2019: Standard for Bead-Applied One Component Polyurethane Air Sealant Foam, Part 1: Material Specification.
 - .3 CAN/ULC S710.2-11: Standard for Thermal Insulation - Bead Applied One-Component Polyurethane Air Sealant Foam, Part 2: Application.
 - .4 CAN/ULC-S711.1-2019: Standard for Bead-Applied Two Component Polyurethane Air Sealant Foam, Part 1: Material Specification.
 - .5 CAN/ULC S711.2-11: Standard for Thermal Insulation - Bead Applied Two-Component Polyurethane Air Sealant Foam, Part 2: Application.
- 1.3 SEQUENCING
 - .1 Sequence installation of Products in conjunction with air barriers and vapour retarders.
- 1.4 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating Product physical properties, performance criteria, and limitations.
- 1.5 MANUFACTURER'S INSTRUCTIONS
 - .1 Submit manufacturer's instructions as specified in Section 01 33 00.
 - .2 Manufacturer's Instructions: Manufacturer's standard installation instructions, indicating preparation and installation requirements and techniques.
- 1.6 DELIVERY STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Deliver Products in undamaged containers and original packaging indicating name of manufacturer and Product.
- 2 Products
- 2.1 MANUFACTURERS
 - .1 Manufacturers having Product considered acceptable for use:
 - .1 DuPont de Nemours, Inc.
 - .2 Henkel Canada Corporation.

- .2 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 PERFORMANCE CRITERIA
 - .1 Ensure continuity of building enclosure air barrier in conjunction with Products specified in other Sections.
 - .2 Seal gaps between building enclosure components and opening frames.
- 2.3 MATERIALS
 - .1 Sprayed Foam Sealant (SFS-1): To CAN/ULC-S710.1; one-component polyurethane sealant.
 - .2 Sprayed Foam Sealant (SFS-2): To CAN/ULC-S711.1; two-component polyurethane sealant.
- 3 Execution
- 3.1 PREPARATION
 - .1 Ensure surfaces are clean, dry and free of oil, grease, dirt, excess mortar, and other contaminants.
- 3.2 INSTALLATION
 - .1 Install sprayed foam sealant in accordance with authorities having jurisdiction.
 - .2 Avoid overfilling restricted spaces.
 - .3 Seal gaps between air barrier membranes and frames installed in openings.
 - .4 Apply sprayed foam sealant Type SFS-1 to cracks or openings 6 mm to 50 mm wide. Conform to CAN/ULC S710.2.
 - .5 Apply sprayed foam sealant Type SFS-2 to gaps over 50 mm wide, and to voids in hidden cavities. Conform to CAN/ULC S711.2.
- 3.3 CLEANING
 - .1 Refer to Section 01 74 00.
 - .2 Clean extra material from adjacent surfaces.
 - .3 Leave a suitable substrate for subsequent construction.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 04 00 00 - Masonry.
 - .2 Section 07 92 00 - Joint Sealants.
 - .3 Section 07 92 21 - Sprayed Foam Sealant.
 - .4 Section 08 13 13 - Hollow Metal Doors.
 - .5 Section 08 71 00 - Finish Hardware.
 - .6 Section 08 80 00 - Glazing.
 - .7 Section 09 21 16 - Gypsum Board Assemblies.
 - .8 Section 09 90 00 - Painting and Coating.
- 1.2 REFERENCES
 - .1 ASTM A653/A653M-23: Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - .2 CSA A500:16 (R2021): Building Guards.
 - .3 CSA W59:24: Welded Steel Construction.
 - .4 CSDMA Canadian Fire Labeling Guide for Commercial Steel Door and Frame Products.
 - .5 CSDMA Canadian Metric Conversion Guide for Steel Doors and Frames (Modular Construction).
 - .6 CSDMA Guide Specification for Installation and Storage of Hollow Metal Doors and Frames.
 - .7 CSDMA Recommended Dimensional Standard for Steel Doors and Frames.
 - .8 CSDMA Recommended Specifications for Commercial Steel Door and Frame Products.
 - .9 NFPA 80-2025: Standard for Fire Doors and Other Opening Protectives.
 - .10 CAN/ULC-S104-15 (R2020): Standard Method for Fire Tests of Door Assemblies.
 - .11 CAN/ULC-S105:2016 (R2020): Standard Specification for Fire Door Frames Meeting Performance Required by CAN/ULC-S104.
 - .12 CAN/ULC-S106-15 (R2020): Standard Method for Fire Tests of Window and Glass Block Assemblies.
 - .13 ULC List of Equipment and Materials.
- 1.3 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets indicating frame components, available ratings, sizes, and thicknesses.
- 1.4 SHOP DRAWINGS
 - .1 Submit Shop Drawings as specified in Section 01 33 00.

- .2 Shop Drawings: Project-specific drawings, illustrating opening sizes, frame configurations, fire ratings, anchor types and spacings, locations of cut outs, reinforcing, and shop finishes.
- 1.5 DELIVERY, STORAGE AND HANDLING
- .1 Refer to Section 01 60 00.
 - .2 Store Products to CSDMA Guide Specification for Installation and Storage of Hollow Metal Doors and Frames.
- 1.6 WARRANTY
- .1 Submit extended warranty in accordance with General Conditions of the Contract.
 - .2 Extended Warranty: For a period of two years, covering against twisting, buckling, weld failure, and corrosion.
- 2 Products
- 2.1 MANUFACTURERS
- .1 Manufacturers having Product considered acceptable for use:
 - .1 All Steel Doors 2000 Limited.
 - .2 Artek Door (1985) Limited.
 - .3 Baron Metal Industries Inc.
 - .4 Daybar Industries Limited.
 - .5 Fleming Door Products Ltd.
 - .6 Gensteel Doors.
 - .7 Metal Door Limited.
 - .8 Trillium Steel Doors Limited.
 - .9 Vision Hollow Metal Limited.
 - .2 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 REGULATORY REQUIREMENTS
- .1 Fire Rated Frame Assemblies: Permanently labelled to NFPA standards for fire rated class indicated, as tested to CAN/ULC-S104 and CAN/ULC-S106.
- 2.3 DESIGN CRITERIA
- .1 Design Products required to act as a building guard by applicable regulatory requirements to CSA A500.
- 2.4 MATERIALS
- .1 Sheet Steel: To ASTM A653/A653M, Commercial Steel (CS) Type B; cold-rolled sheet steel, with regular and paintable galvanneal coatings as noted; thicknesses as indicated.
 - .2 Bituminous Coating: Fibrous asphalt emulsion.
 - .3 Sprayed Foam Sealant: As specified in Section 07 92 21.
 - .4 Touch-up Primer: Zinc-rich alkyd primer.
 - .5 Welding Materials: To CSA W59.
 - .6 Joint Sealant: Interior general purpose sealant, Type SEAL-INT-GP as specified in Section 07 92 00.

2.5 MANUFACTURED UNITS

- .1 Interior Hollow Metal Door and Multi-Opening Frame: Sheet steel, 1.60 mm nominal coated thickness, with paintable galvanneal finish; fire rating as scheduled; sizes and configurations as indicated on Drawings; eg. M-Series Frame by Fleming Door Products Ltd.

2.6 ACCESSORIES

- .1 Reinforcements: Cold-rolled commercial quality steel, regular galvanneal finish, nominal coated thicknesses as follows:
 - .1 Flush Bolt, Lock and Strike Reinforcement: 1.60 mm
 - .2 Hinge Reinforcements: 3.51 mm.
 - .3 Door Closer and Holder Reinforcements: 2.74 mm.
- .2 Anchors: Cold-rolled commercial quality steel, regular galvanneal finish, nominal coated thicknesses as follows:
 - .1 T-Strap Type: 1.30 mm.
 - .2 Stirrup-strap Type: 50 x 250 mm size, 1.60 mm thick.
 - .3 Jamb Floor Type: 1.60 mm thick.
 - .4 Stud Type: 1.00 mm thick.
- .3 Jamb Spreaders: 1.00 mm nominal coated thickness, cold-rolled commercial quality steel, regular galvanneal finish.
- .4 Mortar Guard Boxes: 0.84 mm nominal coated thickness, cold-rolled commercial quality steel, regular galvanneal finish.
- .5 Glazing Stops: Rolled steel channel shape, butted corners; prepared for countersink style tamper-proof screws.
- .6 Bumpers: Resilient rubber.

2.7 FABRICATION

- .1 Fabricate frames as welded units.
- .2 Conform to CSDMA Recommended Specifications for Commercial Steel Door and Frame Products.
- .3 Fabricate fire-rated frames to CAN/ULC-S105.
- .4 Provide fire labels to CSDMA Canadian Fire Labeling Guide for Commercial Steel Door and Frame Products.
- .5 Fabricate frames with fixed mullions, to profiles shown, with hardware reinforcement plates welded in place.
- .6 Welding
 - .1 Perform welding to CSA W59.
 - .2 Fill open joints, seams, and depressions with filler or by continuous brazing or welding.
 - .3 Grind exposed welds smooth and flush, to true sharp arrises and profiles.
 - .4 Sand welds to a smooth, true, uniform finish.
- .7 Mitre corners of frames. Cut frame mitres accurately and weld continuously on inside of frame.
- .8 Protect strike and hinge reinforcements and other openings with mortar guard boxes welded to frame.
- .9 Reinforce frames wider than 1 220 mm with roll formed steel channels fitted tightly into frame head, flush with top.

- .10 Fit frames with channel or angle spreaders, minimum two per frame, to ensure proper frame alignment. Install stiffener plates to spreaders between frame trim where required to prevent bending of trim and to maintain alignment when setting and during construction.
- .11 Provide adjustable T-strap anchors in frames to be installed in masonry openings, spaced at 600 mm OC.
- .12 Where frames are required to terminate at finished floor, Provide plates for anchorage to floor slab.
- .13 Prepare interior door frames for single stud door silencers, three on strike jamb.
- .14 Fabricate frames and screens to accommodate scheduled glazing. Secure glazing stops to frames with counter sunk oval head sheet metal screws.
- .15 Prepare frames for scheduled door hardware and building security system devices. Blank, mortise, reinforce, drill, and tap components.

2.8 FINISHES

- .1 Paintable Galvanneal Coating: To ASTM A653/A653M, Coating Designation ZF120; wiped zinc-iron coating, with streak-free matte grey appearance.
- .2 Regular Galvanneal Coating: To ASTM A653/A653M, Coating Designation ZF75; wiped zinc-iron coating, with streak-free matte grey appearance.

3 Execution

3.1 INSTALLATION

- .1 Install Products to CSDMA Guide Specification for Installation and Storage of Hollow Metal Doors and Frames.
- .2 Install Products plumb, square, and aligned.
- .3 Install Products without twist, and at correct elevation.
- .4 Coordinate with masonry and wallboard construction for anchor placement.
- .5 Fill designated frames set in masonry walls and partitions solid with non-shrink grout or mortar, as specified in Section 04 00 00.
- .6 Fill gaps between frames and adjacent wall assemblies with sprayed foam sealant, as specified in Section 07 92 21.
- .7 Seal gaps between frames and walls with joint sealant, as specified in Section 07 92 00.

3.2 FIELD QUALITY CONTROL

- .1 Perform field inspection and testing as specified in Section 01 40 00.
- .2 Field Inspection and Testing: Arrange for independent testing agency to test installed Products designated as building guards; verifying installed Products meet performance criteria required by applicable regulatory requirements.
- .3 Make Good rejected Products not meeting required performance criteria.
- .4 Re-test replacement Products at no additional cost to Owner.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 08 12 13 - Hollow Metal Frames.
 - .2 Section 08 71 00 - Door Hardware.
 - .3 Section 08 80 00 - Glazing.
 - .4 Section 09 90 00 - Painting and Coating.
- 1.2 REFERENCES
 - .1 ASTM A653/A653M-23: Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
 - .2 CSA W59:24: Welded Steel Construction.
 - .3 CSDMA Canadian Fire Labeling Guide for Commercial Steel Door and Frame Products.
 - .4 CSDMA Canadian Metric Conversion Guide for Steel Doors and Frames (Modular Construction).
 - .5 CSDMA Guide Specification for Installation and Storage of Hollow Metal Doors and Frames.
 - .6 CSDMA Recommended Dimensional Standard for Steel Doors and Frames.
 - .7 CSDMA Recommended Specifications for Commercial Steel Door and Frame Products.
 - .8 NFPA 80-2025: Standard for Fire Doors and Other Opening Protectives.
 - .9 CAN/ULC-S104-15 (R2020): Standard Method for Fire Tests of Door Assemblies.
 - .10 CAN/ULC-S702.1:2021: Standard for Mineral Fibre Thermal Insulation for Buildings, Part 1: Material Specification.
 - .11 ULC List of Equipment and Materials.
- 1.3 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating materials, component sizes and thicknesses, and available finishes.
- 1.4 SHOP DRAWINGS
 - .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, illustrating door elevations and sizes, internal reinforcement, fire ratings, closure method, size and location of cut outs, and shop finishes.
- 1.5 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Store hollow metal doors to CSDMA Guide Specification for Installation and Storage of Hollow Metal Doors and Frames.
- 1.6 WARRANTY
 - .1 Submit extended warranty in accordance with General Conditions of the Contract.

- .2 Extended Warranty: For a period of two years, covering against twisting, buckling, delamination of steel stiffeners, weld failure and corrosion.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 All Steel Doors 2000 Limited.
 - .2 Artek Door (1985) Limited.
 - .3 Baron Metal Industries Inc.
 - .4 Daybar Industries Limited.
 - .5 Fleming Door Products Ltd.
 - .6 Gensteel Doors.
 - .7 Metal Door Limited.
 - .8 Trillium Steel Doors Limited.
 - .9 Vision Hollow Metal Limited.

- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 REGULATORY REQUIREMENTS

- .1 Fire Rated Doors: Permanently labelled to NFPA standards for fire rated class indicated, as tested to CAN/ULC-S104.

2.3 MATERIALS

- .1 Sheet Steel: To ASTM A653/A653M, Commercial Steel (CS) Type B; cold-rolled sheet steel, with regular and paintable galvaneal coatings as noted; thicknesses as indicated.
- .2 Semi-Rigid Board Insulation: To CAN/ULC-S702.1, Type 1; mineral fibre semi-rigid board having an aged thermal resistance of $RSI \geq 0.68$ per 25 mm of thickness.
- .3 Reinforcements: Commercial quality steel, regular galvaneal finish, nominal coated thicknesses as follows:
 - .1 Flush Bolt, Lock and Strike Reinforcement: 1.60 mm
 - .2 Hinge Reinforcements: 3.51 mm.
 - .3 Door Closer and Holder Reinforcements: 2.74 mm.
- .4 Touch-up Primer: Zinc-rich alkyd primer.
- .5 Welding Materials: To CSA W59.

2.4 MANUFACTURED UNITS

- .1 Interior Hollow Metal Flush Doors - Fire Rated: 45 mm thick, fire rating as scheduled; constructed as follows:
 - .1 Door Faces: Sheet steel panels, 1.60 mm nominal coated thickness, flush design, paintable galvaneal finish.
 - .2 Vertical Steel Stiffeners: Sheet steel profiles, 1.00 mm nominal coated thickness, 44 mm deep, interlocking design, regular galvaneal finish.
 - .3 Door Edge Seams: Continuously welded.
 - .4 Glazing Stops: Rolled steel channel shape, butted corners; prepared for countersunk tamper-proof screws.
 - .5 Core: Semi-rigid board insulation.

2.5 FABRICATION

- .1 Fabricate doors to CSDMA Recommended Specifications for Commercial Steel Door and Frame Products.

- .2 Provide fire labels on fire rated doors to CSDMA Canadian Fire Labeling Guide for Commercial Steel Door and Frame Products.
 - .3 Provide continuous faces free from joints, tool markings, and abrasions
 - .4 Provide hardware reinforcement plates welded in place.
 - .5 Welding
 - .1 Perform welding to CSA W59.
 - .2 Fill open joints, seams, and depressions with filler, or by continuous brazing, or welding.
 - .3 Grind exposed welds smooth and flush, to true sharp arrises and profiles.
 - .4 Sand welds to a smooth, true, uniform finish.
 - .6 Fabricate doors to accommodate scheduled glazing. Secure glazing stops to doors with counter sunk oval head sheet metal screws.
 - .7 Prepare doors for scheduled door hardware and building security system devices. Blank, mortise, reinforce, drill, and tap components.
 - .8 Reinforce and stiffen doors with vertical steel stiffeners spaced at 152 mm OC, continuous for full height of door, laminated to both door faces.
 - .9 Completely fill door cores with specified core materials.
 - .10 Reinforce door edges with channel reinforcing.
 - .11 Bevel stiles minimum 3 mm.
 - .12 Continuously weld door edge seams. Finish to a smooth, seamless appearance.
- 2.6 FINISHES
- .1 Paintable Galvanneal Coating: To ASTM A653/A653M, Coating Designation ZF120; wiped zinc-iron coating, with streak-free matte grey appearance.
 - .2 Regular Galvanneal Coating: To ASTM A653/A653M, Coating Designation ZF75; wiped zinc-iron coating, with streak-free matte grey appearance.
- 3 Execution
- 3.1 INSTALLATION
- .1 Install doors to CSDMA Guide Specification for Installation and Storage of Hollow Metal Doors and Frames.
- 3.2 TOLERANCES
- .1 Diagonal Distortion: ≤ 1.5 mm measured with straight edge, corner to corner.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 09 21 16 - Gypsum Board Assemblies.
- .3 Section 09 90 00 - Painting and Coating.

1.2 REFERENCES

- .1 ASTM A1008/A1008M-23e1: Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Required Hardness, Solution Hardened, and Bake Hardenable.
- .2 ASTM B221M-21: Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric).
- .3 ASTM E119-26: Standard Test Methods for Fire Tests of Building Construction and Materials.
- .4 NFPA 80-2025: Standard for Fire Doors and Other Opening Protectives.
- .5 CAN/ULC-S702.1:2021: Standard for Mineral Fibre Thermal Insulation for Buildings, Part 1: Material Specification.
- .6 ULC List of Equipment and Materials.

1.3 SHOP DRAWINGS

- .1 Submit Shop Drawings as specified in Section 01 33 00.
- .2 Shop Drawings: Project-specific drawings, illustrating materials, profiles, accessories, locations, and dimensions.

1.4 CERTIFICATIONS

- .1 Submit certification reports as specified in Section 01 33 00.
- .2 Fire Test Certification Report: Certifying performance within specified fire rating.

1.5 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Store Products in a dry, protected, well-vented area.
- .3 Remove protective wrapping immediately after installation.

1.6 WARRANTY

- .1 Submit extended warranty in accordance with General Conditions of the Contract.
- .2 Manufacturer's Extended Warranty: For a period of 5 years, covering parts against defects.

2 Products

2.1 MANUFACTURERS

.1 Manufacturers having Product considered acceptable for use:

- .1 Acudor Access Doors.
- .2 Bilco Canada.
- .3 Cendrex.
- .4 Nystrom, Inc.
- .5 The Williams Brothers Corporation.

.2 Substitution Procedures: Refer to Section 01 25 00.

2.2 REGULATORY REQUIREMENTS

.1 Fire Rated Assemblies: To applicable regulatory requirements and NFPA requirements for fire rated class indicated.

2.3 MATERIALS

.1 Sheet Steel: To ASTM A1008/A1008M, Commercial Steel (CS) Types A, B, and C; cold-rolled sheet steel; thicknesses as specified below.

.2 Extruded Aluminum: To ASTM B221M, 6061-T5 alloy, mill finish; thicknesses as specified below.

.3 Insulation: To CAN/ULC-S702.1, Type 1; non-rigid mineral fibre insulation, made from rock or slag fibers.

2.4 MANUFACTURED UNITS

.1 Gypsum Board Wall and Ceiling Access Panel - Fire-Rated: 1-1/2 hour B-label with maximum temperature rise of 110 degrees C; suitable for both horizontal or vertical installation; sizes as indicated on Drawings; and meeting the following characteristics:

- .1 Door: 48 mm deep, 1.21 mm thick sheet steel, insulated with non-rigid mineral fibre insulation, completely filling door cavity.
- .2 Box Frame: 1.52 mm thick sheet steel, complete with 25 mm wide, 0.61 mm thick galvanized steel perforated flange.
- .3 Closer: Automatic, spring-type.
- .4 Hinge: Fully concealed, 170 degree opening pivot-type.
- .5 Latch: Self-latching direct action latch, opposite hinge.
- .6 Lock: Ultra lock with key (code 151).
- .7 Finish: Powder coated paintable finish.
- .8 Manufacturer and Product Name: eg. Model WB-FR DW Standard Drywall Fire Rated Access Door by The Williams Brothers Corporation.

.2 Gypsum Board Wall Access Panel - Non-Rated: Suitable for vertical installation in gypsum board partitions; sizes as indicated on Drawings; and meeting the following characteristics:

- .1 Door: 1.52 mm thick sheet steel.
- .2 Box Frame: 1.52 mm thick sheet steel, complete with 25 mm wide, 0.61 mm thick galvanized steel perforated flange.
- .3 Hinge: Fully-concealed offset type.
- .4 Latch: Flush, stainless steel cam.
- .5 Lock: Key cylinder lock with key (code 151).
- .6 Finish: Powder coated paintable finish.
- .7 Manufacturer and Product Name: eg. Model WB-DW Drywall Access Door by The Williams Brothers Corporation.

- .3 Gypsum Board Ceiling Access Panel - Non-Rated: Suitable for horizontal installation in gypsum board ceilings; sizes as indicated on Drawings; and meeting the following characteristics:
 - .1 Door: 2.0 mm thick extruded aluminum, complete with 16 mm thick moisture resistant gypsum board infill, brush gasket, and safety chain.
 - .2 Box Return Frame: 2.0 mm thick extruded aluminum, concealed flange of depth to match adjacent ceiling board thickness.
 - .3 Hinge: Concealed pivot hinge, allowing for door removal.
 - .4 Latch: Push to open.
 - .5 Finish: Mill finish.
 - .6 Manufacturer and Product Name: eg. Model WB-NTG Trimless Gypsum Access Door by The Williams Brothers Corporation.
- .4 Masonry Wall Access Panel - Fire-Rated: 1-1/2 hour B-label with maximum temperature rise of 110 degrees C; suitable for both horizontal or vertical installation in masonry or concrete partitions or bulkheads; and meeting the following characteristics:
 - .1 Door and Trim: 48 mm deep, 1.21 mm thick sheet steel, with rolled safety edge on inside of door; insulated with non-rigid mineral fibre insulation, completely filling door cavity.
 - .2 Box Return Frame: 1.52 mm thick sheet steel, complete with 4 masonry strap anchors.
 - .3 Panel Closer: Automatic, spring-type.
 - .4 Hinge: Fully-concealed rod type hinge, 170 degree opening.
 - .5 Latch: Self-latching direct-action latch, opposite hinge.
 - .6 Lock: Ultra lock with key included with each door.
 - .7 Finish: Powder coated paintable finish.
 - .8 Manufacturer and Product Name: eg. Model WB-FRS-U Standard Ultra Fire Rated Access Door by The Williams Brothers Corporation.
- .5 Masonry Wall Access Panel - Non-Rated: Suitable for both horizontal or vertical installation in masonry or concrete partitions or bulkheads; and meeting the following characteristics:
 - .1 Door: 1.90 mm thick sheet steel.
 - .2 Return Frame: 1.21 mm thick sheet steel, complete with 4 masonry strap anchors.
 - .3 Hinges: Fully-concealed offset type, 170 degree opening.
 - .4 Latch: Flush, stainless steel cam.
 - .5 Lock: Key cylinder lock with key (code 151).
 - .6 Finish: Powder coated paintable finish.
 - .7 Manufacturer and Product Name: eg. Model WB-GP Premium General Purpose Access Door by The Williams Brothers Corporation.

2.5 FINISHES

- .1 Aluminum: Standard factory mill finish.
- .2 Powder Coated Paintable Finish: Electrostatically spray-applied polymer powder, White colour; paintable type.

3 Execution

3.1 PREPARATION

- .1 Coordinate installation of access panels in masonry walls with Section 04 00 00.
- .2 Coordinate installation of access panels in gypsum board partitions and ceilings with Section 09 21 16.
- .3 Coordinate exact locations of access panels with facility services Subcontractors.

3.2 INSTALLATION

- .1 Install Products straight, plumb and level.
- .2 Install Products flush with adjacent surfaces.
- .3 Install Products for long life under hard use.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 07 26 00 - Vapour Retarders.
- .3 Section 07 27 00 - Air Barriers.
- .4 Section 07 92 00 - Joint Sealants.
- .5 Section 07 92 21 - Sprayed Foam Sealant.
- .6 Section 08 80 00 - Glazing.
- .7 Section 09 21 16 - Gypsum Board Assemblies.

1.2 REFERENCES

- .1 AAMA CW-10-15: Care and Handling of Architectural Aluminum from Shop to Site.
- .2 AAMA/WDMA/CSA 101/I.S. 2/A440-22: North American Fenestration Standard / Specification for Windows, Doors and Skylights.
- .3 AAMA 502-21: Voluntary Specification for Field Testing of Newly Installed Fenestration Products.
- .4 AAMA 1503-09: Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors and Glazed Wall Sections.
- .5 AAMA 2605-22: Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (With Coil Coating Appendix).
- .6 ASTM A123/A123M-24: Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- .7 ASTM A153/A153M-23: Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
- .8 ASTM A653/A653M-23: Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
- .9 ASTM B209/B209M-21a: Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate.
- .10 ASTM B221M-21: Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric).
- .11 ASTM E90-23: Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
- .12 ASTM E283/E283M-26: Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Skylights, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen.
- .13 ASTM E330/E330M-14(2021): Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference.
- .14 ASTM E331-00(2023): Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference.

- .15 ASTM E783-02(2018): Standard Test Method for Field Measurement of Air Leakage Through Installed Exterior Windows and Doors.
 - .16 ASTM E1105-15(2023): Standard Test Method for Field Measurement of Water Penetration of Installed Exterior Windows, Skylights, Doors, and Curtain Walls, by Uniform or Cyclic Static Air Pressure Difference.
 - .17 CAN/CGSB-79.1-M91: Insect Screens.
 - .18 CSA A440.4:19: Window, Door, and Skylight Installation.
 - .19 CSA A500:16 (R2021): Building Guards.
 - .20 ANSI/NFRC 100-2023: Procedure for Determining Fenestration Product U-factors.
 - .21 ANSI/NFRC 200-2023: Procedure for Determining Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence.
- 1.3 SHOP DRAWINGS
- .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, illustrating:
 - .1 Large scale details of members and materials, of brackets and anchorage devices, and of connection and jointing details;
 - .2 Fully dimensioned layouts for positioning of brackets and anchorage devices to structures;
 - .3 Dimensions and thicknesses;
 - .4 Glazing details, description of materials including catalogue numbers, Product names, and manufacturer's name;
 - .5 Aluminum alloy and temper designations;
 - .6 Finish specifications; and
 - .7 Other pertinent data.
 - .3 Submit documentation of:
 - .1 Compliance with AAMA/WDMA/CSA 101/I.S. 2/A440.
 - .2 Thicknesses, profiles, and descriptions of components used in assembly.
 - .3 Engineering calculations verifying assembly has been designed, constructed, and attached to withstand forces anticipated for Project, and meet specified performance criteria.
 - .4 Shop Drawings, including engineering calculations, are to be stamped, signed, and dated by fabricator's design engineer.
- 1.4 CERTIFICATES
- .1 Submit certifications as specified in Section 01 40 00.
 - .2 Frame Certification: A certificate from aluminum extruder certifying aluminum alloys and tempers meet or exceed specified types.
- 1.5 TEST AND EVALUATION REPORTS
- .1 Submit test reports as specified in Section 01 33 00.
 - .2 Test Reports: Manufacturer's standard test results indicating Products meet specified performance criteria, prepared by independent testing agency, and current within past 5 years.
- 1.6 CLOSEOUT SUBMITTALS
- .1 Submit closeout submittals as specified in Section 01 78 00.

- .2 Maintenance Data: Manufacturer's standard maintenance and cleaning instructions; sufficient quantity for inclusion in operation and maintenance manual.

1.7 QUALIFICATIONS

- .1 Fabricator's Design Engineer: A professional structural engineer experienced in designing aluminum windows, licensed to practice at Place of the Work.
- .2 Fabricator and Installer: A firm specializing in fabricating and installing aluminum windows, having minimum 5 years documented experience.

1.8 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Conform to AAMA CW-10.
- .3 Take precautionary measures and adequately protect frames and frame finishes to prevent damage during fabrication, storage, shipping, handling, and installation.
- .4 Deliver, handle, and store units by methods approved by manufacturer. Protect from damage and staining.
- .5 Deliver and store units carefully to avoid damage to window frame.

1.9 WARRANTY

- .1 Submit extended warranties in accordance with General Conditions of the Contract.
- .2 Manufacturer's Extended Warranty: For a period of 10 years, covering the following:
 - .1 Finish: Replace any window unit whose finish shows defects, such as but not limited to delamination, blistering, or excessive fading.
 - .2 Performance: Replace or repair any window unit with air leakage, water leakage, defects, or malfunctions under normal usage.
- .3 Installer's Extended Warranty: For a period of two years, protecting against air leakage, water leakage, operational defects, and malfunction under normal usage.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 Aerloc Industries Ltd.
 - .2 Alumicor.
 - .3 Alwind Industries, Ltd.
 - .4 Commdoor Aluminum.
 - .5 CRL US Aluminum.
 - .6 Kawneer.
 - .7 Oldcastle BuildingEnvelope.
 - .8 Windspec Inc.

- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 DESCRIPTION

- .1 Aluminum Windows: Extruded aluminum fixed frame and operable vent sash, shop fabricated, with monochromatic paint finish; site-glazed with sealed insulating glass units; complete with insect screens, operable vent hardware, metal sills and flashings, connection flanges, anchorages, and attachment devices.

- .2 Basis of Design: AA 6600 Thermal Window by Kawneer.
- .3 Configuration: As indicated on Window Schedule.

2.3 PERFORMANCE CRITERIA

- .1 Aluminum Windows: To AAMA/WDMA/CSA 101/I.S. 2/A440, and meeting the following performance criteria:
 - .1 NAFS Performance Class:
 - .1 Fixed Unit: AW-PG70-FW.
 - .2 Operable Vent: AW-PG70-AP.
 - .2 Air Leakage (ASTM E283/E283M):
 - .1 Fixed Unit: $\leq 0.23 \text{ L/s}\cdot\text{m}^2 @ 75 \text{ Pa}$.
 - .2 Operable Vent: $< 0.5 \text{ L/s}\cdot\text{m}^2 @ 75 \text{ Pa}$.
 - .3 Water Resistance (ASTM E331): No leakage at 720 Pa test pressure differential.
 - .4 Uniform Load Deflection (ASTM E330/E330M): $\leq L/175$ at 3 352 Pa, for both positive and negative directions.
 - .5 Condensation Resistance Factor (AAMA 1503):
 - .1 Fixed Unit: $\text{CRF}_{\text{frame}} \geq 77$, $\text{CRF}_{\text{glass}} \geq 72$.
 - .2 Operable Vent: $\text{CRF}_{\text{frame}} \geq 71$, $\text{CRF}_{\text{glass}} \geq 69$.
 - .6 Sound Transmission Loss (ASTM E90):
 - .1 Fixed Unit: $\text{STC} \geq 38 \text{ dB}$, $\text{OITC} \geq 32 \text{ dB}$.
 - .2 Operable Vent: $\text{STC} \geq 35 \text{ dB}$, $\text{OITC} \geq 28 \text{ dB}$.
 - .7 Assembly Thermal Transmittance (ANSI/NFRC 100):
 - .1 Fixed Unit: $U \leq 2.15 \text{ W/m}^2 \text{ degrees C}$.
 - .2 Operable Vent: $U \leq 2.56 \text{ W/m}^2 \text{ degrees C}$.
 - .8 Assembly Solar Heat Gain Coefficient (ANSI/NFRC 200): $\text{SHGC} \leq 0.40$.

2.4 DESIGN CRITERIA

- .1 Design assembly to drain water entering joints, condensation occurring in glazing channel, and migrating moisture occurring within system to exterior.
- .2 Design intermediate members within units to be either solid or tubular design to suit wind loading, weight carrying requirements, and wind deflection limitations.
- .3 Design coupling mullions to permit unit module construction and accommodate thermal expansion. When required, reinforce wind load carrying members with steel reinforcement suitably treated to prevent electrolytic action.
- .4 Design operable vents to have a restricted opening not to project beyond face of masonry veneer on Ground Floor, and not to exceed 100 mm on subsequent floors.
- .5 Design Products designated as building guards by applicable regulatory requirements to CSA A500.

2.5 MATERIALS

- .1 Extruded Aluminum: To ASTM B221M, 6063-T5 alloy.
- .2 Sheet Aluminum: To ASTM B209/B209M, 3003-H14 alloy.
- .3 Sheet Steel: To ASTM A653/A653M, Commercial Steel (CS) Types A, B, and C; cold-rolled sheet steel, galvanized.
- .4 Steel Sections: Shaped to suit mullion sections.
- .5 Shims: Plastic.
- .6 Fastener: Stainless steel.

- .7 Screen Mesh: Heavy duty stainless steel mesh.
- .8 Bituminous Coating: Fibred asphalt emulsion.
- .9 Thermal Break: Rigid polyamide.
- .10 Vapour Retarder: As specified in Section 07 26 00.
- .11 Air Barriers: As specified in Section 07 27 00.
- .12 Sprayed Foam Sealant: As specified in Section 07 92 21.
- .13 Glazing Sealant: Type SEAL-GLZ as specified in Section 07 92 00.
- .14 Glazing Materials: As specified in Section 08 80 00.
- .15 Joint Sealants: As specified in Section 07 92 00, Types as follows:
 - .1 Exterior Applications: Exterior weatherseal sealant, Type SEAL-EXT.
 - .2 Transition Sheet Connections: Exterior flashing sealant, Type SEAL-EXT-FL.
 - .3 Interior Applications: Interior general purpose sealant, Type SEAL-INT-GP.
- .16 Touch-Up Primer for Galvanized Metal Surfaces: Zinc-rich paint type.

2.6 COMPONENTS

- .1 Frames and Mullions: 1.78 mm thick extruded aluminum; 152 mm deep profile; thermally broken with interior tubular section insulated from exterior; applied glazing stops; drainage holes; internal weep drainage system.
- .2 Operable Vent Sash: 1.78 mm thick extruded aluminum sections; 73 x 86 mm size profile, top-hinged projecting out (TPO) design; thermally broken with interior tubular section insulated from exterior; applied glazing stops.
- .3 Metal Sills: 2.5 mm thick extruded aluminum sections, complete with pre-formed clip anchor; sufficient depth to extend beyond wall face, full length pieces to minimize joints; and with integral drip edge profile and end dams.
- .4 Metal Flashing: 2.0 mm thick extruded aluminum, finish to match mullion sections where exposed.
- .5 Operable Vent Hardware:
 - .1 Concealed Hinges: Extruded aluminum concealed hinges, minimum two per sash, greater quantity when required by sash size.
 - .2 Limit Stop: Heavy duty metal construction, manufacturer's standard design.
 - .3 Operator: Pivot shoe roto operator complete with removable crank handle.
 - .4 Locking Handles: Single handle multi-point locking, complete with sash mounted strike plate; Silver painted finish.
 - .5 Weatherstripping: Manufacturers standard type to suit application, finish to match frame.
- .6 Connection Flange: 3.0 mm thick extruded aluminum angle, size as indicated on Drawings.
- .7 Glass: As specified in Section 08 80 00, Types as indicated on Drawings.

2.7 FABRICATION

- .1 Fabricate Products to AAMA/WDMA/CSA 101/I.S. 2/A440.
- .2 Fabricate Products with minimum clearances, and shim spacing around perimeter of assembly.
- .3 Make joints flush, hairline, and weatherproof.

- .4 Arrange fasteners and attachments to conceal from view.
- .5 Prepare components with internal reinforcement for operating hardware.
- .6 Provide minimum two lockable handles per operable vent sash.
- .7 Overlap and seal glazing flanges of abutting members for entire depth and width of flanges to ensure a solid, unbroken air and water barrier. Glass stops shall be screwless, lock-in type.
- .8 Provide fully resilient settings for glass and panels by use of EPDM elastomeric glazing gaskets on both sides of glass installed in window frames.
- .9 Provide connection flange to full perimeter of frame, attached from interior side of frame with concealed fasteners cut flush with face of flange. Pre-drill fastener holes into flange to accommodate immediate on-site installation.
- .10 Insect Screens
 - .1 Fabricate screen frames of tubular extruded aluminum, to CAN/CGSB-79.1-M; prefinished to match window frames.
 - .2 Secure screen mesh to screen frame with removable polyethylene splines.
 - .3 Secure screen assemblies to window frames using mechanical fasteners as required by authorities having jurisdiction.

2.8 FINISHES

- .1 Monochromatic Paint Coating on Aluminum: To AAMA 2605; three-coat thermosetting fluoropolymer PVDF liquid extrusion and coil coating, factory-applied to 0.04 mm dry film thickness; eg. Duranar XL by PPG Industries, Inc., colour as selected by Consultant.
- .2 Galvanized Coating on Steel Components: To ASTM A123/A123M, Coating Grade 55; hot dipped zinc alloy coating.
- .3 Galvanized Coating on Steel Hardware: To ASTM A153/A153M, Classes B3, C or D; hot dipped zinc alloy coating.
- .4 Galvanized Coating on Sheet Steel: To ASTM A653/A653M, Coating Designation Z275; hot dipped zinc alloy coating.

2.9 SOURCE QUALITY CONTROL

- .1 Perform shop inspection and testing as specified in Section 01 40 00.
- .2 Shop Inspection and Testing: Random tests conducted by independent testing agency on fabricated window framing at point of manufacture, verifying compliance with specified performance criteria.

3 Execution

3.1 PREPARATION

- .1 Apply heavy coat of bituminous paint on surfaces of aluminum placed in contact with concrete, mortar, plaster, or dissimilar metals.
- .2 Provide fastenings and anchors required to be built in to adjacent work to other Sections.

3.2 INSTALLATION

- .1 Install Products to CSA A440.4.
- .2 Install Products in correct locations, level, square, and plumb.

- .3 Install Products free from distortion, properly aligned, and at proper elevations.
- .4 Make joints neat, fine, and weathertight.
- .5 Allow for expansion and contraction of components.
- .6 Provide additional mouldings and closures necessary.
- .7 Use appropriate fasteners compatible with materials being fastened. Conceal fasteners.
- .8 Fasten connection flange to wall assembly and connect building envelope air barrier membrane to flange.
- .9 Seal connection flange to transition sheet membranes with continuous bead of joint sealant prior to application of sprayed foam sealant.
- .10 Provide trim panning and flashings of sufficient size to neatly finish window frame to interior and exterior window opening.
- .11 Fill gaps between exterior frames and adjacent wall assemblies with sprayed foam sealant, as specified in Section 07 92 21.
- .12 Install glass as specified in Section 08 80 00.
- .13 Provide sills in place with anchoring devices located at ends and evenly spaced at 600 mm OC. Fasten expansion joint cover plates and drip deflectors with self-tapping stainless steel screws.
- .14 Maintain 6 - 9 mm space between butted ends of continuous sills. For sills over 1 220 mm in length, maintain 3 - 6 mm space at each end.
- .15 Install end dams at each sill.
- .16 Grind smooth exposed edges of aluminum sills, ensuring no sharp edges.
- .17 Seal perimeter joints with joint sealant, as specified in Section 07 92 00.

3.3 TOLERANCES

- .1 Deviation From Plumb and Level: ≤ 3 mm in 3 000 mm.

3.4 FIELD QUALITY CONTROL

- .1 Perform field inspection and testing as specified in Section 01 40 00.
- .2 Field Inspection and Testing: One set of tests, conducted by independent testing agency to AAMA 502, on a completed installation at each floor level, verifying compliance with specified performance criteria.
- .3 Perform field tests as follows:
 - .1 Air Infiltration Test: To ASTM E783.
 - .2 Water Infiltration Test: To ASTM E1105.
- .4 Make Good Products not meeting specified performance criteria.
- .5 Re-test replacement Products at no additional cost to Owner.

3.5 ADJUSTING

- .1 Adjust operable vents, insect screens, hardware, and accessories for tight fit at contact points, and weatherstripping for smooth operation and weather tight closure.
- .2 Lubricate hardware and moving parts.

3.6 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Clean glass and aluminum surfaces.
- .3 Do not scratch or damage surfaces.
- .4 Do not remove protective cover from windows until after final cleaning operations have been completed.

3.7 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect completed installation from damage resulting from subsequent construction operations.
- .3 Make Good damage.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 08 12 13 - Hollow Metal Frames.
- .2 Section 08 13 13 - Hollow Metal Doors.
- .3 Section 26 05 00 - Electrical Basic Materials and Methods.

1.2 REFERENCES

- .1 ANSI/BHMA A156.1-2016: Butts and Hinges.
- .2 ANSI/BHMA A156.2-2017: Bored & Preassembled Locks and Latches.
- .3 ANSI/BHMA A156.3-2014: Exit Devices.
- .4 ANSI/BHMA A156.4-2019: Door Controls - Closers.
- .5 ANSI/BHMA A156.5-2014: Cylinders and Input Devices for Locks.
- .6 ANSI/BHMA A156.6-2010: Architectural Door Trim.
- .7 ANSI/BHMA A156.8-2010: Door Controls - Overhead Stops & Holders.
- .8 ANSI/BHMA A156.12-2018: Interconnected Locks & Latches.
- .9 ANSI/BHMA A156.13-2017: Mortise Locks.
- .10 ANSI/BHMA A156.14-2013: Sliding and Folding Hardware.
- .11 ANSI/BHMA A156.15-2015: Release Devices - Closer Holder, Electromagnetic and Electromechanical.
- .12 ANSI/BHMA A156.16-2018: Auxiliary Hardware.
- .13 ANSI/BHMA A156.17-2014: Self Closing Hinges & Pivots.
- .14 ANSI/BHMA A156.18-2016: Materials and Finishes.
- .15 ANSI/BHMA A156.19-2013: Power Assist & Low Energy Power Operated Doors.
- .16 ANSI/BHMA A156.21-2014: Thresholds.
- .17 ANSI/BHMA A156.22-2017: Door Gasketing and Edge Seal Systems.
- .18 ANSI/BHMA A156.23-2017: Electromagnetic Locks.
- .19 ANSI/BHMA A156.24-2012: Delayed Egress Locks.
- .20 ANSI/BHMA A156.25-2018: Electrified Locking Devices.
- .21 ANSI/BHMA A156.26-2017: Continuous Hinges.
- .22 ANSI/BHMA A156.28-2018: Recommended Practices for Mechanical Keying Systems.
- .23 ANSI/BHMA A156.29-2017: Exit Locks, Exit Alarms, Alarms for Exit Devices.
- .24 ANSI/BHMA A156.31-2019: Electric Strikes and Frame Mounted Actuators.
- .25 ANSI/BHMA A156.36-2016: Auxiliary Locks.
- .26 ANSI/BHMA A156.37-2014: Multipoint Locks.

- .27 CSDMA Recommended Dimensional Standard for Steel Doors and Frames.
 - .28 CSDMA Canadian Fire Labeling Guide for Commercial Steel Door and Frame Products.
 - .29 CSDMA Canadian Metric Conversion Guide for Steel Doors and Frames (Modular Construction).
 - .30 ANSI/DHI A115.IG-1994: Installation Guide for Doors and Hardware.
 - .31 DHI Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames.
 - .32 DHI Recommended Locations for Architectural Hardware for Flush Wood Doors.
 - .33 DHI Sequence and Format for the Hardware Schedule.
 - .34 DHI Keying Systems and Nomenclature.
 - .35 DHI Abbreviations and Symbols.
 - .36 NFPA 80-2025: Standard for Fire Doors and Other Opening Protectives.
 - .37 NFPA 105-2025: Standard for Smoke Door Assemblies and Other Opening Protectives.
 - .38 ANSI/UL 1784-15: Standard for Air Leakage Tests of Door Assemblies and Other Opening Protectives.
- 1.3 PREINSTALLATION MEETINGS
- .1 Refer to Section 01 31 00.
 - .2 Prior to installation of hardware, arrange a meeting between Owner, Contractor, Consultant, manufacturer, hardware Supplier, architectural hardware consultant, and installation Subcontractor to review materials, procedures and coordinate related work.
- 1.4 PRODUCT DATA
- .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, illustrating materials, sizes, and operating features for each specified piece of door hardware.
 - .3 Submit templates to installer prior to installation.
- 1.5 SHOP DRAWINGS
- .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific documents, including door hardware schedule, keying schedule, and wiring diagrams, as follows:
 - .1 Door Hardware Schedule, prepared by architectural hardware consultant (AHC), in vertical format, to DHI Sequence and Format for the Hardware Schedule.
 - .2 Keying Schedule: Prepared by architectural hardware consultant (AHC), to DHI Keying Systems and Nomenclature, including special keying notes and stamping instructions. Do not order locks and cylinders until key schedule has been accepted by Consultant.
 - .3 Wiring Diagrams: A written description of the functional use of power-operated door hardware. Include door and frame elevations showing location of each scheduled power-operated hardware item, including a wiring diagram showing number and size of conductors.
- 1.6 SAMPLES
- .1 Submit samples as specified in Section 01 33 00.

- .2 Samples: One sample of each hardware item complete with fasteners, clearly labeled with hardware schedule designation and manufacturer's name and model number.

1.7 CLOSEOUT SUBMITTALS

- .1 Submit closeout submittals as specified in Section 01 78 00.
- .2 Operating and Maintenance Data: Including maintenance instructions for each hardware item, catalogue cut sheets and Product data sheets for each Product, parts list for each Product, an updated copy of door hardware schedule illustrating actual Products installed, and a copy of final keying schedule.

1.8 EXTRA STOCK MATERIALS

- .1 Supply extra stock materials as specified in Section 01 78 00.
- .2 Extra Stock Materials: Clearly labeled to identify type of hardware, manufacturer name, model number, and finish; for each of the following:
 - .1 Ten key lock cylinders for each master keyed group.
 - .2 Three installation tools for passage sets, locksets and privacy sets.

1.9 QUALIFICATIONS

- .1 Hardware Supplier: A firm specializing in supplying institutional door hardware, and having minimum 10 years documented experience.
- .2 Hardware Supplier Personnel: Employ a qualified architectural hardware consultant (AHC) to supervise scheduling and supplying door hardware.

1.10 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Package hardware separately for each opening in a package which contains all hardware for that opening and is designated with applicable heading number, door number and key-set symbol.
- .3 Store Products in a clean, dry and secure area, on adequate shelving to permit organization so item numbers are readily visible.
- .4 Supply Products complete with keys, templates and installation instructions, together with all required screws, expansion shields, anchors, jigs and other related accessories for satisfactory attachment and installation of hardware.

1.11 WARRANTY

- .1 Submit manufacturers' standard extended warranties for each item of hardware.

2 Products

2.1 REGULATORY REQUIREMENTS

- .1 Conform to applicable regulatory requirements and NFPA requirements for fire rated doors, frames and hardware.
 - .1 Ensure smoke control requirements are met by means of gasketing systems to NFPA 105, as tested to ANSI/UL 1784.
 - .2 Ensure fire exit requirements are met with regard to automatic closers, fusible links, positive latching, and direction of travel.

2.2 KEYING

- .1 Conform to ANSI/BHMA A156.28.
- .2 Key doors to Owner's existing GMK or MK system.
- .3 Each system to be construction master keyed (CMK), and supplied complete with three keys per lock, 5 master keys (MK) or grand master keys (GMK), and 10 construction keys.
- .4 Provide visual key control (VKC) on face of each cylinder and on change keys.

2.3 DOOR HARDWARE

- .1 Butt Hinges: To ANSI/BHMA A156.1, Grade 1.
- .2 Continuous Hinges: To ANSI/BHMA A156.26.
- .3 Self-Closing Hinges and Pivots: To ANSI/BHMA A156.17.
- .4 Locksets and Latchsets: To ANSI/BHMA A156.2, Grade 1.
- .5 Exit Devices: To ANSI/BHMA A156.3.
- .6 Closers: To ANSI/BHMA A156.4; surface-mounted type.
- .7 Cylinders and Input Devices: To ANSI/BHMA A156.5, Operational Class, Grade 1.
- .8 Overhead Door Stops: To ANSI/BHMA A156.8.
- .9 Interconnected Locks and Latches: To ANSI/BHMA A156.12, Grade 1.
- .10 Mortise Locks: To ANSI/BHMA A156.13, Operational Class, Grade 1.
- .11 Auxiliary Locks: To ANSI/BHMA A156.36, Grade 1.
- .12 Multipoint Locks: To ANSI/BHMA A156.13, Operational Class, Grade 1.
- .13 Sliding and Folding Door Hardware: To ANSI/BHMA A156.14.
- .14 Powered Release Devices: To ANSI/BHMA A156.15.
- .15 Powered Door Operators: To ANSI/BHMA A156.19.
- .16 Powered Door Locks: To ANSI/BHMA A156.23; electromagnetic type.
- .17 Powered Locking Devices: To ANSI/BHMA A156.25.
- .18 Powered Strikes and Actuators: To ANSI/BHMA A156.31.
- .19 Delayed Egress Locks: To ANSI/BHMA A156.24.
- .20 Alarms for Exit Devices: To ANSI/BHMA A156.29.
- .21 Door Trim: Protection plates, push plates, door pulls, push bars, and pull bars; to ANSI/BHMA A156.6.
- .22 Thresholds: To ANSI/BHMA A156.21.
- .23 Auxiliary Hardware: To ANSI/BHMA A156.16.
- .24 Door Gaskets and Weatherstripping: To ANSI/BHMA A156.21.

2.4 FINISHES

- .1 Conform to ANSI/BHMA A156.18.

- .2 Provide hardware with finishes stipulated in preliminary hardware schedule.
- 3 Execution
- 3.1 EXAMINATION
- .1 Refer to Section 01 71 00.
 - .2 Verify doors and frames are ready to receive hardware, and that dimensions are as indicated on accepted Shop Drawings and door hardware schedule.
 - .3 Verify power supply of 120V AC, 20 amps, 3 phase, 60 Hz is available to power-operated devices.
- 3.2 INSTALLATION
- .1 Install hardware to ANSI/DHI A115.IG.
 - .2 Use templates provided by hardware manufacturer.
 - .3 Provide routing or mortising for hinges and other items required to be mortised or rebated or otherwise housed within material.
 - .4 Install hardware at mounting heights specified in manufacturers' templates or as indicated in hardware schedule.
 - .5 Install hardware using only manufacturer-supplied and -approved fasteners, in strict accordance with manufacturers' published installation instructions. Provide suitable security-type fasteners as specified in hardware sets.
 - .6 Ensure locksets, latchsets and deadbolts are of correct hand before installation to ensure cylinder is in correct position. Handing is part of installation procedure.
 - .7 Ensure exit devices are of correct hand and adjust device cam for proper outside trim function prior to installation. Handing is part of installation procedure.
 - .8 Install head seal prior to installation of "PA"-parallel arm mounted door closers and push side mounted door stops and holders.
 - .9 Counter sink through-bolt of door pull under push plate during installation.
 - .10 Mount closers, automatic operators and hold-open devices as noted in hardware schedule.
 - .11 Secure thresholds with machine screws and anchors.
- 3.3 FIELD QUALITY CONTROL
- .1 Examine installed hardware and notify Consultant of improper installations, defective Products or where installation does not conform to Contract Documents.
- 3.4 ADJUSTING
- .1 Replace Products exhibiting scratched or damaged surfaces.
 - .2 Properly tighten fasteners and ensure that fasteners are installed to the full required complement.
 - .3 Adjustment is inclusive of spring power, closing speed, latching speed and back-check at the time of installation.
 - .4 Adjust delayed-action door operators and closers to forty-second delay to accommodate barrier-free access. Time period to be approved by Owner.

3.5 DEMONSTRATION

- .1 Refer to Section 01 00 0001 79 00.
- .2 Demonstrate operation and maintenance of hardware items, including proper use, servicing, adjusting and lubrication procedures.

3.6 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Cover surfaces with removable protective film.
- .3 Maintain protection until Owner occupancy.

3.7 ATTACHMENTS

- .1 Refer to attached preliminary hardware schedule for a listing of required door hardware, organized on a door-by-door basis.

END OF SECTION

Hardware Group No. 01

For use on Door #(s):

N206 W211

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1 127X114MM	652	IVE
1	EA	CLASSROOM LOCK	ND70P6D RHO	626	SCH
1	EA	KICK PLATE	8400 205MM X 40MM LDW B-CS	630	IVE
1	EA	WALL STOP	WS401/402CVX	626	IVE
1	EA	SMOKE/SOUND GASKETING	188SBK PSA	BK	ZER
1	SET	GASKETING	870AA-S (1X DR W, 2X DR H)	AA	ZER
1	EA	HMD DOOR BOTTOM	355AA X DR WIDTH	AA	ZER
1	EA	SOUND THRESHOLD	566A X FR WIDTH	A	ZER

Hardware Group No. 02

For use on Door #(s):

W209

Provide each UEP door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
6	EA	HINGE	5BB1HW 127X114MM	652	IVE
1	EA	AUTO FLUSH BOLT	FB32	630	IVE
1	EA	DUST PROOF STRIKE	DP2	626	IVE
1	EA	CLASSROOM LOCK	ND70P6D RHO 14-042	626	SCH
1	EA	COORDINATOR	COR X FL	628	IVE
2	EA	OH STOP	100S	630	GLY
2	EA	SURFACE CLOSER	4040XPT ST-3182	689	LCN
2	EA	FLUSH CEILNG MTG PLATE	4040XP-18G SRT	689	LCN
2	EA	KICK PLATE	8400 205MM X 25MM LDW B-CS	630	IVE
1	EA	SMOKE/SOUND GASKETING	188SBK PSA	BK	ZER
2	EA	HMD DOOR BOTTOM	355AA X DR WIDTH	AA	ZER
1	EA	ASTRAGAL/MEETING STILE	383AA X DR HT	AA	ZER
1	EA	SOUND THRESHOLD	566A X FR WIDTH	A	ZER

Hardware Group No. 03

For use on Door #(s):

W210

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
3	EA	HINGE	5BB1 127X114MM	652	IVE
1	EA	CLASSROOM LOCK	ND70P6D RHO	626	SCH
1	EA	OH STOP	100S	630	GLY
1	EA	KICK PLATE	8400 205MM X 40MM LDW B-CS	630	IVE
1	EA	SMOKE/SOUND GASKETING	188SBK PSA	BK	ZER
1	SET	GASKETING	870AA-S (1X DR W, 2X DR H)	AA	ZER
1	EA	HMD DOOR BOTTOM	355AA X DR WIDTH	AA	ZER
1	EA	SOUND THRESHOLD	566A X FR WIDTH	A	ZER

Hardware Group No. 04

For use on Door #(s):

TEACHER
CLOSET

Provide each SGL door(s) with the following:

QTY		DESCRIPTION	CATALOG NUMBER	FINISH	MFR
1	EA	CLASSROOM LOCK	ALX70P6 RHO 10-013 1 1/8" LIP	626	SCH
1	EA	HARDWARE	BALANCE OF HARDWARE BY MILLWORK SUPPLIER		

1 General

1.1 RELATED SECTIONS

- .1 Section 07 92 00 - Joint Sealants.
- .2 Section 08 12 13 - Hollow Metal Frames.
- .3 Section 08 13 13 - Hollow Metal Doors.
- .4 Section 08 51 13 - Aluminum Windows.

1.2 REFERENCES

- .1 AAMA 800-16: Voluntary Specifications and Test Methods for Sealants.
- .2 ANSI Z97.1-2009: Safety Glazing Materials Used in Buildings - Safety Performance Specifications and Methods of Test.
- .3 ASTM C509-06(2021): Standard Specification for Elastomeric Cellular Preformed Gasket and Sealing Material.
- .4 ASTM C864-05(2019): Standard Specification for Dense Elastomeric Compression Seal Gaskets, Setting Blocks, and Spacers.
- .5 ASTM C1036-25: Standard Specification for Flat Glass.
- .6 ASTM C1115-17(2022): Standard Specification for Dense Elastomeric Silicone Rubber Gaskets and Accessories.
- .7 ASTM C1281-16(2023): Standard Specification for Preformed Tape Sealants for Glazing Applications.
- .8 ASTM C1376-21a: Standard Specification for Pyrolytic and Vacuum Deposition Coatings on Flat Glass.
- .9 ASTM E1300-24: Standard Practice for Determining Load Resistance of Glass in Buildings.
- .10 CAN/CGSB-12.1-2022: Safety Glazing.
- .11 CAN/CGSB-12.8-2017: Insulating Glass Units.
- .12 CPSC 16 CFR 1201: Safety Standard for Architectural Glazing Materials.
- .13 GANA Glazing Manual.
- .14 GANA GIB 01-0300: Proper Procedures for Cleaning Architectural Glass.
- .15 IGMA TM-3000-90(16): North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial & Residential Use.
- .16 IGMA TM-4510-18(19): IGMA Quality Procedures for the Fabrication of Insulating Glass Units to the ISO 9001:2008 Standard.
- .17 ANSI/NFRC 100-2023: Procedure for Determining Fenestration Product U-factors.
- .18 ANSI/NFRC 200-2023: Procedure for Determining Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence.
- .19 CAN/ULC-S104-15 (R2020): Standard Method for Fire Tests of Door Assemblies.
- .20 CAN/ULC-S106-15 (R2020): Standard Method for Fire Tests of Window and Glass Block Assemblies.

1.3 PRODUCT DATA

- .1 Submit Product data as specified in Section 01 33 00.
- .2 Product Data: Manufacturer's standard data sheets, indicating structural, physical, and environmental characteristics, thickness and size limitations, special handling requirements, and installation requirements.

1.4 SAMPLES

- .1 Submit samples as specified in Section 01 33 00.
- .2 Verification Samples: Duplicate 300 x 300 mm size samples of each specified sealed insulating glass unit; illustrating colouration and design.

1.5 CERTIFICATES

- .1 Submit certificates as specified in Section 01 33 00.
- .2 Certificate of Compliance: Manufacturer's standard certificate of compliance, attesting fire-rated glazing materials comply with CPSC requirements.

1.6 TEST AND EVALUATION REPORTS

- .1 Submit test reports as specified in Section 01 33 00.
- .2 Test Reports: Manufacturer's standard test results indicating Products meet specified performance criteria, prepared by independent testing agency, and current within past 5 years.

1.7 QUALITY ASSURANCE

- .1 Conform to glazing installation methods and quality standards specified in:
 - .1 GANA Glazing Manual,
 - .2 IGMA TM-3000, North American Glazing Guidelines for Sealed Insulating Glass Units for Commercial & Residential Use, and
 - .3 IGMA TM-4510, IGMA Quality Procedures for the Fabrication of Insulating Glass Units to the ISO 9001:2008 Standard.
- .2 Select glazing compounds and sealants in accordance with glass manufacturers' instructions.

1.8 WARRANTY

- .1 Submit extended warranty in accordance with General Conditions of the Contract.
- .2 Manufacturer's Extended Warranty: For a period of 5 years, covering complete replacement of sealed insulating glass units exhibiting seal failure, or interpane dusting and misting.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers of single pane glass and sealed insulating glass units having Product considered acceptable for use:
 - .1 Cardinal Glass Industries.
 - .2 Guardian Glass.
 - .3 Saint-Gobain Glass.
 - .4 Vitro Architectural Glass.

- .2 Manufacturers of fire-rated ceramic glass having Product considered acceptable for use:
 - .1 Nippon Sheet Glass Co., Ltd.
 - .2 Schott North America, Inc.
- .3 Substitution Procedures: Refer to Section 01 25 00.

2.2 REGULATORY REQUIREMENTS

- .1 Fire-rated Glass: Each lite to bear a permanent, non-removable label designating type of glass, fire rating, and UL mark.

2.3 DESIGN CRITERIA

- .1 Design glass Products to ASTM E1300.
 - .1 Determine necessary glass thickness to withstand dead loads and positive and negative live loads acting normal to plane of glass.
 - .2 Limit glass deflection to 1/200 or flexure limit of glass with full recovery of glazing materials, whichever is less.
- .2 Design Products installed as exterior glazing to contribute to continuity of building enclosure air and vapour seals.

2.4 PERFORMANCE CRITERIA

- .1 Sealed Insulating Glass Units (SIG-CLR-1): Having the following tested physical properties:
 - .1 Visible Light Transmittance (VLT): 70 percent.
 - .2 Visible Light Reflectance:
 - .1 Exterior: 11 percent.
 - .2 Interior: 12 percent.
 - .3 Coefficient of Heat Transmission, Winter, Argon-Filled (ANSI/NFRC 100):
 $U = 1.36 \text{ W/m}^2 \text{ degrees C.}$
 - .4 Solar Heat Gain Coefficient (ANSI/NFRC 200): SHGC = 0.39.
 - .5 Colour Rendering Index: CRI = 95.

2.5 SINGLE PANE GLASS

- .1 Float Glass (GL-1): To ASTM C1036, Type I; glazing quality, 6 mm thick unless noted otherwise.
- .2 Fire-Rated Ceramic Glass (GL-2): Fire-rated and impact safety-rated glass ceramic with surface-applied safety film; having impact safety rating meeting ANSI Z97.1, Class A and CPSC 16 CFR 1201, Categories I and II; and as follows:
 - .1 Thickness: 5 mm.
 - .2 Style: Clear.
 - .3 Grade: Standard.
 - .4 Visible Light Transmittance: 88 percent.
 - .5 Visible Light Reflectance: 9 percent,
 - .6 Fire Rating (CAN/ULC S104 and CAN/ULC-S106): 90 minutes.
 - .7 Manufacturer and Product Name: eg. FireLite NT by Nippon Sheet Glass Co., Ltd.
- .3 Tempered Safety Glass (GL-3): To CAN/CGSB-12.1, Class A; clear float glass fully tempered horizontally to achieve a net strength of not less than 4 to 5 times greater than regular annealed glass; 6 mm thick unless noted otherwise.

2.6 SEALED INSULATING GLASS UNITS

- .1 Sealed Insulating Glass Units (SIG-CLR-1): To CAN/CGSB-12.8; double pane with warm edge seal; comprised as follows:
 - .1 Outer Pane: 6 mm thick Clear tempered safety glass (GL-3), sputtered Low-E coating on #2 surface.
 - .2 Interpane Space: Filled with minimum 90 percent Argon gas.
 - .3 Inner Pane: 6 mm thick Clear tempered safety glass (GL-3).
 - .4 Overall Thickness: 25 mm.
 - .5 Manufacturer's Name and Product: eg. Solarban 60 (2) Clear + Clear by Vitro Architectural Glass.

2.7 COATINGS AND FILMS

- .1 Low-E Coating: To ASTM C1376, Kind CV; magnetron sputtered vacuum deposition (MSVD) coating; eg. Solarban 60 Solar Control Low-E by Vitro Architectural Glass.

2.8 ACCESSORIES

- .1 Warm Edge Seal: Polyisobutylene primary seal with a secondary seal comprised of either silicone, butyl, polysulphide or urethane, as recommended by sealed insulating glass unit manufacturer for each particular glazing application; and with port at top of unit.
- .2 Dense Compression Gasket: Moulded or extruded gaskets, made from neoprene or EPDM to ASTM C864, or thermoplastic polyolefin rubber to ASTM C1115; of profile and hardness required to maintain watertight seal.
- .3 Soft Compression Gasket: To ASTM C509, Type II; moulded or extruded, closed-cell, integral-skinned gaskets made from neoprene, EPDM or thermoplastic polyolefin rubber; Black colour; profile and hardness required to maintain watertight seal.
- .4 Back-Bedding Mastic Glazing Tapes: To ASTM C1281 and AAMA 800, preformed, butyl-based elastomeric tape with 100 percent solids content; non-staining and non-migrating in contact with non-porous surfaces; with or without spacer rod; packaged on rolls with release paper backing.
- .5 Expanded Cellular Glazing Tapes: Closed cell, PVC foam tape, factory-coated with adhesive on both surfaces; packaged on rolls with release liner protecting adhesive; to AAMA 800 for the following types:
 - .1 Tape Acts as Primary Seal: Type 1.
 - .2 Tape Used in Combination with Full-Bead of Sealant: Type 2.
- .6 Glazing Tape for Fire-rated Glass Applications: Fiberfrax Alumino-Silicate Fiber glazing tape by Unifrax Corporation.
- .7 Setting Blocks: Elastomeric material, having a Shore A durometer hardness of 85, plus or minus 5.
- .8 Setting Blocks for Fire-rated Glass Applications: Calcium silicate.
- .9 Spacers: Elastomeric blocks or continuous extrusions, having a Shore A durometer hardness sufficient to maintain glass lites in place both during and after installation.
- .10 Edge Blocks: Elastomeric material of sufficient hardness to limit glass lateral movement.
- .11 Glazing Sealant: SEAL-GLZ as specified in Section 07 92 00.
- .12 Cleaners, Primers and Sealers: Types recommended by sealant and gasket manufacturers.

2.9 FABRICATION

- .1 Fabricate sealed insulating glass units to IGMA TM-4510.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify openings for glazing are correctly sized, within tolerance, and clean.

3.2 PREPARATION

- .1 Clean contact surfaces with solvent and wipe dry.
- .2 Seal porous glazing channels or recesses with substrate compatible primer or sealer.
- .3 Prime surfaces scheduled to receive sealant.

3.3 INSTALLATION

- .1 Conform to GANA Glazing Manual.
- .2 Install exterior glazing forming part of building envelope to IGMA TM-3000 to achieve airtight and watertight seal.
- .3 Protect glass edges from damage during handling and installation. Remove damaged glass Products from Place of the Work and dispose of in accordance with authorities having jurisdiction. Damaged glass is defined as glass with edge damage or other imperfections that, when installed, could weaken the glass and impair performance and appearance.
- .4 Install setting blocks in sill rabbets, sized and located in accordance with GANA Glazing Manual. Set blocks in heel bead of glazing sealant.
- .5 Do not exceed edge pressures stipulated by glass manufacturer for installing glass lites.
- .6 Provide spacers for glass lites where length plus width is larger than 1 270 mm.
- .7 Provide edge blocking necessary to prevent glass lites from moving sideways in glazing channel, in accordance with GANA Glazing Manual.
- .8 Tape Glazing: Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sight line of stops. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.
 - .1 Cover vertical framing joints by applying tapes first to heads and sills, and then to jambs.
 - .2 Cover horizontal framing joints by applying tapes first to jambs, and then to heads and sills.
 - .3 Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant.
 - .4 Center glass lites in openings on setting blocks and press firmly against tape by inserting dense compression gaskets, formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work towards center of openings.
- .9 Gasket Glazing: Fabricate compression gaskets in lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.
 - .1 Insert soft compression gasket between glass and frame or fixed stop such that it is securely in place, with joints miter cut and bonded together at corners.

- .2 Center glass lites in openings on setting blocks and press firmly against soft compression gasket by inserting dense compression gaskets, formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work towards center of openings.
- .3 Install gaskets so they protrude evenly past face of glazing stops.
- .4 Compress gaskets to produce weather tight seal without developing bending stress in glass.
- .5 Seal gasket joints with compatible sealant.

3.4 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Remove glazing materials from finish surfaces.
- .3 Remove non-permanent labels upon Ready-for-Takeover.
- .4 Clean glass surfaces to GANA GIB 01-0300.

3.5 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect exterior glass from damage immediately after installation by attaching crossed streamers to framing held away from glass. Do not apply markers to glass surface.
- .3 Protect glass from contact with contaminating substances resulting from subsequent construction operations.
- .4 Remove and replace Products that have been damaged, including but not limited to having been broken, chipped, cracked, or abraded; regardless of cause, before Ready-for-Takeover.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 07 92 00 - Joint Sealants.
- .3 Section 08 12 13 - Hollow Metal Frames.
- .4 Section 08 31 00 - Access Door and Panels.
- .5 Section 09 51 23 - Acoustical Tile Ceilings.
- .6 Section 09 81 00 - Acoustic Insulation.
- .7 Section 09 90 00 - Painting and Coating.

1.2 REFERENCES

- .1 ASTM A641/A641M-19(2025): Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire.
- .2 ASTM A653/A653M-23: Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
- .3 ASTM A792/A792M-23: Standard Specification for Steel Sheet, 55% Aluminum-Zinc Alloy-Coated by the Hot-Dip Process.
- .4 ASTM C475/C475M-17(2022): Standard Specification for Joint Compound and Joint Tape for Finishing Gypsum Board.
- .5 ASTM C514-04(2020): Standard Specification for Nails for the Application of Gypsum Board.
- .6 ASTM C645-24: Standard Specification for Nonstructural Steel Framing Members.
- .7 ASTM C754-20: Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products.
- .8 ASTM C840-25: Standard Specification for Application and Finishing of Gypsum Board.
- .9 ASTM C954-22: Standard Specification for Steel Drill Screws for the Application of Gypsum Panel Products or Metal Plaster Bases to Steel Studs From 0.033 in. (0.84 mm) to 0.112 in. (2.84 mm) in Thickness.
- .10 ASTM C1002-20: Standard Specification for Steel Self-Piercing Tapping Screws for Application of Gypsum Panel Products or Metal Plaster Bases to Wood Studs or Steel Studs.
- .11 ASTM C1047-19: Standard Specification for Accessories for Gypsum Wallboard and Gypsum Veneer Base.
- .12 ASTM C1264-19(2024): Standard Specification for Sampling, Inspection, Rejection, Certification, Packaging, Marking, Shipping, Handling, and Storage of Gypsum Panel Products.
- .13 ASTM C1396/C1396M-24: Standard Specification for Gypsum Board.
- .14 ASTM C1629/C1629M-24: Standard Classification for Abuse-Resistant Nondecorated Interior Gypsum Panel Products and Fiber-Reinforced Cement Panels.
- .15 ASTM C1658/C1658M-24: Standard Specification for Glass Mat Gypsum Panels.

- .16 ASTM E90-23: Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
 - .17 CGC Gypsum Construction Handbook.
 - .18 CAN/CGSB-71.25-M88: Adhesive, for Bonding Drywall to Wood Framing and Metal Studs.
 - .19 CISCA Ceiling Systems Handbook, 2012 Edition.
 - .20 GA-214-2021: Levels of Finish for Gypsum Panel Products.
 - .21 GA-226-2019: Application of Gypsum Board to Form Curved Surfaces.
 - .22 CAN/ULC-S101-14 (REV1): Standard Method of Fire Endurance Tests of Building Construction and Materials.
 - .23 ULC List of Equipment and Materials.
- 1.3 QUALIFICATIONS
- .1 Installers: A firm specializing in erecting metal framing and installing gypsum board, having minimum 5 years documented experience.
- 1.4 DELIVERY, STORAGE AND HANDLING
- .1 Conform to ASTM C1264.
- 2 Products
- 2.1 MANUFACTURERS
- .1 Manufacturers of non-loadbearing metal framing having Product considered acceptable for use:
 - .1 Bailey Metal Products Limited.
 - .2 CGC Inc.
 - .3 Dietrich Metal Framing.
 - .2 Manufacturers of gypsum board having Product considered acceptable for use:
 - .1 CertainTeed Canada, Inc.
 - .2 CGC Inc.
 - .3 G-P Gypsum Corporation.
 - .3 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 DESCRIPTION
- .1 Interior Partitions: Vertical non-load bearing metal stud framing clad with wall boards mechanically-fastened or adhered on one or both sides, and including acoustical insulation and accessories where indicated.
 - .2 Suspended Ceilings: Horizontal non-load bearing channels and framing carrying mechanically-fastened ceiling boards, and including acoustical ceiling hangers, insulation, and accessories where indicated.
 - .3 A non-load bearing (non-structural) member is defined as a member in a steel-framed system which is limited to transverse (out-of-plane) load of not more than 480 Pa, a superimposed axial load, exclusive of sheathing materials, of not more than 1 460 N/m, or a superimposed axial load of not more than 890 N.

- .4 A load bearing (structural) stud may be used in a non-load bearing application; however, non-load bearing members (studs or track) may never be used in a load bearing (axial or lateral loading) application.

2.3 PERFORMANCE CRITERIA

- .1 Provide metal wall framing systems with maximum design limit of 240 Pa and maximum allowable deflection of L/360.
- .2 Provide metal ceiling framing systems with maximum allowable deflection of L/240.
- .3 Fire-Resistance Rated Assemblies: Provide Products and construction identical to those tested in listed assemblies. Conform to CAN/ULC-S101.
- .4 Sound Rated Assemblies: Provide Products and construction identical to those tested in listed assemblies. Conform to ASTM E90.

2.4 METAL FRAMING

- .1 Metal Wall Studs: To ASTM C645; 0.455 mm thick sheet steel; galvanized or galvalumed finish; C-Shape with 32 mm wide flange, complete with serrated faces and knock-outs for electrical fitments; depths as indicated on Drawings.
- .2 Heavy Duty Metal Wall Studs: To ASTM C645; 0.836 mm thick sheet steel; galvanized or galvalumed finish; C-Shape with 32 mm wide flange, complete with serrated faces and knock-outs for electrical fitments; depths as indicated on Drawings.
- .3 Shaft Wall Metal Studs: To ASTM C645; 0.836 mm thick sheet steel; galvanized or galvalumed finish; CH- and E-Shapes, complete with serrated faces and knock-outs for electrical fitments; depths as indicated on Drawings.
- .4 Metal Floor and Ceiling Tracks: To ASTM C645; 0.455 mm thick sheet steel; galvanized or galvalumed finish; U-Shape with 32 mm wide flanges; depths as indicated on Drawings.
- .5 Heavy Duty and Shaft Wall Metal Floor and Ceiling Tracks: To ASTM C645; 0.836 mm thick sheet steel; galvanized or galvalumed finish; U-Shape with 32 mm wide flanges; depths as indicated on Drawings.
- .6 Metal Ceiling Deflection Track: To ASTM C645; 0.455 mm thick sheet steel; galvanized or galvalumed finish; U-Shape with long legs, designed to accommodate structural deflections; depths as indicated on Drawings.
- .7 Furring: To ASTM C645; 0.455 mm thick sheet steel; galvanized or galvalumed finish; and as described below:
 - .1 C-Shaped Furring Channels: 13 mm wide flange, 19 mm deep unless noted otherwise on Drawings.
 - .2 Hat-Shaped Furring Channels: 13 mm wide flange, 22 mm deep unless noted otherwise on Drawings.
 - .3 Z-Shaped Furring: With slotted or non-slotted web, 32 mm face flange, 22 mm wall attachment flange; depth as indicated on Drawings.
 - .4 Resilient Furring Channels: Designed to reduce sound transmission; 13 mm deep unless noted otherwise on Drawings.
- .8 Carrying Channels: To ASTM C754; 1.37 mm thick cold-formed steel with galvanized or galvalumed finish; having minimum yield strength of 228 MPa; C-Shape with 13 mm flange width, 38 mm deep unless noted otherwise on Drawings.
- .9 Furring Brackets: 0.79 mm thick sheet steel; galvanized or galvalumed finish; adjustable, with corrugated-edge.

- .10 Flat Strap and Backing Plates: 0.455 mm thick sheet steel; galvanized or galvalumed finish; lengths and widths as indicated on Drawings.
- .11 Channel Bridging: 0.455 mm thick sheet steel; galvanized or galvalumed finish; 13 mm wide flange, 19 mm deep unless noted otherwise on Drawings.
- .12 Hanger Wire: To ASTM A641/A641M; zinc-coated, soft-annealed, 3.77 mm OD steel wire.
- .13 Tie Wire: To ASTM A641/A641M; zinc-coated, soft-annealed, 1.21 mm OD steel wire.

2.5 BOARDS

- .1 Moisture/Mould Resistant Gypsum Wall Board (GB-MR-1): To ASTM C1396/C1396M; 12.7 mm thick gypsum panel with water- and mould-resistant gypsum core and paper facers on both sides, with tapered edges; eg. Sheetrock Brand Ultralight Panels Mold Tough by CGC Inc.
- .2 Moisture/Mould Resistant Gypsum Wall Board (GB-MR-2): To ASTM C1396/C1396M, Type X; 15.9 mm thick gypsum panel with water- and mould-resistant gypsum core and paper facers on both sides, with tapered edges; eg. Sheetrock Brand Mold Tough Panels FireCode X by CGC Inc.
- .3 Fire-Rated Gypsum Board (GB-FR): To ASTM C1396/C1396M, Type C; fire-rated gypsum panel with water- and mould-resistant gypsum core and paper facers on both sides, and tapered edges, ULC labelled; thicknesses as indicated on Drawings; eg. Sheetrock Brand Mold Tough Panels FireCode C by CGC Inc.
- .4 Abuse-Resistant Gypsum Board (GB-AR): To ASTM C1629/C1629M, Type X; Level II - Mild to Moderate Duty; 15.9 mm thick gypsum abuse-resistant panel with water- and mould-resistant gypsum core and paper facers on both sides, and tapered long edges and square ends; eg. Sheetrock Brand Panels Mold Tough AR FireCode X by CGC Inc.
- .5 Gypsum Shaft Liner Board (GB-SL): To ASTM C1658/C1658M, Type X; 25 mm thick silicone-treated gypsum core, with coated glass mat facers both sides, and double bevelled edges; eg. Sheetrock Brand Glass-Mat Liner Panels by CGC Inc.
- .6 Gypsum Ceiling Board (GB-CLG): To ASTM C1396/C1396M; 12.7 mm thick gypsum core with paper facers on both sides, and eased edges; maximum 6.5 kg/m² weight; eg. Sheetrock Brand Ultralight Interior Ceiling Board Sag-Resistant by CGC Inc.

2.6 ACCESSORIES

- .1 Foam Gasket: 3.2 mm thick adhesive-backed, closed-cell vinyl foam strips that allow fastener penetration without foam displacement; width to suit track depth.
- .2 Corner Beads, Casing Beads, Control Joints, and Edge Trim: To ASTM C1047; metal type.
- .3 Reveals and Trim Reglets: Extruded aluminum profiles; as indicated on Drawings.
- .4 Nail Fasteners: To ASTM C514; galvanized steel.
- .5 Steel Drill Screws: To ASTM C954; galvanized steel.
- .6 Self-Tapping Screws: To ASTM C1002, Type S, Fine Thread; galvanized steel.
- .7 Adhesive: To CAN/CGSB-71.25-M.
- .8 Joint Tape: Fiberglass joint tape, 50 mm wide, self-adhering type; eg. Mould Resistant Fiberglass Drywall Tape by CGC Inc.
- .9 Joint Compound: Ready-mixed drying type drywall compound, to ASTM C475/C475M; eg. Synko Brand Classic All Purpose Drywall Compound by CGC Inc.

- .10 Acoustic Insulation: Mineral fibre acoustical batt insulation, as specified in Section 09 81 00.
 - .11 Acoustic Sealant: Interior general purpose sealant, Type SEAL-INT-GP as specified in Section 07 92 00.
 - .12 Water: Potable.
- 2.7 MIXING
- .1 Thoroughly mix joint and skim coat materials to homogeneous mixture with trowelling consistency.
- 2.8 FINISHES
- .1 Galvanized Coating on Metal Framing Components: To ASTM A653/A653M, Coating Designation Z120; hot dipped zinc alloy coating.
 - .2 Galvalumed Coating on Metal Framing Components: To ASTM A792/A792M, Coating Designation AZM150; hot dipped aluminum-zinc alloy coating.
- 3 Execution
- 3.1 PREPARATION
- .1 Suspended Assemblies: Coordinate installation of suspension systems with installation of overhead structure.
 - .1 Ensure inserts and other provisions for anchorages to building structure have been installed to receive hangers at required spacings.
 - .2 Supply concrete inserts and other devices to other related Sections for installation in advance.
 - .2 Before sprayed fireproofing is applied, attach offset anchor plates or ceiling track to surfaces designated to receive sprayed fireproofing. Where offset anchor plates are required, Provide continuous plates fastened to structure at maximum 600 mm OC.
 - .3 Once sprayed fireproofing has been applied, remove them only to the extent necessary for installation of non-load bearing steel framing. Do not reduce thickness for sprayed fireproofing below that required for fire-resistance ratings indicated. Protect adjacent sprayed fireproofing from damage.
- 3.2 METAL WALL FRAMING
- .1 Install metal wall framing to ASTM C754 and CGC Gypsum Construction Handbook.
 - .2 Where metal framing is installed directly against exterior masonry walls or dissimilar metals at exterior walls, Provide foam gasket between metal framing and exterior wall.
 - .3 Install studs with flanges pointing in same direction.
 - .4 Space metal stud framing in straight walls and partitions at maximum 400 mm OC.
 - .5 Install track floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings, except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts penetrating partitions of structure.
 - .6 Where framing extends to overhead structural supports, Provide deflection track to create a slip-type head joints to produce joints at tops of framing system that prevent axial loading of finished assemblies due to deflection of structure.

- .7 Screw vertical studs at door opening jambs to jamb anchor clips at door frames. Install track section for cripple studs at head and secure to jamb studs.
 - .1 Provide two studs at each jamb.
 - .2 Provide cripple studs at head adjacent to each jamb stud, with minimum 13 mm clearance from jamb stud to allow for installation of control joint in finished assembly.
- .8 Provide framing below sills of openings to match framing required above opening heads.
- .9 Fire-Resistance-Rated Partitions: Install framing to comply with fire-resistance-rated assembly indicated. Support closures and make partitions continuous from floor to underside of solid structure.
- .10 Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.
- .11 Curved Walls and Partitions: Conform to GA-226, and as follows:
 - .1 Bend track to uniform curve and locate straight lengths so they are tangent to arcs.
 - .2 Begin and end each arc with a stud, and space intermediate studs equally along arcs at maximum 150 mm OC.
 - .3 On straight lengths of not less than two studs at ends of arcs, place studs at maximum 150 mm OC.
- .12 Attach furring directly to concrete or masonry using stub nails, screws designed for masonry attachment, or power-driven fasteners; spaced at 610 mm OC.
- .13 Z-Furring Members:
 - .1 Erect insulation vertically and hold in place with Z-furring members spaced at 610 mm OC.
 - .2 Except at exterior corners, securely attach narrow flanges of furring members to wall with concrete stub nails, screws designed for masonry attachment, or power-driven fasteners spaced at 610 mm OC.
 - .3 At exterior corners, attach wide flange of furring members to wall with short flange extending beyond corner; on adjacent wall surface, screw-attach short flange of furring channel to web of attached channel.
 - .4 At interior corners, space second member no more than 305 mm from corner and butt insulation to fit.
- .14 Unless indicated otherwise, Provide supplementary framing and furring to conceal pipes, conduit and ducts.
- .15 Provide supplementary framing and blocking necessary to support fixtures, fitments, equipment and furnishings being secured to gypsum board assemblies. Maintain fire rating of wall assembly where applicable.
- .16 Install bracing at terminations in assemblies.
- .17 Do not bridge building control joints and expansion joints with non-load bearing steel framing members. Frame both sides of joints independently.
- .18 Installation Tolerances: Install framing members so fastening surfaces vary not more than 3 mm from plane formed by faces of adjacent framing members.

3.3 SUSPENDED CEILING FRAMING

- .1 Install ceiling framing to ASTM C754 and CISCA installation standards.
- .2 Isolate suspension system from building structure. Prevent transfer of loading imposed by structural movement.
- .3 Install hangers plumb and free from contact with insulation or other objects within ceiling plenum.

- .4 Size supplemental suspension members and hangers to support ceiling loads within established performance limits.
- .5 Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or similar devices.
- .6 Secure wire hangers by looping and wire tying, either directly to structure or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate; and in a manner that will not cause hangers to fail or deteriorate.
- .7 Do not attach hangers to steel roof decking, or to rolled-in hanger tabs of composite steel floor decking.
- .8 Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
- .9 Do not connect or suspend steel framing from ducts, pipes, or conduit.
- .10 For fire-resistance-rated assemblies, wire tie furring channels to supports.
- .11 Installation Tolerances: Level to within 3 mm in 3 600 mm, measured lengthwise on each member that will receive finishes, and transversely between parallel members that will receive finishes.

3.4 ACOUSTICAL ACCESSORIES

- .1 Install resilient channels at maximum 600 mm OC.
- .2 Place acoustical insulation in partitions tight within spaces, around cut openings, behind and around electrical and mechanical items within or behind partitions, and tight to items passing through partitions.
- .3 Install acoustical sealant within designated sound-rated partitions.

3.5 BOARD INSTALLATION

- .1 Install board Products to ASTM C840 and CGC Gypsum Construction Handbook.
- .2 Install gypsum ceiling board perpendicular to supports.
- .3 Screw fasten boards to furring or framing.
- .4 Install abuse-resistant gypsum board on heavy duty metal stud and track framing.
- .5 Install shaft liner gypsum board on shaft wall metal stud and track framing.
- .6 Double Layer Applications: Place first layer perpendicular to framing or furring members. Place second layer perpendicular to first layer.
- .7 Place corner beads at external corners. Place edge trim where gypsum board abuts dissimilar materials. Fasten with nail attachment, unless specified otherwise.
- .8 Provide bulkheads where changes of ceiling or height occur.
- .9 Install access panels when and where directed by affected Subcontractors. Refer to Section 08 31 00.

3.6 BOARD FINISHING

- .1 Tape, fill, and sand exposed joints, edges, and corners to a smooth surface.

- .2 Leave surfaces smooth, even, plumb, and true.
- .3 Leave surfaces ready to receive final finishes specified in other Sections.
- .4 Except as specified below, finish gypsum board to GA-214, Level 4.
 - .1 Provide Level 1 finish on concealed surfaces, such as in plenum spaces above ceilings, and behind casework.
 - .2 Provide Level 5 finish on glass mat-faced gypsum surfaces designated to receive a painted finish.

3.7 CONTROL JOINTS

- .1 Provide control joints where indicated on Drawings, and where:
 - .1 Ceiling, partition or furring abuts a structural element,
 - .2 Ceiling, partition or furring abuts dissimilar construction,
 - .3 Construction changes within plane of the partition or ceiling,
 - .4 Partition or furring run exceeds 9 000 mm,
 - .5 Ceiling dimensions exceed 15 000 mm in either direction,
 - .6 Wings of "L-", "U-" and "T"-shaped ceiling areas are joined, and
 - .7 Expansion or control joints occur in the structural elements of the building.
- .2 Break continuity of gypsum board and framing system at control joints.
- .3 Provide continuous control joint profile.

3.8 RELIEF JOINTS

- .1 Provide relief joints where indicated on Drawings and where gypsum board assemblies abut dissimilar construction.
- .2 Stop gypsum board 6 mm from abutting construction at dissimilar building elements, unless indicated otherwise.
- .3 Provide thermal break where gypsum board comes into contact with frames. Adhere self-adhering tape to casing bead and compress during installation of gypsum board.
- .4 Provide reveal mouldings where gypsum board ceilings meet curved wall surfaces, and where indicated on Drawings.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 09 21 16 - Gypsum Board Assemblies.
- .2 Section 09 81 00 - Acoustic Insulation.
- .3 Section 26 50 00 - Lighting.

1.2 REFERENCES

- .1 ASTM A123/A123M-24: Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- .2 ASTM A153/A153M-23: Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
- .3 ASTM A641/A641M-19: Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire.
- .4 ASTM C635/C635M-17: Standard Specification for Manufacture, Performance, and Testing of Metal Suspension Systems for Acoustical Tile and Lay-in Panel Ceilings.
- .5 ASTM C636/C636M-19(2025): Standard Practice for Installation of Metal Ceiling Suspension Systems for Acoustical Tile and Lay-In Panels.
- .6 ASTM E84-26a: Standard Test Method for Surface Burning Characteristics of Building Materials.
- .7 ASTM E1264-23: Standard Classification for Acoustical Ceiling Products.
- .8 CISCA Ceiling Systems Handbook, 2012 Edition.
- .9 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .10 ULC List of Equipment and Materials.

1.3 SAMPLES

- .1 Submit samples as specified in Section 01 33 00.
- .2 Verification Samples: Duplicate 140 x 290 mm size sample of each specified acoustic lay-in tile, indicating texture, pattern, colour, and edge profile.

1.4 EXTRA STOCK MATERIALS

- .1 Supply extra stock materials as specified in Section 01 78 00.
- .2 Extra Stock Materials: Minimum two full bundles for each lay-in tile ceiling Product, colour, and pattern; clearly marked to identify:
 - .1 Manufacturer's name,
 - .2 Product's name,
 - .3 Product colour and pattern.
- .3 Store bundles in original undamaged packages, in a warm, dry area.

1.5 QUALIFICATIONS

- .1 Installers: A firm specializing in installing suspended ceiling grid and lay-in tile ceiling systems, having minimum three years documented experience.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver Products undamaged original containers.
- .3 Store Products in warm, dry area.

1.7 EXISTING CONDITIONS

- .1 Where existing ceilings require patching, use existing matching acoustic tiles removed from other areas.
- .2 Protect material designated for re-use.
- .3 Arrange for Consultant to inspect and accept existing materials designated for reuse prior to installation.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 Armstrong World Industries.
 - .2 CertainTeed Canada, Inc.
 - .3 CGC Inc.
 - .4 Odenwald Faserplattenwerk GmbH (OWA).
 - .5 Rockfon.
- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 MATERIALS

- .1 Acoustic Ceiling Tile (ACT-1): To ASTM E1264, Type A, Form A1.2, Pattern D; wet-formed mineral fiber non-sagging lay-in tile, complete with anti-mould and mildew treatment, and sag resisting treatment; as follows:
 - .1 Size: 610 x 1 220 mm size.
 - .2 Thickness: 19 mm.
 - .3 Pattern: Medium texture, fissured.
 - .4 Edge: Square.
 - .5 Weight: 6.74 kg/m².
 - .6 Finish: Factory-applied latex paint, White colour.
 - .7 Fire Resistance (CAN/ULC-S102): Class A.
 - .8 Noise Reduction Coefficient: NRC = 0.70.
 - .9 Light Reflectance: LR = 0.85.
 - .10 Manufacturer and Product Name: eg. School Zone Fine Fissured, Item No. 1714 by Armstrong World Industries.
- .2 Suspended Ceiling Grid: To ASTM C635/C635M, Class HD and ICC-ESR-1308; commercial quality, cold rolled steel, non-fire rated; main tees, cross tees and grid adapters with exposed 24 mm T-shape, 43 mm high; die cut and interlocking components; baked enamel finish; eg. Prelude XL by Armstrong World Industries.
- .3 Accessories: Stabilizer bars, clips, splices, edge mouldings, and hold down clips required for suspended grid system; same material and finish as suspended grid.
- .4 Support Channels and Hangers: Galvanized steel, to rigidly secure ceiling system with maximum deflection of L/360.
- .5 Hanger Wire: To ASTM A641/A641M; zinc-coated, soft-annealed, 3.77 mm OD steel wire.

- .6 Tie Wire: To ASTM A641/A641M; zinc-coated, soft-annealed, 1.21 mm OD steel wire.

2.3 FINISHES

- .1 Galvanized Coating on Steel Components: To ASTM A123/A123M, Coating Grade 35; hot dipped zinc alloy coating.
- .2 Galvanized Coating on Steel Hardware: To ASTM A153/A153M, Classes B3, C or D; hot dipped zinc alloy coating.
- .3 Baked Enamel Coating on Ceiling Grid and Trim: One coat of zinc oxide primer sprayed and baked followed by two coats of semi-gloss enamel sprayed and baked; White colour.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify layout of hangers will not interfere with other parts of the Work.
- .3 Verify ducts, pipes, fittings, and other penetrations have been properly installed.

3.2 SUSPENDED CEILING GRID

- .1 Install suspended ceiling grid system to ASTM C636/C636M, and CISCA installation standards.
- .2 Hang ceiling grid directly from structural elements, independent of walls, columns, metal deck, ducts, pipe fittings, and conduit. Provide additional support channels and hangers as required.
- .3 Space hangers at maximum 1 220 mm OC along supporting grillage, and not more than 150 mm OC from ends. Do not place hangers in front of access panels.
- .4 Where ducts or other equipment prevent regular spacing of hangers, reinforce nearest affected hangers to span extra distance.
- .5 Install additional hangers and reinforcing to accommodate loads being carried.
- .6 Provide suspension hanger at each corner of suspended fixtures, and at maximum 610 mm OC around perimeter of fixture.
- .7 Locate ceiling grid system on room axis leaving equal border units according to reflected ceiling plan.
- .8 Install main tees suspended at maximum 1 220 mm OC and maximum 600 mm from wall.
- .9 Install cross tees and grid adapters perpendicular to main tees, and interlock with main tees.
- .10 Frame around fixtures and openings.
- .11 Install edge moulding at intersection of ceiling and vertical surfaces.
- .12 Form expansion joints as detailed. Form to accommodate plus or minus 25 mm movement. Maintain visual closure.

3.3 LAY-IN CEILING TILE

- .1 Fit lay-in ceiling tiles in place, free from damaged edges.
- .2 Neatly cut lay-in ceiling tiles to accommodate necessary penetrations.

- .3 Cut and rabbet lay-in ceiling tiles at border areas and vertical surfaces.
- .4 Lay directional patterned units one way, with pattern parallel to longest room axis. Fit border neatly against abutting surfaces.
- .5 Install hold-down clips to retain lay-in ceiling tiles tight to grid system within 6 000 mm of exterior doors.

3.4 TOLERANCES

- .1 Variation from Flat and Level Surface: ≤ 3 mm in 3 000 mm.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 04 00 00 - Masonry.
 - .2 Section 09 21 16 - Gypsum Board Assemblies.
 - .3 Section 09 65 19 - Resilient Tile Flooring.
 - .4 Section 09 65 66 - Resilient Athletic Flooring.
 - .5 Section 09 68 13 - Tile Carpeting.
- 1.2 REFERENCES
 - .1 ASTM F1861-21(2025): Standard Specification for Resilient Wall Base.
- 1.3 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Selection Samples: Duplicate 100 mm long sample sets, illustrating manufacturer's complete line of available colour selections.
- 1.4 CLOSEOUT SUBMITTALS
 - .1 Submit closeout submittals as specified in Section 01 78 00.
 - .2 Maintenance Data: Manufacturer's standard maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.
- 1.5 EXTRA STOCK MATERIALS
 - .1 Supply extra stock materials as specified in Section 01 78 00.
 - .2 Extra Stock Materials: Three percent or 6 m², whichever is greater, of each Product, colour, and pattern; clearly marked to identify:
 - .1 Manufacturer's name,
 - .2 Product's name, and
 - .3 Product colour and pattern.
 - .3 Package Products neatly in original containers, to prevent damage.
- 1.6 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Deliver and store Products undamaged in original wrapping or cartons.
 - .3 Store Products for minimum three days prior to installation in a warm, dry room; stacked not more than four boxes high.
- 1.7 AMBIENT CONDITIONS
 - .1 Maintain ambient air temperature of 20 degrees C three days prior to, during, and 48 hours after installation of flooring materials.
 - .2 Maintain ambient air relative humidity between 35 percent and 55 percent RH.
 - .3 Do not install Products in conditions of high humidity or where exposed to cold drafts.
 - .4 In hot weather, protect Products from direct sunlight.

- .5 Provide adequate ventilation.
- 2 Products
- 2.1 MANUFACTURERS
- .1 Manufacturers having Product considered acceptable for use:
 - .1 Armstrong World Industries.
 - .2 Roppe Corporation.
 - .3 Tarkett Johnsonite.
 - .2 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 MATERIALS
- .1 Resilient Base (RB): To ASTM F1861, Type TP, Group 1 - Solid, Style B - Cove; 3.2 mm thick thermoplastic rubber, 152 mm high; top set; complete with pre-moulded end stops and external corners; colours as selected by Consultant.
 - .2 Resilient Transition Strips (RTS): Thermoset vulcanized rubber, smooth, purpose made to accommodate wheeled traffic and prevent tripping; tapered designs to suit nature of transition; colours as selected by Consultant.
 - .3 Adhesive: Non-flammable, solvent free contact adhesive, neoprene water-based formulation, Off-white colour; eg. Johnsonite #946 Premium Contact Adhesive by Tarkett Johnsonite.
 - .4 Substrate Filler: Premixed latex filler, White colour.
 - .5 Primers: Acrylic, waterproof type; as recommended by manufacturer.
 - .6 Sealers and Wax: As recommended by manufacturer.
- 3 Execution
- 3.1 EXAMINATION
- .1 Refer to Section 01 71 00.
 - .2 Verify surfaces are dry, true, even, and smooth.
 - .3 Verify surfaces are free of gaps, holes, and depressions.
 - .4 Verify surfaces are free of paint, grease, and oil.
- 3.2 PREPARATION
- .1 Clean substrate to remove deleterious matter which would impair adhesion of Products.
 - .2 Prepare substrate to a smooth and flat surface, as follows:
 - .1 Remove ridges and bumps by grinding or other means.
 - .2 Fill low spots, cracks, joints, holes and other defects with filler.
 - .3 Apply, trowel and float filler to leave smooth, flat, hard surface.
 - .4 Prohibit traffic until filler is cured.
 - .5 Vacuum clean substrate.
 - .3 Prime substrates to ensure proper adhesion of Products.

3.3 INSTALLATION

- .1 Install Products on solid backing.
- .2 Bond Products tight to surfaces.
- .3 Mitre internal corners.
- .4 Use pre-moulded units at exposed ends and external corners.
- .5 Scribe and fit base to door frames and other interruptions.

3.4 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Clean, seal, and wax installed Products.

3.5 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect completed installation with suitable and durable materials.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 09 65 13 - Resilient Base and Accessories.
- .2 Section 09 65 66 - Resilient Athletic Flooring.
- .3 Section 09 66 13 - Portland Cement Terrazzo Flooring.
- .4 Section 09 68 13 - Tile Carpeting.

1.2 REFERENCES

- .1 ASTM F710-22: Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring.
- .2 ASTM F1700-25: Standard Specification for Solid Vinyl Floor in Modular Format such as Tile(s) or Plank(s).
- .3 ASTM F1869-23: Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride.
- .4 ASTM F2170-19a: Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes.
- .5 ASTM F2678-16(2021): Standard Practice for Preparing Panel Underlayments, Thick Poured Gypsum Concrete Underlayments, Thick Poured Lightweight Cellular Concrete Underlayments, and Concrete Subfloors with Underlayment Patching Compounds to Receive Resilient Flooring.
- .6 ASTM F3191-23: Standard Practice for Field Determination of Substrate Water Absorption (Porosity) for Substrates to Receive Resilient Flooring.
- .7 ASTM F3441-24a: Standard Guide for Measurement of pH Involving Resilient Flooring Installations.

1.3 SAMPLES

- .1 Submit samples as specified in Section 01 33 00.
- .2 Selection Samples: Duplicate 300 x 300 mm size samples of each specified Product, illustrating manufacturer's complete line of available colours and patterns.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit closeout submittals as specified in Section 01 78 00.
- .2 Maintenance Data: Manufacturer's standard maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.

1.5 EXTRA STOCK MATERIALS

- .1 Supply extra stock materials as specified in Section 01 78 00.
- .2 Extra Stock Materials: Three percent or 6 m², whichever is greater, of each resilient flooring Product, colour, and pattern; clearly marked to identify:
 - .1 Manufacturer's name,
 - .2 Product's name, and
 - .3 Product colour and pattern.
- .3 Package tile products neatly in original containers, to prevent damage.

1.6 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver and store Products undamaged in original wrapping or cartons.
- .3 Store Products for minimum three days prior to installation in a warm, dry room.
- .4 Store Products stacked not more than four boxes high.

1.7 AMBIENT CONDITIONS

- .1 Maintain ambient air temperature of 20 degrees C three days prior to, during, and 48 hours after installation.
- .2 Maintain ambient air relative humidity between 35 percent and 55 percent RH.
- .3 Do not lay flooring in conditions of high humidity, or where exposed to cold drafts.
- .4 In hot weather, protect flooring from direct sunlight.
- .5 Provide adequate ventilation.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers of luxury vinyl tile having Product considered acceptable for use:
 - .1 Gerflor.
- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 MATERIALS

- .1 Luxury Vinyl Tile (LVT): To ASTM F1700, Class III, Type B, Embossed Surface; heterogeneous vinyl tile, as follows:
 - .1 Total Thickness: 2.5 mm.
 - .2 Wear Layer Thickness: 0.7 mm.
 - .3 Tile Size: 208 x 1 243 mm.
 - .4 Colours and Patterns: Four colours, as selected by Consultant.
 - .5 Manufacturer and Product Name: Creation 70 by Gerflor.
- .2 Adhesive: Moisture-curing, one-component, silane-modified, hybrid-polymer adhesive; Ultrabond ECO MS 4 LVT by Mapei.
- .3 Cementitious Underlayment Patching Compound: Self-drying, hydraulic cement-based underlayment, having a trowel-applied consistency; mould- and mildew-resistant; capable of achieving a true feather edge; zero VOC content; eg. Feather Finish by Ardex Americas.
- .4 Primers: Acrylic, waterproof type; as recommended by flooring manufacturer.
- .5 Sealers and Wax: As recommended by flooring manufacturer.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify substrates are dry, true, even, and smooth.

- .3 Verify substrates are free of gaps, holes, and depressions.
- .4 Verify substrates are free of paint, grease, and oil.
- .5 Verify concrete slabs have cured for minimum 28 days.
- .6 Verify concrete slabs have pH level between 7 and 9, as determined through ASTM F3441.
- .7 Conduct moisture vapour emission rate tests on concrete slabs-on-fill to ASTM F1869. Do not proceed with installation until tests indicate $MVER \leq 11.3$ kg per 93 m² for 24 hours.
- .8 Conduct relative humidity tests on concrete slabs to ASTM F2170. Do not proceed with installation until tests indicate $RH \leq 100$ percent.
- .9 Determine absorptive nature of substrates by conducting porosity tests to ASTM F3191.

3.2 PREPARATION

- .1 Prepare substrate as recommended by manufacturer for absorptive conditions determined by porosity test. Conform to ASTM F710.
- .2 Prepare cementitious underlayment patching compounds and surrounding slab surfaces to ASTM F2678.
- .3 Clean substrate to remove deleterious matter that would impair subsequent installation.
- .4 Prime substrates to ensure proper adhesion of Products.

3.3 INSTALLATION

- .1 Install Products with joints and seams parallel to building lines to produce symmetrical tile patterns.
- .2 Spread only enough adhesive to permit installation of Products before initial set.
- .3 Set Products in place, and press with heavy roller to attain full adhesion.
- .4 Provide perimeter tile of similar size within any given area.
- .5 Provide accent tiles, feature strips, and inserts where indicated on Drawings.
- .6 Lay flooring continuously from wall to wall in each area, including beneath casework.
- .7 Where adjacent floor finish is dissimilar, terminate resilient tile flooring at centre line of door openings.
- .8 Provide transition strip along junction of dissimilar flooring materials.
- .9 Scribe flooring to walls, columns, floor outlets, and other appurtenances to produce tight joints.

3.4 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Clean, seal, and wax installed Products.

3.5 PROTECTION

- .1 Refer to Section 01 76 00.

- .2 Protect completed installation with suitable and durable protective coverings, or by keeping traffic off floor.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 09 65 13 - Resilient Base and Accessories.
- .2 Section 09 65 19 - Resilient Tile Flooring.
- .3 Section 09 66 13 - Portland Cement Terrazzo Flooring.
- .4 Section 09 68 13 - Tile Carpeting.

1.2 REFERENCES

- .1 ASTM F710-22: Standard Practice for Preparing Concrete Floors to Receive Resilient Flooring.
- .2 ASTM F1303-04(2021): Standard Specification for Sheet Vinyl Floor Covering with Backing.
- .3 ASTM F1516-23: Standard Practice for Sealing Seams of Resilient Flooring Products by the Heat Weld Method (when Recommended).
- .4 ASTM F1869-23: Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride.
- .5 ASTM F2170-19a: Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes.
- .6 ASTM F2772-11(2019): Standard Specification for Athletic Performance Properties of Indoor Sports Floor Systems.
- .7 ASTM F2678-16(2021): Standard Practice for Preparing Panel Underlayments, Thick Poured Gypsum Concrete Underlayments, Thick Poured Lightweight Cellular Concrete Underlayments, and Concrete Subfloors with Underlayment Patching Compounds to Receive Resilient Flooring.
- .8 ASTM F3191-23: Standard Practice for Field Determination of Substrate Water Absorption (Porosity) for Substrates to Receive Resilient Flooring.

1.3 SHOP DRAWINGS

- .1 Submit Shop Drawings as specified in Section 01 33 00.
- .2 Shop Drawings: Project-specific drawings, illustrating game line layout, locations and sizes of special graphics, floor inserts, and equipment anchors. Note colours and thicknesses of games lines and graphic inserts.

1.4 CLOSEOUT SUBMITTALS

- .1 Submit closeout submittals as specified in Section 01 78 00.
- .2 Maintenance Data: Manufacturer's standard maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.

1.5 EXTRA STOCK MATERIALS

- .1 Supply extra stock materials as specified in Section 01 78 00.
- .2 Extra Stock Materials: One percent of each resilient athletic flooring Product, colour, and pattern; clearly marked to identify:
 - .1 Manufacturer's name,
 - .2 Product's name, and
 - .3 Product colour and pattern.

- .3 Supply roll goods in full width rolls.
- .4 Store roll goods in upright position, with roll wrapped in a protective cover to prevent damage.
- 1.6 QUALIFICATIONS
 - .1 Installer: A firm specializing in installing resilient athletic flooring, approved by flooring manufacturer, and having minimum two years documented experience indicating successful completion of not less than 5 similar installations.
- 1.7 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Deliver and store Products undamaged in original wrapping or cartons, with manufacturer's labels and seals intact.
 - .3 Store Products in up-right position in a warm dry room for minimum three days prior to installation.
- 1.8 AMBIENT CONDITIONS
 - .1 Maintain ambient air temperature between 18 degrees C and 30 degrees C.
 - .2 Do not lay Products in conditions of high humidity or where exposed to cold drafts.
 - .3 In hot weather, protect flooring from direct sunlight.
 - .4 Provide adequate ventilation.
- 1.9 WARRANTY
 - .1 Submit extended warranties in accordance with General Conditions of the Contract.
 - .2 Installer's Extended Warranty: For a period of two years, covering against punctures, tears, delamination, and excessive wear.
 - .3 Manufacturer's Extended Warranty: A non-prorated manufacturer's extended warranty, covering against the following:
 - .1 Product defects for 10 years.
 - .2 Wear through wear layer (with surface as defined in ASTM F1303) for 15 years.
- 2 Products
- 2.1 MANUFACTURERS
 - .1 Manufacturers having Product considered acceptable for use:
 - .1 Gerflor Sports Flooring.
 - .2 Tarkett Sports.
 - .2 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 DESCRIPTION
 - .1 Resilient Athletic Flooring: Multi-purpose sport vinyl surface, comprised of a vinyl foam backing, reinforced fiberglass mesh and a smooth faced PVC wear layer; complete with game lines and graphics.

2.3 PERFORMANCE CRITERIA

- .1 Resilient Athletic Flooring: To ASTM F2772, as follows:
 - .1 Shock Absorption: 22-33 percent.
 - .2 Vertical Deformation: \leq 3.5 mm.
 - .3 Ball Bounce: \geq 90 percent.
 - .4 Sliding Coefficient: 80 -110.

2.4 MATERIALS

- .1 Resilient Athletic Flooring (RAF): To ASTM F2772, Class 2; 6.5 mm overall thickness, comprised of 2.0 mm thick homogenous wear-layer and closed-cell foam cushioned backing, reinforced with fiber glass mesh interlayer; integral fungistatic and bacteriostatic treatment; treated with factory-applied photoreticulated, UV cured polyurethane, anti-dirt treatment; eg. Omnisports Multiflex by Tarkett Sports, Pure Maple pattern and colour, complete with line work and graphic inserts as indicated on Drawings.
- .2 Welding Rods: 4 mm OD vinyl, solid colour; colour matched to flooring.
- .3 Levelling Compound: Approved by manufacturer to correct minor subfloor deviations.
- .4 Adhesive: Two-part, solvent free adhesive; Multi-Poxy by Tarkett Sports.
- .5 Seaming Tape: eg. Tarkotape by Tarkett Sports.
- .6 Game Line Primer and Paint: As recommended by flooring manufacturer.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify concrete slab is adequately vapour sealed.
- .3 Verify adequate perimeter drainage has been installed.
- .4 Verify concrete slab is clean and dry.
- .5 Verify no curing compounds or sealers have been applied to concrete slab.
- .6 Verify variations in concrete slab do not exceed plus or minus 3 mm in 3 000 mm radius.
- .7 Verify concrete slabs have cured for minimum 28 days.
- .8 Verify concrete slabs have neutral alkalinity and have carbonized.
- .9 Conduct moisture vapour emission rate tests on concrete slabs-on-fill to ASTM F1869. Do not proceed with installation until tests indicate MVER \leq 6.8 kg per 93 m² for 24 hours.
- .10 Conduct relative humidity tests on concrete slabs to ASTM F2170. Do not proceed with flooring installation until tests indicate RH \leq 90 percent.
- .11 Determine absorptive nature of substrates by conducting porosity tests to ASTM F3191.

3.2 PREPARATION

- .1 Prepare substrate as recommended by manufacturer for absorptive conditions determined by porosity test. Conform to ASTM F710.
- .2 Prepare levelling compounds and surrounding concrete slab to ASTM F2678.
- .3 Fill cracks, grooves, voids, and construction joints with approved levelling compound.
- .4 Remove high spots on floor slab by grinding method.
- .5 Remove deleterious matter which would impair adhesion of flooring.
- .6 Broom clean substrate.

3.3 INSTALLATION

- .1 Install Product using loose laid, non-adhered method, similar to Tarkett GreenLay.
- .2 Minimize cross seams.
- .3 Terminate flooring at centerline of openings where adjacent floor finish or colour is dissimilar.
- .4 Cut neatly around penetrations.
- .5 Heat weld seams to ASTM F1516 using matching welding rods.
- .6 Lay out game lines and special graphics in accordance with accepted Shop Drawings.

3.4 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Restrict access to completed installation for 72 hours after completion of flooring.
- .3 Protect completed installation with suitable and durable protective coverings, or by keeping traffic off floor.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 07 92 00 - Joint Sealants.
 - .2 Section 09 65 13 - Resilient Base and Accessories.
 - .3 Section 09 65 19 - Resilient Tile Flooring.
 - .4 Section 09 65 66 - Resilient Athletic Flooring.
 - .5 Section 09 68 13 - Tile Carpeting.
- 1.2 REFERENCES
 - .1 ASTM A1064/A1064M-22: Standard Specification for Carbon-Steel Wire and Welded Wire Reinforcement, Plain and Deformed, for Concrete.
 - .2 CSA A3001:23: Cementitious Materials for Use in Concrete.
 - .3 TTMAC 09 66 00 Terrazzo Specification Guide - 2007.
- 1.3 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating divider strips, control joint strips, expansion joints, and termination strips.
- 1.4 SHOP DRAWINGS
 - .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, illustrating divider strips, control joints, and expansion joint layouts, details of adjacent components and special details.
- 1.5 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Selection Samples: Duplicate 300 x 300 mm size samples, illustrating colour, chip size and variation, mortar colour, and ground top surface of divider strip.
- 1.6 CLOSEOUT SUBMITTALS
 - .1 Submit closeout submittals as specified in Section 01 78 00.
 - .2 Maintenance Data: TTMAC Hard Surface Maintenance Guide, sufficient quantities for inclusion in operation and maintenance manual.
- 1.7 QUALIFICATIONS
 - .1 Applicator: A firm specializing in applying terrazzo flooring, having minimum 5 years documented experience and a member of TTMAC.
- 1.8 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Deliver, store and handle Products in a manner to avoid damage.
 - .3 Store Products in a clean, dry, heated location.

- .4 Condition Products to ambient temperatures for minimum 24 hours prior to installation.

1.9 AMBIENT CONDITIONS

- .1 Do not install wet mixed terrazzo when temperature is below 10 degrees C or above 32 degrees C.

2 Products

2.1 MATERIALS

- .1 Portland Cement: To CSA A3001, Type GU; white colour for topping mix, grey colour for underbed, modified to obtain a higher compressive strength of 19.3 MPa, obtained from single source.
- .2 Colour Pigments For Topping: Non-fading mineral type.
- .3 Sand: Sharp, coarse, clean, screened, free of deleterious material.
- .4 Water: Potable.
- .5 Surface Aggregate: Crushed marble, granite, or quartz, to match existing terrazzo.

2.2 ACCESSORIES

- .1 Welded Wire Reinforcement: To ASTM A1064/A1064M, flat sheets; 51 x 51 mm mesh size, 1.5 mm thick galvanized wire.
- .2 Divider Strips: 1.9 mm thick zinc brass top strip, zinc coated steel bottom strip, depth to match existing.
- .3 Control Joint Strips: Brass top strips, zinc coated steel bottom strip, neoprene filler strip between vertical strips; sizes to match existing.
- .4 Base Caps, Base Divider Strips, and Separator Strips: To match divider strips, with 13 mm projecting base.
- .5 Foam Filler: Closed cell urethane foam, capable of compression to 50 percent of its thickness with full recovery.
- .6 Slip Sheet: 0.15 mm thick polyethylene sheet.
- .7 Subfloor Filler: Latex type.

2.3 MIXES

- .1 Underbed: One part Portland cement to 4-1/2 parts sand by volume. Add water to produce low slump mix.
- .2 Floor and Base: Matrix and aggregate mix to match existing.

3 Execution

3.1 PREPARATION

- .1 Remove loose and unsound materials and clean thoroughly.
- .2 Apply appropriate bonding agent to substrate.

3.2 INSTALLATION

- .1 Install divider strips and control joint strips straight and level, in locations indicated.
- .2 Place terrazzo topping mix over prepared substrate to thickness required to match existing. Conform to appropriate TTMAC Detail.
- .3 Allow terrazzo to cure.
- .4 After curing, grind patches using 80 grit or finer stones until area has similar finish to surrounding floor surface.

3.3 CLEANING

- .1 Scrub and clean terrazzo surfaces with cleaner to requirements of manufacturer's instructions.
- .2 Allow surface to dry.
- .3 Apply appropriate sealer to terrazzo surface.

3.4 SCHEDULE

- .1 Portland Cement Terrazzo Bonded to Concrete Slab - Interior Only: TTMAC Detail 410F.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 09 65 13 - Resilient Base and Accessories.
 - .2 Section 09 65 19 - Resilient Tile Flooring.
 - .3 Section 09 65 66 - Resilient Athletic Flooring.
 - .4 Section 09 66 13 - Portland Cement Terrazzo Flooring.
- 1.2 REFERENCES
 - .1 ASTM F1869-23: Standard Test Method for Measuring Moisture Vapor Emission Rate of Concrete Subfloor Using Anhydrous Calcium Chloride.
 - .2 ASTM F2170-19a: Standard Test Method for Determining Relative Humidity in Concrete Floor Slabs Using in situ Probes.
 - .3 ASTM F3191-23: Standard Practice for Field Determination of Substrate Water Absorption (Porosity) for Substrates to Receive Resilient Flooring.
 - .4 ASTM F3441-24a: Standard Guide for Measurement of pH Below Resilient Flooring Installations.
 - .5 CAN/CGSB-71.28-M88: Adhesive, for Direct Glue-Down Carpet Installation.
 - .6 CRI 104-2002: Standard for Installation Specification of Commercial Carpet.
- 1.3 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating physical and performance characteristics; sizes, patterns, colours available, and method of installation.
- 1.4 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Selection Samples: Duplicate complete sets, 150 x 150 mm in size; illustrating colour and pattern selection for each specified carpet tile.
- 1.5 CLOSEOUT SUBMITTALS
 - .1 Submit closeout submittals as specified in Section 01 78 00.
 - .2 Maintenance Data: Manufacturer's standard maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.
- 1.6 EXTRA STOCK MATERIALS
 - .1 Supply extra stock materials as specified in Section 01 78 00.
 - .2 Extra Stock Materials: Minimum 4 percent for each carpet tile flooring Product, colour, and pattern; clearly marked to identify:
 - .1 Manufacturer's name,
 - .2 Product's name, and
 - .3 Product colour and pattern.
 - .3 Package Products neatly in original containers, to prevent damage.

1.7 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver Products in original packaging, with each package having its register number properly marked on each bale.
- .3 Protect Products from damage, dirt, stains, and moisture.

1.8 AMBIENT CONDITIONS

- .1 Maintain ambient air temperature at 21 degrees C for 48 hours before, during, and after installation.
- .2 Maintain substrate temperature at 10 degrees C.

1.9 WARRANTY

- .1 Submit extended warranties in accordance with General Conditions of the Contract.
- .2 Installer's Extended Warranty: For a period of two years, covering against loose fitting, breaking or unraveling of seams, breaking away from sub-base, and failure of materials or workmanship which proves detrimental to either appearance or performance of carpeting.
- .3 Manufacturer's Extended Warranty: For a period of 10 years, covering against wear, colour fading, and deterioration of backing materials.

2 Products

2.1 MATERIALS

- .1 Carpet Tile (CPT-1): Combination of Bikepath Collection and On Line by InterfaceFLOR Commercial, or combination of Frenemy Stock & Stock Brights and Elemental Solids II by Mannington Commercial; up to 4 colours as selected by Consultant.
- .2 Carpet Adhesive: To CAN/CGSB-71.28-M, solvent free, latex based waterproof adhesive; eg. Eco Tech 9600 by Chembond Ltd.
- .3 Seam Adhesive: Latex seam sealer or thermoplastic adhesive.
- .4 Subfloor Filler: Premixed latex cementitious type.
- .5 Transition Strips: Resilient type, as specified in Section 09 65 13.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify concrete slabs have cured minimum 28 days.
- .3 Verify concrete slabs have pH level between 5 and 11, as determined by ASTM F3441.
- .4 Conduct moisture vapour emission rate tests on concrete slabs-on-fill to ASTM F1869. Do not proceed with installation until tests indicate $MVER \leq 2.27$ kg per 93 m² for 24 hours.
- .5 Conduct relative humidity tests on concrete slabs to ASTM F2170. Do not proceed with installation until tests indicate $RH \leq 75$ percent.
- .6 Determine absorptive nature of substrate by conducting porosity tests to ASTM F3191.

3.2 PREPARATION

- .1 Prepare substrate as recommended by manufacturer for absorptive conditions determined by porosity test.
- .2 Remove subfloor ridges and bumps.
- .3 Fill low spots, cracks, joints, holes, and other defects with subfloor filler.

3.3 INSTALLATION

- .1 Install carpet tile to CRI 104 for Direct Glue-Down Installation Method.
- .2 Lay carpet tile in manufacturer's recommended pattern.
- .3 Verify carpet tile pattern match to ensure minimal variation between dye lots.
- .4 Lay carpet tile with joints and seams parallel to building lines to produce symmetrical tile patterns. Provide perimeter tile of similar size within any given area.
- .5 Lay carpet tile continuously from wall to wall in each area, including beneath casework.
- .6 Cut and fit carpet tiles around interruptions.
- .7 Fit carpet tiles tight to intersection with vertical surfaces without gaps.
- .8 Where adjacent floor finish is dissimilar, terminate carpet tile flooring at centre line of door openings.
- .9 Provide transition strip along junction of dissimilar flooring materials.

3.4 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Remove dirt, carpet scraps, and threads from carpet surface.
- .3 Clean carpet with a beater-type vacuum cleaner.
- .4 Remove soiled spots or adhesive from carpet with a proper spot remover.
- .5 Remove loose pieces of face yarn with sharp scissors.

3.5 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect completed installation with protective covering.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 09 21 16 - Gypsum Board Assemblies.
- .2 Section 09 51 23 - Acoustical Tile Ceilings.

1.2 REFERENCES

- .1 ASTM C167-25: Standard Test Methods for Thickness and Density of Blanket or Batt Thermal Insulations.
- .2 ASTM C423-23e1: Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method.
- .3 ASTM E90-23: Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
- .4 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .5 CAN/ULC-S114-2018: Standard Method of Test for Determination of Non-Combustibility in Building Materials.
- .6 CAN/ULC-S129-15 (REV1): Standard Method of Test for Smoulder Resistance of Insulation (Basket Method).
- .7 CAN/ULC-S702.1:2021: Standard for Mineral Fibre Thermal Insulation for Buildings, Part 1: Material Specification.
- .8 ULC-S702.2-15: Standard for Mineral Fibre Thermal Insulation for Buildings, Part 2: Installation.

1.3 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Store Products away from construction activity and sources of ignition.
- .3 Protect Products from damage during handling, installation and at point of installation.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers of acoustical insulation having Product considered acceptable for use:
 - .1 CertainTeed Canada, Inc.
 - .2 Knauf Insulation.
 - .3 Owens-Corning Canada Inc.
 - .4 Rockwool.
- .2 Manufacturers of flame-resistant acoustical insulation having Product considered acceptable for use:
 - .1 Johns Manville.
 - .2 Owens-Corning Canada Inc.
 - .3 Rockwool.
- .3 Substitution Procedures: Refer to Section 01 25 00.

2.2 MATERIALS

- .1 Acoustical Insulation: To CAN/ULC-S702.1, Type 1; mineral fibre acoustical batts, non-rigid, friction fit type, manufactured from glass, rock, or slag fibers; and as follows:
 - .1 Noise Reduction Coefficient (ASTM C423): $NRC \geq 1.10$ @ 76 mm thick.
 - .2 Facing: Unfaced.
 - .3 Density (ASTM C167): $\geq 40 \text{ kg/m}^3$.
 - .4 Combustibility (CAN/ULC-S114): Noncombustible.
 - .5 Surface Burning Characteristics (CAN/ULC-S102)
 - .1 Flame Spread Index = 0.
 - .2 Smoke Developed Index = 0.
 - .6 Thickness: As indicated on Drawings.
 - .7 Manufacturer and Product Name: eg. Safe'n'Sound by Rockwool.
- .2 Flame-Resistant Acoustical Insulation: To CAN/ULC-S702.1, Type 1; mineral fibre acoustical batts, non-rigid, friction fit type, manufactured from only rock or slag fibers; acceptable for use in fire-rated partitions; and as follows:
 - .1 Noise Reduction Coefficient (ASTM C423): $NRC \geq 1.10$ @ 100 mm thick.
 - .2 Facing: Unfaced.
 - .3 Density (ASTM C167): $> 40 \text{ kg/m}^3$.
 - .4 Combustibility (CAN/ULC-S114): Noncombustible.
 - .5 Surface Burning Characteristics (CAN/ULC-S102)
 - .1 Flame Spread Index = 0.
 - .2 Smoke Developed Index = 0.
 - .6 Smoulder Resistance (CAN/ULC-S129): 0.04 wt percent.
 - .7 Thickness: As indicated on Drawings.
 - .8 Manufacturer and Product Name: eg. AFB Acoustical Fire Batt Insulation by Rockwool.
- .3 Mechanical Fasteners: Stainless steel screw type fastener, complete with 75 mm OD moulded plastic disc washer.
- .4 Adhesive: Mastic type, synthetic rubber base, fungi resistant, gun or trowel application.

3 Execution

3.1 INSTALLATION

- .1 Install Products to ULC-S702.2 and ASTM E90, without gaps and voids.
- .2 Fit acoustic insulation tight within spaces, around cut openings, behind and around facility service components within or behind partitions, and tight to items passing through partitions.

3.2 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect acoustic insulation at the end of each Working Day.
- .3 Protect acoustic insulation in areas where welding will be carried out.
- .4 Replace acoustic insulation damaged by others.
- .5 Protect acoustic insulation requiring a thermal barrier in accordance with authorities having jurisdiction.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 04 00 00 - Masonry.
 - .2 Section 07 92 00 - Joint Sealants.
 - .3 Section 09 21 16 - Gypsum Board Assemblies.
 - .4 Section 09 51 23 - Acoustical Tile Ceilings.
 - .5 Section 09 81 00 - Acoustic Insulation.
- 1.2 REFERENCES
 - .1 ASTM C423-23e1: Standard Test Method for Sound Absorption and Sound Absorption Coefficients by the Reverberation Room Method.
 - .2 ASTM D1779-98(2017): Standard Specification for Adhesive for Acoustical Materials.
 - .3 ASTM E84-26a: Standard Test Method for Surface Burning Characteristics of Building Materials.
 - .4 ASTM E90-23: Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions and Elements.
 - .5 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- 1.3 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating materials, component sizes, methods of attachment, and physical properties.
- 1.4 SHOP DRAWINGS
 - .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, illustrating panels sizes, mechanical attachment details and frequency of fasteners, and panel configuration.
 - .3 Field measure areas prior to determining panel layout on Shop Drawings.
- 1.5 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Samples: Duplicate 150 x 150 mm size samples, illustrating full range of exposed texture, and conditions of panel edges and ends.
- 1.6 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Store materials stacked on a raised platform clear of ground, and adequately protected from weather using waterproof coverings.
 - .3 Protect edges and surfaces from marring, soil, and damage.
 - .4 Cover bottom of stacks with moisture-proof membrane, allowing for adequate air circulation to prevent condensation.

- .5 Protect material from water damage.
- 1.7 AMBIENT CONDITIONS
- .1 Do not install Product until building is enclosed and HVAC system is operational.
 - .2 Locate Products in area of the Work at least 72 hours before beginning installation to allow materials to reach temperature and moisture content equilibrium.
 - .3 Maintain the following environmental conditions for 24 hours before, during and after installation:
 - .1 Relative Humidity: ≤ 55 percent RH.
 - .2 Ambient Air Temperature: Between 15 degrees C and 30 degrees C.
- 2 Products
- 2.1 MANUFACTURERS
- .1 Manufacturers of sound-absorptive panels having Product considered acceptable for use:
 - .1 Acoustic Panels Canada.
 - .2 Manufacturers of acoustical wall diffuser panels having Product considered acceptable for use:
 - .1 Wenger.
 - .3 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 PERFORMANCE CRITERIA
- .1 Surface Burning Characteristics:
 - .1 Sound-Absorptive Panels, Type SAP (CAN/ULC-S102): Class A, as follows:
 - .1 Flame Spread Index = 0.
 - .2 Smoke Developed Classification ≤ 40 .
 - .2 Acoustical Wall Diffuser Panels (ASTM E84): Class A.
 - .2 Noise Reduction Coefficient:
 - .1 Sound-Absorptive Panels, Type SAP (ASTM C423): $NRC \geq 0.9$.
 - .3 Sound Transmission Class
 - .1 Acoustical Wall Diffuser Panel (ASTM E90): $STC \geq 23$.
- 2.3 MATERIALS
- .1 Diffuser Fabric: FR701 Style 2100 Series by Guiford of Maine Company, colour and pattern as selected by Consultant.
 - .2 Mechanical Wall Fastening Systems: Flush mount 1.2 mm thick galvanized metal Z-Clips for use at top and angle supports for use along bottom, complete with galvanized steel bolts.
 - .3 Diffuser Panel Adhesive: To ASTM D1779.
 - .4 Diffuser Fabric Adhesive: Single-component polyurethane, fire-resistant type; as recommended by wall diffuser panel manufacturer.
- 2.4 MANUFACTURED UNITS
- .1 Sound-Absorptive Panels (SAP):
 - .1 Panel Core: 50 mm thick semi-rigid mineral fiber acoustic insulation.
 - .2 Panel Face: Gallery wrap fabric, recycled polyester.
 - .3 Panel Back: Protective scrim backing.
 - .4 Panel Frame: Lightweight polyvinyl chloride.

- .5 Panel Sizes: 610 x 1 220 mm.
- .6 Manufacturer and Product Name: 24 x 48 Wall - Pro Acoustic Fabric by Acoustic Panels Canada.
- .2 Acoustical Wall Diffuser Panel: 610 x 1 219 mm size, 127 mm deep sound diffuser panel; fabricated from 3 mm thick thermo molded plastic, complete with factory-applied fabric covering and mounting hardware; Convex profile; Type I Wall Diffuser Panel by Wenger.

2.5 FABRICATION

- .1 Fabricate Products in strict accordance with accepted Shop Drawings.
- .2 Field cutting will not be allowed.
- .3 Fabricate lay-in diffuser panels with square, chemically hardened edges.
- .4 Apply adhesive continuously on backing sheet to prevent air movement through diffusers.
- .5 Provide finished openings and recesses for fixtures, fittings, and devices.
- .6 Reinforce Products as necessary to ensure rigid, sturdy construction.
- .7 Apply fabric across exposed face of wall diffuser panels, free of seams, sags, and wrinkles.
- .8 Fully bond fabric cover to wall diffuser panel surfaces with fire-resistant adhesive.
- .9 Wrap fabric around edges and return to back of wall diffuser panel.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Inspect surfaces for unevenness, irregularities, and dampness that would affect quality and execution of the Work.

3.2 INSTALLATION

- .1 Install Products straight, level, and plumb.
- .2 Install Products with evenly spaced joints.
- .3 Mounting Method: Mounting Method A, with concealed, flush mount Z-Clips.
- .4 Install Products in layouts as indicated on Drawings.
- .5 Space fasteners at 610 mm OC maximum, both directions.
- .6 Provide additional fasteners as required.
- .7 Install wall mounted panels with tight seams between adjacent panels.

3.3 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Clean exposed surfaces in accordance with manufacturer's printed instructions.
- .3 Remove and replace damaged Product.

3.4 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect installed Products and assemblies from damage resulting from subsequent construction operations.
- .3 Protect completed installation from inclement weather, excessive temperature and humidity conditions, and dust.

END OF SECTION

1 General

1.1 PRODUCTS FURNISHED OR INSTALLED UNDER OTHER SECTIONS

- .1 Carefully examine scope of the Work as indicated on Drawings, and include all finishing, whether specifically mentioned or not, except as specifically excluded below:
- .1 Section 05 50 00 - Metal Fabrications: Shop priming.
 - .2 Section 06 24 00 - High Pressure Decorative Laminate: Integral colour.
 - .3 Section 06 41 00 - Architectural Wood Casework: Shop finishing.
 - .4 Section 07 42 43 - Composite Wall Panels: Shop finishing.
 - .5 Section 07 81 00 - Applied Fireproofing: Integral colour.
 - .6 Section 07 84 00 - Firestopping: Integral colour.
 - .7 Section 07 92 00 - Joint Sealants: Integral colour.
 - .8 Section 08 12 13 - Hollow Metal Frames: Galvannealed coating.
 - .9 Section 08 13 13 - Hollow Metal Doors: Galvannealed coating.
 - .10 Section 08 31 00 - Access Doors and Panels: Shop priming.
 - .11 Section 08 51 13 - Aluminum Windows: Anodized coating.
 - .12 Section 08 71 00 - Door Hardware: Shop finishing.
 - .13 Section 09 51 23 - Acoustical Tile Ceilings: Shop finishing.
 - .14 Section 09 84 13 - Fixed Sound-Absorptive Panels: Shop finishing.
 - .15 Section 09 96 13 - Abrasion-Resistant Coatings.
 - .16 Section 10 11 00 - Visual Display Surfaces: Shop finishing.
 - .17 Section 10 14 00 - Signage.
 - .18 Section 12 24 13.16 - Manual Roller Window Shades: Shop finishing.
 - .19 Section 12 56 34 - Music Room Furniture: Shop finishing.
 - .20 Do not paint glass surfaces.
 - .21 Do not paint plastic components.
 - .22 Do not paint plated, polished or anodized metal components.
 - .23 Do not paint stainless steel components.

1.2 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 05 50 00 - Metal Fabrications.
- .3 Section 06 10 00 - Rough Carpentry.
- .4 Section 06 20 00 - Finish Carpentry.
- .5 Section 08 12 13 - Hollow Metal Frames.
- .6 Section 08 13 13 - Hollow Metal Doors.
- .7 Section 08 31 00 - Access Doors and Panels.
- .8 Section 09 21 16 - Gypsum Board Assemblies.

1.3 REFERENCES

- .1 MPI Architectural Painting Specification Manual.
- .2 MPI Maintenance Repainting Manual.
- .3 SSPC Painting Manual, Volume 2 - Systems and Specifications.

1.4 SCHEDULING

- .1 Schedule painting operations to prevent disruption to the Work.

- .2 Schedule painting and coating operations in occupied facilities to prevent disruption of occupants at existing facility. Conduct painting and coating after facility working hours or on weekends in accordance with Owner's operating requirements.
 - .3 Schedule work such that finished surfaces have dried before occupants are affected.
 - .4 Schedule site finishing of doors and frames prior to door, glass, and hardware installation.
 - .5 Obtain written authorization from Consultant for changes in work schedule.
- 1.5 PRODUCT DATA
- .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturers' standard data sheets for each finishing Product being used, indicating relevant MPI finish system, volatile organic compound (VOC) content, and volume solids (VOL SOL) content.
- 1.6 SAMPLES
- .1 Submit samples as specified in Section 01 33 00.
 - .2 Selection Samples: A full range of colour selector samples for each type of coating required.
 - .3 Verification Samples: If requested by Consultant, prepare 1 000 x 1 000 mm size sample panels. Apply finish to actual substrate material or to an acceptable alternate material if required to be portable.
- 1.7 EXTRA STOCK MATERIALS
- .1 Supply extra stock materials as specified in Section 01 78 00.
 - .2 Extra Stock Materials: Minimum 4 L of each Product, colour, and sheen used.
 - .3 Supply extra stock materials in unopened, new containers, clearly labelled as to manufacturer, Product, colour, and sheen.
- 1.8 QUALIFICATIONS
- .1 Applicators: A firm specializing in commercial painting and finishing of buildings in accordance with MPI Architectural Painting Specification Manual and MPI Maintenance Repainting Manual, having minimum 10 years documented experience.
- 1.9 DELIVERY, STORAGE AND HANDLING
- .1 Refer to Section 01 60 00.
 - .2 Deliver Products in original containers with unbroken seals and labelled to indicate name of manufacturer, brand, colour and quality of contents.
 - .3 Store thinners, loose soaked rags and similar combustible materials in closed containers. Remove from Place of the Work or store in an assigned area.
 - .4 Provide adequate safe-guards against spontaneous combustion of finishing materials.
 - .5 Arrange for properly enclosed and heated space, satisfactory to Consultant, to be used as paint shop. Store Products at minimum 10 degrees C.
- 1.10 AMBIENT CONDITIONS
- .1 Conform to MPI Architectural Painting Specification Manual.

- .2 Apply water-based paints only when temperature of surfaces to be finished and surrounding air temperatures are between 10 degrees C and 30 degrees C.
- .3 Apply solvent-thinned paints only when temperature of surfaces to be finished and surrounding air temperatures are between 6 degrees C and 32 degrees C.
- .4 Do not apply finishes in snow, rain, fog, or mist.
- .5 Do not apply finishes when relative humidity exceeds 85 percent RH; or at temperatures less than 2 degrees C above dew point; or to damp or wet surfaces.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturer: Use only Products from manufacturers listed in MPI Architectural Painting Specification Manual for specified paint and finish system.
- .2 Single-Source Responsibility: Provide primers and undercoats from same manufacturer as finish coats.

2.2 DESCRIPTION

- .1 Gloss Ratings: Paint gloss shall be defined as the sheen rating of applied paint, in accordance with the following gloss level categories, as defined in MPI Architectural Painting Specification Manual:
 - .1 Gloss Level G1: Matte or Flat finish.
 - .2 Gloss Level G2: Velvet finish.
 - .3 Gloss Level G3: Eggshell finish.
 - .4 Gloss Level G4: Satin finish.
 - .5 Gloss Level G5: Semi-Gloss finish.
 - .6 Gloss Level G6: Gloss finish.
 - .7 Gloss Level G7: High-Gloss finish.
- .2 Colours: A maximum of 5 exterior colours and 20 interior colours may be required. There may be more than two colours used in each room or space.

2.3 PERFORMANCE CRITERIA

- .1 Volatile Organic Compound Content (VOC): Use only paints and coatings having a volatile organic compound (VOC) content as follows:
 - .1 Gloss Level G1: < 50 g/L.
 - .2 Gloss Levels G2-G7: < 150 g/L.
- .2 Volume Solids Content (VOL SOL): Use only paints and coatings having a volume solids (VOL SOL) content as follows:
 - .1 Alkyd Paints and Coatings: \geq 45 percent.
 - .2 Latex Paints and Coatings: \geq 40 percent.

2.4 MATERIALS

- .1 Paints and Coatings: Use only Products meeting specified performance criteria and listed in most current Approved Products List included in MPI Architectural Painting Specification Manual, for each specified paint and finish system.
- .2 Paint Accessory Materials: Linseed oil, shellac, turpentine, and other materials of commercial quality.

2.5 MIXING

- .1 Pigments shall be fully ground and shall maintain a soft paste consistency in the vehicle during storage, that can and will be dispersed readily and uniformly by paddle to a complete, homogeneous mixture.
- .2 Carefully mix and prepare paint materials according to manufacturer's directions.
- .3 Maintain containers used in mixing and applying paint in a clean condition, free of foreign materials and residue.
- .4 Stir material before application to produce a mixture of uniform density. Do not stir surface film into material. Remove film and, if necessary, strain material before using.
- .5 Use only thinners approved by paint manufacturer, and only within recommended limits.
- .6 Tint each undercoat a lighter shade to facilitate identification of each coat where multiple coats of same material are applied. Tint undercoats to match colour of finish coat, but with sufficient differences in shade of undercoats to distinguish each separate coat.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Measure moisture content of surfaces using an electronic moisture metre. Do not apply finishes unless moisture content of surfaces are below recommended maximum values.

3.2 PREPARATION

- .1 Prepare surfaces to MPI Architectural Painting Specification Manual.
- .2 Prepare existing, previously finished surfaces designated for re-finishing to MPI Maintenance Repainting Manual.
- .3 Mask out surrounding surfaces not to receive paint, to protect from overspray or overbrushing.
- .4 Remove hardware and accessories, plates, machined surfaces, lighting fixtures and similar items already installed but not intended to be painted.
- .5 Remove mildew, efflorescence and foreign materials from surfaces using appropriate methods.
- .6 Correct minor defects and deficiencies in surfaces which affect application of paints and coatings.
- .7 Clean and prepare surfaces to be painted according to manufacturers' instructions for each particular substrate condition and finish system.
- .8 Provide barrier coats over incompatible primers.
- .9 Clean ungalvanized ferrous metal surfaces designated to receive site finish. Use solvent or mechanical cleaning methods to SSPC Painting Manual, Volume 2 - Systems and Specifications.
- .10 Clean galvanized surfaces with non-petroleum-based solvents. Surface to be free of oil and surface contaminants. Remove pretreatment from galvanized steel metal fabricated from coil stock by mechanical methods.

3.3 APPLICATION

- .1 Apply Products to MPI Architectural Painting Specification Manual.
- .2 Protect adjacent surfaces and areas, including equipment, labels and signage from damage during painting operations. Use drop cloths, shields, masking, templates or other suitable protective means.
- .3 Make Good damage caused by failure to protect surfaces.
- .4 Erect barriers or screens and post signs to warn of or limit or direct traffic away or around work areas as required.
- .5 Use methods best suited for substrate and type of material being applied.
- .6 Do not use compressed air or aerosol methods of application without prior written approval of Consultant.
- .7 Spread finishes evenly and flow on smoothly without runs or sags.
- .8 Apply Products no thinner than manufacturer's recommended spreading rate. Provide total dry film thickness of entire system as recommended by manufacturer.
- .9 Apply Products under adequate illumination.
- .10 Sand lightly between coats to achieve required finish.
- .11 Where clear finishes are required, tint fillers to match wood. Work fillers into grain before set. Wipe excess from surface.
- .12 Back prime interior wood work with enamel primer sealer paint.
- .13 Back prime exterior wood work with exterior primer paint.
- .14 Pigmented (Opaque) Finishes: Completely cover substrate to a smooth, opaque surface of uniform finish, colour, appearance, and coverage. Cloudiness, spotting, holidays, laps, brush marks, runs, sags, ropiness or other surface imperfections will not be accepted.
- .15 Transparent (Clear) Finishes: Use multiple coats to produce a glass-smooth surface film of even luster. Provide a finish free of laps, cloudiness, colour irregularity, runs, brush marks, orange peel, nail holes or other surface imperfections.
- .16 Match approved samples for colour, texture, and coverage. Remove, refinish or repaint work not complying with specified requirements.

3.4 FACILITY SERVICES

- .1 Unless otherwise specified or noted, paint "unfinished" conduits, piping, hangers, ductwork, and other mechanical and electrical equipment with colour and texture to match adjacent surfaces, in the following areas:
 - .1 Where exposed-to-view in exterior and interior areas.
 - .2 In high humidity interior areas.
 - .3 In mechanical and electrical rooms.
- .2 Remove finished louvres, grilles, covers, and access panels on facility service components from location and paint separately. Finish paint primed equipment to colour selected by Consultant.
- .3 Paint inside of air ducts, convection and baseboard heating cabinets where visible behind louvers, grilles, and diffusers for minimum 460 mm or beyond sight line, whichever is greater with primer and one coat of matt black (non-reflecting) paint.

- .4 Paint inside of light valances gloss white.
- .5 Paint disconnect switches for fire alarm system and exit light systems in red enamel.
- .6 Paint red or band fire protection piping and sprinkler lines. Keep sprinkler heads free of paint.
- .7 Paint yellow or band natural gas piping.
- .8 Backprime and paint face and edges of plywood service panels a semi-gloss, gray colour before installation of telephone and electrical equipment. Leave equipment in original finish except for touch-up as required. Paint conduits, mounting accessories, and other unfinished items.
- .9 Do not paint exterior steel electrical light standards, outdoor transformers, and substation equipment.
- .10 Colour code equipment, piping, conduit, and exposed ductwork in accordance with colour schedule. Colour band and identify with flow arrows, names, and numbering.
- .11 In unfinished areas, leave exposed conduits, piping, hangers, ductwork, and other facility service components in original finish. Touch-up scratches and marks.
- .12 Touch-up scratches and marks on factory painted finishes and equipment with paint as supplied by equipment manufacturer.
- .13 Do not paint over nameplates.

3.5 FIELD QUALITY CONTROL

- .1 Inspect surfaces, preparation and paint applications.
- .2 Painted surfaces shall be considered to lack uniformity and soundness if any of the following defects are apparent:
 - .1 Brush or roller marks, streaks, laps, runs, sags, drips, heavy stippling, hiding or shadowing by inefficient application methods, skipped or missed areas, and foreign materials in painted coatings.
 - .2 Evidence of poor coverage at fastener heads, plate edges, lap joints, crevices, pockets, corners and re-entrant angles.
 - .3 Damage due to touching before paint is sufficiently dry or other contributory cause.
 - .4 Damage due to application on moist surfaces or caused by inadequate protection from weather.
 - .5 Damage or contamination of paint due to blown contaminants (dust, spray paint, etc).
- .3 Painted surfaces will be rejected if any of the following are evident under natural lighting source for exterior surfaces and final lighting source (including daylight) for interior surfaces:
 - .1 Visible defects are evident on vertical surfaces when viewed at normal viewing angles from a distance of not less than 1 000 mm.
 - .2 Visible defects are evident on horizontal surfaces when viewed at normal viewing angles from distance of not less than 1 000 mm.
 - .3 Visible defects are evident on ceiling, soffit and other overhead surfaces when viewed at normal viewing angles.
 - .4 When final coat on any surface exhibits a lack of uniformity of colour, sheen, texture and hiding across full surface area.
- .4 Make Good rejected surfaces. Small affected areas may be touched up; large affected areas or areas without sufficient dry film thickness of paint shall be repainted. Runs, sags or damaged paint shall be removed by scraper or by sanding prior to application of paint.

3.6 ADJUSTING

- .1 Following completion of painting and finishing operations, reinstall removed items.

.2 Remove protective covers and masking from protected surfaces.

.3 Repaint damaged surfaces to satisfaction of Consultant.

3.7 CLEANING

.1 Refer to Section 01 74 00.

.2 Remove paint where spilled, splashed, splattered, or sprayed using means and materials that are not detrimental to affected surfaces.

.3 Keep work area free from unnecessary accumulation of tools, equipment, surplus materials, and debris.

.4 Remove combustible rubbish materials and empty paint cans each day and safely dispose of in accordance with authorities having jurisdiction.

.5 Clean equipment and dispose of wash water / solvents as well as other cleaning and protective materials, paints, thinners, paint removers, and strippers in accordance with authorities having jurisdiction.

.6 Leave the Work clean and free from dirt and debris.

3.8 WASTE MANAGEMENT

.1 Paint, stain, wood preservative finishes and related materials (thinner, solvents, etc.) are regarded as hazardous products and are subject to regulations for disposal. Obtain information on these controls from authorities having jurisdiction.

.2 Separate and recycle waste materials. Where paint recycling is available, collect waste paint by type and deliver to recycling or collection facility. Materials that cannot be reused must be treated as hazardous waste and disposed of in an appropriate manner.

.3 Place materials defined as hazardous or toxic waste, including used sealant and adhesive tubes and containers, in containers or areas designated for hazardous waste.

.4 To reduce the amount of contaminants entering waterways, sanitary sewers, storm sewers or into the ground strictly adhere to the following procedures:

.1 Retain cleaning water for water-based materials to allow sediments to be filtered out. Do not clean equipment using free draining water.

.2 Retain cleaners, thinners, solvents, and excess paint and place in designated containers and ensure proper disposal.

.3 Return solvent and oil soaked rags used during painting operations for contaminant recovery, proper disposal, or appropriate cleaning and laundering.

.4 Dispose of contaminants in an approved legal manner in accordance with applicable regulatory requirements dealing with hazardous waste.

.5 Empty paint cans are to be dry prior to disposal or recycling.

.6 Close and tightly seal partly used cans of materials, including sealant and adhesive containers, and store protected in a well ventilated, fire-safe area at moderate temperature.

.5 Set aside and protect surplus and uncontaminated finish materials not required by Owner, and deliver or arrange collection of verifiable re-use or re-manufacturing.

3.9 PROTECTION

.1 Refer to Section 01 76 00.

.2 Protect other surfaces from paint or damage.

.3 Repair damage.

3.10 FINISH SCHEDULE

- .1 Provide indicated paint and finish systems for identified substrates to MPI Architectural Painting Specification Manual.
- .2 Refinishing Existing, Previously Finished Surfaces:
 - .1 Refer to MPI Maintenance Repainting Manual Section for refinishing existing finishes.
 - .2 Use finish coat of respective new surface finish system for minor repair of existing finishes.
 - .3 Use system primer where existing finishes are damaged down to bare surface.
- .3 Exterior Painting and Finishing Schedule
 - .1 Concrete Vertical Surfaces
 - .1 Opaque Painted Finish: EXT. 3.1C - W.B. LIGHT INDUSTRIAL COATING (over w.b. alkali resistant primer), Premium Grade; Gloss Level G3.
 - .2 Structural Steel
 - .1 Corrosion-Resistant Opaque Painted Finish: EXT. 5.1B - W.B. LIGHT INDUSTRIAL COATING (over inorganic zinc), Premium Grade; Gloss Level G5.
 - .3 Metal Fabrications
 - .1 Opaque Painted Finish: EXT. 5.1D - ALKYD (over alkyd metal primer), Premium Grade; Gloss Level G5.
 - .4 Galvanized and Galvannealed Metal
 - .1 Opaque Painted Finish: EXT. 5.3B - ALKYD (over cementitious primer), Premium Grade; Gloss Level G6.
 - .5 Aluminum (Not Anodized)
 - .1 Opaque Painted Finish: EXT. 5.4H - LATEX (over q.d. metal primer), Premium Grade, Gloss Level G6.
 - .6 Dimension Lumber and Panels
 - .1 Opaque Painted Finish: EXT 6.2A - LATEX (over alkyd/oil primer), Premium Grade; Gloss Level G5.
 - .2 Opaque Stained Finish: EXT. 6.2B - SOLID COLOR STAIN, W.B. (over alkyd/oil primer), Premium Grade; Gloss Level G1.
 - .3 Semi-Transparent Stained Finish: EXT. 6.2E - VARNISH, S.B. (over s.b. stain), Premium Grade; Gloss Level G5.
 - .7 Dressed Lumber and Panels
 - .1 Opaque Painted Finish: EXT. 6.3A - LATEX (over alkyd/oil primer), Premium Grade; Gloss Level G5.
 - .2 Semi-Transparent Stained Finish: EXT. 6.3E - VARNISH, S.B. (over s.b. stain), Premium Grade; Gloss Level G5.
 - .3 Opaque Stained Finish: EXT. 6.3K - SOLID COLOR STAIN, W.B. (over alkyd/oil primer), Premium Grade; Gloss Level G1.
- .4 Interior Painting and Finishing Schedule
 - .1 Concrete Surfaces (except floors)
 - .1 Epoxy Finish: INT. 3.1G - EPOXY-MODIFIED LATEX (for smooth concrete), Premium Grade; Gloss Level G6.
 - .2 Opaque Painted Finish: INT. 3.1M - INSTITUTIONAL LOW ODOR / VOC, Premium Grade; Gloss Level G4.
 - .2 Concrete Floors
 - .1 Epoxy Finish: INT. 3.2C - EPOXY, Premium Grade; Gloss Level G5.
 - .3 Concrete Masonry Units
 - .1 Opaque Painted Finish: INT. 4.2E - INSTITUTIONAL LOW ODOR / VOC (over latex block filler), Premium Grade; Gloss Level G4.
 - .2 Epoxy Finish: INT. 4.2J - EPOXY-MODIFIED LATEX (over latex block filler) FOR DRY ENVIRONMENTS, Premium Grade; Gloss Level G6.
 - .4 Structural Steel, Steel Joists, Steel Deck and Metal Fabrications
 - .1 Opaque Painted Finish - Overhead Applications: INT. 5.1C - W.B. DRY FALL (over q. d. alkyd primer), Budget Grade; Gloss Level G5.

- .2 Opaque Painted Finish: INT. 5.1E - ALKYD (over q.d. alkyd primer), Premium Grade; Gloss Level G5.
- .3 Epoxy Finish: INT. 5.1K - EPOXY-MODIFIED LATEX (over w.b. rust-inhibitive primer), Premium Grade; Gloss Level G6.
- .5 Galvanized and Galvannealed Metal
 - .1 Opaque Painted Finish: INT. 5.3N - INSTITUTIONAL LOW ODOR / VOC (over w. b. galvanized primer), Premium Grade; Gloss Level G5.
- .6 Dimension Lumber and Panels
 - .1 Opaque Painted Finish: INT. 6.2L - INSTITUTIONAL LOW ODOR / VOC (over latex primer), Premium Grade; Gloss Level G5.
- .7 Dressed Lumber, Panels, and Veneers
 - .1 Semi-Transparent Stained Finish: INT. 6.3EE - POLYURETHANE VARNISH (over w.b. stain), Premium Grade; Gloss Level G4.
 - .2 Semi-Transparent Stained Fire Retardant Finish: INT. 6.3RR - FIRE RETARDANT, PIGMENTED, W.B., Gloss Level G4.
 - .3 Opaque Painted Finish: INT. 6.3V - INSTITUTIONAL LOW ODOR / VOC (over latex primer), Premium Grade; Gloss Level G5.
- .8 Gypsum Board
 - .1 Epoxy Finish: INT. 9.2F - EPOXY-MODIFIED LATEX (over latex primer/sealer), Premium Grade; Gloss Level G6.
 - .2 Opaque Painted Finish: INT. 9.2M - INSTITUTIONAL LOW ODOR / VOC (over latex primer/sealer), Premium Grade; Gloss Levels as follows:
 - .1 Ceiling Applications: G1.
 - .2 Other Applications: G3.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 06 20 00 - Finish Carpentry.
 - .2 Section 09 90 00 - Painting and Coating.
- 1.2 REFERENCES
 - .1 ASTM D1308-20(2025): Standard Test Method for Effect of Household Chemicals on Clear and Pigmented Coating Systems.
 - .2 ASTM D2486-17(2025): Standard Test Methods for Scrub Resistance of Wall Paints.
 - .3 ASTM D2794-93(2024): Standard Test Method for Resistance of Organic Coatings to the Effects of Rapid Deformation (Impact).
 - .4 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- 1.3 PREINSTALLATION MEETINGS
 - .1 Conduct preinstallation meeting as specified in Section 01 31 00.
 - .2 Preinstallation Meeting: Conducted at Place of the Work one week prior to commencement of Product application, and comprised of Contractor, Consultant, applicator, and manufacturer's representative.
 - .3 Review material selections, application procedures, and coordination with adjacent parts of the Work.
 - .4 Include review of mock-up panel.
- 1.4 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating physical properties, surface preparation, and installation guidelines.
- 1.5 SAMPLES
 - .1 Submit Samples as specified in Section 01 33 00.
 - .2 Verification Samples: Duplicate 100 x 125 mm size samples, applied to rigid backing, in specified colour and finish.
- 1.6 CLOSEOUT SUBMITTALS
 - .1 Submit closeout submittals as specified in Section 01 78 00.
 - .2 Maintenance Data: Manufacturer's standard maintenance and cleaning guidelines, including procedures for stain removal, repairing surface, and cleaning; sufficient quantity for inclusion in operation and maintenance manual.
- 1.7 EXTRA STOCK MATERIALS
 - .1 Supply extra stock materials as specified in Section 01 78 00.
 - .2 Extra Stock Materials: Minimum 4 litres of each Product, colour, and sheen used.

- .3 Supply extra stock materials in unopened, new containers, clearly labelled as to manufacturer, Product, colour, and sheen.

1.8 QUALIFICATIONS

- .1 Applicator: Person or firm experienced in applying abrasion-resistant coatings, approved by manufacturer, and having minimum three years documented experience.

1.9 DELIVERY, STORAGE AND HANDLING

- .1 Refer to Section 01 60 00.
- .2 Deliver Products in unopened containers, with manufacturer's labels intact.
- .3 Store materials in a dry, enclosed area protected from exposure to moisture. Maintain temperature between 10 degrees C and 27 degrees C.

1.10 AMBIENT CONDITIONS

- .1 Perform Work as specified in Section 01 60 00.
- .2 Do not install coating when temperature is below 10 degrees C or above 27 degrees C.
- .3 Maintain relative humidity at less than 50 percent RH before, during, and one day after Product application.
- .4 Ensure adequate ventilation is maintained during and after Product application.
- .5 Comply with WHMIS requirements and manufacturer's instructions.

1.11 WARRANTY

- .1 Submit extended warranties in accordance with the General Conditions of the Contract.
- .2 Manufacturer's Extended Warranty: For a period of 5 years, protecting against manufacturing faults, and defects in Products.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 Master Coating Technologies, Inc.
- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 REGULATORY REQUIREMENTS

- .1 Conform to applicable fire and building codes for surface burning characteristics when tested to CAN/ULC-S102.

2.3 PERFORMANCE CRITERIA

- .1 Abrasion-Resistant Coating: Having the following physical properties:
 - .1 Volatile Organic Compounds (VOC) Content: < 50 g/L.
 - .2 Fire Rating (CAN/ULC-S102): Class A.
 - .3 Scrub Test (ASTM D2486): Passing \geq 8000 cycles.
 - .4 Impact Resistance (ASTM D2794): \geq 60 in/lbs.
 - .5 Chemical Resistance (ASTM D1308): Maximum for all chemicals tested.
 - .6 Finish: 10 percent to 15 percent gloss at 60 degrees.
 - .7 Stain Removal: 8 to 10 for all stains tested, four-hour Open Spot Test.

2.4 MATERIALS

- .1 Bonding Primer: Scuffmaster Primemaster Bonding Primer by Master Coating Technologies, Inc.
- .2 Finish Coat: Two-component polyurethane coating with antimicrobial, Scuffmaster Scrubtough by Master Coating Technologies, Inc.; Black colour.

3 Execution

3.1 PREPARATION

- .1 Clean substrate surface free of foreign matter.
- .2 Sand wood surfaces smooth, and free of marks.
- .3 Wash sap spots and knots with mineral spirits.
- .4 Allow to dry, then cover spots and knots with two coats shellac.

3.2 APPLICATION

- .1 Prime substrate with sufficient number of coats of bonding primer. Allow to dry.
- .2 Lightly sand primer, and thoroughly remove dust from surface.
- .3 Apply finish coat in a continuous, even film; applied in minimum two coats; free of runs, sags, holidays, and irregularities.
- .4 Apply each coat to natural break point.
- .5 Terminate coating in straight lines, at masking tape line.

3.3 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect completed installation from damage and wear during construction with temporary covering.
- .3 Remove temporary covering, and clean surfaces prior to Ready-for-Takeover.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 06 20 00 - Finish Carpentry.
- .3 Section 06 41 00 - Architectural Wood Casework.
- .4 Section 09 21 16 - Gypsum Board Assemblies.

1.2 REFERENCES

- .1 AAMA 611-20: Voluntary Specification for Anodized Architectural Aluminum.
- .2 ASTM A424/A424M-25: Standard Specification for Steel, Sheet, for Porcelain Enameling.
- .3 ASTM A653/A653M-23: Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
- .4 ASTM B221M-21: Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric).
- .5 PEI 1002: Manual and Performance Specifications for Porcelain Enamel Writing Surfaces.
- .6 CAN/ULC-S102-2018 (REV1): Standard Method of Test for Surface Burning Characteristics of Building Materials and Assemblies.
- .7 CAN/ULC-S706.1-2020: Standard for Wood Fibre Insulating Boards for Buildings.

1.3 SHOP DRAWINGS

- .1 Submit Shop Drawings as specified in Section 01 33 00.
- .2 Shop Drawings: Project-specific drawings, illustrating materials, layouts, component dimensions and thicknesses, details of connections and fastening, trim and hardware, and shop-applied finishes.

1.4 CLOSE-OUT SUBMITTALS

- .1 Submit closeout submittals as specified in Section 01 78 00.
- .2 Maintenance Data: Manufacturer's standard maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.
- .3 Additionally, apply removable maintenance instruction labels to each markerboard.

1.5 MOCK-UPS

- .1 Construct mock-ups as specified in Section 01 40 00.
- .2 Mock-Up Panel: A 1 000 x 1 000 mm size mock-up panel; comprised of two markerboard panels; demonstrating quality of material, trim pieces, and method of joining adjacent panels.
- .3 Accepted mock-ups will be used as the standard for acceptance of the Work.
- .4 Remove and replace installed Product that does not conform to accepted mock-up.
- .5 Remove mock-ups from Place of the Work upon Ready-for-Takeover.

1.6 WARRANTY

- .1 Submit extended warranty in accordance with General Conditions of the Contract.
- .2 Manufacturer's Extended Warranty: Warrant markerboards for a period of 10 years against defects other than those due to normal usage and wear, including fading, crazing, chipping, peeling, and surface becoming slick, glassy, or otherwise unsuitable for use.

2 Products

2.1 MANUFACTURERS

- .1 Manufacturers having Product considered acceptable for use:
 - .1 ASI Visual Display Products, Inc.
 - .2 Claridge.
 - .3 Delta Products, Ltd.
 - .4 Global School Products Inc.
 - .5 Martack Specialties Ltd.
- .2 Substitution Procedures: Refer to Section 01 25 00.

2.2 DESCRIPTION

- .1 Use only matching components from a single manufacturer's series of Products.

2.3 REGULATORY REQUIREMENTS

- .1 Test Products for surface burning characteristics to CAN/ULC-S102.

2.4 MATERIALS

- .1 Extruded Aluminum: To ASTM B221M, 6063 alloy, T5 temper.
- .2 Porcelain Enameled Sheet Steel: To ASTM A424/A424M, Type I, Commercial Steel.
- .3 Sheet Steel: To ASTM A653/A653M, Commercial Steel (CS), Types A, B, and C; galvanized.
- .4 Fibreboard: To CAN/ULC-S706.1, Type I; impregnated, sound absorbing type.

2.5 MANUFACTURED UNITS

- .1 Markerboard: Sandwich type construction, as follows:
 - .1 Face Panel: 0.76 mm thick porcelain enameled sheet steel; writable and washable surface, acid-resistant; White colour.
 - .2 Core: 11 mm thick fibreboard.
 - .3 Back-up Balancing Sheet: 0.4 mm thick sheet steel.
- .2 Aluminum Trim: 1.5 mm thick extruded aluminum profiles; eg. Series 9800 by ASI Visual Display Products, Inc., comprised of:
 - .1 Perimeter and divider trim,
 - .2 Map rail, with integral tan cork insert, end stops and two combination roller map hooks for every 1 830 mm of map rail,
 - .3 Concealed mechanical joining system, including 25 mm wide integrally slotted PVC inserts laminated into ends of panels, and 2.0 mm thick galvanized steel splines.
 - .4 Marker tray, with contour fitting end castings; flat type.

2.6 FABRICATION

- .1 Markerboards: Factory laminate core to face panel and back-up balancing sheet under heat and pressure.

- .2 Provide permanent music score lines to one markerboard in each Music Room.

2.7 FINISHES

- .1 Anodized Coating on Extruded Aluminum: To AAMA 611, AA-A41 Clear etched and anodized satin finish, free from extruding draw marks and surface scratches.
- .2 Porcelain Enamel Coating on Sheet Steel: To PEI 1002; with gloss factor between 6 - 8 when measured with 45 degree glossometer.
- .3 Galvannealed Coating on Sheet Steel: To ASTM A653/A653M, Coating Designation ZF120; wiped zinc-iron alloy coating, with streak-free matte grey appearance.

3 Execution

3.1 EXAMINATION

- .1 Refer to Section 01 71 00.
- .2 Verify casework designated to incorporate visual display surfaces are installed.

3.2 INSTALLATION

- .1 Install Products to a rigid, straight, square, and plumb installation, with horizontal lines level.
- .2 Securely attach aluminum trims, ensuring fastenings are concealed.
- .3 Join markerboards together using concealed mechanical joining system to ensure a flush butted joint, with hairline appearance.

3.3 ADJUSTING

- .1 Leave visual display boards in a state suitable for immediate use by Owner.

3.4 CLEANING

- .1 Refer to Section 01 74 00.
- .2 Clean down, remove dirt, and leave elements in first class condition.

END OF SECTION

1 General

1.1 RELATED SECTIONS

- .1 Section 04 00 00 - Masonry.
- .2 Section 05 50 00 - Metal Fabrications.
- .3 Section 07 42 43 - Composite Wall Panels.
- .4 Section 08 13 13 - Hollow Metal Doors.
- .5 Section 09 21 16 - Gypsum Board Assemblies.

1.2 ALLOWANCES

- .1 Contract Price includes a stipulated sum cash Allowance as specified in Section 01 21 00.
- .2 Cash Allowance: Cost for supply and installation of:
 - .1 Exterior signage,
 - .2 Interior door signage, and
 - .3 Interior wayfinding signage and directories.
- .3 Cash Allowance includes costs associated with applying for and obtaining municipal signage permits.

1.3 REFERENCES

- .1 AAMA 611-20: Voluntary Specification for Anodized Architectural Aluminum.
- .2 AAMA 2604-22: Voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels (With Coil Coating Appendix).
- .3 AAMA 2605-22: Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (With Coil Coating Appendix).
- .4 ASTM A123/A123M-24: Standard Specification for Zinc (Hot-Dip Galvanized) Coatings on Iron and Steel Products.
- .5 ASTM A153/A153M-23: Standard Specification for Zinc Coating (Hot-Dip) on Iron and Steel Hardware.
- .6 ASTM A240/A240M-22b: Standard Specification for Chromium and Chromium-Nickel Stainless Steel Plate, Sheet, and Strip for Pressure Vessels and for General Applications.
- .7 ASTM A276/A276M-25: Standard Specification for Stainless Steel Bars and Shapes.
- .8 ASTM A307-21: Standard Specification for Carbon Steel Bolts, Studs, and Threaded Rod 60 000 PSI Tensile Strength.
- .9 ASTM A563/A563M-24: Standard Specification for Carbon and Alloy Steel Nuts (Inch and Metric).
- .10 ASTM A653/A653M-23: Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process.
- .11 ASTM A1008/A1008M-23e1: Standard Specification for Steel, Sheet, Cold-Rolled, Carbon, Structural, High-Strength Low-Alloy, High-Strength Low-Alloy with Improved Formability, Required Hardness, Solution Hardened, and Bake Hardenable.
- .12 ASTM B85/B85M-18e1: Standard Specification for Aluminum-Alloy Die Castings.

- .13 ASTM B209/B209M-21a: Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate.
 - .14 ASTM B221M-21: Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric).
 - .15 ASTM B456-17(2022): Standard Specification for Electrodeposited Coatings of Copper Plus Nickel Plus Chromium and Nickel Plus Chromium.
 - .16 ASTM D3363-20: Standard Test Method for Film Hardness by Pencil Test.
 - .17 ASTM F436/F436M-24: Standard Specification for Hardened Steel Washers Inch and Metric Dimensions.
 - .18 ASTM F844-19(2024): Standard Specification for Washers, Steel, Plain (Flat), Unhardened for General Use.
 - .19 CSA/ASC B651:23: Accessible Design for the Built Environment.
- 1.4 SHOP DRAWINGS
- .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, illustrating materials, dimensions, thicknesses, design style, fonts and font sizes, finishes, methods of attachment, power supply requirements, and special details.
- 1.5 SAMPLES
- .1 Submit samples as specified in Section 01 33 00.
 - .2 Verification Samples: One full size sample of each sign type, illustrating size, thickness, methods of attachment, font style, font size, and factory-applied finishes.
- 1.6 CLOSEOUT SUBMITTALS
- .1 Submit closeout submittals as specified in Section 01 78 00.
 - .2 Maintenance Data: Manufacturer's standard care, maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.
- 1.7 QUALIFICATIONS
- .1 Manufacturer: A firm specializing in manufacturing building signage, having minimum 5 years documented experience.
- 2 Products
- 2.1 DESCRIPTION
- .1 Exterior Building Signage: Individual die cut or die cast metal letters, numbers, and symbols; factory-applied finish; securely attached to building face; design as indicated on Drawings.
 - .2 Stairwell Signage: To applicable regulatory requirements.
 - .3 Braille and Tactile Characters: To CSA/ASC B651; raised surface type, and incorporating international symbols of access.
- 2.2 MATERIALS
- .1 Stainless Steel Sheet and Plate: To ASTM A240/A240M, Type 304.

- .2 Stainless Steel Bar and Shapes: To ASTM A276/A276M, Type 304.
- .3 Sheet Steel: To ASTM A1008/A1008M, Commercial Steel (CS) Types A, B, and C; cold-rolled sheet steel.
- .4 Galvanized Sheet Steel: To ASTM A653/A653M, Commercial Steel (CS) Types A, B, and C; cold-rolled sheet steel; galvanized.
- .5 Extruded Aluminum: To ASTM B221M, 6061 alloy, T6 temper.
- .6 Cast Aluminum: To ASTM B85/B85M, 6063 alloy, T5 temper.
- .7 Sheet Aluminum: To ASTM B209/B209M, 5005-H32 alloy.
- .8 Fasteners:
 - .1 Exterior Fasteners: To ASTM A307, Grade A; carbon and alloy steel, galvanized where noted; concealed types.
 - .2 Interior Fasteners: Countersunk screw-type with tamperproof heads, complete with plastic wall plugs when required for securement to wall surfaces; suitable sizes for intended application. Do not use through-fastening types.
- .9 Nuts: To ASTM A563/A563M, Grade A, Hex Style; carbon and alloy steel, galvanized.
- .10 Washers:
 - .1 Hardened Types: To ASTM F436/F436M, Type 1 for interior applications, Type 3 for exterior applications; hardened steel; circular, bevelled, and clipped types as required.
 - .2 Unhardened Types: To ASTM F844; punched from cold-rolled steel, plain (flat) type; diameter to suit bolt size; galvanized.
- .11 Adhesive: As recommended by sign manufacturer.

2.3 MANUFACTURED UNITS

- .1 Text Door Sign Plates: Surface engraved type; 2.0 mm thick dual-layered acrylic with 30 degree bevelled edges; as follows:
 - .1 Length: As required to fit text, minimum 300 mm;
 - .2 Height: 57.2 mm high;
 - .3 Text: 25 mm high Helvetica upper and lower case letters;
 - .4 Fastening: Pre-drilled 5 mm OD holes to accommodate countersunk fasteners, centered along left and right edges;
 - .5 Colours: As selected by Consultant from manufacturer's complete colour selection;
 - .6 Text: As determined by Owner.
- .2 Pictogram Door Sign Plates: 3.2 mm thick plexiglass, square edged, hot stamped or silk screened image on rear face, 150 mm high; pre-drilled 5 mm OD holes to accommodate countersunk fasteners, centered along left and right edges; sizes, colours, and graphic symbols as selected by Consultant.

2.4 FABRICATION

- .1 Fabricate sign plates with letters and numbers centered within sign plate's length and height.
- .2 Provide countersunk holes for screw fasteners.

2.5 FINISHES

- .1 Stainless Steel: To AISI No. 4 - Brushed.
- .2 Chrome/Nickel Plating on Metal Components: To ASTM B456, Type SC 2; electrodeposited nickel plus chromium coating; Polished.

- .3 Anodized Coating on Aluminum: To AAMA 611, AA-M10C21A41, Class I Clear Anodic Oxide coating (No. 14 - Clear).
- .4 Monochromatic Paint Coating on Aluminum: To AAMA 2605; three-coat thermosetting fluoropolymer PVDF liquid extrusion and coil coating, factory-applied to 0.04 mm dry film thickness; eg. Duranar XL by PPG Industries, Inc., colour as selected by Consultant.
- .5 Metallic Paint Coating on Aluminum: To AAMA 2605; three-coat thermosetting fluoropolymer PVDF liquid extrusion and coil coating, complete with metal flakes incorporated in the colour coat; factory-applied to 0.04 mm dry film thickness; eg. Duranar XL by PPG Industries, Inc., colour as selected by Consultant.
- .6 Powder Coated Finish on Metal Components: To AAMA 2605; electrostatically sprayed polymer powder, factory-applied to 0.075 mm dry film thickness, with 4H Hardness rating to ASTM D3363; colour as selected by Consultant.
- .7 Galvanized Coating on Steel Components: To ASTM A123/A123M, Coating Grade 55; hot dipped zinc alloy coating.
- .8 Galvanized Coating on Steel Hardware: To ASTM A153/A153M, Classes B3, C or D; hot dipped zinc alloy coating.
- .9 Galvanized Coating on Sheet Steel: To ASTM A653/A653M, Coating Designation Z275; hot dipped zinc alloy coating.

3 Execution

3.1 INSTALLATION

- .1 Install Products straight, plumb, and level.
- .2 Secure Products to substrate in a manner to prevent distortion or displacement.
- .3 Finished work shall be free of defects, warping, open seams, and rattles.
- .4 Provide double-sided foam tape adhesive on rear face of sign plates prior to securing with mechanical fasteners.
- .5 Provide routing or mortising for items required to be mortised, rebated, or otherwise housed within material.
- .6 Replace Products that are bent, scratched, or damaged.
- .7 Provide fasteners to full required complement, properly tightened.
- .8 Exposed fasteners shall be neatly executed, and shall match adjacent surfaces.
- .9 Install braille and tactile character signage adjacent to sign plates.
- .10 Do not fasten signage through acoustically-rated or fire-rated doors.
- .11 Coordinate connections to power supply with Section 26 05 00.

3.2 PROTECTION

- .1 Refer to Section 01 76 00.
- .2 Protect installed Products with temporary removable film.
- .3 Maintain protection until Owner occupancy.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 04 00 00 - Masonry.
 - .2 Section 09 21 16 - Gypsum Board Assemblies.
- 1.2 REFERENCES
 - .1 AAMA 2604-22: Voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels (With Coil Coating Appendix).
 - .2 ASTM B209/B209M-21a: Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate.
 - .3 ASTM B221M-21: Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes (Metric).
 - .4 Canada Consumer Product Safety Act, SOR/2019-97: Corded Window Coverings Regulations.
 - .5 NFPA 701-2004: Methods of Fire Tests for Flame Propagation of Textiles and Films.
 - .6 CAN/ULC-S109-14 (R2019): Standard Method for Flame Tests of Flame-Resistant Fabrics and Films.
 - .7 ANSI/WCMA A100.1-2018: American National Standard for Safety of Corded Window Covering Products.
- 1.3 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating materials, components and accessories, component sizes, available fabrics and finishes, and installation instructions.
- 1.4 SHOP DRAWINGS
 - .1 Submit Shop Drawings as specified in Section 01 33 00.
 - .2 Shop Drawings: Project-specific drawings, illustrating wall opening dimensions, shade sizes, operator details, top rail, anchorage details, joint locations, hardware and accessory details, conditions between adjacent units, corner conditions, and required clearances.
- 1.5 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Selection Samples: Duplicate 200 x 200 mm size samples of each specified shade fabric, demonstrating available colours for selection by Consultant.
 - .3 Verification Samples: Duplicate samples of the following:
 - .1 Shade Fabric: 200 x 200 mm size samples of each specified fabric, verifying openness factor and colour selection.
 - .2 Visually-Exposed Components: 300 mm long samples of each visually-exposed component, illustrating material, colour, surface texture and sheen.
 - .3 Metal Finish: 50 x 100 mm size samples, illustrating specified finish and colour.
- 1.6 SOURCE QUALITY CONTROL SUBMITTALS
 - .1 Submit source quality control submittals as specified in Section 01 33 00.

- .2 Fire Test Reports: Manufacturer's standard fire test reports, prepared by independent testing agency deemed acceptable by authorities having jurisdiction, indicating fire hazard classification of shade fabric meets regulatory requirements.
- 1.7 CLOSEOUT SUBMITTALS
- .1 Submit closeout submittals as specified in Section 01 78 00.
 - .2 Operation and Maintenance Data: Manufacturer's standard operating instructions, and maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.
- 1.8 QUALIFICATIONS
- .1 Supplier: A manufacturer-certified firm, approved to supply specified Products and to honour warranty claims.
 - .2 Installer: A manufacturer-certified firm, trained and experienced in installing specified Products.
- 1.9 DELIVERY, STORAGE AND HANDLING
- .1 Refer to Section 01 60 00.
 - .2 Protect Products with suitable heavy weight wrapping before delivery to Place of the Work.
 - .3 Store Products at Place of the Work in a designated area, allowing for natural ventilation over finished surfaces.
- 1.10 WARRANTY
- .1 Submit extended warranty in accordance with General Conditions of the Contract.
 - .2 Extended Warranty: For a period of 5 years, covering complete replacement cost of defective Product, including removal and disposal of defective assembly, and installation of replacement Product. Covered defects to include the following:
 - .1 Fading of shade fabric colour,
 - .2 Shrinkage of shade fabric,
 - .3 Loss of flame-retardant properties of shade fabric,
 - .4 Punctures, rips or tears in shade fabric, and
 - .5 Mechanical failure of operating mechanisms.
- 2 Products
- 2.1 MANUFACTURERS
- .1 Manufacturers having Product considered acceptable for use:
 - .1 Altex Inc.
 - .2 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 DESCRIPTION
- .1 Roller Window Shades (RWS-1): Manual wand-controlled operation, single sprocket roller shade, rectangular-shaped, with infinite positioning; each unit consisting of two end brackets, shade roller tube, cassette fascia, exposed hembar, and sun control fabric; sizes as indicated on Drawings.

- .2 Roller Window Shades (RWS-2): Manual wand-controlled operation, dual sprocket roller shade, rectangular-shaped, with infinite positioning; each unit consisting of two end brackets, shade roller tubes, cassette fascia, exposed hembars, one roller for blackout fabric and one roller for sun control fabric; sizes as indicated on Drawings.

2.3 DESIGN CRITERIA

- .1 Basis of Design: Newton High-Speed Lite-Lift with Fascia by Altex Inc.
- .2 Design manual roller window shades to operate without any exposed cords or chains, in accordance with Canada Consumer Product Safety Act SOR/2019-97 and ANSI/WCMA A100.1.
- .3 Design system to allow lowering shade by pulling on hembar without damaging clutch or spring.
- .4 Design system with embedded upper limit stop device to ensure constant upper position and avoid shade being over lifted.
- .5 Design system to be operable with one hand, from any height while sitting.
- .6 Design system to be operated using two wands per roller, as follows:
 - .1 Front Wand: To raise shade.
 - .2 Rear Wand: To lower shade.

2.4 PERFORMANCE CRITERIA

- .1 Fire Classification of Fabrics: Flame-retardant and fire-resistant to CAN/ULC-S109 and NFPA 701.
- .2 Required Lifting Force: Minimum 1.134 kg and maximum 1.814 kg to raise or lower shade.
- .3 Operating Speed: ≥ 1.0 m/s.
- .4 Durability: $\geq 5\ 500$ cycles.

2.5 MATERIALS

- .1 Extruded Aluminum: To ASTM B221M, 6063 alloy, T5 temper; unless specified otherwise.
- .2 Sheet Aluminum: To ASTM B209/B209M, 3003 alloy, H14 temper.
- .3 Plastic: ABS type.
- .4 Sun Control Fabric: Vinyl-coated polyester yarn, consisting of 79 percent vinyl and 21 percent denier polyester core yarn; three percent openness factor, complete with antimicrobial coating; tensioned prior to heat setting; colour as selected by Consultant.
- .5 Blackout Fabric: Totally opaque, first quality materials with no pinholes, breaks, or cracks; 4-ply opaque close woven fibreglass base textile with sun resistant vinyl film; colour as selected by Consultant.
- .6 Bituminous Coating: Fibrous asphalt emulsion.
- .7 Screw Fasteners: Non-corrosive type, size as recommended by shade manufacturer.

2.6 COMPONENTS

- .1 End Bracket: 77 x 96 mm, two-piece moulded ABS construction; 64 mm OD nylon drive sprocket; finish to match fascia colour.
- .2 Shade Roller Tube: 1.52 mm thick extruded aluminum with three internal 4.82 mm high continuous fins spaced 120 degrees apart.

- .3 Cassette: Two-piece interlocking 1.9 mm thick extruded aluminum housing, rectangular profile.
- .4 Fascia: 1.7 mm thick extruded aluminum complete with three continuous screw flute.
- .5 Drive Assembly: Factory set for size and travel of shades, field adjustable; complete with built-in shock absorber.
- .6 Wand: Extruded aluminum, with powder coated finish to match assembly.
- .7 Hem Bar: 32 x 19 mm size, extruded aluminum, with upper groove to secure shading fabric; complete with high-impact nylon plugs inserted into each end.

2.7 FINISHES

- .1 Powder Coated Finish on Metal Components: To AAMA 2604; electrostatically sprayed polymer powder, factory-applied to 0.05 mm dry film thickness; colour as selected by Consultant.

3 Execution

3.1 PREPARATION

- .1 Apply heavy coat of bituminous paint on aluminum surfaces placed in direct contact with concrete, mortar, plaster, or dissimilar metals.
- .2 Provide fastenings and anchors required to be built in to adjacent work to other Sections.

3.2 INSTALLATION

- .1 Install Products inside window openings, level, plumb, and square.
- .2 Install Products parallel with window plane.
- .3 Install Products rigidly coupled and adequately anchored.
- .4 Maintain uniform clearances and accurate alignment levels.
- .5 Conform to manufacturer's Product data and accepted Shop Drawings.
- .6 Conceal brackets and rollers with closure panels for full width of opening.

3.3 TOLERANCES

- .1 Gap Variation Along Perimeter: ≤ 6 mm per 2 440 mm of shade height.
- .2 Offset from Level: ≤ 3 mm.
- .3 Conform to manufacturer's edge clearance requirements for shades exceeding 1:3 width-to-height ratio.

3.4 ADJUSTING

- .1 Adjust Products to ensure smooth and trouble free operation, without binding.
- .2 Adjust shade and fabric to hang flat without buckling or distortion.
- .3 Leave shades in raised position upon completion.

3.5 CLEANING

- .1 Refer to Section 01 74 00.

- .2 Clean exposed surfaces using recommended non-abrasive materials and methods.

3.6 DEMONSTRATION

- .1 Refer to Section 01 79 00.
- .2 Demonstrate proper operation and maintenance of roller shades.

END OF SECTION

- 1 General
- 1.1 RELATED SECTIONS
 - .1 Section 06 10 00 - Rough Carpentry.
- 1.2 ALLOWANCES
 - .1 Contract Price includes a stipulated sum cash allowance as specified in Section 01 21 00.
 - .2 Cash Allowance: For supply and installation of musical instrument storage cabinets.
- 1.3 PRODUCT DATA
 - .1 Submit Product data as specified in Section 01 33 00.
 - .2 Product Data: Manufacturer's standard data sheets, indicating applicable reference standards, performance data, application recommendations, and Product limitations.
- 1.4 SAMPLES
 - .1 Submit samples as specified in Section 01 33 00.
 - .2 Selection Samples: Duplicate 150 x 150 mm size, illustrating colour availability of decorative laminate, edge banding, and hardware.
- 1.5 CLOSEOUT SUBMITTALS
 - .1 Submit closeout submittals as specified in Section 01 78 00.
 - .2 Operation and Maintenance Data: Manufacturer's standard maintenance and cleaning guidelines; sufficient quantity for inclusion in operation and maintenance manual.
- 1.6 DELIVERY, STORAGE AND HANDLING
 - .1 Refer to Section 01 60 00.
 - .2 Deliver and store Product in protective packaging, and in a manner suitable to protect factory finishes.
 - .3 Store Product in an indoor location, near point of installation.
- 1.7 WARRANTY
 - .1 Submit extended warranty in accordance with General Conditions of the Contract.
 - .2 Extended Warranty: Manufacturer's extended warranty protecting against defective Products for a period of three years.
- 2 Product
- 2.1 MANUFACTURERS
 - .1 Manufacturers having Product considered acceptable for use:
 - .1 Wenger.
 - .2 Substitution Procedures: Refer to Section 01 25 00.
- 2.2 MANUFACTURED UNITS
 - .1 Fixed Storage Units: Laminate-faced particle board construction, with solid PVC edgebanding on exposed edges, lockable compartment doors; quantities, sizes, and configurations as indicated on Drawings; colours as selected by Consultant.

- .2 Percussion Workstation: Laminate-faced particle board construction, with solid PVC edgebanding on exposed edges, lockable compartment doors, padded top and foam-lined drawers; complete with 4 heavy duty casters; Percussion Workstation Model 147G002 by Wenger, colour as selected by Consultant.
 - .3 Stringed Instrument Racks: Laminate-faced particle board construction, with solid PVC edgebanding on exposed edges; complete with 4 heavy duty casters; colours as selected by Consultant; types as follows:
 - .1 String Bass Rack: Model 148F003 by Wenger.
 - .2 Cello Rack: Model 148F001 by Wenger.
 - .3 Violin / Viola Rack: Model 148F005 by Wenger.
- 3 Execution
- 3.1 INSTALLATION
- .1 Set and secure components in place, rigid, square, and plumb.
 - .2 Provide wood blocking, framing, or furring necessary to secure fixed storage units. Refer to Section 06 10 00.
- 3.2 PROTECTION
- .1 Refer to Section 01 76 00.
 - .2 Protect installed Products from being defaced.

END OF SECTION

Part 1 - General

1.1 REFERENCE

- .1 Division 00 and Division 01 apply to and are a part of each Electrical Division Section.

1.2 APPLICATION

- .1 This Section specifies products, criteria and characteristics, and methods and execution that are common to one or more Sections of Electrical Divisions. It is intended as a supplement to each Section of Electrical Divisions and is to be read accordingly.

1.3 SUBMITTALS

- .1 Submit shop drawings for products of this Section.
- .2 Additionally as part of shop drawing submission process, submit following to Consultant for review:
 - .1 sample of each proposed type of access door if supplied under work of this Division, as well as electronic copies of reflected ceiling plan drawings and wall elevation drawings showing proposed access door locations;
 - .2 dimensioned location drawings indicating required sleeves and formed openings in structural poured concrete or precast concrete construction or in roofing, and locations of cutting or drilling required for Electrical Divisions work;
 - .3 samples of materials and any other items as specified in succeeding Sections of Electrical Divisions;
 - .4 weight loads of selected equipment (upon request);
 - .5 equipment nameplate and warning sign proposed nomenclature, print type, symbols, sizing and colours;
 - .6 fire stopping installation drawings with ULC certifications;
 - .7 copies of prior to start of construction approvals from local governing authorities having jurisdiction.
- .3 Prior to application for Substantial Performance of the Work, submit following to Consultant for review (note: funds will be withheld until each of following items have been completed and documented to satisfaction of Consultant):
 - .1 fire alarm system testing and verification report of each component of work; devices to be certified working and in proper order;
 - .2 final distribution system testing and arc flash study performed and documented to satisfaction of Consultant;
 - .3 structured network cabling system tested and verified to be operating and performing in accordance with specified standards.

1.4 CONTINUITY OF SUPPLY FOR STANDARDIZATION

- .1 Utilize materials of one manufacturer for aspects of work, where practical. Utilize one common manufacturer for wiring devices, such as switches and receptacles, whether installed loose or in a pre-manufactured component. Coordinate with each supplier and ensure conformance with this requirement. Identify deviations to Consultant and obtain approval of change prior to proceeding with work.

1.5 HAZARDOUS MATERIALS

- .1 Hazardous materials and infectious materials are known to be present on site in existing buildings, including but not limited to following:
 - .1 aspergillus;
 - .2 mould;

- .3 asbestos;
 - .4 PCBS;
 - .5 lead;
 - .6 mercury.
- .2 Division 01 identifies specific requirements and if such materials are present, include for costs to be educated and trained on special working conditions, to work in areas with hazardous materials including protective clothing, gear, tenting, enclosures, etc., and perform necessary partitioning/tenting/ventilation work to isolate areas and maintain disturbances of such materials to a minimum. Comply with infection control requirements and those of governing local Health and Welfare authority. An asbestos abatement report is available for review from Consultant. Unless otherwise noted, any abatement removal is responsibility of another Division of Work.
- .3 If proper abatement procedures are not followed, be responsible for bearing full cost of a full time qualified abatement inspector chosen by Owner. In areas where work is being done above or below an area being occupied, any slab penetrations into vertically adjacent occupied space are to utilize a proper enclosure in area of that work on that occupied floor. Be responsible for failure to comply with special requirements in working in areas of hazardous materials.
- .4 Include for company specializing in removal and disposal of materials containing PCB's to remove and dispose off-site luminaire ballasts containing PCB's. Check luminaires being deleted for ballasts containing PCB's. Disconnect and dispose off-site such ballasts. Only companies that are certified and comply with Ministry of Environment and Ministry of Transport regulations with regards to hazardous waste materials are to be used to perform this Work. Prior to start of Work, submit to Consultant a copy of PCB disposal certificate and identification of Ministry authorized and designated disposal site.
- .5 Fluorescent lamps being replaced and containing mercury are to be properly transported offsite and disposed of as per local governing Ministry guidelines.

1.6 PRODUCT REQUIREMENTS IN SPECIAL AREAS

- .1 Products in non-climate controlled areas are to include weatherproof provisions such as gasketed covers, corrosion resistant hardware, weatherproof finishes, etc. Devices to be manufactured to operate in extreme temperatures.

Part 2 - Products

2.1 CONDUITS

- .1 EMT (Thinwall), galvanized electrical metallic tubing to CSA C22.2 No. 83, complete with factory made bends where site bending is not possible and joints and terminations made with steel couplers and steel set screw type connectors with insulated throats, and concrete tight where required.
- .2 Rigid galvanized steel to CSA C22.2 No. 45, with exterior zinc and interior enamel coatings, galvanized threads where factory cut and red lead coated threads where site cut. Factory made bends where site bending is not possible, factory made and threaded fittings, and connectors, and terminations with rigid couplings, and concrete tight where required.
- .3 Galvanized steel flexible liquid tight metallic conduit to CSA C22.2 No. 56, complete with Ideal "Steel Tough" liquid-tight flexible conduit connectors at terminations.
- .4 Galvanized steel flexible metallic conduit to CSA C22.2 No. 56, complete with proper and suitable squeeze type connectors at terminations.

- .5 CSA approved and labelled, FT-4 rated, rigid plastic (PVC) conduit complete with site made heat gun bends on conduit to 50 mm (2") diameter, factory made elbows in conduit larger than 50 mm (2") diameter, solvent weld joints, factory made expansion joints where required, and terminations made with proper and suitable connectors and adaptors.

2.2 OUTLET BOXES

- .1 CSA approved stamped galvanized steel outlet boxes for all recessed device installations.
- .2 CSA certified rigid plastic (PVC) outlet boxes.
- .3 Standard general purpose service floor boxes: CSA approved, UL scrub water compliant, fully adjustable angular and vertically, formed steel/cast iron, round single gang / rectangular or square multi-gang as required, flush in concrete floor installation, boxes complete with conduit knockout openings, adjustable collars, hinged flip open brass covers with provisions for mounting of duplex power receptacles, telephone jacks and data jacks. Provide barriered boxes when boxes contain both power and communication outlets and different voltage levels. Size boxes to suit thickness of floor slab as confirmed with Consultant and also to suit required bending radii of conductors. Refer to drawings for number of gang requirements. Acceptable manufacturers are Hubbell, Legrand and Thomas & Betts. Special floor boxes are specified elsewhere in another Section.
- .4 Each outlet box and back box to be suitable in respects for application and complete with suitable securing lugs, connectors suitable for connected conduit, knockouts and, where necessary, suitable plaster rings, concrete rings, covers, carpet flanges and any other required accessory.
- .5 Electrical boxes exposed exterior of building or in non-climate controlled locations to be weatherproof boxes complete with gasketed covers/faceplates.

2.3 PULL BOXES & JUNCTION BOXES

- .1 Galvanized or prime coat plated steel, suitable in respects for application and complete with screw-on or hinged covers as required, and connectors suitable for connected conduit.
- .2 Eaton Crouse-Hinds, "Condulet", threaded cast Feraloy outlet boxes of an exact type to suit application, each complete with screw-on gasketed cover.
- .3 Rigid plastic (PVC), CSA certified, junction boxes and access fittings with solvent weld type joints and screw-on PVC covers.
- .4 Physical size of pull boxes to be as required by local governing electrical code to suit number and size of conduits and conductors.
- .5 Each box to be suitable in respects for application and complete with suitable securing lugs, connectors suitable for connected conduit, knockouts and, where necessary, suitable plaster rings, concrete rings, covers and any other required accessory.
- .6 Boxes exposed exterior of building or in non-climate controlled locations to be weatherproof boxes complete with gasketed covers.

2.4 SLEEVES

- .1 Galvanized steel sleeves as follows:
 - .1 No. 24 gauge with an integral flange at one (1) end to secure sleeve to formwork construction;
 - .2 Schedule 40 pipe;
- .2 Schedule 40 PVC sleeves.

2.5 FIRESTOPPING & SMOKE SEAL MATERIALS

- .1 Asbestos-free, elastomeric materials and intumescent materials, tested, listed and labelled by ULC in accordance with CAN 4-S115-M85, and CAN/ULC-S101-M for installation in ULC designated firestopping, and smoke seal systems to provide a positive fire, water and smoke seal and a fire resistance rating (flame, hose stream and temperature) no less than fire rating for surrounding construction.
- .2 Fire stopping and smoke seal material system to be specifically ULC certified with designated reference number for its specific installation. As part of shop drawing submission, submit copies of firestopping drawings with ULC certificate and number for each specific installation. Submit schedule of opening locations and sizes, penetrating items, and required listed design numbers to seal openings to maintain fire resistance ratings.
- .3 Systems to consist of both elastomeric and intumescent materials that are compatible with abutting dissimilar materials and finishes. Coordinate material requirements with trades supplying abutting areas of materials.
- .4 Typically, for openings of up to 250 mm (10") in diameter, provide putty pad type firestop materials equivalent to Specified Technologies Inc. "SpecSeal" intumescent, non-hardening, water resistant putties containing no solvents, inorganic fibres or silicone compounds.
- .5 Typically, for openings of greater than 250 mm (10") in diameter, and for rectangular openings, provide pillow type firestop materials equivalent to Specified Technologies Inc. "SpecSeal" re-enterable, non-curing, mineral fibre core encapsulated on six sides with intumescent coating contained in a flame retardant poly bag.
- .6 Supply products of a single manufacturer for use on work of this Division.
- .7 Installer to be manufacturer trained and certified on specific product. Submit copy of certificate with shop drawings.
- .8 Include for manufacturer authorized representative to inspect and verify each installation and application. Submit test report signed and verified by system installer's authorized representative and manufacturer representative.
- .9 Acceptable certification to also include certification by Underwriters Laboratories of Northbrook IL, using tests conforming to ULC-S115 and given cUL listing published by UL in their "Products Certified for Canada (cUL) Directory".
- .10 Acceptable manufacturers are:
 - .1 Hilti Canada;
 - .2 Specified Technologies Inc.;
 - .3 3M Canada Inc.;
 - .4 Tremco;
 - .5 A/D Fire Protection Systems;
 - .6 Nelson.

2.6 FASTENING & SECURING HARDWARE

- .1 Concrete inserts - Crane Canada Ltd., No. 4-M for concrete work for single or double conduit, cable tray, etc., runs and equipment. Unistrut Ltd. multiple type inserts for runs of three (3) or more conduits etc., or where a grid support system is required.
- .2 Concrete fasteners - "WEJ-IT" anchors, lead cinch anchors and/or "STAR" or "PHILLIPS" self-drilling anchors.
- .3 Masonry inserts - "WEJ-IT" expansion shields and machine bolts or, for light loads, fibre or lead plugs and screws.
- .4 Drywall or plaster wall and/or ceiling fasteners - 2-wing spring toggles.
- .5 Structural steel - Crane Canada Ltd., beam clamps.

- .6 Metal framing channels - 40 mm (1-5/8") width, galvanized steel channels complete with required fittings and ancillary hardware; acceptable manufacturers are:
 - .1 Unistrut;
 - .2 Thomas & Betts;
 - .3 Hilti;
 - .4 Eaton B-Line.
- .7 Metal "J" hooks or Panduit "J-Pro" cable support systems for communications system cabling in accessible ceiling spaces where conduit or cable tray is not being provided. Obtain written approval of Consultant for use of J-hooks.
- .8 Velcro tie wraps for bundling and securing cables.

2.7 ACCESS DOORS

- .1 Access doors to be provided under work of Division 08 by General Trades Contractor.
- .2 Coordinate with Mechanical Contractor and General Trades Contractor to ensure that access doors on project are provided by a single manufacturer, installed as part of work of General Trades Contractor and that work involving both mechanical and electrical services to where possible be accessible from common access door. Coordinate work to ensure that same common location access doors are not supplied by more than one Division.
- .3 Size access door to suit concealed work for which they are supplied and wherever possible they are to be of standard size for all applications, but in any case they are to be minimum 300 mm x 300 mm (12" x 12") for hand entry and 600 mm x 600 mm (24" x 24") for body entry.
- .4 Access doors in fire rated ceilings, walls, partitions, structures, etc., to be ULC listed and labelled and of a rating to maintain fire separation integrity.
- .5 Identify on reflected ceiling plans and wall elevation drawings, coordinated locations of proposed access door locations and submit to Consultant for review.

2.8 IDENTIFICATION NAMEPLATES

- .1 Laminated plastic (Lamacoid) black-white-black with bevelled edges, stainless steel screws, and proper identification engraving. Each nameplate to be sized to suit equipment for which it is provided, and required wording. Confirm nomenclature with Consultant. Various colour configurations to be used to differentiate systems. Confirm exact colour scheme with Consultant and/or Owner.
- .2 Brother "P-Touch", portable electronic labelling system complete with self-adhesive, permanent printed labels with required nomenclature.

2.9 SYSTEM BACKBOARDS

- .1 FSC (Forest Stewardship Council), G1S (good one side) construction grade fir plywood, containing no added urea formaldehyde, flame retardant prime coat painted on exposed surfaces, minimum 20 mm (3/4") thick, as sized on drawings and with flame spread rating in accordance with local governing building code requirements.

2.10 MOTOR STARTER PANELS

- .1 Minimum No. 14 gauge sheet steel panels complete with steel angle reinforcing, framing and suitable splitter trough, fully primed and enamel painted, sized to accommodate starters required with spare space and capacity for at least two additional units.

2.11 SPRINKLER PROTECTION

- .1 Provide drip shields for protection of surface mounted equipment enclosures from water spray and dripping of liquids. Features of shields include:

- .1 factory constructed by respective equipment manufacturers;
 - .2 constructed from non-combustible materials (sheet steel);
 - .3 enamel painted to match equipment;
 - .4 surfaces and edges filled/sanded smooth prior to painting;
 - .5 supported from equipment with structural steel rods/metal framing or other method approved by Consultant;
 - .6 structural support finish painted to match shield.
- .2 Include with equipment shop drawings, detailed dimensions of drip shields and methods of supporting.
 - .3 Equipment with top cable/conduit entries to include additional sealing of entries with gasketing and/or waterproof sealant to prevent water from entering enclosure.
 - .4 Design ventilation louvers such that live components are not exposed to water spray and dripping liquids.
 - .5 Above requirements are additional minimum "sprinkler protection" standards for equipment specified as EEMAC/NEMA 1, 2 or 12.
 - .6 Obtain CSA approval where required by local governing authorities.

2.12 ROOFTOP CONDUIT SUPPORT SYSTEM

- .1 Cooper B-Line "Dura - Blok" series rooftop support systems with features as follows:
 - .1 CSA approved and/or ULC listed and labelled;
 - .2 non-penetrating of roof;
 - .3 vibration dampening;
 - .4 does not float;
 - .5 suitable for outdoor wet and freezing environments without damage caused by weather or freeze and thawing when exposed to de-icing chemicals;
 - .6 environmental friendly;
 - .7 constructed of recycled rubber.
- .2 Materials:
 - .1 Dura-Blok Curb base made of 100% recycled rubber and polyurethane pre-polymer with a uniform load capacity to suit specific load application of support (minimum 744 kg/m [500 pounds/linear foot]); each base to have a reflective red stripe.
 - .2 DB Series base: Dimensions: 150 mm (6") wide by 125 mm (5") tall by required overall length (minimum 225 mm [9"]); this is to be minimum dimensions, but base requirements must be increased to suit specific applications as recommended by system manufacturer; includes low base steel frame C channel 1.9 mm (14 gauge) - 25 mm (1") high strut galvanized per ASTM A653; and pipe roller assembly.
 - .3 Attaching hardware: Zinc-plated threaded rod, nuts and attaching hardware per ASTM B633.
 - .4 Conduit clamps: single pipe supports constructed of galvanized steel and sized to accommodate sizing of installed conduits.
- .3 Confirm with system manufacturer that selected products provide proper support for application.
- .4 Acceptable manufacturers are as follows:
 - .1 Cooper B-Line;
 - .2 Clearline Technologies (C-Port);
 - .3 Erico (Caddy Pyramid).

Part 3 - Execution

3.1 GENERAL CONDUIT INSTALLATION REQUIREMENTS

- .1 Install conduit concealed in finished areas, and concealed to degree made possible by finishes in partially finished and unfinished areas. Conduit may be exposed in unfinished areas such as Electrical and Mechanical Rooms, unless otherwise noted on drawings or specified herein. Refer to and examine architectural drawings and room finish schedules to determine finished, partially finished or unfinished areas of building. Documents do not identify exact routing. Where shown, routing is diagrammatic, identifying general requirements of routing and locations. Include for necessary offsets, fittings, transformations and similar items required as a result of obstructions and other architectural or structural details not shown.
- .2 Where conduits are exposed, arrange them to avoid interference with other work, parallel to building lines and install as high as possible. Do not install conduits within 150 mm (6") of "hot" pipes or equipment unless conduits are associated with equipment. Independently run conduit to be supported from wall/ceiling structure, not from ceiling hangers, ductwork, piping, cable trays, formed steel decking, etc. Do not run conduits within 900 mm (3') of equipment access opening covers.
- .3 So as not to impair required strength of structure, following criteria to be generally followed but which is to be reviewed and coordinated with Consultant prior to start of Work:
 - .1 where conduits pass by a column, stay at least two times thickness of slab and drop away from column;
 - .2 where conduits terminate adjacent to a column or wall, bring conduit in toward column/wall as close to 90° to face of column as possible within two times thickness of slab and drop away from column;
 - .3 maximum size of conduit in structural slabs is 1/5 of solid portion of slab thickness;
 - .4 where more than two conduits are adjacent to each other, they are to be spaced greater of 3 diameters or 100 mm (4") apart;
 - .5 total of depth of conduits crossing over each other is to be less than one-third thickness of slab;
 - .6 place conduit in middle third of thickness of slab; do not lay conduit directly on reinforcing steel;
 - .7 do not run conduit adjacent to parallel reinforcing bars;
 - .8 do not run conduit longitudinally in beam without approval of Owner and review with Consultant; pass through beams at right angles to span of beam;
 - .9 where conduits pass through beams, maintain at least twice depth of beam separation away from supports;
 - .10 do not run conduits in slab beside a drop or beam within twice depth of slab from edge of drop or beam;
 - .11 do not run conduits through shear walls or columns without approval of Owner and review with Consultant;
 - .12 do not place conduit in structural elements in parking garage structures, water retaining structures or structures subjected to de-icing chemicals, without approval of Owner and review with Consultant.
- .4 Conduits are sized on drawings, but in absence of type and sizing, type and size to suit intended application in accordance with applicable local governing electrical code requirements. Sizes identified on drawings are minimum sizes and are not to be decreased unless approved by Owner and reviewed with Consultant.
- .5 Minimum conduit size shall be 3/4" unless otherwise noted.

- .6 Where receptacle type devices are located in existing floors and/or where feeds are required to furniture systems in open spaces, and where chasing of floor slab to run conduit is not acceptable to Owner after review with Consultant provide fire rated "poke-thru" assembly installed through floor and feed from conduit runs provided in ceiling space of floor below.
- .7 Mounting heights of devices may be typically identified on drawings, but such dimensions are for general pricing only. Review exact mounting heights with Consultant prior to roughing-in, refer to Architectural drawings and comply with local governing codes and standards including building code barrier free requirements.

3.2 **INSTALLATION OF CONDUIT**

- .1 Provide conduit for conductors except armoured cable and copper sheathed mineral insulated conductors, and except where duct or similar raceway materials are provided.
- .2 Provide conduit as follows:
 - .1 for interior building surface mounted services greater than 600 V - rigid galvanized steel;
 - .2 for branch circuit conductors underground inside building, and underground outside building beneath concrete, asphalt, and similar paving material-rigid PVC;
 - .3 for exposed conduit mounted at a height of less than 1200 mm (4') in electrical, mechanical or other service areas - rigid galvanized steel;
 - .4 for short branch circuit connectors to motorized equipment and distribution transformers (minimum length 450 mm (18"), maximum length 600 mm (24") with 180° loop where possible) - galvanized steel flexible liquid-tight conduit;
 - .5 for branch circuit conductors associated with isolated power systems and located in a concealed space in a wall or in a concrete floor slab-rigid PVC with separate insulated ground conductor;
 - .6 at points, where conductors cross building expansion joints - galvanized steel flexible conduit with no less than 600 mm (24") of extra curve;
 - .7 for branch circuit conductors in poured concrete slab - rigid PVC;
 - .8 for interior conduit above 50 mm (2") diameter containing distribution conductors or communication systems conductors (fire alarm, telephone etc.) (except as noted above) - EMT with separate insulated ground conductor;
 - .9 for corrosive environments - epoxy coated rigid steel;
 - .10 for conductors except as noted above or elsewhere in this Specification - EMT.
- .3 Run rigid conductors in rigid type conduits suitable for application. Do not use flexible conduit.
- .4 Secure conduit located in poured concrete work in place in a manner such that conduit will not float or move when concrete is poured. Adequately protect such conduit from damage prior to and during concrete pour, and from concrete and water penetration.
- .5 Review with Consultant prior to Start of Work, maximum allowable size of conduit for installation in poured concrete. Placement of reinforcing steel in structural concrete work will take precedence over placement of conduit. Spaced adequately multiple runs of conduit in poured concrete work, as reviewed with Consultant.
- .6 Install flexible polyethylene conduit in continuous lengths wherever possible and "snake" conduit in trench. Where joints are necessary, make same with nylon inserts and stainless steel gear type clamps. Terminate with rigid conduit threadless connectors. Grade bed to provide proper drainage of conduits.

- .7 Support underground conduit on a well-tamped flat bed of earth, free from rocks or protrusions of any kind. Grade and slope bed to provide conduits and ducts with proper drainage. Coordinate with General Trades Contractor for provision of means to carry away drainage water. Obtain required approvals of work from local governing electrical utility and review with Consultant prior to back filling and covering. Provide pull cord in each duct run.
- .8 Provide manufactured expansion joints in rigid PVC plastic conduit at spacing as recommended by conduit manufacturer.
- .9 Provide a separate ground conductor in plastic conduits.
- .10 Support and secure surface mounted and suspended single or double runs of metal conduit at support spacing in accordance with local governing electrical code requirements by means of galvanized pipe straps, conduit clips, ringbolt type hangers, or by other proper manufactured devices.
- .11 Support multiple mixed size metal conduit runs with Unistrut Ltd., Electrovert Ltd. "CANTRUSS" or Burndy Ltd. "FLEXIBLE" conduit racks spaced to suit spacing requirements of smallest conduit in group.
- .12 Unless otherwise noted, provide conduit fittings constructed of same materials as conduit and which are suitable in respects for application.
- .13 Provide proper adaptors for joining conduits of different materials.
- .14 Cut square and properly ream site cut conduit ends.
- .15 Provide conduit as sized on drawings. Size conduit not sized on drawings in accordance with latest edition of local governing electrical code with consideration that sizes of branch circuit conductors indicated are minimum sizes and must be increased as required to suit length of run and voltage drop in accordance with voltage drop schedule found on drawings or at end of this section. Where conductor sizes are increased to suit voltage drop requirements, increase scheduled or specified conduit size to suit. Unless otherwise noted on drawings or required by local governing electrical code or specified elsewhere, conduit to be of minimum size 13 mm (1/2") diameter. Structured network cabling system conduit to be of minimum 19 mm (3/4") diameter, unless otherwise noted.
- .16 Site made bends for conduit to maintain full conduit diameter with no kinking, and conduit finishes are not flake or crack when conduit is bent.
- .17 Plug ends of roughed-in conduits which are exposed during construction with approved plugs.
- .18 Ensure that conduit systems which are left empty for future wiring are clean, clear, capped and properly identified at each termination point. Provide end bushing and suitable fish wires in such conduits.
- .19 Provide empty conduits to ceiling spaces from flush mounted panelboards located below and/or near hung ceiling. Refer to drawing detail.
- .20 Conduits shall be colour coded with paint located at junction boxes and every 5 feet along each run as follow:
 - .1 Yellow - Line voltage
 - .2 Red - Fire alarm
 - .3 Blue - Low voltage emergency lighting
 - .4 Green - Network cabling

3.3 EXPANSION FACILITIES FOR CONDUIT CROSSING BUILDING EXPANSION JOINTS

- .1 Wherever concealed or surface mounted conduits cross building expansion joints, provide expansion facilities to permit free movement without imposing additional stress or loading upon support system, and to prevent excessive movement at joints and connections, in accordance with drawing details and local governing inspection approvals.

3.4 INSTALLATION OF OUTLET BOXES & BACK BOXES

- .1 Provide an outlet box or back box for each luminaire, wiring device, telephone outlet, fire alarm system component, communications systems components, and each other such outlet.
- .2 Size boxes to accommodate exact supplied components and for bending radii of installed cables. Confirm requirements with respective system vendors.
- .3 Outlet boxes flush mounted in interior construction, surface mounted in concealed interior locations, to be stamped and galvanized steel outlet boxes unless otherwise noted.
- .4 Provide sealing around boxes in walls where insulation and vapour barrier is present or for walls of rooms that are sealed. Maintain sealing system of wall.
- .5 Outlet boxes in underground plastic conduit systems to be rigid PVC plastic outlet boxes, unless otherwise noted.
- .6 Outlet boxes for flush floor mounted devices to be concrete tight formed galvanized steel fully adjustable flush floor boxes. Locate in to position and install in accordance with manufacturer instructions. Coordinate installation with trades pouring concrete floor slab or trade responsible for floor construction.
- .7 Provide a barriered outlet box for switches connected to normal and emergency power and share a common faceplate.
- .8 Provide outlet boxes for special wiring devices, for special equipment and special applications. Refer to requirements specified in other Sections and/or on drawings.
- .9 Size and arrangement of outlet boxes to suit device which they serve.
- .10 Mounting heights and locations for outlet boxes are typically indicated on drawings, however confirm exact location and arrangement of outlets prior to roughing-in. Architectural drawings and Consultant's instructions have precedence over electrical drawing diagrammatic layouts and specified mounting heights and locations.
- .11 Do not install outlet or back boxes "back-to-back" in walls and partitions. Stagger such outlets and seal against noise transmission in accordance with drawing details. "Thru-wall" type boxes will not be permitted for any application.
- .12 Provide blank coverplates on existing obsolete boxes which are to remain in position.
- .13 Provide blank coverplates over boxes left empty for future installation of devices. Clearly identify each box as to its intended use, to Owner's approval and reviewed with Consultant.

3.5 INSTALLATION OF PULL BOXES & JUNCTION BOXES

- .1 Provide pull boxes in conduit systems wherever shown on drawings, and/or wherever necessary to facilitate conductor installations. Generally, conduit runs exceeding 30 m (100") in length, or with more than two - 90° bends, are to be equipped with a pull box installed at a convenient and suitable intermediate accessible location.
- .2 Size boxes to accommodate exact supplied system and for bending radii of installed cables. Confirm requirements with respective system vendors.
- .3 Provide junction boxes wherever required and/or indicated on drawings and as required by local governing electrical code.

- .4 Provide sealing around boxes in walls where insulation and vapour barrier is present or for walls of rooms that are sealed. Maintain sealing system of wall.
- .5 Boxes in rigid conduit and EMT inside building to be stamped galvanized or prime coated steel.
- .6 Boxes in exterior rigid conduit and boxes in perimeter wall where insulation and vapour barrier is present, to be "Condulet" cast gasketed boxes, unless otherwise noted.
- .7 Boxes in plastic conduit to be rigid PVC plastic boxes complete with required couplings.
- .8 Pull boxes and junction boxes to be accessible after work is completed.
- .9 Accurately locate and identify concealed pull boxes and junction boxes on "As-built" record drawings.
- .10 Clearly identify main pull or junction boxes (excluding obvious outlet boxes) with painted cover plate and machine printed labels. Text shall be minimum 3/8" high bold text font for legibility. Labelling to identify system, and source panel circuits for power wiring. Junction box covers to be colour coded as follow:
 - .1 Yellow - line voltage
 - .2 Red - Fire alarm
 - .3 Blue - Low voltage emergency lighting
- .11 Cover boxes in fire walls with aluminium tape and seal with caulking.

3.6 **INSTALLATION OF SLEEVES**

- .1 Where conduits, round ducts and conductors pass through structural poured concrete, provide sleeves of type suitable for application, and approved by local governing codes.
- .2 Sleeves in concrete slabs, except as noted below, are to be No. 24 gauge or equivalent, with an integral flange to secure sleeves for formwork construction.
- .3 Sleeves in waterproof concrete slabs and in other slabs where waterproof sleeves are required are to be lengths of Schedule 40 pipe sized to extend 100 mm (4") above floor.
- .4 Sleeves in poured concrete walls and foundation are to be Schedule 40 pipe.
- .5 Size sleeves, unless otherwise noted, to leave 13 mm (1/2") clearance around conduit, duct, conductor, etc. Void between sleeves and conduit, duct, conductors, etc., to be packed and sealed for length of sleeves as in accordance with article titled "Firestopping and Smoke Seal Materials" specified here in this Section. Ensure that sleeves set in exterior walls are packed and sealed with governing authority approved materials suitable for application and that both ends of sleeves are packed watertight with approved permanently flexible and water tight materials. Exact responsibility of work to be coordinated with General Trades Contractor.
- .6 Submit to concrete reinforcement detailer at proper time, drawings indicating required sleeves, recesses and formed openings in poured concrete work. Completely and accurately dimension such drawings and relate sleeves, recesses and formed openings to suitable grid lines and elevation datum.
- .7 Supply sleeves of a water protecting type in accordance with detail found on drawings for installation in following locations:
 - .1 in Mechanical and Fan Room floor slabs, except where on grade;
 - .2 in slabs over Mechanical, Fan, Electrical and Telephone Equipment Rooms or closets;
 - .3 in floors equipped with waterproof membranes.
- .8 "Gang" type sleeving to be permitted only with approval of Owner and reviewed with Consultant.

- .9 Terminate sleeves for work which is exposed, so that sleeve is flush at both ends with wall, partition, or slab surface such that sleeve may be covered completely by escutcheon plates.

3.7 **INSTALLATION OF FIRESTOPPING & SMOKE SEAL MATERIALS**

- .1 Where electrical work penetrates or punctures fire rated construction, provide ULC certified, listed and labelled firestopping and smoke sealing packing material systems to seal openings and voids around and within raceway and to ensure that continuity and integrity of fire separation is maintained. Submit to Consultant, copies of certificates of compliance from an independent testing agency, attesting that fire stopping and smoke seal materials meet ULC requirements. Openings not in immediate vicinity of working areas are to be firestopped and sealed same day as being opened.
- .2 Install fire stopping and smoke seal materials for each installation in strict accordance with specific ULC certification number and manufacturer instructions. Comply with local governing building code requirements and obtain approvals from local building inspection department. Ensure that openings through fire separations do not exceed maximum size wall opening, and maximum and minimum dimensions indicated in ULC Guide No. 40 U19 for Service Penetration Assemblies and fire stopping materials.
- .3 Ensure that continuity and integrity of fire separation is maintained and conform to requirements of latest edition of ULC publication "List of Equipment and Materials, Volume II, Building Construction".
- .4 Comply with following requirements:
 - .1 Manufacturer's installation instruction for each specific application.
 - .2 Clean areas and surfaces before materials are installed.
 - .3 Examine substrates, openings, voids, adjoining construction and conditions under which firestop and smoke seal system is to be installed. Confirm compatibility of surface.
 - .4 Verify penetration items are securely fixed and properly located with proper space allowance between penetrations and surfaces of openings.
 - .5 Report any unsuitable or unsatisfactory conditions to Consultants in writing, prior to commencement of work. Commencement of work will mean acceptance of conditions and surfaces.
 - .6 Mask where necessary to avoid spillage and over coating onto adjoining surfaces. Remove stains on adjacent surfaces.
 - .7 Prime substrates in accordance with product manufacturer's written instructions.
 - .8 Provide temporary forming as required and remove only after materials have gained sufficient strength and after initial curing.
 - .9 Tool or trowel exposed surfaces to neat, smooth, and consistent finish.
 - .10 Remove excess compound promptly as work progresses and upon completion.
- .5 Notify Consultant when work is complete and ready for inspection, and prior to concealing or enclosing firestopping and smoke seal materials and service penetration assemblies. Arrange for final inspection of work by local governing authority inspector prior to concealing or enclosing work. Make any correction required.
- .6 On completion of firestopping and smoke sealing installation, submit a letter of Assurance to Consultant certifying the firestopping and smoke sealing installation has been carried out throughout the building to service penetrations and that installation has been performed in strict accordance with requirements of local governing building code, any applicable local municipal codes, ULC requirements, and manufacturer's instructions.
- .7 Manufacturer's authorized representative to inspect and verify each installation and provide a test report signed by installing trade and manufacturer's representative. Test report to list each installation and respective ULC certification and number.

- .8 Where work requires removal of existing firestopping materials and replacement of firestopping materials after cabling changes have been made, ensure that replacement material is same material and manufacturer of existing if any remains in place, or ensure that all existing material is removed before installation of replacement material.

3.8 **INSTALLATION OF FASTENING & SECURING HARDWARE**

- .1 Provide fasteners and similar hardware required for conduit, duct, raceway, conductors, etc. and for equipment hanger and/or support material unless otherwise noted.
- .2 Accurately and properly set concrete inserts in concrete framework. Where multiple type inserts are used, space same to suit requirements of smallest conduit, etc., in group.
- .3 Fasten hanger and support provisions to masonry with expansion shields and machine bolts, or, for light loads, use plugs, and screws.
- .4 In drywall or plaster walls and/or ceilings use two wing toggles and for heavy loads, provide steel anchor plates with two or more toggles to spread load.
- .5 Provide beam clamps for attaching hanging and/or support provisions to structural steel, or where approved by Owner and reviewed with Consultant, weld hanging and support provisions to structural steel.
- .6 Install devices in accordance with manufacturer's instructions to suit each respective application.
- .7 Explosive powder actuated fasteners are not permitted unless specific written approval for their use and type has been obtained from Consultant.
- .8 Under no circumstances use ceiling suspension hangers or grids for suspension of conduit and conductors. Install supports to permanent structure of building, limited to areas that will not damage structural stability.
- .9 Provide "J" hooks in accessible ceiling spaces where conduit is not provided for structured cabling runs or other telecommunication cabling, as approved by Consultant.
- .10 Comply with J-hook manufacturer loading limitations and spacing criteria. Do not exceed 1.2 m (4') spacing interval. Add additional J-hooks if cabling sags, at discretion of Consultant. Drill anchors for J-hooks into slab not into post tensioned beams. Do not install more than one system on each J-hook.
- .11 Install Velcro tie wraps on bundled telecommunication cables and do not over tighten. Provide FT6/CMP rated wraps in plenum type spaces as per local building code requirements.
- .12 Comply with Structural Engineer's limitations for maximum penetrations of securing hardware into concrete slabs.

3.9 **INSTALLATION OF IDENTIFICATION NAMEPLATES**

- .1 For each piece of electrical distribution equipment from electrical source of supply up to and including panelboards, for special control panels and cabinets, and for each other piece of electrical equipment, provide engraved Lamacoid identification nameplates secured to apparatus with stainless steel screws. Nameplates to indicate source of electrical supply and include Consultant's equipment identification number.
- .2 Equip large multiple cell or component apparatus such as switchboards and distribution panels with main nameplates identifying equipment, voltage characteristics, capacity and source of supply, and with sub-nameplates clearly identifying each cell or component and panel tag and location.
- .3 Panelboard nameplates to identify panelboard number as designated on drawings, unless otherwise instructed. Nameplates for disconnect switches, control panels, and cabinets to outline their service and source of supply.

- .4 In areas where equipment having removable doors that can be commonly installed on different equipment, ensure that each door is identified to which piece of equipment it is associated with, such that nameplates are with correct equipment.
- .5 Faceplates for all wiring devices shall include source panel/circuit on machine printed clear self-adhesive label.
- .6 Nameplates to be mechanically secured lamacoid and be colour coded as follows:
 - .1 Normal Power Black with white letters;
 - .2 Emergency Power Red with white letters;
 - .3 Isolated Power Red with white letters;
 - .4 Vital Power Yellow with white letters;
 - .5 UPS Power Orange with white letters.
- .7 Above identification nameplate and nomenclature requirements are for typical requirements for pricing only.
- .8 In pull boxes, junction boxes and at terminations, identify feeders by use of plastic plates indicating system voltage and circuit designations. Plates to be 25 mm (1") in diameter and have letter stamped 9 mm (5/8") high. Colour coding to be:
 - .1 Phase A - red;
 - .2 Phase B - black;
 - .3 Phase C - blue;
 - .4 Neutral - white;
 - .5 Ground - green.
- .9 Review print size type and size, colours, sizing and nomenclature of nameplates with Consultant prior to ordering. Submit sample board.

3.10 **INSTALLATION OF TERMINAL BACKBOARDS**

- .1 Provide specified terminal backboards for communication systems and electrical distribution equipment.
- .2 Securely wall mount each backboard with proper fasteners to suit wall construction.
- .3 Unless otherwise noted, size backboards to sufficiently provide adequate terminal space for each system, plus 20% space for future additions.

3.11 **INSTALLATION OF ROOFTOP SUPPORT SYSTEM**

- .1 Install rooftop support system for conduits/raceways in accordance with manufacturer instructions and recommendations to suit type of raceway and roofing materials.
- .2 If gravel top roof, remove gravel from around and under pipe support. Coordinate work with building roofing vendor confirmed with Owner and reviewed with Consultant.
- .3 Consult existing roofing vendor for roof membrane compression capacities and roof loading limitations. Comply with restrictions.
- .4 Use properly sized clamps to suit conduit sizes. Ensure that installation and use of system does not invalidate existing roof warranties.
- .5 Engage existing roofing vendor to inspect installation and verify that installation has not damaged roof.

3.12 **BRANCH CIRCUIT BALANCING**

- .1 Connect branch lighting and power circuits to panelboards so as to balance actual loads (wattage) within 5%. If required, transpose branch circuits when work is complete to meet this requirement.

- .2 Perform necessary tests to show compliance with above requirement. Make such tests after building is occupied.

3.13 DISCONNECTION, REMOVAL & RELOCATION WORK

- .1 Where indicated on drawings or where required to perform Work of this Project, disconnect and remove items of existing obsolete electrical work. Relocate required devices as required to accommodate work of other Divisions. Where luminaires, switches, receptacles, and other devices and/or equipment is removed, disconnect at point of electrical supply, remove obsolete wiring and conduit up to source, unless otherwise noted, and make system safe to Owner satisfaction and as reviewed with Consultant. Remove obsolete conduit/raceways in accessible ceiling spaces, exposed locations, etc. Where existing obsolete conduit and similar raceway material cannot be removed, such as embedded in concrete, cut back and cap obsolete conduit and raceways. Refer to specific notes on drawings.
- .2 When respective work is deleted, such deletions are to in no way affect operation of any existing interconnected mechanical or electrical components that remain. When existing circuits are being disconnected, maintain supervision of area to ensure that such circuits do not affect essential existing circuits being retained.
- .3 Refer to architectural drawings which define extent of areas being demolished in existing building. Review drawings and site and include for demolition and/or renovation of services as required to accommodate alterations detailed.
- .4 Unless otherwise noted, obsolete materials which are removed and are not to be relocated or reused are to become your property. Remove from site and properly dispose. Obtain from Owner and coordinate with Consultant, a list of existing electrical items which are to be removed and turned over to Owner. Said items are to remain property of Owner.
- .5 Where existing services pass through or are in an area to serve items which are to remain, or pass through areas that are to be deleted, maintain services, but re-route as required. Include for rerouting existing services concealed behind existing finishes and which become exposed during renovation work, so as to be concealed behind new or existing finishes. Confirm with Owner services which are to be kept in service and operational.
- .6 Revise panelboard directories accordingly, if affected by any renovation, disconnection, or removal of work. Use Owner's actual room names/numbers.
- .7 Protect existing devices being relocated or deleted to ensure that they are not damaged. Test such devices prior to disconnection and de-energization, to ensure that each device is in proper working condition. Ensure that motors are in proper rotation direction. Examine each device for damage. Report devices not working or with damage to Consultant prior to initiating any work. It will be assumed that devices are in proper working order and good condition if not reported.
- .8 Provide junction boxes, outlet boxes, wiring, plates, etc., as necessary for complete relocation of devices. Clean relocated or temporary removed devices and equipment, and ensure that they are in good operating condition before being reinstalled. Where existing luminaires are relocated, clean luminaires and inspect for damage. Re-lamp relocated luminaires. Report defects or damages to Consultant. Do not splice conductors unless approved by Owner and reviewed with Consultant. Utilize junction boxes and terminal devices for proper extension of circuits where approved. Otherwise replace circuits with home run continuous run of suitable lengths.
- .9 Provide blank coverplates on existing obsolete boxes which are to remain in position.

- .10 After installation is complete, test parts of re-used or relocated electrical equipment and correct faults and grounds. Include for fire alarm verification company to verify any relocated devices and downstream affected devices, and verify system as required by local fire authority to suit actual relocation work. For other existing systems, engage manufacturers authorized representative or Owner's system maintenance contractor, to inspect and verify relocated devices. Coordinate and confirm exact requirements with Owner and/or Consultant. Document testing in test reports, signed by testing technician. Submit copies to Consultant.
- .11 Interior, exterior or underground electrical services (including auxiliary services, telephone, fire alarm, P.A. System, etc.) to operating parts of building are not to be hampered under any conditions and to that effect, necessary work may have to be carried out on an overtime basis, at no additional cost to this project. Existing risers are to be maintained in service as required to feed other areas of building(s). Do not interrupt any services without prior written approval by Owner and reviewed with Consultant. Submit formal requests to Consultant outlining in detail requirements of proposal and wait for instructions from Consultant.
- .12 Be present when new doors or openings are being cut into existing walls and ceilings. Should any damage occur to electrical system, restore system to a safe and sound condition.
- .13 Where references are made on drawings that existing receptacles, etc., be extended and/or relocated to suit new construction, receptacles, etc., are to be tested and if found defective, be replaced with new devices. Cracked or broken cover plates are to be replaced and match Architectural finishes. Contractor may optionally replace existing basic receptacles, switches, and faceplates with devices matching existing devices.
- .14 Be responsible for disconnecting power supply to branch circuits controlling lighting, receptacles, panels, mechanical equipment, etc., for safe removal of equipment, conduit, wiring, boxes, etc., affected by demolition.
- .15 Close openings in boxes, panels, etc., that result from removal of equipment, conduit, wiring, fixtures, etc. Close openings in a proper manner and properly terminate and insulate cables to restore system to a safe operating condition, to Consultant's satisfaction.
- .16 Be present and supervise removal of electrical equipment, P.A. speakers, etc., during demolition of ceilings, walls, floors, etc. Existing equipment which is not to be relocated but interferes with demolition, are to be temporarily relocated until demolition work is completed. Services to temporarily relocated equipment are to be maintained at all times.
- .17 Remove and re-install existing ceiling tiles as required to perform work. Prior to removal, inspect tiles for damage and report any to Owner and Consultant. Any loose cabling is to be secured, and luminaires additionally supported with cables secured to ceiling slab. After work has been completed and successfully inspected, re-install ceiling tiles to existing standards and re-install devices. Be responsible for replacement of tiles and grid members damaged during work of Electrical Division. Comply with applicable governing authority requirements with regards to ceiling work in special areas.
- .18 Where existing surfaces are damaged by Electrical Divisions work and/or where existing devices are removed from wall, ceilings, floors and other surfaces, and such deleted devices are not being replaced in same locations, patch locations of these removed devices and re-finish. Patching and finishing is to be provided by tradesmen skilled in particular trade or application worked on, to Consultant's approval. Where openings are left in existing ceiling tiles, replace ceiling tiles with new matching tiles approved by Consultant. Unless otherwise included for in other Divisions, include for:
 - .1 preparing existing surfaces to be filled and repainted to be cleaned as required to remove dirt, dust, oil, grease, loose paint, rust and any other foreign matter which would prevent proper bonding of new finish; sand glossy surfaces to uniform dull texture;

- .2 filling in and patching surfaces with same material as existing surfaces; finished surfaces to match and line with existing adjoining surfaces;
 - .3 providing fire stopping materials to maintain fire rating of the existing surfaces; refer to specification article titled - Firestopping and Smoke Seal Materials.
 - .4 using paint rollers and/or brushes to apply and extend paint finish over full height and/or width of area affected, to a straight line in location determined by Consultant;
 - .5 applying sufficient number of coats such that patched area is indistinguishable to surrounding area;
 - .6 materials used to be of equivalent quality to existing finishes standards and be compatible with finishes to which they are applied;
 - .7 finishes to be approved by Owner and reviewed with Consultant.
- .19 Check luminaires to be deleted for PCB ballasts. Disconnect and remove such ballasts. As specified previously, include for company specialized in such hazardous materials to remove and dispose such materials off-site in compliance with Ministry of Environment, Ministry of Transport and any other governing authority regulations.
- .20 If at any time during course of building work, asbestos containing materials are encountered or suspected, cease work in area in question and immediately notify Consultant. Comply with local governing authority regulations. Do not resume work in affected area without approval from Consultant.

3.14 **INTERRUPTIONS TO & SHUT-DOWNS OF SERVICES & SYSTEMS**

- .1 Shutdowns and interruptions to existing systems and services are to be coordinated fully with and performed at times acceptable to Owner and reviewed with Consultant. Generally, shutdown may be performed only between hours of 12:00 midnight Sunday until 6:00 a.m. Monday morning. Include for costs of premium time to perform work during nights, weekends or other times outside of normal working hours, which may be necessary to comply with stipulations specified herein this Article. Services for operation of existing non-renovated areas of building are to be maintained.
- .2 Upon award of contract, submit to Consultant for review and approval, a list of anticipated shut-down times and their maximum duration.
- .3 Prior to each shut-down or interruption, inform Consultant and Owner in writing 5 working days in advance of proposed shut-down or interruption and obtain written consent to proceed. Do not shut down or interrupt any system or service without written consent. Note that shutdowns of some essential services may require additional advance notification time.
- .4 Work associated with shut-downs and interruptions are to be carried out as continuous operations to minimize shut-down time and to reinstate systems as soon as possible. Prior to any shut-down, ensure that materials and labour required to complete work for which shut-down is required are available at site.

3.15 **EQUIPMENT BASES & SUPPORTS**

- .1 Provide equipment bases and supports. Coordinate concrete pour for housekeeping pads and luminaire poles bases with Division 03. Ensure that applicable seismic restraint provisions are provided as per local governing building code.
- .2 Secure floor mounted equipment in place on minimum 100 mm (4") high concrete housekeeping pads, minimum 100 mm (4") wider and longer than equipment base dimensions.
- .3 Supply dimensioned drawings, templates, and anchor bolts for proper setting of equipment on bases and pads. Be responsible for required levelling, alignment, and grouting of equipment.

- .4 Submit to Consultant for review, dimensioned shop drawings of structurally designed bases for support of large, heavy equipment. Indicate on shop drawings total weight of base, reinforcement, and equipment for which it is required.
- .5 Unless otherwise noted, support equipment suspended above floor level with suitable welded or bolted prime coat painted structural steel angles or channels bracketed to wall or secured by hanger rods.

3.16 CONCRETE WORK

- .1 Unless otherwise noted, concrete required for electrical work is to be provided as part of Work of Division 03. Coordinated exact requirements (sizes, locations) with General Trades Contractor.
- .2 Layout, mark, coordinate and work with Division 03 contractor as required for installation of concrete necessary for duct banks, housekeeping pads, cubed openings, etc.

3.17 EXCAVATION & BACKFILL

- .1 Unless otherwise noted, excavation and backfill work required for electrical work is to be done as part of work of Division 02 or 31, except for final hand grading work and backfill to 450 mm (18") above service which is to be done as part of electrical work. Mark out location and routing of excavation required for work as well as required depth. Ensure that bedding is graded to provide proper drainage for ducts as directed by Consultant.
- .2 Inverts and locations of existing site services may have been site surveyed and approximate location may be shown on drawings. Confirm that local utilities have performed locates and marking out. Ensure inverts and locations are correct, prior to commencement of work. Where discrepancies are found, immediately inform Consultant, and await direction.
- .3 Ensure that work is inspected by Consultant before covering and backfilling. Failure to do so prior to backfilling will require re-excavating work and re-backfill at no additional cost to Owner.

3.18 CUTTING, PATCHING & CORE DRILLING

- .1 Unless otherwise noted, General Trades Contractors are responsible for cutting, patching, and core drilling of existing building required for installation of Work.
- .2 Where added conduits and/or conductors penetrate existing construction, identify, and mark out locations for openings. Size openings to leave 13 mm (1/2") clearance around conduit and/or conductors. Coordinate work with General Trades Contractor.
- .3 Ensure that openings in fire rated construction are sealed as per requirements of article titled "Firestopping And Smoke Seal Materials" specified herein this Section and as per Division 07, as applicable.
- .4 Fire stop and seal openings as specified, and patch as required before end of workday. No openings are to be left open overnight unless approved by Owner and coordinated with Consultant.

3.19 FINISH PAINTING OF ELECTRICAL WORK

- .1 Unless otherwise noted, finish painting of exposed Electrical Divisions work is to be performed as part of work of Division 09.
- .2 Provide identification painting for electrical distribution equipment in accordance with application requirements of Division 09. Confirm exact finish colours with Consultant. Equipment requiring special colour identification painting to include but not be limited to following:
 - .1 pull boxes and junction boxes;

- .2 communication system conduit;
- .3 genset exhaust piping.
- .3 Spray painting is not permitted unless approved in writing by Owner and reviewed by Consultant.

3.20 PROVISIONS FOR FURNITURE SYSTEMS

- .1 Ensure that rough-in for electrical devices including but not limited to outlets, switches, thermostats, control devices, fire alarm devices and clocks and communications devices are located to avoid wall mounted systems furniture wall strips. Relocate conduit and devices which do not coordinate with systems furniture requirements identified on systems furniture drawings.
- .2 Coordinate location of electrical conduits/ducts within floor slabs and mounted to underside of floor slabs, with location of free standing work stations and furniture systems.
- .3 Coordinate connection of electrical and communication devices with systems furniture supplier. Generally, supply and installation of power, data and communication wiring and devices are by Electrical Division. Furniture system connection "whips" to be supplied by furniture system vendor and turned over to Electrical Division for installation. Confirm responsibility of supply of whip with General Trades Contractor. Power conductors are to be installed to a wall/ceiling mounted junction box and extended out to furniture system, through empty conduit, raceways, and back boxes provided within furniture system. Branch circuit conductors in furniture system raceways may be AC-90 flexible armoured conductors. Telecommunication (data/voice) conductors are to be complete home runs from LAN closet to work station outlet. Testing and verification of furniture system devices is responsibility Electrical Division. Confirm exact requirements with furniture system trades. Where furniture systems are not supplied with pre-wired devices, be responsible for supply, installation and wiring of required devices.

3.21 CONDUIT PROVISIONS FOR MISCELLANEOUS SYSTEMS

- .1 Provide following components to accommodate future installation of various miscellaneous systems by system installers who are to provide equipment and wiring:
 - .1 conduit - diameters as sized on drawings with non-metallic fish wires or pull cords and suitable bushings for conduit terminations, and as specified in Part 2; provide labelling at each end to clearly identify each conduit run with respect to system and path;
 - .2 outlet boxes - standard galvanized steel, each complete with a blank type faceplate, and as specified in Part 2;
 - .3 pull boxes, junction boxes, back boxes and sleeves - and as specified in Part 2.
- .2 Miscellaneous systems are typically as shown on drawings. Unless otherwise noted on drawings, provide dedicated conduit runs for each system. Coordinate sizes of boxes with respective system vendors to ensure proper sizing to accommodate components and that allows for wiring bending radii. Confirm conduit and box requirements also with system vendors.
- .3 Provide pull boxes in conduit runs longer than 30 m (100') or having more than two - 90 bends. Size pull boxes to be at least 8 times entering conduit in length. Pull box sizes to comply with respective system standards.
- .4 Leave conduits free and clear of all obstructions and terminate as required. Equip terminations with bushing, and clearly identify each run. Provide fish wires in all empty conduits. Run telecommunications conduits to comply with separation from sources of electromagnetic radiation as per standard ANSI/TIA/EIA-569. Site bend telecommunications conduit elbows to comply with system conduit bending radii requirements.

- .5 Review exact requirements and locations of equipment with Consultant and respective system installers prior to roughing-in.
- .6 Refer to system riser diagrams on drawings.
- .7 Quantities for outlets to be as per floor plan drawings and not riser diagrams.

3.22 DOOR HARDWARE

- .1 Generally, Division 08 or another Division not under scope of electrical Contractor, is responsible for supply and installation of door alarm contacts, door holders, electric strikes, electromagnetic locks, door operator controls, power supplies, door controllers, central electromagnetic lock release controller and other door hardware. Coordinate and confirm with General Trades Contractor and respective equipment vendors (door hardware / security) exact responsibility of each Division of the Work.
- .2 Confirm product and wiring requirements, back box requirements and wiring installation requirements with door hardware trades and with equipment vendors. Provide required wiring in conduit from each device to respective controllers, between each device, and to central control panel and for power connection to such controls and devices. Provide line level voltage power feeds to equipment as required.
- .3 For controls and interconnections between devices, when such device terminations are responsibility of others, supply and run interconnecting wiring in conduit to devices and allow spare length of 1.8 m (6') coiled wiring at each end for final termination to devices by others.
- .4 For applications of electro- magnetically held closed doors, engage fire alarm system vendor to provide fire alarm type pull station with auxiliary contacts as required for interconnection of electro- magnetic door hardware and fire alarm system for release of doors. Provide required wiring in conduit and connections. Coordinate pull station requirements with fire alarm system vendor.
- .5 Exact type of door alarm contacts to be coordinated with door construction and finishes. Contacts to generally be recessed mounted and wiring be installed in concealed conduits. Confirm exact requirements with door hardware / security vendor and General Trades Contractor.
- .6 Where controls are located remotely from door locations, such as in closets, provide wiring in conduit and extend from local above door junction boxes and devices as required with homeruns back to closet location of equipment and leave slack wiring for terminations by others. Confirm exact requirements with door hardware / security vendor and General Trades Contractor.
- .7 Drawing details issued with electrical drawings are for pricing reference only and are based on assumptions. Obtain detailed design drawings from successful door hardware / security vendors and provide wiring in conduit to coordinate with and accommodate final systems designs. Coordinate with General Contractor.
- .8 Submit as part of shop drawing submission, detailed responsibility matrix identifying work and responsibilities of each trade and required interconnections.
- .9 After installation is complete, test and verify operation of components in coordination with General Contractor and door hardware vendor.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products and accessories.
- .2 Submit samples of conductors, when requested by Consultant.

Part 2 - Products

2.1 GENERAL POWER CABLES

- .1 CSA approved, ULC labelled and certified. Unless otherwise noted, conductors to be copper and be suitable for applications as noted in governing local electrical code.
- .2 RW90 CSA certified, single copper conductor to CSA C22.2 No. 38, 600/1000 volts, maximum 90°C (194°F) conductor temperature, -40°C (-40°F) minimum installation temperature, X-link polyethylene (XLPE) insulation, colour coded.
- .3 T90 Nylon, CSA certified, single copper conductor to CSA C22.2 No. 75, 600 volts, maximum 90°C (194°F) dry conductor temperature, -10°C (-14°F) minimum installation temperature, PVC insulated, nylon covered.
- .4 AC90 flexible armoured cable with "RW90" conductors and bare copper ground conductor and overall interlocked aluminium tape armour, to CSA C22.2 No. 51 (R2004).
- .5 AC90 ISO-BX flexible armoured cable with "RW90" conductors with low temperature Exelene insulation and two additional solid copper bonding conductors (one bare, one insulated) and overall interlocked aluminium tape armour, to CSA C22.2 No. 51 (R2004).
- .6 DLO stranded tinned copper conductor, to CSA type RW90, with 90°C rated ethylene propylene rubber insulation and black chlorinated polyethylene overall jacket; flame retardant and suitable for wet locations; rated for up to 2000 volts.
- .7 Solid conductors to and including No. 10 AWG; stranded conductors in sizes larger than No. 10 AWG; branch circuit conductors constructed of 98% conductive copper; and approved for minimum 600 volts, with minimum 1000 volts where noted.

2.2 CONNECTORS

- .1 Armoured cable connectors must be proper squeeze type connectors and plastic anti-short bushings at terminations.
- .2 Connectors for conductors connecting to devices as per local governing electrical requirements to be equal to IDI Electric (Canada) Ltd., "Ideal" No. 451, No. 452 and No. 453, "Wing-Nut", CSA certified, 600 volts, rated pressure type connectors.

2.3 FIRE RATED CABLES

- .1 Pentair - Pyrotenax, model "System 1850", CSA certified, ULC listed and labelled, FM Specifications tested, 600 V, type MI, 2 hour fire rated, copper sheathed, copper conductor, highly compressed magnesium oxide mineral insulated power cable. Connectors for copper-sheathed mineral conductors to be cable manufacturer proper connectors and accessories as recommended by manufacturer to suit specific applications.
- .2 Pentair - Pyrotenax, model "System 1850 Twisted Pair", CSA certified as FAS, FAS 90 and FAS 105 cable, ULC listed and labelled, 300 V, type MI, 2 hour fire rated, copper sheathed, copper conductor, highly compressed magnesium oxide mineral insulated fire alarm and voice communication cable. Connectors for copper-sheathed mineral conductors to be cable manufacturer proper connectors and accessories as recommended by manufacturer to suit specific applications.

- .3 Manufacturer termination kits: Pyropak epoxy sealing compound kits and "Quick Term" connectors; connectors for MI conductors to be cable manufacturer proper connectors and accessories as recommended by the manufacturer to suit specific applications.
- .4 Cable clips and straps as recommended by cable manufacturer to suit specific installation application. In applications of dissimilar materials, provide tape to insulate cabling and hardware.
- .5 Brass plates for cable openings in ferrous metal enclosures.
- .6 Include for required cable manufacturer accessories and identification labelling.
- .7 Include for manufacturer authorized technician to be present on site for initial coordination with installing personnel on review of proper installation of cabling runs and termination of cabling. After completion of Work, manufacturer technician to review installation work and provide in writing that installation work has been performed to satisfaction of cable manufacturer.
- .8 Acceptable manufacturer of fire rated MI type cables is Pentair Thermal Management.

2.4 **STANDARD CONTROL & COMMUNICATIONS CABLES**

- .1 ULC listed and labelled, CSA certified to C22.2 No. 127, No. 18 AWG "TEW" thermoplastic insulated, solid copper wire rated for 600 volts service, and 105°C (220°F) conductor temperature, complete with required number of copper conductors and colour coding.
- .2 Nexans, "Securex II", FAS 105, 300 volts, 105°C (220°F) conductor temperature rated fire alarm system flexible armoured cable with solid copper conductor, shielding, flame retardant PVC insulation and red colour outer overall jacket, ULC listed and labelled and CSA certified to C22.2 No. 208.

2.5 **CONDUCTOR PULLING LUBRICANT**

- .1 IDI Electric (Canada) Ltd., "Ideal Yellow 77" or "Wire Lube" as required.

2.6 **TECK CABLES**

- .1 Nexans, "Firex II Teck" cables as follows:
 - .1 certified to CAN/CSA C22.2 No.131, Type TECK 90 Cable;
 - .2 rated for outdoor, weather resistant and wet locations applications;
 - .3 600/1000 V rated;
 - .4 Conductor: Bare, Soft drawn, Class B Compact or Compressed Stranded Copper conductors per ASTM;
 - .5 insulation: chemically cross linked thermosetting polyethylene (XLPE);
 - .6 bonding conductor (1/C Cable): Soft drawn bare copper;
 - .7 inner jacket: sunlight resistant PVC jacket tightly applied over assembly, to prevent slipping of core in a vertical position;
 - .8 armour: flexible interlocked aluminum armour, over inner jacket for mechanical protection;
 - .9 overall PVC jacket rated -40°C (-40°F).
 - .10 barrier tape over shield.
- .2 Acceptable manufacturers are:
 - .1 Nexans;
 - .2 Prysmian Cables (Pirelli);
 - .3 General Cable;
 - .4 Aetna Cables;
 - .5 Kerite Company.

Part 3 - Execution

3.1 PROJECT CONDITIONS

- .1 If identified in documents, verify that field measurements and conditions are as identified.
- .2 Cable routing on drawings is schematic and approximate. Route cable as required to meet project conditions. Determine exact routing and lengths on site.
- .3 Confirm fire protection ratings of construction to ensure that rooms and paths of conductors are fire rated in accordance with local governing codes requirements. Include fire rated conductors as required to meet local governing codes requirements.

3.2 CO-ORDINATION

- .1 Co-ordinate work with work provided under other electrical work and work of other trades.
- .2 Determine required separation between cable and other work.
- .3 Determine cable routing to avoid interference with other work.
- .4 Submit any alternative cable routing to Consultant for review prior to proceeding with work.

3.3 INSTALLATION OF CONDUCTORS

- .1 Provide required conductors. Ensure fire rated conductors are provided for applications as required by local governing codes, standards and local governing authorities.
- .2 In applications where multiple conductors in conduit are being run, provide a trapeze configuration of metal C-channels and threaded rod hangers to support cable/conduit from ceiling slab. Wall mounted cable/conduit brackets and ring type conduit hangers may also be permitted in applications approved by Consultant. Provide required cable support system accessories which are not specified herein or shown on drawings but are required for proper installation.
- .3 Conductors, unless otherwise noted, to be as follows:
 - .1 for connections to electric heating coils in supply air ductwork systems, and for connections to other electric heating equipment where use of 90 degrees C. rated conductors are recommended by heating equipment manufacturer - "RW90";
 - .2 for conductors requiring fire rating by current regulations and local codes including feeders for emergency systems, fire fighter's elevators, fire alarm systems, other life safety systems and for applicable signal and control circuits of these systems - type "MI" CSA approved, ULC listed and labelled, 2 hour fire rated, copper sheathed mineral insulated copper conductors;
 - .3 climate controlled areas branch circuit wiring in accessible ceiling spaces and within stud wall construction consisting of drops down to luminaries and drops down stud walls to devices and in furniture systems - "AC90" flexible armoured cable ("BX") (maximum 6m (20') run permitted);
 - .4 for climate controlled areas wiring except as noted above or specified elsewhere in Specification or as noted on drawings - "T90 Nylon" or "RW90".
- .4 Support flexible armoured cable in ceiling spaces and in stud wall construction with steel 2 hole cable straps to "Code" requirements. Flexible armoured cables must run in a neat manner parallel to building lines. Utilize centralized conduit runs to maintain maximum permitted runs of flexible armoured cables as specified. Provide insulating grommet at cut ends of flexible armoured cable to protect conductor insulation.
- .5 Install compression connectors with proper dies and compression tool as per connector manufacturer instructions. Install cold shrink tubing and associated materials as per manufacturer instructions.

- .6 Low voltage conductors to typically be No. 18 AWG "TEW" except for use in fire alarm system applications, unless otherwise noted. Provide specified fire alarm cables for fire alarm system applications or security system applications as approved by Code and local governing authorities. Conductors not installed in conduit or raceways to be fire insulated rated in accordance with latest governing Code Flame Spread requirements.
- .7 When installing type NMD90 conductors through metal studs, provide insulating grommets on stud openings to protect conductor insulation.
- .8 Generally, conductor sizes are indicated on drawings. Such sizes are minimum requirements and must be increased, where required, to suit length of run and voltage drop in accordance with applicable conductor voltage drop schedule appended to end of this Section.
- .9 Do not use conductors smaller than No. 12 AWG in systems over 30 volts, unless otherwise noted. Do not use conductors smaller than No. 6 AWG for exterior luminaire wiring unless otherwise noted.
- .10 Colour code conductors throughout to identify phases, neutrals and ground by means of self-laminating coloured tape, coloured conductor insulation, or properly secured coloured plastic discs. Colours, unless otherwise noted, to be as follows:
 - .1 Phase A - red;
 - .2 Phase B - black;
 - .3 Phase C - blue;
 - .4 Ground - green;
 - .5 Neutral - white;
 - .6 Control - orange.
- .11 When pulling wires into conduit use lubricant and ensure that wires are kept straight and are not twisted or abraded.
- .12 Control conductors, in addition, to be numbered with Brady Ltd. or Electrovert Ltd. Z type markers.
- .13 Colour code conductors for communications systems in accordance with system component manufacturer recommendations.
- .14 Neatly secure exposed wire in apparatus enclosures with approved supports or ties.
- .15 Install low voltage conductors in conduits, unless otherwise noted within Documents.

3.4 **INSTALLATION OF FIRE RATED CONDUCTORS**

- .1 Submit with shop drawings, copy of manufacturer detailed installation manual and testing procedures. Provide minimum 2 hour fire rated type "MI" CSA approved, ULC listed and labelled, mineral insulated copper conductors for following:
 - .1 feeders to emergency lighting panel boards;
 - .2 feeders to fire alarm control panels and transponders;
 - .3 feeders as required by Code requirements;
 - .4 fire alarm system feeders as shown interconnecting existing fire alarm system and additional system;
 - .5 applicable local governing code required applications for control and signalling conductor circuits of and between life safety equipment and systems;
 - .6 feeders and conductors as noted on drawings.

- .2 Provide fire rated type "MI" conductors for specific feeders as required and as noted. Install type "MI" copper sheathed, mineral insulated conductors for applications noted above and as shown on drawings in strict accordance with the manufacturer instructions and recommendations. Refer to latest issue of Pyrotenax MI cable Commercial Wiring Installation Manual. Installation must be in a neat and professional manner as per manufacturer approval. Make arrangements for manufacturer technician to provide onsite services as specified.
- .3 Provide Unistrut C-channels, clips, wall brackets, etc., as required and as recommended by cable manufacturer to suit the on-site installation conditions. Provide system of Unistrut hangers and rods spaced at minimum 1.2 m (4') but which must be confirmed with cable manufacturer, for running of cables. Where clips and other hardware are in contact with cables, insulate cables/hardware with suitable tape as per cable manufacturer recommendations for applications of dissimilar metals.
- .4 Make terminations of "MI" conductors with manufacturer approved components and "Pyropak" or "Quick Term" connectors in accordance with the manufacturer recommendations. Obtain proper tools for cable terminals from the cable manufacturer. Terminations must be completed immediately once started to avoid moisture ingress from the surrounding air. Connections to ferrous cabinets for single conductor cables shall incorporate brass plates sized as required and as per cable manufacturer requirements. Brass plates shall be complete with required drilled and tapped holes. For 99°C applications, cable lugs shall be temperature rated as such.
- .5 When pulling cable, apply pulling tension to the conductor not in the sheath of the cable. Limit cable pulling tension to as recommended by cable manufacturer.
- .6 Terminate cable in the equipment with termination kits as per cable manufacturer instructions.
- .7 Ground cabling as per cable manufacturer instructions and as per local governing electrical code requirements.
- .8 Take necessary precautions when handling cable on reel to ensure that no damage will result in the uncoiling process.
- .9 Where cables penetrates fire rated construction, provide ULC listed and labelled, fire stopping and smoke seal materials or fittings to protect integrity of fire rated construction. Install work in compliance with ULC standards and where required by local governing codes, provide tray type suitable for plenum environments.
- .10 Test MI cables after installation, in strict accordance with cable manufacturer instructions. Megger terminations to check that insulation resistance is acceptable to cable manufacturer. Prior to completing each termination, test insulation resistance and follow cable manufacturer drying procedures until resistance reaches cable manufacturer listed acceptable level.
- .11 Provide for cable manufacturer authorized representative to review the installation, termination, splicing and testing of installed cables. Prepare report consisting of test sheets with results of cables tested and a certificate of verification signed by testing engineer/technician. Report to include copy of cable manufacturer signed inspection letter documenting that work was performed to satisfaction of manufacturer. Submit minimum 3 hard copies and electronic copy to Consultant.

3.5 **INSTALLATION OF TECK CABLES**

- .1 Provide cables as required for specific applications. Handle, install, and terminate in accordance with manufacturer recommendations and instructions and as herein specified.
- .2 When pulling cable, apply pulling tension to conductor not in sheath of cable. Limit cable pulling tension to as recommended by cable manufacturer.
- .3 Terminate cable in equipment with lugs and termination kits as per cable manufacturer instructions.

- .4 Installation of cable splices and terminations to be made by personnel skilled in this type of work.
- .5 Ground shielding as per cable manufacturer instructions.
- .6 Take necessary precautions when handling cable on reel to ensure that no damage will result in uncoiling process.
- .7 No splices are allowed unless justified by cable pulling tension calculations and approved in writing by Consultant. Obtain approval of splice location from Consultant.

END OF SECTION

MAXIMUM BRANCH WIRING DISTANCE FOR 120 VOLT SYSTEM AT 3% VOLTAGE DROP

WIRE SIZE	BREAKER SIZE (AMPERES)	15	20	30	40	50	60	70	80	100
	MAX LOAD AT 80% (AMPERES)	12	16	24	32	40	48	56	68	80
No. 12	-	24.4	18.3	-	-	-	-	-	-	-
No. 10	-	38.1	29.0	19.1	-	-	-	-	-	-
No. 8	-	59.4	44.2	30.5	22.9	-	-	-	-	-
No. 6	-	91.4	70.1	47.2	35.1	28.2	23.6	-	-	-
No. 4	-	-	109.7	73.2	54.9	42.7	38.1	32.0	27.4	-
NO. 2	-	-	-	114.3	85.3	68.6	57.9	50.3	41.1	35.0
No. 1	-	-	-	-	103.6	85.3	73.2	61.0	54.9	43.4
No. 1/0	-	-	-	-	128.0	102.9	85.3	73.2	64.0	48.8
No. 2/0	-	-	-	-	-	121.9	100.6	86.9	74.7	60.9
No. 3/0	-	-	-	-	-	-	118.1	102.1	88.4	70.1
No. 4/0	-	-	-	-	-	-	-	120.4	102.9	83.8
250 MCM	-	-	-	-	-	-	-	-	114.3	91.4
300 MCM	-	-	-	-	-	-	-	-	-	103.6

Note: Distances indicated in metres from panel to load for single phase.

END OF APPENDIX

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products and accessories.

Part 2 - Products

2.1 BASIC MATERIALS

- .1 Ground Conductors: Solid copper, insulated and bare to suit application and code requirements; and bond conductors.
- .2 Ground Connections:
 - .1 When making ground and bonding connections, apply a corrosion inhibitor to contact surfaces. Use corrosion inhibitor appropriate for protecting a connection between metals used.
- .3 Miscellaneous ancillary components to complete grounding and bonding work to requirements of local governing electrical authority and codes.

Part 3 - Execution

3.1 GENERAL GROUNDING & BONDING REQUIREMENTS

- .1 Provide required grounding and bonding work in accordance with drawings, local governing electrical authority, governing authorities having jurisdiction and local governing electrical inspection authority.
- .2 Connect grounding conductors to motors 10 hp and above or circuits 20A or above, with a solderless terminal and a bolt tapped to motor frame or equipment housing. Connect to smaller motors or equipment by fastening terminal to a connection box. Connect junction boxes to equipment grounding system with grounding clips mounted directly on box or with machine screws. Completely remove paint, dirt, or other surface coverings at grounding conductor connection points so good metal-to-metal contact is made.
- .3 Provide service conductors exceeding 400 amperes with minimum No. 3/0 AWG grounding conductors, unless otherwise noted.
- .4 Ground and bond various telecommunications, audio visual systems, security, life safety and control systems in accordance with respective system manufacturers recommendations and in accordance with local governing electrical code requirements.
- .5 Ground conductors not sized on drawings are to be sized in accordance with local governing electrical authority requirements. Ground conductor size is to be no smaller than requirements specified herein this article or on drawings.

3.2 ADDITIONAL TELECOMMUNICATIONS GROUNDING

- .1 Comply with TIA/EIA-607 grounding and bonding requirements.
- .2 Provide wire and hardware required to properly ground, bond, and connect communications raceway, cable tray, metallic cable shields, and equipment to a ground source.
- .3 Ground bonding jumpers to be continuous with no splices. Use shortest length of bonding jumper possible.
- .4 Bonding Jumpers:
 - .1 Use insulated ground wire of size and type if identified on Drawings if not identified, comply with local governing code, but which is to be a minimum of No. 6-AWG insulated copper wire.

- .2 Assemble bonding jumpers using insulated ground wire terminated with compression connectors.
- .3 Use compression connectors of proper size for conductors specified. Use connector manufacturer's compression tool.
- .5 Bonding Jumper Fasteners:
 - .1 Conduit: Fasten bonding jumpers using screw lugs on grounding bushings or conduit strut clamps, or clamp pads on push-type conduit fasteners. When screw lug connection to a conduit strut clamp is not possible, fasten plain end of a bonding jumper wire by slipping this plain end under conduit strut clamp pad; tighten clamp screw firmly. Where appropriate, use zinc-plated external tooth lockwashers.
 - .2 Wireway and Cable Tray: Fasten bonding jumpers using zinc-plated bolts, external tooth lockwashers, and nuts. Install protective cover; e.g., zinc-plated acorn nuts, on any bolts extending into wireway or cable tray to prevent cable damage.
 - .3 Ground Plates and Busbars: Fasten bonding jumpers using two-hole compression lugs. Use tin-plated copper or copper alloy bolts, external tooth lockwashers, and nuts.
 - .4 Unistrut and Raised Floor Stringers: Fasten bonding jumpers using zinc-plated, self-drill screws and external tooth lockwashers.
- .6 Ground metallic conduits, wireways, and other metallic equipment located away from equipment racks or cabinets to cable tray pan or telecommunications ground busbar, whichever is closer, using insulated No. 6-AWG ground wire bonding jumpers.
- .7 Ground metallic conduit at each end using No. 6-AWG bonding jumpers.
- .8 Comply with cable tray manufacturer grounding and bonding recommendations. Bond metallic structures of wireway to provide 100% electrical continuity throughout wireway system.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings of products specified in this Section.
- .2 Submit copies of documents requested herein, testing reports, certificate of approvals, and commissioning sheets.

Part 2 - Products

2.1 VIBRATION CONTROL & SEISMIC RESTRAINT

- .1 Electrical equipment installation is to meet local governing authority having jurisdiction and code seismic requirements and additional requirements for vibration isolation.
- .2 Provide labour, materials, and equipment required and necessary to seismically restrain electrical equipment and equipment bases including concrete pads, and guarantee function of materials and equipment supplied.
- .3 Make electrical connections to vibration-isolated equipment with flexible conduit or other flexible means acceptable to Consultant and local governing authority having jurisdiction so as not to restrict maximum anticipated movement of equipment under seismic excitation movement.
- .4 In event that inadequate isolation is provided by isolation product Manufacturer isolation package, be responsible for improving isolation to an acceptable standard at no additional cost to contract. Isolation product Manufacturer seismic restraint engineer to verify that seismic restraints and combination isolator/restraints intended for use on project are fit for intended purpose. Be responsible for ensuring that Manufacturer seismic restraints are in compliance with applicable local building code requirements for Place of Work.
- .5 Provide additional seismic requirements for suspended electrical raceways, luminaires, and other equipment as per governing local authority requirements and requirements of current codes and by-laws.
- .6 Acceptable manufacturers of seismic restraints include:
 - .1 Vibro-Acoustics;
 - .2 Mason Industries;
 - .3 Kinetic Noise Control;
 - .4 Eaton B-Line.

Part 3 - Execution

3.1 INSTALLATION

- .1 Comply with seismic restraint Engineer and manufacturer installation recommendations.
- .2 Obtain required training from Manufacturer representative on any special installation procedures. Install components in accordance with Manufacturer instructions to suit specific installation requirements.
- .3 Test, adjust, and certify installation. Submit copies of test report to Consultant.
- .4 Refer to Part 2 for specific installation requirements.

3.2 INSPECTION

- .1 Inspect for removal of break away hardware to ensure proper torques of installed systems.

- .2 For non-visually verifiable product, manufacturers to verify proper torque for a minimum 10% of application. Document torques for applications per Manufacturer instructions.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings of major electrical distribution equipment. Allow in shop drawing process, sufficient time for Consultant to review and make comments and for Contractor and equipment vendors to incorporate Consultant comments, necessary revisions and results of reports into equipment shop drawings. Do not order equipment until shop drawings are acceptable to Consultant. Time for this shop drawing review process will be at Consultant's discretion, but typically allow for 15 working days for initial review submission with additional 10 working days added to accommodate each resubmission.

Part 2 - Products

2.1 GENERAL SCOPE OF WORK

- .1 Include for, but not be limited, to following:
 - .1 product manufacturers providing equipment inspection, testing, start-up, adjustments and verification;
 - .2 electricians/trades people on site to handle equipment, make temporary connections, operate equipment and make repairs and adjustments and assist Manufacturer / testing organization's personnel during on-site inspection, testing, calibration, start-up, verification work and where supplementary commissioning;
 - .3 coordination of work with testing company and equipment/system Manufacturer authorized technician in performing adjustments and start-up procedures to equipment/systems;
 - .4 preparing testing reports and documentation for submission to Consultant.

Part 3 - Execution

3.1 GENERAL ELECTRICAL WORK TESTING

- .1 In addition to tests required by local governing authorities having jurisdiction, local codes and regulations, perform following:
 - .1 after luminaires, switches, receptacles, motors, signals, etc., are installed, whether same are installed as part of this Division or by other Divisions (telephone systems excepted), test work to ensure that there are no leaks, grounds or crosses;
 - .2 establish and ensure proper motor rotation - measure full load running currents and check overload elements - report to Consultant any discrepancies which are found; existing motors which have been worked on (disconnected and reconnected) must be checked with rotation meter to ensure proper rotation; be responsible for any damage caused by reverse rotation;
 - .3 demonstrate to Consultant that branch circuit voltage drop is within specified units;
 - .4 ensure that devices are commissioned and operable.
- .2 Document results into distribution system testing report. Report must state that testing was successful and Work complies with project documents, applicable CSA standards, and other applicable governing codes and requirements.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products specified in this Section.

1.2 PRODUCT COMPATIBILITY

- .1 Lighting controls and luminaires when integrated together for control purposes must be 100% compatible with each other. Coordinate with ballast/driver and lamp manufacturers, dimmer/occupancy control manufacturers to ensure that components are compatible with each other and that interconnections do not affect performance, life or any warranties.

Part 2 - Products

2.1 WALL BOX DIMMERS

- .1 Lutron Electronics Co. "Nova-T" Series, ULC listed and labelled, CSA approved wall box dimmers as follows:
 - .1 of type and size to suit intended loads;
 - .2 air gap accessible without removing faceplate, to meet UL20 and UL1472 short circuit test requirement for snap switches;
 - .3 withstand voltage surges up to 600 V and current surges up to 200 A as per ANSI/IEEE C62.41;
 - .4 voltage regulated;
 - .5 power failure memory;
 - .6 LC filtering to minimize RFI;
 - .7 linear slide with smooth and continuous square law dimming curve operation;
 - .8 snap on faceplate (seamless multi-gang at locations with multiple devices);
 - .9 finish to Consultant's direction.
- .2 Where noted for applications of multiple wall box dimmers located in one location, provide CSA approved, NEMA 2 type, flush wall mounting, electrical cabinet with hinged locking front door, of painted enamel painted steel construction, complete with conduit knockout entries, flush trim and sized to accommodate dimmers. Refer to applicable drawing detail.
- .3 Generally, acceptable manufacturers are:
 - .1 Lutron;
 - .2 Legrand-Watt Stopper;
 - .3 Hubbell (supplied by Omnilumen);
 - .4 Sensor Switch;
 - .5 Leviton;
 - .6 NX Lighting Controls;
 - .7 Acuity Brands Controls.

2.2 OCCUPANCY SENSORS (STANDARD)

- .1 Legrand - Watt Stopper, CSA approved devices to provide automatic control of lighting with following components:
 - .1 power and slave packs;
 - .2 dual technology occupancy sensors;
 - .3 controls and daylight sensors;
 - .4 wiring in conduit and mounting hardware.

- .2 Where required, power packs to be self-contained, 347/120 VAC/24 VDC (or of voltage shown on drawings) transformer relay system. Slave packs to contain isolated relay. System to allow one sensor to control luminaires circuited to both essential power circuits and normal power circuits.
- .3 For applications in general areas: ceiling mounted, DT-355, dual technology type sensors as follows:
 - .1 combination passive infrared and ultrasonic technologies;
 - .2 when both PIR and ultrasonic technologies detect occupancy, lights turn ON automatically; once lights are ON, detection by either technology holds lights ON until occupancy is no longer detected and time delay elapses;
 - .3 can be set so that only one technology is needed to trigger;
 - .4 low voltage operation;
 - .5 360° lens area coverage, extending out up to 6 m (20') and area of 92.9 m² (1000 ft²);
 - .6 low profile ceiling mounting design;
 - .7 integral light sensor;
 - .8 adjustable sensitivity and digital time delay;
 - .9 walk-through mode;
 - .10 LED indication of occupancy detection;
 - .11 isolated relay for interconnection to auxiliary control systems where required.
- .4 For sensors mounted in ceiling/wall corners: series DT-200 with features as follows:
 - .1 combination passive infrared and ultrasonic technologies;
 - .2 when either or both (user set option) PIR and ultrasonic technologies detect occupancy, lights turn ON automatically; once lights are ON, detection by either technology holds lights ON until occupancy is no longer detected and time delay elapses;
 - .3 complete with adjustable swivel mounting bracket;
 - .4 wide dispersion lens area coverage, extending out up to 16 m (55') and area of 185 m² (2000 ft²);
 - .5 low voltage operation;
 - .6 low profile design;
 - .7 integral light sensor;
 - .8 adjustable sensitivity and digital time delay;
 - .9 walk-through mode;
 - .10 LED indication of occupancy detection;
 - .11 isolated relay for interconnection to auxiliary control systems where required.
- .5 For applications in washrooms and small storage rooms: wall mounted "DW-100" Series dual technology sensors as follows:
 - .1 wall switch sensor turns lights OFF and ON based on occupancy;
 - .2 factory default operation is for Manual-ON mode, so that users turn light on only when needed;
 - .3 variety of control options including Auto-ON operation, walk-through and test mode; additional settings allow choice of which sensing technologies hold ON or retrigger lighting;
 - .4 colour matched lens and low profile design;
 - .5 wide dispersion lens area coverage, extending out up to 10 m (35') and area of 37 m² (400 ft²);
 - .6 infrared and ultrasonic technologies;
 - .7 adjustable time delays and sensitivity;
 - .8 manual pushbutton operation (override);

- .9 low voltage or line voltage operation to suit specific applications;
- .10 complete with required mounting accessories.
- .6 For corridors or wide space coverage: Ceiling mounted, WT series, ultrasonic technology type sensors as follows:
 - .1 ultrasonic technologies;
 - .2 when ultrasonic technology detects occupancy, lights turn ON automatically; once lights are ON, detection holds lights ON until occupancy is no longer detected and time delay elapses;
 - .3 low voltage operation;
 - .4 corridor applications to include linear lens area coverage, extending out up to 13.5 m (45') in 2 directions;
 - .5 wider spaces applications to include wide dispersion coverage to suit space, up to 200 m² (2200 ft²);
 - .6 low profile ceiling mounting design;
 - .7 integral light sensor;
 - .8 adjustable digital time delay;
 - .9 LED indication of occupancy detection;
 - .10 isolated relay for interconnection to auxiliary control systems where required.
- .7 Override switches to be wall mounting in single gang recessed outlet boxes.
- .8 Wiring in conduit, mounting hardware and ancillary devices to be provided as per Manufacturer requirements.
- .9 System to be complete with initial 1 year parts and labour warranty, with additional extended 5 years parts warranty.
- .10 Where sensors are interconnected to dimming system, ensure that they are 100% compatible with respective control systems, dimmers and ballasts. Confirm with respective equipment manufacturers and obtain in writing that such integrations are acceptable to each manufacturer.
- .11 Generally, acceptable manufacturers are:
 - .1 Legrand-Watt Stopper;
 - .2 Hubbell (supplied by Omnilumen);
 - .3 Sensor Switch;
 - .4 Leviton;
 - .5 NX Lighting Controls;
 - .6 Acuity Brands Controls.

2.3 STAGE LIGHTING

- .1 Coordinate with Hamilton Video and Sound for package to be supplied.
- .2 Existing dimming system is to be replaced with new for control of new package.

Part 3 - Execution

3.1 INSTALLATION OF WALL BOX DIMMERS

- .1 Provide flush wall box dimmers in locations and connect to control lighting as indicated. Confirm exact locations prior to roughing-in. Equip each dimmer with a faceplate. Confirm faceplate colour prior to ordering.
- .2 Install components in accordance with Manufacturer instructions to suit specific installation requirements.

- .3 Where identified, provide central enclosure cabinet for mounting dimmers within and connect complete. Clearly identify each dimmer and enclosure with engrave Lamacoid nameplates. Confirm exact nomenclature with Consultant prior to ordering.
- .4 When installation is complete, check and test operation of each dimmer and adjust as required.
- .5 Ensure that each dimmer is properly sized to suit connected load.

3.2 **INSTALLATION OF OCCUPANCY SENSORS**

- .1 Provide occupancy sensors and daylight sensors and associated devices to control lighting in areas as required. Provide power packs as required with suitable voltage and power ratings.
- .2 Exact type of occupancy sensors and type of lenses to be verified by manufacturer/supplier to ensure proper coverage in sensed areas only, and compatibility to interconnected systems. Confirm with respective manufacturers.
- .3 Be responsible for providing, locating, and aiming appropriate sensors in correct location required for complete and proper volumetric coverage within range of coverage(s) of controlled areas per Manufacturer recommendations. Rooms to have 90-100% coverage to completely cover controlled area to accommodate occupancy habits of single or multiple occupants at any location within room(s). Locations and quantities of sensors shown and/or noted are illustrations only and should only be used as guidelines. Provide additional sensors if required to properly and completely cover respective room.
- .4 Verify with Manufacturer factory authorized representative, exact type of sensor to be used in each area, placement of sensors and installation criteria, to best meet requirements of end user. Manufacturer representative should be consulted for more non-typical installation types. Ensure that sensors connected to dimming system are 100% compatible with dimming system.
- .5 Where luminaires in rooms/areas are fed from normal and emergency power circuits, provide suitable relays and provisions to ensure that operation of luminaires on emergency power are maintained during loss of normal power.
- .6 Proper judgement must be exercised in executing installation so as to ensure that best possible installation in available space and to overcome local difficulties due to space limitations or interference of structural components. Also provide, at Owner's facility, training necessary to familiarize Owner personnel with operation, use, adjustment, and problem solving diagnosis of occupancy sensing devices and systems.
- .7 Install devices in accordance with Manufacturer instructions. Provide wiring in conduit. Provide required power connections and interconnection to luminaires and power panels. Provide manual switches to override control system in each area/room as shown.
- .8 Confirm finishes of sensors with Consultant prior to ordering.
- .9 Confirm mounting heights with Architect and manufacturer prior to roughing-in and installation.
- .10 Adjust sensitivity and time delays to best suit Owner furniture layout drawings. Allow for minor adjustments of locations (1 m [3.3']) of sensors.
- .11 Refer also to testing and verification requirements in Section titled Electrical Work Analysis and Testing and include applicable requirements.

3.3 **STAGE LIGHTING**

- .1 Install according to supplier instructions, providing all power, control wiring, conduits, and supports for a turn-key system, from new dimming panel to fixtures.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products specified in this Section.

Part 2 - Products

2.1 SURFACE SERVICE RACEWAYS

- .1 Legrand-Wiremold, Series 4000, CSA certified, ULC listed and labelled, prime coated galvanized steel, 2-compartment, surface mounted, metal service raceways, complete with following:
 - .1 duplex grounding receptacles and mounting knockout plates;
 - .2 data outlet mounting bracket;
 - .3 telephone outlet mounting bracket;
 - .4 dual covers (one for power and one for communications);
 - .5 clips, couplings, brackets, fittings, elbows, boxes, tees mounting hardware, etc., for a complete raceway system;
 - .6 wiring for power.
- .2 Legrand-Wiremold, Series 5400, CSA certified, ULC listed and labelled, 2-compartment, surface mounted, painted non-metallic service raceways, complete with following:
 - .1 duplex grounding receptacles and mounting knockout plates;
 - .2 data outlet mounting bracket;
 - .3 telephone outlet mounting bracket;
 - .4 clips, couplings, brackets, fittings, elbows, boxes, tees mounting hardware, etc., for a complete raceway system;
 - .5 wiring for power.
- .3 Generally, type of raceways are noted on drawings, but in absence of direction, in areas where multiple services are required, provide multi-compartment raceways to suit application. Where only single service is required, provide single type raceways. Provide stainless steel type raceways in laboratories, testing rooms, and similar type rooms. Confirm exact requirements with Consultant.
- .4 Coordinate and measure exact dimensions for lengths, to meet site installation. Where horizontal sections meet vertical sections, provide manufacturer proper connecting fitting such that there are no openings or exposed conductors. Ensure that bending radii requirements of various cabling standards are met.
- .5 Coordinate requirements for data/voice jacks and wiring with telecommunications network cabling specialist trade. Size raceways for computer network structured cabling in compliance with EIA/TIA Standards for required Category of cabling as per section titled Structured Cabling System. Increase raceway sizing to suit.
- .6 Acceptable manufacturers are:
 - .1 Legrand-Wiremold;
 - .2 Thomas & Betts;
 - .3 Hubbell;
 - .4 Panduit.

Part 3 - Execution

3.1 INSTALLATION OF SURFACE SERVICE RACEWAYS

- .1 Provide surface mounted, service raceway assemblies complete with specified and required accessories necessary for a complete electrical raceway system. Site measure for proper lengths. Provide required type and quantity of receptacles. Confirm exact types for each application with Consultant prior to ordering. Confirm finishes with Consultant prior to ordering.
- .2 Obtain required training from manufacturer representative on any special installation procedures. Install raceways in accordance with manufacturer instructions to suit specific installation requirements. Use manufacturer recommended tools for cutting and installing raceways.
- .3 Assemble and secure raceways, boxes and other components to surfaces in accordance with manufacturer instructions and requirements. Connect complete. Where possible butt raceway ends to adjacent walls, cabinets, counters, etc. Where raceway is to be attached to equipment or sections of millwork, install raceway for full length of equipment/millwork, unless otherwise noted. Mount-faceplates flush to raceway with no gaps. Keep number of elbows, offsets and connectors to a minimum.
- .4 Do not exceed wire fill requirements given in manufacturer instructions.
- .5 Provide barriers for systems with different voltages in raceway.
- .6 Test prewired raceways after installation work is complete.
- .7 Provide wiring devices of types and standards as specified in wiring devices section.
- .8 Coordinate requirements with structured cabling system vendor to ensure that raceways are suitable for and comply with standard for telecommunication jacks and cabling. Ensure that device mounting brackets are co-ordinated to suit final modular jack being installed.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products specified in this Section.
- .2 Do not order any device unless finishes have been reviewed and approved by Consultant.

Part 2 - Products

2.1 SWITCHES

- .1 Switches to be CSA approved, ULC listed and labelled devices.
- .2 Hubbell Canada Inc., HBL 1221 Series, CSA approved, heavy duty, industrial grade, back, and side wired, AC quiet action toggle type, 20 ampere, 120-277 V switches. Switches to include steel-nickel plated bridge, nylon toggle, one piece rivet-less copper alloy spring contact arm and terminal plate, silver cadmium oxide contacts, brass binding head screws, one piece integral grounding terminal and stainless steel automatic grounding clips. Provide single way, 2-way, 3-way, and key type to suit specific application requirements.
- .3 Hubbell Canada Inc. No. 1221-IL, CSA approved, heavy duty, specification grade, AC quiet action, illuminated polycarbonate handle toggle type, 20 ampere, 120-277 V switches.
- .4 Acceptable manufacturers are:
 - .1 Hubbell Canada Inc.;
 - .2 Cooper Wiring Devices (Arrow Hart);
 - .3 Leviton.

2.2 RECEPTACLES

- .1 Receptacles to be CSA approved, ULC listed, certified and labelled devices.
- .2 Hubbell Canada Inc., No. HBL5262 / HBL5362 CSA approved, ULC listed, extra heavy duty, specification grade, back and side wired, flush, nylon face/body construction, duplex U-ground, 15/20 ampere, 125 V, 2-pole, 3-wire grounding receptacles complete with one piece nickel-plated brass mounting strip with integral grounding clips, ground retention clips, nickel-plated brass wiring clamps with nickel-plated brass screws, front circuit identification area and reinforced thermoplastic base.
- .3 Hubbell Canada Inc., No. BR15TR series, commercial specification grade, 15 ampere, 125 V, 2-pole, 3-wire grounding, tamper-resistant (safety shutter) duplex receptacles.
- .4 Hubbell Canada, No. GFR 5262SG / GFR 5362SG "AUTOGUARD" Series, extra heavy duty grade, 15/20 ampere, 125 V, duplex, ULC Class "A", Group One, tamper resistant, weather resistant ground fault circuit interrupting receptacles complete with automatic self-test diagnostics, green power ON LED, red ground fault LED and 10 kA short circuit current rating.
- .5 Hubbell Canada Inc., No. USB 15X2 "Style Line" series, CSA approved, ULC listed, 2-USB ports (3.8 A, 5V DC, type A, class 2.0) and 15 ampere, 125 V rated duplex decorative power receptacles, tamper resistant, back and side wired.
- .6 Hubbell Canada Inc., No. BR15C2GRY/BR20C2GRY "Permanently marked" plug load controlled series, industrial grade, permanently marked with two controlled faces symbol identifying controlled receptacle, CSA approved, ULC listed, back and side wired, nylon face/body construction, 15/20 ampere, 125 V, grounding, duplex receptacles; for use with automatic outlet control systems, and with factory broken split circuit tab allowing control of half of receptacle; interconnected to control module relays of lighting control system or other building control systems;

- .7 Hubbell Canada Inc., No. 9430, EEMAC type 14-30R, 30 ampere, 125/250 V, 3-pole, 4-wire single electric clothes dryer receptacles with steel faceplates.
- .8 Hubbell Canada Inc., No. 9450, EEMAC type 14-50R, 50 ampere, 125/250 V, 3-pole, 4-wire single electric range receptacles with steel faceplates.
- .9 Hubbell Canada, No. IG 5262, heavy duty, specification grade, 15 ampere, 125 V, duplex, orange colour, nylon construction, back, and side wired isolated receptacles.
- .10 Hubbell Canada, No. BR15TR series, specification grade, 15 ampere, 125 V, 2-pole, 3-wire, tamper resistant, safety shutter receptacles.
- .11 Hubbell Canada, No. 4710, specification grade, 15 ampere, 125 V, single, 2-pole, 3-wire grounding twist lock receptacle.
- .12 Hubbell Canada, No. 15 ampere and 50 ampere receptacles complete with neutral and ground conductors required for indicated number of phases as shown.
- .13 Acceptable manufacturers are:
 - .1 Hubbell Canada Inc.;
 - .2 Cooper Wiring Devices (Arrow Hart);
 - .3 Leviton.

2.3 FACEPLATES

- .1 Grade 18 8, type 430, 1 mm (0.032") thick stainless steel, satin, brushed or natural finish, complete with a peel off protective plastic film, and stainless steel screws.
- .2 Hubbell Canada Inc., No. WP26E/WP26EH, NEMA 3R rated, CSA approved, ULC listed and labelled, single gang, vertical/horizontal mounting, weather-proof in-use, gasketed, cast aluminium faceplates for GFI receptacles in wet locations.
- .3 Hubbell Canada Inc., No. HBL1795, ULC listed and labelled, single gang, vertical mounting, weather proof in-use, gasketed, clear bubble plate, silicone rubber faceplates for standard AC toggle switches in wet locations.
- .4 Galvanized steel stamped faceplates.
- .5 Acceptable manufacturers are as per switches and receptacles.

2.4 PUSHBUTTONS OPERATORS

- .1 Rockwell Automation (Allen-Bradley) Ltd., 800T Series operators as follows:
 - .1 emergency off pushbuttons: oversized 60 mm (2-1/2") diameter red plastic mushroom head pushbutton with shroud, thrust washer, and an aluminum faceplate with "EMERGENCY POWER OFF" identification lettering or other nomenclature as required to suit application;
 - .2 pushbuttons: standard 30 mm (1-1/4") diameter plastic pushbuttons in Red/Green colours as required for application, momentary/maintained/2 position push-pull operations as required, flush/extended/mushroom heads; non-illuminated/illuminated, with aluminum faceplate with identification lettering nomenclature as required to suit application;
 - .3 key operated switches: standard 30 mm (1-1/4") diameter key cylinder lock operator, 2 or 3 position operations; non-illuminated, with aluminum faceplate with identification lettering nomenclature as required to suit application;
 - .4 with enamel painted steel or stainless steel faceplate for flush mounting onto recessed wall boxes or in millwork, suitable for mounting of devices;
 - .5 with NEMA 1 box for surface mounting applications in climate controlled areas, CSA approved for application and of size suitable for mounting of devices;
- .2 Exact type and ratings of devices are to suit specific applications.

- .3 Acceptable manufacturers:
 - .1 Rockwell Automation (Allen-Bradley);
 - .2 Eaton (Cutler-Hammer);
 - .3 Square D;
 - .4 GE.

2.5 RETRACTABLE REELS

- .1 Gleason Reel, ACA Cord Reel, ACA Industrial series, CSA approved, ULC listed and labeled, designed for indoor and outdoor applications. Hazardous location types are to be provided in areas designated as hazardous locations. Requirements for end receptacles and boxes are to be as per drawing notes.
- .2 ACA series features include:
 - .1 maximum operating capacity of 30A, 250V AC;
 - .2 Durable, corrosion resistant cast aluminum construction;
 - .3 Yellow or white powder coat finish;
 - .4 Movable guide arm can be mounted in two positions;
 - .5 Positive latch mechanism automatically maintains desired cord length;
 - .6 Ratchet lock can be disengaged in field for constant tension applications;
 - .7 16-10AWG, 3&4 conductor cord;
 - .8 10AWG fully rated at 30 amps;
 - .9 Bare SJO cable, length of 35ft;
 - .10 Dual Receptacle module complete with two (2) back-to-back, 120V, 15/20A, T-Slot, GFCI receptacles with two (2) USB Charging ports per receptacle
- .3 Where applicable, determine classification of hazardous location and provide properly rated reel to suit classification requirements. Ensure that connecting conduits and boxes comply with hazardous location rating requirements.
- .4 Acceptable Manufacturers:
 - .1 Appleton Electric;
 - .2 Crouse-Hinds;
 - .3 Thomas & Betts;
 - .4 Cooper Wiring.

Part 3 - Execution

3.1 INSTALLATION OF SWITCHES

- .1 Provide switches and install in electrical outlet boxes. Refer to drawings to determine flush or surface mounting requirements. Generally, flush mount devices in finished areas. Size electrical boxes to suit device requirements as per device manufacturer recommendations. Properly ground device to box and ground system as per code requirements and manufacturer instructions.
- .2 For pricing only, switches to be ivory for devices connected to normal power circuits, red for devices connected to essential power circuits including isolated power centres.
- .3 Illuminated operation of lighted switches to suit specific applications as confirmed with Consultant.
- .4 Ensure that switches located adjacent to doors are located at strike side of door. Confirm door swing requirements on architectural drawings, not on electrical drawings.
- .5 Coordinate installation of door switches with trades responsible for provision of doors and frames. Confirm exact locations of switches with Consultant to ensure optimum operation of switch to door position.

- .6 Additionally, refer to testing and verification requirements in Section titled Electrical Work Analysis and Testing and include applicable requirements.

3.2 **INSTALLATION OF RECEPTACLES**

- .1 Provide receptacles and install in electrical outlet boxes. Refer to drawings to determine flush or surface mounting requirements. Generally, flush mount devices in finished areas. Size electrical boxes to suit device requirements as per device manufacturer recommendations. Properly ground device to box and ground system as per code requirements and manufacturer instructions.
- .2 Install USB charger receptacles in extra deep boxes in accordance with manufacturer recommendations.
- .3 Provide machine printed clear label with black lettering identifying circuit number and panelboard from where each device is fed, and secure to device faceplates at all outlets. Review exact location for identification with Consultant.
- .4 Where receptacles are indicated in counters and benches, box cut-out to be provided in counter and bench. Provide a box, receptacle, plate and branch circuit wiring. Branch circuit wiring within counters and benches to be flexible armoured cable, under requirements of local governing electrical code and standards. Install and connect complete.
- .5 Install plug load controlled receptacles of type compatible with and coordinated with connected control system. Confirm compatibility of receptacle with control system vendor. Circuit split controlled receptacles as per local governing electrical code requirements.
- .6 Review final device finishes with Consultant. Do not order any devices unless final finishes have been approved by Owner and reviewed with Consultant.
- .7 Additionally, refer to testing and verification requirements in Section titled Electrical Work Analysis and Testing and include applicable requirements.

3.3 **INSTALLATION OF FACEPLATES**

- .1 Provide each switch and receptacle with a faceplate with an opening or openings suitable for device it conceals and covers openings around boxes. Secure faceplates to device frames with screws to match faceplates. Provide larger than standard type faceplates for devices that require engraved nomenclature to define special purpose for that device.
- .2 Provide galvanized stamped steel faceplates in service areas and equipment rooms where devices are surface mounted.
- .3 Provide stainless steel type standard size faceplates for flush mounted devices.
- .4 For flush mounted devices, provide oversized faceplates as required to properly cover wall opening around recessed boxes.
- .5 Provide faceplates with suitable identification labels. Review exact locations for labelling with Consultant.
- .6 In addition to identification requirements specified with devices, provide faceplates with printed self-adhesive clear label with black lettering on outside face identifying circuit number and panel feeding device.
- .7 Review exact material, finish, and colour of faceplates for devices in any particular area with Consultant prior to ordering.

3.4 **INSTALLATION OF PUSHBUTTON OPERATORS**

- .1 Provide specified and suitable pushbutton operators and pilot lamps to suit various applications.
- .2 Where flush mounted, provide faceplate for mounting onto recessed boxes.

- .3 Where surface mounted climate controlled areas, provide suitable NEMA 1 box. In non-climate controlled areas, surface mounted devices to be mounted within minimum NEMA 3R rated boxes.
- .4 Install devices in accordance with manufacturer instructions to suit application requirements of Owner. Connect complete to respective equipment being controlled. Provide required wiring in conduit.
- .5 Test and verify operation of each device. Provide engraved lamacoid nameplate to identify system being operated and any special instructions. Confirm exact nomenclature with Consultant prior to ordering.

3.5 **INSTALLATION OF RETRACTABLE REELS**

- .1 Provide retractable reels and secure to construction in accordance with manufacturer instructions. Ceiling box to be secured to ceiling slab or ceiling structure in manner to provide adequate support to entire assembly.
- .2 Install devices in accordance with manufacturer instructions.
- .3 Provide receptacles and boxes in required configuration and types.
- .4 Ground and bond devices as per local electrical code requirements.
- .5 Refer to and provide additional applicable testing requirements of distribution system testing and coordination study article.
- .6 Provide engraved lamacoid nameplates for equipment and components. Prior to manufacture of nameplates, confirm exact nomenclature with Consultant in writing. During installation on site, provide temporary labelling until permanent nameplates are installed.
- .7 Label outlets with circuit number and source panel.
- .8 Test each device and assembly. Verify proper operation. Adjust as required.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products specified in this Section.

Part 2 - Products

2.1 DISCONNECT SWITCHES

- .1 Eaton, heavy duty, CSA approved, disconnect (safety) switches. Features include:
 - .1 front operated with a handle suitable for padlocking in "OFF" position and arranged so that enclosure cover cannot be opened while handle is in "ON" position
 - .2 operating mechanisms: quick-break, positive acting with visible blades and a line terminal shield;
 - .3 fusible units with fuse clips suitable for HRC fuses, unless otherwise noted;
 - .4 ampere rating, number of poles and fuse requirements as indicated on drawings;
 - .5 factory primed and painted switch enclosures.
- .2 Disconnects for variable speed drives to be suitable for use with such drives and include auxiliary switch/contact to de-energize control power circuit, as required and as applicable.
- .3 Enclosures for disconnects mounted in interior climate controlled areas and standard non-climate controlled areas to be NEMA 3R. For corrosive environmental applications, enclosures to be minimum NEMA 4X.
- .4 Acceptable manufacturers are:
 - .1 Eaton;
 - .2 Siemens Electric Ltd.;
 - .3 Schneider Electric (Square D).

2.2 FUSES

- .1 Unless otherwise indicated, fuses to be Form I, Class "J" HRC fuses for constantly running equipment, and Form II, Class "C" HRC fuses for motorized equipment that cycle "ON" and "OFF".
- .2 Fuses to be of type suitable for applications as required by local governing electrical codes and in coordination with respective equipment Manufacturer recommendations in which fuses are required. Coordinate also with Mechanical Division Contractor for requirements for Mechanical Division equipment.
- .3 Fuses to be of product of one manufacturer.
- .4 Acceptable manufacturers are:
 - .1 Mersen (Ferraz Shawmut);
 - .2 English Electric Ltd.;
 - .3 Noram;
 - .4 Cooper Bussmann.

Part 3 - Execution

3.1 INSTALLATION OF DISCONNECT SWITCHES

- .1 Provide disconnects switches and install into locations and connect complete. Ensure adequate clearance is provided as per local code requirements and as required for access for operation and maintenance. Install as follows:
 - .1 wherever shown on drawings and/or specified herein;
 - .2 wherever required by MCC/VFD/starter schedule drawings;
 - .3 for motorized equipment which cannot be seen from motor starter location or is more than 9 m (30') from starter location (in accordance with local governing electrical code requirements);
 - .4 for "packaged" equipment fed from a motor starter panel.
- .2 Ensure enclosure ratings are suitable for intended applications.
- .3 Provide engraved Lamacoid nameplate with nomenclature reviewed with Consultant.

3.2 INSTALLATION OF FUSES

- .1 Install fuses in mounting devices immediately before energizing circuit.
- .2 Ensure correct fuses fitted to physically matched mounting devices.
- .3 Ensure correct fuses fitted to assigned electrical circuit.
- .4 Provide a complete set of fuses for each fusible disconnect, motor starter, and similar fusible equipment provided or supplied.
- .5 Supply 3 spare fuses of each size and type used on project, mount fuses in cabinet. Secure cabinet in wall location as reviewed with Consultant.

3.3 ELECTRICAL CONNECTIONS FOR MECHANICAL, OWNER, ETC., EQUIPMENT

- .1 Provide required electrical connections to apparatus provided and/or supplied by Electrical Divisions. Review shop drawings and coordinate with each equipment vendor, requirements for power feeds and control/communication interconnections and provide these requirements to complete installations work.
- .2 In addition to providing electrical feeders and connections to equipment provided by Electrical Divisions, provide required electrical connections to apparatus provided and/or supplied by Mechanical Divisions, Owner and as part of other Divisions.
- .3 Unless otherwise noted, provide electrical connections including power and control wiring for equipment supplied by Owner or by other Divisions, and except where specified for control wiring of Mechanical Divisions automatic control systems specification Section. Provide complete wired and empty conduit systems with fish cord, junction boxes, pull boxes, outlet boxes, faceplates, sleeves, etc. Provide disconnect switches, receptacles and other required wiring and connection accessories. Coordinate work with respective Consultants and suppliers of equipment to be provided with electrical connections.
- .4 Refer to Division 11, and include for coordination and interconnections of Division 11 requirements and equipment schedule.

- .5 Coordinate with trades of other Divisions to ensure provision of proper electrical requirements. Unless otherwise noted or reviewed with Consultant, be responsible for provision of interconnect wiring between remote operator devices, controllers, and equipment being controlled by operator devices, whether or not such devices/controllers are supplied by Electrical Divisions. Where equipment is of split unit design and line voltage is required to both units, be responsible for feeders to each unit as coordinated with equipment manufacturer and Division responsible for equipment. Provide disconnect switches, receptacles and other required wiring and connection accessories. Provide system/equipment power feeds with hard wired or receptacle type connections, as required. Coordinate exact requirements prior to start of work, at time of shop drawing submissions and prior to roughing-in of work. Coordinate work with suppliers of equipment to be provided with electrical connections which may include but not be limited to following:
 - .1 laboratory equipment;
 - .2 audio visual systems;
 - .3 telecommunication systems;
 - .4 mechanical systems and equipment.
- .6 Provide coordination of alarm connections of equipment with Mechanical Divisions BAS Contractor. Refer to drawings of both Electrical Divisions and Mechanical Divisions for BAS points to be connected. Include for wiring in conduit, contacts, termination/junction boxes, etc., as required for inter connection.
- .7 Mechanical Divisions are responsible for supply of motor starters and variable frequency drives (VFDs) (also known as variable speed drives -VSDs) and harmonic filters for motorized apparatus supplied by them and is to provide Lamacoid identification throughout. Motor starters, VFDs and/or MCCs are generally to be as scheduled. Generally starters are supplied in following manner:
 - .1 loose starters for mounting adjacent to apparatus or on motor starter panels;
 - .2 mounted starters in factory assembled and pre-wired motor control centres;
 - .3 mounted starters on factory assembled and pre-wired packaged equipment.
- .8 VFDs (with harmonic filters where required) are to be supplied and set in position by Mechanical Divisions. Coordinate installation and connection requirements with Mechanical Divisions and respective equipment manufacturers. Obtain required wiring diagrams.
- .9 Be responsible for following work:
 - .1 mounting loose starters and providing "line" and "load" power connections;
 - .2 making "line" side power connections to panelboards and "load" side connections to motors;
 - .3 making "line" side power connections to starters on "packaged" equipment;
 - .4 coordinating feeder entries to starters and starter assemblies with Mechanical Divisions;
 - .5 providing additional disconnect switches (complete with identification) detailed on drawings, or required by Code, or for apparatus which cannot be seen from its starter or is in excess of 9 m (30') from its starter;
 - .6 connections to thermistors and provision of additional relays as required for connections to starters; generally, Mechanical Divisions are to supply required thermistors and relays necessary for starters; review Mechanical Divisions specifications and/or drawings defining these requirements and include necessary work, wiring, conduit and components not being supplied by Mechanical Divisions;
 - .7 performing required motor starter interlocking in accordance with requirements specified and as outlined on starter schedules; coordinate interlocking requirements with Mechanical Divisions;

- .8 ensure that an identification nameplate is provided on each motor starter or disconnect;
- .9 ensure that an identification nameplate is provided on each disconnect switch nameplate is to identify name and voltage;
- .10 ensure that an identification nameplate is provided and attached with stainless steel screws to each separately mounted 3-phase motor starter or group of 3-phase motor starters a suitably sized black-white-black Lamacoid nameplate engraved to read:
- .11 "MOTOR(S) IS CAPABLE OF MAKING TWO (2) STARTS IN SUCCESSION, COASTING TO REST WITH APPROXIMATELY 15 MINUTES ELAPSED TIME BETWEEN STARTS, WITH MOTOR INITIALLY AT AMBIENT TEMPERATURE, OR OF MAKING ONE (1) START WITH MOTOR INITIALLY AT A TEMPERATURE NOT EXCEEDING ITS RATED LOAD OPERATING TEMPERATURE, IF Ω^2 OF LOAD, LOAD TORQUE DURING ACCELERATION, APPLIED VOLTAGE AND METHOD OF STARTING ARE THOSE FOR WHICH MOTOR WAS DESIGNED."
- .12 Where supplied by Mechanical Divisions and connected by Electrical Divisions, connect VFDs and harmonic filters in strict accordance with manufacturer instructions. Provide manufacturer recommended conductors and connectors to suit respective connected equipment. Provide required upstream fused disconnects or breakers and overload protection. Maintain separation of power and control conductors as per Manufacturer requirements to minimize effects of electromagnetic interference. Properly ground and bond equipment. Coordinate exact installation requirements with Mechanical Division and equipment vendors.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products of this Section, and on Schedule of Luminaires on drawings.
- .2 Include photometric data, lamp, and ballast information for each luminaire. Include ballast data identifying maximum circuit loading limitations.
- .3 Photometric data to include: total input watts, candlepower summary, candela distribution zonal lumen summary, luminaire efficiency, CIE type, coefficient of utilization, lamp type and lumen rating in accordance with IESNA testing procedures.
- .4 Include copy of certification that lenses and louvers comply with local governing building code requirements for flame spread ratings.

1.2 WARRANTY

- .1 Warranty requirements are as follows:
 - .1 unless otherwise noted, LED and LED drivers for a period of five (5) years from date of acceptance of Work by Owner for its intended use;

1.3 SUBSTITUTIONS

- .1 Provide luminaires as specified in Schedule of Luminaires and as per documented List of Manufacturers, where applicable. During construction period, no substitutions are permitted unless compelling reasons are given and accepted by Owner and Consultant. A delay caused by Contractor's failure to order luminaires to meet construction schedule is not a valid reason.
- .2 Make requests for proposed substitutions as per requirements of Section titled Electrical Work General Instructions and Division 01.
- .3 Consideration of any proposed substitutions after Bid Period to be at Consultant's sole discretion.

Part 2 - Products

2.1 LUMINAIRES

- .1 Provide luminaires in accordance with Schedule of Luminaires found on drawings. Luminaires are to be CSA approved or have special local electrical authority approval.
- .2 Some luminaires as noted or directed by Consultant or identified in other Division documents may be supplied by Owner or under another Division of Work. Include in Bid, Work and materials to accommodate such fixtures, including:
 - .1 receiving and inspecting fixtures;
 - .2 complete installation;
 - .3 providing basic installation hardware not supplied by luminaire manufacturer;
 - .4 aiming and connecting;
 - .5 providing power feeders and conduit/boxes;
 - .6 cleaning, adjusting and testing;
 - .7 providing lamps where documented or as scheduled, unless otherwise noted or directed by Consultant or supplied with fixture by fixture manufacturer;
 - .8 provide required power connections and where luminaires are controlled via remote low voltage controller;
 - .9 include for installation of controller and providing required low voltage wiring in conduit and necessary connections;

- .10 coordination of exact requirements with supplier of fixtures and Consultant prior to installation.
- .3 Provide thickness of metal as indicated in Schedule of Luminaires and details, or as required so that luminaires are rigid, stable and resists deflection, twisting, warping or bending under normal installation procedures, re-lamping etc., or no less than requirements specified herein the specifications.
- .4 Unless otherwise noted, construct fluorescent luminaire bodies from minimum 20 gauge cold rolled prime steel and of rigid construction to permit any suspension method without sag. Unless otherwise noted, provide body finishes of corrosion resistant, chemically treated and electrostatically spray painted baked white enamel. Reflecting surfaces to be white with an average reflectance of not less than 85%. Provide adjustable mounting brackets for troffers mounted in ceilings.
- .5 Unless otherwise noted, linear and continuous linear architectural LED luminaires bodies to be constructed of extruded aluminum and of rigid construction. Unless otherwise noted, provide body finishes of corrosion resistant, chemically treated and electrostatically applied post powder coat finish. Efficiency not to be less than 69%.
- .6 Unless otherwise noted, vandal resistant luminaires to be constructed of heavy duty extruded aluminum rails and die cast end caps, complete with stainless steel Torx with centre reject pin and Allen head set screws. Screw heads to be mounted and concealed under lens. Lens to be extruded UV stabilized polycarbonate lens with internal linear ribbed design.
- .7 Provide neoprene or silicone gasketing, barriers and stops where required to prevent light leaks or water/water vapour penetration.
- .8 Fabricate housings to allow for easy accessibility and replacement of parts.
- .9 Fabricate fixtures with a minimum number of joints. Make unexposed joints by acceptable method such as welding, brazing, screwing or bolting. Soldered joints are unacceptable. Do not use blind metal tapping methods or rivets for fastening parts which must be removed during service, or for fastening electrical components and supports. Cast parts, including die-cast members, to be of uniform quality, close grained, rigid, true to pattern, free from blow holes, pores, discoloration, hard spots, shrinkage defects, and cracks or other imperfections that affect strength and appearance or are indicative of inferior metals or alloys.
- .10 Reflectors and reflecting cones or baffles to be free of any tooling marks, spinning lines or marks by other assembly techniques. For fluorescent sources, iridescence to be low. Finishes to be equal to first quality polished, baffled, and anodized "Alzak".
- .11 Lenses and louvres to comply with local governing building code and other local governing code flame spread rating requirements.
- .12 Unless otherwise noted, construct acrylic lens from 100% virgin acrylic and not less than 3.22 mm (0.125") thick. Glass lenses to be minimum 9.5 mm (0.375") thick.
- .13 Luminaires to be factory assembled and tested prior to delivery on site.
- .14 Exposed parts and hardware of luminaires located in non-climate controlled areas to be corrosion resistant and weather resistant. Hardware to be tamper-proof. Manufacturer exterior luminaire poles with corrosion resistant finish and construction. Pole suppliers to ensure that poles supplied are suitable for steady wind velocity and gust velocity of area of installation, and suitable for total effective projected area of lighting equipment. Submit verification of this with shop drawings.
- .15 When requested, submit luminaire samples.
- .16 Dimensions for coves, valances, and strips as shown on drawings are for bidding purposes only. Job measure for exact dimensions of louvres, lenses and strips.
- .17 Dimensions for linear and continuous linear LED as shown on drawings are for bidding purposes only. Job measure for exact dimensions requirements to suit installation location.

- .18 Confirm exact colours and finishes of luminaires with Consultant after award of contract but prior to ordering. Obtain information in time to meet installation schedule.
- .19 Acceptable Luminaires Manufacturer/Supplier.
 - .1 GS Lighting Group;
 - .2 Medgar Lighting;
 - .3 Saalex SW;
 - .4 WSC Lighting Systems.

2.2 **LEDS & DRIVERS**

- .1 General features include:
 - .1 CSA approved, ULC listed and labelled;
 - .2 Operating temperature:
 - .1 Luminaires for applications in non-climate controlled area: operating temperature range through -40°C (-40°F) to 60°C (140°F);
 - .2 Luminaires for applications in climate controlled area: operating temperature range through -20°C (-4°F) to 50°C (122°F);
 - .3 With rapid and changing development of LED technology, provide most technically proven and most advanced and successfully tested LED technology at time of installation;
 - .4 Specification standards to meet requirements of IES LM 79 and LM-80.
 - .5 Be 100% compatible with connected dimmer controls to provide dimming down to 5%.
- .2 Light emitting diodes (LEDs) features to include:
 - .1 LEDs to be selected from same colour bin size for consistency in chromaticity and meet ANSI C78 377A as a minimum;
 - .2 generally, colour temperature range to be from 2700 K to 6500 K; specific temperature requirements to be identified on Schedule of Luminaires;
 - .3 minimum CRI of 80 ;
 - .4 rated life (based on 70% lumen depreciation level) from 50,000 to 70,000 hours.
- .3 Driver (ballast) features to include:
 - .1 Operate from 60 Hz input source of 120 VAC with sustained variations of $\pm 10\%$ (voltage and frequency) with no damage to driver;
 - .2 Output regulated to $\pm 5\%$ across load range;
 - .3 Power factor greater than 0.90;
 - .4 Total harmonic distortion less than 20%;
 - .5 Class A sound rating;
 - .6 Comply with ANSI C62.41 Category A for transient protection.
- .4 Acceptable manufacturers to be as recommended by luminaire manufacturers.

2.3 **STAGE LIGHTING**

- .1 Coordinate with Hamilton Video and Sound for package to be supplied.
- .2 Existing fixtures are to be replaced with new.

Part 3 - Execution

3.1 INSTALLATION

- .1 Provide luminaires as required. Obtain required training from manufacturer representative on any special installation procedures. Install products in accordance with manufacturer instructions to suit specific installation requirements.
- .2 Before placing luminaire orders:
 - .1 verify quantity requirements;
 - .2 thoroughly review ceiling types, finishes and construction details; verify ceiling types with latest Architectural Drawings; order luminaires to suit correct ceiling type;
 - .3 ensure that required mounting assemblies, frames, rings and similar features are included;
 - .4 confirm colours and finishes with Consultant.
- .3 Include for assembly and mounting of luminaires and lamps, complete with:
 - .1 wiring and connections;
 - .2 fittings and hangers;
 - .3 aligners;
 - .4 box covers;
 - .5 other accessories required for a complete, safe and fully operational assembly.
- .4 Where outlet boxes locations are shown on drawings, they are diagrammatic only. Position outlet boxes to coincide with suspension hangers and knockouts.
- .5 Install ceiling fixtures in centre of tiles unless dimensioned otherwise on Reflected Ceiling Plans. Locate hangers on tile centres or intersections. Mount recessed downlights, troffers, and surface mounted luminaires in or on full tiles. Install fixtures in and on acoustical tile ceilings in alignment with tile joints.
- .6 Cut holes for recessed luminaires to exact size so that gaps are not visible or luminaire trims cover gaps.
- .7 Mount surface ceiling luminaires perfectly level or plumb, tightly to ceiling without showing a space or light leak between frame and ceiling.
- .8 Carefully align linear luminaires shown in continuous lines or rows, so that rows appear as straight lines. Variation in alignment not to exceed 6 mm (1/4") for any 5 m (16') run.
- .9 Provide spacers for fixtures mounted on low density ceiling material.
- .10 Provide plaster frames for recessed fixtures in plaster or gypsum board ceilings.
- .11 Prepare fixtures, trim and poles and standards required to be painted.
- .12 Wiring between fluorescent lamp holders and associated operating and starting equipment to be of similar or heavier gauge than leads furnished with approved types of ballasts with equal or better insulating and heat-resistant characteristics.
- .13 Protect wiring with tape or tubing at all points where abrasion may occur. Conceal wiring within fixture construction except where design or mounting dictates otherwise.
- .14 Splices:
 - .1 Minimize number of splices.
 - .2 Make with approved mechanical insulated steel spring type connectors, suitable for temperature and voltage conditions to which splices are to be subjected.
 - .3 Splices are not to be made unless properly terminated in accessible identified junction boxes.
- .15 Support luminaires directly by ceiling slab structure and not to formed steel decking, ceiling hangers, ductwork, piping, cable trays, etc.

- .16 Do not tighten wing nuts, bolts, or screws that allow fixture adjustment for recessed adjustable fixtures.
- .17 Install spread lenses only where called out on Schedule of Luminaires and Specifications.
- .18 Use cloth gloves when handling reflector cones, louvers, halogen lamps, glass, sconces and all exposed surfaces of fixtures.
- .19 Co-ordinate luminaire installation with work of other trades to ensure that necessary recessing depths and mounting spaces are provided.
- .20 Install luminaires in accordance with applicable architectural drawing reflected ceiling plans and/or wall elevations and/or field instructions issued by Consultant. Confirm luminaire locations prior to roughing-in. In equipment rooms, shafts and similar secondary areas, install luminaires after mechanical and other major work is roughed in and adjust luminaire locations as required.
- .21 Align and position all adjustable luminaires, and ensure that luminaires with adjustable lamp holders are properly positioned to correspond to lamps specified.
- .22 Comply with requirements of local governing electrical code regarding support of luminaires in suspended ceilings.
- .23 Independently suspend luminaires in suspended ceilings from ceiling slab. For each luminaire, provide minimum two (2) cable supports secured to ceiling slab and to luminaire. Confirm with local governing authorities and review with Consultant if a variance to this requirement can be made for specific luminaires of low weight.
- .24 Connect luminaires to power circuits and controls as required. Refer to drawings notes and schedules. Include for both normal and emergency power circuits as required.
- .25 Locate exit signs in final locations confirmed with Consultant and approved by local building code authority. Connect to power circuits as required. Where applicable for emergency power requirements, connect to emergency battery units. Relocate exit sign and re-direct direction arrows to suit local building code authority requirements and Consultant's directions.
- .26 Notify Consultant immediately and relocate if necessary as directed by Consultant, if:
 - .1 fixture placement is in conflict with a structural beam, mechanical duct, plumbing pipe, etc.;
 - .2 space above ceiling is not sufficient;
 - .3 any reason that a fixture cannot be located where it is dimensioned or shown on construction documents.
- .27 Provide seismic restraints to suspended luminaires, in accordance with latest local governing building code requirements.
- .28 Ground and bond luminaires as per local governing electrical code requirements.
- .29 Prior to turn over of Work to Owner, clean luminaires in manner recommended by manufacturer and to satisfaction of Consultant.
- .30 Lamps to be new and intact when project is complete and ready for acceptance.
- .31 Include a full lamp listing in Operating and Maintenance Instruction Manuals.
- .32 Additionally, refer to testing and verification requirements in Section titled Electrical Work Analysis and Testing and include applicable requirements.

3.2 **STAGE LIGHTING**

- .1 Install according to supplier instructions, providing all power, control wiring, conduits, and supports for a turn-key system, from new dimming panel to fixtures.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products specified in this Section.
- .2 Include data sheets for cabling, faceplates, terminal cabinets, racks, etc., and proposed cabling testing sheets.
- .3 Submit following:
 - .1 proof that final installation drawings have been reviewed by a Registered Communications Distribution Designer (RCDD);
 - .2 sample of proposed test sheet;
 - .3 written confirmation that telecommunication system vendor is Manufacturer valid certified system vendor for at least duration of contract work and is in good standing at time of Bid submission;
 - .4 written evidence (copies of certificates) of vendor and technician qualifications;
 - .5 copy of system Manufacturer warranty.

1.2 REFERENCE STANDARDS

- .1 Comply with latest editions of following, as applicable for project:
 - .1 ANSI/TIA-568-C family of Telecommunications Standards, including:
 - .1 ANSI/TIA-568-C.0 - Generic Telecommunications Cabling for Customer Premises;
 - .2 ANSI/TIA-568-C.1 - Commercial Building Telecommunications Cabling Standard;
 - .3 ANSI/TIA-568-C.2 - Balanced Twisted-Pair Telecommunication Cabling and Components Standard;
 - .4 ANSI/TIA-568-C.3 - Optical Fiber Cabling Components Standard;
 - .5 Issued addenda.
 - .2 ANSI/EIA/TIA 606-B (CSA T528) - Administration Standard for Telecommunications Infrastructure of Commercial Buildings;
 - .3 ANSI/EIA/ TIA-607-B (CSA T527) - Grounding and Bonding Requirements for Telecommunications in Commercial Buildings;
 - .4 ANSI/EIA/TIA-569-C (CSA T530) - Commercial Building Standards for Telecommunications Pathway and Spaces;
 - .5 ANSI/TIA-526-14-B - Optical Power Loss Measurements of Installed Multimode Fiber Cable Plant;
 - .6 ANSI/TIA/EIA-526-7 - Optical Power Loss Measurements of Installed Singlemode Fiber Cable Plant;
 - .7 Latest Building Industry Consulting Service International (BICSI) standards;
 - .8 Applicable local Building Codes.
- .2 Work to be installed by system manufacturers certified system installers/vendors who are certified and experienced in implementing selected data cabling system and to perform related testing programs.
- .3 System final installation layout to be designed and/or reviewed by a RCDD. Submit shop drawings verifying this requirement.

1.3 WARRANTY

- .1 System manufacturers to provide a minimum twenty (20) year full parts, labour, and performance warranty on all passive components including structural cabling system. These warranties to be provided in written certificate form and that guarantee following:
 - .1 passive system components, e.g. patch panels, UTP cable and outlet jacks, are free from manufacturing defects in material or workmanship;
 - .2 approved cabling systems exceed specifications of TIA-EIA 568B.2.1 standards for specified category, in particular for attenuation and near-end cross-talk, loss and bandwidth requirements;
 - .3 installation supports applications for which it was originally designed as well as future versions of system performance specifications and any future applications using TIA/EIA 568B.2.1 component and cabling standards;
 - .4 replacement or repair of any originally installed registered system component to be completed at no cost for parts and labour to Owner during warranty period. Any components repaired or replaced to be warranted for remainder of warranty.
- .2 System manufacturers to provide in writing to Owner that in event of demise or failure or change in approved status of installing certified system installer/vendor, manufacturer to be responsible for providing another certified system installer/vendor to fulfil remainder of warranty conditions.
- .3 Claim for repair procedure to comprise of contractor being notified of a problem and who will conduct necessary tests and repairs to correct problem. Should contractor be unable to resolve problem, contractor to contact system supplier who will take necessary action and provide any technical support to correct problem.
- .4 Initial response time to a repair claim for a registered system to be within four (4) hours from time Contractor was notified of system fault.
- .5 Ensure that selected network cabling component manufacturer includes a system warranty that is a true "end-to-end" structured cabling system warranty from a single manufacturer, which includes data/voice communications outlet and patch cord at workstation, horizontal copper cabling, and patch panel and patch cords at LAN room.

1.4 SCOPE OF WORK

- .1 This Section provides minimum standards for provision of a structured cabling system to network computer systems for complex. Requirements for network electronics are responsibility of Owner Network Integrator. Work includes but is not to be limited to following:
 - .1 provision of category grade rating Category 6A cabling system for wireless access points within complex which can support use of intelligent network switches with Network Management capabilities;
 - .2 provision of category grade rating Category 6 cabling system for wall devices within complex which can support use of intelligent network switches with Network Management capabilities;
 - .3 organized wiring in a structured cabling system using point to point distribution system incorporating modular terminations;
 - .4 provision of data and voice cabling, data and voice communications outlets, patch panels and associated equipment;
 - .5 system testing and verification;
 - .6 coordination of system requirements and integration requirements with integrated systems.

- .2 The local area network system must be "protocol neutral" and provide users access into a variety of resources from any location within the Complex. An Ethernet backbone shall be utilized for the system with intelligent network switches coordinating and managing data flow. The wiring configuration is based on a "physical star" topology in which cabling runs emanate in a radial pattern from the main data communications room in which the intelligent switches are located.
- .3 Technical features of the structural cabling plan include:
 - .1 use of Category 6A cabling to each data outlet serving wireless access points.
 - .2 use of Category 6 cabling to all other data/voice outlets;
 - .3 use of modular Category 6A jacks at wireless access points ends of data cabling run;
 - .4 use of modular Category 6 jacks at workstation ends of data/voice cabling run;
 - .5 backward compatibility to categories 5e, 5 and 3.
- .4 The network cabling system vendor shall coordinate with Electrical Contractor to ensure that properly sized conduits, back boxes outlet boxes, junction boxes and floor boxes are provided of sufficient size as per EIA/TIA Standards to accommodate Category system wiring and devices, with particular emphasis on bending radii of cabling. Replace to suit, Conduit and boxes not meetings required Category rating requirements.
- .5 Design system to support minimum 802.11a/b/g/n/ac standards.

1.5 SYSTEM SUPPLIER QUALIFICATIONS

- .1 Vendor responsibility for provision of system to have following qualifications:
 - .1 being an established communications and electronics contractor that has and currently maintains a locally run and operated business for at least five years and holds applicable provincial and local licenses;
 - .2 be an Authorized Distributor or established franchisee for manufacturer of product/system proposed with full Manufacturer warranty privileges and be capable of providing post warranty service;
 - .3 employ technicians who have attended and successfully completed Manufacturer technical certification classes for proposed system;
 - .4 show satisfactory evidence, upon request, that they maintain a fully equipped service organization capable of furnishing adequate inspection and service to system on a 24-hour/7-day basis;
 - .5 maintain at their facility necessary spare parts in proper proportion as recommended by manufacturer to maintain and service equipment being supplied.
- .2 Submit written evidence of qualifications with shop drawings submission.
- .3 Vendors not meeting any of the above qualifications may be disqualified at Owner's discretion and replaced with qualified vendor acceptable to Owner.

Part 2 - Products

2.1 HORIZONTAL CABLING

- .1 Colour coded Data (White) cables shall be 4 conductors, solid copper #24 AWG, 100 ohms balanced, Cat 6A/CAT 6 UTP (enhanced unshielded twisted pair) cable.
- .2 Category 6 system to exceed ANSI/TIA/EIA 568-C.2-1 standard for a Category 6 cable. Demonstrate that proposed Manufacturer solution is guaranteed to exceed Category 6 requirements across entire swept frequency range of 1 - 250 MHz, by margin as per base specified product. Submit with shop drawings, ETL test reports to verify full channel performance of cable.

- .3 Plenum rated UTP CMP cable (NFPA 262 Flame rating) is to be used exclusively in all ceiling spaces above tile. Whether or not those areas are designed as plenum areas or not.
- .4 For installations in all ceiling spaces, Cat 6A plenum rated cables shall be Panduit #PUP6AM04WH-UG, UTP, CMP, NFPA 262, CMP, cable.
- .5 For non-plenum use, Cat 6 cables shall be Panduit #PUR6C04WH-U (white), Cat 6, UTP, CMR, riser cable.
- .6 For installations in air plenums, Cat 6 cables shall be Panduit #PUP6C044WH (white), Cat 6, UTP, CMP, NFPA 262, CMP, plenum cable.
- .7 Incoming copper cabling to be provided with suitable lightning protection devices. Refer to additional requirements later in this Section.

2.2 WALL DEVICE BOXES

- .1 Recessed/flush mount device boxes to be based on the following specifications:
 - .1 Single gang cover plate mounting bracket (where applicable) - Cooper B-Line #BB15.
 - .2 Single gang cover plate mounting bracket (where applicable) - Cooper B-Line #BB10.
- .2 Surface device boxes to be based on the following specifications:
 - .1 Single gang deep cast box, grey, with 3/4" threaded hubs (conduit fill rate 4 cables=44.6%, 3 cables=33.5%) - T&B #TD14-2
 - .2 Two gang deep cast box, grey, with 1" threaded hubs (conduit fill rate 6 cables=41.1%, 5 cables=34.5%) - T&B #T&B 2IHD5-3 (1" box); Note: requires single gang reducing plate Panduit #MIWBAlW.

2.3 OUTLETS

- .1 Data/voice outlets to be based on the following specifications:
 - .1 Provide RJ-45 jacks Panduit #CJ688TGOR (CAT6, orange) and Panduit #CJ6X88TGWH (CAT 6A, white) data outlets.
 - .2 Where 1 jack is shown provide a 2-position faceplate, Panduit #CFPL2IGY
 - .3 Where 2 jacks are shown provide a 4-position faceplate, Panduit #CFPL4IGY
 - .4 Where 4 jacks are shown provide a 6-position faceplate, Panduit #CFPL6IGY, and an appropriately sized box.
 - .5 Provide snap-in plastic dust covers on blank outlets and unused outlets.

2.4 PATCH PANELS

- .1 Terminate all computer data and voice cables on 24 port modular patch panel(s) Panduit Mini-com #CP24BLY mounted in standard floor mounted 19 inch-wide equipment rack (Minimum depth 19 inches).
- .2 Panels to be loaded with jacks. Each jack connector module to have a T568 (ISDN) eight pin RJ 45 jack on front and IDC type connectors on back. Confirm pin orientation with Owner and review with Consultant. Panels to mount onto standard EIA 19 inch racks or cabinets and have capability to be stacked in larger systems. Horizontal data and voice cabling for various server/hub rooms to terminate onto patch panels provided into floor standing equipment enclosures, as detailed and as required. Consult with Supervisor of Network Services, Information Technology Services Dept. for approval of wall mounting equipment enclosures.
- .3 Patchpanel system to include required accessories such as bezels, harnesses, pigtails, connectors, jumpers, and retaining rings, interlay racking panels, horizontal wire managers etc., to provide for patch cord management.

2.5 PATCH CORDS & CABLES

- .1 Copper data patchcords to be Panduit #UTP6ASD7 (Off white) Panduit Advanced MaTriX Cat6A (SD-small diameter) UTP, CM, 7ft patch cord. Note: Consult with Supervisor of Network Services, Information Technology Services Dept. for additional patch cord colour requirements.
- .2 Copper patchcords to be factory terminated and tested, and be provided in lengths to meet manufacturer's requirements to comply with required category grade performance standards. Provide patchcords in quantities to accommodate requirement that each port is active. Unless otherwise noted, patchcords at workstation ends are responsibility of others.
- .3 Include for provision of suitable patchcord extending to Owner's switch/server in room/rack. Confirm exact requirements with Owner and review with Consultant.
- .4 Where voice terminations are terminated onto wall mounted blocks, include for required patch cord to extend to rack voice patch panels and patchcords to further extend to Owner switch/server in room/rack. Confirm exact requirements with Owner and review with Consultant.

2.6 PUNCHDOWN BLOCK TERMINATIONS

- .1 Capacity of connectors to be to suit number of conductors. Confirm and coordinate exact type of termination means with local carrier/provider and review with Consultant. Mounts to be suitable for wall mounting.
- .2 Category 6 punchdown block bases for termination of UTP cabling and connecting blocks; finished in white; can be interlocked and stacked to accommodate system capacity; of types to be either rack mounted or panel mounted to suit application and room requirements.
- .3 Cross connect jumper wire, patch cords, cable HUB harness or pigtails as required to extend connections from blocks to patchpanels and to Owner's switches/servers.
- .4 Connecting tool, termination kits, designation strips, labels, and wiring distribution rings.

2.7 OPEN EQUIPMENT RACKS

- .1 Each data hub to have equipment mounted on a 19" standard rack, 44U-83" tall floor standing rack R.F. Mote #RFM-1944-RB.
- .2 Vertical rack cable managers, 44U size, both sides with doors R.F. Mote RFM-RVCM-B.
- .3 Vertical power bar - 15A, 12 plug minimum, black, with breaker, UL, cUL approved and must be vertically mounted. #RFM-VRTBC200-10.
- .4 Note: If space is limited, consult with the Supervisor of Network Services, Information Technology Services Dept. for alternative wall-mount solutions.
- .5 Each rack to include grounding provisions to meet previously listed standards, which include but are not limited to following provisions:
 - .1 copper ground strip mounted on side rail extending full height of rack;
 - .2 equipment jumper kits, to bond network equipment to rack ground strip;
 - .3 common bonding network to rack jumper kit, to bond rack to room common bonding network;
 - .4 hardware including, copper compression HTAPS, paint piercing washer kits, bonding screws and electrostatic discharge port kits.
- .6 Racks to be of size and quantity to accommodate respective number of patch panel ports to suit number of required drops, quantity of network electronic components as directed by Owner network integrator, uninterruptible power supply unit and an additional 20% spare capacity for future expansion.

- .7 Within LAN rooms, provide flexible steel type wire basket tray to manage cabling to and from racks. Refer to cable tray section for tray requirements.

2.8 WIRELESS LAN INFRASTRUCTURE

- .1 Provisions for a wireless LAN infrastructure to be provided with 100% coverage of entire complex, utilizing structured network cabling system as a rough-in for future wireless access points (WAP) located in ceiling spaces. Generally, quantity of outlets to be identified on drawings, but Electrical Divisions contractor to coordinate device locations with Supervisor of Network Services, Information Technology Services Dept.
- .2 Locations may generally be shown on drawings, however, following criteria to be followed:
 - .1 above accessible ceiling tile or high up in open ceiling areas as confirmed with Consultant;
 - .2 classroom priority;
 - .3 in service areas and public areas as identified on plans;
 - .4 in light cove if WAP is hidden;
 - .5 with access panel (location identified).

2.9 ACCEPTABLE NETWORK CABLING SYSTEM MANUFACTURERS

- .1 Horizontal copper structured cabling infrastructure is to be end-to-end solution from a single manufacturer, which includes data communication outlets and patch cords at workstations, and patch panels and patch cords at LAN/Telecommunication rooms.
- .2 Acceptable network cabling system manufactures for provision of horizontal network copper cabling infrastructure are:
 - .1 Panduit
 - .2 Belden/CDT;
 - .3 Commscope Systimax/Uniprise;
 - .4 TE (Tyco AMP);

2.10 ACCEPTABLE CONTRACTORS

- .1 Contractor selected for installation of structured cabling system to provide confirmation of following:
 - .1 detailed knowledge and experience in fibre optic cabling and category grade rating copper UTP wiring installations;
 - .2 detailed knowledge and experience in installation of Intelligent HUB equipment;
 - .3 experience in troubleshooting and problem solving in data communication networks.
 - .4 ability to provide system Manufacturer certified warranties;
 - .5 certified and valid proof of being system Manufacturer authorized vendor.
- .2 Refer also to supplier requirements specified in Part 1.

Part 3 - Execution

3.1 INSTALLATION OF NETWORK CABLING - GENERAL

- .1 Properly handle and install structured network cabling in accordance with Manufacturer specifications. Avoid undue pulling tension, abrasion, or rough handling to ensure that cables will permit transmission up to required category rating design speed for cables. Install cables without splices or cuts to ensure elimination of reflections, discontinuities, impedance mismatches, etc. maximum horizontal length of copper cabling from workstation to network switch is not to exceed 90 m (295') or less if recommended by system manufacturer to meet required category grade rating performance standards. Maximum length of patch cables (either cross connects or interconnecting with electronic equipment to connect devices at work area outlet), to be a total of 10 m (30'). Maintain system Manufacturer minimum channel lengths as confirmed with system manufacturer. Provide cable loops in accordance with Manufacturer instructions.
- .2 Unless otherwise noted or where cable tray is shown for such use, run cabling in conduit. Install pull cords for future use, in conduits extending between floors.
- .3 Generally, no more than two (2) 90-degree changes in direction are recommended for cable installed in conduit without pull boxes and not more than 40% fill ratio. Confirm exact conduit bending radii restrictions and fill ratios with system manufacturer and comply with those standards.
- .4 With consideration in minimizing alien crosstalk to levels as per BICSI standards and Manufacturer standards, dress cables in a neat and orderly fashion from entrance of communications closet to relay racks using vertical and horizontal cable management trays and paths. Do not exceed Manufacturer distance limitations to maintain required category rating performance standards.
- .5 Care to be taken to ensure that during installation, nicks, abrasions, burning and scuffing of cable is prevented. Replace cables found to be damaged regardless of whether cable passes category grade rating or fibre performance testing standards.
- .6 Secure bundled cables transitioning between floors via ladder cable tray, to vertical ladder sections with Velcro wraps. Use waterfall (rounded transition) fittings for cable changing from a horizontal path to a vertical one. This is to maintain minimum bend radius for cabling system. Support cables running through risers between floors such that they are properly supported for their weight, especially in situations with high pair count cables and large bundles.
- .7 Electrical Contractor and telecommunication system vendor to provide coordination of structured cabling system with other systems as required. Review data outlet and connection requirements with various system vendors and provide data drops to equipment as required. Size head end equipment to accommodate these additional outlets.
- .8 Required necessary drilling and anchoring components to be installed before any horizontal cable is installed.
- .9 Route horizontal cable into equipment racks/enclosures and neatly bundle with Velcro cable ties. Maximum number of cables per bundle to be 25.
- .10 Securely mount fire retardant plywood on wall in each telecommunications room or closet.
- .11 Cables wraps are to be Velcro type and are not to be over tightened.
- .12 Provide grounding and bonding requirements as specified in Section titled Grounding and Bonding.

3.2 INSTALLATION OF PATCH PANELS & ACCESSORIES

- .1 Provide patch panels onto racks in locations. Provide terminating hardware and connectors to suit incoming and outgoing cabling. Clearly identify each port. Provide patch cords as required. Install devices in accordance with system Manufacturer requirements.
- .2 Terminate both data and voice horizontal cabling onto patch panel punch down using Manufacturer recommended tools. Bundle cabling in neat configuration and secure to patch panels and rack assemblies. Typically dedicated separate patch panels are required for data and voice.
- .3 Install rack enclosures on walls. Neatly bundle wiring within wiring management channels. Do not over tighten Velcro straps. Ground racks as required.

3.3 INSTALLATION OF TERMINATION HARDWARE

- .1 For main telephone service incoming conductors to main communication closets and other conductors as detailed, provide required punchdown connectors and mounts on hardwood backboards on walls or on racks. Refer to drawing details. Design system layout to best suit incoming and outgoing cables. Properly punchdown cabling with manufacturer's required tool and label each connector as required.
- .2 Run interconnect cables neatly secured and bundled across connectors and between banks of mounts. Use D-rings to their full advantage. Neatly bundle pigtails and secure to IDC connectors.
- .3 Where wall mounted, align mounts in straight formations to provide a neat installation and to minimize interconnect wiring lengths.
- .4 Where horizontal cables are terminated to patchpanels, provide appropriate patch cords/ jumper cables to interconnect patch panels to respective wall mounted punchdown blocks.
- .5 Clearly and properly identify each cable and block terminations.
- .6 Co-ordinate with Owner's network integrator to determine exact requirements for telephone service interconnections.

3.4 COPPER CABLE INSTALLATION

- .1 Run horizontal, UTP cables continuous from end to end with no splices. Install horizontal cables in Star topology, emanating from rack mounted patch panel(s) and terminating on data outlet faceplates in rooms or other workstation locations. maximum length for horizontal cables to not exceed 90m (295'). Maximum length for patch cords at patch panel to not exceed 3m (10').
- .2 Install conductors in cable tray and conduit runs designated for data and voice conductors. Do not fasten conductors and conduit to suspended ceiling support systems. Support conduit to building structure slab independent of other support.
- .3 Terminations to involve as little outer jacket removal as possible and cable pairs "untwisting" is to not exceed 6 mm (1/4").
- .4 Provide slack cable to allow for minor workstation relocations. Provide a coil of slack cable of an approximate 2 m (6') length for each workstation outlet run.
- .5 Where conduits and/or cable tray is not being provided, conductors within accessible ceiling spaces to be properly bundled using "Velcro" type wraps and supported with "J" hooks. Secure "J" hooks to ceiling slab structure. Install conductors following building lines. Do not fastened conductors to suspended ceiling support systems. Obtain Consultant's approval in use of "J" hooks. Unless otherwise noted, drops down from ceiling spaces to consist of cabling installed in vertical conduits running down within walls to outlet boxes and terminating onto jacks.

- .6 For main voice backbone cabling from main telecom room, provide 110 connectors and mounts on hardwood backboards on walls, as required. Design system layout to best suit incoming and outgoing cables. Properly punch down cabling with Manufacturer required tool and label each connector as required.
- .7 Run interconnect cables neatly secured and bundled across connectors and between banks of mounts. Use D-rings to their full advantage. Neatly bundle pigtails and secure to BIX/110 connectors.
- .8 Align mounts in straight formations to provide a neat installation and to minimize interconnect wiring lengths.
- .9 Coordinate with Owner network integrator to determine exact requirements for telephone service interconnections.
- .10 Provide jumpers/pigtails to interconnect backbone wiring to rack mounted voice patch panels where horizontal voice cabling is terminated.
- .11 For horizontal copper backbone cabling, multi-pair conductor cabling is preferred. If available only in limited number of pair cabling, provide multiple runs to provide quantity as identified on drawings, and increase conduit diameters to suit exact number requirements, in accordance with standards and codes.

3.5 PENETRATION THROUGH FIREWALLS

- .1 Provide a conduit sleeve where horizontal cables penetrate firewalls. Size conduit sleeve at 40% fill ratio with a plastic bushing at both ends.
- .2 After conduit sleeve is installed, fill opening around conduit with firestop and smoke seal materials.

3.6 INSTALLATION OF OUTLETS

- .1 Connect each data/voice outlet with a 4-pair, UTP cable. Test and identify each outlet and faceplate. Wire and connect data/voice jacks back to respective dedicated racks in LAN/TEL rooms. As detailed, extend voice cabling from voice patch panels to wall mounted 110 connectors, using patch cords, cross connects/jumpers, etc. as required.
- .2 Provide outlet jack/faceplate configuration as detailed on drawings.
- .3 Drawings identify data jacks for wireless access point receivers (antennae). These locations are approximate. Confirm exact locations during onsite radio frequency studies. Allow for jacks to be repositioned up to 4m (15') to suit results of studies. Perform studies after completion of construction of interior structures. If studies are not performed at discretion of Owner, leave slack coiled length of cable on each run, allowing for repositioning and review with Consultant.

3.7 SEPARATION OF DATA COMMUNICATION CABLES FROM SOURCES OF ELECTROMAGNETIC INTERFERENCE

- .1 Separate data communication cables from sources of electromagnetic radiation in accordance with standard ANSI/TIA/EIA-269 and following:
 - .1 FT-6 rated data cabling raceway and power conductors (2 KVA power circuits) raceway require 125 mm (5") clearance;
 - .2 for fluorescent luminaires, required clearance is 300 mm (12");
 - .3 clearance increases up to 600 mm (24") for power circuits over 5 KVA.
 - .4 for large motor, transformers, power panels, etc., required clearance is 1m (39");
 - .5 route cables to avoid direct contact with steam piping, hot water piping or other heat sources to avoid thermal degradation.

3.8 INSTALLATION OF RACKS

- .1 Provide racks and secure to floor with bolts and concrete anchors.

- .2 In locations where more than one rack is required, butt multiple racks together. Provide wiring channel interconnection such that wiring from rack to another is not exposed.
- .3 For open racks, provide metal raceway chimney channel for conductors extending down from ceiling, such that wiring is not exposed. Secure channel to rack and ceiling.
- .4 Run wiring neatly bundled within wiring management channels. Do not over tighten Velcro tie wraps such that they deform cable jacket. Velcro straps to easily slide along length of cable. Velcro tie wraps used in plenum spaces to be CMP/FT-6 rated.
- .5 Protect cable from any obstructions using appropriate grommets in roof of rack.
- .6 Properly ground and bond rack and equipment to room ground bus as per specifications and to standards of TIA/EIA 607.

3.9 INSTALLATION OF EQUIPMENT ENCLOSURES

- .1 Provide equipment enclosures and secure to wall/floor/ceiling as required with suitable anchors.
- .2 In locations where more than one enclosure is required, butt multiple enclosures together. Provide wiring channel interconnection such that wiring from enclosure to another is not exposed.
- .3 Provide metal raceway chimney channel for conductors extending down from ceiling, such that wiring is not exposed. Secure channel to enclosure and ceiling.
- .4 Provide suitable power supply to cabinets having fans and other active components or designated as such.
- .5 Run wiring neatly bundled within wiring management channels. Do not over tighten Velcro tie wraps such that they deform cable jacket. Velcro straps to easily slide along length of cable. Velcro tie wraps used in plenum spaces to be CMP/FT-6 rated.
- .6 Protect cable from any obstructions using appropriate grommeting in roof of enclosure.
- .7 Properly ground and bond enclosure and equipment to room ground bus as per specifications and to standards of TIA/EIA 607.

3.10 SYSTEM IDENTIFICATION

- .1 Provide a complete identification system that clearly designates following:
 - .1 horizontal cable;
 - .2 workstation (or faceplate);
 - .3 horizontal/passive patch panel port;
 - .4 switch/active patch panel port;
 - .5 patch cords;
 - .6 switch rack.
- .2 Obtain Owner approval of identification format, prior to start of work. Format to comply with Owner standards. Submit proposed identification system and nomenclature with shop drawing submission.
- .3 Labels:
 - .1 Labels for outlet and patch panel identification to be typewritten/computer printed self-adhesive type with white printing area at outlet location and on face of patch panel; legible permanent marker on inside of outlet box cover; use minimum font size Arial 10 point.
 - .2 Number and identify each computer hub rack with a 20 mm x 50 mm (3/4" x 2") engraved lamacoid plate, with white letters on black background. For letters and numbers use Arial 24 font size. Fasten nameplates with minimum two metal screws.

- .3 Cable Identification:
 - .1 Permanently identify horizontal UTP cables at both ends of cable, placed within 13 mm (1/2") at outlet location and 50 mm (2") at rack location and inside of outlet cover in following manner:
 - .2 "CABLE # / RACK # / PATCH PANEL PORT # / OUTLET #"
- .4 Faceplate:
 - .1 Label data ports: "Closet / Patch Panel/Port Number", where closets to be numerically assigned, patch panels to be sequentially alphabetically assigned beginning at top of rack and ports sequentially numerically assigned related to number of ports per patch panel.
 - .2 Label voice ports: "Port Number/Level/Closet", where ports are sequentially numerically assigned, level refers to floor level on which communication closet is located and closets to be numerically assigned as per data ports.
- .5 Patch panel And Patch Cord Identification:
 - .1 Identify patch panel ports in simple numeric form approved by Consultant/Owner.
 - .2 Identify patch cords at both ends in simple numeric form, not necessarily corresponding to port numbers and be approved by Consultant/ Owner.
- .4 Identification Log:
 - .1 Record cable and workstation identification in a hard copy "CABLE IDENTIFICATION LOG" which is to be handed over to Owner after cable testing and certification is complete. Forward duplicate copy to Consultant.

3.11 CABLE TESTING & SYSTEM CERTIFICATION

- .1 Structured cabling system certification to include 100% cable testing and verification for an EIA/TIA required category grade rating solution.
- .2 Perform verification of each cable and document on a cable testing sheet forming part of hard and soft copy documentation supplied at end of installation. Testing sheets to list detailed performance test measurements as requested and as required to prove compliance with referenced standards. Also include summary sheet of passes, failures and rectified failures. Submit sample of test sheet with shop drawings.
- .3 Comply with system Manufacturer testing and certification procedures.
- .4 Testing Procedures:
 - .1 Perform testing using Category 6 testers such as Fluke Networks Versiv family, or equivalent Microtest or Scope Communications. Tester to meet TIA/ISO certification standards for Levels IIe, III, IIIe, IV and V. Submit with shop drawings copy of calibration certificate issued by tester Manufacturer authorized technician identifying calibration within one year of use for testing on this project. Testing to include, but not be limited to following:
 - .1 wire map;
 - .2 cable length;
 - .3 attenuation;
 - .4 near end crosstalk (next);
 - .5 power sum near end crosstalk (PSNEXT);
 - .6 equal level far end crosstalk (ELFEXT);
 - .7 power sum equal level far end crosstalk (PSELFEXT);
 - .8 return loss;
 - .9 ACR;
 - .10 power sum ACR;

- .11 end to end continuity;
- .12 opens or shorts;
- .13 pair polarity.
- .2 Field testing units for multimode fibre optic cabling to comply with ANSI/TIA-526-14-B. Field testing units for singlemode fibre optic cabling to comply with ANSI/TIA/EIA-526-7.
- .3 Conduct test set-up and performance in accordance with ANSI/TIA/EIA-526-7 and/or ANSI/TIA/EIA-526-14 Standards, and to Manufacturer application guides.
- .4 Perform attenuation testing with a stable launch condition using two-meter jumpers to attach test equipment to cable plant. Light source to be left in place after calibration and power meter moved to far end to take measurements.
- .5 Acceptable loss measurements for 50 micron laser optimized solution at 850 nm wavelength is not to exceed 2.5 db.
- .6 Since optical signal attenuation at one wavelength is independent of attenuation at a second wavelength, measure attenuation of channel at both standard wavelengths (850 nm and 1300 nm) for backbone links.
- .7 Replace cable not passing testing procedure, in its entirety. No splicing is permitted.
- .5 Reports:
 - .1 Submit test results to system manufacturer and obtain Manufacturer certificate of approval of system. Submit detailed indexed test report in a 3-ring binder with Manufacturer certificate of approval and covering letter from company responsible for installation and testing of system stating accuracy of report. Letter to be signed by company authorized testing technician. Document testing and reports with date and time of testing, testing technician's name and signature and specification Section number that test fulfilled.
 - .2 Submit copy of report including test reports in digital format loaded on USB type memory flash drive.

3.12 SYSTEM TRAINING & INSTRUCTIONS

- .1 Provide training of Owner designated staff on principles of connections and operations to system. Clearly instruct on procedures of disconnections and reconnections to accommodate changes and relocations of connected equipment.

END OF SECTION

Part 1 - General

1.1 SUBMITTALS

- .1 Submit shop drawings for products specified in this Section. Include annunciator schedules, revised system programming and sample of revised graphic annunciator layout and nomenclature.
- .2 Submit copies of final system testing and verification reports and certificates of approval from local governing inspection authority.

Part 2 - Products

2.1 EXISTING FIRE ALARM SYSTEM

- .1 Existing fire alarm system serving complex is EST, MODEL 3X-SFS1. Provide additional devices and work to extend system to serve additional and renovated areas. Additional devices to be 100% compatible with and of same manufacture as per existing system. Include provision of necessary control panel and annunciator work of existing system to accommodate integration of additional devices.
- .2 Include for and engage Owner existing system manufacturer authorized technicians to provide and perform required system products and work.
- .3 Verify with existing fire alarm system manufacturer during Bid period, exact requirements needed to provide renovation work. If necessary, visit site with manufacturer to review existing conditions. Confirm and coordinate exact work responsibilities with system vendor. Items of clarification or proposed revisions to Bid Documents must be reviewed with Consultant during Bid Period.

2.2 ADDITIONAL FIRE ALARM SYSTEM WORK

- .1 System work to include but not be limited to provision of following:
 - .1 modifications to existing head end equipment including provision of additional device connection modules, zone modules, amplifiers and system re-programming;
 - .2 additional transponders/data gathering panels (DGP);
 - .3 additional initiating devices (pull stations, heat/smoke detectors);
 - .4 additional alarm indicating devices (horns, strobes);
 - .1 All new horns sound pattern shall match sound pattern of existing-to-remain horns throughout the existing school.
 - .5 additional interfaces and interconnections to auxiliary building systems;
 - .6 review of existing battery backup capacity and amplifiers (as applicable) and increasing capacities to accommodate additional device loading and to meet applicable governing local code requirements;
 - .7 additional wiring in conduit and/or fire rated cables.

- .2 Additional system components to be listed as products of a single manufacturer under appropriate category, by Underwriters Laboratories of Canada and bear ULC label. System components and work in conjunction with system installation to meet specific application requirements of local governing authorities, codes, standards, regulations and requirements of following:
 - .1 CAN/ULC-S524, Standard For Installation Of Fire Alarm Systems;
 - .2 CAN/ULC-S527, Control Units For Fire Alarm Systems;
 - .3 CAN/ULC-S537, Standard For Verification Of Fire Alarm Systems ;
 - .4 local governing building code;
 - .5 local governing building permit applications for approvals;
 - .6 other requirements of local governing authorities.

2.3 MODIFICATIONS & DEVICES

- .1 Modify control panels and annunciators to supervise and annunciate additional and relocated devices. Additional initiating devices shall be devices that are 100% compatible with existing controls and be ULC listed and labelled for connecting to respective control units. Include costs for manufacturer authorized representative to perform control panel/transponder work and to reprogram system software to accommodate renovation work. Provide additional zone modules as required and additional batteries as required to supply back-up battery capacity to the additional components.
- .2 Additional devices to be ULC listed and labelled devices suitable for fire alarm applications. Power supplies and other components to be CSA approved where required by local governing authorities and codes.
- .3 Exact type of device to be used in each area of installation to be as recommended by system manufacturer to suit specific applications and to be approved for such use as per ULC standards. Devices in non-climatic controlled areas to be weatherproof, corrosion resistant and ULC listed for use in below freezing temperatures. System manufacturer to be responsible for ensuring compliance with these requirements.
- .4 Devices:
 - .1 Additional smoke detectors and heat detectors: to be of type and rating to suit specific application as per existing system Manufacturer recommendations.
 - .2 Audible devices: of type to match existing system standards.
 - .3 Strobes and combinations strobes/audible devices: of type to match existing system standards; include additional strobes to meet latest governing building code requirements.
 - .4 Addressable modules as required for connection of additional devices.
 - .5 Ancillary devices as required to complete system.
 - .6 Refer to drawings for additional device requirements.
- .5 End-Of-Line Resistors and Isolators:
 - .1 End-of-line resistors for standard alarm and signalling circuits to be sized to ensure correct supervisory current flows in each circuit.
 - .2 End-of-line resistors to be mounted on a stainless steel plate for mounting on a standard single gang box and bear ULC label.

- .3 Isolators to be provided in accordance with code requirements and installed as per system Manufacturer requirements to isolate/monitor zones, loops, group of devices within building and between buildings.
- .6 Wiring:
 - .1 CSA approved and ULC listed wire and cable, approved for fire alarm circuits; with colour coded, insulated solid copper conductors; of type as per local governing electrical code and local governing fire authority requirements.
 - .2 Sized and installed in accordance with system Manufacturer instructions and local governing electrical code.
 - .3 Fire rated MI for wiring as required by local governing building code, local governing authorities and as noted on drawings, for connections and interconnections to equipment for life safety applications.
 - .4 To be mechanically protected to satisfaction of local fire authority.
 - .5 Pentair "Pyrotenax" type "MI" ULC listed and labelled, 2 hour fire rated, mineral insulated, copper sheathed, copper conductors for power, control and signal wiring to and between each transponder/control panel, and for other local code required or local governing authority required applications with regards to life safety equipment.

2.4 TESTING & VERIFICATION WORK

- .1 Refer to Part 3 for system testing, verification and certification Work.

Part 3 - Execution

3.1 INSTALLATION - GENERAL

- .1 Prior to start of Work as part of shop drawing submission process, review with system manufacturer following:
 - .1 device types to ensure that selected type is suitable for intended application on project;
 - .2 locations of devices to ensure proper operation and coverage are in compliance with requirements of local fire authorities;
 - .3 device mounting heights to ensure proper operation and coverage are in compliance with requirements of local fire authorities;
 - .4 device back box requirements to ensure size and depth suit system Manufacturer recommendations for specific devices;
 - .5 types of system wiring and required sizing taking into consideration applications and voltage drop;
 - .6 system circuiting and device quantities per circuit while maintaining limitations in Specifications;
 - .7 proposed revisions required to existing system sequence of operation.
- .2 Immediately advise Consultant of any requirements of above that may necessitate revisions to design documents.
- .3 Install fire alarm system components and connect complete.

- .4 Perform Work in conjunction with this installation to meet requirements of latest editions of local governing building code, local governing electrical code, ULC Standards including Installation Standard CAN/ULC-S524, and any applicable local governing codes. If any requirements of these specifications are different, omitted or contrary to ULC-S524 Standard, then ULC Standard governs and overrides these specifications, but in no instance will standards established by drawings and specifications be reduced by any of Codes referred to previously. Control units and annunciators to be in accordance to latest requirements of ULC Standard CAN/ULC-S527 "Control Units for Fire Alarm Systems.
- .5 In addition, work to meet Owner's standards, and recommendations and instructions from system manufacturer.
- .6 During work to existing fire alarm system, proposed time and duration of interruption to be approved by Consultant. At any time due to emergency situations, Owner may request by-passed zone(s) to be re-instated immediately. In all areas where renovation work requires shutdown of any part of fire alarm protection system, provide manual fire alarm protection (Fire Warden) by means of supervising area as approved by local governing authorities. At no time allow fire alarm system or any one (1) zone to be left inoperative overnight. Provide required bypass wiring and temporary wiring to maintain all parts of fire alarm system operative during construction and alterations.
- .7 Fire alarm system Manufacturer authorized technician to supervise control panel, transponder, and annunciator work.
- .8 Provide sequence of operation for fire alarm system as approved by local fire authority and reviewed by Consultant. Refer to additional requirements on drawings.
- .9 Demonstrate system to local Fire Department and obtain their approval for complete system.

3.2 **INSTALLATION OF CONTROL UNITS**

- .1 Install required additional transponders, and make modifications to existing controls, panels, and annunciator.
- .2 Re-programme system to accommodate system modifications and to accommodate additional devices and zones, as required. Submit proposed software programming revisions to Consultant and local fire authority for review and approval prior to start of work.
- .3 Install units in accordance with Manufacturer instructions.
- .4 Connect transponders to dedicated 15A breakers in nearest emergency panel as shown or as scheduled. Ensure that room housing panels have fire rating to local governing code requirements. Provide fire rated conductors as required.
- .5 Properly ground and bond transponders to building ground. Conduit ground will not be acceptable. Provide green coloured grounding loop, a minimum #10 AWG insulated copper conductor run in conduit. Connect ground loop to main building ground system source. Do not run ground wire in same conduit as fire alarm and communication wiring.

3.3 INSTALLATION OF DEVICES

- .1 Install required devices. Do not install devices in locations that may hamper proper operation of devices including adjacent devices.
- .2 Obtain required training from manufacturer representative on any special installation procedures. Install devices and perform work in accordance with Manufacturer instructions and requirements and in accordance to applicable codes of local governing authorities having jurisdiction.
- .3 Review device finishes with Consultant prior to ordering.
- .4 Install manual pull stations in boxes as required, recessed outlet boxes with plaster rings, except in unfinished areas where pull stations are surface mounted, in which case, install stations in surface mounted boxes. Comply with mounting height requirements for local governing building code barrier free access.
- .5 Install mounting plate of thermal detectors to ceiling mounted boxes as required. Secure detectors to plates. Refer to floor plans and drawing symbol list to determine rating of detectors in any given area. Generally, do not install rate-of-rise type detectors in areas subject to sudden changes in temperatures, such as entrance vestibules. Confirm application requirements with system manufacturer and ensure that devices are ULC listed for such applications and are approved by local fire authority for such use.
- .6 Secure base of each ceiling mounted products of combustion detectors to boxes as required, either flush or surface mounted as required. Secure detector heads to bases.
- .7 Install cross zoned connection of detectors and remote indicating devices for areas of raised floors or within accessible ceiling spaces or for applications detailed on drawings.
- .8 In application with hold open devices on doors, ensure compliance with NFPA regarding smoke detectors tied to hold open devices such that a signal received directly from smoke detector to cause release of door. Where electromagnetic locks are used on doors of egress, provide required automatic release of locks upon activation of fire alarm (i.e. via connection to auxiliary contact of adjacent pull station). Provide required conductors and connections to fire alarm system and to electromagnetic locks.
- .9 Wire speakers in Class B, 2 wire circuit configuration, terminating in end of line devices. Wire alternate speakers in same circuits with a minimum of 2 circuits per floor.
- .10 Generally, audible device locations are indicated on drawings, however, exact audible device quantities and locations to be in accordance with results of audibility device coverage site tests. Provide suitable sound detection metering and personnel to make necessary tests. Relocate audible devices and/or provide additional audible devices as required.
- .11 Install amplifiers sized as required to power additional speakers and include spare capacity as specified.
- .12 Typically, Install visual notification appliances 2400 mm (8') above floor or 300 mm (12") below finished ceiling line. Provide visual notification devices in areas subject to high ambient noise levels, such as mechanical equipment rooms, computer equipment rooms, parking garage, etc., and areas designated for hearing impaired as per local building code requirements. Provide minimum 2 circuits per floor and connect devices in alternating scheme.

- .13 Provide required additional devices and install existing devices as required. Circuit devices to existing standards and in compliance with local governing codes and authorities. Determine exact quantities of circuits based on requirements of governing codes and standards, and recommendations of system manufacturer.
- .14 Unless otherwise noted in Contract Documents, do not load device circuits more than 80% capacity.
- .15 Devices in non-climate controlled areas to be weatherproof, corrosion resistant, ULC listed for operation in below freezing temperatures, and as recommended by system manufacturer for use for each specific application. Where electronics are not recommended for cold temperature applications, include for Manufacturer recommendations and directions in remotely locating addressable modules in closest heated areas and connecting to respective device in non-climate controlled areas.

3.4 REQUIREMENTS FOR INTEGRATED SYSTEMS & EQUIPMENT

- .1 Perform required fire alarm system wiring connections to mechanical equipment and other building systems to perform required interrelated functions. Provide required wiring, relays and/or contactors between fire alarm system and various equipment to achieve automatic or manual control of equipment, to perform required integrated to fire alarm system functions. Provide shunt trip breakers as required. Provide fire rated conductors where required by local codes and local authorities.
- .2 Provision of fire alarm supervisory wiring connections to include but not be limited to following (where applicable):
 - .1 fan equipment starters;
 - .2 pumps;
 - .3 door holders/releases and electromagnetic locks;
 - .4 devices as shown on drawings.

3.5 ADDITIONAL REQUIREMENTS

- .1 Provide required system wiring in accordance to requirements of applicable governing electrical code, other local governing code and standards requirements, system manufacturer's recommendations and based on specific applications and consideration of voltage drop.
- .2 Install wiring in conduit unless otherwise directed by Consultant. Perform wiring connections associated with fire alarm system on terminal strips in junction boxes and colour coded. Provide wiring colour coding consistent for entire length of each run. When pulling wires into conduit, use lubricant and run wires straight and not twisted or abraded. Neatly secure exposed wires in apparatus enclosures with approved supports or ties. Clearly identify wiring at each termination point. In addition, number wiring with Brady Ltd. or Electrovert Ltd. Z-type markers. Colour conductors for each part of system in accordance with system equipment Manufacturer recommendations. Paint conduit couplings red of paint type suitable for application to standards of Division 09.
- .3 Where existing devices are relocated and existing wiring is of insufficient length to connect to relocated position, provide replacement wiring and conduit of sufficient length.

- .4 Where required by local governing codes and/or local governing authorities, provide ULC listed, fire rated conductors (MI) for connections to and interconnections between equipment for life safety applications requiring fire rating. Install MI type conductors in accordance with manufacturer's instructions and requirements in Specification.
- .5 Run alarm indicating circuits (speakers) and alarm receiving circuits (pull stations, detectors) in separate conduits from each other.
- .6 Provide engraved Lamacoid identification nameplates for each equipment or wiring housing and secure to front of housing. Confirm exact wording designations and sizes to with Consultant prior to manufacture.
- .7 Review nomenclature of annunciator identification with Consultant prior to ordering.
- .8 Install end-of-line resistors to electrically supervise wiring. Generally, locate end-of-line resistors at ceiling lines above a pull station location. Provide isolators and install in accordance with ULC standards. Properly label and identify. Do not locate end-of-line resistors and isolators in concealed locations. Generally install in equipment rooms.
- .9 Refer to drawing riser diagram. Riser drawings are diagrammatic and are not to be used for determining quantities or lengths. Quantities of components to be as per floor plans. Determine exact quantities of circuits based on drawings information, connected devices, requirements of governing codes and standards, and recommendations of system manufacturer.
- .10 Review exact location of components prior to roughing-in.
- .11 Ground and bond system as required by local governing electrical code and authority and system manufacturer.

3.6 **SYSTEM TESTING, VERIFICATION & CERTIFICATION**

- .1 Submit to Consultant for approval, proposed schedule for testing and verification of system. Obtain such approvals prior to start of testing. Consultant and/or other Owner representatives to have option to witness all or part of testing and verification work. Notify Consultant and Owner minimum 7 working days in advance of testing.
- .2 Include for fire alarm system manufacturer to inspect, test, verify and certify system components and wiring, individually and as a complete system, in accordance with requirements of CAN/ULC S537. Work to include but not be limited to provision of following:
 - .1 to ensure that type of equipment installed is that designated by Contract Documents;
 - .2 to ensure that wiring connections to equipment components show that installer observed ULC and CSA requirements;
 - .3 to ensure that equipment was installed in accordance manufacturer recommendations, and that signalling devices of whatever manufacture were operated or tested to verify their operation;
 - .4 to ensure that supervisory wiring of those items of equipment connected to a supervised circuit is operating and that governmental regulations, if any, concerning such supervisory wiring, have been met to satisfaction of inspecting officials;

- .5 to ensure that sequence of operation is in accordance with existing sequence of operation and any modifications identified on documents and are approved by local fire authority;
- .6 to ensure that devices are commissioned and operable.
- .3 System manufacturer to also be responsible for, but not be limited to, provision of following additional work to existing systems:
 - .1 coordinate with local fire authority inspector and Electrical Division Contractor, required testing and verification work in order to obtain certification and meet local fire code and local fire authority requirements;
 - .2 test system battery power supplies and demonstrate compliance with local governing building code and local fire authority requirements that battery supplies are capable of providing required 24 hours of supervisory power followed by local governing building code required time (or time directed by local fire authority) of full load power; exact method of testing to be approved by local fire authority, Consultant and Owner; confirm exact procedures with previously named parties prior to testing; include for sufficient sound measurement devices and personnel in order to successfully comply with this requirement;
 - .3 full review, testing, and verification of operation of building ventilation and smoke exhaust system and its integrated operation with fire alarm system and various pieces of air handling equipment;
 - .4 full review, testing and verification of operation of integrated systems such as elevators and their emergency sequence of operation, supervisory annunciation of sprinkler/standpipe monitor switches, pressure switches and flow switches, diesel genset alarms, security alarms, BAS alarms, release of door holders and electromagnetic locks, and any other integrated components; coordinate requirements with trades responsible for integrated components and systems who will be present at time of testing and verification work;
 - .5 test that system audible devices provide alarm sound levels in areas as per local governing building code and local fire authority requirements; site adjust tap settings of audible devices as required to achieve required audibility levels; also test that emergency voice communication system meets or exceed intelligibility requirements of local governing building code and is approved by local fire authority;
 - .6 assist in testing and verification of electromagnetic door locks to meet requirements of authorities having jurisdiction and to obtain overall approval of installation;
 - .7 coordination with Electrical Divisions and local fire authority to provide requirements to obtain certificates of approvals from local fire authority;
 - .8 provide full detailed test sheets of tested components and provide certification that system work has been fully tested, that devices have passed testing and that system is in proper work order in compliance to local governing code requirements and project documents; testing report documents to be additionally provided in electronic format as confirmed with Owner and Consultant.

- .4 Where project work is phased and Owner requires occupancy at various stages, include for providing system testing, verification and certification after completion of each phase of work, to approval of local governing authorities. Upon Substantial Performance of the Work, include for providing system testing, verification and certification of entire system work.
- .5 Contact local fire authority inspector and coordinate and arrange for Fire Inspector to perform required inspections. Integrate local fire authority inspection requirements with testing and verification work to extent as per Fire Inspector's directions. Obtain full approval and certification by local fire authority.
- .6 Local fire authority inspector, Consultant and Commissioning Agent to at their discretion test system or parts of system in their review of test reports. Correct/repair any failures or deficiencies found in system, whether or not identified in test reports of manufacturer. Re-test and re-verify until successfully passed, at no extra cost to Owner.
- .7 Obtain from local fire authority required certificate of approval of system and forward to Consultant.
- .8 Arrange for manufacturers to supply reasonable amounts of technical assistance with respect to any changes required to conform to paragraphs above. During period of inspection, testing and verification, make Electricians available to do any required correction work and to assist during this Work. Include for trades responsible for integrated components (i.e. exhaust fans, sprinklers, elevators, gensets, etc.) and systems to be present at time of testing and verification work.
- .9 On completion of verification, inspection and testing of system, obtain from manufacturer and forward to Consultant, a verification certificate together with detailed inspection reports listing each and every system component, its location in building and its acceptability. Verification certificate and inspection reports to be prepared and signed by certified testing technicians of manufacturer. Signed test reports to confirm that systems are installed and perform in accordance with requirements specified above.
- .10 Obtain from system manufacturer and testing agency and forward to Consultant a certificate of liability insurance of minimum amount of Two Million Dollars (\$2,000,000.00) that is to be registered for this project to show satisfactory proof of manufacturer liability coverage for both their product and personnel.
- .11 Include for re-verification of any failed device repaired or replaced, until successful testing and verification.
- .12 Unless approved in writing by Consultant and Owner, do not use open flame and/or smoke for testing.
- .13 Testing technician to be certified and approved for fire alarm system testing by Canadian Fire Alarm Association (CFAA) and or be a Certified Fire Alarm Electrician (CFAE) with Electrical Contractors Association of Ontario (ECAO) as deemed acceptable to Ontario Fire Marshall.
- .14 Additionally, refer to testing, coordination and verification requirements in Section titled Electrical Work Analysis and Testing and include applicable requirements.

- .15 The Electrical Contractor shall warrant that the components of the fire alarm system installed as part of this work shall remain in good working order for a period of one year from the date of verification. Should components of the system fail to perform as intended under normal operating conditions at any time during this one year period, the Client shall notify the Electrical Contractor in writing. The Electrical Contractor shall repair or replace the failed equipment/devices to maintain a fully operational fire alarm system.

3.7 **MONITORING OF SYSTEMS**

- .1 In areas that remain occupied and used by Owner during Work, daily monitor and supervise existing fire alarm system serving renovation/working areas. Ensure that system is left in proper operating condition at end of each working day. Include for but not be limited to performing following:
 - .1 under presence of Owner representative, check each morning and evening (start and end of work) of each day, system to ensure that it is in proper working condition;
 - .2 if portions of system are not in proper working order, provide temporary bypass wiring (if fire alarm system, must be subject to approval of local fire authority), and/or provide supervisory personnel to monitor systems for area affected;
 - .3 document and sign off with Owner representative signing off also, each respective daily check condition;
 - .4 ensure that work to system does not affect portion of system serving areas outside of renovation/working areas.
- .2 Maintain fire protection of areas which may include fire watch during temporary shutdowns of existing systems, in accordance with requirements of local governing code and local governing authorities.

END OF SECTION